

Attachment VI-4

Stormwater Management
Table of Contents

Stormwater Management1

Figure 1.....Drawing of Stormwater Drainage Patterns

Figure 2.....Rainfall Frequency Distribution Curves

STORMWATER MANAGEMENT

Stormwater management at the Grassy Mountain Facility provides for the control of surface water drainage, resulting from precipitation falling on areas that are tributary to or from the landfill cells. Precipitation that falls on the site will do one of the following: infiltrate directly into the ground; evaporate; adhere directly to vegetation; or run off into the drainage ways and be transported to collection points or runoff directly into collection points. The stormwater management plan consists of facilities to control runoff inside and outside of the landfill cells. The control facilities outside of the cells will control runoff from precipitation which fall outside of the landfill cells, whereas the control facilities inside of the cells will control runoff from precipitation which falls inside of the landfill cells. These together make up the “runoff management system.”


The control facilities inside the cells must be capable of collecting and controlling the runoff water volume resulting from a 25-year, twenty-four hour storm as required by Utah Admin. Code R315-8-14.2 of the Utah Hazardous Waste Management Rules. The system is designed to manage the volume of runoff that would be produced by a 100-year, twenty-four hour storm event, thus meeting and exceeding the requirements of the rules. These requirements are met by maintaining enough capacity in the open cells to contain the necessary amount of water.

Outside of the cells, the stormwater runoff from uncontaminated surfaces, including exterior cell embankment surfaces and caps of closed cells, is managed via dikes, conveyance facilities (ditches, culverts, drain boxes, etc.), and ponds. The facility is relatively flat. Allowing stormwater to accumulate around the toe of the cell berms would be a nuisance to facility operations. These controls are implemented to minimize the negative impact that the accumulation of stormwater would have on operations.

Currently, the facility has nine (9) identified stormwater run-off ponds that provided for drainage from each RCRA, PCB, and Industrial Waste Landfill Cells, as well as, the Bulk Container Storage Areas East and West. A series of ditches provide for containment of run-off from parking and sampling areas.

Figures 1a and 1b, presents the rainfall frequency distribution for the Clive Area. Figures 1a and 1b were developed from U.S. Department of Commerce Weather Bureau Technical Paper No 40. (Jershfield, D.M). As illustrated on Figure 1a, the rainfall depth for the 100-year, 24-hour precipitation event in the Clive area is approximately 2.5 inches and as shown on figure 1b, 2.0 inches for a 25-year, 24-hour precipitation event. Figure 2 shows the stormwater drainage patters that the run off management system was designed to create in the area of Disposal Cells 8 – 13 and Surface Impoundment B. The size of the stormwater containment ponds was based on assumptions as to the amount of precipitation that run off the embankments and cell caps which are tributary to the ponds and the volume of rain produced by a 100-year, 24-hour precipitation event.

25-YEAR 24-HOUR RAINFALL (INCHES)



M:\clients\Cameron-Cole\1815-Grassy-Mtn\2017\Permit\rainfall.dwg

BY	DATE
DRAWN FR	11/30/17
CHECKED	
REVISED	
REVISED	
APPROVED	
APPROVED	




Cameron-Cole
 5777 CENTRAL AVENUE, SUITE 200
 BOULDER, COLORADO 80301
 PHONE: (303) 938-5500
 FAX: (303) 539-7283
<http://www.cameron-cole.com>

FIGURE 1b

25-YEAR 24-HOUR RAINFALL (INCHES)
 CLEAN HARBORS GRASSY MOUNTAIN, LLC

SCALE:	AS SHOWN	PROJECT:	1968
--------	----------	----------	------

100-YEAR 24-HOUR RAINFALL (INCHES)



M:\clients\Cameron-Cole\1815-Grassy-Mtn\2017\Permit\rainfall.dwg

BY	DATE
DRAWN FR	11/30/17
CHECKED	
REVISED	
REVISED	
APPROVED	
APPROVED	
APPROVED	



Cameron-Cole
 5777 CENTRAL AVENUE, SUITE 200
 BOULDER, COLORADO 80301
 PHONE: (303) 938-5500
 FAX: (303) 539-7283
<http://www.cameron-cole.com>

FIGURE 1a

**100-YEAR 24-HOUR RAINFALL (INCHES)
 CLEAN HARBORS GRASSY MOUNTAIN, LLC**

SCALE:	AS SHOWN	PROJECT:	1968
--------	----------	----------	------