

2702 South 1030 West, Suite 10 Salt Lake City, Utah 84119 Ph: 801.270.9400 Fax: 801.270.9401

TRANSMITTAL

Sta Dej Div 195 Sal Att		nh 84114 n	DATE: 11/ IGES JOB SENT VIA ontrol	#: 00853		
Copies	Date		Description			
1	11/6/20	NPSWSSD Construction and	d Demolition (C&D)	Repermit Application		
1	11/6/20	Class VI Permit Checklist				
For you	oproval our use quested our review and ent	Approved as submitted Approved as noted Returned for corrections Other	Resubmit Submit Return	Copies for approval Copies for distribution Corrected prints		
Remarks: Attached are PDF files associated with the NPSWSSD Construction and Demolition (C&D) Repermit Application. Please call or email with any questions or comments.						
SIGNED: Butt Whichelson						



NPSWSSD CONSTRUCTION AND DEMOLITION (C&D) 2020 LANDFILL REPERMIT APPLICATION

November 6, 2020

NPSWSSD CONSTRUCTION AND DEMOLITION (C&D) 2020 LANDFILL REPERMIT APPLICATION

Submitted by:



Prepared by

IGES, INC.

2702 South 1030 West, Suite 10 Salt Lake City, Utah 84119

November 6, 2020

ANNOTATED TABLE OF CONTENTS

Part <u>Title</u>

Introduction

Includes summary of permit with technical and operational issues highlighted

I. General Information

Includes State of Utah Solid Waste Permit Application forms

II. General Report

Includes information required by Utah Administrative Rule R315-305

III. Technical Report

Includes information required by Utah Administrative Rule R315-305

APPENDICES

APPENDIX A – Drawings

APPENDIX B – Evidence of Ownership

APPENDIX C - Landfill Forms

APPENDIX D – 2010 Permit Renewal Application


APPENDIX E - Financial Assurance

INTRODUCTION

This document presents an application to repermit and operate a construction and demolition (C&D) landfill south of Fairfield in Utah County, Utah. The landfill is on land owned by North Pointe Solid Waste Special Service District (NPSWSSD) and operated by NPSWSSD personnel. The Class VI Landfill is currently operated under permit number 0012R2 issued by the Utah Division of Waste Management and Radiation Control (DWMRC) Board.

The area to be permitted is in the west quarter Section 5, Township 7 South, Range 2 West, Salt Lake Baseline and Meridian, Utah County, Utah. Drawing 1 (Appendix A) shows the location of the landfill.

Part I of this document duplicates the standard form outlining General Information pertaining to the site. Part II is a General Report that includes a facility description and landfill operations plan. Part III is the Technical Report and includes details on the design of the site closure, post-closure care and financial assurance.



Utah Class IV and VI Landfill Permit Application Form

Part I General Information		APPLICANT: PLEASE COMPLETE ALL SECTIONS.									
<i>I</i> . Landfill Type	☐ Class IVa ☑ Class VI	☐ Class IVb	II. Applica	Ation New Application Facility Expansion Modification							
For Renewal Applic	For Renewal Applications, Facility Expansion Applications and Modifications Enter Current Permit Number 0012R2										
III. Facility Na	III. Facility Name and Location										
Name of Facility North Pointe C&D Landfill											
Site Address (stree 480N 18150 W	Site Address (street or directions to site) 480N 18150 W County Utah										
City Fairfield				Zip Code		043	Telep	ohone			
Township 7S	Range 2	Section(s) 5&8	(Quarter/Qu	uarter S	ection	1	Quarter S	Section		
Main Gate Latitude	degrees 40	minutes 14	seconds 28	Longi	tude	degrees 1	12	minutes	5	seconds	49
	vner(s) Informa	tion									
Name of Facility Over North Pointe Science		ial Service Distric	ct								
Address (mailing) 2000 West 200	South										
City Lindon			State UT	Zip Code	84	042	Telep	ohone	(801) 225-853	8
V. Facility Ope	erator(s) Inform	ation									
Name of Facility Op Same as above											
Address (mailing)	<u>, </u>										
City			State	Zip Code		Telephone					
VI. Property C	wner(s) Inform	ation		•	•		•		-		
Name of Property (Same as above											
Address (mailing)	<u>, </u>										
City			State	Zip Code			Telep	ohone			
VII. Contact In	formation	<u>'</u>	·		•		<u>.</u>		-		
Owner Contact	Neil Schwendir	nan		Title	Distri	ct Manager					
Address (mailing) 2000 West 200	South										
City Lindon			State UT	Zip Code	84	042	Telep	ohone	(801) 225-853	8
Email Address neil.np@gmail.com					tive Tele	ephone (cell or	•	(435)	668-5	799	
Operator Contact Title											
Address (mailing) Same as above											
				Zip Code							
Email Address Alternative Telephone (cell or other)											
Property Owner Contact Title											
Address (mailing) Same as above											
City State Zip Code Telephone											
Email Address Alternative Telephone (cell or other)											

Utah Class IV and VI Landfill Permit Application Form

Part I General Information (Continued)						
VIII. Waste Types (check all that apply) IX. Facility Area						
☐ Landfill will accept all wastes allowed in Class IV or VI landfil	lls Or				298	acres
landfill will accept only the following wastes Waste Type Combined Disposal Unit Mon Construction & Demolition □	ofill Unit	Disposa Area			<u>51</u>	acres
Tires Yard Waste	Ħ	Design (,		50 :	
Animals Contaminated Soil	Ä	×	Years		<u>50+</u>	
Other			Cubic Yards		27000000	
			Tons		<u>13500000</u>	
X. Fee and Application Documents						
Indicate Documents Attached To This Application		Applicatio	n Fee: Amount \$	Class VI	Special Requirer	nents
☐ Facility Map or Maps ☐ Facility Legal Description ☐ Ground Water Report ☐ Closure Design ☐	Plan of Cost Es	Operation timates	☐ Waste Description☐ Financial Assurance	Doci	uments required ad (10)	by UCA 19-6-
I HEREBY CERTIFY THAT THIS INFORMATION AN	ND ALL A	ATTACH	ED PAGES ARE CORRE	ECT AND	COMPLETE	.
Signature of Authorized Owner Representative			Title Date			
ittsee		DISTRICT MANNER 11/10/2020 Address				
Name typed or printed Address ZOCO UD ZOOS LINDON UT 84042					1042	
Email Address New Alternative Telephone (cell or other) 435-668-5799						
Signature of Authorized Land Owner Representative (if applicable)		Title	Date		
			Address			
Name typed or printed						
Email Address Alternative Telephone (cell or other)						
Signature of Authorized Operator Representative (if applicable)			Title	Date		
		Address				
Name typed or printed						
Email Address	Alternativ	re Telepho	one (cell or other)			



TABLE OF CONTENTS

1.0 - FAC	ILITY DESCRIPTION	1
1.1	AREA SERVED	1
1.2	WASTE TYPES	1
1.3	FACILITY HOURS	2
1.4	LANDFILL EQUIPMENT	3
1.5 I	LANDFILL PERSONNEL	3
2.0 - LEG	AL DESCRIPTION	5
	RTH POINTE C&D LANDFILL OPERATIONS PLAN	
3.1	SCHEDULE OF CONSTRUCTION	7
3.2	DESCRIPTION OF WASTE HANDLING PROCEDURES	7
3.2	.1 General	7
3.2	.2 Waste Acceptance Records	8
3.2	.3 Waste Disposal	9
3.2	.4 Special Wastes – Wastes Excluded from the Landfill	10
į	3.2.4.1 Used Oil and Batteries	10
į	3.2.4.2 Appliances	10
3	3.2.4.3 Tires	10
3	3.2.4.4 Dead Animals	10
į	3.2.4.5 Asbestos Waste	10
	3.2.4.6 Grease By-Products	10
	3.2.4.7 Sewer Sludge	10
3.3	WASTE INSPECTION	11
3.3	.1 Landfill Spotting	11
3.3	.2 Random Waste Screening	11
3.3	.3 Removal of Hazardous or Prohibited Waste	12
3.3	.4 Hazardous or Prohibited Waste Discovered After the Fact	12
3.3	.5 Notification Procedures	13
3.4	FACILITY MONITORING AND INSPECTION	13
3.4	.1 Groundwater	13
3.4	.2 Surface Water	13
3.4	.3 Leachate Collection	14
3.4	.4 Landfill Gas	14
3.4	.5 General Inspections	14
3.5	CONTIGENCY AND CORRECTIVE ACTION PLANS	15
3.5	.1 Fire	15
3.5	.2 Explosion	16
3.5	.3 Failure of Run-On/Run-Off Containment	16

3	3.5.4	Groundwater Contamination	16
3.6	CONT	NGENCY PLAN FOR ALTERNATIVE WASTE HANDLING	17
3.7	MAIN ¹	TENANCE PLAN	17
3	3.7.1	Groundwater Monitoring System	17
3	3.7.2	Leachate Collection and Recovery System	17
3	3.7.3	Gas Monitoring System	17
3.8	DISEA	SE AND VECTOR CONTROL	18
3	3.8.1	Insects	18
3	3.8.2	Rodents	18
3	3.8.3	Birds	18
3	3.8.4	Household Pets	18
3	3.8.5	Wildlife	19
3	3.8.6	Fugitive Dust	19
3	3.8.7	Litter Control	19
3.9	RECYC	CLING	20
3.10	O TRA	INING PROGRAM	20
3.1	1 REC	ORDKEEPING	20
3.12	2 SUB	MITTAL OF ANNUAL REPORT	20
3.13	3 INSF	PECTIONS	21
3.14	4 REC	ORDING WITH COUNTY RECORDER	21
3.1	5 STA	TE AND LOCAL REQUIREMENTS	21
3.1	6 SAF	ETY	22
3.1	7 EME	RGENCY PROCEDURES	22

1.0 - FACILITY DESCRIPTION

The North Pointe Construction and Demolition (C&D) Landfill is located in the Town of Fairfield in Utah County. The facility is located 1.5 miles south of the center of town. The facility is a Class VI landfill that receives yard waste, inert waste, and construction and demolition (C&D) waste. The landfill consists of 298 acres of property which is flat and generally sloping to the south and east with approximately 70 acres of the property currently fenced. Of the 70 acres currently fenced, 6 acres have been closed with 51 acres currently being utilized for disposal. Site structures include a scale and scale house, small office, and a diesel fuel tank. The landfill site is operated by excavating each cell below grade to provide both airspace for waste disposal as well as to provide soils for landfill operations. The location of the Landfill is presented in the drawings in Appendix A.

1.1 AREA SERVED

The Landfill primarily serves the residents and businesses located in the western side of Utah County.

1.2 WASTE TYPES

Based upon the recent C&D waste stream and estimates of future trends; approximately 450-550 tons per day of C&D waste is expected to be delivered to the Landfill.

The waste diverted into the Landfill shall be limited to the following wastes:

- Yard Waste brush, branches, clippings, leaves and grass.
- Construction Wastes waste generated from construction and includes building materials used in construction. Construction related materials include packaging materials from products, waste lumber, wallboard, boxes from appliances, empty paint cans, empty caulking tubes, and empty sealer and adhesive cans. "EMPTY" means that no more than 10% of the product remains inside the container.

- Demolition Wastes waste generated from the destruction or remodeling of buildings and houses. Demolition Wastes may include furnaces, pipes, ducting and water heaters.
 Furniture and other materials that are not part of the building structure must be removed before demolition.
- Untreated wood, including pallets and crates
- Asphalt from roads and other surfaces

Waste materials that are specifically prohibited from the landfill include the following:

- Household Wastes (Municipal Solid Waste)
- Contaminated Soils
- Friable asbestos
- Tanks of any kind
- Railroad ties
- Cardboard not directly generated from construction or demolition activities
- Furniture of all kind
- Metal not directly generated from construction or demolition activities
- Electronics of all kind
- Treated lumber

1.3 FACILITY HOURS

The operating hours for the facility are 8:00 a.m. to 5:00 p.m. year-round. The facility is open Monday through Friday with the following holidays being observed:

- New Year's Day
- Memorial Day
- Independence Day (July 4th)
- Labor Day
- Thanksgiving Day
- Christmas Day

The following facility information is posted at the gate:

Landfill Owner

Days of Landfill Operation

Hours of Landfill Operation

Instructional Signs (no scavenging, no hazardous materials, dump in designated areas,

etc.)

Emergency Telephone Numbers

1.4 LANDFILL EQUIPMENT

The following equipment is on site and used in Landfill operations:

Dozer

Loader

Compactor

Scraper

Water Truck

Fuel Truck

Dump Truck

1.5 LANDFILL PERSONNEL

The following briefly presents the responsibilities for all on-site Landfill personnel at the Landfill:

<u>District Manager</u> - The District Manager (Manager) is responsible for all matters relating to the solid waste program for the Landfill. The Manager is responsible for the landfill operations meeting all Division of Waste Management and Radiation Control (DWMRC) permit requirements. The Manager conducts regular facility inspections and monitors all Landfill

activities. The Manager is responsible for all operational documentation including the preparation of the annual reports to DWMRC.

<u>Landfill Supervisor</u> - The Landfill Supervisor (Supervisor) is responsible for all matters relating to the day-to-day solid waste program for the Landfill; including the overall landfill operations, equipment operations, waste management and site development. The Supervisor is responsible that the Landfill operations meet all DWMRC permit requirements. The Supervisor conducts regular facility inspections and monitors all Landfill activities.

<u>Landfill Operators</u> — The Landfill Operators (Operators) are responsible for all day-to-day equipment and waste placement activities at the Landfill. These responsibilities include, waste acceptance and placement, traffic control, visual inspection of incoming waste, random waste screening operations, and general construction as it pertains to Landfill operations.

<u>Scale House Attendant</u> – The Scale House Attendants (Attendants) are responsible for the initial screening of all incoming waste. The Attendants track all incoming waste and updates Landfill records as required. The Attendants are also responsible for all transactions at the scale house, and the receipt of all monies.

2.0 - LEGAL DESCRIPTION

The landfill is located on property currently owned by North Pointe Solid Waste Special Service District. The facility is located in Township 7 South, Range 2 West, Sections 5 & 8, Salt Lake Baseline Meridian, Utah County, Utah.

The overall legal description is as follows:

Commencing at a point in the center land of a county road, said point being located N00°45'22"W along the Section Line 1343.60 feet, and East 1257.45 feet from the West Quarter Corner of Section 5, Township 7 South, Range 2 West, Salt Lake Base and Meridian, thence S89°42'06"E, 74.22 feet, thence S00°16'40"E, 1347.56 feet, thence S89°48'26"E along the quarter section line 1320.48 feet to the center of Section 5, thence S00°12'08"W, along the quarter section line 2646.06 feet to the quarter corner common to Section 5 and Section 8, thence S00°20'54"W along the quarter section line 2707.93 feet to the center off said section 8, Township 7 South, Range 2 West, thence N89°32'40"E, along the quarter section line 1327.91 feet, thence S00°20'12"W, 1325.56 feet, thence N89°34'40"E, 1328.17 feet, thence S00°19'3I"W, along the section line 1326.33 feet to the Southeast Corner off said Section 8, thence S89°36'40"W, along the section line 2656.85 feet to the South Quarter Corner off said Section 8, thence S89°36'21 "W, along the Section line 837.61 feet to the center line of a county road, thence along the center line of said county road as follows N00°12'43"E, 302.92 feet, thence N00°39'59"E, 1196.28 feet, thence N00°37'44"E, 2427.90 feet, thence N00°35'40"E, 1861.44 feet, thence N00°52' I 2"E, 405.93 feet, thence along the arc of a 400.00 foot radius curve to the left 316.45 feet (chord bears N21 °47'38"W, 308.26 feet), thence N44°27'28"W, 473.22 feet, thence N45°02'02"W, 137.61 feet, thence N44°56'18"W, 131.01 feet, thence N42°46'2I"W, 92.34 feet, thence along the arc of a 360.00 foot radius curve to the right, 313.28 feet (chord bears NI7°50'34"W, 303.49 feet), thence N07°05'14"E, 428.46 feet, thence N05°05'24"E, 201.10 feet, thence N04°53'03"E, 678.65 feet, thence N06°19'16"E, 569.05 feet, thence along the arc of a 2550.00 foot radius curve to the left, 130.05 feet (chord bears N04°51 '36"E, 130.04 feet) to the point of beginning Less and exempting the following:

Beginning at a point in the center line of a county road said point being located N00°45'22"W, along the Section Line 1343.60 feet, and East 1257.45 feet from the West Quarter Corner of Section 5, Township 7 South, Range 2 West, Salt Lake Base and Meridian and running thence S89°42'06"E, 74.22 feet, thence S00°16'40"E, 447.43 feet to a fence line, thence S 89°59'07"W 122.66 feet along said fence line and the extension thereof to the center of said county road, thence N06°19' 16"E, 320.22 feet along the center line of said county road, thence northerly 130.06 feet along the arc of a curve to the left, having a radius of 2550.00 feet (chord bears N04°51 '36"E, 130.037 feet) to the point of beginning.

Evidence of ownership is included as Appendix B.

3.0 - NORTH POINTE C&D LANDFILL OPERATIONS PLAN

The Operation Plan for the Landfill has been written to address the requirements of Utah State Solid Waste Regulations and describes the ongoing operations of the North Pointe C&D Landfill.

The general arrangement of the Landfill is as indicated on Drawing 2 (Appendix A). The following section details the operational specifics of the Landfill. Forms used to document the operations of the Landfill are included in Appendix C.

3.1 SCHEDULE OF CONSTRUCTION

The Landfill was an ongoing C&D landfill operation owed by Cedar Valley Landfill LC that started operation in 2002 and was purchased by NPSWSSD in 2013. Formal permit to operate the facility was formally transferred to NPSWSSD on May 2, 2013.

The construction of the Landfill started at the north property boundary with the scale house and scale operation and the initial landfill operations just south of the existing entrance. The Landfill operation continues to move south with plans to relocate the scale house and scale southward at some point in the future.

3.2 DESCRIPTION OF WASTE HANDLING PROCEDURES

3.2.1 General

The waste control program is designed to detect and deter attempts to dispose of hazardous, municipal solid waste or other unacceptable wastes at the Landfill. The program is designed to protect the health and safety of employees, customers, and the general public, as well as to protect against the contamination of the environment.

The Landfill is open for public and private disposal. Signs are posted along the Landfill access road to clearly indicate (1) the types of wastes that are accepted at the C&D facility; (2) the types of wastes not accepted at the site; and (3) the penalty for illegal disposal.

- All vehicles delivering wastes enter through the scale house area and are met by the Scale House Attendant. The Attendant inquires as to the contents of each incoming load and enter the description of the vehicle and waste content into the scale software program.
- Any vehicle suspected of carrying unacceptable materials (liquid waste, sludges, or hazardous waste) will be prevented from entering the disposal areas unless the driver can provide evidence that the waste is acceptable for disposal at the site. NPSWSSD reserves the right to refuse service to any suspect load. Vehicles carrying unacceptable materials will be required to exit the site without discharging their loads.
- Loads will be regularly surveyed at the tipping area. If a discharged load contains inappropriate or unacceptable material, the discharger will be required to reload the material and remove it from the Landfill. If the discharger is not immediately identified, the area where the unacceptable material was discharged will be cordoned off. Unacceptable material will be moved to a designated area for identification and preparation for proper disposal.

No open burning or smoking is allowed near the work face.

3.2.2 Waste Acceptance Records

A monthly summary of all landfill transactions is created and kept on file at the Landfill or at the NPSWSSD operations at the Lindon Transfer Station as part of the monthly billing activities. Any or all transactions may be retrieved as necessary.

3.2.3 Waste Disposal

Ideally, the C&D wastes will be dumped at the toe of the work face when possible and spread up the slope in one to two-foot lifts, keeping the slope at a typical five to one (horizontal to vertical) configuration. Depending on the configuration of the working face and site access, the waste will occasionally be pushed downslope into the working face.

Work face dimensions will be kept narrow enough to minimize blowing litter and reduce the amount of soil needed for cover.

Typically, the Compactor is operated with the blade facing uphill. Equipment operations across the slope are avoided to minimize the potential of equipment tipping over. In addition to safety concerns, a toe of slope to crest of slope working orientation provides the following benefits:

- Increases effective compaction.
- Increased visibility for waste placement and compaction.
- More uniform waste distribution.

The wastes will be compacted by making three to five passes up and down the slope. Compaction reduces litter, differential settlement, and the quantities of cover soil needed. Compaction also extends the life of the site, reduces unit costs, and leaves fewer voids to help reduce potential vector problems. Care is taken that no holes are left in the compacted waste. Voids are filled with additional waste as they develop. At a minimum, cover soils will be applied to all areas of the active cell at a minimum of every 30 days. Historically, the waste is been covered with soil weekly to minimize the impact of any potential landfill fires.

3.2.4 Special Wastes – Wastes Excluded from the Landfill

3.2.4.1 Used Oil and Batteries

Used Oil and Batteries are not accepted at the Landfill. NPSWSSD directs patrons with used oil to "Used Oil Recycling Centers."

3.2.4.2 Appliances

White goods are not accepted at the Landfill.

3.2.4.3 Tires

The Landfill accepts small quantities of tires from the general public. Only tires larger than a rim size of 24.5 inches are accepted at the facility.

3.2.4.4 Dead Animals

Dead animals are not accepted at the Landfill.

3.2.4.5 Asbestos Waste

Asbestos waste is not accepted at the Landfill.

3.2.4.6 Grease By-Products

Grease By-Product wastes are not accepted at the Landfill.

3.2.4.7 Sewer Sludge

Sewer sludge of any nature (wet or dry) is not accepted at the Landfill.

3.3 WASTE INSPECTION

3.3.1 Landfill Spotting

Learning to identify and exclude prohibited and hazardous waste from the Landfill is required to maintain the Class VI classification and necessary for the safe operation of the Landfill. The Operators are required to receive initial and periodic hazardous waste screening inspection training. Waste screening certificates of the training received are kept in the personnel files.

3.3.2 Random Waste Screening

Random inspections of incoming loads are conducted at least weekly or on a minimum of 1% of incoming loads (whichever is greater). If frequent violations are detected, additional random checks will be scheduled at the discretion of the Supervisor.

If a suspicious or unknown waste is encountered, the Operators proceeds with the waste screening as follows:

- The driver of the vehicle containing the suspect material is directed to the waste screening area.
- The Random Load Inspection form (Appendix C) is completed.
- The suspect material is spread out with landfill equipment or hand tools and visually examined. Suspicious marking or materials, like the ones listed below, are investigated further:
 - Containers labeled hazardous
 - Material with unusual amounts of moisture
 - Biomedical (red bag) waste
 - Unidentified powders, smoke, or vapors
 - Liquids, sludges, pastes, or slurries
 - Asbestos or asbestos contaminated materials

- Batteries
- Other wastes not accepted by the Landfill
- The District Manager is called if unstable wastes that cannot be handled safely or radioactive wastes are discovered or suspected.

3.3.3 Removal of Hazardous or Prohibited Waste

Should hazardous or prohibited wastes be discovered during random waste screening or during tipping, the waste will be removed from the Landfill as follows:

- The waste will be loaded back on the hauler's vehicle. The hauler is then informed of the proper disposal options.
- If the hauler or generator is no longer on the premises and is known, they will be asked to retrieve the waste and informed of the proper disposal options.
- The Supervisor will arrange to have the waste transported to the proper disposal site and then bill the original hauler or generator.

A record of the removal of all hazardous or prohibited wastes will be kept in the site operational records.

3.3.4 Hazardous or Prohibited Waste Discovered After the Fact

If hazardous or prohibited wastes are discovered at the Landfill after the hauler has left the premises, the following procedure will be used to remove them:

- Access to the area will be restricted.
- The Manager will be immediately notified.
- The Operator will remove the waste from the working face if it is safe to do so.
- The waste will be isolated in a secure area of the Landfill and the area cordoned off.
- Local authorities will be notified as appropriate.

The DWMRC, the hauler (if known), and the generator (if known) will be notified within 24 hours of the discovery. The generator (if known) will be responsible for the proper cleanup, transportation, and disposal of the waste.

3.3.5 Notification Procedures

The following agencies and people are contacted if any hazardous materials are discovered at the Landfill:

- Neil Schwendiman, District Manager(435) 668-5799
- Utah County Fire Department(801) 851-4141
- Utah County Health Department(801) 851-7095
- Director, DWMRC.....(801) 536-0200

A record of conversation will be completed as each of the entities is contacted. The record of conversation will be kept in the site operational records.

3.4 FACILITY MONITORING AND INSPECTION

3.4.1 Groundwater

The Landfill is not required to monitor groundwater.

3.4.2 Surface Water

Run-on diversion structures have been installed around the perimeter of the active Landfill during the initial construction. The diversion structures include both ditches and berms. Potential run-on waters will be diverted away from the working face of the Landfill.

In general, surface water that falls within the Landfill will naturally be contained in the active area of the landfill. All potential run-on will be directed away from the Landfill via berms.

Run-off from the final cover will be managed by a combination of berms and ditches. The berms will be placed to divert the water around the active area to ditches. The Drawings (Appendix A) illustrate the locations and details of the run-off control structures.

Facility staff will inspect the drainage system monthly. Temporary repairs will be made as required to any observed deficiencies until permanent repairs can be scheduled. NPSWSSD or a licensed general contractor will repair drainage facilities as required.

3.4.3 Leachate Collection

The Landfill is not required to collect or monitor leachate.

3.4.4 Landfill Gas

The Landfill is not required to monitor landfill gas.

3.4.5 General Inspections

Routine inspections are necessary to prevent malfunctions and deterioration, operator errors, and discharges that may cause or lead to release of wastes to the environment or a threat to human health. Operators are responsible for conducting and recording routine inspections of the landfill facilities according to the following schedule:

- Operators perform pre-operational inspections of all equipment daily. A postoperational inspection is performed at the end of each shift while equipment is cooling down.
- All equipment is on a regular maintenance schedule. A logbook is maintained on each piece of equipment and any repairs and comments concerning the inspection are contained in the log.

Facility inspections are completed on a quarterly basis. Any needed corrective action items are recorded and the Operators complete needed repairs. If a problem is of an urgent nature, the problem will be corrected immediately.

3.5 CONTIGENCY AND CORRECTIVE ACTION PLANS

The Utah County Fire Department will be contacted in all cases where hazardous materials are suspected to be involved. The following sections outline procedures to be followed in case of fire, explosion, run-on/run-off contamination, or suspected groundwater contamination:

3.5.1 Fire

The potential for fire is a concern in any landfill. The Landfill staff follows a waste handling procedure to minimize the potential for a landfill fire. If any load comes to the Landfill on fire, the driver of the vehicle will be directed to a pre-designated area away from the working face. The burning waste will be unloaded, spread out, and immediately covered with sufficient amounts of soil to smother the fire. Once the burning waste cools and is deemed safe, the material will then be incorporated into the working face. Some loads coming to the Landfill may be on fire but not detected until after being unloaded at the working face. If a load of waste that is on fire is unloaded at the working face, the load of waste will be immediately removed from the working face, spread out, and covered with soil.

The Utah County Fire department will be called if it appears that Landfill personnel and equipment cannot contain any fire at the Landfill. The Utah County Fire department will also be called if a fire is burning below the Landfill surface or is difficult to reach or isolate.

In case of fire, the District Manager will be notified immediately. A written report detailing the event will be placed in the operating record within seven days, including any corrective action taken.

3.5.2 Explosion

If an explosion occurs or seems possible, all personnel and customers will be accounted for and the Landfill evacuated. Corrective action will be immediately evaluated and implemented as soon as practicable.

The District Manager will be notified immediately and the Utah County Fire department called. The DWMRC Director will be notified immediately.

3.5.3 Failure of Run-On/Run-Off Containment

The purpose of the run-on/run-off control systems is to manage the stormwater falling in or near the Landfill. Were possible, water will be diverted away from the Landfill by utilizing ditches and berms. These ditches will be inspected on a regular basis and repaired as needed. All precipitation falling near the Landfill will flow around the perimeter of the Landfill and eventually towards the center of Cedar Valley.

If a run-off ditch or berm fails, temporary berms or ditches will be constructed until a permanent run-off structure can be repaired.

Any temporary berms or other structures will be checked at least every 2 hours during the storm event until storm water flow has stopped. Permanent improvements or repairs will be made as soon as practicable.

The Supervisor will be notified immediately if a failure of the run-off systems is discovered. The event will be fully documented in the operating record, including corrective action within 14 days.

3.5.4 Groundwater Contamination

The Landfill has no ground water monitoring wells. If ground water contamination is ever suspected, studies to evaluate the potential contamination will be conducted and the existence

and/or extent of contamination will be documented. This program may include the installation of ground water monitoring wells. A ground water monitoring program would be developed and corrective action taken as deemed necessary, with the approval of the DWMRC Director.

3.6 CONTINGENCY PLAN FOR ALTERNATIVE WASTE HANDLING

The most probable reason for a disruption in the waste handling procedures at the Landfill will be weather related. The Landfill may close during periods of inclement weather such as high winds, heavy rain, snow, flooding, or any other weather-related condition that would make travel or operations dangerous. The Landfill may also close for other reasons like fire, natural disaster, etc. In general, the NPSWSSD staff minimizes the possibility of disruption of waste disposal services from an operational standpoint.

In case of equipment failure, replacement equipment will be mobilized from the NPSWSSD Transfer Station operations or leased to continue operations while repairs are being made.

3.7 MAINTENANCE PLAN

3.7.1 Groundwater Monitoring System

The Landfill is currently exempt from requirements for groundwater monitoring. As a result, no groundwater monitoring system is planned.

3.7.2 Leachate Collection and Recovery System

The Landfill is currently exempt from requirements for leachate collection. As a result, no leachate collection and recovery system is planned.

3.7.3 Gas Monitoring System

The Landfill is currently exempt from requirements for a landfill gas monitoring system. No gas collection system is planned.

3.8 DISEASE AND VECTOR CONTROL

The vectors encountered at the Landfill are flies, birds, mosquitoes, rodents, skunks, and snakes. Due to the rural location of the landfill, stray house pets are occasionally encountered at the landfill. The program for controlling these vectors is as follows:

3.8.1 Insects

The elimination of breeding areas is essential in the control of insects. Landfill staff will minimize the breeding areas by covering the waste with soil at a minimum of every 30 days and maintaining surfaces to reduce ponded water.

3.8.2 Rodents

Reducing potential food sources minimizes rodent populations at the Landfill. Due to the nature of the C&D wastes, no significant numbers of mice or rats have been observed.

In the unlikely event of a significant increase in the number of rodents at the Landfill, a professional exterminator will be contacted. The exterminator would then establish an appropriate protocol for pest control in accordance with all county, state and federal regulations.

3.8.3 Birds

The Landfill has had minimal problems with birds. Good landfilling practices of waste compaction, daily covering of working faces, the minimization of ponded water, and the nature of the waste at the site has alleviated most of the bird problems. If the occasional need arises, the birds will be encouraged to leave by using cracker and whistler shells.

3.8.4 Household Pets

Because of the Landfills location, some stray cats and dogs may wander onto Landfill property. When stray animals are encountered (and can be caught), they are turned over to the animal

shelter. If the Operators are unable to apprehend the animals, they are chased off the property.

3.8.5 Wildlife

The Landfill has a variety of wildlife located on or near the landfill property. Wildlife includes deer, snakes, foxes, skunks, and coyotes. If problem skunks or snakes are encountered, they will be exterminated. If other site wildlife becomes a problem, the Landfill staff will coordinate with the Division of Wildlife Resources to provide methods and means to eliminate the problem.

In the event that any of these vectors become an unmanageable problem, the services of a professional exterminator will be employed.

3.8.6 Fugitive Dust

The roads leading to the Landfill are paved, however; access roads to the working face are improved dirt/gravel roads and will need occasional dust control measures. General operational activities and site access by vehicles compounded by the occasional high wind may present a fugitive dust problem. If the dust problem elevates above the "minimum avoidable dust level", the Operators will apply water to problem areas.

3.8.7 Litter Control

The nature of the C&D waste received at the Landfill is such that will naturally minimize the blowing of litter. However; due to the nature of Landfilling operations, blowing litter will still be an occasional problem. Landfill personnel perform routine litter cleanup to keep the Landfill and surrounding properties clear of windblown debris.

Whenever possible, the working face is placed downwind so that blowing litter is worked into the operating face. During windy conditions, landfill personnel minimize the spreading of the waste to reduce the amount of windblown debris.

3.9 RECYCLING

Currently, no recycling activities are conducted in conjunction with the ongoing C&D operations.

3.10 TRAINING PROGRAM

All personnel associated with the operation of the Landfill receive site specific training annually. The "Sanitary Landfill Operator Training Course" offered by the Solid Waste Association of North America (SWANA) is required by all employees. SWANA waste screening is also required of all Operators. Certificates of completion are kept in personnel files.

Regular safety and equipment maintenance training sessions are held to ensure that employees are aware of the latest technologies and that good safety practices are used at all times.

3.11 RECORDKEEPING

An operating record is maintained as part of a permanent record on the following items:

- Number of vehicles entering the landfill and types of wastes received on a monthly basis. Daily logs forms are submitted to the NPSWSSD Transfer Station operations for processing.
- Deviations from the approved Plan of Operation.
- Personnel training and notification procedures.
- Random load inspection log.

3.12 SUBMITTAL OF ANNUAL REPORT

NPSWSSD staff will submit a copy of its annual report to the DWMRC Director by March 1 of each year for the most recent calendar or fiscal year of facility operation. The annual report will include facility activities during the previous year and will include, at a minimum, the following:

- Name and address of facility.
- Calendar or fiscal year covered by the annual report.
- Annual quantity, in tons or volume, in cubic yards, and estimated in-place density in pounds per cubic yard of solid waste.
- Annual update of required financial assurances mechanism pursuant to Utah Administrative Code.
- Training programs completed.

3.13 INSPECTIONS

The District Manager, or his/her designee, will inspect the facility to minimize malfunctions and deterioration, operator errors, and discharges that may cause or lead to the release of wastes to the environment or to a threat to human health. These inspections will be conducted on a quarterly basis, at a minimum. A Facility Inspection Sheet (Appendix C) will be kept as part of the operating record. This log includes at least the date and time of inspection, the printed name and handwritten signature of the inspector, a notation of observations made, and the date and nature of any repairs or corrective actions. Inspection records are available to the DWMRC Director or an authorized representative upon request.

3.14 RECORDING WITH COUNTY RECORDER

Plats and other data, as required by the County Recorder, will be recorded with the Utah County Recorder as part of the record of title no later than 60 days after certification of closure.

3.15 STATE AND LOCAL REQUIREMENTS

The Landfill personnel will maintain compliance with all applicable state and local requirements including zoning, fire protection, water pollution prevention, air pollution prevention, and nuisance control.

3.16 SAFETY

Landfill personnel are required to participate in an ongoing safety program. This program complies with the Occupational Safety and Health Administration (OSHA), and the National Institute of Occupational Safety and Health (NIOSH) regulations as applicable. This program is designed to make the site and equipment as secure as possible and to educate landfill personnel about safe work practices.

3.17 EMERGENCY PROCEDURES

In the event of an accident or any other emergency situation, the Operator will immediately contact the Supervisor and proceeds as directed. If the Supervisor is not available, the Operator will call the District Manager or appropriate emergency number posted by the telephone. The emergency telephone numbers are:

Director, DWMRC.....(801) 536-0200



TABLE OF CONTENTS

1.0 – ENGIN	EERING REPORT	1
1.1 CELL DESIG	GN	
1.1.1	Fill Method	
1.1.2	Interim Cover	
1.1.3	Final Cover	2
1.1.4	Final Cover Elevations	2
1.2 DESIGN AI	ND LOCATION OF RUN-ON/RUN-OFF CONTROL SYSTEMS	2
1.3 REGIONAL	GEOLOGY	3
1.4 SITE SOILS		3
1.5 FLOODPLA	IN	3
1.6 WETLANDS	5	3
1.7 GROUND V	VATER	3
2.0 – CLOSU	IRE PLAN	4
2.1 CLOCUPE	SCHEDULE	4
	F FINAL COVER	
	OF SITE IN VOLUME AND TONNAGE	
	PECTION	
3.0 – POST-(CLOSURE CARE PLAN	6
3.1 SITE MON	ITORING	6
3.2 CHANGES	TO RECORD OF TITLE, LAND USE AND ZONING	6
3.3 MAINTEN	ANCE	6
3.4 POST-CLO	SURE CONTACTS	7
4.0 – FINAN	CIAL ASSURANCE	8
4.1 CLOSURE	COSTS	8
4.2 POST CLO	SURE CARE COSTS	8
4.3 FINANCIA	L ASSURANCE MECHANISM	8

1.0 - ENGINEERING REPORT

1.1 CELL DESIGN

The North Pointe Construction and Demolition Landfill (Landfill) is an ongoing C&D landfill operation located south of Fairfield in Utah County. The landfill is operated as a continuous cell with no specific boundaries to indicate individual landfill cells. The operation of the landfill is progressing from north to south while bringing the elevation of the final waste to design final cover elevations. Permit Drawings (Appendix A) shows the general arrangement of the landfill.

The landfill is designed such that operational soils are excavated some 10 feet to 15 feet below the existing grade to generate operational soils for monthly cover, landfill berms and final cover construction. The excavation of the 10 to 15 feet of operational soil is also shallow enough to ensure that the bottom of the landfill is more than 10 feet above the highest ground water elevations projected for the site. A Central Valley Water Reclamation stock water well located immediately west of the landfill shows ground water at 32 feet below the ground surface.

1.1.1 Fill Method

As described in Section 3.2.3 of Part II – General Report, waste is dumped at the toe of the working face and pushed uphill into place where possible. The C&D wastes will continue to be dumped at the toe of the work face when possible and spread up the slope in one to two-foot lifts, keeping the slope at a typical five to one (horizontal to vertical) configuration. The C&D wastes will then be compacted by making three to five passes up and down the slope. Site specific geometries associated with the landfill tipper are such that waste may need to be place at the top of the working face and pushed downhill for processing.

1.1.2 Interim Cover

Interim cover will be placed in compliance with the DWMRC Class VI requirements. Section R315-305 stipulates that timbers, wood, and other combustible waste be covered as needed to avoid a fire.

1.1.3 Final Cover

As specified in Rule R315-305-5, the final cover will consist of a minimum of two feet of soil, the upper six inches of which will be topsoil material capable of sustaining native vegetation. The topsoil layer will then be seeded with indigenous grasses and other shallow rooted vegetation.

1.1.4 Final Cover Elevations

The maximum elevation for the final cover is planned to be approximately 50 to 70 feet above surrounding grade along the west edge of the landfill. The top of the final cover will slope a minimum of 5% to the east and west to provide for a positive drainage of the final cover after potential settlement. The side slopes of the final cover have been planned to be as steep as 2.4:1 for the initial areas of the landfill but will be no steeper than to 3:1 for future side slopes. These slopes will allow for some settlement without compromising the run-off characteristics of the cover soil. The Drawings (Appendix A) details the topography of the final cover.

1.2 DESIGN AND LOCATION OF RUN-ON/RUN-OFF CONTROL SYSTEMS

Run-on control berms have been installed to intercept potential run-on precipitation from areas surrounding the Landfill. Given the nature of C&D debris, most of the precipitation falling within the operating area of the Landfill will infiltrate or be stored on site until the precipitation evaporates. Any precipitation that does not infiltrate or evaporate will be contained by the run-off control berms. The run-on and run-off control berms constructed are as indicated on the Drawings (Appendix A).

The Landfill operation has had all perimeter berms and ditches installed associated with the initial landfill operations. All precipitation that falls on the site will remain on the site. As the landfill operations continues to be developed to the south, additional perimeter ditches and berms will be constructed to route the water from the Landfill's operational face but maintain the water on-site.

Appendix D (2010 Application for Permit Renewal for Cedar Valley Construction and Demolition Landfill) contains the initial design of the ditches and berms for the facility. Specifically, Appendix G of the 2010 Application for Permit Renewal for Cedar Valley Construction and Demolition Landfill contains the data utilized to generate the storm water

calculations. IGES has reviewed the initial hydrological assessment along with site records and find the existing water diversion structures to be adequate.

1.3 REGIONAL GEOLOGY

The Landfill is located in Cedar Valley in Utah County. Appendix D (2010 Application for Permit Renewal for the Cedar Valley Construction and Demolition Landfill) presents the regional geology in that documents Appendix I.

1.4 SITE SOILS

Excavations across the site that were made in conjunction with the development of the Landfill indicate that the site is predominantly silty fine sand or fine sandy silts. Geologic maps identify the soils as:

Qlf: Lacustrine fine-grained deposits (upper Pleistocene)

Sand, silt, marl, and calcareous clay of Lake Bonneville; thinly to very thick bedded; locally includes the white marl of Gilbert (1890); thickness to 100 feet (30 m) or more.

1.5 FLOODPLAIN

The Landfill is not located in a floodplain.

1.6 WETLANDS

The Landfill is not located in or near wetlands.

1.7 GROUND WATER

The depth to ground water; measured in the Central Valley Water Reclamation stock water well located immediately west of the landfill indicates ground water at approximately 32 feet below the ground surface. Additional information on the ground water resources in the Cedar Valley can be found in Appendix D.

2.0 - CLOSURE PLAN

2.1 CLOSURE SCHEDULE

The Landfill will be closed incrementally as portions of the landfill reach final grade. Currently, six acres of the landfill have been closed while 51 acres are currently being operated for C&D waste disposal. Based on facility life calculations using a one- and one-half percent growth rate, final closure of the facility is expected to be more than 50 years in the future.

2.2 DESIGN OF FINAL COVER

As discussed previously, the final cover will consist of a minimum of two feet of soil six inches of which will consist of a topsoil material. The future side slopes of the final cover will be no steeper than a 3:1 (horizontal to vertical) with no portion of the final cover less than a 5% slope. The cover soil will be seeded with indigenous grasses.

2.3 CAPACITY OF SITE IN VOLUME AND TONNAGE

The Landfill capacity and projected life are presented in the following summary table:

YEAR	ESTIMATED DAILY	DAYS OF OPERATION	ESTIMATED YEARLY	ESTIMATED YEARLY	CUMULATIVE WASTE	REMAINING LANDFILL	
	C&D WASTE	OFERATION	C&D WASTE	C&D WASTE	(Cubic Yards)	CAPACITY	
	(Tons)*		(Tons)	(Cu. Yds.)	(000.010.00)	(Cu. Yds.)	
	(7		(/	(** ***)		23,625,000	
2020	558	260	145,145	290,290	290,290	23,048,710	
2025	601	260	156,362	312,725	312,725	21,530,624	
2030	648	260	168,447	336,893	336,893	19,895,214	
2035	698	260	181,465	362,930	362,930	18,133,412	
2040	752	260	195,489	390,979	390,979	16,235,452	
2045	810	260	210,597	421,195	421,195	14,190,810	
2050	873	260	226,873	453,747	453,747	11,988,150	
2055	940	260	244,407	488,814	488,814	9,615,259	
2060	1013	260	263,296	526,591	526,591	7,058,982	
2065	1091	260	283,644	567,288	567,288	4,305,145	
2070	1175	260	305,565	611,131	611,131	1,338,481	
Approximate Initial Waste Disposal Capacity (Cubic Yards) = 27,000,000							
Soil Usage is Approximately 12.5 Percent (Cubic Yards) = 3,375,000							
Net Airspace (Cubic Yards) = 23,625,000							
* Annual Growth Rate of 1.5%. **Conversion of Tons of Waste to Cubic Yards of Waste is Based Upon an Estimated Conversion							
Conversion of Tons of Waste to Cubic Yards of Waste is Based Opon an Estimated Conversion							

^{**}Conversion of Tons of Waste to Cubic Yards of Waste is Based Upon an Estimated Conversion Rate of 1,000 Pounds per One Cubic Yard

2.4 FINAL INSPECTION

A final inspection will be performed at the Landfill site at the termination of landfilling activities. The final inspection will determine if the Landfill meets all the closure requirements as outlined in the permit and closure plans. The final inspection will be performed by both NPSWSSD and State of Utah DWMRC personnel.

3.0 - POST-CLOSURE CARE PLAN

3.1 SITE MONITORING

There are no post-closure monitoring requirements for ground water, leachate, or landfill gas at the Landfill since there are no ground water, leachate or gas collection systems at the facility. However; the landfill cover and other physical aspects of the Landfill will be monitored on a quarterly basis during the post-closure care period.

Landfill topography shall be visually checked for depressions that could result in ponding or rapid erosion. Irregularities in the surface of the final cover will be regraded and revegetated as needed to protect the surface from erosion and to eliminate ponding.

Side slopes will be maintained or regraded to original slopes and the top slopes will be maintained or regraded to prevent ponding. The frequency of monitoring may be reduced only after a successful demonstration to the DWMRC Director that the closed Landfill has stabilized.

During the post-closure care period, run-off from the covered Landfill will be directed toward ditches constructed to collect and transport runoff to natural drainages east and southeast of the site. The ditches will be inspected quarterly through the post-closure period. Repairs to the ditches will be completed as part of the maintenance activities.

3.2 CHANGES TO RECORD OF TITLE, LAND USE AND ZONING

The Utah County Recorder will be provided plats and a statement of fact concerning the location of any disposal site no later than 60-days after certification of closure. If necessary, the closed Landfill will be rezoned to conform to the existing Utah County zoning regulations after final closure. A description of the Landfill history and filled areas will be permanently appended to the record of title. Land use restrictions will be assigned to the site in compliance with existing regulations for closed landfills at the time of closure.

3.3 MAINTENANCE

Post-closure maintenance activities will be designed and implemented under the direction of a licensed professional engineer in response to results of inspections. Results of post-closure

maintenance shall be reported to the DWMRC Director by a professional engineer licensed in the state of Utah.

Because of the arid climate in Utah County, maintenance of final covers and run-on/run-off systems should be minimal. Final cover and control structures will be inspected quarterly as indicated previously.

Run-on/run-off control structures and final covers could be damaged by an unusually intense storm. Consequently, an unscheduled inspection may be required after any occurrence of an unusual storm event within a five-mile radius of the site. If the post-storm inspection discloses damage, it will be appraised by a licensed engineer. NPSWSSD staff will solicit bids if necessary and supervise repair construction as necessary. Funds for payment for the repair work will be disbursed from the Financial Assurance Funds after approval by the DWMRC Director.

3.4 POST-CLOSURE CONTACTS

North Pointe SWSSD	(801) 225-8538
1101 (11 FOILLE 37733D	

4.0 - FINANCIAL ASSURANCE

4.1 CLOSURE COSTS

The North Pointe Construction and Demolition (C&D) Landfill will be closed as portions of the Landfill reach final grade. The typical size of each closure is anticipated to be no larger than 10–acres. The closure cost estimates are based on the cost to close the largest area open which is the existing 51 acres. Closure cost estimates include the cost of obtaining, moving and placing the cover material, final grading, placing topsoil, fertilizing and seeding.


4.2 POST CLOSURE CARE COSTS

The post-closure estimate must be the cost for completing care reasonably expected during the 30-year post-closure period. These tasks include site inspections, maintenance, and record keeping.

4.3 FINANCIAL ASSURANCE MECHANISM

Financial assurance cost estimates and PTIF fund paperwork are presented in Appendix E.

APPENDIX A





CEDAR VALLEY CLASS VI LANDFILL 2020 PERMIT RENEWAL

VICINITY MAP

PROPERTY

SITE MAP





North Point Solid Waste Special Service District

2000 West 200 South Lindon, Utah (801) 225-8538 (T)



CHECKED BY:

CEDAR VALLEY LF - PERMIT TITLE


SHEET



- 1 TITLE SHEET
- 2 GENERAL ARRANGEMENT
- 3 LANDFILL DEVELOPMENT
- **4 ELEVATION VIEW**
- 5 DETAILS









MARK DATE DESCRIPTION

00853\009\2020 Permit

CEDAR VALLEY LF - PERMIT

ELEVATION

1 2 3 4 4'-0" North Point Solid Waste Special Service District 2000 West 200 South Lindon, Utah (801) 225-8538 (T) CONSULTANTS 6'-0" 2702 South 1030 West, Suite 10 Salt Lake City, Utah 84119 (801)270-9400 (T) (801)270-9401 (F) DT-01 RUN-ON DIVERSION BERM - TYPICAL CROSS SECTION
3,4 NTS 14'-0" DT-02 RUN-OFF CONTROL BERM - TYPICAL CROSS SECTION
3,4 NTS MARK DATE DESCRIPTION (DT-03) FINAL C&D LANDFILL COVER 00853-009 CAD DWG FILE: 00853\009\2020 Permit DRAWN BY: DESIGNED BY: BDM CHECKED BY: RH COPYRIGHT: SHEET TITLE CEDAR VALLEY LF - PERMIT **DETAILS**

APPENDIX B

WHEN RECORDED, MAIL TO: FAIRFIELD TOWN P.O. Box 271 Cedar Valley, Utah 84013



ENT 29924:2012 PG 1 of 3
JEFFERY SMITH
UTAH COUNTY RECORDER
2012 APR 12 1:32 PM FEE 0.00 BY DRG
RECORDED FOR FAIRFIELD TOWN

Quit-Claim Deed

Parcel # 59:116:0014

Utah County

NORTH POINTE SOLID WASTE SPECIAL SERVICE DISTRICT, **Grantor**, hereby Grants quit-claims and conveys to the FAIRFIELD TOWN, UTAH, a political subdivision of the State of Utah, herein referred to as **Grantee**, for the sum of Ten Dollars, and other good and valuable considerations, the following described parcel of land for use as a city street right-of-way in Utah County, State of Utah, without warranties of title, to-wit:

A parcel of land being part of tract of property situate in the South Half of Section 8, T-7-S., R-2-W., S.L.B. & M. The boundaries of said right-of-way parcel are described as follows:

Beginning at the South Quarter Corner of Section 8, Township 7 South, Range 2 West, Salt Lake Base and Meridian; thence along the South Line of Said Section 8, South 89°36'09" West 837.61 feet; thence North 0°12'31" East (record North 0°12'43" East) along the westerly boundary of the NORTH POINTE parcel 33.00 feet; thence North 89°36'09" East along a line parallel and 33.00 feet distant northerly from the South line of said Section 8, 837.26 feet; thence North 89°36'36" East along a line parallel and 33.00 feet distant northerly from the South line of said Section 8, 2657.27 feet to the East line of said Section 8; thence along the East line of said Section 8, South 0°19'06" West 33.00 feet to the Southeast Corner of said Section 8; thence along the South line of said Section 8, South 89°36'36" West 2656.86 feet to the South Quarter Corner of said Section 8, and the point of beginning.

Containing 2.65 Acres

(Note: Basis of Bearing: Utah State Plane Coordinate System, Utah Central Zone, (NAD 1983)

IN WITNESS WHEREOF, said North Bint Solid Waste Special Savice District have cause this instrument to be executed thereunto duly authorized, this
North Pointe Solid Waste Special Service District By: Its Chairman
STATE OF UTAH)) ss. County of Utah)
On the date first above written personally appeared before me, Rodger D. Harper,
who, being by me duly sworn say that he is the Chairman of North Pointe Solid Waste special
Service District and executed the same.
WITNESS my hand and official stamp the date in this certificate first above written:
ABBY M. ROWETT NOTARY PUBLIC-STATE OF UTAH COMMISSIONS 577717 COMM. EXP. 02-23-2013



Fairfield School House, 1898

FAIRFIELD

Established 1856 - Incorporated 2004

Mayor Michael Burch P.O. Box 271 Cedar Valley, Utah 84013 (801) 766-3509

April 2, 2012

Jeff Smith Utah County Recorder 100 East Center Street, Room 1300 Provo, Utah 84606

RE: Acknowledgment of exchange of property for proposed landfill road right-of-way.

Mr. Smith,

This letter is to inform you that the Town of Fairfield acknowledges that the following described parcels of land owned by North Pointe Solid Waste Special Service District and ROC Fund Landfill Holdings LLC is to be granted and conveyed to the town for use as a city street right-of-way in Utah County, State of Utah.

North Pointe Solid Waste Special Service District property is a parcel of land being part of tract of property situate in the South Half of Section 8, T-7-S., R-2-W., S.L.B. & M.

ROC Fund Landfill Holdings LLC property is a parcel of land being part of tract of property situate in the Northwest Quarter of Section 16, T-7-S., R-2-W., S.L.B. & M.

Should you have any questions, please contact me at (801) 631-5451.

Sincerely,

Michael Burch

Mayor


APPENDIX C

North Pointe Cedar Valley Landfill Facility Inspection Sheet

Date:	Inspector:
This inspections sheet is use Monthly basis.	d to document the condition of the facility on
Scale:	
ToolShack:	
Perimeter Fences:	
	ems:
Roadways:	
Cian aturn	
Signature	

North Pointe Cedar Valley Landfill Random Load Inspection

Inspector:		
Customer:		
Load Size:		
Contents:		
Description	Yes	No
Lumber		
Concrete		
Plastic		
Paper		
Large Tires		
Metal		



Utah Class V and V Landfill Permit Application Form 2010 022				_ H <i>A</i>	ND	DELIVER
Tandfill Class IVa Class IVb Application New Application Talephone Class IVb Mapplication Map	Utah Glass I	V and VI Lai	ndfill Permit Application	on Form	20	10,0211.
For Renewal Applications Facility Expansion Applications and Modifications Enter Curient Permit Number	Part 7 General Information APPLICANT	PLEASE COM	APLETE ALL SECTIONS		ĴŪ	N Z 1 ZUIU
For Renewal Applications Facility Expansion Applications and Modifications Enter Curient Permit Number			ation New App (X) Renewal	Application	HA	FORWYSTORNSON WORKSMANIS W
Legal Name of Facility Operator (s) Information Owner Contact DAVID JOHNSTON Title MANAGER Address (making) P O BOX 1503 City OREM State UT Zip Code 84059 Telephone (801) 437-9502	For Renewal Applications Facility Expansion Applications	s and Modifications		0012		
County		<u>-</u>				
18150 WEST ALLEN RANCH ROAD						
Code				1 -		
Name Company Section Section Counter	City FAIRFIELD			Telephone	801) 437	-9502
TV Facility Owner(s) Information Legal Name of Facity Owner CEDAR VALLEY LANOFILL LC / GZ ROCK LLC Address (mailing) P.O BOX 1503 City OREM State UT Zip Code 84059 Teleptione (801) 437-9502 V Facility Operator(s) Information Legal Name of Facity Operator CEOAR VALLEY LANOFILL LC Address (mailing) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801)437-9502 VI Property Owner(s) Information Legal Name of Property Owner(s) Information Cety Owner(s) Information Owner Contact Information Owner Contact Information Owner Contact DAVID JOHNSTON Title MANAGER Address (mailing) P O BOX 1503 City ONEM State UT Zip Code 84059 Telephone (801) 437-9502 Alternative Telephone (cell or other) Operator Contact DAVID JOHNSTON Title MANAGER Address (meiling) P O BOX 1603 City OREM State UT Zip 84069 Telephone (801) 437-9502 City OREM State UT Zip Alternative Telephone (cell or other) Operator Contact DAVID JOHNSTON Title MANAGER Address (meiling) P O BOX 1603 City OREM State UT Zip 84069 Telephone (801) 437-9502 Code 84069 Telephone (801) 437-9502 Address (meiling) P O BOX 1603 City OREM State UT Zip Alternative Telephone (cell or other) Alternative Telephone (cell or Alternative Telephone (cell or other) Alternative Telephone (cell or Alternative Telephone (cell or other) Alternative Telephone (cell or Alternative Telephone (cell or Alternative Telephone (cell or other) Alternative Telephone (cell or Alte	Township 7 S Range 2 W Section(s) 5 & 8			Quarter	Section	
Legal Name of Facility Operator (SDR VALLEY LANOFILL LC / GZ ROCK LLC Address (mailing) P.O BOX 1503 City OREM State UT Zip Code 84059 Teleptione (801) 437-9502 V Facility Operator (S) Information Legal Name of Facility Operator CEOAR VILEY LANDFILL LC Address (mailing) P O BOX 1503 City OREM Stale UT Zip Rode 84069 Telephone (801)437-9502 V Property Owner(s) Information Legal Name of Property Owner (S) Information Title MANAGER Address (mailing) P O BOX 1503 City ONEM State UT Zip Code 84059 Telephone (801) 437-9502 Alternative Telephone (cell or other) Operator Contact DAVID JOHNSTON Tide MANAGER Address (melling) P O BOX 1603 City OREM State UT Zip Rode 84069 Telephone (801) 437-9502 Email Address (melling) P O BOX 1603 City OREM State UT Zip Rode 84069 Telephone (801) 437-9502 Email Address (melling) P O BOX 1603 City OREM State UT Zip Rode 84069 Telephone (801) 437-9502 Alternative Telephone (cell or other) Alternative Telephone (cell or Alternative Telephone (cell or OREM) Alternative Telephone (cell or Alternative Telephone (cell or OREM) Alternative Telephone (cell or Alternative Telephone (cell or OREM) Alternative Telephone (cell or Alternative Telephone (cell or OREM) Alternative Telephone (cell or Alternative Telephone (cell or Alternative Telephone (cell or OREM)	Mam Gale Latitude40 degrees 14 minutes 28	seconds N	Longitude 112 degrees	05 minutes	49	seconds W
CEDAR VALLEY LANOFILL LC / GZ ROCK LLC	7V Facility Owner(s) Information					
Address (mailing) P.O BOX 1503 City OREM State UT Zip Code 84059 Teleptrone (801) 437-9502 V Facility Operator (\$0 information Legal Name of Facility Operator CEORY VLLEY LANDFILL LC Address (mailing) P.O. BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 VI Property Owner(\$) Information Legal Name of Property Owner GROCK LLC Address (mailing) 1819 EAST MORTON AVENUE City PHOENIX State AZ Zip Code 85020 Telephone (602) 943-2360 VII Contact Information Owner Contact DAVID JOHNSTON Address (mailing) P.O. BOX 1503 City ONEM State UT Zip Code 84059 Telephone (801) 437-9502 Email Address david@sununitdevelop.coin Operator Contact DAVID JOHNSTON Title MANAGER Address (mailing) P.O. BOX 1503 City ONEM State UT Zip Code 84059 Telephone (801) 437-9502 Address (meiling) P.O. BOX 1503 City OREM State UT Zip MANAGER Address (meiling) P.O. BOX 1503 City OREM State UT Zip MANAGER Address (meiling) P.O. BOX 1503 City OREM State UT Zip MANAGER Alternative Telephone (cell or other)	Legal Name of Facility Owner CEDAR VALLEY LANOFILL LC / GZ ROCK LLC					
V Facility Operator(s) Information Legal Name of Facility Operator CEOAR VLLEY LANDFILL LC Address (making) P O BOX 1503 City OREM Stale UT Zip Code 84069 Telephone (801)437-9502 V Property Owner(s) Information Legal Name of Property Owner GZ ROCK LLC Address (making) 1819 EAST MORTON AVENUE City PHOENIX Stale AZ Zip Code 85020 Telephone (602) 943-2360 VI Contact Information Owner Contact DAVID JOHNSTON Address (making) P O BOX 1503 City ONTEM State UT Zip Code 84059 Telephone (801) 437-9502 Alternative Telephone (cell or other) Address (making) P O BOX 1503 City ONTEM State UT Zip Code 84069 Telephone (801) 437-9502 Address (making) P O BOX 1503 City ONTEM State UT Zip Code 84069 Telephone (801) 437-9502 Address (making) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Address (melling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Address (melling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Alternative Telephone (cell or other) Alternative Telephone (cell or Alternative Telephone (801) 437-9502 Alternative Telephone (cell or Alternative Telephone (cell or Code 84069)	Address (mailing)					
V Facility Operator(s) Information Legal Name of Facility Operator GEOAR VLLEY LANDFILL LC Address (mailing) P O BOX 1503 City OREM Stale UT Zip Code 84069 Telephone (801)437-9502 VI Property Owner(s) Information Legal Name of Property Owner GE ROCK LLC Address (mailing) 1819 EAST MORTON AVENUE City PHOENIX Stale AZ Zip Code 85020 Telephone (602) 943-2360 VII Contact Information Owner Contact DAVID JOHNSTON Title MANAGER Address (mailing) P O BOX 1503 City ONTEM State UT Zip Code 84059 Telephone (801) 437-9502 Alternative Telephone (cell or other) Operator Contact DAVID JOHNSTON Title MANAGER Address (mailing) P O BOX 1503 City ONTEM State UT Zip MANAGER Address (mailing) P O BOX 1603 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Address (mailing) P O BOX 1603 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Alternative Telephone (cell or other) Address (mailing) P O BOX 1603 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Alternative Telephone (cell or Alternative Telephone (cell or Other)	City OREM	State UT		Teteptione	(801) 437	7-9502
Address (maling)	V Facility Operator(s) Information	<u></u>		L	· · · · · · · · · · · · · · · · · · ·	
City OREM Stale UT Zip 84069 Telephone (801)437-9502 VI Property Owner(s) Information Legal Name of Property Owner GZ ROCK LLC Address (mailing) 1819 EAST MORTON AVENUE City PHOENIX Stale AZ Zip Code 85020 Telephone (602) 943-2360 VII Contact informiation Owner Contact DAVID JOHNSTON Title MANAGER Address (mailing) P O BOX 1503 City ONEM Stale U7 Zip Code 84059 Telephone (801) 437-9502 Atternative Telephone (cell or other) Operator Contact DAVID JOHNSTON Title MANAGER Address (meiling) P O BOX 1503 City OREM Stale UT Zip MANAGER Address (meiling) P O BOX 1503 City OREM Stale UT Zip MANAGER Address (meiling) P O BOX 1503 City OREM Stale UT Zip MANAGER Address (meiling) P O BOX 1503 City OREM Stale UT Zip MANAGER Address (meiling) P O BOX 1503	Legal Name of Faoilly Operator CEOAR VLLEY LANDFILL LC					
VI Property Owner(s) Information Legal Name of Property Owner GZ ROCK LLC Address (malking) 1819 EAST MORTON AVENUE City PHOENIX State AZ Zip Code 85020 Telephone (602) 943-2360 VII Contact Information Owner Contact DAVID JOHNSTON Address (malking) P O BOX 1503 City ONTEM State U7 Zip Code 84059 Telephone (801) 437-9502 Email Address david@sununitdevelop.coin often of the management of the managem				-		
VI Property Owner(s) Information Legal Name of Property Owner GZ ROCK LLC Address (malking) 1819 EAST MORTON AVENUE City PHOENIX State AZ Zip Code 85020 Telephone (602) 943-2360 VII Contact information Owner Contact DAVID JOHNSTON Title MANAGER Address (malling) P O BOX 1503 City ONTEM State U7 Zip Code 84059 Telephone (801) 437-9502 Email Address david@sununitdevelop.coin Other) Operator Contact DAVID JOHNSTON Tide MANAGER Address (melling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 City OREM State UT Code 84069 Telephone (801) 437-9502 Email Address (melling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502	City OREM	Stale UT		Telephone	(801)437	7-9502
Address (malking) 1819 EAST MORTON AVENUE City PHOENIX State AZ Zip Code 85020 Telephone (602) 943-2360 VII Contact informiation Owner Contact DAVID JOHNSTON Title MANAGER Address (malking) P O BOX 1503 City (NtEM State U7 Zip Code 84059 Telephone (801) 437-9502 Email Address david@suntinitdevelop.coin Alternative Telephone (cell or other) Operator Contact DAVID JOHNSTON Tide MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84059 Telephone (801) 437-9502 Email Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502	VI Property Owner(s) Information			1		
Title MANAGER City PHOENIX Contact Information Owner Contact DAVID JOHNSTON Address (malling) P O BOX 1503 City Ontem State U7 Code 84059 Email Address david@sununitdevelop.coin Operator Contact DAVID JOHNSTON Atternative Telephone (cell or other) Title MANAGER Telephone (801) 437-9502 Atternative Telephone (cell or other) P O BOX 1503 City OREM State UT Zip MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Atternative Telephone (cell or Other)						
Code 85020 Telephone (602) 943-2360 VII Contact information Owner Contact DAVID JOHNSTON Title MANAGER Address (mailing) P O BOX 1503 City ONTEM State U7 Code 84059 Telephone (801) 437-9502 Email Address david@sununitdevelop.coin Other) (801) 420-1924 Operator Contact DAVID JOHNSTON Tide MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Email Address david@sununitdevelop.com Alternative Telephone (801) 437-9502			-	<u> </u>		
Owner Contact Informiation Owner Contact DAVID JOHNSTON Address (malling) P O BOX 1503 City ONTEM State U7 Code 84059 Alternative Telephone (cell or other) Operator Contact DAVID JOHNSTON Address (meiling) P O BOX 1503 City OREM State U7 Zip Code 84059 Alternative Telephone (cell or other) Tide MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Alternative Telephone (cell or Alternative Telephone (cell or Ocode) Alternative Telephone (cell or Ocode) Alternative Telephone (cell or Ocode)	City PHOENIX	State AZ	Zip Code 85020	Telephone	(602) 943	-2360
Address (mailing) P O BOX 1503 City ONTEM State U7 Code 84059 Telephone (801) 437-9502 Email Address david@sununitdevelop.coin Alternative Telephone (cell or other) (801) 420-1924 Operator Contact DAVID JOHNSTON Tide MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Email Address david@summitdevelop.com Alternative Telephone (cell or other)	VII Contact information					
City ONTEM State U7 Code 84059 Telephone (801) 437-9502 Email Address david@sununitdevelop.coin Alternative Telephone (cell or other) (801) 420-1924 Operator Contact DAVID JOHNSTON Tide MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Email Address david@sunmitdevelop.com Alternative Telephone (cell or	Owner Contact DAVID JOHNSTON		Title MANAGER			
City ONTEM State U7 Code 84059 Telephone (801) 437-9502 Email Address david@sunrinitdevelop.coin Alternative Telephone (cell or other) (801) 420-1924 Operator Contact DAVID JOHNSTON Tide MANAGER Address (meiling) PO BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Email Address david@sunmitdevelop.com Alternative Telephone (cell or	Address (malling) P O BOX 1503					
Operator Contact DAVID JOHNSTON Tide MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Email Address david@summitdevelop.com Alternative Telephone (cell or		State U7	Zip Code 84059	Telephone (301) 437-	9502
Operator Contact DAVID JOHNSTON Tide MANAGER Address (meiling) P O BOX 1503 City OREM State UT Zip Code 84069 Telephone (801) 437-9502 Email Address david@summitdevalor.com Alternative Telephone (cell or	Email Address david@suniinitdevelop.coin			(8	01) 420-1	924
P O BOX 1503 City OREM State UT Zip 84069 Telephone (801) 437-9502 Email Address david@summitdevelop.com Alternative Telephone (cell or	Operator Contact DAVID JOHNSTON					· · · · · · · · · · · · · · · · · · ·
Email Address david@summitdevalor.com Alternative Telephone (cell or	• •					
Email Address david@summitdevelop.com Alternative Telephone (cell or	City OREM	State UT		Telephone	(801) 43	7-9502
other) (801) 420-1924	Email Address david@summitdevelop com		Alternative Telephone (cell or		01) 420-1	924
Property Owner Contact BARRY ZEMEL Title MANAGER	Property Owner Contact BARRY ZEMEL					
Address (mailing) 1819 EAST MORTON AVENUE	Address (maling) 1819 EAST MORTON AVENUE					
Zin Zin	O	State A7	Zip	Telephone 4	502\ D42	.2250
Email Address zeinel36@yahoo com State AZ Code 85020 Telephone (602) 943-2360 Alternative Telephone (cell or other)	· IIOLIIA	74	Alternative Telephone (cell or	1	UUZ) 343-	-2300

Utah Class IV and VI Landfill Permit Application Form

Pa <i>r</i> t	d General Information (Continued)				
VIII	Waste Types (check all that apply)	DX F	acility Area		
	Landfill will accept all wastes allowed m Class IV or VI landfills Or	Facility Area		298 6	acres
Wast	il will accept only the following wastes e Type Combined Disposal Unit Monolill Unit	Dispos Area	al	27 0	acres
	Construction & Demolition	Design	Capacity Years	58	
	Contaminated Soil		Cubic Yards	29.5 milli	on
	Disposal of dead animals must be approved by the Executive stry		Tons	14 8 mill	on
ΧF	ee and Application Documents				
Indica	te Documents Attached To This Application	Applicah	on Fee Amount \$	Class VI Special Requi	rements
		of Operatio Estimates	Waste Oescription Financial Assurance	Documents raquii 108(9) and (10)	ed by DCA 19 6
THE	REBY CERTIFY THAT THIS INFORMATION AND ALL	ATTAC	HED PAGES ARE CORR	ECT AND COMPLE	TE
Signal	Wire of Authorized Owner Representative Wire N. William		Thie Manger	Date 7/15	11)
Name	14 VID NY JOHNS TON typed arpfinled		Address POBOA 150	3 0 Pany Vt	, 8405
Signat	ture of Authorized Kand Owner Representative (if applicable)		Title MGL MAR	Date 2/10/10	,
	BANY ZEMEL		Address		
	typed or printed		1819 £ MONDEN	PAX AVE	3020
Signat	ure of Authorized Oparator Representative (if applicable)		Manager	Date 2/15/1/	,
Name	AND N. FOHNSTON typed or prifited		Address	Over Ut. 8	34-059
	77F		<u> </u>	viva vv.	

Cedar Valley Construction and Demolition Landfill

Class VI Landfill

Application for Permit Renewal

June 2010

Current Pennit No 0012

Cedar Valley Landfill P O Box 1503 Orem, Utah 84059

Application Form

Cedar Valley Construction and Demolition Landfill

Table of Contents

		Page Number
10	General Information	4
11	Legal Description	4
12	Proof of Ownership	5
1 3	Waste Type	5
1 4	Schedule of Construction	6
20	Plan of Operation	6
2 1	Waste Handling Procedures	6
22	Inspections and Monitoring	7
23	Fire and Explosion	7
24	Fugitive Dust	8
2 5	Litter Control	8
26	Prohibited Waste Exclusion Plan	9
2 7	Controlling Disease Vectors	11
28	Alternate Waste Handling	12
29	General Traimng and Safety Plan	12
2 10	Recycling Programs	13
2 11	Site Specific Information	13
3 0	Engineering	13
3 1	General Construction Plans	13
3 2	Run On and Run Off	14
3 3	Facility Life	14
3 4	Location Standards	14
3 5	Borrow Sources	15
3 6	Rim-off Collection	15
4 0	Closure Plan	15
5 0	Post Closure Plan	16
60	Financial Assurance	16

Part II General Report

1.0 General Facility Description

Cedar Valley Construction and Demolition Landfill is located in the Town of Fairfield in Utah Coimty, Utah The facility is located 1.5 miles southerly of the main center of Town. The facility is a Class VI landfill that receives yard waste, inert waste, and construction and demolition waste. It contains 298 6 acres of land all of which is flat and generally sloping to the south and east. Currently 69.5 acres of land is fenced with a 6' chain link fence topped with 3 strands of barbed wire. Located on site are a scale and scale house, a 120,000 gallon water reservoir, a water shed, and a small office house. The landfill site is first excavated below ground to create a pit for dumping. The waste is covered and mixed with soil as it fills in. The site is bermed on the sides and extends above grade at a slope of 2.4.1

1.1 Legal Description

The overall legal description is as follows

Commencing at a point m the center line of a county road, said point being located N00°45'22"W along the Section Line 1343 60 feet, and East 1257 45 feet from the West Quarter Comer of Section 5, Township 7 South, Range 2 West, Salt Lake Base and Meridian, thence S89°42'06"E, 74 22 feet, thence S00°16'40"E, 1347 56 feet, thence S89°48'26"E along the guarter section line 1320 48 feet to the center of Section 5, thence S00°12'08"W, along the quarter section line 2646 06 feet to the guarter comer common to Section 5 and Section 8, thence \$00°20'54"W along the guarter section line 2707 93 feet to the center of said section 8. Township 7 South, Range 2 West, thence N89°32'40"E, along the quarter section line1327 91 feet, thence S00°20'12"W, 1325 56 feet, thence N89°34'40"E, 1328 17 feet, thence S00°19'31"W, along the section line 1326 33 feet to the Southeast Comer of said Section 8, thence S89°36'40"W, along the section line 2656 85 feet to the South Ouarter Comer of said Section 8, thence S89°36'21"W, along the Section line 837 61 feet to the center line of a county road, thence along the center line of said county road as follows N00°12'43"E, 302 92 feet, thence N00°39'59"E, 1196 28 feet, thence N00°37'44"E, 2427 90 feet, thence N00°35'40"E, 1861 44 feet, thence N00°52'12"E, 405 93 feet, thence along the arc of a 400 00 foot radius curve to the left 316 45 feet (chord bears N21°47'38"W, 308 26 feet), thence N44°27'28"W, 473 22 feet, thence N45°02'02"W, 137 61 feet, thence N44°56'18"W, 131 01 feet, thence N42°46'21"W, 92 34 feet, thence along the arc of a 360 00 foot radius curve to the right, 313 28 feet (chord bears N17°50'34"W, 303 49 feet), thence N07°05'14"E, 428 46 feet, thence N05°05'24"E, 201 10 feet, thence N04°53'03"E, 678 65 feet, thence N06°19'16"E, 569 05 feet, thence along the arc of a 2550 00 foot radius curve to the left, 130 05 feet (chord bears N04°51'36"E, 130 04 feet) to the point of beginning

Less and excepting the following

Beginning at a point in the center line of a county road said point being located N00°45'22"W, along the Section Line 1343 60 feet, and East 1257 45 feet from the West Quarter Comer of Section 5, Township 7 South, Range 2 West, Salt Lake Base and Mendian and running thence S89°42'06"E, 74 22 feet, thence S00°16'40"E, 447 43 feet to a fence line, thence S 89°59'07"W 122 66 feet along said fence line and the extension thereof to the center of said county road, thence N06°19'16"E, 320 22 feet along the center line of said county road, thence northerly 130 06 feet along the arc of a curve to the left, having a radius of 2550 00 feet (chord bears N04°51'36"E, 130 037 feet) to the point of beginning

1.2 Proof of Ownership

The property is currently owned by GZ Rock, LLC A copy of the recorded Tmstee's **D**eed is attached in Appendix A The facility owner and operator is Cedar Vally Landfill, LC

1.3 Waste Type

Waste accepted for disposal at this site is construction and demolition waste, mert waste, and yard waste comprised mainly of wood, cardboard, wallboard, and any and all waste that meet the requirements of the UAC R315-301-2(17)(37)(87) Waste not accepted includes, but not limited to mumcipal, industrial, medical, and hazardous wastes, liquids, used oils, contaminated soils, dead animals, and tires

Construction and **D**emolition Waste is defined in R305-301-2(17) means solid waste from building materials, packaging, and mbble resulting from construction, remodeling, repair, abatement, rehabilitation, renovation, and demolition operations on pavements, houses, commercial buildings, and other structures, including waste from a conditionally exempt small quantity generator of hazardous waste, as defined by R315-2-5, that may be generated by these operations

- (a) Such waste may mclude
 - (1) Concrete, bncks, and other masonry materials
 - (u) Soil and rock

- (111) Waste asphalt
- (iv) Rebar contamed m concrete
- (v) Untreated wood and tree stumps

Inert Waste is defined in R315-301-2(37) and means, noncombustible nonhazardous solid wastes that retain their physical and chemical structure under expected conditions of disposal, including resistance to biological or chemical attack

Yard Waste is defined in R315-301-2(87) means vegetative matter resulting from landscaping, yard maintenance, and land clearing operations including grass clippings, pruning, and other discarded material generated from yards, gardens, parks, and similar types of facilities. Yard waste does not include garbage paper, plastic, processed wood, sludge, septage, or manure

The daily volume anticipated for the landfill is approximately 260 cubic yards per day. This is based on last years amount of 50,000 tons of waste received at the landfill

1.4 Schedule of Construction

The permit application is for renewal The landfill is constructed and in operation

2.0 Plan of Operation

2.1 Waste Handling Procedures

The landfill operates by excavating and removing the existing soil from the site to a depth of approximately 20 feet deep. Beyond the 20 feet deep, the amount of soil removed becomes burdensome to the overall productivity of the landfill. The soil is stock piled to be mixed with the waste and also to cover the site after the desired height is obtained. When waste is brought to the site it is first weighed at the scales and then taken to a location on the site to be dumped. A cat and or compactor pushes

the waste to consolidate and compact it, and mix it with soil. The compactor is used to remove voids within the dumped waste. Dirt is mixed with the waste, as well as dumped over the surface of the waste to bind the waste and to keep it from blowing from the site, and to better control the possibility of combustion. Timcks that have dumped waste will again pass over the scales to determine the amount of waste that was deposited on the site.

See sample form for weight recording m Appendix B

The working surface of the site is covered by a minimum of 6" of native soil. This covering allows for a better driving surface, as well as to provide the cover required to avoid combustion of the waste. This cover is applied daily to the working surface.

2.2 Inspections and Monitoring

Inspections are performed to satisfy R315-302-2(5)(a) A brief visual inspection of equipment and the facility is completed daily. All problems found which threaten human health or environmental quality will be noted and fixed immediately. All other findings of these brief visual inspections will be fixed in a timely manner. A thorough inspection of the whole facility will be done quarterly. Its findings will be logged and any and all corrective action will be noted. See Appendix C for sample form (please note that not all of the items apply)

2 3 Fire and Explosion

Facility personnel will be prepared for immediate fire suppression in the event of a fire mvolving the waste. Fire extinguishers are mounted on equipment. On-site cover fill will be used to cover the known fire, or smoldering areas. Water will be applied to the affected areas only as a last resort, thus to mimmize water to waste contact. In the event that the on-site personnel can not manage the fire because of its size, or a dangerous condition is evident, the Eagle Mountain Fire Department will be notified. The Fire Department is located in Eagle Mountain City approximately

10 miles away Response time is estimated at 15 mmutes. The responding Fire Department will then take responsibility for fire suppression and extinguishing

2.4 Fugitive Dust

Dust can be a problem from May through October as these are the drier and warmer times of the year. The soil on the site consists mainly of clay and silty sands. A water trick is employed to keep the site damp especially in the traveled areas. Crished concrete and road base are used at the site entrance to keep a roadway that is more dust free. Also, the main road to the site is being improved by wideming the roadway and placing road base and eventually asphalt.

As the height of the landfill mcreases, the new exposed sides are planted with a native seed mix. This planting is accomplished in the fall, October or November of each year. By planting in the fall, the seed will remain dormant through the winter and then have the spring moisture to germinate. The vegetation around the landfill holds the soil from blowing and creating dust from the perimeter slopes.

2.5 Litter Control

Blowing litter has been a problem and continues to be a challenge on the site. The active portion of the site is fenced with a six-foot chain link fence to attempt to keep blowing litter from leaving the site. However, the fence alone does not keep litter from blowing. In addition to the fence portable "wind screens" have been fabricated to collect litter that is blown from the landfill. The "wind screens" are located on top of the berm allowing for maximum efficiency. As the operations continue to be refined, more dirt is mixed with the waste. The additional cover and mixture of dirt also keeps litter from blowing from the site. Occasionally, a wind storm has come across the site that has picked up litter and blown it from the site. When this occurs, the litter is gathered manually and brought back to the site and buried



(Portable Wind Screens located on the site)

2.6 Prohibited Waste Exclusion Plan

Wastes which are prohibited from disposal at the Cedar Valley Landfill include, but are not limited to, municipal, industrial, and medical wastes, hazardous wastes, liquids, used oils, contaminated soils, dead animals, and tires. Pursuant to UAC 315-303-4(7), an owner or operator of a solid waste disposal facility shall not knowingly dispose, treat, store, or otherwise handle hazardous waste or waste containing PCBs. An owner or operator of a solid waste disposal facility shall include and implement, as part of the plan of operation, a plan that will inspect loads or take other steps as approved by the Executive Secretary that will prevent the disposal of prohibited hazardous waste or prohibited waste containing PCB's (R315-303-4-(7)(b)). This plan includes random inspections, separate inspection area, training of on-site personnel to identify prohibited waste, and a written record of the inspections signed by the inspector.

Containers holding liquid, larger than household containers, are not acceptable at the landfill Containers exceeding this requirement are loaded back on to the trick they arrived in and hauled off

2.6.1 Random Inspections

Tracks using the facility will be subject to random inspections performed by an on-site attendant who will be trained and qualified to identify hazardous waste and waste containing PCB's. Drivers will be notified by the scale house attendant to proceed to the special inspections area. The contents will be spread with a front loader or dozer, and inspected for regulated hazardous waste or waste containing PCB's. Acceptance of the load will depend on the findings of the following procedures.

- > The load will be dumped and spread in a designated area
- > The vehicle and driver will be required to wait until the contents have been properly inspected and verified
- > The contents will be spread out, with special attention not to break or mpture any unknown or unmarked containers, by a front loader or dozer
- ➤ Any containers such as 55 gallon druins, that are unmarked or are not easily identifiable will be treated a hazardous waste and will be opened only by trained and qualified personnel
- ➤ If the waste has been inspected and is deemed safe, it will be allowed to be disposed of at the face of the landfill

If the inspection of the waste determines that it contains hazardous waste or waste-containing PCB's, the inspection area will be immediately closed to the public and on-site personnel. The operator will immediately contact AET Environmental they will then be responsible for the proper management, transport, and care of the waste. If known, the hauler of the waste will be notified that they have transported hazardous waste or waste containing PCB's into the facility. A copy of the Random Inspection Form is included in Appendix D.

In addition to the random inspections, the on-site attendant that will operate near the face of the landfill will have the responsibility to momtor the waste of incoming loads and to remove any questionable material from the site as to facility guidelines

2.6.2 Training of Facility Personnel

All facility personnel will be trained to identify suspected hazardous waste or waste containing PCB's using standard labels used to mark said waste. Training will include identification, handling, safety precautions, and documentation requirements. All records of training will be maintained in the facilities operating record.

2 6.3 Written Record of Inspections

Inspections will be recorded on the Random Load Inspection Form (See appendix D) Inspection records will include, but are not limited to inspector's name, date, and time of inspection, hauler information, time and driver information, observations of the inspector, results of inspection, description of any questionable materials, and the reason for rejection of the waste

2,6.4 Notification of the Solid Waste Management Authority

Within 24 hours of the receipt of suspected hazardous or PCB containing waste the operator will notify the Utah Division of Environmental Quality. A record of the notification will be submitted to the Utah Division of Environmental Quality that identifies the date and time of discovery, type of material (if possible), probable hauler, an estimate of the material quantity, and actions proposed for the removal of the material from the facility. A record of the notification will then be entered into the operating record of the facility.

2.7 Controlling Disease Vectors

Cedar Valley Landfill will be accepting only construction and demolition waste and yard waste. In accepting only these wastes it is hoped that any available food source for rodents or wild animals will be an absolute minimum. The presence of wild animals will Imit the choice of animal control. All effort will be made to keep the debris face compacted and graded to keep the area unacceptable for habitation for

rodents and other wild animals Smoke devices and sonar techniques will be employed first if a problem is discovered Poisons will be the absolute last option attempted

Some ammals present in the surrounding area (mule deer and antelope) may not be stopped from encroaching on the facility by the fencing. If these ammals are found in an active area of the site, they will be escorted off of the facility with as little stress as possible. At no time will any animals be purposely injured or killed to remove them. Any migrating birds that locate on the storage pond will be left alone.

2.8 Alternative Waste Handling

The Cedar Valley Landfill is open Monday through Friday from 7 30 am to 5 00 pm There will be enough capacity at the site to hold 15 working days worth of material without having to move any borrow. If a major equipment failure occurs, the facility will replace the damaged equipment with a rental or lease machine within 1 working day. If the Cedar Valley Landfill can not accept incoming waste because of an unforeseen or unknown problem, major customers will be contacted and told of their options. These options include North Point Transfer Station, Trans Jordan Landfill, and the Payson Landfill. All of these options are inside a fifty-mile radius of the site.

2.9 General Training and Safety Planifor Site Operations

The employees and management of the Cedar Valley Landfill will receive mstmction and traiming in landfill and equipment operations. The training of all personnel will be an ongoing process. Basic first aid, site safety, and CPR certification will also be included. Seminars to keep all personnel up to date on any new procedures for landfill operations will be held at least once a year. The traiming of personnel will be noted and entered into the operating record of the facility. (See form in Appendix E)

Basic first aid will be administered to non-life threatening injuries 9-1-1 will be called if any injury appears to be life threatening or beyond basic first aid techniques

2.10 Recycling Programs

Cedar Valley Landfill recogmzes the importance of recycling and makes it part of their plan of operation. Currently loads of concrete and asphalt are gmded to a specific area on the site. Concrete and asphalt is crished to create a road base material. Also, metals that are found within loads are currently set aside and recycled. As a market exists for other materials, recycling will continue to be incorporated in day to day site operations.

2.11 Site Specific Information

Because of the remoteness of the Cedar Valley Landfill, the possibility of illegal after hours dumping on or near the site will be monitored. Security cameras have been set up that momtor the site and record 24 hours a day

3.0 Engineering Reports

3.1 General Construction Plan

Plans are included in Appendix F showing the general construction standards of the site. The plans show the site being constructed so as to use excavated material to berm and cover the waste. As waste is dumped on site it will be moved and shaped to allow for 2.4.1 side slopes and a minimum of a 2-foot cap. The plans also propose a phasing plan.

3.2 Run On and Run Off Control Systems.

Storm water will not be allowed to run off the active area of the landfill. A berm has been constructed around the active portion of the landfill in the magnitude of 8 to 10 feet high. Storm Drainage Calculations are included in Appendix G showing that a 25 year 1 hour storm will generate approximately 50,000 cubic feet of water. This will stay within the 10-feet high berms. As the water flows to the low point on the site it will pond in an area approximately 225 feet by 225 feet, 1-foot deep. As the site is not smoothly graded, much of this water will not reach the low point, rather, the storm water will be sread out over the 69 5 acre site.

The same berm keeping storm water on site prohibits storm water from flowing onto the site. The flow from the surrounding area after a 1 hour storm may be 1-inch deep. This flow will be diverted by the berm around the landfill. Eventually, all storm water will slowly percolate into the soil, or evaporate from the site.

3.3 Facility Life

The facility has a life expectancy of approximately 60 years. The life expectancy is based on the assumptions that the conversion of tons to yards is 2 yards per ton of waste. In 2004, approximately 135,000 tons of waste was accepted at the landfill. The "build-out" volume of the landfill is approximately 30 million cubic yards. There are many assumptions and variables that may alter the calculations for this site. The conversion from tons of material to yards is dependant on the material, the compaction that is achieved of the waste to fill voids, and the amount of on-site dirt that is mixed with the soil. The landfill has been in operation since 2002 and currently encompasses approximately 21 acres. The total acreage of the landfill is over 298 acres, and the operation plan may vary as the amount of waste increases to the site.

3.4 Location Standards

Floodplam – The Cedar Valley Landfill is not located within a floodplam, or near any body of water

Wetlands – The Cedar Valley Landfill is not located near any Wetlands A copy of the wetland documentation from previous permit included in Appendix H

Ground Water Clearance – The site is excavated down approximately 20 feet from the surface Initial ground water depths and subsequent test holes have determined the ground water to vary from 33 feet to over 43 feet from the surface (pending

location on the site) The 20-foot depth allows for keeping a 10-foot clearance above the groundwater A copy of a Groundwater Study is included in Appendix I

3.5 Borrow Sources

The final cover for the site will use native material from the site

3.6 Run-off Collection

No run-off collection, treatment, or disposal is anticipated from the site

4.0 Closure Plan

Closure of Cedar Valley Landfill is not anticipated for many years. As the northern portion of the facility fills with waste, and the face of the landfill moves to the south, it may be possible to begin closure of portions of the landfill. With the normal operating plan that includes sloping the sides at a 2.4.1 slope, and yearly vegetation of the slopes, part of the closure procedures will be worked in. As the engineering detail shows m Appendix F, Sheet 3, the closure includes a 2-foot mimmum cap, vegetation, and 2.4.1 side slopes. The native soil is a clay and silty-clay soil. This native soil will be used in the construction of the 2-foot cap.

The seeding of the slopes will occur m the fall of each year. The seed is put on by hydro-seeding which allows the seed to lay dormant through the winter months and have the benefit of the spring moisture to germinate. The seed type is a native plant that will grow in the on-site soil. It is not anticipated that top-soil will need to be imported to the site.

The facility is planned to be m operation for many years. It is anticipated that the overall tonnage exceeds 15 million tons of waste to be stored and the landfill site. At least 90 days before the final date of operation of the landfill, Cedar Valley Landfill will notify the Department of Environmental Quality and begin the implementation of the closure plan. The construction schedule to complete the closure plan is anticipated to be 180 days.

Currently Cedar Valley Landfill, LC, is anticipated to be the main contact through the life and closure of the facility. As the design life is many years, any change in ownership will be reported as required

5.0 Post Closure Care Plan

The post closure care plan shall require monthly inspections of the site to check the landfill for settlement and erosion. Should settlement occurs that is excessive, or erosion that removes the cap of the landfill, new soil will be hauled and filled into the areas of settlement or erosion and reseeded to prevent further erosion. As necessary, matting, or hydro-seeding may be used. The intent of the post closure plan is to mometor the integrity of the final cap.

Cedar Valley Landfill, LC, will be responsible for Post Closure Care Contact mformation is as follows

Cedar Valley Landfill Attn David Johnston P O Box 1503 Orem, Utah 84059 (801) 437-9502

6.0 Financial Assurance

Cedar Valley Landfill maintains a letter of credit posted with the Division of Environmental Quality This Letter of Credit will be adjusted by pending the amount of landfill that is under operation As area is closed and opened, the bond amount may need to be adjusted

A copy of the letter of credit and bond amount for 21 acres of area is included m Appendix J

Cedar Valley Landfill 21 05 Acre Phase Closure Bond

item	Quantity	Unit	Unit Cost	Total Cost
2-foot Cap				
Soil (located on site)	67921 3	cu yd	\$0 00	\$0.00
Load / Haul	67921 3	cu yd	\$0 95	\$64,525 24
Spread and grade	67921 3	cu yd	\$0 30	\$20,376 39
Landscape				
Native Seed Mix	421 0	PLS lbs	\$4 63	\$1,949 23
Fourwmg saltbush		10	4.50	V1,0102
Wyoming big sagebrush		0 75		
Alkalı sacation		1	1	
Blue grama		25		
Bluebunch wheatgrass		14 25		
Streambank wheatgrass		13		
Smooth brome		15 5		
Intermediate wheatgrass		10		
Sandbarg bluegrass		2		
Sheep fescue		3		
Slender wheatgrass		11		
Western wheatgrass		17		
		100%		
Planting with Gram Drill		hrs		
Post Closure Care				
Inspection *	60 0	ea	\$150 00	\$9,000 00
Fence Repair **	300 0	If	\$9 00	\$2,700 00
Soil Repair ***	3000 0	sf	\$1 25	\$3,750 00
Total Bond Amount				\$102,300 86

<sup>Inspection assumes twice per year for 30 years
Fence repair assumes 20 feet per year</sup>

^{***} Cap repair assumes 100 sq ft per year

APPENDIX A

WHEN RECORDED RETURN TO

Kyle V Leishman
Jones, Waldo, Holbrook & McDonough
170 Soudi Mam Street, Suite 1500
Salt Lake City, UT 84101

MAIL TAX NOTICE TO

GZ Rock, LLC P O Box 47638 Phoenix, AZ 85068 Attn Barry Zemel



ENT 39909 2010 PG 1 of 5 RODNEY D. CAMPBELL UTAH COUNTY RECORDER 2010 May 14 1 00 pm FEE 22 00 BY SS RECORDED FOR JONES WALDO HOLBROOK &2

TRUSTEE'S DEED

BY THIS TRUSTEE'S DEED, made this 13th day of May, 2010, Kyle V Leishman, a member of the Utah State Bar, whose address is 170 South Main Street, Suite 1500, Salt Lake City, Utah 84101, as Trustee (hereinafter Grantor), under that certain Deed of Trust and Assignment of Rents dated December 2, 2005, recorded December 7, 2005, as Entry No 141656 2005, in the records of the County Recorder of Utah County, State of Utah, executed by CEDAR VALLEY LANDFILL, LC, a hmitcd liability company, as to 49% interest, THE WASTE GROUP, LC, a limited liability company, as to a 36 6% interest, DON FLOYD PHILLIPS and SHEILA PHILLIPS, husband and wife as joint tenants, as to a 7% interest, and M TIMOTHY ROSS and MARIE ROSS, husband and wife as joint tenants, as to a 7 4% interest, collectively as Trustor, in favor of STEWART TITLE & TRUST OF PHOENIX, INC, a Delaware corporation, as Trustee, and KENWOOD MORTGAGE & INVESTMENT, INC, an Arizona corporation, as Beneficiary (the "Deed of Trust"), grants and conveys to GZ ROCK, LLC, an Arizona limited liability company (hereinafter "Grantee") all of the title of the Trustee

ENT 39909 2010 PG 2 of 5

under the Deed of Trust and all of the nght, title interest and claim of CEDAR VALLEY

LANDFILL, LC, THE WASTE GROUP, LC, DON FLOYD PHILLIPS, SHEILA PHILLIPS,

M TIMOTHY ROSS, and MARIE ROSS, and of all persons claiming by, through or under
them, including all such nght, title, interest and claim acquired by CEDAR VALLEY

LANDFILL, LC, THE WASTE GROUP, LC, DON FLOYD PHILLIPS, SHEILA PHILLIPS,

M TIMOTHY ROSS, and MARIE ROSS, or their successors in interest subsequent to the
execution of the Deed of Trust in and to the real property and all other property situated at or on
the property described in Exhibit "A" attached hereto, in Utah County, State of Utah, together
with all appurtenances thereto (the "Trust Property")

The Trust Property was also described in the Notice of Default and Election to Sell under Deed of Trust (the "Notice of Default") dated February 18, 2009 and recorded February 18, 2009, as Entry No 16689 2009, in the Records of the Utah County Recorder, State of Utah

Grantor makes this transfer and conveyance pursuant to the powers conferred by the Deed of Trust Grantor, as Trustee, conveys the Trust Property for the benefit of PEACHTREE MORTGAGE, LTD, an Arizona corporation, and RANDOLPH O PERSSON, Trustee of the Randolph O Persson Separate Property Trust dated May 1, 2000, the current Beneficiaries under the Deed of Trust. This grant and conveyance is made after the fulfillment of the conditions specified in said Deed of Trust and authorizing the same as follows.

- Breach and default under the terms of the Deed of Trust as set forth in particular in the Notice of Default referred to herein, which default continued to the time of sale under said Deed of Trust
- Notice of the declaration of said default was duly given to the Trustor and demand for sale pursuant to the terms of said Deed of Trust made, and thereafter, the Notice of Default 929507_1 DOC

ENT 39909 2010 PG 3 of 5

was filed as set forth above, and required copies were sent to the Trustor and to other persons having requested and entitled to the same m accordance with the provisions of the applicable statutes within ten (10) days of such filing for record

- At least three (3) months elapsed after the filing of said Notice of Default, at which time the Grantor executed a Notice of Trustee's Sale stating that, by virtue of authority granted pursuant to said Deed of Trust, Grantor would sell at public auction to the highest bidder, for cash in lawful money of the United States, the afore-described Trust Property Said Notice of Trustee's Sale fixed the time and place of sale as March 24, 2010 at 10 30 a m, at the front entrance of the Fourth Judicial District Court, located at 125 North 100 West, Provo, Utah, at which time and place the Trustee's Sale was postponed by Trustee until April 27, 2010
- The Trustee gave written notice of the time and place of sale, particularly describing the property to be sold, as follows (a) Grantor caused a copy of said Notice of Trustee's Sale to be published once a week for three (3) consecutive weeks in a newspaper having general circulation in Utah County, the county in which the said property is situated, the dates of publication being February 27, 2010, March 6, 2010 and the last date of such publication being March 13, 2010, (b) by publishing the Notice of Sale on the website created by the Utah Press Association in accordance with Utah Code Section 45-1-101, (c) by posting such notice at least twenty days prior to the date of sale at the following locations (i) Utah County Recorder's Office located at 100 East Center Street, #1300, Provo, Utah, and (ii) the property located at 18150 West Allen Ranch Road, Fairfield, Utah, and (in) by mailing, by certified mail, with postage prepaid, at least twenty days prior to the date of sale, a copy of the Notice of Trustee's Sale to the Trustor and other parties entitled to notice thereof

929507_1 DOC

ENT 39909 2010 PG t of 5

- 5 All applicable statutory provisions of the State of Utah and all of the provisions of said Deed of Trust have been complied with as to acts to be performed and notices to be given
- The Grantor, at the time and place of sale fixed in accordance with the foregoing, then and there sold, at public auction, to Grantee, who was the highest bidder therefor, the Trust Property hereinbefore described, in full accordance with the laws of the State of Utah and with the terms of the said Deed of Trust

THIS SALE AND CONVEYANCE IS MADE WITHOUT ANY COVENANT OR
WARRANTY, EXPRESS OR IMPLIED, AS TO TITLE, POSSESSION, OR OTHERWISE
WITH RESPECT TO THE TRUST PROPERTY

DATED this 13th day of May, 2010

GRANTOR/TRUSTEE

Kyle V Leishman, Trustee

STATE OF UTAH)) ss COUNTY OF SALT LAKE)

This instrument was acknowledged and executed before me this 13th day of May, 2010, by Kyle V Leishman who acknowledged to me or proved to me on the basis of satisfactory evidence, to be the persons whose names are subscribed to the withm instrument and acknowledged to me that he executed the same in his audionzed capacity, and that by his signature on the instrument the person or the entity upon behalf of which the person acted, executed the instrument

WITNESS my hand and official seal

My Commission Expires

929507_1 DOC

BARBARA K PARRY
MOTARY PUBLIC STATE OF UTAH
170 S. MAIN STREET #1500
SALT LAKE CITY, UT 84101
My Comm Exp. 11/04/2011

ENT 39909'2010 PG 5 of 5

EXHIBIT "A"

That certain property situated in Utah County, State of Utah, and more particularly described as follows

Commencing at a point m the center line of a county road said point being located North 00°45'22" West along the Section line 1343 60 feet and East 1257 45 feet from the West quarter comer of Section 5, Township 7 South, Range 2 West, Salt Lake Base and Mendian, thence South 89°42'06" East 74 22 feet, thence South 00°16'40" East 1347 56 feet, thence South 89°48'26" East along the quarter section line 1320 48 feet to the center of said Section 5, thence South 00°12'08" West along the quarter section line 2646 06 feet to the quarter common to Section 5 and Section 8, thence South 00°20'54" West along the quarter section line 2707 93 feet to the center of said Section 8, Township 7 South, Range 2 West, dience North 89°32'40" East along the quarter section line 1327 91 feet, thence South 00°20'12" West 1325 56 feet, thence North 89°34'40" East 1328 17 feet, thence South 00°19'31" West along the Section line 1326 33 feet to the Southeast corner of said Section 8, thence South 89°36'40" West along die Section line 2656 85 feet to the South quarter corner of said Section 8, thence South 89°36'21" West along the Section line 837 61 feet to die center line of a county road, thence along the center line of said county road as follows North 00°12'43" East 302 92 feet, thence North 00°39'59" East 1196 28 feet, thence North 00°37'44" East 2427 90 feet, dience North 00°35'40" East 1861 44 feet, thence North 00°52'12" East 405 93 feet, along the arc of a 400 00 foot radius curve to the left 316 45 feet (chord bears North 21°47'38" West 308 26 feet), thence North 44°27'28" West 473 22 feet, thence North 45°02'02" West 137 61 feet, thence North 44°56'18" West 131 01 feet, thence North 42°46'21" West 92 34 feet, along the arc of a 360 00 foot radius curve to the nght 313 28 feet (chord bears North 17°50'34" West 303 49 feet), thence North 07°05'14" East 428 46 feet, thence North 05°05'24" East 201 10 feet, thence North 04°53'03" East 678 65 feet, thence North 06°19'16" East 569 05 feet, along die arc of a 2550 00 foot radius curve to the left 130 05 feet (chord bears North 04°51'36" East 130 04 feet) to the pomt of beginning

929507_1 DOC

APPENDIX B

Cedar	بمالديا	Landfill	Dail	/ Hauling	lοσ
CEUai	valley	Lanuiiii	vany	/ nauling	LOK

Cedar Valley Landfill, LC P O Box 1503 Orem, UT 84059 (801) 437-9502

Date		

Load No	Load Time	Weight	Cubic Yards	Ticket No	Customer Name
				 	
					<u> </u>
				<u></u>	
				}	
+					
					!
+					
					
——					
					
——]			
					<u> </u>
 -					
\longrightarrow					
——					
	*******	******			
					
					<u> </u>
		 			
					
 +					
					
					
i					

APPENDIX C

Landfill Inspection End of Day Check-Out Procedure

ay of Week Won Tues Wed Thurs Fit Sal Date		_ i ime _	
Weather Conditions			·
	en an earlie de la companse de Carres		
<u>em</u>	Acceptable	<u> </u>	Jnacceptable
SW Disposal Cell – Required Daily Cover (Note if ADC is used)			
ead Animal Pit - Required Daily Cover			
ass IV Disposal Cell – Cover Soil Provided as Needed			
een Waste Storage Pile – Non-Green Waste Removed			
etals Recycling Area – No Solid Waste Present			
ter Control – Blown litter picked up - as needed			
ter Control Fence – Maintained and cleaned			
ctive Disposal Area – Adequate cover material			
plosive Gas Detectors – Functioning			
trance Gate Locked/Penmeter Secured – Prevent Unauthorized Entry			
mments scribe details of any Unacceptable conditions and describe needed co ments or problem which could affect the site's integrity (Use addition			any related
		···.	
) 		·	
}			
nature of Person Completing Form			

APPENDIX D

Cedar Valley Landfill Random Record Inspection Form


	Time Received
Driver's Name	
Vehicle Identification	
Source of Waste Generator	
Observations Made During Inspection	
Non-Conforming Items Included in Load (if any)	If Rejected, Reason for Rejection
Notes	


APPENDIX E


Annual Training and /or Procedures Completed

Person	Traiming Course	Date Completed
, , , , , , , , , , , , , , , , , , , ,		
		<u></u>

APPENDIX F







APPENDIX G

CEDAR VALLEY LANDFILL

Area	Total (AC)	1mpervio (AC)	us Perv (AC)	vious
Lar	ndfill 6	9 5	0	69 50
Runoff Coef	ficient	0 !	9	02
Weighted A	rea 13	90 0 00	0	13 90


Storm Depth 101 In (25-year 1-hour)

Storm Volume 50962 (CF)

No Allowable Discharge 0 cfs

Duration (min)	Intensity (in/hr)	Runoff (cfs)	Total Runoff (CF)	Allow Discharge (CF)	Storage Reg'd (CF)
5	3 85	53 52	16054 50	0 00	16054 50
10	2 93	40 73	24436 20	0 00	24436 20
15	2 42	33 64	30274 20	0 00	30274 20
30	1 63	22 66	40782 60	0 00	40782 60
60	1 01	14 04	50540 40	0 00	50540 40

Total Pond Voi Required - 1 50540 CF



APPENDIX H



••••••••

amlandresources@cs com (801) 451-7695, (208) 841-5766

April 13, 2000

Mr Mel Radmall Cedar Valley Landfill P O. Box 952 American Fork, Utah 84003

Re: Proposed Cedar Valley Landfill Wetland Delineation

Dear Mr Radmall

I am writing this letter to document our field visit to document the existence of any special aquatic sites including jurisdiction wetlands within the boundaries of the above referenced project

There are no special aquatic sites including jurisdictional wetlands found within 2000 feet or within the property boundaries. The entire site was a typical Great Basin high desert scrub-shrub vegetative community characterized by sagebrush (Artemisia tridentata), rabbitbrush (Chrysothamnus nauseosus), greasewood (Sarcobatus vermiculatus), and vanous grasses including tall wheatgrass (Elymus elongatum) and cheatgrass (Bromus tectorum).

If you have any questions, please call me at (208) 841-5766

Sincerely,

Brian Young Sr. Wetland Scientist

c File




Figure 1.0: Cedar Valley Landfill

Cedar Valley Site Map

APPENDIX I

UTAH STATE ENGINEER Technical Publication No. 16



GROUND-WATER CONDITIONS IN CEDAR VALLEY, UTAH COUNTY, UTAH

by R D. Feltis

Geologist, U S Geological Survey

Prepared by the U.S. Geological Survey
in cooperation with
The Utah State Engineer
1967

CONTENTS

	Page
Abstract	5
Introduction	5
Purpose and scope	5
Location of the area	6
Acknowledgments	6
Well-numbering system used m Utah	6
Geology	6
Consolidated rocks of Paleozoic age	6
Sedimentary and igneous rocks of Tertiary age	9
Sedimentary rocks	9
Igneous rocks	9
Unconsolidated rocks of Quaternary age	9
Structure	10
Water resources	11
Volume of precipitation	11
Surface water	11
Ground water	11
Recharge	11
Occurrence	12
Movement of ground water	12
Water-level fluctuations	13
Water-bearing characteristics of the aquifers	15
Discharge	15
Test-well drilling	19
Chemical quality of water	20
Summary and conclusions	22
Selected references	23
Publications of the Utah State Engineer's Office	32

ILLUSTRATIONS

Fig	rure	Page
1	Index map	7
2	Diagram showing well-numbering system	8
3	Geologic map	In pocket
4	Map showing normal annual precipitation for the period 1 approximate recharge area, water-table contours of Marc the line of reference used in calculating subsurface outflow locations of wells	h 1966,
5	Hydrographs of selected wells, discharge of Fairfield Spring cumulative departure from the 1943-65 average annual pretion at Fairfield	
6	Map showing changes of water levels m the artesian at March-April 1964 to March-April 1966 in part of Cedar Valley	quifer, 16
7	Map showing the chemical composition and the dissolved concentration of water	solids n pocket
8	Diagram showing classification of water for irrigation	21

TABLES

Tab	le Pa	ıge
1	Annual precipitation over the recharge area and estimated water available for recharge to the ground-water reservoir in Cedar Valley	
2	Records of selected wells m Cedar Valley	24
3	Records of selected springs in Cedar Valley	26
4	Chemical analyses of water from wells and springs m Cedar Valley	27
5	Water levels in observation wells in Cedar Valley	28
6	Selected drillers' logs of wells in Cedar Valley	30
7	Logs of test wells in Cedar Valley	31

GROUND-WATER CONDITIONS IN CEDAR VALLEY, UTAH COUNTY, UTAH

by R. D Feltis

Geologist, U S Geological Survey

ABSTRACT

Cedar Valley is m north-central Utah about 20 miles west of Provo m Utah County The valley is mostly a topographically closed basm, developed m a structural trough caused principally by faulting, and is bordered by mountains largely composed of Paleozoic sedimentary rock. The valley is filled with semiconsolidated to unconsolidated alluvial, colluvial, lacustrine, and eolian deposits of Tertiary and Quaternary age.

Ground water occurs under both water-table and artesian conditions, but most of the wells are developed in the artesian aquifer. The source of most recharge to the ground-water reservoir is in the Oquirih Mountains in the northwest corner of the valley. After seeping into the ground, water moves directly from the bedrock in the valley fill, thence east and southeast across the valley. The estimated subsurface outflow along the east edge of the valley ranges from about 10,000 to 20,000 acre-feet per year.

Water levels and spring discharges generally fluctuate in response to variations of precipitation, but they have declined markedly in response to pumping at nearby irrigation wells. Durmg 1965, about 1,900 acre-feet of water was pumped from eight urigation wells in the valley.

The coefficient of transmissibility of the artesian aquifer in the north-central part of the valley, as determined by pumping and recovery tests at wells, ranges from about 5,000 to 26,000 gallons per day per foot. The specific capacities of irrigation wells in the center of the basin range from about 1 to 7 gallons per minute per foot of drawdown, but two wells at the west edge of the basin had specific capacities of 30 and 37 gallons per minute per foot of drawdown.

Most of the ground water in the north half and southwest corner of the valley is of good chemical quality, containing less than 500 parts per million of dissolved solids. In the southeast part of the valley, the water is of poor quality, containing more than 1,000 parts per million of dissolved solids.

INTRODUCTION

Purpose and Scope

This study of the ground-water conditions in Cedar Valley, Utah, was made by the US Geological Survey m cooperation with the Utah State Engineer during the period July 1965-July 1966. The purposes of the study were to estimate the recharge to and the yield of the ground-water reservoir and to determine the direction of ground-water movement through Cedar Valley.

Water levels have been measured in observation wells m Cedar Valley from time to time since 1943. During the present investigation, water-level measurements were made in 38 observation wells, and 5 test wells were drilled to provide additional observation wells and

also to provide information that would be helpful in understanding the subsurface geology of the valley. Geophysical logs were run in several wells and test wells to aid m interpreting the subsurface geology and to show the occurrence of ground-water aquifers. Tables 2-7 contain the basic data collected for the investigation and include records of selected wells and springs, chemical analyses of water, water-level measurements, drillers' logs of wells, and logs of test wells. The locations of wells are shown in figure 4 and of springs in figure 7

Location of the area

Cedar Valley is in the northwest comer of Utah County, Utah, about 20 miles west of Provo, and lies between 39°58′ and 40°29′ north latitude and between 111°55′ and 112°13′ west longitude (figure 1) The drainage basin for the valley includes about 300 square miles, but the valley proper includes only about 140 square miles. The valley has a maximum north-south length of about 25 miles and a maximum east-west width of about 8 miles. The valley is a topographically closed basin except at the extreme north end where the surface drainage is into northern Utah Valley. The valley is almost completely surrounded by mountains or low hills, and altitudes range from about 4,840 feet on the valley floor to 10,626 feet in the Oquirrh Mountains along the northwest edge of the valley. Mountains on the east side and south end of the valley reach altitudes of 7,647 and 7,828 feet.

Acknowledgments

Many thanks are owed to the residents and landowners of Cedar Valley who furnished or permitted the collection of hydrologic data and water samples from wells and springs and who gave permission to construct test holes for the collection of geologic and hydrologic data

Well-numbering system used in Utah

The system of numbering wells in Utah is based on the cadastral land-survey system of the Federal Government. The well number, in addition to designating the well, locates its position to the nearest 10-acre tract in the land net. By this system the State is divided into four quadrants by the Salt Lake base and ineridian, and these quadrants are designated by the capital letters A, B, C, and D. A is the northeast quadrant, B is the northwest, C is the southwest, and D is the southeast. Numbers designating the township and range follow the quadrant letter, and all three are enclosed in parentheses. The number after the parentheses designates the section, and the lowercase letters give the location of the well within the section. The first letter indicates the quarter section, which is generally a tract of 160 acres, the second letter indicates the 40-acre tract, and the third letter indicates the 10-acre tract. The number following the letters indicates the serial number of the well within the 10-acre tract. Thus, well (C-6-2)13caa-1 in Utah County is in the NE1/4NE1/4SW1/4 sec 13, T 6 S, R 2 W, and is the first well constructed or visited in that tract. Figure 2 shows the method of numbering wells as described above. In this report springs and sampling sites are also located by using this system, but the serial number within a 10-acre-tract is omitted.

GEOLOGY

Consolidated rocks of Paleozoic age

The mountains surrounding Cedar Valley contain mostly rocks of Paleozoic age that include limestone, dolomite, quartzite, conglomerate, sandstone, and shale (figure 3) Each rock type is generally present in each mountain range, but limestone and dolomite predomi-




Figure 1 — Index map of Utah showing location of the Cedar Valley drainage basm

Sections within a township

Tracts within a section

Figure 2 — Well-numbering system used m Utah

nate The age of the formations ranges from Devonian to Permian in the Lake Moiuitams, from Cambrian to Permian in the East Tintic Mountains, and from Mississippian to Pernuan in the Oquirrh and Traverse Mountains

Sedimentary and igneous rocks of Tertiary age

Sedimentary rocks—Scattered exposures of limestone and fresh and argillized tuff in the low hills southwest of the Lake Mountains is part of an unnamed sequence believed to be of early Tertiary—probably late or middle or early late Eocene—age (Morris and Lovering, 1961, p 126) The limestone is fine to medium grained The argillized tuff, where it has been mined, consists of halloysite and montmorillonite

The Salt Lake Formation of Pliocene age probably occurs along the mountam fronts and in the subsurface of Cedar Valley, although it has not been mapped within the drainage basm of Cedar Valley by those who have described the geology of the surrounding mountains. The formation has been described by Morris and Lovering (1961, p. 126-127) in Rush and Tm-tic Valleys to the west and southwest of Cedar Valley as "* * marly limestone, bentonitic tuff, sandy silt, and gravel * * * " In the Jordan Narrows, northeast of Cedar Valley, it is described by Hunt and others (1953, p. 13), as " * * * alternating dark-gray silt and white or light-gray, firm, ledge-forming beds that probably are cemented, reworked tuffs. The individual beds range from 2 to 20 feet in thickness, included with them are a few, very thin, clay partings * * * These light-colored beds are overlain inconformably by a series of buff beds with a basal conglomerate * * * The basal conglomerate is about 15 feet thick * * * Above this is 50 feet of moderately consolidated buff sand and silt, which apparently is reworked crystal tuff partly cemented by hime carbonate"

The upper part of the Salt Lake Formation is not easily distinguished from younger alluvial deposits. Some of the partly indurated alluvium around the edges of the valley and in canyons of the mountains, that is mapped as unconsolidated Quateruary deposits in figure 3, may be Salt Lake Formation.

Igneous rocks—Most of the igneous rocks around Cedar Valley crop out m the Traverse Mountains, northeast of the valley, and the East Tintic Mountains, m the southwest comer of the valley. Gilluly (1932, p 41) described the extrusive igneous rocks in the Traverse Moimtains as "* * * chiefly latite and quartz latite, with some minor flows of basalt, rhyolite obsidian, and nephebte basalt. Among the extrusive rocks, flows, although numerous, are quantitatively subordinate to breccias". The mtrusive igneous rocks of the Traverse Moimtains are several small rhyohte plugs.

Morris and Lovering (1961, p 124) described the igneous rocks of the East Tmtic Mointams as "* * * deeply eroded remnants of a large composite volcano * * *." These igneous rocks include intrusive bidies and thick lava flows as well as the bedded tuffs, breccias, agglomerates, and volcanic gravels that can be considered to be, m part at least, sedimentary deposits" The extrusive rocks are latite tuffs, flows, agglomerates, volcanic gravels, quartz latite, and basalt flows. The mtrusive rocks consist of quartz monzonite, monzonite, monzonite, and diabase

Unconsolidated rocks of Quaternary age

The Quaternary deposits of the basm fill of Cedar Valley consist mostly of alluvial fans, lacustrme clay, silt, sand, and gravel, and eolian sand and silt

The alluvial fans, composed largely of silt, sand, and gravel, extend from withm the canyons of the mountains toward the center of the basin, where they Interfinger with lake

and eolian deposits. The fans range in age from early Pleistocene to Recent and m some areas may be lithologically similar to and indistinguishable from the upper part of the Salt Lake Formation of late Pliocene age. The individual fans coalesce along the inountam front to form a continuous undulating surface around the edge of the valley. The fans are generally very coarse grained and permeable near the mountains but become finer grained and less permeable toward the center of the valley. A large alluvial fan in the north end of Cedar Valley extends from the mouth of West Canyon southward to the latitude of Cedar Fort It has overlapped the bedrock in the northeast coruer of the valley, diverting the West Canyon drainage into Utah Valley

Lakes have probably occupied Cedar Valley during the several periods of glaciation of the Pleistocene Epoch. The resultant lacustrine deposits are mostly impermeable, well-sorted, tabular beds of lake-bottom silt and clay, with some permeable lenticular beds of shoreline sand and gravel deposits. Few large deposits of sand and gravel are present, because no large perennial streams earned coarse debris into the lakes and because the sheltered nature of the valley prevented strong lake currents which could have deposited material on the lakeshore. Lake Bonneville was the last of the Pleistocene lakes that occupied the valley, and its shoreline can be seen etched in the alluvium around the basin.

Active sand dunes as much as 15 feet thick are present about 2 miles south of Fairfield Goode (in Morris and Lovering, 1961, p. 137) reports that the dimes probably were formed during or immediately after the recession of Lake Bonneville and are now being reattacked by the wind. Blowouts in low stabilized dunes and in imderlying lake beds are common across the floor of the valley and result in scattered, shifting masses of silt and sand.

Other Quaternary deposits m the valley include colluvium, talus, and landslide debris which occur along the edges of the valley and m the canyons of the mountains. Glacial moraines are at the heads of West Canyon and the Left Fork of West Canyon m the Oquirrh Mountains.

Structure

Cedar Valley is a basin similar in structure to the many basins of the Basin and Range physiographic province in Utah and Nevada. It is principally a graben produced by a system of faults that has uplifted and tilted the surrounding mountain blocks relative to the valley floor. A gravity map of Cedar Valley (Cook and Berg, 1961, pl. 13) shows the north-central part of the basin (T 6 S, R 2 W) to be deepest. The fault system that produced the basins of western Utah is still active, therefore, Cedar Valley may shill be m the process of development.

The rocks in the mountains surrounding the basin generally have been folded into broad, north to northwest trending folds (figure 3). These broad folds and their subsidiary faults and folds were probably made during Cretaceous and early Tertiary time, prior to development of the Cedar Valley graben. The structural elements of the bedrock are of great importance to the hydrology of the valley because of their partial control of movement of ground water into and from Cedar Valley.

WATER RESOURCES

Volume of precipitation

The range in the normal annual precipitation in Cedar Valley and surrounding mountains is generally from 12 to 40 inches. The isohyetal lines of figure 4 show that the greatest precipitation is on the Oquir h Mountains, from which most of the surface and ground water in Cedar Valley is derived.

Not all precipitation in the Cedar Valley drainage basin is available to recharge the ground-water reservoir. It is assumed that only aleas above the 12-inch isohyetal line on the west side of the basin receive precipitation that is effective in recharging the reservoir. Precipitation directly on the valley floor is used by vegetation or evaporated back to the atmosphere, and water from precipitation on the Lake Mountains moves eastward away from Cedar Valley (see p. 12).

The normal annual precipitation that falls above the 12-inch isohyetal line in the Cedar Valley drainage basin is about 150,000 acre-feet (table 1). Of this amount about 80,000 acre-feet falls above the 16-inch isohyetal line in the Oquirrh Mointains.

Surface water

The only perennial stream in Cedar Valley is m West Canyon in the Oquii rh Mountains, and all the water is diverted in sec. 7, T. 5 S, R. 2 W. for irrigation near Cedar Fort. The discharge from West Canyon from July 1965 through June 1966, as determined at a gaging station in sec. 7, T. 5 S, R. 2 W, was 2,100 acre-feet of water. Although the stream channel crosses the north end of Cedar Valley and drains into northern. Utah Valley, surface water leaves the valley only m flash floods or as runoff from local snowmelt.

Ground water

Recharge.—The principal recharge area of the ground-water reservoir m Cedar Valley is m the Oquirrh Mountains along the northwest edge of the valley, where snowmelt percolates directly into fractures and solution channels of the rock. The ahgmment of springs (C-4-3) 20dba, (C-1-3) 26cbd, (C-4-3) 26dda, and (C-4-3) 27bab, and springs (C-5-3) 36cba, (C-6-2) 6cad, and (C-6-3) 1aad, along the strike of the bedrock, shows that some strata transmit water more readily than others (See figures 3 and 7) Some precipitation also enters the alluvial and glacial deposits m the mountain valleys. Most of the water in the basm fill throughout Cedar Valley entered the ground in the Oqmrrh Mountains (figure 4)

Table 1 — Annual precipitation over the recharge area and estimated water available for recharge to the ground-water reservoir in Cedar Valley

Interval of annual precipitation (inches)	Area (acres)	Average annual precipitation (feet)	Quantity of water from precipitation (acre-feet, rounded)	Estimated percentage of precipitation as recharge	Estimated water available for recharge to ground-water reservoir (acre-feet, rounded)
12-16	60,500	1 17	70,800	5	3,500
16- 20	16,400	1 50	24,600	15	3,700
20.25	7,600	1 88	14,300	20	2,900
25- 30	6,000	2 29	13,700	27	3,700
30-40	6,500	2 92	19,000	35	6,600
More than 40	2,700	3 33	9,000	40	3,600
	Totals (rounded)		151,000		24,000

Other areas of recharge are the East Tintic Mountains, Topliff Hill, Thorpe Hills, and alluvial fans along the west side and north end of the valley above the 12-inch isohyetal line. At the north end of the valley, discharge from West Canyon is a source of recharge beginning near the moulli of the canyon, extending south along the West Canyon ditch, and ending in the irrigated land east of Cedar Fort

The estimated water available for recharge to the ground-water reservoir from precipitation is about 24,000 acre-feet (table 1). The percentages used in the calculations are based on the method used by Eakin and Maxey (1951, p. 79-81) in which an increased percentage of water from precipitation becomes available for recharge as the total precipitation increases with an increase in altitude of a mountain mass (isohyetal intervals of figure 4). Of the 24,000 acre-feet of water available for recharge, about 20,500 acre-feet originates above the 16-inch isohyetal line in the Oqinrih Mountains.

The amount of recharge to the ground-water reservoir from West Canyon is probably less than 5 percent of the total recharge. The valley fill m the area crossed by the stream, the West Canyon ditch, and the irrigated fields consists of perineable alluvial-fan deposits, and it is estimated that 50 percent of the water is recharged to the ground-water reservoir. The recharge from streamflow in West Canyon for 1965-66 (See p. 11) amounts to about 1,000 acre-feet.

Occurrence —Ground water in the unconsolidated deposits in Cedar Valley occurs under both water-table (unconfined) and artesian (confined) conditions. Water-table conditions predominate in the southern part of the valley, where stock wells have been hand dug to depths of more than 200 feet. In the central part of the basin, south and east of Fairfield, water in the shallow beds in unconfined, and these beds extend from the land surface to depths of about 100 feet. Water-table conditions occur around the edges of the basin fill as indicated by the water levels in wells (C-5-2)31dcd-1, (C-6-1)18dca-1, and (C-6-1)31dab-1

Artesian aquifers are present in the valley fill opposite the drainages of Pole and Manning Canyons, and possibly in the alluvial fan of West Canyon. Permeable and impermeable beds in the lower parts of the alluvial fans in Pole and Manning Canyons form the aquifers and confining beds of the artesian system on the west side of the valley in sees. 17, 29, 32, and 33, T. 6 S., R. 2 W. Toward the center of the valley, as in sees. 13, 14, 15, and 26, T. 6 S., R. 2 W., fine-grained lake-bottom deposits overlap the alluvial deposits and act as the confining beds for the artesian system. The artesian aquifers between Cedar Fort and Fairfield, extending eastward across the basin, have had the greatest development as sources of ground water in Cedar Valley. In the town of Fairfield, wells flow from the artesian aquifer at depths ranging from 100 to 824 feet. Although the artesian system may extend across the central part of the basin, artesian pressures are not sufficient to cause wells in the center or topographically low parts of the basin to flow. The low artesian pressure may be due to the discharge of water from the basin fill into the bedrock along the east edge of the valley. Artesian conditions may occur at depths exceeding 200 feet in the southern part of the valley, but no substantiating data are available.

Movement of ground water —The ground water in Cedar Valley moves generally from the west to the east side of the valley Figure 4 shows contour lines connecting points of equal altitude on the water surface in March 1966 Because ground water moves from points of higher altitude to points of lower altitude, the contours indicate the direction of movement and the areas of ground-water recharge and discharge

Altitudes of the water surface are highest near Fairfield and Cedar Fort, where water from the Oquirrh Mountains enters the basin fill Nearly all the ground water in the central and southern parts of the valley has infiltrated along the Pole Canyon synclime (figure 3), and inoved through fractures and solution channels in the rock, down the syncline, and into the valley fill

The lowest altitudes of the water surface arc along the east edge and southeast corner of the valley Along the base of the Lake Mountains from about sec 24, T 5 S, R 2 W, southward to sec 8, T 7 S, R 1 W, the beds of the west limb of the Lake Mountains syncline (figure 3) dip toward the east and water leaves Cedar Valley along the bedding planes and through fractures and solution channels in the rocks. The water may discharge m springs and seeps on the east side of the Lake Mountains, in the bottom of Utah Lake, or to the alluvium northeast of the Lake Mountains on the west side of northern Utah Valley

Ground water also leaves Cedai Valley through bedrock in the low pass between the Lake and Traverse Mountains. This movement is indicated by the difference of water levels m test wells (C-5-1)20ddc-1 and (C-5-2)24aab-1, which are completed m bedrock at the north end of the Lake Mountains

The ground-water trough extending southwest of sec 25, T $5\,S$, R $2\,W$ (figure 4), is probably caused by ground water draining from the basin m the northeast corner of the valley and by pumping irrigation wells m sees 13, 14, and 15, T $6\,S$, R $2\,W$

Ground water may also leave the southeast corner of Cedar Valley through the bedrock of the eastern East Tmtic Mountains in Tps $\,8\,$ and $\,9\,$ S , R $\,2\,$ W $\,$ This water may move into the alluvium on the west side of Goshen Valley

Water in bedrock m the western East Tintic Mountains in Tps 8 and 9 S , R 3 W , probably moves to the west and east, controlled by the structure of the North Tmtic anticline (figure 3) Water from the west limb of the anticline probably moves mto Rush Valley, whereas water from the east limb moves into the valley fill in the southern end of Cedar Valley

Water-level fluctuations —Water levels in observation wells in Cedar Valley rise and fall in response to recharge to and discharge from the ground-water reservoir

The hydrograph of well (C-6-2)29cac-1 (figure 5) shows three general water-level conditions a relatively steady trend of high water levels from 1943 through 1952, a generally declining trend from 1953 to 1964, and rising water levels during 1965 and the spring of 1966. These trends generally follow the curve of the cumulative departure from the 1943-65 average annual precipitation at Fairfield (figure 5). Lines trending upward on the cumulative-departure curve indicate periods of above-average precipitation, when recharge to the ground-water reservoir is comparatively great, and limes trending downward indicate periods of below-average precipitation, when recharge is comparatively small

Precipitation was above average for most of the period 1944 through 1952, but water levels m well (C-6-2)29cac-1 did not rise continuously because the discharge of nearby Fairfield Sprmg, (C-6-2)29ccc, had a damping effect

From 1952 to 1962, however, the nearly continuous below-average precipitation resulted in a nearly continuous decline in water levels. This decline was accentuated in 1963-64 by the pumping of irrigation wells in sees 17 and 32, T 6 S, R 2 W

Water levels rose m 1965 and early m 1966 because of a combination of above-average precipitation from 1963 to 1965 and cessation of pumping at the irrigation wells m sees 17 and 32, T 6 S, R. 2 W

The hydrographs of wells (C-6-2)14cba-1 and (C-6-2)16baa-1 (figure 5) show the dechne of water levels from 1954 to 1966 m an area 3 miles northeast of Fairfield where irrigation wells have been pumped annually duing the entire period of the hydrograph. Although water levels rose m 1965, they dechned m the pumping season of 1966 to record lows at each observation well




Figure 5. — Hydrographs of selected wells, discharge of Fairfield Spring, and cumulative departure from the 1943-65 average annual precipitation at Fairfield

The effects of pumping an irrigation well, (C-6-2)26cbb-1, on two wells of different depths are indicated by water-level measurements in table 5. The water level in well (C-6-2)27ccc-1 declined 11.1 feet from April 7 to June 9, 1966 while the irrigation well was being pumped. The wells are about 1 mile apart, and both are 505 feet deep. During the same period, however, water levels in well (C-6-2)27ccc-2, which is 100 feet deep, did not decline but rose 0.2 foot.

Figure 6 shows the change of water levels in north-central Cedar Valley from March-April 1964 to March-April 1966. The rise of water levels in the western part of the valley reflects above-average precipitation in the recharge area from 1963 to 1965 and a cessation of pumping at the irrigation wells in secs. 17 and 32, T. 6 S., R. 2 W., in 1965. The decline of water levels method the central part of the basin is the result of continued withdrawal of water for irrigation method that area. (See well. (C-6-2)14aba-1 metable 5.)

Water-bearing characteristics of the aquifers —Information on the water-bearing characteristics of the aquifers in Cedar Valley is based on data obtained from a pumping test of well (C-6-2)14cac-1 and recovery tests of wells (C-6-2)13caa-1 and (C-6-2)26cbb-1 and calculations of specific capacities of wells in various sections of T 6~S, R 2~W

Data from the pumping test were used to determine the coefficients of transmissibility and storage² of the aqmfer Well (C-6-2)14cac-1 was pumped at an average rate of 600 gpm (gallons per minute) from March 28 to April 1, 1966, at the beginning of the irrigation season and prior to the pumping of other irrigation wells Water-level fluctuations were observed in wells (C-6-2)14aba-1, (C-6-2)14cba-1, and (C-6-2)14dba-1 The coefficients of transmissibility and storage were computed using the nonequilibrium formula (Theis, 1935) The respective determined values for T at wells (C-6-2)14aba-1, (C-6-2)14cba-1, and (C-6-2)14dba-1 were 26,000, 12,000, and 8,000 gpd per ft (gallons per day per foot) and for S were 0 002, 0 001, and 0 0005

At the end of the 1965 pumping season, recovery tests were made at wells (C-6-2)26cbb-1 and (C-6-2)13caa-1 on Septemtier 15 and 17, respectively. The coefficients of transmissibility were computed using the Theis recovery formula (Theis, 1935). The coefficient of transmissibility was 9,000 gpd pet ft at well (C-6-2)26cbb-1 and 5,000 gpd per ft at well (C-6-2)13caa-1

The specific capacities of irrigation wells in Cedar Valley range from 0.7 to 37 gpm per foot of drawdown (table 2). This wide range is due mostly to the variation in the composition of the aquifers. Wells (C-6-2)17dcc-1 and (C-6-2)17dcc-2, which have respective specific capacities of 30 and 37 gpm per foot of drawdown, are developed in coarse-grained aquifers of the alluvial fan of Pole Canyon. Wells in the central part of the basin, with specific capacities of 0.7 to 6.8 gpm per foot of drawdown, are developed in fine-grained lacustrine, eoban, and alluvial deposits. Some of the lower specific capacities can be attributed to caving around the well, and several wells have been abandoned because of caving

Data from the pumping test, recovery tests, and specific capacities of wells indicate an increase m the coefficient of transmissibility from the center of the basin toward the north end and west side of the basin

Discharge.—Water is discharged from the ground-water reservoir in Cedar Valley by springs, by wells, by evapotranspirauon, and by subsurface outflow from the basin

'The coefficient of transmissibility, T, is the late of flow of water, in gallons per day, at the prevailing water temperature, through a vertical strip of the aquifer 1-foot wide extending the full saturated height of the aquifer under a hydraulic gradient of 100 percent

2The coefficient of storige, S, of in aquifei is the volume of water released of taken into storage per umt surface area of the aquifei per unit change in the component of head normal to that surface




Figure 6 — Changes of water levels in the artesian oquifer, March-April 1964 to March-April 1966 in part of Cedar Valley

Fairfield Spring, (C-6-2)29ccc, at the west edge of Fairfield, is the largest spring in Cedar Valley. It discharges water that is derived from precipitation on the Oqunrh Mountains. The permeable coarse-grained aquifers at the head of the alluvial fans of Manning and Pole Canyons readily transmit the water, but increasingly finer grained deposits toward the toe of the fan and mithe lake beds in the center of the basin retaid the flow, forcing some of the water to the surface. This discharges at the spring, which is at the break in slope of the alluvial fan with the valley floor.

Fairfield Spring generally discharges between 3 and 5 cfs (cubic feet per second), and the maximum discharge on record is 5 96 cfs (figure 5). A comparison of the spring hydrograph with the curve showing the cumulative departure from average annual precipitation at Fairfield (figure 5) shows the time lag between precipitation on the Oquirrh Mountams and discharge from the spring. For example, the above-average precipitation of 1957 resulted m a record high discharge of Fairfield Spring m late 1958. The sharp decrease in yield of the spring during the irrigation seasons of 1962-64 was due to pumping of irrigation wells m sec. 17, T. 6 S., R. 2 W., which tap the same or intercoinected agmfers

The water from Fairfield Spring is used mostly for irrigation near Fairfield m the summer and for irrigation of native pasture, from Fairfield southeast to the Sinks, during the winter. The upper part of the valley fill between Fairfield and the Sinks consists of fine grained lake beds with low permeability. Much of the water applied for irrigation, therefore, is discharged by evapotranspiration. Assuming an average discharge of 4 cfs from the spring, it is estimated that 70 percent of the water, or about 28 cfs (2,000 acre-feet per year), is consumed by evapotranspiration.

The total annual discharge of three springs west of Cedar Foit, based upon measurements made in October 1965, was about 800 acre-feet. About 50 percent of this water is returned to the ground-water reservoir, the remainder is consumed by evapotranspiration.

Numerous springs discharge m the mointams, but their yields are generally less than 15 gpm. They are used for stock watering

During 1965, about 10 acre-feet of water was withdrawn from small-diameter wells for domestic and stock use, and about 1,900 acre-feet of water was pumped at 8 large-diameter irrigation wells in sees 13 (1 well), 14 (3 wells), 15 (3 wells), and 26 (1 well), T 6 S, R 2 W The yield of the wells ranged from 130 to 1,115 gpm All the pumps are driven by electric motor, and the annual well discharge was computed from the amount of water discharged per 1,000 kilowatt hours of electricity used in 1965

During 1964, about 3,800 acre-feet of water was pumped at 11 irrigation wells. These meluded the eight large-diameter negation wells mentioned above and three additional wells misses 17 (2 wells) and 32 (1 well), T 6 S, R 2 W. The two wells in sec 17 reportedly yielded 2,000 and 3,600 gpm upon their completion might 1961-62. The three wells misses 17 and 32 produced 2,700 acre-feet of water might 1964 compared to 1,100 acre-feet from the 8 wells in secs 13, 14, 15, and 26. The wells in secs 17 and 32 tap more permeable, coarse-grained aquifers might allowed by wells misses 13, 14, 15, and 26 misses 14, 15, and 26 misses 15, 14, 15, an

Evapott anspu ation m sees 13, 14, 15, 26, and 32, T 6 S, R 2 W, probably consumes 90 percent of the water pumped for irrigation because the low permeability of the surface deposits prevents rapid downward percolation. Thus m 1965, when the pumpage in these sections was about 1,900 acre-feet, approximately 1,700 acre-feet was consumed by evapotranspiration. The rate of evapotranspulation is probably lower in sec 17, T 6 S, R 2 W., because the surface deposits consist of alluvial-fan sediments which permit a greater rate of infiltration.

Two methods were used to estimate the subsurface outflow of water along the east edge of the basin. The fust method was based on transmissibility data obtained from aquifer tests and the hydraulic gradient of March 1966, determined from the water-table contour map (figure 4). The second method was a water budget for the ground-water reservoir.

In the fust method, the parts of the ground-water reservoir to which the calculations apply are shown by the line of reference m figure 4. The transmissibility and hydraulic gradient along each section of the line were assumed to be uniform. The subsurface outflow beneath each segment of the line of reference was calculated using the formula

$$Q = 0.00112 T I W$$

where \mathbf{Q} is the outflow, in acte-feet per year, 0 00112 is a factor that converts gallons per day to acte-feet per year, T is the coefficient of transmissibility, in gallons per day per foot, I is the hydraulic gradient, in feet per mile, and W is the length of the segment, m miles

No aquifer test data are available for the southern part of Cedar Valley The valley fill is relatively fine grained, however, and the coefficient of transmissibility along segment 1 is estimated to be about 7,000 gpd per ft. The hydraulic gradient is about 8 feet per imle

Along segment 2, the hydrauhc gradient is about 31 feet per mile. The coefficient of transmissibility based on data obtained during the recovery test at well. (C-6-2)26cbb-1 is 9,000 gpd per ft.

Segment 3 is across an area where the depression of ground-water contours has been accentuated by pumping imagation wells in sees 13, 14, and 15, T 6 S, R 2 W. The transmissibility along this segment is based on the change in hydraulic gradient across the segment for an annual rate of discharge from wells of 1,500 acre-feet per year. The formula used to calculate the transmissibility of the segment is

$$T = \frac{Q}{0.00112 (I-I')W}$$

where T is the transmissibility, in gallons per day per foot, Q is the discharge of wells, 1,500 acre-feet per year, 0 00112 is a factor converting gallons per day to acre-feet per year, I is the average hydraulic gradient as determined from figure 4, 50 feet per mile, I' is the estimated average hydraulic gradient before pumping began, 33 feet per mile, and W is the length of the segment, 43 miles or

$$T = \frac{1,500}{0.00112 (50-33)4.3} = 18,320$$
, rounded to 20,000 gpd per ft

Aquifei-test data are not available for the north end of Cedar Valley, however, the valley fill in this area consists of coarse-grained sediments of the West Canyon alluvial fan, which are assumed to be as permeable as the sediments of the Pole Canyon alluvial fan, which underlie the line of segment 3. The coefficient of transmissibility along segment 4, therefore, is assumed to be 20,000 gpd per ft. The hydraulic gradient is 73 feet per mile

Underflow for the four segments is presented in the following table

Segment (location shown in figure 4)	Coefficient of transmissibility (gallons per day per foot)	Hydiaulic gradient (feet pei mile)	Length of segment (miles)	Subsurface outflow past the segment (acre-feet per year)
1	7,000	8	6.1	400
2	9,000	31	84	2,600
3	20,000	33	4 3	3,200
4	20,000	73	22	3,600
	Total	(rounded)		10,000

Thus the total subsurface outflow along the east edge of the basin is estimated to be 10,000 acre-feet per year

The second method used to estimate subsurface outflow was a water budget of the ground-water reservoir in Cedar Valley. This budget is only an approximation of true conditions, however, because few data are available for rates of precipilation, evapotranspiration, and recharge in urigated and nonurigated areas.

It is assumed that all the water leaving the basin along the eastern margin (figure 4) is subsurface outflow from the basin and is a constant quantity. On this basis, the equation of the hydrologic budget is as follows: subsurface outflow iS) from the basin equals recharge from precipitation (Rp) minus evapotranspiration of surface water from West Canyon (Es), and of ground water from Fanfield Spring (Ef) and the three springs west of Cedar Fort (Ec), and of water pumped from wells (Ep), or

$$S = Rp - (Es + Ef + Ec + Ep)$$

Substituting values determined m previous sections of this report,

$$S = 24\ 000 - (1,000 + 2,000 + 400 + 1,700)$$

S = 19,000 acre-feet per year (rounded)

Thus the subsurface outflow along the east edge of the basm is estimated by the budget method to be 19,000 acre-feet per year. Although this is almost twice as much as the outflow calculated by the fust method the two figures are of the same order of magnitude and they are a good indication of the magnitude of the actual quantity of outflow

Test-well drillug—Five test wells were drilled at four sites in Cedar Valley to constituct water-level observation wells and to obtain additional data about the aquifers in parts of the valley Descriptive data, water-level measurements, and logs for the test wells are given in tables 2, 5, and 7 Electric and gamma-ray logs for four of the wells are m the files of the US Geological Survey in Salt Lake City

Test wells (C-5-1)20ddc-1 and (C-5-2)24aab-1 were drilled in the pass between the Lake Mountains and the Traverse Mountains to determine the thickness of the alluvium, the depth to water, and whether or not water moves from Cedar Valley to Utah Valley through the alluvium. The alluvium was found to be 70 feet thick in well (C-5-1)20ddc-1 and 60 feet thick in well (C-5-2)24aab-1 (table 7). Water levels in the two test wells m May 1966 were 94 and 127 feet below the land surface, respectively. This indicates that the water does not leave Cedar Valley through the alluvium, but it does move through the bedrock.

Test well (C-6-2)1acc-1 was dilled to provide water-level data for the northeast coiner of the valley and to define inoie closely the water-level contour lines of that area (figure 4). The test well was drilled entirely in unconsolidated valley-fill deposits, mostly sandy and clayey silt with occasional beds of fine to medium-grained sand or silty sand, ranging in thickness from 2 to 8 feet. The water level in the well was 175 feet below the land surface m March 1966.

Two test wells, about 15 feet apart, were dilled m sec 27, T 6 S, R 2 W Test well (C-6-2)27ccc-1 was dilled to a depth of 505 feet for observation of water levels m the deep artesian aquifer. It was dilled entuely in unconsolidated valley-fill deposits, mostly clayey and sandy silt with occasional beds of fine-gramed sand or silty sand, ranging m thickness from 2 to 10 feet. Test well (C-6-2)27ccc-2 was drilled to a depth of 100 feet to provide water-level measurements m the shallow unconfined aquifer. A plug was installed m the annulus of the deep test well at a depth of 150 feet in an attempt to isolate the deep and shallow aquifers. Water levels in the shallow lest well and the annulus of the deep test well were at the same level and almost 3 feet higher than the level within the deep test well itself during April 1966.

Chemical quality of water

The concentration of dissolved solids in the water in Cedar Valley ranges from 225 to 2,020 ppm (parts per million). Figure 7 shows the areal distribution of dissolved-solids concentrations and also illustrates the chemical composition of the water with lined diagrams. Differences in chemical composition are shown by the differences in the slope and length of lines comprising the diagrams.

The water from most of the wells and springs in the northern and south-western parts of the valley contains less than 500 ppm of dissolved solids, and the principal chemical constituents are calcium and bicarbonate. The springs in the principal recharge area (Oquirrh Mountain slopes, west and northwest of Cedar Fort) yield a calcium bicarbonate type of water chemically similar to that of ground water in the north-central part of the valley. The wells in the southeastern part of the valley yield water containing the highest concentration of dissolved solids, and the principal chemical constituents are sodium and sulfate

Most of the water in the valley is very hard (more than 180 ppm), but generally the chemical constituents do not exceed the recommended maximum concentrations of the US Public Health Service (1962, p 7) as given below

Constituen ^e	Recommended maximum concentration (parts per million)
Dissolved solids	500
Chloride (Cl)	250
Sulfate (SC+)	250
Nitrate (NO ₃)	45

Thirty water samples from wells and springs in Cedar Valley were evaluated for smtability for irrigation by using a method devised by the U.S. Salinity Laboratory Staff (1954, p. 80). The water was classified in regard to salimity hazard and sodium hazard by plotting the specific conductance versus the sodium-adsorption ratio (figure 8). The interpretation of these quality-class ratings plotted m figure 8 are summarized by the U.S. Salimity Laboratory Staff (1954, p. 79-81) as follows.

"Medium-salimty water (C2) can be used if a moderate amount of leaching occurs Plants with moderate salt tolerance can be grown m most cases without special practices for salimty control

"High-sahnity water (C3) cannot be used on soils with restricted drainage. Even with adequate dramage, special management for salinity control may be required and plants with good salt tolerance should be selected.

"Very high salinity water (C4) is not suitable for irrigation under ordinary conditions, but may be used occasionally under very special circumstances. The soils must be permeable, drainage must be adequate, irrigation water must be applied in excess to provide considerable leaching, and very salt-tolerant crops should be selected.

"Low-sodium water (S1) can be used for irrigation on almost all soils with little danger of the development of harmful levels of exchangeable sodium. However, sodium-sensitive crops such as stone-fruit trees and avocados may accumulate mjurious concentrations of sodium.

"Medium-sodium water (S2) will present an appreciable sodium hazard m fine-textured soils having high cation-exchange-capacity, especially under low-leaching conditions, unless gypsum is present in the soil. This water may be used on coarse-textured or organic soils with good permeability.




Figure 8 — Classification of water for irrigation in Cedar Valley (method of U.S. Salinity Lab. Staff, 1954, p. 80)

Numbers refer to analyses in table 4.

"High-sodium water (S3) may produce harmful levels of exchangeable sodium m most soils and will require special soil management—good drainage, high leaching, and organic matter additions. Gypsiferous soils may not develop harmful levels of exchangeable sodium from such waters. Chemical amendments may be required for replacement of exchangeable sodium, except that amendments may not be feasible with waters of very high salimity."

Water from most of the wells and springs that were sampled in Cedar Valley has a low-sodium hazard and a medium-salinity hazard (figure 8). The analyses of water from the three wells that were sampled in the southern part of the valley, however, suggests that water in a large area southeast of Fanfield probably has a very high sahnity hazard and medium to high-sodium hazard.

SUMMARY AND CONCLUSIONS

Most of the water in the ground-water reservoir of Cedar Valley is derived from precipitation on the Oquirrh Mountains northwest of the valley. After seeping into the ground, the water moves directly from the bedrock of the mountains into the aquifers of the valley fill, thence east and southeast across the valley

Most of the wells in the valley tap artesian aquifers in the noith-central part of the basin and yield water of good quality for domestic use and irrigation. Stock wells in the southeast part of the basin yield water of poor quality from aquifers under water-table conditions. In the southwest comer of the valley, where some recharge occurs at the base of the East Tintic Mountains, stock wells yield water of good quality.

During 1965, eight irrigation wells in sees 13, 14, 15, and 26, T. 6 S, R 2 W, discharged a total of 1,900 acre-feet of water. The yields of the wells ranged from 130 to 1,115 gpm, and specific capacities ranged from 0.7 to 6.8 gpm per ft of drawdown. During 1964, the eight wells discharged only 1,100 acre-feet of water, but three wells in sees. 17 and 32 discharged an additional 2,700 acre-feet of water. Two of the wells in sec. 17, reportedly yielded 2,000 and 3,600 gpm, with specific capacities of about 30 and 37 gpm per ft of drawdown upon then completion in 1961-62. The difference in well performance in the two areas is an indication of more permeable aquifers on the west edge of the basin

Water levels in the valley generally fluctuate m response to variations of precipitation In sees 14 and 15, T $\,6$ S , R $\,2$ W , however, where mne irrigation wells were drilled during 1951-64, water levels have dechned as much as 21 feet during the period 1954-66. Water levels in wells near Fanfield and the discharge of Fairfield Spring declined during the period 1962-64 when large irrigation wells in sec 17, T $\,6$ S , R $\,2$ W , were pumped in the same or interconnected aquifers

The estimated subsulface outflow of water from Cedar Valley along the east edge of the basin ranges from about 10 000 to 20,000 acre-feet per year. Some of this water could be recovered in the valley by an increased withdrawal of water from wells, principally along the west edge of the basm in T 6 S, R 2 W, where most of the recharge enters the valley fill from the bedrock in the Oquirrh Mountains. The aquifers m this area are the most permeable known in the basm, they are under artesian conditions, and the quahty of the water is good. The altitude of the area would permit gravitational flow of the water to nearly any area now being irrigated. A long-term effect of pumping the wells, however, would be a decrease in the artesian pressure of the aquifers and a resultant decrease m or cessation of discharge from flowing wells and springs m the Fairfield area.

Another area of potential ground-water development is the alluvial fan of West Canyon No well or water-level data are available for the large area north of Utah Highway 73, but permeable materials should be present in the fan which was built by the only perennial stream in the valley

SELECTED REFERENCES

- Bissell, H J. 1963, Lake Bonneville Geology of southern Utah Valley, Utah US Geol Survey Prof Paper 257-B
- Bullock, K C, 1951, Geology of Lake Mountain, Utah Utah Geol and Mineralog Survey Bull
- Cook, K L , and Berg, J W , Jz , 1961 Regional gravity survey along the central and southern Wasatch front, Utah U S Geol Survey Prof Paper 316-E
- Disbrow, A E, 1957, Preliminary geologic map of the Fivemile Pass quadrangle, Tooele and Utah Counties, Utah US Geol Survey Mineral Inv Field Studies Map MF-131
 - 1961, Geology of the Boulter Peak quadrangle, Utah US Geol Survey Geol Quad Map GQ-141
- Eakm, T E, and Maxey, G B, 1951, Ground water m Ruby Valley, Elko and White Pine Counties, Nevada, in Contributions to the hydrology of eastern Nevada Nevada State Engineer Water Resources Bull 12
- Gilluly, James, 1932, Geology and ore deposits of the Stockton and Fairfield quadrangles, Utah U.S. Geol. Survey Prof. Paper 173
- Hunt, C B, Varnes, H D, and Thomas, H E, 1953, Lake Bonneville Geology of northern Utah Valley, Utah U S Geol Survey Prof Paper 257-A
- Morris, H $\,$ T , 1964, Geology of the Tintic Junction quadrangle, Tooele, Juab, and Utah Counties, Utah $\,$ U S $\,$ Geol $\,$ Survey Bull $\,$ 1142-L $\,$
 - 1964, Geology of the Eureka quadrangle, Utah and Juab Counties, Utah U.S. Geol Survey Bull 1142-K
- Morris, H T, and Lovering, T S, 1961, Stratigraphy of the East Timtic Mointams, Utah, with a section on Quaternary deposits by H D Goode US Geol Survey Prof Paper 361
- Proctor, P D, and others, 1956, Preliminary geologic map of the Allens Ranch quadrangle, Utah US Geol Survey Mineral Inv Field Studies Map MF-45
- Rigby, J. K., 1952, Geology of the Selma Hills, Utah County, Utah. Utah Geol and Mineralog Survey Bull. 45
- Snyder, C T , 1963, Hydrology of stock-water development on the public domain of western Utah U S Geol Survey Water-Supply Paper 1475-N
- Stokes, W L, ed, 1963, Geologic map of Utah, NW1/4 Utah Umv
- Theis, C V , 1935, The relation between the lowering of the piezometric surface and the rate and duration of discharge of a well using ground-water storage. Am Geophys Union Trans , v 16, p 519-524
- U.S. Public Health Service, 1962, Drinking water standards. Public Health Service Pub. 956
- U.S. Salinity Laboratory Staff, 1954, Diagnosis and improvement of sabne and alkali soils U.S. Dept. Agriculture Handb. 60

Table 2 — Records of selected wells in Cedar Valley

Well number See existed description is subsessed in the see that the s

n feet

Redulring poin Description** Ahp access hole in pump Apc access pipe in centing Bph** button if pump hase Edo end of ditharge pipo Mc4 note in casing

**Upb hold in peop hase if principle in centing in the point of the point of

			T		T	T			aur ing olnt	Water	rlevel]	Y	eld	Dre	udoun		٠,	T	
Well number	Ovner or user	Year drilled		0 5	Diameter of umll (inches)	Depth of Casing (feet)	Altitude of land surface datum (fact)	13	Abova(+) or below() land surface datum (feet)	above(+) ur bolou() euriace (éast)	Data of measurement	Hathod of lift	Hate (BMs)	Data of umasurement	Amount	Durmition of test (days)	Specific capacity (gen/ft)	Use of weter in 1965	lanparature ()	Jamarka and other data e allabla
	t I J S Geologi a' Survey	1963 1966		105 3C0			9C0 4 795	Tea	+0.5	Dry 93	S 4 65 5 3 60	b N						٧ ٩٤		→ 3 Perl 60 0 90 100 210 220 fr ZGR → L W
(C 3 2) 24aah 1	do do	1966	Dr	155	1	155	4 989 7	Tue	0	12/ 3	5 3 60							٧ŧ		TW 2 Part 55 65 145 155 EGR
	State of Ucali IG S Cook	1316 1903	Or	44.8 325	9	321	5 082 9 5 8 -	Tea		Ì	6-22 60 2 28 66	1	18Pr	6-22 6				M	53	C Bailet test April 1963 ylald 12 gpm ao drawdovn aftar 1 hr Parf 300-320 fc L W
34d∉b 1 (C 4-)		1943	Dr	280	64	280	4 962 2	Tea	+ 9	249 0	3-26 66	N						Я		To partorationa rapoztad Watar level 250 tt in April 1943 reported by well driller W
Sdca 1	Coeperative Security Corp		ll	264	1	i i	., 387 e	ı		l	3 '4 66	11		8 31 6	1					Per(235-264 ft C d
3 td4b 1 (C 6 2)	du. US Geologicai	1966		223 300	i	1 1	4 575 4 891 5	Tea	+l 1 0		3 14 66	1 1	6Pm	7 21 6	1			5 Vt	61	Perf 190 223 ft C w
Sted 1	Survay	193_	1	105		į į	4 9/2 8		3 3	i	2 28 66	1 1					i	H		290 (t ECR TWL allocal realdent reported well drilled in early 1930 s as drought tallef we l to depth or about 200 fc Wal
I3taa l	Couperative Secar ty Corp	1962	Dr	525	0	333	4 856 6	Ape	- 1 5	119 8	3 18 66	т	400 <i>P</i> m	5 3 6	72	(1)	5 3	1	61	was never used of medit was gravel packed 15 339 fc peri 0 339 fc smalled 0-15 fc with bontonits in 20 inch turface casing C L W
l4aba 1 14aca 1	do do	1954 1954	De Dr	1 238 1 014	20 12 20 12	1 254 1 014	4 965 7 4 862 6	Tea Tea	0	121 / 109 /	3-28-66 2-28 56	X H	90P r	2 54	•		-	N A)	Parf 150-300 306 I 254 it L W Perf 130 274 280 I 014 ft W
14cac 1 1Acsa 1		1951 1954	Dr	1 230	14 IC 16	1 250 1 007	4 855 i 4 856 7	Edp Mca	+14 4	99 2	3 28-66 3 28 66	17		5 3 60	s -			DI		Perf below 300 ft C w Parf 98 1 007 fc C W W
t/ulna 1	do	1964	Or.	830	20 12, 10	600	4 858 4	Врь	+1 9	97 3	3 28-66	T	130Pu	5 3 60	174	(1)	7	I	64	Casing 20-inth from 0-556 ft 12 inch from 0-350 ft and 10 Inch from 350 to 500 fc Perf 120 356 ft 1a 20 inch casing 170-500 it in 12- and 10 inch casing Cravel packed between 20 inch and 12- and 10 tech casing 0 600 tc C
L5elb 1	do	1961	Dr	2 366	16 IQ S	2 085	4 864 9	Tea	0	120 4	3 27-66	H	47CP:si	7 16	-	-		4	-	Wall deepened from 460 to 890 ft in 1959 and from 890 to 2 366 (c in 1961 Perf 222 440 985 995 1 045 1 375 1 440-1 485 1 844 2 070 r L W
15hbb 1 13hub 1	do	1957 1959	Dr	835 955	16 10	955	4 871 7 4 864 6	Ape	0+25	S# 9	2-28-66 3 24 66	ıτ	515Pm 390Pm	5 3 66 5 3 66 5 3 66	134	33 (1)	3 8 2 8	I	53 53	Pert below 185 ft C W Parf 278-955 ft C W
15cbb I 16hma 1 17dcc 1		1957 1951 1961	Or!	455 505 600	16 10 16	505	4 860 5 4 876 5 4 913 6	Мрь	+1 5 +1 3 + 5	67 9	3-28-66 4 1-66 3 31-66	I T	335Pm 335Pm 2 000Pr 2 890Pm	7 10 63 12 30 61	67	2 6		I I I	53	Perf 190-340 395 403 fc C W Perf below 80 fc N W Parf 150-175 237 246 350-376 422 432 445-492 525-535 fc The south wall of two wells L W
lødec 2	do	1962	Dr	595	16	595	4 920 9	Ahp	+ 5	27 9	3 31-66		3 600Pr 2 765Pm			1	3	I	•	Perf 170-174 238 248 325 350 365 371 410-440 465 481 488 493 530-544 550 574 582 587 ft The norch well of two wells W
	Cnoperaftive Secur ty Corp	- [- 1				4 838 8		+1 7		3 30-66	11	-	•				3		u
2 7ecc i	W S Geological Survey	1962 1953 1966	Dr	505 #0 505	18 6 1	90 505	4 844 1 4 842 8 4 843 2	Tec Tc•		34 6 27 9	4- 7-66 4- 7 66 4- 7 66	A N	l LLSPn	5 3 66	164	26	6 8	H c	-	Perf 210 505 ff C L a Perf below 35 fc W TW 4 Perl 265-275 455 465 485 495 fc EGR INL W
27c c 2		1966 7953	- 1	100	1	- 1	4 843 2 4 858	- 1	0		4-766	I ł	- [-	Nt W		TW 5 Perf 90-100 ft Located 15 tt from wall (C 6 2)27ccc 1 J Pert below 20 ft W
29hdd	S D 11 holus E R Carsun L Mainzer	-	Dr	150 350	3	150 350	4 875 1 4 888 4	Tea	+ 5 +1 2 0	+13 1 T 9	3-11 66 4 7 66 4 6 66	r e	l SFat <lfe< td=""><td>7 30 65 4 6 61</td><td></td><td></td><td>-</td><td>s</td><td>50</td><td>С W С N W</td></lfe<>	7 30 65 4 6 61			-	s	50	С W С N W
29c∉c 2 29ccc 1	do C R Carann	1953	Dr	220 189 619	4 3 16	220 4 389 4	4 888 7 4 886 7 4 880	Tca	+ 5	- 4	4- 6 6 6 3 11 66	я I	, 7Fm 42 8₽>	9 9 65	-	1 3	- , 2	N 1 S 1	52	C W Perf at 14 tntervals between 205 and 595 tr C L

Table 2 — Records of selected wells in Cedar Valley — Continued

			Π						eurlng int	ates	level	Γ	Yıc	1d	Dra	rudown	j	2		
ell n.mber	Owner ruer	Year drilled	Type of well	Depth of well (feat)	Dismerer of well (and e)	Depth of casing (feat)	Altitude or land sufface detum (feet)	Description	Above(+) or below() land surface datum (feet)	Abu e(+) ur beluu() surface (teet)	Date of measurement	Nethod f 11ft	Rate (Kpis)	Dete of mussurament	Amount	Duration of test (days)	Specific capacity (gpm/ft)	Use of water in 1965	Temperature (F)	Kematka and other data evallabls
13bcb l	Utah state Palks and Recreation Camm Rusum Carsoo S O Micholas	i	Dr Dr Dr	64 525 275	4 2 6	525	4 890 4 862 4 4 843 5				4- 7 66 3-11 66		6Pr ≪1Fm 25Pr	4- 7 66 8- 53				I D I		C W Weil depth sounded at 55 fc below the tap of castag in May 1963 ferf below 30 ft W
	W McKinney R J McKinney do	1948	Du Or Du			220	4 902 4 835 4 846	8pe	D -	45 114 6	3-21 66	Ey Cy	10Pr	7 22 48	,		-		58r	Weter level reported by Snyder (1963 p 522) L W Original dug weil backfilled eround 6 inch clie casieg with 4 inch steel pump column C
	L & Pitzgereld	1948	Du Dr	198	5	225		Tíc Tca	İ	İ	3 11-66 3 11 66		0Br	7 14 48				s	60 r	Original dug well backfilled eround binch tile coaseg with 4 inch steel pump celumn W
(C 3 2)	J d Allen		Du Du	275	"×72		4 895	Трс	ŧ	240 8) 11 ot	Cy Cy						s		Original dug wall backfilled eround 6 inch tile casing with 4 inch steel pump column C W C
3ledb [do do		Pu	365				Tca	+ 8	343 0	3 1 66	Сý						S		Original dug wall backfilled eround 6 inch steet casing with 4 inch pump coluen C W

I' Well had been pumped for about I month since the beginning of the irrivacion seaso

Table 3 — Records of selected springs in Cedar Valley

Lutation See igure

Ceuligit source Oquiri: Formation is of Ponns; vanian and PenoiAn age

Use of water D dissest: I regation S sock

Dependent lify C good F lair

Vield (gpm gailons par minute) e estimated m measured

Remarks and other data a milable C chenical analisis (able 4) H nydrograph (ig 5) K specific tunductaoca (table 4)

			Geol	ogic suurca	1 2 2 2	4	111,		Q 7 5		}
Locatiun	Owner t ummr	Yene	Frmatiun or type of rock	Yatura of openings	Use of W	Tumperature (F)	Dependability	Impruvaments	Yield (gpm) and dete of measurament	Deposite	Remarks and other data available
(C 4 2) 26cbc		Tickville Spr ng	A luvium In contact with igneous Tock of Tertiary	Large iccp area in itreas ehanaci	s		G	. Yn ie	10a 4 7 66	Tone	С
(C 4 3) 20dba			age Oquirth Porma tion	Joints and aclution channels in lime stone	s	45		do	15au 1 -3-6>	do	С
26c b d		Cocconuood Spring	do	do	5	ÞΙ	G	Water trough	15a 11 3-65	Tufa	x
26dda			do	d∎	s	49	G	do	15a 11 3 65	do	С
27 b a b			d⊕	dυ	s	46	G	Yon•	17m 11-3-65	do	K
(C 5 1) 17bdc	<u> </u>		Alluvium	Seep area in stream	s		F	Water traugh	<la>6 °> 65</la>	Yone	С
(C 5 3)4cdc			Oquitri Torma tiun	Juints and solu in thannels to lime atome	s	44		Hone	10e 11 2 65	do	K
4dcd	<u>:</u>		41 luviam	seep area in canyon fill	s	42	С	Pipaline and trough	5m 11 2 65	d∎	Water piped amoor had a mile to water trough K
36cba	Cedar Fort Irrigation Co		Oquir h Forme- tion	Join a and a lucion chainels in lime stona	1.5	46	C	None	300a 7 22 65	Tu a	C C
(C tı 2) 6c ad	do		Alluvius over- lying cha Oquirth Formation	SCORE	015	50	0	Headhouea and pipa na	>124max 7 22 65	Yone	С
29cce	Fairtlald Irrigation Cn	Faitfield Spring	A ¹ luvial fan	Large saep and spring area at toc of allouial fan	DIS	52	G	Headhouse pipeline and diver sion system	2 070an 3 1 66	do	СН
(L 6 3) land	Cedar Fort Ir Igar on Ca		Oquirrh Forms tlor	Joints and solution channels in ilse cane	DIS	4.2	G	Tunnel and pipeline	>85m 7 22 65	Tufe	С
15hed			do	do	s	52	г	None	7m 6 21 65	Yone	G
(C 9 2)29b and 32c	J H Alen		Aluviss	Seep & e&	D S		С	Pipeline and tanks			Water pipad about 4 Milae from two aprin Si es to ramen nouse and several stnek tanks K

Table 4 — Chemical analyses of water from wells and springs in Cedar Valley

		П						Par	e per :	nillion			,	,	,	retto	.0	
Sampling site	Data of collection	Temperature ()	8/1/cm (S102)	Celcium (Ce)	Magnes fun (Ha)	M (M)	Petassium (X)	Micerhonate (MCO ₃)	Carbonate (CO _J)	Sultate (SO ₄)	Chlor1de (G1)	Nitrate (NO ₃)	Utsmolved solids	Haroness as GaCO ₃	boncactonate hardnass as OaCD3		Spacific condoctance (micromhda/cm at 25 C)	
C 4 2) 26cbc C 4 3) 20d6a 26cbd 26dd& 27bab	4 7 66 11 3 65 11- 3 65 11- 3 65 13- 3-63	46 51 49	48 7 0 12	77 95 - 130	10 13 - 28	1	1 10 57	220 330 447	0 0	33 25 38	76 11 80	0 8 3	431 323 558	234 290 - 438	54 19 71	1 2 3	558 773	7 7 . 7
C 5 1)17bdc C 5 2)26bbb 1 C 5-))4ede 4dcæ 36cba C 6-1)18dca 1	8 25 65 6 30-65 11 3-65 11 2-65 7 22-65 7 1-63	53 45 42 46	49 19 6 5 21	148 50 62 73	30 14 - 16 25	,	7 1 2 y 5	148 262 - 240 240	12 0 0	56 37 - 15 70	295 34 8 0 66	2 3 1 1 - 3 5 1 4	853 337 227 421	494 257 220 288	353 42 - 23 91	1 3 6 1	1 360 572 477 518 424 706	8 7 7 7
31deb 1 ¹ / 3 6 2)6ced 13ees 1 14cec 1 4cbs 1	7 1-65 7 22-65 7 1-65 6 8-65 6 8-65	50 61 59	46 8 0 55 53 48	32 88 35 31 27	116 12 18 14 13	17 ⁴ 3 20 20	5 5 7 0	324 288 208 170 174	0 0	291 27 38 14 14	335 11 21 16 14	7 2 1 4 0 2	2/1 230 290 300 229 225	680 269 160 134 120	414 33 0 0	3 0 3 1 3 7 1 0	2 060 520 461 344 346	7 7 8 8 7
14dbs 1 15bob 1 15bcb 1 15cbb 1 26cob 1	6 9 65 6 8 65 6 8-65 6 8-65 7 1-63	53 53 53	46 40 38 40 53	29 80 55 46 36	13 32 26 20 30	30 14 10 20	4 6 8 6	198 263 248 194 246	0 0 0 6	22 36 37 23 27	14 78 26 17 19	0 7 0 2 1 2	253 451 313 273 298	126 332 244 200 212	0 116 41 43 10	1 4 3 4 3 6	393 709 512 434 470	8 7 8 8 3
29bdd 1 29cac 1 29ccc-1 29ccc 32bbd 1	7 30 65 1 3-66 9 9-65 6 3 65 6 30 65	50 52	11 11 10 14	58 57 39 36	17 - 18 20 27	,	5 9 9 2 3 7 2	228 232 236 248	0 0	17 18 29 40	15 17 17 18 21	2 7 - 3 4 2 3 1 0	235 - 262 253 290	215 - 234 232 250	28 - 24 38 47	3	430 421 444 457 502	7 7 8 8
32eoc 1 33bcb 1 6 3) lead 15bed 17 2) 25bdb 1 ² /	10 4-63 1 3-66 7 22-65 6-21-65 3 31 66	47 32	19 15 6 8 6 9 32	67 32 65 67 28	30 16 16 29 135	31 31 4 12 426	.	325 393 248 303 338	0 0 0 0	49 34 17 38 941	29 16 8 7 20 140		360 237 235 321 2/2 020	292 146 227 289 625	26 0 24 41 200	1 2 1 3 7 4	647 424 436 586 2 870	7 8 • 7 8
35bcc-1 2 8 2)15mmd 1 18bcb-1 31mdb 3 9 2)29b and 32c	3 29 66 3 66 3 66 3 66	-	23 52 30 38	42 30 31 26	114 92 24 19	383 439 75 101	;	487 764 226 2°8	0 0 0	842 638 72 64	94 84 56 79	4 5 1 5 5	2/1 740 2/1 710 391 448	57.5 455 176 146	376 0 0 0	7 0 8 9 2 5 3 6	2 430 2 410 668 717 381	7 8 7 7

^{1/} Analysis includes 2 2 ppm fluorida 2/ Calculated from decarminad constituents 2/ Amalysis includes 0 00 ppm iron (at time of analysis) 4 0 ppm fluoride and 1 3 ppm borom

Table 5 — Water levels in observation wells in Cedar Valley

Jater favels in feet bet at land our see do im so designated by a sinus () sign immediately before the first entry in each tolen in he table those above land unface darism are designated abs larly by a plus (+) algo. The sign applied to any water level applies to all succeeding water level until a lange is indicated.

As actatisk (*) immediace; after a neas rement indicates that the neasurement is ft and ata supplied by the Office of the Utah. State Engineer is discovered as were (t) also a meas rement is discovered to the neas rement is from data supplied by pri ace consultant all other mass rement were vade by the U.S. Go logical riev

(c :	5 12	20ddc 1	l Record	. a /a L	lable	1965						(C 6	2)14	icha-I	l Contin	.ed								
Her	18		5 -, →9 7	Ча	30	1966	2 88	Yay	,	1950		Aug	25		4/ 39 6	Sept		1965	<u>±/ 1.</u>		Har	ı		
Mar Mar	21 26		1/ 60 0	Apr Apr	į,		1/ 42 4	June	9		91 3	Aug Sept	11		4/ 123 8 4/ 121 >	Oct Oct	4 29			18	Mar Mar	28 29		6/ 102 2
												Sept	16		5/ 2 8 4 4/ 154 >	Nov Jan	30 3	1906		93	Mar Mat	30 11		6/ 104 6 4/ 106 6
		24aab 1 5 1966						Jane	9	066	1/ 131 0	Sept Sept			4/ 143 3	Fac	í	1900	4/ 10	0 7	Apr	1		6/ 107 9
Mar Mac	30		1/ 96 7	May	3		127 3	June	, ,	700	131 0				Bacocde	(1		1064 6						
// 5	. 21.2	lded l	Pecord		ah I a	1965 6	4					0cc	10	1964		Sept				8 8	Yar	1	1966	- 97 5
Aug				Oct	29	1965	298 6		1	1966	297 1	Dac	16		105 3	Sapo	19		11	9 1	Mar	28 29		4, 97 1
Aug Oc	31 4		299 7 299 0	Nov Jan	30 3		297 9 297 4	Pah	25		246 1	Mer	9 12	1963	102 4 120 2	Sept Oct	20 4			13	Mar Mar	30		6/ 103 9
								-				July	1		169 7 147 1	Oct	29 30			44	Mac Apr	31 1		6/ 108 3
		4dab 1		avail	able	1966						Aug	25 11		128 6	Xov Jon	1	1966	9	91	May	3		3/ 271 2
May		1966										Sapc	17		195 8	Fab	1		9	8 2				
		8dca '				1964 6						C 6	-2) 1 :	abb 1	Records	avail	able	1964 6	6					
Apr Yov	28 9		227 l 228 8	July Aug	21		229 9 . 229 7	Oct	4 29	1965	229 B 230 O	Har Hov	25 10	1964	123 9 122 3	Aug	11 16	1965		63 53	Oct Yov	29 30	1965	121 9 122 4
Mar	9		229 6 232 8	Aug	١2		210 2	Ma	14	1966	730 0	Dec	16		121 2	Sept Sepc				4 9	Jan	3	1966	121 6
Apr	12		232 6	Sept			229 9					Har	9 12	1965	121 3 124 9	Sepc Sepc				43 36	Feb Feb	1 _8		121 1 20
(C 6		ldab l				1964 66						Apr July	1		136 1	Sept				28	Mar	27		120 4
Apr Dac	28 16		194 2 194 7	Aug Sapo	12 1		94 9 195 0	Nov Jan	30	1965 1966	193 3 195 3	July Aug	30 12		137 3 138 3	Sept Oct	27 4			88 69	Hay	4		133 1
Mar	26	1965	194 6	Oct	4		193 l	Yer	t-	.,	195 3													
Aug	1		194 9	Oct	29		195 2							1059				1958 6		64 <u>66</u> 0 9*	Oct	4	1965	-127 4
		acc l	Recorde									Mer Dec	14 24	1958 1959	107 6	Mov Mov	6 10	1704	12	0 4	Oc t	29	170)	121 1
Mer Mer	'1 22	960	1/ 116 3	Yet Apr	10 1	1966	17 4 1 4 5	May Juna	9	1966	174 8 174 6	Mar Dec	25 7	1960	131 2	Dec Apr	16 12	1963		91 41	Mov Jan	30 3	1966	121 4 120 2
Mar	- 6		174 5	Apr	<u>;</u>		د 174					Yar	22	1961	118 1	Aug	24		14	50	Fen	1	1,00	119 4
(C 6	2)5	cad 1	Racorda	availa	ble 1	965-66						Mar Oct	25 2	1964	116 6 126 0*	Sapc Sapt	9 16		シ/ 24 16	02 59	Feb Mar	28 10		119 0 118 6
Aug	17		85 6	0ct	29	1965	- 81 3	Feb	ı	1966	82 8	Oct	22		122 0*					19	Yay	1		2/ 252 1
Aug Oct	31		94 5 81.7	Hov	30		S3 4	Feb	28		82 6	(C 6	2)15	bcb 1	Baecrdt	availe	ble	1961 6	6					
												Mar	21	1961	96 5*	Dec	16	1964	9) 1	0c t	29	1965	- 96 0
		3eaa-1 1961			12	1963-66	119 5	N	30	1965	122 8	July Mar	1 25	1964	4/ 127 4 88 4	Mar Apr	9 12	1965		68	Yov Jaa	30 3	1966	93 2 92 2
Mar Apr	29 5		117 4		9	4	110 5	Nov Jen	3	1966	121 4	Oc.	2	1754	107 4#	Sapt	19		4/ 15	2 1	Fab	1	.,,,,	90 0
June Julø			*/ 156 6 4/ 133 1	Sept Sept	7 18		169 3	Feb Mar	1 14		120 6 120 0	Occ Nov	22 6		95 0≃ 91 0±		20		4/ 14 10	51 39	Mar Mar	1 30		89 2 88 8
Mar	25		118 1	Sept	19	3	136 6	Mar	27		119 8	Nav.	13		97.1									
Oct Dec	10		122 3 120 6	Sapt Oct	20 4	9	134 1	Mar May	28 3		118 8 192 1	(0 6	2) 15	cbb l	Recorde	availe	ble	1963-6	6					
Her	9	1963		Oct	29		124 6	,	,		- 1,12 1	Mar	23	1963	6/ 74 0		29	1964		8 8*	Sapt	18	1965	4/-124 8
Mar	26		4/ 124 6									Mar Apt	29 5		6/ 79 4* 6/ 93 0*	Oct Mov	22 6			8 7* 6 6*	Sapc Sapt	19 20		4/ 118 0 4/ 113 2
(8-6	2) 14	eba-1	Bacorda	e aile	.bla	1954 55	1963 6	6				Apr	10		91 7*	Mov	10		7	5 6	Oc t	4		86 9
Dec Apr	9 12		111 0 1C9 1	Mar Occ	25 1	1964	118 9 129 6	J∶ly Aug	11 11	1965	119 1 114 9	Hay Hay	7 11		6/ 98 5# 95 8*	Dac Mar	16	1965		3622	Oct Yov	29 30		78 4 75 2
Mar	23		119 9	Xov	10		123 7	Sapt	17		133 2	June	6		. 94 2	Apr	12		ļ', 7	93	Jan	1	1966	71 4
Ma Apr	29 5		122 4* 127 0*		1 e 31		122 J	>apc Oct	50 31		129 9 125 2	July	15		95 34	tape Sept	15		弘, 2i	3 3	Fab Mar	ì		72 J 71 7
Apr	30		129 5* 129 9*	Jan	31	1965	121 6	Yuv	30		123 7 122 3	July Mar	20 25	1964	6/ 117 2* 72 8	Sapc Sapc	16 17) 8 3 3	Mar Mar	7. 28		71 5 71 4
May May	ıí		130 7*		25 1		121 4 121 2	0ec Fab	31 1	1966	122 3							<u>-</u>						
May June	23 6		132 -* 111 i		11 30		128 8 129 6	Har Har	1 28		121 9 121 7		2)16 9		Recorda - 51 7		7	1954-6 1960		65 66) 6	Sept	19	1965	85 Z
June	15		112 1*		11		131 8	Hay	3		133 0	Dac	12	1954 1953	51 8	Dac Dac	20	1961	7	1 8	Oct	4	190)	75 9
July July	1 20		128 4* 132 6*	June	30		136 7	June	9		116 3	Dec Mar	22 28	1936	58 0 58 3	July July	1 30	1965		77	Oc t No v	29 30		72 7 1 2
												Jan	2	1937	60 4	Aug	12		<u>6/</u> , 8	3	Jan	3	1966	70 3
(C-6 Dec	2) 14	1954	- 98 4	avail:	25	1954 55 1964	1963 6 109 3	6 Occ		1965	120 1	Dac	6 14	1938	64 7 64 6	Aug Aug	25 31			8 7 7	Fab Fab	1 28		69 7 69 2
Apr	12		- 98 4 95 7	Mar	9	1965	109 7	Oct	29	190)	114 7	Apr	11	1959	69 6	Sapc	16	1	<u>6/</u> 8	7 7	Apr	1		67 9
Mer Mer	21 29	1963	110 6* 120 1*		1 10		145 4 150 5	Nov Jan	30 3	1966	112 3 111 t	Dac Mar	24 25,	1960	68 1 71 8	Sapt Sapt	17 15			70 51	Yay Juaa	3		84 2 88 9
Apr	5		133 1*	Aug	12		155 4	Fab	ì	1,00	110 2	1						1041 4	۷.					
Apr Juna	30 6		130 0± 139 2	Aug Sapt	11 17		131 5 135 7	Mer	1		109 7	(C 6	2)1/4	1963	- 23 6*		l l	1964		9 41	July		1965	23 8t
	23.17					1061 66	•					Yer	23	.,,,,	21 1*	Mov	6		2	9 0*	July	10		23 61
10 4			76 8	Dec	22	1955	, 1964 6 - 82 7	Oct	79	1965	92 7	Mar lpr	29 5		23 3* 23 3*		13			3 9† 3 8	July Aug	30 12		23 2 22 8
(C 6			76 7	Ma	25	1964	86 6	Yo v	lu		89 7	ipr Va)	30 7		23 2* 23 1*	Dac	17	1965	2	7 6 5 8*	Aug	2 31		22 9
Yay Juaa	17				2		100 8*		1	1966	88 6 87 8	May	11		23 1		9	1703	2	5 8	Oct	4		22 1 21 3
Yay	17	1952	77 6 78 2	Occ Oct	22		92 3*					Hay	23		23 2*	Apr	2			- 24		29		
May Juna Apr Dec Apr	17 6 22 31 22		77 6 78 2 77 8	Oct Nov	22 10		91 1	Mar	1 28		8/3									5 2* 5 1*	Oct Sov			21 2 20 8
May Juan Apr Dec	17 6 22 31 22 14	1952 1953	77 6 78 2	Oc t	22 10 16	1965 <u>6</u>	91 1 89 2		1 78		8 1	Juna uly	3		23 6 23 1*	Apr Apr	10 12		2 2	5 1* 5 6	5ov Jan	30 3	1966	20 8 20 7
May Juan Apr Dec Apr May Dac	17 6 22 31 22 14 9	1952 1953 1934	77 6 78 2 77 8 77 8 79 2	Oct Mov Dec Apt	22 10 16 12,		91 1 89 2 / 08 1	Har Har				Juna uly July	3 3 20	2461	23 6 23 1* 23 2*	Apr Apr Apr	10 12 17		2 2 2	5 1* 5 6 5 2t	5ov Jan Feb	30	1966	20 8 20 7 20 8
May Juan Apr Dec Apr May Dac	17 6 22 31 22 14 9,	1952 1953 1934 seha 1	77 6 78 2 77 8 77 8 79 2 Accurda	Oct Mov Dec Apt	22 10 16 12,	1954 60	91 1 89 2 / 08 1 , 1962 6	Har Har	⁷⁸	1963 4	8 1	Juna uly July Apr Apr	3 20 8 29	1964	23 6 23 1* 23 2* 24 2 24 0*	Apr Apr Apr Juna Juna	10 12 17 5 19		2 2 2 2	5 1* 5 6 5 2t 6 3t	Sov Jan Feb Fab Mar	30 3 2 28 28	1966	20 8 20 7 20 8 ² 0 7 20 7
May Juna Apr Dec Apr May Dac (C 6- Dec Apr	17 6 22 31 22 14 9, -2) 14	1952 1953 1934 seha 1 1954	77 6 78 2 77 8 77 8 79 2 Accurda 8 1 84 9	Oct Nov Dec Apt a alla Mar Dac	22 10 16 12, bta 13 24	1954 60 1959 4	91 1 89 2 08 1 , 1962 66 / 110 2 96 4	Mar Mar S Apr Dac	30 5	1963 4	8 1 	Juna uly July Apr	3 3 20 8	1964	23 6 23 1* 23 2* 24 2 24 0*	Apr Apr Apr Juna	10 12 17 5		2 2 2 2	5 1* 5 6 5 2t 5 3t	Sov Jan Feb Fab	30 3 2 28	1966	20 8 20 7 20 8 20 7
May Juan Apr Dec Apr May Dac (C 6-	17 6 22 31 22 14 9,	1952 1953 1934 Peha 1 1954 1955	77 6 78 2 77 8 77 8 79 2 Accurda 8 L	Oct Nov Dec Apt a alla Mar	22 10 16 12, bta	1954 60	91 1 89 2 / 08 1 , 1962 60 / 110 2 96 4 95 6	Mar Mar S Apr Dac Mar	30 5 25	1963 4	8 1 150 3* 101 3 96 7	Juna uly July Apr Apr	3 20 8 29 31		23 6 23 1* 23 2* 24 2 24 0*	Apr Apr Apr June June July	10 12 17 5 19	1963 6	2 2 2 2 2	5 1* 5 6 5 2t 6 3t	Sov Jan Feb Fab Mar	30 3 2 28 28	1966	20 8 20 7 20 8 ² 0 7 20 7
May Juna Apr Dec Apr May Dac (C 6- Dec Apr Dee Har Jan	17 6 22 31 22 14 9, -2) 14 9 12 22 78 2	1952 1953 1934 seha 1 1954 1955	77 6 78 2 77 8 77 8 79 2 Accurda 8 1 84 9 91 6 89 6 93 8	Oct Mov Dec Apt a alla Mar Dac Har Dec Her	22 10 16 12, 13 24 25 7	1954 60 1959 4	91 1 89 2 08 1 , 1962 66 / 110 2 96 4 95 6 100 8 92 0	Mar Mar Mar Apr Dac Mar Mov Dac	30 5 25 19 16	1964	8 1 150 3* 101 3 96 7 100 1 99 0	Juna uly July Apr Apr Oct fC 6	3 20 8 29 31 2) _7		23 6 23 1* 23 2* 24 2 24 0* 29 7t Racorda	Apr Apr Apr Juna Juna July availa	10 12 17 5 19 1	1963 66 1963	2 2 2 2 2 2 2	5 1* 5 6 5 2t 5 3t 6 t 3 8	Sov Jan Feb Fab Mar Mar	30 3 2 28 28 31	1966	20 8 20 7 20 8 30 7 20 7 20 7
May Juna Apr Dec Apr May Dac (C 6- Dec Apr Dee Har	17 6 22 31 22 14 9 -2) 14 9 12 22 78 2 6	1952 1953 1934 seha 1 1954 1955	77 6 78 2 77 8 77 8 79 2 Accurda 8 1 84 9 91 6 89 6	Oct Hov Dec Apt a alla Mar Dac Mar Dec	22 10 16 12, 13 24 25 7 5	1954 60 1959 4 1960	91 1 89 2 08 1 , 1962 66 110 2 6 4 95 6 100 8	Apr Dac Har Hov Dac Apr	30 5 25 19 16	1964	8 1 1/ 150 3* 101 3 96 7 100 1 99 0	Juna uly July Apr Apr Oct fC 6	3 3 20 8 29 31 2) ~7	iec-2	23 6 23 1* 23 2* 24 2 24 0* 29 7t Racorda	Apr Apr Apr Juna Juna July evaila Apr	10 12 17 5 19 1		2 2 2 2 2 2 2 6	5 1* 5 6 5 2t 5 3t 6 t 3 8	Sov Jan Feb Fab Mar Mar	30 3 2 28 28 28 31	<u>.</u>	20 8 20 7 20 8 20 7 20 7 20 7

Table 5 — Water levels in observation wells in Cedar Valley — Continued

(C 6) 1 dct 2 Curtinued	(C 5 2 Peac 1 Cont nued
July 3 1963 30 * a 16 1965 33 6+ July 10 965 30	
J iy 20 30 5* Fan 13 13 1† J 1y 30 30	
Mar 24 1964 32 9 Feb 1 33 0* Aug 12 10	
Apr 8 31 5 Mar 9 33 1 Aug 25 30 Apr 29 31 3* Apr 2 1 * Aug 1' 29	
Oct 31 36 91 Apr 3 12 6† Oct 4 28	7 Dec 5 6 Aug 12 10 Hay 3 11
Nov 1 36 t Apr 10 3 3 t Oct 29 28	
Nov 6 16 3* Apr 12 12 9 Nov 30 28	
Nov 7 36 21 Apr 17 32 3 Jan 3 1966 7 Nov 15 36 1 June 5 31 bt Fan 2 48	
Nov 14 35 7† June 19 11 3* Fan 28 27	9 Mar 14 1958 0 Nept 19 8 0 Har 9 4 1
Nov 21 35 31 July 1 31 1 Mar 28 28	
Dac 17 14 9 July 1 11 0+ Mar 31 27	
Dec. 26 34 0 [†]	Mar 77 1961 4 Oc 3 8 27 Apr 12 1 7
(C 6 2) 25cbc 1 Records available 1964 66	Mar 3 1962 1 9 Oct 17 8 3† Juna 30 2 6
Dae 17 1964 67 8 Aug 12 1963 68 4 Jan 4 1966 66	
Mar 9 1963 67 9 Aug 31 68 2 Fab 1 68	9 Mar 8 1963 1 8 Oct 20 8 Ot July 30 2 2 9 May 23 1 7 2 Oct 22 7 8 2 Aug 12 2 0
Apr 20 68 7 Oct 4 68 7 Mar 11 68 July 1 68 0 Oct 29 68 7 Mar 30 68	/
July 1 68 0 Oct 29 68 7 Har 30 68 July 30 68 0 Mov 30 68 9	J.usa 10 1 6* Oct 29 7 4* Oct 4 8
00 0 100 30 00 7	
(C 6 7) 26cbo 1 88cords 8v8118ble 1963 66	July 9 1 7 Nov 1 7 2t Nov 30 5
Har 2 1963 - 53 1* Apr 12 1965 56 1 Peo 1 1966 60	
Apr 30 2 02 / 34112 / -/ 02 // 1121	3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Hay 7 60 7* Sapt 13 2/225 7 Mar 28 59 Har 24 1964 58 1 Sapt 16 4/107 2 Mar 29 59	3 Aug 21 2 5 Nov 14 6 2+ Fab 1 6
Apr 29 57 8* 5apr 18 4/ 97 1 Kar 30 59	2 Dec 5 1 1 Nov 21 6 Or Har 27 6
Oct 2 68 3* Sapt 19 4/ 92 4 Mar J	2 Nar 24 1964
0 22 63 6* Sept 20 4/88 4 Apr 1 59 Mc 6 62 0* Oct 4 74 0 Apr 6 59	1 Ang 13 7 2* Dec. 26 4 9t May 1 4
10 21 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Sant 5 2 9t Jan 16 1965 4 6t May 3 7/ 3
Dec I 59 8 Nov 30 a3 9 May 3 5'22	8 Sept 12 8 Jf Fan 11 4 31 Juna 9 3
Ma 9, 1965 58 0 Jan 4 1966 61 5	(C-6 2)29ccc 1 Records available 1965 66
(C 6 2)2 ccs 1 Racords available 1963 66	Sapt 9 1965 + 1 7 Nov 30 1965 + 2 9 Fab 2 1966 + 2 8
May 7 1961 31 2* Aor 29 1964 32 9* July 30 1965 14	
Hay 11 31 2* Oct 2 34 2* Aug 12 14	7
M4y 22 31 3* Oct 10 34 3* Aug 31 34	
Juna 3 31 8 Oct 22 34 4* Oct 4 35	
June 3 31 6 Nov 6 34 3* Occ 29 35 June 15 31 6* Nov 10 34 3 Nov 30 33	The state of the s
June 15 31 6* Nov 10 34 3 Nov 30 33 July 3 31 8* Dac 17 34 6 Jan 4 33	2 Dac 9 1954 15 L Dae 4 9 L Aug 31 8 6
July 9 30 4 Max 9 1965 14 1 Feb 2 33	
July 20 32 1* Apr 12 34 0 Mar 1 34	
A g 21 12 5 Apr 15 33 9 Apr 7 34 Har 24 1964 33 2 July 1 33 9	6 Mar 28 1956 13 6 Joly 9 10 0 Nov 10 9 8 pac 13 12 6 Aug 21 8 7 Jan 1 1966 10 3
Hai 24 1704 33 2 July 1 33 7	
(C 6-2) 27cce 1 Records aval lable 1966	— Nar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4
	Var 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Apr 13 1959 11 4 Mar 24 1964 7 9 Feb 28 10 2 10 2 2 3 10 2 3 4 3 4 3 4 3 4 3 4 3 4 3 </td
Mar 31 1966 27 7 Apr 6 1966 - 27 9 May 3 1966 14	■ Nar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Apr 1J 1959 11 4 Mar 24 1964 7 9 Feb 28 10 2 1 Dec 24 12 J Mo 9 J 0 Apr 7 10 6
	■ Nar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Apr 1J 1959 11 4 Mar 24 1964 7 9 Feb 28 10 2 1 Dec 24 12 J Mo 9 J 0 Apr 7 10 6
Mar 31 1966 27 7 Apr 6 1966 - 27 9 May 3 1966 14 Apr 1 27 9 Ap 7 27 9 Jura 9 39	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Mar 24 1964 7 9 Feb 28 10 2 Mar 24 1964 7 9 Feb 28 10 2 Mar 25 1960 12 6 Dec 17 5 1 May 3 11 1 Mar 2 9, 1965 6 4 Mar 3 11 1 Mar 9, 1965 6 4 Mar 3 1 1 1 Mar 9, 1965 6 4 Mar 3 1 1 1 Mar 9, 1965 6 4 Mar 3 1 1 1 Mar 9, 1965 6 4 Mar 3 1 1 1 1 Mar 9, 1965 6 4 Mar 3 1 1 1 1 Mar 3 1 1 1 1 Mar 3 1 1 1 1 Mar 3 1 1 1 Mar 3 1 1 1 1 Mar 3 1 1 1 1 Mar 3 1 1 1 1 Mar 3 1 1 1 Mar 3 1 1 1 Mar 3 1 1 1
Mar 31 1966 27 7 Apr 6 1966 - 27 9 May 3 1966 14	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Mar 24 1964 7 9 Feb 28 10 2 Mar 24 1964 7 9 Feb 28 10 2 Mar 24 1964 7 9 Feb 28 10 2 Mar 25 1960 12 6 Dec 17 5 1 May 3 11 1 Mar 25 1960 12 6 Dec 17 5 1 May 3 11 1 Mar 27 1965 6 4 Mar 27 1960 12 6 Dec 17 5 1 May 3 11 1 Mar 28 1963 6 6 Mar 28 1963 6 Mar 28 1963 6 6 Mar 28 1963 6 6 Mar 28 1963 6 6 Mar 28 1963 6 6 Mar 28 1963 6 6 Mar 28 1963 6 Mar 2
Mar 31 1966 27 7 Apr 6 1966 - 27 9 May 3 1966 14 Apr 1 27 9 Ap 7 27 9 Jura 9 39 (C 6 2) 2/erc ? Racords avallable 1966	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Apr 13 1959 11 4 Mar 24 1964 7 9 Feb 28 10 2 1
Mar 31 1966 27 7 Apr 6 1966 - 27 9 May 3 1966 14 Apr 1 27 9 Apr 7 27 9 Jura 9 39 (C 6 2) 2 / etc ° Racord# avallable 1966 Har 31 1966 25 2 Apr 6 1966 25 1 Hay 1 1966 24 Apr 1 25 1 Apr 7 25 1 uuna 9 24	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Apr 11 1959 11 4 Mar 24 1964 7 9 Feb 28 10 2 Dac 24 12 3 Mo 9 3 0 Apr 7 10 6 Dac 7 11 3 Mar 9, 1965 6 4 Dac 7 11 3 Mar 9, 1965 6 4 G (C 6 2) 345ac 1 Recurde evailable 1963 66 Mav 7 1963 28 4* Mar 24 1964 29 9 Jul 30 1965 31 5 May 11 28 4* Apr 29 79 6* Aug 12 31 8
Mar 31 1966 27 7 Apr 6 1966 - 27 9 May 3 1966 14 Apr 1 27 9 Apr 7 - 27 9 Jura 9 39 (C 6 2) 2 recc 2 Records avallable 1966 Har 31 1966 25 2 Apr 6 1966 25 1 May 1 1966 24 Apr 1 25 1 Apr 7 25 1 uuna 9 24 (C-6-2) 28bee 1 Records avallable 1963	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Apr 11 1959 11 4 Mar 24 1964 7 9 Feb 28 10 2 1
Har 31 1966 27 7 Apr 6 1966 -27 9 May 3 1966 14	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4
Mar 31 1966 27 7 Apr 6 1966 - 27 9 May 3 1966 14 Apr 1 27 9 Apr 7 - 27 9 Jura 9 39 (C 6 2) 2 recc 2 Records avallable 1966 Har 31 1966 25 2 Apr 6 1966 25 1 May 1 1966 24 Apr 1 25 1 Apr 7 25 1 uuna 9 24 (C-6-2) 28bee 1 Records avallable 1963	Mar 14 1958
Har 31 1966 27 7 Apr 6 1966 -27 9 May 3 1966 14 Apr 1 27 9 Ap 7 27 9 Jura 9 39 39	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4
Mar 31 1966 27 7 Apr 6 1966 -27 9 Kay 3 1966 14 Apr 1 27 9 Apr 7 7 27 9 Jura 9 39 39 (C 6 2) Zietc ? Racorda avallable 1966 Har 3 1966 25 2 Apr 6 1966 25 1 May 1 1965 24 Apr 1 25 1 Apr 7 25 1 uana 9 24 (C-6-2) 28bee 1 Records avallabla 1963 66 8 20 4 Aug 12 1965 19 May 13 1963 -19 7* Apr 29 1964 -20 3* Aug 12 1965 19 Hay 13 1963 -197* Nov 6 20 3* Aug 12 1965 19 June <th< td=""><td> Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 </td></th<>	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4
Har 31 1966 27 7 Apr 6 1966 -27 9 Hay 3 1966 14	Mar 14 1958
Mar 31 1966 27 7 Apr 6 1966 -27 9 Kay 3 1966 14 Apr 1 27 9 Apr 7 7 27 9 Jura 9 39 39 (C 6 2) Zietc ? Racorda avallable 1966 Har 3 1966 25 2 Apr 6 1966 25 1 May 1 1965 24 Apr 1 25 1 Apr 7 25 1 uana 9 24 (C-6-2) 28bee 1 Records avallabla 1963 66 8 20 4 Aug 12 1965 19 May 13 1963 -19 7* Apr 29 1964 -20 3* Aug 12 1965 19 Hay 13 1963 -197* Nov 6 20 3* Aug 12 1965 19 June <th< td=""><td> Mar 14 1958</td></th<>	Mar 14 1958
Mar	Mar 14 1958
Mar 31 1966 27 7 Apr 6 1966 -27 9 May 3 1966 14 Apr 1 27 9 Apr 7 7 27 9 Jura 9 39 (C 6 2) Z verc ? Racords available 1966 25 1 May 1 1966 25 2 Apr 6 1966 25 1 May 1 1965 24 Apr 1 1968 25 1 Apr 7 25 1 May 1 1966 24 Apr 1 1963 Apr 7 25 1 May 1 1965 24 May 11 1963 -197 Apr 29 1964 -20 3 Aug 12 1965 19 May 13 197 Nov 6 20 24 Aug 31 1965 19	Mar 14 1958
Har 31 1966	Mar 14 1958
Har 31 1966 27 7 Apr 6 1966 -27 9 May 3 1966 14 Apr 1 27 9 Ap 7 27 9 Jura 9 39 39	Mar 14 1958
Har 31 1966 27 7 Apr 6 1966 -27 9 Kay 3 1966 14 Apr 1 27 9 Ap 7 27 9 Jura 9 39 39	Mar 14 1958
Har 31 1966	Mar 14 1958
Har 31 1966	Mar 14 1958
Mar	Mar 14 1958
Har 31 1966	Mar 14 1958
Mar	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4 Apr 13 1959 11 4 Mar 24 1964 7 9 Feb 28 10 2 Dac 24 12 3 Mo 9 3 0 Apr 7 10 6 Dac 7 11 3 Mar 9 1965 64 G(C 6 2) 345ac
Mar	Mar 14 1958
Har 31 1966	Mar 14 1958
Mar	Mar 14 1958
Mar	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4
Mar	Mar 14 1958
Mar	Mar 14 1958
Mar	Mar 14 1958 11 8 Dec 5 6 9 Feb 2 10 4

^{1/} Mater le ele deul ing altor complatin it drilling and fluin ng of-wrvatin well.

2/ Mater to aliption to flual givall fidatargant ell in

1/ Mater laval daclining altar fluoling fluorvation wull.

4/ Mall race tluy pumped.

5/ Mall was buing jumped.

6/ Mall was buing jumped.

6/ Marry vall was baing pinped.

6/ Marry vall was baing pinped.

6/ Marry flwing we in with in for 30 ninutos.

Table 6 — Selected drillers' logs of wells in Cedar Valley

(Sirveyed altit de flato su fa c'at the el 1965 Geological Si ey are given in feet not ently a to ide interpolated from pographic map are given in feet 1

Thick e s Gi an i feet Dapth Ci on in feat helow land s reace

	Thickne	Je tp		*hickness	Deati		Thicaress	Depti
(C 5 2) 31 dcd 1 Lig 1 y E W			(C 6-2)15ahh Log by Robinson			(C n 7) loabh 1 Cuit Inued	3	960
hale Al > 181 4 1	15	15	Prilling Co Alt 4 864 9 ft Clay yell w	42	42	Sand and fine gravel 1/2 lnuh	-	
Boulde s Clay and sand	50	65	Clay blue	11	51	gravel	15	1 955
Boulders	2	67	Clay /all w	29	82	Sand and gravel 3/1-Inch	10	1 965
Clay	9	76	Cravel lry	4 31	86 117	graval Sand and gravel 1 inch grava	35	2 000
Ooulear	2 17	78 94	Clay yallıu Sand f ıa making water	31	121	Sand nard	5	2 00 5
C ay Hardpan	1,	96	Clay and gravel sandy yellow	6	127	Sand and gravel nc's gravel	20	2 025
Clay and sand	22	118	sand fine	10	137	Bentunite	5	2 030
Boulders	3	121	hand and gravel	9 56	146 202	Sand and graval Clay sand and gra el nixed	ś	2 040
Clay	3 2	124 126	Clay yall-u Clay sandy yellow	22	224	3a vl and Arave T	2	2 04 2
Boulders Clay	10	136	Clay sand and gravel	20	244	Cra el clay and sand	3	2 045
Souldacs	1	137	Clay yel' w and t na graval	28	272 282	Clas olse and and shells Clay bloom	5 6	2 056
Clay and sand	27	164	Llay sticky Clay sandv	10 6	288	Sand hard	4	2 060
Soulders Clay	2 26	166 191	Clay sctcav	ž	291	Shale bl a hacd and sticky	5	2 06
Boulders	ì	193	Clay and fina gravel	3	29/	Sand hard and gravel Shale blue hard and streky	5 5	2 070
Clay	26	2 9	Cla sticky		29 300	Shale blue hard and streky	,	2 07
Clay and sand	31	250	Clay and fine graval Clay sticky ligh brown	,	308	shell	13	2 090
Boulders	24	252 276	Clay sardy light prown	28	336	Linas one gray hard and		
Clay Bo lders	2	278	Clay and gravel	11	34	eharp	18	2 128
Clay	16	29/	Clay sticky ligh roun	4	351	Sand hard and starp	8 3	2 136
Souldars	2	296	Gravel	9	160 160	Lime grav hald pand and	9	2 48
Cla/	4	100	Clay sticky light brown Clay sardy light brown	5 1	402	Line gra is d	53	2 20
Sand and graval water	25	32	Sand and tubb ea	4	406	L rant ne d (ferent t lors		
(C 6 1) 18dca 1 Log by L E		i	C'a, andy light brown	5	411	extra nard	3	2 204
Hala Alt 4 887 9 1			Sand and c hbles hard	2	413	Limeatone hard trown	3 12	2 207
Sand and CLAY	70	70	Clay s leky light brown	2 1 4	442	Limas ne "rav Limestone "ray astra hard and	12	2 215
Clay with gravel	159 5	229	Clay white sandy Clay sloky light brown	54	300	sharp	36	2 25 5
Craval Clay	4	238	Clay val uw	34	ء14	Shale gray with lime shells	18	2 27
Sand	5	243	Clay tus	4	338	Linesi ne cray hard	18	2 291
Clay	7	250	Clay yell w	22	360	facit fractured zone gray limestone	18	2 309
Quicksand	2	252	Gravel and clay	3 15	565 38il	Gravel 3/4 inch diancter	t	2 310
Crave	12	264	Clay velLow Craval and clay	10	590	Fault rone limest ne	5	7 315
(C 6-2) 13cma l Log by Robinso		i	Clay vellow	12	602	Lime gray	31	2 366
Drilling Co Alt A 856 6		1	Gravel and clay	4	606			
Silt	2	2	Clay vellow	29	635	(C 6 2)17dcc 1 Log by J S Lae and Sons Alt 4 911 6 ft		
Clay and hatdpan	2	.4	Sand hard	4 19	643	Tup soil	,	2
Clay blue	41	45 95	Clay yellow Clay blue	4	666	Clay	3	•
Clay yellow	50 10	105	Clay yellow	109	2 5	Craval	3	10
Ciay and sand Clay yeliav	40	145	Clay yel ow with some line			Clay	50	60
C'ay gray	3	148	gravel	40	817	Sand surface water	5 82	6: [+]
Clay and gravel small anoun	_	1	Clay yellow	15 8	830 833	Clay Sand and gravel	4	155
ef vater	2 10	150 160	Clay and gravel Clay brown	35	871	Clay and gravel	20	175
Clay gray Clay yellow	30	190	Sand hard brown	12	885	Clav	35	210
Clay blue	15	205	Clay stice; ya low	32	917	Clay and gravel	15 10	22 2
Clay yelluw	47	252	Clay sciegy blus	69 10	986 996	Sand and gravel Cravel camancad	11	246
Sand	16 82	268 350	G aval and sand I theh aravel Clay yellow	49	1 045	Clay	39	28
Clay and sand Clay and sand hard and so	02	,,,, l	Clay vallow sandy	30	1 075	Cravel cemanted	10	29
streaks	45	395	Clay blue	27	1 102	Clay	20 30	3 1
Clay and sand	40	435	Clay yellow	13 32	1 115	stir Cravel	31	176
C'ay and gravel nixed	S 82	443 525	Clay sticky brown Sand brown and stands up	23	1 465	Clay	34	410
Clay and sand	02	~ 1	Clay brown and white	5	1 470	Clay and gravel	5	41
(C 6-2) 14eba 1 log by Roncoa		- 1	Clay white and red	>	1 475	Congl meracc	10 7	42
Hoss Drilling C Alt		1	Clay sandy vellow	10	1 485	Cravel Clay and gravel	13	43:
4 865 7 tt			Clay s leay brown	230	1 715	Cravel	16	46
Soil	4	70	Clay brown and gravel mixed 1/4 inch prayol	10	1 725	Conglumerace	19	48
Clay gray Clay brown sandy	66 47	217	Clay brown	10	1 735	Cravel and b ulders	12	49
Clay brown	508	725	Clay brown and ('ne bravel			Llar	29	52
Sand gravel and ulay	13	738	wited 1/4-inch graval	10	1 74 >	Cungl Merate Clay	64 15	58 60
Clay gray hard sandy	17	753	Clay briwn Clay sandy trown	20 10	1 765	- C1-y		-
Clay bram soft Clay bram hard sandy	29 6	784 790	Clay brown	35	1 810	(C b 2)26cbb 1 Lng hy Robinaun		
Clay bram soft streaks of	•		Clay sciky Irwn	15	1 82>	Drillns, Lo Ale 6 844 1 f	10	_
aand	20	810	Clay sandy Iryun	15	1 0/40	Clas scay Clas vella	30 25	31
Clay blue soft	15	825	Clay from mixed ulth Tina graval 1/8 inch grovel	30	1 870	Llay ray	13	6
Clay brown bord or du	15 20	640 860	Clay Irwn with streaks	,,	1 0.3	Sand and gravel smal am ert of		
Clay brown hard sa dy Clay brown xtraak / sa i	20	387	line traval 1/2 nch gravel	10	l dd0	water	2	7
Clay light luc	15	902	Sand and thuo P aval with a man			Clay pro	10 30	8
Clay Reay screaks t sand	aı	1 001	hrwn clas wLxed	25 9	1 نار <u>1</u> زار إ	Lia, veil # Cla, and sard	15	11
	102	1 103	Sand haid	-		Clay vell W	35	16
Clay nrnwn soft			tend and live usame!	17				
C'ay nrown soft Sand and gravel straako of	_	, , , , ,	Sand and lima gravel Sand and cravel 1/7 nuit	12	1 925	Clay hi a	15	
Clay nrnwn soft Sand and gravel straakn of tlay	50	1 155	Sand and lima gravel Sand and gravel 1/7 nult gravel	5	1 930	Clay hia Clay yalim	35	17 210
C'ay nrown soft Sand and gravel straako of	_	1 155 1 226	Sand and gravel 1/7 nult			Clay his Clay yallow Clay time and sand		

Table 6 — Selected drillers' logs of wells in Cedar Valley — Continued

	Thickness	0eprn		Thickness	Depeb		Thickness	Dapth
(C 6-2)26cbb Continued			(C 6 2)29cac 2 Continued			(C A 2)32bod L Concinued		
Clay blie and sand	17	272	Clay	41	208	Conglonerate	13	445
Sand	6	278	Cravel black 1/4 to 1 inch	10	218	Clay brown	7	452
Clay bie and sand	27	105	Hardpan	2	220	Gravel	11	463
Clay vellnw	د2	330	Quicksand			Clay and gravel	22	485
Gravel	3	335	•			Conglone rara	2	487
Clay yellow	35	370				Clay brown	1	490
Sand hard	10	380	(C 6 2)32bbd l Log by J s Lac			Conglomerare	16	506
Graves	22	402	and Sons Alt 4 880 ft			Clay	4	310
Clay hi a	8	410	Clay brown	60	60	Congionerate	23	535
Clay yellow	10	420	Sand	1	61	Clay and gravel	13	548
Clay yallow and sand	18	438	Clay brown	62	123	Conglonerate	4	552
Sand hard	20	478	Clay and gravel	7	130	Cravel	7	359
C ay yallow	7	485	Clay brown	3	203	Con glone rata	16	575
Clay yal ow and send	15	300	Craval	3	208	Clay sand and gravel	11	586
Clay yellnv	5	505	Clay sand and gravel	45	253	Cravel	9	595
		1	Congloserata	7	260	Clay and gravel	t0	605
		- 1	Clay sand and gravel	37	297	Clay yeltow	3	613
(C 6 2329eac 2 Log by L M		- 1	Cravel	2	299			
Helncac Alt 4 888 7 ft		ì	Clay and gravel	31	330	(C 7 2) 23bec L Log by J P		
Clay and hardpan layers	110	110	Cravel	3	333	Felghry Alt 4 833 ft		
Gravel black 1/4 to 1 inch	6	116	Clay and gravel	21	354	Clay	180	166
Clay	44	160	Conglomerace	10	364	Clay soft with water	15	193
Hardpan on sandstons	1	161	Clay and gravel	68	432	Clay	23	220

Table 7. — Logs of test wells in Cedar Valley

(Logs by U.S. Geological Survey Surveyed altitudas of land xur ace at the Pell by U.S. Ceological Survey are given in feet and tenths. altitudes interpolated from topographic saps are given in feet.)

Thickness Given in fact
Depth Given in feat balaw land aurface

	Thickness	Depth		Th Loanses	Depti
(C 5 1120dde 1 Alt 4 795 fc			(C 6 25 lace 1 - Concluded		
Recent and P slatocana daposica			Racent and Pleistocene dapoalts Continued		
sand vary fina to vary coarse and vary clas gravel slity			Silt and very fine to madium sand tan	14	49
Gravel is tubrounded to rounded Composed ut saddmentary			Sand vary fine to madlus sllry tas	,	56
and amaous rocks	12	12	Silt clayey and sandy can	7	63
Cravel vary fine to vary coarse and small cnhôles angular	. 14	12	Silt and vary fine to medium sand brown Conrains fine		• • •
o rounded Composed of sadtmentary and Immaous rocks			gravel angular to rounded composed of quartzite and lisa		
Slight caving	2	14	stone from 70 to 71 feat	10	73
S it brown and light gray sandy and clayev Contains some		1~	Silt and clay brown	13	86
very fire to nedlus gravel angular to subrounded Com-			Silt nd ary fine to coarse sand light brown to brown	12	98
posed ot sedimencary and ignaous rocks	29	43	Silt and clay brown	à	106
Craval very fine to very coarse and scull cobbles angular		4,	Silt and vary fine to maditel sand brown alightly clayay	9	113
to rounded Composed of sedimencary and Ignaous rocks			Slit end clay brown	á	119
interval concains brown sandy silt match ron 43 to 38			Silt and ery ine to mediam mand brown Contains vary	•	117
feat and yallow 6rova clayer silt Iron 38 to 60 feat Load			tine to neditm gravel angular to subrounded composed of		
erroulation backman 45 and 55 fast	17	60	guarcalce and Ilmeatone from 131 to 132 feet Slightly		
Cobbles ameli and coarse gravel soutly quarcalts but some		90		22	
limations and ignature rocks Slight lose of eleculation	10		clayey from 132 to 133 feet	22	141
	to	70	Silt and clay brown	3	144
Manning Canyon Shale of Pennsylvanian and Mississippian age			Cravel fine to coarse angular to subrounded composed of		
Claystona gray gray brawn and olive and gray allty clay	21	91	quarculce and linestone Contains brown allt	4	148
Shala ruat-brown fisalle Loat circulacium while			Silt brown clayey and oceanionally sandy	54	202
drilling	5	96	Sand very fine to madium Silty from 202 to 208 feet	11	213
Claystona gray to dara gray gray brown oliva and black			Silt brown clayey Sandy from 220 to 222 feet	18	231
and gray to gray brown sand clay	46	142	Sand very fine to coarse illty	.7	238
Clay and elaystons dara gray to back Formation changed			Silt brown clayey	12	250
color o(drilling and from brown to black	63	205	Sand vary ina to andiam silty	3	255
Shale black	95	300	Silt brown clayey	10	265
			Send very fine to andlum milty	2	267
(C 3 2) 24aab-1 Alt 4 989 7 ft			Silt brown clayey from 273 to 288 feet end mendy from 288		
Recent and Pleistocene deposits			to 291 feat	33	300
Silt brown and tan sandy and clayey	39	39			
Sand varg fina to very coarse and very fina to coarse			(C 8 2) 27ecc 1 Alt 4 843 2 ft		
gravel Craval is angular to rounded and ecoposed of sedi			Recent and Ploiatocetma deposits		
mantary and ignaous rocks Lose circulation while drilling	4	43	Clay light gray silty	31	51
Silc brown clayey and sandy	7	30	Clay dark gray to blue gray allty	39	90
Craval very fine to very coarse angular on rounded Con			Silt light grey end light to dark brown amndy and clayey	33	125
posed of audlneocary and Ignaoua rocks	2	52	Clay gray ailty	23	148
Silt brown sandy and clayey as a autrix is vary fina to			Silt brown sandy and clayey Color grades to gray-brown		
commam graval Incarval to about 50 percent atlt and 50			ac 163 to 170 feat	32	155
percent gravel Gravel la angular to aubcoundad and com-			Clav gray allty Contains thin lass than I foot bade of		
posed of sadlmentary and ignaous rocks	8	60	white clay	41	226
Ignaous rock of Tertiary age Probably lower Tertiary ande			Silt tan and brown sandy and clayey	38	264
alte-cracnyce lacica flows (Stokes 1963)	87	147	Sand very fina to madica alley	8	272
Linestone of Paleocolc age Probably Dquirth Formatlum of			Silt tem and brown sandy and clayey loterbadded with 2 to		
Permian and Pannsylvanian age	8	155	6 foot beds of milty sand	40	312
	-	•	Sand very floe to medium silty	10	322
(C 6 2) Lace 1 Ale 4 891 3 fr			Silt gray agody and clayey Contains 2 to 6 foot thick		- • •
Recant end Pialscomma depomita			beds of allty sand	86	408
Silt and clay tem and light gray	8	8	Silc gray brown sandy and clayay Contains 2 to 10 foot		
Silt and vary fine to ordine sand tan and gray	14	22	thick beds of stity sand	36	464
Silt and clay tan and iighi gray	13	15	Silc gray and blue gray sandy and clayey	41	505
			Sive Brat and order Brat aming Elle Crayes	-1	,,,,

PUBLICATIONS OF THE UTAH STATE ENGINEER'S OFFICE

(*) - Out of Print

TECHNICAL PUBLICATIONS

- No 1 Underground leakage from artesian wells in the Flowell area, near Fillmore, Utah, by Penn Livingston and G B Maxey, US Geological Survey, 1944
- No 2 The Ogden Valley artesian reservoir, Weber County, Utah, by H E Thomas, US Geological Survey, 1945
- *No 3 Ground water m Pavant Valley, Millard County, Utah, by P E Dennis, G B Maxey, and H E Thomas, U S Geological Survey, 1946
- *No 4 Ground water m Tooele Valley, Tooele County, Utah, by H E Thomas, U S Geological Survey, m Utah State Eng 25th Bienn Rept, p 91-238, pls 1-6, 1946
- *No 5 Ground water in the East Shore area, Utah Part I, Bountiful District, Davis County, Utah by H E Thomas and W B Nelson U S Geological Survey, in Utah State Eng 26th Brenn Rept, p 53-206, pls 1-2, 1948
- *No 6 Ground water in the Escalante Valley, Beaver Iron, and Washington Counties, Utah, by P F Fix, W B Nelson, B E Lofgren, and R G Butler, U S Geological Survey, in Utah State Eng 27th Bienn Rept, p 107-210, pls 1-10, 1950
- No 7 Status of development of selected ground-water basins m Utah, by H E Thomas, W B Nelson, B E Lofgren, and R G Butler, U S Geological Survey, 1952
- *No 8 Consumptive use of water and ungation requirements of crops in Utah, by C O Roskelly and Wayne D Criddle, 1952
- No 8 (Revised) Consumptive use and water requirements for Utah, by W. D. Criddle, K. Harris, and L. S. Willardson, 1962
- No 9 Progress report on selected ground water basins in Utah, by H A Waite, W B Nelson, and others, U S Geological Survey, 1954
- No 10 A compilation of chemical quality data for ground and surface waters in Utah, by J G Connor, C G Mitchell, and others, U S Geological Survey, 1958
- No 11 Ground water in northern Utah Valley, Utah A progress report for the period 1948-1963, by R M Cordova and Seymour Subitzky, US Geological Survey, 1965
- No 12 Reevaluation of the ground-water resources of Tooele Valley, Utah, by Joseph S Gates, U S Geological Survey, 1965
- No 13 Ground-water resources of selected basins m southwestern Utah, by G W Sandberg, US Geological Survey, 1966
- No 14 Water-resources appraisal of the Snake Valley area, Utah and Nevada, by J W Hood and F E Rush, U S Geological Survey, 1966

No 15 Water from bedrock in the Colorado Plateau of Utah, by R. D. Feltis, U.S. Geological Survey, 1966

WATER CIRCULAR

No 1 Ground water in the Jordan Valley, Salt Lake County, Utah, by Ted Arnow, U S Geological Survey, 1965


BASIC-DATA REPORTS


- No 1 Records and water-level measurements of selected wells and chemical analyses of ground water, East Shore area, Davis, Weber, and Box Elder Counties, Utah, by R E Smith, US Geological Survey, 1961
- No 2 Records of selected wells and springs, selected drillers' logs of wells, and chemical analyses of ground and surface waters, northern Utah Valley, Utah County, Utah, by Seymour Subitzky, U S Geological Survey, 1962
- No 3 Ground-water data, central Sevier Valley, parts of Sanpete, Sevier, and Piute Counties, Utah, by C H Carpenter and R A Young, U S Geological Survey, 1963
- No 4 Selected hydrologic data, Jordan Valley, Salt Lake County, Utah, by I W Marine and Don Price, US Geological Survey, 1963
- No 5 Selected hydrologic data, Pavant Valley, Millard County, Utah, by R W Mower, U S Geological Survey, 1963
- * No 6 Ground-water data, parts of Washington, Iron, Beaver, and Millard Counties, Utah, by G W Sandberg, US Geological Survey, 1963
- No 7 Selected hydrologic data, Tooele Valley, Tooele County, Utah, by J S Gates, U S Geological Survey, 1963
- No 8 Selected hydrologic data, upper Sevier River basin, Utah, by C H Carpenter, G B Robinson, Jr, and L J Bjorklund, U S Geological Survey, 1964
- No 9. Ground-water data, Sevier Desert, Utah, by R W Mower and R D Feltis, US Geological Survey, 1964
- No 10 Quahty of surface water in the Sevier Lake basin, Utah, by D C Hahl and R E Cabell, US Geological Survey, 1965
- No 11 Hydrologic and climatologic data, collected through 1964, Salt Lake County, Utah, by W V Iorns, R W Mower, and C A Horr, US Geological Survey, 1966
- No 12 Hydrologic and climatologic data, 1965, Salt Lake County, Utah, by W V Iorns, R W Mower, and C A Horr, U S Geological Survey, 1966
- No 13 Hydrologic and climatologic data, 1966, Salt Lake County, Utah, by A G Hely, R W. Mower, and C A Horr, US Geological Survey, 1967.

INFORMATION BULLETINS

- *No 1 Plan of work for the Sevier River Basm (Sec. 6, P.L. 566), United States Department of Agriculture, 1960
- No 2 Water production from oil wells in Utah, by Jerry Tuttle, Utah State Engineer's Office, 1960

- No 3 Ground water areas and well logs, central Sevier Valley, Utah, by R. A. Young, United States Geological Survey, 1960
- *No 4 Ground water investigations in Utah in 1960 and reports published by the Umted States Geological Survey of the Utah State Engineer prior to 1960, by H D Goode, Umted States Geological Survey, 1960
- No 5 Developing ground water in the central Sevier Valley, Utah, by R A Young and C H Carpenter, United States Geological Survey, 1961
- *No 6 Work outline and report outline for Sevier River basm survey, (Sec 6, PL 566), Umted States Department of Agriculture, 1961
- No 7 Relation of the deep and shallow artesian aquifers near Lynndyl, Utah, by R W Mower, United States Geological Survey, 1961
- No 8 Projected 1975 municipal water use requirements, Davis County, Utah, by Utah State Engineer's Office, 1962
- No 9 Projected 1975 inunicipal water use requirements, Weber County, Utah, by Utah State Engineer's Office, 1962
- No 10 Effects on the shallow artesian aqinfer of withdrawing water from the deep artesian aquifer near Sugarville, Millard County, Utah, by R W Mower, Umted States Geological Survey, 1963
- No 11 Amendments to plan of work and work outline for the Sevier River basm (Sec 6, P L 566), United States Department of Agriculture, 1964
- No 12 Test drilling in the upper Sevier River drainage basin, Garfield and Piute Counties, Utah, by R D Feltis and G B Robinson, Jr, United States Geological Survey, 1963
- No 13 Water requirements of lower Jordan River, Utah, by Karl Harris, Irrigation Engineer, Agricultural Research Service, Phoenix, Arizona, prepared under informal cooperation approved by Mr William W Donnan, Chief, Southwest Branch (Riverside, California) Soil and Water Conservation Research Division, Agricultural Research Service, USDA and by Wayne D Criddle, State Engineer, State of Utah, Salt Lake City, Utah, 1964
- *No 14 Consumptive use of water by native vegetation and irrigated crops m the Virgin River area of Utah, by Wayne D Criddle, Jay M Bagley, R Keith Higginson, and David W Hendricks, through cooperation of Utah Agricultural Experiment Station, Agricultural Research Service, Soil and Water Conservation Branch, Western Soil and Water Management Section, Utah Water and Power Board, and Utah State Engmeer, Salt Lake City, Utah, 1964
- No 15 Ground-water conditions and related water administration problems in Cedar City Valley, Iron County, Utah, February, 1966, by Jack A Barnett and Francis T Mayo, Utah State Engineer's Office
- No 16 Summary of water well drilling activities in Utah, 1960 through 1965, compiled by Utah State Engineer's Office, 1966
- No 17 Bibliography of U S Geological Survey Water Resources Reports for Utah, compiled by Ohve A Kellei, U S Geological Survey, 1966







APPENDIX J

HAND DELIVERED

JAN 0 4 2011

SW177

UTAH DIVISION OF SOLID & HAZARDOUS WASTE

2011.00013



IRREVOCABLE STANDBY LETTER OF CREDIT NO DATE December 10, 2010 **EXPIRATION DATE December 10, 2011** CORPORATION NAME Cedar Valley Landfill, LC FACILITY NAME Cedar Valley Landfill FACILITY PERMIT NO 0012R1

Executive Secretary Solid and Hazardous Waste Control Board of the State of Utah PO Box 144880 Salt Lake City, Utah 84114-4880

We hereby issue our IRREVOCABLE STANDBY LETTER OF CREDIT No your favor on behalf of Cedar Valley Landfill hereinafter known as the Company, for a sum of One Hundred Five Thousand dollars and no/100's U S dollars \$105,000 00, available by your drafts at sight drawn on our institutionCentral Bank Drafts must be marked "Drawn under 125113803, IRREVOCABLE STANDBY LETTER OF CREDIT No l" dated todav's date This IRREVOCABLE STANDBY LETTER OF CREDIT is issued to provide financial assurance to the Executive Secretary of the Solid and Hazardous Waste Control Board for the cost of closure, post-closure maintenance and monitoring, and if necessary, corrective action pursuant to Utah Code Annotated 19-6-108(9)(c) and Utah Administrative Code (UAC) R315-309-7, for the solid waste disposal facility known as

Cedar Valley Landfill LC located at Fairfield Utah

Requests to draw on this IRREVOCABLE STANDBY LETTER OF CREDIT must be accompanied by the following documents

- 1 Your signed statement as follows I, (Executive Secretary), certify that t have issued a Notice of Violation or other order to the Company indicating that the Company has failed to comply with the closure, post-closure maintenance and monitoring, or corrective action requirements of UAC R315-301 through 320
- 2 A copy of the Notice of Violation or other order issued to the Company by the Executive Secretary,
- 3 Your signed statement as follows I, (Executive Secretary), certify that the Company has failed

provide the Executive Secretary with an extension of Letter of Credit No with an acceptable replacement irrevocable standby letter of credit or other acceptable financial assurance within the 90 days of receipt of the expiration or cancellation notice by the issuing institution

and

Provo-Downtown 75 N University 375-1000 Provo-Riverside 1300 N State

375-5963

373-3336 Orem 415 N State

224-1420

Provo-Mortgage Loan

95 N University Ave

Springville 202 S Main 489-9466

Mapleton 385 N Main 489-5640

American Fork 175 E Main 756-9900

Spanish Fork IN Main 798-7481

Lehi 475 E Main 766-3886

Payson 182 N Main 465-9276

4 Your sight draft, bearing reference to this IRREVOCABLE STANDBY LETTER OF CREDIT No Partial drawings are permitted. This original IRREVOCABLE STANDBY LETTER OF CREDIT No must be submitted to us together with any drawings hereunder for our endorsement of any payments effected by us and/or cancellation. This IRREVOCABLE STANDBY LETTER OF CREDIT is effective as of 12/10/2010 and shall expire on 12/10/2011, but such expiration date shall be automatically extended for a penod of at least one year on 12/10/2011 and on each successive expiration date, unless the issuing institution has cancelled the IRREVOCABLE STANDBY LETTER OF CREDIT by sending notice of cancellation by certified mail to the Executive Secretary and the company 120 days in advance of cancellation.

In the event the Executive Secretary is so notified, any unused portion of the credit shall be available upon presentation of a sight draft for 120 days after the date of receipt by both the Executive Secretary and Cedar Valley Landfill as shown on the signed return receipts Whenever this IRREVOCABLE STANDBY LETTER OF CREDIT is drawn on under and in compliance with the terms of this credit, we shall duly honor such draft upon presentation to us, [insert, [we shall deposit the amount of the draft directly into a STANDBY TRUST of the [insert, owner's or operator's name]] or [we shall provide for partial drawings to third parties]] in accordance with the Executive

Secretary's instructions

The ISSUING INSTITUTION further warrants that this IRREVOCABLE STANDBY LETTER OF CREDIT conforms in all respects with the requirements Utah Administrative Code R315-309, as applicable and as such regulations were constituted on the date shown immediately below. It is agreed that any provision of this IRREVOCABLE STANDBY LETTER OF CREDIT that is inconsistent with such regulations is hereby amended to eliminate such inconsistency.

Type Name of Authorized Representative

Signature Institution Jared V Peterson

Assistant Manager, 175 East Main Street, American Fork UT 84003

This IRREVOCABLE STANDBY LETTER OF CREDIT No most recent edition of the Uniform Customs and Practice for Documentary Credits, published and copyrighted by the International Chamber of Commerce," or "the Uniform Commercial Code"


Cedar Valley Landfill 21,05 Acre Phase Closure Bond

lte <i>m</i>	Quantity	Unit	Unit Cost	Total Cost
2-foot Cap				
Soil (located on site)	67921 3	cu yd	\$0 00	\$0 00
Load / Haul	67921 3	cu yd	\$0 95	\$64,525 24
Spread and grade	67921 3	cu yd	\$0.30	\$20,376 39
Landscape				
Native Seed Mix	421 0	PLS lbs	\$4 63	\$1,949 23
Fourwing saltbush		10	7.00	Ţ.,JO 10
Wyoming big sagebrush		075		
Alkslı sacabon		1		
Blue grama		25	 	
Bluebunch wheatgrass		14 25		
Streambank wheatgrass		13		
Smooth brome		15 5		
Intermediate wheatgrass		10		
Sandberg blusgrass		2		
Sheep fescue		3		
Siender wheatgrass		11		
Western wheatgrass		17		
		100%		
Planting with Grain Dntl		hrs		
Post Closure Care		······································		
Inspection *	60 0	ea	\$150 00	\$9,000 00
Fence Repair **	300 0	If	\$9 00	\$2,700 00
Soil Repair ***	3000 0	sf	\$1 25	\$3,750 00
Total Bond Amount				\$102,300 86

^{*} Inspection assumes twice per year for 30 years

^{**} Fence repair assumes 20 feet per year

^{***} Cap repair assumes 100 sq ft per year



2020 Closure/Post Closure

North Pointe Cedar Valley Landfill 57 Acres

Financial Assurance Plan

Item	Quantity	Unit		Unit Cost	Т	atal Cost
CLOSURE COSTS	Quantity	Onit	<u> </u>	Unit Cost	10	otal Cost
			<u> </u>			
Active Cell					-	111111111111111111111111111111
Final Cover	27	Acres	 			
Soil (located on site)		Acies				
Load & Haul	43560	Cu Yd	\$	1.89	\$	82,479.99
Spread & Grade	43560	Cu Yd	\$	0.56	\$	24,517.87
Spicaa a Stade	13300	Cara	+	0.50	7	24,317.07
		***************************************		-		
Intermediate Covered Cell	6					
Load & Haul	9680		\$	1.89	\$	18,295.20
Spread & Grade	9680		\$	0.56	\$	5,392.53
Landscape	51	Acres	\$	1,161.56	\$	59,239.63

Closed Area	6	Acres				
				· · · · · · · · · · · · · · · · · · ·		
POST CLOSURE CARE	30	Years	\$	2,147.18	\$	64,415.38
			<u> </u>			

				····		
			<u> </u>			
					\$	254,340.60

Total Financial Assurance Amount

Price includes 1.018 Inflation factor

2019 Closure/Post Closure

North Pointe Cedar Valley Landfill 47.5 Acres

Financial Assurance Plan

Item	Quantity	Unit	Unit Cost	Total Cost
CLOSURE COSTS	Quarterty	Ome	Ome cost	Total Cost
Active Cell				
2 foot Cap	7	Acres		
Soil (located on site)	,	7.0103		
Load & Haul	17170	Cu Yd	\$ 1.11	\$ 18,986.61
Spread & Grade	17170	Cu Yd	\$ 0.55	\$ 9,493.30
Intermediate Covered Cell	34.5			
Load & Haul	25570		\$ 1.11	\$ 28,348.53
Spread & Grade	25570	***************************************	\$ 0.55	\$ 14,039.27
Landscape	42	Acres	\$ 1,141.02	\$ 47,922.97
Closed Area	6	Acres		

		·····		
POST CLOSURE CARE	30	Years	\$ 2,109.21	\$ 63,276.40
	!			
				···
		, , , , , , , , , , , , , , , , , , ,		
				\$ 182,067.08
				7 102,007.00

Total Financial Assurance Amount

Price includes 1.02389 Inflation factor

STATEMENT OF ACCOUNT

PTIF

UTAH PUBLIC TREASURERS' INVESTMENT FUND

David Damschen, Utah State Treasurer, Fund Manager
PO Box 142315
350 N State Street, Suite 180

350 N State Street, Suite 180 Salt Lake City, Utah 84114-2315 Local Call (801) 538-1042 Toll Free (800) 395-7665 www.treasurer.utah.gov

ESC NO POINTE SSD LANDFILL ACCT RODGER HARPER 2000 W 200 S LINDON UT 84042

Account			Account Period	
7363		September 01, 2020 through September 30, 2020		
Summary				
Beginning Balance	\$ 256,130.69	Average Daily Balance	\$ 256,130.69	
Deposits	\$ 111.58	Interest Earned	\$ 111.58	
Withdrawals	\$ 0.00	360 Day Rate	0.5228	
Ending Balance	\$ 256,242.27	365 Day Rate	0.5300	

Date	Activity	Deposits	Withdrawals	Balance
09/01/2020	FORWARD BALANCE	\$ 0.00	\$ 0.00	\$ 256,130.69
09/30/2020	REINVESTMENT	\$ 111.58	\$ 0.00	\$ 256,242.27
09/30/2020	ENDING BALANCE	\$ 0.00	\$ 0.00	\$ 256,242.27