



Div of Waste Management
and Radiation Control

SALT LAKE AREA OFFICE
859 W South Jordan Pkwy, Ste 200
South Jordan, Utah 84095
Phone: (801) 566-5599
www.HALengineers.com

OCT 30 2020

DSHW-2020-015867

Mr. Ty L. Howard
Utah Division of Waste Management and Radiation Control
195 North 1950 West
Salt Lake City, Utah 84114

October 29, 2020

ATTN: Matt Sullivan

RE: Intermountain Regional Landfill – Class V Landfill Permit Renewal Application

Dear Mr. Sullivan:

On behalf of ROC Fund Landfill Holdings, LLC (Intermountain Regional Landfill), Hansen, Allen & Luce, Inc. (HAL) is submitting this landfill permit renewal application and design report.

Included in the permit renewal package is the original 2010 permit application. Some aspects of the renewal application checklist are fulfilled within the original 2010 permit application and are therefore referred to in the checklist. In the case there is a discrepancy between the 2020 Design Engineering Report and the contents of the 2010 permit application, the 2020 Design Engineering Report takes precedent. This includes, but is not limited to landfill floor and closure cap drawings.

Please contact me if you have any questions regarding this submittal at (801) 566-5599.

Sincerely,

A handwritten signature in black ink, appearing to read 'Gordon L. Jones', is written over a horizontal line.

Gordon L. Jones, M.S., P.E.
Principal

Mr. Ty L. Howard
Utah Division of Waste Management and Radiation Control
195 North 1950 West
Salt Lake City, Utah 84114

October 29, 2020

ATTN: Matt Sullivan

RE: Intermountain Regional Landfill – Class V Landfill Permit Renewal Application

Dear Mr. Sullivan:

On behalf of ROC Fund Landfill Holdings, LLC (Intermountain Regional Landfill), Hansen, Allen & Luce, Inc. (HAL) is submitting this landfill permit renewal application and design report.

Included in the permit renewal package is the original 2010 permit application. Some aspects of the renewal application checklist are fulfilled within the original 2010 permit application and are therefore referred to in the checklist. In the case there is a discrepancy between the 2020 Design Engineering Report and the contents of the 2010 permit application, the 2020 Design Engineering Report takes precedent. This includes, but is not limited to landfill floor and closure cap drawings.

Please contact me if you have any questions regarding this submittal at (801) 566-5599.

Sincerely,



Gordon L. Jones, M.S., P.E.
Principal



INTERMOUNTAIN
REGIONAL LANDFILL

INTERMOUNTAIN REGIONAL LANDFILL

2020 CLASS V PERMIT RENEWAL

October 2020

TABLE OF CONTENTS

EXHIBIT 1
2020 PERMIT RENEWAL APPLICATION
AND CHECKLIST

EXHIBIT 2
2020 DESIGN ENGINEERING REPORT

EXHIBIT 3
2010 PERMIT APPLICATION

EXHIBIT 1
2020 PERMIT RENEWAL
APPLICATION AND
CHECKLIST

Utah Class I and V Permit Application Checklist

| Part I General Information APPLICANT: PLEASE COMPLETE ALL SECTIONS. | | | | | |
|---|---|-----------------------------|---|--|---------------------------|
| I. Landfill Type | <input type="checkbox"/> Class I <input checked="" type="checkbox"/> Class V | II. Application Type | <input type="checkbox"/> New Application <input checked="" type="checkbox"/> Renewal Application | <input type="checkbox"/> Facility Expansion <input type="checkbox"/> Modification | |
| For Renewal Applications, Facility Expansion Applications and Modifications Enter Current Permit Number | | | | | <u>1102</u> |
| III. Facility Name and Location | | | | | |
| Name of Facility ROC-Intermountain Regional MSW Landfill | | | | | |
| Site Address (street or directions to site) 800 South Allen Ranch Road (18150 West) | | | | County Utah | |
| City Fairfield | | Zip Code 84013 | | Telephone (801) 403-7651 | |
| Township 7 N | Range 2 W | Section(s) 16 | | Quarter/Quarter Section | Quarter Section NW, SW |
| Main Gate Latitude 40 degrees 13 minutes 2.31 seconds | | | Longitude 112 degrees 4 minutes 5.89 seconds | | |
| IV. Facility Owner(s) Information | | | | | |
| Name of Facility Owner ROC Fund Landfill Holdings, LLC | | | | | |
| Address (mailing) 11629 South 700 East, Suite 190 | | | | | |
| City Draper | | State Utah | Zip Code 84020 | Telephone (801) 403-7651 | |
| V. Facility Operator(s) Information | | | | | |
| Name of Facility Operator ROC Fund Landfill Holdings, LLC | | | | | |
| Address (mailing) 11629 South 700 East, Suite 190 | | | | | |
| City Draper | | State Utah | Zip Code 84110-1889 | Telephone (801) 403-7651 | |
| VI. Property Owner(s) Information | | | | | |
| Name of Property Owner ROC Fund Landfill Holdings, LLC | | | | | |
| Address (mailing) 11629 South 700 East, Suite 190 | | | | | |
| City Draper | | State Utah | Zip Code 84110-1889 | Telephone (801) 403-7651 | |
| VII. Contact Information | | | | | |
| Owner Contact Name Rob Richards | | | Title President and General Manager | | |
| Address (mailing) 11629 South 700 East, Suite 190 | | | | | |
| City Draper | | State Utah | Zip Code 84110-1889 | Telephone (801) 403-7651 | |
| Email Address rob@irlutah.com | | | Alternative Telephone (cell or other) | | |
| Operator Contact Name Rob Richards | | | Title President and General Manager | | |
| Address (mailing) 11629 South 700 East, Suite 190 | | | | | |
| City Draper | | State Utah | Zip Code 84110-1889 | Telephone (801) 403-7651 | |
| Email Address rob@irlutah.com | | | Alternative Telephone (cell or other) | | |
| Property Owner Contact Name Rob Richards | | | Title President and General Manager | | |
| Address (mailing) 11629 South 700 East, Suite 190 | | | | | |
| City Draper | | State Utah | Zip Code 84110-1889 | Telephone (801) 403-7651 | |

Utah Class I and V Permit Application Checklist

| Part I General Information (Continued) | | | IX. Facility Area | |
|--|--|---|--|--|
| VIII. Waste Types (check all that apply) | | | | |
| <input checked="" type="checkbox"/> All non-hazardous solid waste (see R315-315-7(3) for PCB special requirements) OR the following specific waste types: | | | Facility Area..... <u>330</u> acres | |
| Waste Type | Combined Disposal Unit | Monofill Unit | Disposal Area..... <u>300</u> acres | |
| <input type="checkbox"/> Municipal Waste | <input type="checkbox"/> | <input type="checkbox"/> | Design Capacity | |
| <input type="checkbox"/> Construction & Demolition | <input type="checkbox"/> | <input type="checkbox"/> | Years..... <u>50</u> | |
| <input type="checkbox"/> Industrial | <input type="checkbox"/> | <input type="checkbox"/> | Cubic Yards..... <u>28,900,000</u> | |
| <input type="checkbox"/> Incinerator Ash | <input type="checkbox"/> | <input type="checkbox"/> | Tons..... <u>18,200,000</u> | |
| <input type="checkbox"/> Animals | <input type="checkbox"/> | <input type="checkbox"/> | | |
| <input type="checkbox"/> Asbestos | <input type="checkbox"/> | <input type="checkbox"/> | | |
| <input type="checkbox"/> PCB's (R315-315-7(3) only) | <input type="checkbox"/> | <input type="checkbox"/> | | |
| <input type="checkbox"/> Other _____ | <input type="checkbox"/> | <input type="checkbox"/> | | |
| X. Fee and Application Documents | | | | |
| Indicate Documents Attached To This Application | | | <input checked="" type="checkbox"/> Application Fee: Amount \$ | |
| <input checked="" type="checkbox"/> Facility Map or Maps | <input checked="" type="checkbox"/> Facility Legal Description | <input checked="" type="checkbox"/> Plan of Operation | Class V Special Requirements | |
| <input checked="" type="checkbox"/> Ground Water Report | <input checked="" type="checkbox"/> Closure Design | <input checked="" type="checkbox"/> Cost Estimates | <input type="checkbox"/> Documents required by UCA 19-6-108(9) and (10) | |
| I HEREBY CERTIFY THAT THIS INFORMATION AND ALL ATTACHED PAGES ARE CORRECT AND COMPLETE. | | | | |
| Signature of Authorized Owner Representative | | | Title <u>President</u> | |
| <u>Rob Richards</u> | | | Date <u>10/30/20</u> | |
| Name typed or printed | | | Address <u>11629 South 700 East, Suite 190</u> <u>Draper, Utah 84110-1889</u> | |
| Email Address <u>rob@irlutah.com</u> | | Alternative Telephone (cell or other) | | |
| Signature of Authorized Land Owner Representative (if applicable) | | | Title | |
| _____ | | | Date | |
| Name typed or printed | | | Address | |
| Email Address | | Alternative Telephone (cell or other) | | |
| Signature of Authorized Operator Representative (if applicable) | | | Title | |
| _____ | | | Date | |
| Name typed or printed | | | Address | |
| Email Address | | Alternative Telephone (cell or other) | | |

Utah Class I and V Permit Application Checklist

Important Note: The following checklist is for the permit application and addresses only the requirements of the Division of Waste Management and Radiation Control. Other federal, state, or local agencies may have requirements that the facility must meet. The applicant is responsible to be informed of, and meet, any applicable requirements. Examples of these requirements may include obtaining a conditional use permit, a business license, or a storm water permit. The applicant is reminded that obtaining a permit under the *Solid Waste Permitting and Management Rules* does not exempt the facility from these other requirements. Please take note of the heading of each section for the facilities that the section applies to.

An application for a permit to construct and operate a landfill is the documentation that the landfill will be located, designed, constructed, operated, and closed in compliance with the requirements of Utah Administrative Code R315-301 through 320 (*Utah Solid Waste Permitting and Management Rules*) and Utah Code Annotated 19-6-101 through 126 (*Utah Solid and Hazardous Waste Act*). The application should be written to be understandable by regulatory agencies, landfill operators, and the general public. The application should also be written so that the landfill operator, after reading it, will be able to operate the landfill according to the requirements with a minimum of additional training.

Copies of the *Solid Waste Permitting and Management Rules*, the *Utah Solid and Hazardous Waste Act*, along with many other useful guidance documents can be obtained by contacting the Division of Waste Management and Radiation Control at 801-536-0200. Most of these documents are available on the Division's web page at <https://deq.utah.gov/division-waste-management-radiation-control>. Guidance documents can be found at the solid waste section portion of the web page.

Part II Application Checklist

| I. Facility General Information | |
|---|----------------------|
| Description of Item | Location In Document |
| 1a. Information Required for All Class I and V Landfills | |
| Completed Part I General information Form (See form above) | |
| General description of the facility (R315-310-3(1)(b)) | |
| Legal description of property (R315-310-3(1)(c)) | |
| Proof of ownership, lease agreement, or other mechanism (R315-310-3(1)(c)) | |
| Area served by the facility including population (R315-310-3(1)(d)) | |
| If the permit application is for a class I landfill a demonstration that the landfill is not a commercial facility | |
| Waste type and anticipated daily volume (R315-310-3(1)(d)) | |
| 1b. Information Required for All New Or Laterally Expanding Class I and V Landfills | |
| Intended schedule of construction (R315-302-2(2)(a)) | |
| Name and address of all property owners within 1000 feet of the facility boundary (R315-310-3(2)(a)(i)) | |
| Documentation that a notice of intent to apply for a permit has been sent to all property owners listed above (R315-310-3(2)(ii)) | |
| Name of the local government with jurisdiction over the facility site (R315-310-3(2)(iii)) | |

Utah Class I and V Permit Application Checklist

| I. Facility General Information | |
|---|----------------------|
| Description of Item | Location In Document |
| <i>Ic.</i> Location Standards for All New Or Laterally Expanding Class I and V Landfills (R315-302-1) | |
| Documentation that the facility has met the historical survey requirement of R315-302-1(2)(f) | |
| Land use compatibility (R315-302-1(2)(a)) | |
| Maps showing the existing land use, topography, residences, parks, monuments, recreation areas or wilderness areas within 1000 feet of the site boundary | |
| Certifications that no ecologically or scientifically significant areas or endangered species are present in site area | |
| List of airports within five miles of facility and distance to each | |
| Geology (R315-302-1(2)(b)) | |
| Geologic maps showing significant geologic features, faults, and unstable areas | |
| Maps showing site soils | |
| Surface water (R315-302-1(2)(c)) | |
| Magnitude of 24 hour 25 year and 100 year storm events | |
| Average annual rainfall | |
| Maximum elevation of flood waters proximate to the facility | |
| Maximum elevation of flood water from 100 year flood for waters proximate to the facility | |
| Wetlands (R315-302-1(2)(d)) | |
| Ground water (R315-302-1(2)(e)) | |
| <i>Id.</i> Plan of Operations Requirements for All Class I And V Landfills (R315-310-3(1)(e) and R315-302-2(2)) | |
| Forms and other information as required in R315-302-2(3) including a description of on-site waste handling procedures and an example of the form that will be used to record the weights or volumes of waste received (R315-302-2(2)(b) And R315-310-3(1)(f)) | |
| Schedule for conducting inspections and monitoring, and examples of the forms that will be used to record the results of the inspections and monitoring (R315-302-2(2)(c), R315-302-2(5)(a), and R315-310-3(1)(g)) | |
| Contingency plans in the event of a fire or explosion (R315-302-2(2)(d)) | |
| Corrective action programs to be initiated if ground water is contaminated (R315-302-2(2)(e)) | |
| Contingency plans for other releases, e.g. explosive gases or failure of run-off collection system (R315-302-2(2)(f)) | |
| Plan to control fugitive dust generated from roads, construction, general operations, and covering the waste (R315-302-2(2)(g)) | |

Utah Class I and V Permit Application Checklist

| I. Facility General Information | |
|--|----------------------|
| Description of Item | Location In Document |
| Plan for litter control and collection (R315-302-2(2)(h)) | |
| Description of maintenance of installed equipment (R315-302-2(2)(i)) | |
| Procedures for excluding the receipt of prohibited hazardous or PCB containing wastes (R315-302-2(2)(j)) | |
| Procedures for controlling disease vectors (R315-302-2(2)(k)) | |
| A plan for alternative waste handling (R315-302-2(2)(l)) | |
| A general training plan for site operations (R315-302-2(2)(o)) | |
| Any recycling programs planned at the facility (R315-303-4(6)) | |
| Closure and post-closure care Plan (R315-302-2(2)(m)) | |
| Procedures for the handling of special wastes (R315-315) | |
| Plans and operation procedures to minimize liquids (R315-303-3(1)) | |
| Plans and procedures to address the requirements of R315-303-3(7)(c) through (i) and R315-303-4 | |
| Any other site-specific information pertaining to the plan of operation required by the Director (R315-302-2(2)(p)) | |
| IIe. Special Requirements for New Or Laterally Expanding Class V Landfill (R315-310-3(3)) | |
| Submit information required by the <i>Utah Solid and Hazardous Waste Act</i> Subsections 19-6-108(9) and 19-6-108(10) (R315-310-3(2)(a)) | |
| <i>Note the following information must be provided following issuance of the permit but prior to Director approval to take waste for a new Class V facility.</i> | |
| Approval from the local government within which the solid waste facility sits | |
| Approval from the Legislature and the Governor | |

| II Facility Technical Information | |
|--|----------------------|
| Description of Item | Location In Document |
| IIa. Maps for All Class I and V Landfills | |
| Topographic map drawn to the required scale with contours showing the boundaries of the landfill unit, ground water monitoring well locations, gas monitoring points, and the borrow and fill areas (R315-310-4(2)(a)(i)) | |
| Most recent U.S. Geological Survey topographic map, 7-1/2 minute series, showing the waste facility boundary; the property boundary; surface drainage channels; any existing utilities and structures within one-fourth mile of the site; and the direction of the prevailing winds (R315-310-4(2)(a)(ii)) | |
| IIb. Geohydrological Assessment for All Class I and V Landfills (R315-310-4(2)(b)) | |
| Local and regional geology and hydrology including faults, unstable slopes and subsidence areas on site (R315-310-4(2)(b)(i)) | |

Utah Class I and V Permit Application Checklist

| // Facility Technical Information | |
|---|----------------------|
| Description of Item | Location In Document |
| Evaluation of bedrock and soil types and properties including permeability rates (R315-310-4(2)(b)(ii)) | |
| Depth to ground water (R315-310-4(2)(b)(iii)) | |
| Direction and estimated flow rate of ground water (R315-310-4(2)(b)(iv)) | |
| Quantity, location, and construction of any private or public wells on-site or within 2,000 feet of the facility boundary (R315-310-4(2)(b)(v)) | |
| Tabulation of all water rights for ground water and surface water on-site and within 2,000 feet of the facility boundary (R315-310-4(2)(b)(vi)) | |
| Identification and description of all surface waters on-site and within one mile of the facility boundary (R315-310-4(2)(b)(vii)) | |
| Background ground water and surface water quality assessment and, for an existing facility, identification of impacts upon the ground water and surface water from leachate discharges (R315-310-4(2)(b)(viii)) | |
| Ground Water Monitoring (R315-303-3(7)(b) and R315-308) | |
| Statistical method to be used (R315-308-2(8)) | |
| Calculation of site water balance (R315-310-4(2)(b)(ix)) | |
| //c. Engineering Report - Plans, Specifications, And Calculations for All Class I and V Landfills | |
| Documentation that the facility will meet all of the performance standards of R315-303-2 | |
| Engineering reports required to meet the location standards of R315-302-1 including documentation of any demonstration or exemption made for any location standard (R315-310-4(2)(c)(i)) | |
| Anticipated facility life and the basis for calculating the facility's life (R315-310-4(2)(c)(ii)) | |
| Cell design to include liner design, cover design, fill methods, elevation of final cover including plans and drawings signed and sealed by a professional engineer registered in the State of Utah (R315-303-3(3), R315-303-3(6) and (7)(a), R315-310-3(1)(b) and R315-310-4(2)(c)(iii)) | |
| Leachate collection system design and calculations showing system meets the requirements of R315-303-3(2) | |
| Equipment requirements and availability (R315-310-4(2)(c)(iii)) | |
| Identification of borrow sources for daily and final cover and for soil liners (R315-310-4(2)(c)(iv)) | |
| Run-On and run-off diversion designs (R315-303-3(1)(c), (d) and (e)) | |
| Leachate collection, treatment, and disposal and documentation to show that any treatment system is being or has been reviewed by the Division of Water Quality (R315-310-4(2)(c)(v) and R315-310-3(1)(i)) | |

Utah Class I and V Permit Application Checklist

| // Facility Technical Information | |
|---|----------------------|
| Description of Item | Location In Document |
| Ground water monitoring plan that meets the requirements of Rule R315-308 including well locations, design, and construction (R315-310-4(2)(b)(x) and R315-310-4(2)(c)(vi)) | |
| Landfill gas monitoring and control plan that meets the requirements of Subsection R315-303-3(5) (R315-310-4(2)(c)(vii)) | |
| Slope stability analysis for static and under the anticipated seismic event for the facility (R315-310-4(2)(b)(i) and R315-302-1(2)(b)(ii)) | |
| Design and location of run-on and run-off control systems (R315-310-4(2)(c)(viii)) | |
| //d. Closure Plan for All Class I and V Landfills (R315-310-3(1)(h)) | |
| Closure Plan (R315-302-3(2) and (3)) | |
| Closure schedule (R315-310-4(2)(d)(i)) | |
| Design of final cover (R315-303-3(4) and R315-310-4(2)(c)(iii)) | |
| Capacity of site in volume and tonnage (R315-310-4(2)(d)(ii)) | |
| Final inspection by regulatory agencies (R315-310-4(2)(d)(iii)) | |
| //e. Post-Closure Care Plan for All Class I and V Landfills (R315-310-3(1)(h)) | |
| Post-Closure Plan (R315-302-3(5) and (6)) | |
| Site monitoring of landfill gases, ground water, and surface water, if required (R315-310-4(2)(e)(i)) | |
| Changes to record of title, land use, and zoning restrictions (R315-310-4(2)(e)(v)) | |
| Maintenance activities to maintain cover and run-on/run-off control systems (R315-310-4(2)(e)(iii)) | |
| List the name, address, and telephone number of the person or office to contact about the facility during the post-closure care period (R315-310-4(2)(e)(vi)) | |
| //f. Financial Assurance for All Class I and V Landfills (R315-310-3(1)(j)) | |
| Identification of closure costs including cost calculations (R315-310-4(2)(d)(iv)) and (R315-302-2(2)(n)) | |
| Identification of post-closure care costs including cost calculations (R315-310-4(2)(e)(iv)) | |
| Identification of the financial assurance mechanism that meets the requirements of Rule R315-309 and the date that the mechanism will become effective (R315-309-1(1)) | |

**EXHIBIT 2
2020 DESIGN
ENGINEERING REPORT**



INTERMOUNTAIN

REGIONAL LANDFILL

DESIGN ENGINEERING REPORT

(HAL Project No.: 373.02.101)

October 2020

INTERMOUNTAIN REGIONAL LANDFILL

DESIGN ENGINEERING REPORT

(HAL Project No.: 373.02.101)



Gordon L. Jones, P.E.
Principal



October 2020

TABLE OF CONTENTS

| | |
|--|------------|
| TABLE OF CONTENTS | i |
| CHAPTER 1 - INTRODUCTION | 1-1 |
| CHAPTER 2 – LANDFILL FLOOR DESIGN | 2-1 |
| PREVIOUS DESIGN AND CURRENT LANDFILL STATUS | 2-1 |
| 2020 PERMIT RENEWAL | 2-1 |
| 2016 PERMIT MODIFICATION GENERAL LAYOUT AND DESIGN | 2-1 |
| FLOOR ELEVATIONS AND SLOPES..... | 2-2 |
| LINING SYSTEM..... | 2-2 |
| LEACHATE COLLECTION AND REMOVAL SYSTEM (LCRS)..... | 2-3 |
| RUNOFF CONTAINMENT | 2-5 |
| GROUNDWATER MONITORING WELLS | 2-6 |
| GEOTECHNICAL INVESTIGATION | 2-6 |
| CHAPTER 3 – MODIFIED CLOSURE DESIGN | 3-1 |
| GENERAL LAYOUT AND DESIGN..... | 3-1 |
| STORM WATER MANAGEMENT | 3-1 |
| STABILITY | 3-2 |
| CHAPTER 4 – STORM WATER MANAGEMENT | 4-1 |
| HYDROLOGY | 4-1 |
| HYDRAULIC DESIGN OF CHANNELS | 4-2 |
| DOWNSPOUT DESIGN..... | 4-3 |
| EROSION PROTECTION | 4-3 |
| CHAPTER 5 – GAS COLLECTION AND CONTROL SYSTEM | 5-1 |
| CHAPTER 6 – 2020 OPERATIONAL UPDATES | 6-1 |
| REFERENCES | 1 |
| APPENDIX A Permit Design Drawings | |
| APPENDIX B Geotechnical Investigation | |
| APPENDIX C Slope Stability and Settlement Analysis | |
| APPENDIX D Differential Settlement Update | |
| APPENDIX E Leachate Collection and Removal System | |

APPENDIX F
Hydrology

APPENDIX G
Erosion Protection

LIST OF TABLES

| | | |
|-----------|--|-----|
| Table 2-1 | HELP Model Generated Leachate Rates | 2-3 |
| Table 2-2 | Required Properties for Geocomposite | 2-4 |
| Table 2-3 | Required Properties for Geotextile Filter Fabric | 2-4 |

CHAPTER 1 - INTRODUCTION

Intermountain Regional Landfill (IRL) seeks the renewal of their Class V landfill permit. IRL retained Hansen, Allen & Luce, In. (HAL) to prepare the application and perform a small modification to the closure cap benches to accommodate gas collection. This report provides a summary of background information associated with the design of the landfill floor and closure cap, proposed design modifications to other associated features, and results from the engineering calculations for the proposed modifications. The engineering calculations are included to provide a basis for approval of a permit modification from the Utah Division of Waste Management and Radiation Control (DWMRC).

The permit modification that was approved in 2016 included the following design modifications:

1. Floor elevations and leachate collection system, including sumps and leachate withdrawal pipes.
2. Closure cap final grade, including access, benches for runoff and erosion control, downspout drainage piping to remove runoff from the top of the closure cap and benches.

The 2020 permit renewal modification that was approved in 2016 included the following design modifications:

1. Closure cap benches to accommodate gas collection, downspout drainage piping, and erosion control.

Locations and configurations of some other on-site facilities to support landfill operations were also modified to provide a general concept layout plan regarding the types of facilities needed. These facilities include a potential leachate management pond, parking areas, and soil stockpile areas. The locations, sizes and configurations of these facilities are not critical to the design requirements associated with the landfill and its closure. Therefore, it is understood that the types and locations of proposed support facilities may be modified from those presented herein.

CHAPTER 2 – LANDFILL FLOOR DESIGN

This chapter presents the general layout and design concept of the landfill floor systems, which includes more specific information for the leachate collection and removal system components and runoff/run-on containment. References to the permit drawings in Appendix A, geotechnical report in Appendix B, the original slope stability and settlement analysis completed by HDR in Appendix C, and calculations provided in Appendices D and E should be noted throughout this chapter.

PREVIOUS DESIGN AND CURRENT LANDFILL STATUS

The original design of the landfill was completed by HDR, Inc. and presented in a design engineering report dated November 2010 that was included in the permit application as Part 3. The original capacity of the facility was listed as 27,000,000 cubic yards. As of June of 2016, several cell construction projects covering approximately 20 acres have been completed in the western portion of what was previously referred to as Cell 1 and Cell 2 in the original permit drawings.

2020 PERMIT RENEWAL

In conjunction with the 2020 permit renewal, some small modifications were made to the closure cap. The benches were updated with a minimum slope of 2% to better accommodate gas collection. The bench modifications resulted in hydrology changes and this report has been updated to reflect the current drainage design.

2016 PERMIT MODIFICATION GENERAL LAYOUT AND DESIGN

The redesign of the facility consists of a landfill area formed by incised embankments along all sides of the facility with a floor system concept very similar to the previous design. The facility has three main cells with each containing its own leachate collection system, sump and leachate withdrawal system. In order to improve on the previous design concept, the floor elevations were raised to reduce the amount of excavation required. The floor slope was reversed for the undeveloped portion of Cell 1 and taken to the north in order to minimize excavation and provide an accessible location for a leachate sump and withdrawal system. The other two cells function very similarly to the previous design with the only major change being the elevations. Cells 2 and 3 are both similar in design which drain down the center of the cell to a sump located on the far east end of the cell floor. Cell 1 differs because it includes the 20 acre area that has already been developed. Cell 1 needed to be altered because the previous design placed the floor trajectory toward the east which would have made the excavation much deeper.

The overall capacity above the protective soil cover material placed above the lining system is about 28.9 million cubic yards, slightly more than the previous design. This does not include the final cover system. The design modification maintains the previous horizontal footprint and makes grade adjustments to the floor and closure cap that do not increase the overall height above existing topography (100 feet) and actually decreases the maximum height from floor to the top of the closure cap. The slight increase in capacity was not the intent of this modification and also cannot be attributed to either horizontal or vertical expansion. The increase is a byproduct of a change in the geometry of the waste mound that produces a more favorable cut/fill balance while maintaining the original design constraints.

FLOOR ELEVATIONS AND SLOPES

The floor elevations were raised significantly from the previous design to decrease the amount of cut required for the facility. This resulted in the distance to ground water being much greater than the minimum 5 feet as required in R315-302-2(e). The bottom liner has a 2% slope, consistent with the previously approved design and with R315-303-3-3a(ii) that specifies minimum liner slopes. The slope of the leachate collection system piping was set at a minimum of 1% but ranged to as high as 2% in some areas.

As part of the original Technical and Engineering Report completed by HDR in 2010, a slope stability analysis and settlement analysis entitled "Slope Stability and Settlement Evaluation" was completed and included as Appendix C. This evaluation included a review of the site conditions, static, pseudo-static stability and deformation analyses, and settlement and liner strain. The modified design has maximum cut slopes and maximum fill slopes that are equal to or less than those considered for the stability and seismic analyses completed by HDR. Therefore, the geometry of the design is considered acceptable from a stability standpoint based on the previous evaluation, which is found in this report in Appendix C.

The differential settlement and liner strain calculations were updated due to the modification of the overall closure geometry and changes to the leachate collection piping slopes. This update was necessary to ensure that the leachate collection system would maintain a positive slope toward the sump given differential settlement once final waste grade has been reached. A summary of the results are found in Appendix D.

LINING SYSTEM

A composite lining system is proposed for the landfill disposal area consisting of a Geosynthetic Clay Liner (GCL) overlain by a 60-mil HDPE geomembrane liner. This system was approved as part of the permit issued in 2011 and has been used on each landfill construction project to date.

An extra GCL and 60-mil HDPE geomembrane are proposed for placement in the sump areas directly above the GCL and HDPE geomembrane placed across the rest of the cell area. This extra GCL and geomembrane provide added protection against leakage in the sump areas which is the most vulnerable area for leakage to occur. Geosynthetic materials placed on interior slopes of the landfill area will consist of reinforced GCL and textured HDPE geomembrane liner. Geosynthetic materials placed across the cell floor may be unreinforced GCL with a smooth HDPE geomembrane.

Geosynthetic Clay Liner (GCL)

Hydraulic equivalency of the geosynthetic clay liner was included as part of the original permit application and was approved by the Executive Secretary as required by UAC R315-503-3(3)(a)(ii) as stated in the current permit.

HDPE Geomembrane Liner

HDPE geomembrane is proposed for use as the synthetic liner system above the GCL. The floor area will consist of 60-mil smooth HDPE geomembrane and the interior slopes will consist of 60-mil textured HDPE geomembrane to increase slope stability for materials placed on the side slopes above the HDPE geomembrane.

LEACHATE COLLECTION AND REMOVAL SYSTEM (LCRS)

A leachate collection and removal system (LCRS) will be constructed consisting of a geocomposite (geonet bonded to a geotextile) placed directly over the HDPE geomembrane liner. The geocomposite on the floor will be a single sided geocomposite on the floor and a double sided geocomposite on the side slope. Perforated leachate conveyance pipes surrounded by gravel will be placed along the collection areas where the floor surfaces come together with additional conveyance collection pipes provided at specified intervals. The leachate will then be directed to the leachate sumps for removal.

HELP Model

The Environmental Protection Agency's (EPA) Hydrologic Evaluation of Landfill Performance (HELP) model is a quasi-two-dimensional hydrologic computer model used for conducting water balance analyses of landfills, cover systems and other solid waste containment systems. The model accepts weather, soil and design data, and uses solution techniques that account for the effects of surface storage, snowmelt, runoff, infiltration, evapotranspiration, vegetative growth, soil moisture storage, lateral subsurface drainage, leachate recirculation, unsaturated vertical drainage, and leakage through soil, geomembrane and/or composite liners.

The evaporation and solar radiation values for the modeling effort were obtained from default data contained within the HELP model software corresponding to the Salt Lake area. The precipitation and average temperature data used in the model came from the data reported in the Western Regional Climate Center database for Fairfield, Utah.

Five layers were defined in the HELP model corresponding to municipal waste material, soil cover, geocomposite, HDPE geomembrane and GCL to represent the open cell area. An additional three layers were added above the waste consisting of HDPE geomembrane, soil cover material and the erosion protection layer to represent closed portions of the landfill. Model default data were used to define the physical properties of the individual design layers. Leachate quantities were generated for the landfill under the following conditions: no waste, waste thicknesses of 10 feet, 50 feet, 100 feet, 121 feet and at closure. These different depths of waste were used to simulate leachate production at various stages of landfill development. Table 2-1 provides the leachate quantity values generated by the HELP model that were the basis for the LCRS design.

**TABLE 2-1
HELP MODEL GENERATED LEACHATE RATES**

| Waste Height (feet) | Peak Daily Leachate | Annual Average Leachate |
|------------------------|---------------------|-------------------------|
| | (inch) | (inches) |
| No Waste | 0.204 | 0.134 |
| 10 | 0.161 | 0.571 |
| 50 | 0.157 | 0.571 |
| 100 | 0.160 | 0.571 |
| 121 | 0.158 | 0.571 |
| Closure | 0.001 | 0.013 |

Geocomposite

A geocomposite will be placed above the HDPE liner to collect and convey leachate from the floor area to the leachate conveyance pipes that convey the leachate to the sumps for removal. The geonet component of the geocomposite was designed based on the peak daily leachate rate of 0.162 inches/day. The design of the geonet was completed based upon a one-foot wide section of geonet over the longest flow path for the facility. The longest one-foot wide flow path is 460 feet from the leachate conveyance pipe to the upper end of the surface at its longest reach. This will provide the longest flow path and a typical design that can be applied to all areas of the floor.

The longest flow path for each cell is presented in Table 2-2. "Designing with Geosynthetics", by Robert Koerner, suggest several safety factors that should be applied to the leachate rate to obtain a design capacity for the geocomposite. These safety factors include: 1) creep deformation of the geonet 2) biological clogging of the geonet and 3) chemical clogging of the geonet. Therefore, a total safety factor of 4.5 was used for the design of the geocomposite. Applying this resulting safety factor to the leachate rate gives the design transmissivity requirement presented in Table 2-2.

**TABLE 2-2
REQUIRED PROPERTIES FOR GEOCOMPOSITE**

| Cell | Longest Flow Path | Peak Daily Flow | Transmissivity Requirement |
|------|-------------------|-----------------------------|---|
| 1 | 426 ft | 5.7 ft ³ /ft-day | 1.38 x 10 ⁻³ m ² /sec |
| 2 | 418 ft | 5.6 ft ³ /ft-day | 1.36 x 10 ⁻³ m ² /sec |
| 3 | 460 ft | 6.2 ft ³ /ft-day | 1.49 x 10 ⁻³ m ² /sec |

Geotextile Filter Fabric

Geotextile will be used as part of the geocomposite above the HDPE liner and around the leachate conveyance piping on the cell floor in order to provide a filter layer between the soil cover and the LCRS. Gradation properties of the native soil were provided by Applied Geotechnical Engineering Consultants (AGEC) and used for the calculations.

**TABLE 2-3
REQUIRED PROPERTIES FOR GEOTEXTILE FILTER FABRIC**

| Property | Standard |
|-----------------------|------------------------------|
| Equivalent Opening | 0.22 mm |
| Permeability | 1.35x10 ⁻² cm/sec |
| Grab Tensile Strength | 90 lbs |

Leachate Conveyance Pipes

The leachate conveyance pipes are designed to be placed along the valley of the cell floors that are formed by the intersection of the planar surfaces of the floor. Additional leachate pipes along the toes at the north and eastern ends as well as along the planar surfaces of the floor at

specified spacing are also included to provide for adequate drainage given the assumed limitations of the geocomposite. These leachate collection pipes receive leachate from the geocomposite and convey the leachate to the sumps for removal.

The maximum leachate rate calculated using the HELP model was applied to the maximum width and length of floor area where leachate will be collected in the geocomposite for each planned leachate pipe. The contributing area for each leachate pipe varies due to different factors, including cell layout, especially the difference between Cell 1 and Cells 2 and 3. The peak leachate rate of 0.161 inches/day for the cell floor and 0.124 inches/day for the slopes was applied to each contributing area.

Eighty percent of the maximum flow depth in the pipe was assumed for the actual capacity for each pipe using Manning's equation with a Manning's n roughness value of 0.016. A detailed breakdown of the capacity calculations for each leachate pipe is provided in Appendix E.

Landfill Leachate Withdrawal Pipes

Leachate withdrawal pipes were evaluated for wall crushing, wall buckling, and ring deflection using published procedures. Overburden loadings were determined based on the loading over the low point at the sump at closure. The calculations for the determination of pipe's ability to withstand wall crushing, wall buckling, and deflection are found in Appendix E. It was found that the 24-inch HDPE leachate withdrawal pipes specified in the drawings provide sufficient strength under the ultimate load.

Leachate Pond

Leachate will generally be contained and managed within the landfill where the sumps will be pumped when necessary and the leachate will be either used for dust control or placed in active phases of the landfill where leachate containment is provided. Currently, leachate production levels are far below the levels that would be anticipated according to the HELP model predictions. Leachate production rates will be tracked in order to provide a basis for the sizing of the leachate pond. When management of leachate production levels approaches the capacity of the facility to contain the leachate within lined areas, a leachate pond will be designed to be located in the northeast corner of the property as depicted in the permit drawings.

The leachate pond lining system will include a composite secondary (bottom) lining system constructed of GCL overlain by a 60-mil HDPE membrane. A leak detection and removal system consisting of a geonet, a sump and a leachate withdrawal pipe will be placed above the secondary lining system. A primary (upper) lining system consisting of a 60-mil HDPE geomembrane will be placed above the leak detection system above which the leachate will be stored.

RUNOFF CONTAINMENT

Precipitation runoff from the waste material in open areas of the landfill will be contained and managed within the lined landfill area. Containment areas may be formed on waste surfaces and/or by maintaining waste set-back areas where runoff water will be contained between the top of lined embankment and the waste mound. Sufficient capacity will be maintained in these areas to contain runoff from the 25-year 24-hour precipitation event as required by the regulations.

GROUNDWATER MONITORING WELLS

Groundwater monitoring wells were installed prior to the first construction phase at the facility. This permit modification does not include any modifications to the existing groundwater monitoring wells. Since the landfill footprint has not be modified, no changes to the groundwater monitoring well locations should be required.

GEOTECHNICAL INVESTIGATION

A geotechnical study was completed by Earthtec Testing and Engineering, P.C. dated October 13, 2006. Based on that study, HDR Engineering, Inc., who were responsible for the original permit application submitted in 2010, completed the slope stability, seismicity and settlement evaluations. The proposed design modifications do not go outside of the parameters considered as part of HDR's slope stability and settlement evaluation. The maximum cut slope evaluated by HDR was based on a maximum of 50 feet whereas the modified design has a maximum cut slope of 37 feet. The maximum fill slope evaluation completed by HDR was based on a maximum waste fill height of 130 feet and 100 feet above existing grade (although the design only had 80 feet of height over existing grade) at the toe whereas the modified design has a maximum height of 126 feet and maintains the 100 feet above grade with the same 4H:1V slopes as the original design. The maximum operational fill slope evaluated by HDR was 130 feet at a 3H:1V slope which is consistent with the height of 126 feet achieved under the modified design.

The differential settlement calculations were revised due to the change in the geometry of the closure cap and floor which was completed using the same methodology used in the original evaluation completed by HDR. Those calculations are found in Appendix D.

CHAPTER 3 – MODIFIED CLOSURE DESIGN

This section presents the general layout and design concept for the landfill closure system. The geometry of the closure design was modified in order to offset the airspace capacity lost from below existing grade due to the reconfiguration of the floor elevations. This allows for a more efficient use of the available footprint.

GENERAL LAYOUT AND DESIGN

The final waste mound with the overlying layers of daily cover material provides the subgrade for the final closure system. The final cover system for the modified design is consistent with the final cover system that was approved as part of the original permit application in 2010. The cover system consists of 18 inches of intermediate cover, a textured 60-mil HDPE liner followed by 2 feet of final soil cover. The two feet of cover material includes soil fill and an erosion protection layer consisting of native vegetation. A discussion of the erosion protection measures is provided in Chapter 4.

Closure Slopes

Waste mounding and the overlying closure cap extends up on a 4H:1V slope from the top of the floor embankment slopes around the perimeter of the landfill area. An intermediate bench (25 feet wide) is designed into the 4H:1V slopes to provide for intermediate storm water collection and conveyance necessary for erosion protection on the slopes around the facility. The waste mound and closure cap rise to an elevation of about 100 feet above the top of the west cut slope. The waste mound and closure cap then break grade to a 2 percent slope extending to the east. The north, south and east slopes extend upward on 4H:1V slopes from the top of the incised embankments to intersect with the top surface as it extends east on the 2 percent slope.

Sub-Surface Drainage

Some storm water may infiltrate through the cover system and collect on the surface of the HDPE membrane. A drainage system consisting of a perforated drain pipe will be installed underneath the storm water containment berm on the east side of the top of the waste mound. The drain pipes are placed in drain rock with a geotextile wrap around the drain rock. These pipes are provided to drain water that is conveyed along the HDPE liner before it reaches the side slope. Additional perforated drain pipes will be placed under the intermediate bench located on the 4H:1V slopes and will be conveyed to either the downspout pipes directly or run parallel to the downspouts in a separate solid pipe to the exterior toe of the landfill on the east side.

STORM WATER MANAGEMENT

The storm water management system consists of a 2 percent slope at the top of the landfill that directs precipitation runoff from the top surface of the closure cap toward the east. Runoff is then collected and directed to storm water downspouts using a storm water containment berm that directs water to inlet boxes and into parallel 18-inch storm drain pipes. The downspouts convey the storm water from the top of the closure cap to the exterior toe that discharges into an energy dissipation basin where it will then exit the property to the east.

The intermediate bench is located on the 4H:1V perimeter slopes of the closure cap primarily to shorten the length of the 4H:1V slope for erosion control purposes. The intermediate bench also provides storm water conveyance that is collected at inlet boxes and to parallel 18-inch diameter downspout pipes located at the northeast and southeast corners. The storm water management system associated with the closure cap is designed for the 25-year 24-hour precipitation event. Design of the storm water management system, including the hydrology, hydraulic design of the downspout pipes and erosion control is presented in more detail in Chapter 4.

STABILITY

The stability of the closure cap design was originally evaluated by HDR based on information provided in a geotechnical investigation completed by EarthTec Engineering. Although the geometry of the closure cap is changed from the original design, the design parameters are all within the values used for the prior evaluation, including maintaining the exterior slopes at 4H:1V and keeping the overall height of the slope within 100 feet vertical from the base of the slope. The maximum cut slope was also maintained below the height contemplated during the previous evaluation. Because the current design is not outside of the parameters used in the original slope stability evaluation, the previous evaluation is incorporated by reference for use in the modified design.

CHAPTER 4 – STORM WATER MANAGEMENT

A diversion channel/berm will be constructed to manage storm water from the tributary area to the west of the facility. A berm on the top of the closure cap as well as an intermediate bench will convey storm water to downspouts that will take the water off the closure cap. A hydrologic analysis was completed in order to determine peak flow rates to use for the design of the channels, downspouts and erosion control.

HYDROLOGY

Hydrologic calculations were completed for the tributary area to the landfill and the closure cap to determine peak runoff for design purposes. The Soil Conservation Service (SCS) curve number methodology was used in conjunction with the Army Corps of Engineers HEC-HMS hydrology model to predict the peak flows.

Off-Site Run-On Storm Water

Storm water that originates from outside of the landfill facility will need to be diverted in order to prevent water from entering the facility and from eroding the base of the closure cap.

Methodology. Storm drainage diversions extending to the north and south on the western edge of the landfill property will collect and convey storm flows around the facility. Tributary areas to the diversions were delineated based on USGS topographical maps.

Curve numbers were determined based on the hydrologic soil type and soil vegetative cover. The hydrologic soil type is a general indication of the soil's infiltration capacity. Soils are assigned a hydrologic soil type of A, B, C or D by the Natural Resource Conservation Service (NRCS). Soils of hydrologic soil type A have the highest infiltration rate, and therefore produce the least amount of runoff. Soils of hydrologic soil type D have the lowest infiltration rate, and therefore produce the highest amount of runoff. Most of the soils within the tributary area are hydrologic soil type C or D with smaller portions of B and A type soils. The soil vegetation cover and conditions were assumed based on information provided from a custom soil resource report for Fairfield-Nephi Area, Utah and Tooele Area, Utah and verified with a field visit. The cover conditions were combined with the hydrologic soil type to produce a curve number based on Table 2-2d of Technical Release 55 "Urban Hydrology of Small Watersheds" (TR-55). The entire tributary area was combined in one subbasin where an area weighted curve number was applied to the total area.

The lag times (T_L), defined as the time to the hydrograph peak, were calculated by using the time of concentration (T_C) and the equation $T_L = 0.6T_C$. The time of concentration was calculated using the criteria found in Worksheet 3 in TR-55.

The SCS Type II distribution was used to model a 24-hour 25-year storm, consistent with the requirement of R315-305-4-3(a). The rainfall amount was taken toward the higher elevations of the tributary area from the "Point Precipitation Frequency Estimates from NOAA Atlas 14".

The magnitude of the area tributary to the landfill site is large enough to warrant the use of a reduction of the precipitation value due to the likelihood of the full amount of the storm affecting the whole region decreases with an increase of tributary area. The factor is based on

information from the Salt Lake City Hydrology Manual. According to the manual, a 24-hour event has an areal reduction factor of:

$$ARF = 0.01(100 - 2 * \text{Area}^{0.46}) \text{ where}$$

$$\text{Area} = \text{Total Tributary Area, } 6.69 \text{ mi}^2$$

$$ARF = 0.95$$

This reduction factor was applied to the tributary area for run-on calculation purposes.

Peak Design Flow. Hydrologic calculations presented above were used to generate a peak flow of 61 cubic feet per second (cfs) for the run-on from the tributary area to the west of the facility. The calculations and summary of methodology and results are presented in Appendix F.

On-Site Run-Off Storm Water

Storm water will need to be conveyed off the landfill facility in order to protect the integrity of the closure cap.

Methodology. Delineation of the subbasins from the closure cap, shown in the figure included in Appendix F, was based on the cell closure cap design discussed in Chapter 3. Each subbasin is designed to drain either directly off of the closure cap or to a downspout that conveys flow away from the facility.

A curve number was determined based on the hydrologic soil type C found at the facility and assumed to be used as part of the cover system. The cover type was assumed to be similar to a dirt road in order to account for the period before vegetation becomes fully established. The cover conditions were combined with the hydrologic soil type to produce a curve number of 87 based on Table 2-2a of TR-55.

The lag times for each subbasin were calculated using Worksheet 3 in TR-55 with a minimum lag time of 5 minutes being applied to subbasins where the calculated value was less than 5 minutes.

The SCS Type II Distribution was used with the 25-year 24-hour storm, consistent with the requirement of R315-305-4-3(b). The rainfall amount was taken from the "Point Precipitation Frequency Estimates from NOAA Atlas 14" based on a location defined at the center of the landfill facility. The value of the 25-year 24-year event is 1.74 inches.

Peak Design Flows. The hydrologic analysis presented above was used to generate peak design flows for each of the subbasins defined for the closure cap and for the downspout piping located at points along the east side of the closure cap. The calculations and summary of methodology and results are presented in Appendix F.

HYDRAULIC DESIGN OF CHANNELS

The peak flow rates based on the hydrology discussed above provided the basis for the design of the drainage conveyances. An existing run-on diversion channel on the west side of the property has been constructed based on the design provided in the original design. This channel/berm will be extended to the south as construction of the landfill continues to ensure that run-on is directed around the facility.

DOWNSPOUT DESIGN

Hydrologic calculations for run-off described above were used to design the downspouts. The design is based on peak flows up to 30.7 cfs contributing to downspouts.

Downspout sizes were determined used inlet control conditions and selecting the size and head water depth requirement using the orifice equation. Inlet control conditions were assumed because at peak flow supercritical flow in the system on the 4H:1V slopes and the elevation differences between the inlet and outlet ends of the downspout pipes will not allow for outlet conditions to control.

The downspout pipes were sized based on calculations provided in Appendix F. Two 18-inch pipes in parallel are to be installed for each of the four downspout locations. The headwater depth requirements are provided within the inlet boxes below the grating with additional depth and freeboard provided by the grading of the benches and the berm height on the top of the closure cap.

EROSION PROTECTION

Long term options to provide erosion protection generally consist of establishing vegetation or by placing a stone mulch. In this case, the establishment of vegetation is the selected erosion protection method. Procedures presented in "Erosion and Sedimentation in Utah A Guide for Control", a Utah-specific publication, were used to determine the adequacy of the vegetative system. The detailed calculations are found in Appendix G. According to the calculations, a native vegetative cover of approximately 30% on the 4H:1V slopes will provide adequate protection against erosion and the top of the closure cap with the 2% slope provides adequate protection due to the minimal slope, although vegetation will be established there as well.

CHAPTER 5 – GAS COLLECTION AND CONTROL SYSTEM

IRL is regulated under the New Source Performance Standards (NSPS), 40 CFR Part 60, Subpart WWW and is required to address landfill gas (LFG). HAL prepared a Gas Collection and Control System (GCCS) Design Plan for the facility that was submitted to the Utah Department of Environmental Quality - Division of Air Quality (DQA) on August 26, 2020. The GCCS is currently in the review process. GCCS construction is expected in 2021 and will be operational by February 28, 2022. Some general GCCS design elements are shown in the drawings included in this report.

CHAPTER 6 – 2020 OPERATIONAL UPDATES

IRL currently serves Northern Utah, including the counties of Salt Lake, Utah, Weber and Davis. Estimated remaining life is 38 years resulting in an estimated closure date of 2058. Currently there is no recycling program in place.

REFERENCES

- Chevron Chemical Co., 1996. *Plexco/Spirolite Engineering Manual 2 - System Design*.
- Das, B., 2011. *Principles of Foundation Engineering, 7th Edition*. Samford, CT: Cengage Learning.
- Koerner, R.M., 1990. *Designing with Geosynthetics*. Englewood Cliffs, New Jersey. Prentice-Hall, Inc.
- Earthtec Testing and Engineering, PC, 2006. *Geotechnical Study Intermountain Regional Landfill, Fairfield, Utah*. Orem, UT: Earthtec Testing and Engineering, PC.
- HDR Engineering, Inc., 2010. *Slope Stability and Settlement Analysis, Intermountain Regional Landfill, Fairfield, Utah*. Salt Lake City, UT: HDR Engineering, Inc.
- Hansen, Allen, & Luce, Inc. 2014. *Intermountain Regional Landfill - Request for Construction Phasing Permit Modification and 2014 Cell Expansion Submittal*. Midvale, UT: Hansen, Allen, & Luce, Inc.
- National Oceanic and Atmospheric Administration (NOAA), 2016. *Point Precipitation Frequency Estimates from NOAA Atlas 14*. Maryland: National Weather Service.
- Natural Resources Conservation Service, 2016. *National Cooperative Soil Survey – Web Soil Survey*. websoilsurvey.sc.egov.usda.gov.
- Plastics Pipe Institute, 2009. *Handbook of Polyethylene Pipe, Second Edition*. Plasticpipe.org/publications.
- U.S. Army Corps of Engineers, Hydrologic Engineering Center, 2000. *Hydrologic Modeling System HEC-HMS Technical Reference Manual*. Davis, CA: U.S. Army Corps of Engineers.
- U.S. Department of Agriculture, Natural Resources Conservation Service, 1986. *Urban Hydrology for Small Watersheds, Technical Release No. 55 (TR-55)*.
- U.S. Environmental Protection Agency EPA, 1994. *The Hydrologic Evaluation of Landfill Performance (HELP) Model Users Guide for Version 3*. Cincinnati, Ohio: US EPA Office of Research and Development.
- Utah Division of Administrative Rules. 2016. *Utah Administrative Code, R315*. The Department of Administrative Services.
- Utah Water Research Laboratory, 1984. *Erosion and Sedimentation in Utah: A Guide for Control*. Logan, Utah: Utah State University.
- Western Regional Climate Center website maintained by the Desert Research Institute (www.wrcc.dri.edu)


APPENDIX A

Permit Design Drawings

INTERMOUNTAIN REGIONAL LANDFILL

2020 PERMIT RENEWAL DRAWINGS

OCTOBER 2020




STATE OF UTAH



FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\G-1 COVER 16 FT NORTH.DWG
FILE DATE: 10/28/2020 13:44:26 (GMT)



859 W. South Jordan Pkwy. Ste. 200
South Jordan, Utah 84095
(801) 566-5599



FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\G-2 GENERAL NOTES.DWG
FILE DATE: 10/28/2020 13:48:57 (GAR)

GENERAL NOTES

NOTES:

1. COORDINATES PROVIDED ARE BASED ON THE MODIFIED STATE PLANE NAD 83 COORDINATE SYSTEM. (GROUND DATUM)
2. PROMPT NOTIFICATION SHALL BE PROVIDED TO THE STATE HISTORIC PRESERVATION OFFICE UPON DISCOVERY OF ANY ARCHEOLOGICAL OR BURIAL FINDINGS.
3. MONITORING WELLS SHALL BE PROTECTED FROM DAMAGE DURING CONSTRUCTION.
4. ALL AREAS TO BE CLEARED AND GRUBBED OF VEGETATION AND OTHER DEBRIS PRIOR TO FILL PLACEMENT.
5. SUBGRADES FOR FILLS TO BE MOISTURE CONDITIONED AND RECOMPACTED TO 95% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D-698 PRIOR TO FILL PLACEMENT.
6. ALL FILL MATERIAL TO BE COMPACTED TO 95% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D-698.
7. DRAWINGS ARE INTENDED FOR PERMIT PURPOSES ONLY. THEY ARE NOT INTENDED FOR CONSTRUCTION SINCE THE PARTICULAR PHASES FOR CONSTRUCTION HAVE NOT BEEN DEFINED HERE. HOWEVER, THESE DRAWINGS AND THEIR INCORPORATION INTO THE PERMIT DO CONSTITUTE APPROVAL OF THE OVERALL FLOOR AND CLOSURE DESIGNS TO THE EXTENTS SHOWN. THEREFORE, SUBMITTALS FOR PHASED CONSTRUCTION OF ADDITIONAL FLOOR SPACE OR PARTIAL CLOSURES WILL NOT REQUIRE PUBLIC COMMENT PERIODS DUE TO ALREADY BEING PART OF THE CURRENT PERMIT. ANY EXPANSION BEYOND THE CURRENTLY DEFINED BOUNDARIES, EITHER VERTICAL OR HORIZONTAL, WILL REQUIRE A MAJOR PERMIT MODIFICATION PROCESS INCLUDING THE CUSTOMARY PUBLIC COMMENT PERIOD.

INDEX OF DRAWINGS

SHEET NO.

GENERAL

- G-1 COVER SHEET
- G-2 GENERAL NOTES & LEGEND
- G-3 OVERALL SITE PLAN

LANDFILL

- LF-1 CELL FLOOR PLAN
- LF-2 LINER "TIE-IN" DETAILS

LEACHATE CONVEYANCE & REMOVAL SYSTEM (LCRS)

- LS-1 LEACHATE PIPE PLAN
- LS-2 LCRS DETAILS
- LS-3 SUMP PLAN & SECTIONS
- LS-4 SUMP PLANS & SECTIONS
- LS-5 LEACHATE WITHDRAWAL PIPE SECTIONS
- LS-6 LEACHATE WITHDRAWAL SYSTEM DETAILS

SHEET NO.

GAS SYSTEM

- GS-1 DETAILS

PHASING

- PH-1 PHASING DETAILS

CLOSURE

- CL-1 FINAL CLOSURE PLAN
- CL-2 SECTIONS & DETAILS


DRAINAGE SYSTEM

- DS-1 DOWNSPOUT DRAINAGE PLAN
- DS-2 DOWNSPOUT DETAILS


SECTION & DETAIL IDENTIFICATION

SECTION IDENTIFICATION

SECTION CUT ON DRAWING NO. 6 AND SHOWN ON DRAWING NO. 8 ON DRAWING NO. 6 THIS SECTION IS REFERENCED AS:




ON DRAWING NO. 8, THIS SECTION IS IDENTIFIED AS:




DETAIL IDENTIFICATION

DETAIL CALL-OUT ON DRAWING NO. 6 AND SHOWN ON DRAWING NO. 8 ON DRAWING NO. 6 THIS DETAIL IS REFERENCED AS:



ON DRAWING NO. 8, THIS DETAIL IS IDENTIFIED AS:




NOTES:

1. IF SECTION AND DETAILS ARE SHOWN ON THE SAME DRAWING AS SECTION CUTS AND SECTION OR DETAIL CALL-OUTS DRAWING NUMBER IS REPLACED BY A LINE.
2. DETAIL LETTERS "I" AND "O" NOT USED.

TABLE OF ABBREVIATIONS

| | | | |
|---------|---------------------------|--------|-------------------------------------|
| C.C. | CENTER TO CENTER | N. | NORTHING COORDINATE |
| ☉ | CENTER LINE | N.T.S. | NOT TO SCALE |
| CLR. | CLEAR | O.C. | ON CENTER |
| CPE | CORRUGATED POLYETHYLENE | OD | OUTSIDE DIAMETER |
| DIA. | DIAMETER | OZ. | OUNCE |
| E. | EASTING COORDINATE | PC | POINT OF CURVE |
| EL. | ELEVATION | PCPE | PERFORATED CORRUGATED POLYETHYLENE |
| FL | FLOW LINE | PI | POINT OF INTERSECTION |
| GCL | GEOSYNTHETIC CLAY LINER | PL | PLATE |
| HDPE | HIGH DENSITY POLYETHYLENE | PT | POINT OF TANGENT |
| ID | INSIDE DIAMETER | SCPE | SMOOTH WALL CORRUGATED POLYETHYLENE |
| INV EL. | INVERT ELEVATION | SDR | STANDARD DIMENSION RATIO |
| MAX. | MAXIMUM | STA. | STATION |
| MIN. | MINIMUM | TYP. | TYPICAL |




| | | | | | |
|----------|--------------|-----|------|-----------|-------|
| DESIGNED | TGA | 3 | | | |
| DRAFTED | CAH | 2 | | | |
| CHECKED | GLJ | 1 | | | |
| DATE | OCTOBER 2020 | NO. | DATE | REVISIONS | BY |
| | | | | | APVD. |

SCALE




**INTERMOUNTAIN
REGIONAL LANDFILL**


2020 PERMIT RENEWAL
GENERAL
GENERAL NOTES & LEGEND



FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\G-3 SITE PLAN.DWG
 FILE DATE: 10/28/2020 13:53:34 (CAT)



● EXISTING MONITORING WELL



| | | | | | | | | | |
|----------|--------------|-----|------|-----------|----|-------|--|--|--|
| DESIGNED | TGA | 3 | | | | | | | |
| DRAFTED | CAH | 2 | | | | | | | |
| CHECKED | GLJ | 1 | | | | | | | |
| DATE | OCTOBER 2020 | NO. | DATE | REVISIONS | BY | APVD. | | | |


SCALE
AS
SHOWN





**INTERMOUNTAIN
REGIONAL LANDFILL**

2020 PERMIT RENEWAL
GENERAL
OVERALL SITE PLAN

SHEET
G-3
373.02.101



FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\LF-1 FLOOR PLAN.DWG
 FILE DATE: 10/28/2020 13:54:47 (GMT)



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
AS SHOWN




**INTERMOUNTAIN
REGIONAL LANDFILL**


2020 PERMIT RENEWAL
LANDFILL
CELL FLOOR PLAN

SHEET
LF-1
373.02.101


FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\LF-2 LINER TIE IN DETAILS.DWG
 FILE DATE: 10.28.2020 13:55:27 (CAH)




TYPICAL FLOOR LINER TERMINATION TRENCH
N.T.S.




TYPICAL TOP SLOPE SECTION
N.T.S.



TYPICAL "TIE-IN" SECTION
N.T.S.



TYPICAL CELL FLOOR LINER SYSTEM SECTION
N.T.S.



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |


SCALE
AS SHOWN




INTERMOUNTAIN
REGIONAL LANDFILL

2020 PERMIT RENEWAL
LANDFILL
LINER "TIE-IN" DETAILS


SHEET
LF-2
373.02.101



FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\CAD\LS-1 LEACHATE PLAN.DWG
 FILE DATE: 10/28/2020 14:01:00 (CAT)



- NOTES:
- SEE SHEET LS-2 FOR TYPICAL LEACHATE PIPE DETAILS.
 - SEE SHEETS LS-5 & LS-6 FOR TYPICAL LEACHATE WITHDRAWAL PIPE DETAILS.



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
AS SHOWN




**INTERMOUNTAIN
REGIONAL LANDFILL**

2020 PERMIT RENEWAL
LCRS
LEACHATE PIPE PLAN

SHEET
LS-1
373.02.101

FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\LS-2 LINER AND LCRS SECTIONS.DWG
 FILE DATE: 10/28/2020 14:01:57 (CAH)




TYPICAL LEACHATE CONVEYANCE PIPE WRAP DETAIL

N.T.S.

NOTES:


- 1 1/2" MINUS WASHED DRAIN ROCK TO BE PLACED AROUND ALL PCPE PIPE AND CPE PIPE MATERIALS. A MINIMUM COVER OF 6 INCHES TO BE PROVIDED OVER PIPES.
- PCPE REFERS TO PERFORATED CORRUGATED POLYETHYLENE PIPE.
- FLOOR CONFIGURATION ALONG LEACHATE PIPE ALIGNMENT WILL VARY.



LEACHATE CONVEYANCE "TIE-IN" DETAIL

N.T.S.

10/07



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
AS SHOWN




INTERMOUNTAIN
REGIONAL LANDFILL

2020 PERMIT RENEWAL
LCRS
LCRS DETAILS

SHEET
LS-2

373.02.101


PROJECTS\373 INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\LS-3 SUMP PLAN.DWG
 FILE NAME: 10.28.2020 14:03:02 (GAR)
 10/07




- NOTES:
1. FILL ENTIRE SUMP WITH 1 1/2" MINUS WASHED DRAIN ROCK TO TOP OF SUMP.
 2. PCPE REFERS TO PERFORATED CORRUGATED POLYETHYLENE PIPE.
 3. SEE SHEET LS-2 FOR PCPE PIPE LCRS DETAILS.

NOTE:
 EXTEND EXTRA 60 MIL HDPE AND GCL TO TOP OF SUMP AND WELD TO LINER.


SUMP PLAN VIEW
 N.T.S. [A] [A] [LF-1] [LS-1]



SUMP CROSS SECTION
 N.T.S. [2] []



SUMP CROSS SECTION
 N.T.S. [1] []



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
 AS SHOWN











2020 PERMIT RENEWAL
 LCRS
 SUMP PLAN & SECTIONS

SHEET
LS-3
 373.02.101

PROJECTS: 373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\LS-4 SUMP PLANS.DWG
 FILE NAME: P:\028\2020\14-08-27 (CAR)
 10/07

- NOTES:
1. FILL ENTIRE SUMP WITH 1 1/2" MINUS WASHED DRAIN ROCK TO TOP OF SUMP.
 2. PCPE REFERS TO PERFORATED CORRUGATED POLYETHYLENE PIPE.
 3. SEE LS-2 FOR PCPE PIPE LCRS DETAILS.



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |


SCALE
 AS SHOWN




2020 PERMIT RENEWAL
 LCRS
 SUMP PLANS & SECTIONS

SHEET
 LS-4
 373.02.101

FILE NAME: PROJECTS\373 INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\LS-5 SUMP SECTION PIPE.DWG
 FILE DATE: 10.28.2020 14:09:45 (CAT)




SECTION 1
N.T.S.



SECTION 3
N.T.S.

LEACHATE CONVEYANCE PIPE OUTSIDE OF SUMP → SUMP AREA



DESIGNED TGA 3
 DRAFTED CAH 2
 CHECKED GLJ 1
 DATE OCTOBER 2020 NO. DATE

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
AS SHOWN





INTERMOUNTAIN
REGIONAL LANDFILL

2020 PERMIT RENEWAL
LCRS
LEACHATE WITHDRAWAL PIPE SECTIONS

SHEET
LS-5
373.02.101

FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\LS-6 LEACHATE WITHDRAWAL SYSTEM DETAILS.DWG
 FILE DATE: 10/28/2020 14:10:36 (CAH)



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
AS SHOWN




INTERMOUNTAIN
REGIONAL LANDFILL


2020 PERMIT RENEWAL
LCRS
LEACHATE WITHDRAWAL SYSTEM DETAILS

SHEET
LS-6
373.02.101


FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\GS-1 DETAILS.DWG
 FILE DATE: 10-28-2020 14:13:30 (CMT)




KNOCKOUT CONDENSATE REMOVAL DETAIL




BRANCH PIPE DETAIL




HEADER / BRANCH PIPE CONNECTION DETAIL



CONDENSATE HEADER / KNOCKOUT DETAIL



BRANCH PIPE DETAIL



DESIGNED TGA 3
 DRAFTED CAH 2
 CHECKED GLJ 1
 DATE OCTOBER 2020 NO. DATE

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
 NOT
 TO
 SCALE




**INTERMOUNTAIN
 REGIONAL LANDFILL**


2020 PERMIT RENEWAL
 GAS
 COLLECTION & CONTROL SYSTEM DETAILS

SHEET
GS-1
 373.02.101

FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\PH-1 PHASING SECTIONS.DWG
 FILE DATE: 10/28/2020 14:14:27 (CAT)




TYPICAL SOUTH TEMPORARY CONTAINMENT BERM DETAIL
 FOR CELLS 2 & 3 AS CELL EXPANSION PROGRESSES




TYPICAL EAST TEMPORARY EMBANKMENT DETAIL FOR CELLS
 2 & 3 AS CELL EXPANSION PROGRESSES

- NOTE:
1. ANCHOR TRENCH TO BE EXCAVATED WITH VERTICAL SIDES AS SHOWN OR MAY BE CONSTRUCTED AS A V-SHAPE TRENCH A MINIMUM OF 3' DEEP.
 2. EAST EMBANKMENT IS ONLY NECESSARY IF PHASED CONSTRUCTION PROCEEDS FROM WEST TO EAST. EAST TO WEST CONSTRUCTION WILL NOT REQUIRE A TEMPORARY EMBANKMENT.



LEACHATE CONVEYANCE PIPE TERMINATION AT EAST EMBANKMENT DETAIL



DESIGNED TGA 3
 DRAFTED CAH 2
 CHECKED GLJ 1
 DATE OCTOBER 2020 NO. DATE

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |


SCALE
 NOT
 TO
 SCALE




INTERMOUNTAIN
 REGIONAL LANDFILL

2020 PERMIT RENEWAL
 LANDFILL
 PHASING DETAILS


SHEET
 PH-1
 373.02.101



FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\CL-1 FINAL CLOSURE PLAN.DWG
 FILE DATE: 10/28/2020 14:18:21 (GMT)



NOTE:
 GENERAL DESIGN OF ACCESS RAMP IS BASED ON A 50 FT WIDE RAMP WITH A 12% MAXIMUM SLOPE, 2% CROSS SLOPE, AND VERTICAL CURVES DESIGNED TO ACCOMMODATE LOW CLEARANCE TRAILERS WITH A MEASURED LOADED CLEARANCE OF 8" (MEASURED BY LANDFILL EMPLOYEES). DETAILS NOT PRESENTED IN THIS DRAWING WILL BE PROVIDED AT THE TIME OF CONSTRUCTION.



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |


SCALE
 AS SHOWN




2020 PERMIT RENEWAL
 CLOSURE
 FINAL CLOSURE PLAN

SHEET
CL-1
 373.02.101

FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\CL-2 CLOSURE CAP DETAILS.DWG
 FILE DATE: 10.28.2020 14:20:34 (CAH)




STORM WATER CONTAINMENT BERM SECTION 1
 N.T.S. CL-1




TYPICAL CLOSURE CAP LAYER DETAIL A
 N.T.S. -


- NOTES:
 1. DRAIN PIPES UNDER STORM WATER CONTAINMENT BERMS AND UNDER BENCH DRAINAGE CHANNELS TO TIE INTO DOWN SPOUT INLET BOXES.



TYPICAL CLOSURE CAP BENCH DRAINAGE CHANNEL SECTION 2
 N.T.S. CL-1



TYPICAL 18" DIA. PIPE OUTLET DETAIL A A
 N.T.S. DS-1 DS-2



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |


SCALE
 AS SHOWN




INTERMOUNTAIN
 REGIONAL LANDFILL

2020 PERMIT RENEWAL
 CLOSURE
 SECTIONS & DETAILS


SHEET
 CL-2
 373.02.101



FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\DS-1 DOWNSPOUT DRAINAGE.DWG
 FILE DATE: 10/28/2020 14:23:40 (CAT)



➔ = RUNOFF FLOW DIRECTION ARROW



| | | |
|----------|--------------|-----|
| DESIGNED | TGA | 3 |
| DRAFTED | CAH | 2 |
| CHECKED | GLJ | 1 |
| DATE | OCTOBER 2020 | NO. |

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
AS SHOWN




**INTERMOUNTAIN
REGIONAL LANDFILL**


2020 PERMIT RENEWAL
DRAINAGE SYSTEM
DOWNSPOUT DRAINAGE PLAN

SHEET
DS-1
373.02.101


FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.101 - 2020 PERMIT RENEWAL\CAD\DS-2 DOWNSPOUT SECTION.DWG
 FILE DATE: 10.28.2020 14:24:34 (CAH)



TYPICAL BENCH DOWNSPOUT DETAIL B
 N.T.S. DS-1



TYPICAL TOP DOWNSPOUT DETAIL C
 N.T.S. DS-1



HANSEN ALLEN & LUCE
 ENGINEERS

DESIGNED TGA 3
 DRAFTED CAH 2
 CHECKED GLJ 1
 DATE OCTOBER 2020 NO. DATE

| NO. | DATE | REVISIONS | BY | APVD. |
|-----|------|-----------|----|-------|
| | | | | |

SCALE
 AS SHOWN



2020 PERMIT RENEWAL
 DRAINAGE SYSTEM
 DOWNSPOUT DETAILS

SHEET
DS-2
 373.02.101

APPENDIX B

Geotechnical Investigation

Prepared by:
Earthtec Testing & Engineering, P.C.

October 13, 2006



Earthtec Testing & Engineering, P.C.

133 North 1330 West
Orem, Utah - 84057
Phone (801) 225-5711
Fax (801) 225-3363

1596 W. 2650 S #108
Ogden, Utah - 84401
Phone (801) 399-9516
Fax (801) 399-9842

GEOTECHNICAL STUDY INTERMOUNTAIN REGIONAL LANDFILL FAIRFIELD, UTAH

Prepared By



133 North 1330 West
Orem, Utah 84057
(801) 225-5711

Job No. 062496

Prepared for

Mr David Johnston
P O Box 1503
Orem, Utah 84059

October 13 , 2006

Earthtec

| TABLE OF CONTENTS | | Page No. |
|-------------------|---------------------------------------|----------|
| 1 0 | INTRODUCTION | 1 |
| 2 0 | CONCLUSIONS | 1 |
| 3 0 | PROPOSED DEVELOPMENT | 2 |
| 4 0 | GENERAL SITE DESCRIPTION | 3 |
| 5 0 | SUBSURFACE INVESTIGATION | 3 |
| 5 1 | <u>Soil Exploration</u> | 3 |
| 5 2 | <u>Percolation Testing</u> | 4 |
| 6 0 | LABORATORY TESTING | 5 |
| 7 0 | SUBSURFACE CONDITIONS | 6 |
| 7 1 | <u>Soil Types</u> | 6 |
| 7 2 | <u>Groundwater</u> | 7 |
| 8 0 | SITE GRADING | 7 |
| 8 1 | <u>General Site Grading</u> | 7 |
| 8 2 | <u>Temporary Excavations</u> | 7 |
| 8 3 | <u>Fdl Matenal</u> | 8 |
| 8 4 | <u>Fill Placement and Compaction</u> | 8 |
| 9 0 | SEISMIC CONSIDERATIONS | 9 |
| 9 1 | <u>Faultmg</u> | 9 |
| 9 2 | <u>Liquefaction Potential</u> | 9 |
| 9 3 | <u>IRC Seismic Design Category</u> | 10 |
| 10 0 | FOUNDATIONS | 11 |
| 10 1 | <u>General</u> | 11 |
| 10 2 | <u>Estimated Settlement</u> | 12 |
| 11 0 | FLOOR SLABS | 13 |
| 12 0 | MOISTURE CONTROL AND SURFACE DRAINAGE | 13 |
| 13 0 | GENERAL CONDITIONS | 14 |

FIGURES

| | |
|-----------|--|
| No 1 | VICINITY MAP |
| No 2 | SITE PLAN AND LOCATION OF EXPLORATIONS |
| Nos 3-22 | TEST PIT LOG |
| Nos 23-24 | TEST HOLE LOGS |
| No 25 | LEGEND |
| Nos 26-30 | CONSOLIDATION-SWELL TEST |

TABLES

| | |
|------|-------------------------|
| No 1 | LABORATORY TEST RESULTS |
| No 2 | PAVEMENT SECTION DESIGN |



Earthtec Testing & Engineering, P.C.

133 North 1330 West
Orem, Utah - 84057
Phone (801) 225-5711
Fax (801) 225-3363

1596 W. 2650 S #108
Ogden, Utah - 84401
Phone (801) 399-9516
Fax (801) 399-9842

GEOTECHNICAL STUDY INTERMOUNTAIN REGIONAL LANDFILL FAIRFIELD, UTAH

Prepared By



133 North 1330 West
Orem, Utah 84057
(801) 225-5711

Job No. 062496

Prepared for

Mr David Johnston
P O Box 1503
Orem, Utah 84059

October 13 , 2006

Earthtec

| TABLE OF CONTENTS | | Page No |
|-------------------|---------------------------------------|---------|
| 1 0 | INTRODUCTION | 1 |
| 2 0 | CONCLUSIONS | 1 |
| 3 0 | PROPOSED DEVELOPMENT | 2 |
| 4 0 | GENERAL SITE DESCRIPTION | 3 |
| 5 0 | SUBSURFACE INVESTIGATION | 3 |
| 5 1 | <u>Soil Exploration</u> | 3 |
| 5 2 | <u>Percolation Testmg</u> | 4 |
| 6 0 | LABORATORY TESTING | 5 |
| 7 0 | SUBSURFACE CONDITIONS | 6 |
| 7 1 | <u>Soil Types</u> | 6 |
| 7 2 | <u>Groundwater</u> | 7 |
| 8 0 | SITE GRADING | 7 |
| 8 1 | <u>General Site Gradmg</u> | 7 |
| 8 2 | <u>Temporary Excavations</u> | 7 |
| 8 3 | <u>Fill Material</u> | 8 |
| 8 4 | <u>Fill Placement and Compaction</u> | 8 |
| 9 0 | SEISMIC CONSIDERATIONS | 9 |
| 9 1 | <u>Faultmg</u> | 9 |
| 9 2 | <u>Liquefaction Potential</u> | 9 |
| 9 3 | <u>IRC Seismic Design Category</u> | 10 |
| 10 0 | FOUNDATIONS | 11 |
| 10 1 | <u>General</u> | 11 |
| 10 2 | <u>Estimated Settlement</u> | 12 |
| 11 0 | FLOOR SLABS | 13 |
| 12 0 | MOISTURE CONTROL AND SURFACE DRAINAGE | 13 |
| 13 0 | GENERAL CONDITIONS | 14 |

FIGURES

| | |
|-----------|--|
| No 1 | VICINITY MAP |
| No 2 | SITE PLAN AND LOCATION OF EXPLORATIONS |
| Nos 3-22 | TEST PIT LOG |
| Nos 23-24 | TEST HOLE LOGS |
| No 25 | LEGEND |
| Nos 26-30 | CONSOLIDATION-SWELL TEST |

TABLES

| | |
|------|-------------------------|
| No 1 | LABORATORY TEST RESULTS |
| No 2 | PAVEMENT SECTION DESIGN |

1.0 INTRODUCTION

Earthtec has completed a geotechnical study for an approximately 1 square mile parcel located about 3 miles south of the town of Fairfield, Utah as shown on Figure No 1, *Vicinity Map*. We understand that it is proposed to construct a new solid waste landfill. This report presents our findings and geotechnical engineering recommendations for the proposed development.

The purposes of this study were to 1) evaluate the subsurface soil conditions at the site, 2) assess the engineering characteristics of the subsurface soils, and 3) provide geotechnical recommendations for general site grading and the design and construction of foundations, concrete floor slabs, miscellaneous concrete flatwork, and asphalt pavement sections. The scope of work completed for this study included field reconnaissance, subsurface investigation, field and laboratory soil testing, engineering analysis, and the preparation of this report.

2.0 CONCLUSIONS

The following is a brief summary of our findings and conclusions:

1. Our subsurface exploration included test pits excavated with a rubber tire backhoe, and test holes drilled with a hydraulic drill rig. In the test pits we observed approximately 12 to 24 inches of topsoil followed by Fat Clay (CH), Elastic Silt (MH), and a few layers of Silty Sand (SM), extending to the bottom of the test pits at about 10 to 11 feet below the existing surface. We also encountered topsoil at the surface of the test hole locations followed by Fat Clay (CH) extending to the bottom of the test holes at about 31½ to 41½ feet below the ground surface. Groundwater was not encountered in the test pits nor in the test holes.
2. Percolation tests were performed in Test Pits 2, 3, 5, 9, 16, 18, and 19 at depths of about 4½ to 6½ feet below the existing surface. Measured percolation rates ranged from 1½ to 24 minutes per inch, but slower rates would likely have been measured if the native soils had been saturated.
3. Vegetation should be removed from below areas that will be filled with debris. Where structures are planned, both the vegetation and topsoil should be completely removed from below foundation, floor slab, and exterior concrete.

flatwork areas. Soils in foundation areas disturbed during construction should also be removed or recompacted prior to placement of footings.

4. We estimate that a fill depth of 20 feet (with an estimated unit weight of 50 pcf for debris fill) will induce approximately 4 inches of consolidation settlement in the underlying native soils.
5. The majority of the subsurface clay soils were found to have high plasticity characteristics. Each of the consolidation test samples indicated swell potential of about 1 to 1½%. If allowed to become saturated after construction, these soils can swell under foundations and floor slabs causing distress and cracking. The drainage recommendations presented in Section 13.0 could be carefully followed if structures are planned.
6. Conventional strip and spread footings may be used to support proposed structures within this development. Foundations should be constructed entirely on undisturbed, uniform, native soils, or entirely on a minimum 36 inches of structural fill placed on undisturbed native soils. Footings constructed on the native soils should be designed for a minimum bearing capacity of 4,000 pcf. We also recommend a crawl space beneath floor slabs to minimize the potential for swelling soils to impact floor slabs. More details regarding foundation design can be found in Section 10.0 of this report.

These findings and conclusions should not be relied upon without reading and consulting this entire report for a more detailed description of the geotechnical evaluation and recommendations contained herein.

3.0 PROPOSED DEVELOPMENT

We understand that the site will be used as a landfill and understand that the landfill will handle mixed solid waste. We also anticipate that some associated structures will be constructed. We estimate that foundation loads for structures will not exceed 4 kips per linear foot for bearing walls, 30 kips for columns, and 150 pounds per square foot for floor slabs. If structural loads will be greater, our office should be notified so that we may review our recommendations and, if necessary, make modifications.

4.0 GENERAL SITE DESCRIPTION

At the time we conducted our subsurface explorations, the site for the proposed landfill was an approximately 1 square mile parcel vegetated with sage brush and weeds. No existing structures were observed. The ground surface appeared to be relatively flat. The site was bounded on the east, west, and south by fields, and on the north by a dirt road.

5.0 SUBSURFACE INVESTIGATION

5.1 Soil Exploration

Subsurface soil conditions at the site were investigated under the direction of a qualified member of our geotechnical staff. On September 7 and 8, 2006 a rubber tire backhoe was used to excavate 20 test pits extending to approximate depths of 10 to 11 feet below the existing surface. On September 27, 2006 we returned to the site with an all-terrain hydraulic drill rig and drilled 2 test holes to depths of about 31½ to 41½ feet below the existing surface. The approximate locations of the test pits and the test holes are shown on Figure No. 2 at the end of this report.

The soils exposed in the test pits, and the samples collected in the test holes, were classified by visual examination following the guidelines of the Unified Soil Classification System (USCS). In the test pits, disturbed bag samples and relatively undisturbed block samples of the subsurface soils were collected at various intervals. In the test holes disturbed samples were collected with a 1½ inch inside diameter spt spoon sampler. The spt spoon sampler was driven 18 inches into undisturbed soil with a 140 pound hammer free-falling through a distance of 30 inches. The blows required to drive the sampler through the final 12 inches of penetration is called the blow count, which is recorded on the attached test hole logs at the respective sample depths. When 50 blows were achieved for any 6-inch interval, sampling was stopped and the blows for each 6-inch interval (or less) are indicated on the logs. Relatively undisturbed samples were collected with thin walled "Shelby" tubes hydraulically pushed into the soil below the augers by the drill.

The collected samples were transported to our Orem, Utah laboratory where they will be retained for 30 days following the date of this report and then discarded, unless a written request for additional holding time is received prior to the 30 day limit.

5.2 Percolation Testing

To provide information regarding the permeability of the native soils we conducted percolation tests in several of the test pits as part of our subsurface explorations. The percolation tests were performed by digging a small hole into undisturbed soil with a shovel at the depth indicated, filling the hole with water, and measuring the rate of water loss with time. The tests were conducted several times and the final measured percolation rate is presented in the following table.

Table No. 2: Percolation Test Results

| TEST PIT NO | DEPTH (ft.) | SOIL TYPE | PERCOLATION RATE (min/inch) |
|-------------|-------------|-----------|-----------------------------|
| TP-2 | 6½ | SM | 1½ |
| TP 3 | 6 | CH | 3 |
| TP-5 | 6 | CH | 20 |
| TP-9 | 5 | CH | 6 |
| TP-16 | 6 | CH | 17 |
| TP 18 | 5 | CH | 9 |
| TP 19 | 4½ | CH | 24 |

These tests give a representation of how percolation rates may change across the site. The soils encountered in the test pits had high plasticity characteristics which would indicate these soils have the ability to absorb a significant amount of water. The percolation rates generally were still slowing when the final percolation test was conducted, and actual percolation rates would likely be much slower if the soils were saturated.

6.0 LABORATORY TESTING

From the samples collected in the test pits and test holes, representative samples were selected for laboratory testing to assess pertinent engineering properties and to aid in refining field classifications, if needed. Laboratory testing consisted of natural moisture content and dry density tests, one-dimensional consolidation tests, Atterberg limits determinations, and mechanical gradation analyses. The following table summarizes the results of the laboratory testing. Test results are also shown on the enclosed test pit and test hole logs at the respective sample depths, and on Figure Nos 26 through 30, *Consolidation-Swell Test*

Table No 1 • Laboratory Test Results

| TEST PIT/ HOLE NO | DEPTH (ft) | NATURAL MOISTURE (%) | NATURAL DRY DENSITY (pcf) | ATTERBERG LIMITS | | GRAIN SIZE DISTRIBUTION (%) | | | SOIL TYPE |
|-------------------------|---------------|----------------------------|------------------------------------|------------------|---------------------|--------------------------------|------|-----------------------|--------------|
| | | | | LIQUID LIMIT | PLASTICITY INDEX | GRAVEL #4 | SAND | SILT/ CLAY #200 | |
| TP-2 | 9 | 4 | -- | -- | -- | 0 | 75 | 25 | SM |
| TP-4 | 2½ | 19 | -- | 50 | 17 | -- | -- | -- | MH |
| TP-6 | 8 | 22 | -- | 63 | 41 | -- | -- | - | CH |
| TP-7 | 9 | 23 | 90 | 70 | 37 | -- | -- | -- | CH |
| TP-9 | 7 | 23 | -- | 73 | 50 | -- | -- | -- | CH |
| TP-10 | 8½ | 26 | 91 | 70 | 50 | -- | -- | -- | CH |
| TP-12 | 4 | 11 | -- | -- | -- | 0 | 37 | 63 | ML |
| TP-14 | 6 | 20 | 93 | 71 | 47 | -- | -- | -- | CH |
| TP-15 | 7½ | 19 | 93 | 61 | 37 | -- | -- | -- | CH |
| TP-16 | 8½ | 20 | -- | 70 | 46 | -- | -- | -- | CH |
| TP-18 | 9 | 22 | -- | 71 | 47 | -- | -- | -- | CH |
| TP-19 | 4 | 16 | -- | 53 | 28 | -- | -- | -- | CH |
| TP-20 | 3 | 16 | -- | 58 | 35 | -- | -- | -- | CH |
| TH-1 | 15 | 21 | 97 | 77 | 51 | -- | -- | -- | CH |
| TH-1 | 25 | 19 | -- | 52 | 26 | -- | -- | -- | CH |

Table No. 1 Laboratory Test Results continued

| TEST PIT NO | DEPTH (ft) | NATURAL MOISTURE (%) | NATURAL DRY DENSITY (pcf) | ATTERBERG LIMITS | | GRAIN SIZE DISTRIBUTION (%) | | | SOIL TYPE |
|-------------|------------|----------------------|---------------------------|------------------|------------------|-----------------------------|------|----------------|-----------|
| | | | | LIQUID LIMIT | PLASTICITY INDEX | GRAVEL #4 | SAND | SILT/CLAY #200 | |
| TH-2 | 20 | 13 | --- | 55 | 36 | --- | -- | -- | CH |
| TH-2 | 30 | 15 | --- | 55 | 33 | --- | -- | --- | CH |

7.0 SUBSURFACE CONDITIONS

7.1 Soil Types

At the locations of the test pits we encountered about 12 to 24 inches of topsoil at the surface. Subsurface soils were predominately fine-grained and consisted of Fat Clay (CH), Elastic Silt (MH), and a few layers of Silty Sand (SM) to Sandy Silt (ML), extending to the maximum depths explored in the test pits of approximately 10 to 11 feet below the existing ground surface.

At the locations of the test holes we also encountered topsoil at the surface which we estimated to extend about 18 inches in depth, followed by layers of Fat Clay (CH) extending to the bottom of the test holes at about 31½ to 41½ feet below the existing surface. The subsurface soils encountered in the test holes below those observed in the test pits were found to be very stiff to hard and the hydraulic drilling had considerable difficulty penetrating to the exploration depths.

Graphical representations and detailed descriptions of the soils encountered in the test pits and test holes are shown on Figure Nos 3 through 22, *Test Pit Log*, and Figure Nos 23 and 24, *Test Hole Log*, at the end of this report. The stratification lines shown on the logs represent the approximate boundary between soil units, the actual transition may be gradual. Due to potential natural variations inherent in soil deposits, care should be taken in interpolating between and extrapolating beyond exploration points. A key to the symbols and terms on the logs is presented on Figure No 25, *Legend*.

7.2 Groundwater

Groundwater was not encountered within the depths explored. Groundwater levels will fluctuate in response to the season, precipitation and snow melt, irrigation, and other on and off-site influences. Precisely quantifying these fluctuations would require long term monitoring.

8.0 SITE GRADING

8.1 General Site Grading

Vegetation should be removed from below the landfill areas. Unsuitable soils and vegetation should be removed from below foundation, floor slab, exterior concrete flatwork, and pavement areas to minimize the potential for distress and settlement. Unsuitable soils consist of: topsoil, organic soils, undocumented fill, soft, loose, or disturbed native soils, and any other inapt materials. Topsoil was encountered on the surface of the site which extended to depths of about 12 to 24 inches below the existing surface. The topsoil, including any soil containing roots larger than about 1/4 inch in diameter, and any other unsuitable soils, should be completely removed beneath building, flatwork, and pavement areas.

Fill placed over large areas, even if only a few feet in depth, can cause consolidation in the underlying native soils and settlement of the overlying fill. We assume that fairly deep fills will be placed on the site. For settlement estimates (See Section 10.2) we have assumed that the material placed and compacted in the landfill will have a density of about 50 pounds per cubic foot.

8.2 Temporary Excavations

For temporary excavations less than 5 feet in depth into the native soils or into structural fill, slopes should not be made steeper than 0.5:1.0 (horizontal:vertical). Temporary excavations extending up to 10 feet in depth should not be made steeper than 1:1. If unstable conditions or groundwater seepage are encountered, flatter slopes, shoring, or bracing may be required.

8.3 Fill Material

The native soils are not suitable for use as structural fill due to their generally high plasticity characteristics and difficulty controlling the moisture content needed to achieve the required compaction. These soils are also subject to swelling and shrinkage with changes in moisture content.

Structural fill should consist of imported material meeting the following requirements:

| | |
|--|------------|
| Maximum particle size | 4 inches |
| Percent retained on the 3/4 inch sieve (coarse gravel) | 30 maximum |
| Percent passing the No. 200 sieve (fines) | 15 maximum |
| Liquid Limit of fines | 35 maximum |
| Plasticity Index of fines | 15 maximum |

In some situations, particles larger than 4 inches and/or more than 30 percent coarse gravel may be acceptable, however, compaction and compaction testing may be more difficult. As a result, more strict quality control measures than normally used may be required. Such measures may include using thinner lifts, and increased or full time observation of fill placement.

Utility trench fill below structures, concrete flatwork, and asphalt paving should consist of structural fill as defined above.

8.4 Fill Placement and Compaction

The thickness of each lift should be appropriate for the compaction equipment that is used. We recommend a maximum lift thickness of 4 inches for hand operated equipment, 6 inches for most "trench compactors", and 8 inches for larger rollers, unless it can be demonstrated by in-place density tests that the required compaction can be obtained throughout a thicker lift. The full thickness of each lift of structural fill placed should be compacted to at least the following percentages of the maximum dry density, as determined by ASTM D-1557:

| | |
|---|-----|
| In landscape areas not supporting structural loads | 90% |
| Less than 5 feet of fill below foundations, flatwork and pavements | 95% |
| Five or more feet of fill below foundations, flatwork and pavements | 98% |

Generally, placing and compacting fill at a moisture content within 2% of the optimum moisture content, as determined by ASTM D-1557, will facilitate compaction. Typically, the further the moisture content is from optimum the more difficult it will be to achieve the required compaction.

Fill should be tested frequently during placement and early testing (initial lift) is recommended to demonstrate that placement methods and compaction efforts are achieving the required compaction. It is the contractor's responsibility to ensure that fill materials and compaction efforts are consistent so that tested areas are representative of the entire fill.

9.0 SEISMIC CONSIDERATIONS

9.1 Faulting

Based on published data no active faults are known to traverse the site and no surficial evidence of faulting was observed during our field investigation. The nearest mapped¹ fault trace considered to be active is one of a group of faults located beneath Utah Lake and is located approximately 12 miles east of the site.

9.2 Liquefaction Potential

The site appears to be located in an area mapped by the Utah Geological Survey² as having very low liquefaction potential. Liquefaction is a phenomenon where a soil loses intergranular strength due to an increase in soil pore water pressures during a dynamic event such as an earthquake. The potential for liquefaction is based on several factors, including 1) the grain size

¹Hecker, S., 1993, Quaternary Faults and Folds, Utah, Utah Geologic Survey, Bulletin 127

²Liquefaction Potential Map, Utah Geological Survey, Public Information Series 25, 1994

distribution of the soil, 2) the plasticity of the fine fraction of the soil (material passing the No. 200 sieve), 3) relative density of the soil, 4) earthquake strength (magnitude) and duration, and 5) overburden pressures. In addition, the soils must be saturated for liquefaction to occur. As a part of this investigation, the potential for liquefaction to occur in the soils we observed was assessed.

Loose, saturated sands are most susceptible to liquefaction, but soft, sensitive silt soils also have the potential to experience failure and movement during a seismic event. Sand soils encountered in the test pits were unsaturated, and the remainder of the soils were predominately composed of Fat Clay (CH), typically considered non-liquefiable. These conditions, in our opinion, support the very low liquefaction potential designation.

9.3 IRC Seismic Design Category

The Site Class definitions in the International Building Code (IBC) are based upon the soil properties in the upper 100 feet of the soil profile. These properties are determined from SPT blow counts and undrained shear strength measurements. The code states that "Where site specific data are not available to a depth of 100 feet, appropriate soil properties may be estimated by the registered design professional preparing the soils report." We estimate the soils encountered in the test pits and test holes have properties consistent with those defined by Site Class D.

The site is located at approximately 40° 21' latitude and -112° 07' longitude. Using Site Class D, the design spectral response acceleration parameters are 0.55 g for S_{DS} and 0.31 g for S_{D1} , for short and one second periods, respectively. The intermediate values from the IBC used to obtain the design parameters are contained in Table Nos. 2 and 3 below.

Table No. 2: Design Acceleration for Short Period

| S_s | F_a | S_{MS} | S_{DS} |
|--------|-------|--------------------|-----------------------|
| | | $S_{MS} = F_a S_s$ | $S_{DS} = 2/3 S_{MS}$ |
| 0.65 g | 1.28 | 0.83 g | 0.55 g |

S_s = The mapped spectral accelerations for short periods from Figure 1615(5)
 F_a = Site coefficient from Table 1615.1.2(1)
 S_{MS} = The maximum considered earthquake spectral response accelerations for short periods
 S_{DS} = Five-percent damped design spectral response acceleration at short periods

Table No. 3: Design Acceleration for 1 Second Period

| S_1 | F_v | S_{M1} | S_{D1} |
|--------|-------|--------------------|-----------------------|
| | | $S_{M1} = F_v S_1$ | $S_{D1} = 2/3 S_{M1}$ |
| 0.24 g | 1.92 | 0.46 g | 0.31 g |

S_1 = The mapped spectral accelerations for 1-second period from Figure 1615(6)
 F_v = Site coefficient from Table 1615.1.2(2)
 S_{M1} = The maximum considered earthquake spectral response accelerations for 1 second period
 S_{D1} = Five-percent damped design spectral response acceleration at 1 second period

10.0 FOUNDATIONS

10.1 General

The foundation recommendations presented in this report are based on the soil conditions observed in the test pits, the results of laboratory testing of samples of the native soils, the site grading recommendations presented in this report, and the foundation loading conditions presented in Section 3.0, *Proposed Construction*, of this report. If loading conditions are significantly different, we should be notified in order to re-evaluate our design parameters and estimates, and to provide additional recommendations if necessary.

Conventional strip and spread footings may be used to support proposed structures. Foundations should not be installed on topsoil, disturbed native soils, undocumented fill, debris, combination soils (structural fill/native soil combinations), frozen soil, or in ponded water. If foundation soils become disturbed during construction they should be removed or recompacted until firm.

The native soils have a potential to swell when wetted. Foundations constructed directly on undisturbed, uniform native soils should be designed for a minimum bearing pressure of 4,000 psf to help counter potential swell pressures which could develop if the native soils are allowed to become saturated. As an alternative, native soils directly below footings could be over excavated a minimum of 36 inches and replaced with compacted structural fill and footings designed for a maximum bearing capacity of 4,000 psf. The recommendations given in Section 13.0 below should also be carefully followed to minimize the potential for foundation soils to become saturated.

A representative from Earthtec should observe the soil conditions in foundation excavations if soil conditions differing from those described in this report are encountered. Other general footing design parameters are as follows:

| | |
|---|------------|
| Minimum embedment for frost protection | 30 inches |
| Minimum strip footing width | 20 inches |
| Minimum spot footing width | 30 inches |
| Bearing pressure increase for transient loading | 33 percent |

Structural fill used below foundations should extend laterally a minimum of 12 inches for every 12 vertical inches of structural fill placed. For example, if 36 inches of structural fill are required to bring the excavation to footing grade, the structural fill should extend laterally a minimum of 36 inches beyond the edge of the footings.

10.2 Estimated Settlement

For structures, if the proposed foundations are properly designed and constructed using the parameters provided above, total settlement for non-earthquake conditions is estimated not to exceed one inch. Differential settlement is anticipated to be one-half of the total settlement over a 25-foot length of foundation. Additional movements could occur during an earthquake due to ground shaking, or if foundation soils become saturated.

We estimate that consolidation settlement of about 4 inches will occur under the weight of 20 feet of debris fill. Deeper fill depths could cause additional settlement.

11.0 FLOOR SLABS

The swell potential of the native soils could have the most detrimental impact to floor slabs if allowed to become saturated after construction. To minimize this potential we recommend that crawl-spaces be constructed between the floor slabs and the native soils. Suspended concrete floor slabs would require proper design by a structural engineer.

For exterior concrete flat work, to facilitate construction, act as a capillary break, and aid in distributing loads we recommend that exterior flatwork be underlaid by four inches of free-draining granular material such as "pea" gravel or three-quarters to one-inch minus clean gravel supported on native soils or structural fill.

Special precautions should be taken during placement and curing of all concrete slabs and flatwork. Excessive slump (high water-cement ratios) of the concrete and/or improper finishing and curing procedures used during hot or cold weather conditions may lead to excessive shrinkage, cracking, spalling, or curling of slabs. We recommend all concrete placement and curing operations be performed in accordance with American Concrete Institute (ACI) codes and practices.

12.0 MOISTURE CONTROL AND SURFACE DRAINAGE

The native subsurface soils were found to have high plasticity characteristics and a potential to swell when wetted. To minimize the potential for subsurface soils to become wetted below and adjacent to any structures constructed at this site we recommend that the following precautions be taken:

- 1 Adequate compaction of foundation backfill should be provided i e a minimum of 90% of ASTM D-1557 Water consolidation methods should not be used
- 2 The ground surface should be graded to drain away from structures in all directions We recommend a minimum fall of 8 inches in the first 10 feet More slope may be needed in areas where settlement due to debris fill will occur
- 3 Roof runoff should be collected in rain gutters with down spouts designed to discharge well outside of the backfill limits, or at least 10 feet from foundations, whichever is greater
- 4 Sprinklers should be aimed away from foundation walls and sprinkler heads, lines, and valves should be kept at least 5 feet from foundations Sprinkler systems should be well maintained, checked for leaks frequently, and repaired promptly Over watering should be avoided and consideration should be given to minimizing lawn areas
- 5 Any additional precautions which may become evident during construction

13.0 GENERAL CONDITIONS

The exploratory data presented in this report was collected to provide geotechnical design recommendations for this project The test pits and test holes may not be indicative of subsurface conditions outside the study area or between points explored and thus have a limited value in depicting subsurface conditions for contractor bidding Variations from the conditions portrayed in the test pits and test holes may occur and may be sufficient to require modifications in the design If during construction, conditions are different than presented in this report, please advise us so that the appropriate modifications can be made

The geotechnical study as presented in this report was conducted within the limits prescribed by our client, with the usual thoroughness and competence of the engineering profession in the area No other warranty or representation, either expressed or implied, is intended in our proposals, contracts or reports

**Geotechnical Study
Intermountain Regional Landfill
Fairfield, Utah**

Page 15

We appreciate the opportunity of providing our services on this project. If we can answer questions or be of further service, please call

Respectfully,

EARTHTEC TESTING AND ENGINEERING, P.C

Jeffrey J Egbert, P E
Project Geotechnical Engineer


William G Turner, P E
Senior Geotechnical Engineer

Earthtec

Professional Engineering Services - Geotechnical Engineering - Drilling Services - Construction Materials Inspection / Testing - Non-Destructive Examination - Failure Analysis
ICBO - ACI - AWS

VICINITY MAP

INTERMOUNTAIN REGIONAL LANDFILL




PROJECT NO 062496



FIGURE NO. 1

SITE PLAN & LOCATION OF EXPLORATIONS

INTERMOUNTAIN REGIONAL LANDFILL



TEST PIT LOG

NO.: TP- 1

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USGS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cent (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, light brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY, some sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | CH | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | X | | | | | | | | | |
| 7 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | | |
| 8 | | SM | | X | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | FAT CLAY with sand, very stiff, moist, gray | | | | | | | | | | |
| 11 | | CH | | X | | | | | | | | | |
| 12 | | | Bottom at approximately 11 feet | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO.: 062496



FIGURE NO 3

LOG OF TESTPIT 062496 GPJ EARTHTEC.GDT 4/12/07

TEST PIT LOG

NO.: TP- 2

PROJECT Intermountam Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO . 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇ .

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, minor pinholes, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | X | | | | | | | | | |
| 4 | | CH | | | | | | | | | | | |
| 5 | | | | X | | | | | | | | | |
| 6 | | | | | | | | | | | | | |
| 7 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | | |
| 8 | | SM | | | | | | | | | | | |
| 9 | | | | X | 4 | | | 0 | 75 | 25 | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolodation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO . 062496



FIGURE NO 4

TEST PIT LOG

NO.: TP- 3

PROJECT Intermountain Regional Landfill
CLIENT. David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT. RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE: 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, very stiff, slightly moist, gray-brown | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | CH | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | X | | | | | | | | | |
| 7 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | | |
| 8 | | SM | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | X | | | | | | | | | |
| | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 5

LOG OF TESTPIT 062496.GPJ EARTHTEC.GDT 4/12/07

TEST PIT LOG

NO.: TP- 4

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY. P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | |
| 3 | | | ELASTIC SILT with sand, minor pinholes, very stiff, slightly moist, gray | X | 19 | | 50 | 17 | | | | |
| 4 | | MH | | | | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | |
| 7 | | | | X | | | | | | | | |
| 8 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | |
| 9 | | SM | | | | | | | | | | |
| 10 | | | | X | | | | | | | | |
| 11 | | | Bottom at approximately 10 feet. | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO. 062496



FIGURE NO 6

LOG OF TESTPIT_062496.GPJ EARTHTEC.GDT 4/12/07

TEST PIT LOG

NO.: TP- 5

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇ .

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | Perc |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | X | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GFI EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 7

TEST PIT LOG

NO.: TP- 6

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION: NM
LOGGED BY: P E

AT COMPLETION ▽ .

| Depth (Ft.) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|-------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, pockets of white sand, very stiff, slightly moist, gray | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | |
| 5 | | | | X | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | X | 22 | | 63 | 41 | | | | |
| 9 | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO · 8

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP- 7

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ▽

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | FAY CLAY with sand, very stiff, slightly moist to moist, gray | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | |
| 5 | | | | X | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | | | | | 23 | 90 | 70 | 37 | | | | C |
| 11 | | | Bottom at approximately 10 feet | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 9

TEST PIT LOG

NO.: TP- 8

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 10

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP- 9

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION. Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇ .

PROJECT NO 062496
DATE. 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | |
| 3 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 4 | | | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | X | 23 | | 73 | 50 | | | | | |
| 11 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 11

TEST PIT LOG

NO.: TP-10

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | |
| 9 | | | | | | 26 | 91 | 70 | 50 | | | C |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes. No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496.GPJ EARTHTEC GBT 4/12/07

PROJECT NO • 062496



FIGURE NO 12

TEST PIT LOG

NO.: TP-11

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION. Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE. 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | |
| 3 | | | FAT CLAY with sand, some layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | Minor pinholes at 8.5 feet | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 13

TEST PIT LOG

NO.: TP-12

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO. 062496
DATE. 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 1 | | | | | | | | | | | | | | |
| 2 | | | Sandy SILT, stiff, slightly moist, brown | | | | | | | | | | | |
| 3 | | ML | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | |
| 5 | | CH | FAT CLAY with sand, very stiff, slightly moist to moist, gray-brown | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | |
| 11 | | | Bottom at approximately 10 feet | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |

Notes. No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 14

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP-13

PROJECT Intennountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO · 062496
DATE · 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft.) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|-------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, minor pinholes, very shff, slightly moist, white | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | X | | | | | | | | |
| 5 | | | Moist, gray-brown at 4 feet, | X | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | X | | | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 15

TEST PIT LOG

NO.: TP-14

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY: P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|---------|---------------------------------|----------------|----|----|------------|----------|-----------|-------------|--|---|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | ▽▽ | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 1 | ▽▽ | | FAT CLAY with sand, minor pinholes, very stiff, slightly moist, white | | | | | | | | | | | |
| 2 | ▨ | CH | Moist, gray at 4 feet | | | | | | | | | | | |
| 3 | ▨ | | | | | | | | | | | | | |
| 4 | ▨ | | | | | X | | | | | | | | |
| 5 | ▨ | | | | | | | | | | | | | |
| 6 | ▨ | | | | | | █ | 20 | 93 | 71 | 47 | | | C |
| 7 | ▨ | | | | | | | | | | | | | |
| 8 | ▨ | | | | | | | | | | | | | |
| 9 | ▨ | | | | | | X | | | | | | | |
| 10 | ▨ | | | | | | | | | | | | | |
| 11 | | | | | Bottom at approximately 10 feet | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |

Notes: No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO. 16

TEST PIT LOG

NO.: TP-15

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER; INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|---------|-----------------------|----------------|----|----|------------|----------|-----------|-------------|--|---|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 1 | | | | | | | | | | | | | | |
| 2 | | CH | FAT CLAY with sand, minor pinholes, very stiff, slightly moist, light brown | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | |
| 5 | | | | | Moist, gray at 5 feet | X | | | | | | | | |
| 6 | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | |
| 8 | | | | | | █ | 19 | 93 | 61 | 37 | | | | C |
| 9 | | | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key
 CBR = California Bearing Ratio
 C = Consolidation
 R = Resistivity
 DS = Direct Shear
 SS = Soluble Sulfates
 UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 17

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP-16

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇.

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, very stiff, slightly moist, light brown | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | Moist, gray at 4 feet | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | Perc |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | X | 20 | | 70 | 46 | | | | | |
| 10 | | | Bottom at approximately 10 feet. | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 OF J EARTHTEC 09/07 4/12/07

PROJECT NO : 062496



FIGURE NO 18

TEST PIT LOG

NO.: TP-17

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇.

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | |
| 3 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray-brown | | | | | | | | | | |
| 4 | | | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | X | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | |
| | | | Bottom at approximately 10 feet | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO. 062496



FIGURE NO. 19

TEST PIT LOG

NO.: TP-18

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | | | |
|------------|-------------|------|---|---------|----------------|---------------------------------|----|----|------------|----------|-----------|-------------|--|--|--|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | | | |
| 1 | | | FAT CLAY with sand, minor pinholes, very stiff, slightly moist, light brown | | | | | | | | | | | | | |
| 2 | | CH | Moist, gray at 5 feet | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | |
| 5 | | | | | | | X | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | | |
| 10 | | | | | | | X | 22 | | 71 | 47 | | | | | |
| 11 | | | | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC 09/07 4/12/07

PROJECT NO 062496



FIGURE NO 20

TEST PIT LOG

NO.: TP-19

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|--------------|----------------|----------------|----|----|------------|----------|-----------|-------------|------|
| | | | | Samples | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | FAT CLAY with sand, very stiff, slightly moist, light brown | | | | | | | | | | |
| 2 | | | Moist, gray at 3 feet | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | X | 16 | | 53 | 28 | | | | | Perc |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | X | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 G.F.J. EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO. 21

TEST PIT LOG

NO.: TP-20

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR: Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|--|---------------------------------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | FAT CLAY with sand, very stiff, slightly moist, light brown Moist, gray at 5 feet CH | | | | | | | | | | |
| 2 | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | X | 16 | | 58 | 35 | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | X | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | Bottom at approximately 10 feet | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 22

TEST HOLE LOG

NO.: TH-1

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basm
EQUIPMENT Mobile A T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE: 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----------------|----|----|------------|----------|-----------|-------------|---|
| | | | | | Blows per feet | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | ▽▽▽ | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 3 | ▨▨▨ | | FAT CLAY with sand, stiff to hard, slightly moist to moist, brown | | | | | | | | | | | |
| 6 | ▨▨▨ | | | | 25 | | | | | | | | | |
| 9 | ▨▨▨ | | | | 26 | | | | | | | | | |
| 12 | ▨▨▨ | | | | 35 | | | | | | | | | |
| 15 | ▨▨▨ | CH | | | 15 | | | | | | | | | |
| 18 | ▨▨▨ | | | | | 21 | 97 | 77 | 51 | | | | | C |
| 21 | ▨▨▨ | | | | 40 | | | | | | | | | |
| 24 | ▨▨▨ | | | | | | | | | | | | | |

Notes. No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO: 062496



FIGURE NO 23a

LOG OF TESTHOLE 062496.GPJ EARTHTEC.GDT 4/12/07

TEST HOLE LOG

NO.. TH-1

PROJECT Intermountam Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basm
EQUIPMENT Mobile A.T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▽ :

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------------|------|---|-------------------|---------------------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Blows per foot | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 27 | [Hatched Pattern] | CH | FAT CLAY with sand, stiff to hard, slightly moist to moist, brown | [Hatched Pattern] | 20 | 19 | | 52 | 26 | | | | |
| 30 | | | | | 17 35 50/5.5" | | | | | | | | |
| 33 | | | Bottom at approximately 31 feet 5 5 inches | | | | | | | | | | |
| 36 | | | | | | | | | | | | | |
| 39 | | | | | | | | | | | | | |
| 42 | | | | | | | | | | | | | |
| 45 | | | | | | | | | | | | | |
| 48 | | | | | | | | | | | | | |

Notes: No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolhdation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO. 062496



FIGURE NO. 23b

LOG OF TESTHOLE 062496 GPJ EARTHTEC GDT 4/12/07

TEST HOLE LOG

NO.: TH-2

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basin
EQUIPMENT Mobile A T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▽ :

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|--|
| | | | | | Blows per foot | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | | |
| 3 | | CH | FAT CLAY with sand, hard to very stiff, slightly moist to moist, brown | | | | | | | | | | | | |
| 6 | | | | 47 | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | |
| 12 | | | | 24 | | | | | | | | | | | |
| 15 | | | | 45 | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | | | |
| 21 | | | | 38 | 13 | | 55 | 36 | | | | | | | |
| 24 | | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTHOLE 062496 G/F J EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 24a


TEST HOLE LOG

NO.: TH-2

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basn
EQUIPMENT Mobile A T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE: 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▽

| Depth (Ft) | Graphic Log | USGS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|--|------|--|---------|----------------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Blows per foot | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 27 |  | CH | FAT CLAY with sand, hard to very stiff, slightly moist to moist, brown | | | | | | | | | | | |
| 30 | | | | | | | | | | | | | | |
| 33 | | | | | | | | | | | | | | |
| 36 | | | | | | | | | | | | | | |
| 39 | | | | | | | | | | | | | | |
| 42 | | | Bottom at approximately 41 feet 5 5 inches | | | | | | | | | | | |
| 45 | | | | | | | | | | | | | | |
| 48 | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTHOLE 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO · 062496



FIGURE NO 24b

LEGEND

PROJECT Intermountain Regional Landfill
CLIENT David Johnston

DATE 09/07/06
LOGGED BY P E

UNIFIED SOIL CLASSIFICATION SYSTEM

USCS
MAJOR SOIL DIVISIONS **SYMBOL** **TYPICAL SOIL DESCRIPTIONS**

| | | | | | | |
|--|---|--|--|---|---|---|
| COARSE GRAINED SOILS (More than 50% retaining on No 200 Sieve) | GRAVELS (More than 50% of coarse fraction retained on No 4 Sieve) | CLEAN GRAVELS (Less than 5% fines) | | GW | Well Graded Gravel, May Contain Sand, Very Little Fines | |
| | | GRAVELS WITH FINES (More than 12% fines) | | GP | Poorly Graded Gravel, May Contain Sand, Very Little Fines | |
| | | SANDS (50% or more of coarse fraction passes No 4 Sieve) | CLEAN SANDS (Less than 5% fines) | | SW | Well Graded Sand, May Contain Gravel, Very Little Fines |
| | | | SANDS WITH FINES (More than 12% fines) | | SP | Poorly Graded Sand, May Contain Gravel, Very Little Fines |
| | FINE GRAINED SOILS (More than 50% passing No 200 Sieve) | SILTS AND CLAYS (Liquid Limit less than 50) | | CL | Lean Clay, Inorganic, May Contain Gravel and/or Sand | |
| | | | | ML | Silt, Inorganic, May Contain Gravel and/or Sand | |
| | | | | OL | Organic Silt or Clay, May Contain Gravel and/or Sand | |
| | | SILTS AND CLAYS (Liquid Limit Greater than 50) | | CH | Fat Clay, Inorganic, May Contain Gravel and/or Sand | |
| | | | MH | Elastic Silt, Inorganic, May Contain Gravel and/or Sand | | |
| | | | OH | Organic Clay or Silt, May Contain Gravel and/or Sand | | |
| HIGHLY ORGANIC SOILS | | | | PT | Peat, Primarily Organic Matter | |

SAMPLER DESCRIPTIONS

- SPLIT SPOON SAMPLER
(1 3/8 inch inside diameter)
- MODIFIED CALIFORNIA SAMPLER
(2 inch outside diameter)
- SHELBY TUBE
(3 inch outside diameter)
- BLOCK SAMPLE
- BAG/BULK SAMPLE

WATER SYMBOLS

- Water level encountered during field exploration
- Water level encountered at completion of field exploration


- NOTES:**
- 1 The logs are subject to the limitations, conclusions, and recommendations in this report
 - 2 Results of tests conducted on samples recovered are reported on the logs and any applicable graphs
 - 3 Strata lines on the logs represent approximate boundaries only Actual transitions may be gradual
 - 4 In general, USCS symbols shown on the logs are based on visual methods only actual designations (based on laboratory tests) may vary

PROJECT NO 062496



FIGURE NO · 25

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intennountain Regional Landfill |
| Location | TP-7 |
| Sample Depth | 9 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 90 |
| Natural Moisture, % | 23 |
| Liquid Limit | 70 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 15 |

PROJECT NO 062496



FIGURE NO 26

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-10 |
| Sample Depth | 8½ |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 91 |
| Natural Moisture, % | 26 |
| Liquid Limit | 70 |
| Plasticity Index | 50 |
| Water Added at | 1 ksf |
| Percent Swell | 1.1 |

PROJECT NO 062496



FIGURE NO 27

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-14 |
| Sample Depth | 6 |
| Description | Block |
| Soil Type | FTA CLAY (CH) |
| Dry Density, pcf | 93 |
| Natural Moisture, % | 20 |
| Liquid Limit | 71 |
| Plasticity Index | 47 |
| Water Added at | 1 ksf |
| Percent Swell | 0.9 |

PROJECT NO 062496



FIGURE NO 28

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-15 |
| Sample Depth | 7½ |
| Description | Block |
| Soil Type | FTA CLAY (CH) |
| Dry Density, pcf | 93 |
| Natural Moisture, % | 19 |
| Liquid Limit | 61 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 0.9 |

PROJECT NO 062496



FIGURE NO 29

CONSOLIDATION - SWELL TEST



| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TH-1 |
| Sample Depth | 15 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 97 |
| Natural Moisture, % | 21 |
| Liquid Limit | 77 |
| Plasticity Index | 51 |
| Water Added at | 1 ksf |
| Percent Swell | 0.7 |

PROJECT NO 062496



FIGURE NO 30

APPENDIX C

Slope Stability and Settlement Analysis

Prepared by:
HDR Engineering, Inc.

August, 2010

SLOPE STABILITY AND SETTLEMENT ANALYSIS

INTERMOUNTAIN REGIONAL LANDFILL
FAIRFIELD, UTAH

CLASS I LANDFILL PERMIT APPLICATION

ISSUED AUGUST 2010
PREPARED BY
HDR ENGINEERING, INC

TABLE OF CONTENTS

| | | |
|-------------|--|---|
| SECTION 1 0 | INTRODUCTION | 1 |
| | 1 1 PURPOSE | 1 |
| | 1 2 SCOPE | 1 |
| SECTION 2 0 | SITE CONDITIONS | 2 |
| | 2 1 LOCATION | 2 |
| | 2 2 SOILS | 2 |
| | 2 3 SEISMICITY | 2 |
| | 2 4 ADOPTED DESIGN VALUES | 2 |
| SECTION 3 0 | STATIC AND PSEUDO-STATIC STABILITY ANALYSES AND DEFORMATION ANALYSES | 4 |
| | 3 1 METHOD OF ANALYSIS | 4 |
| | 3 2 CASES CONSIDERED | 4 |
| | 3 2 1 MAXIMUM CUT SLOPE (EXCAVATION) | 4 |
| | 3 2 2 MAXIMUM FILL SLOPE (WASTE) | 4 |
| | 3 2 3 WASTE FILL OVER LINER AND LEACHATE COLLECTION SYSTEM (SLIDING BLOCK) | 4 |
| | 3 3 METHODOLOGY | 4 |
| SECTION 4 0 | SETTLEMENT AND LINER STRAIN | 6 |
| | 4 1 SETTLEMENT | 6 |
| | 4 2 LINER STRAIN | 6 |
| SECTION 5 0 | FINDINGS AND CONCLUSIONS | 7 |
| | 5 1 FINDINGS | 7 |
| | 5 2 CONCLUSIONS | 7 |
| SECTION 6 0 | REFERENCES | 8 |

ATTACHMENTS

| | |
|-----------------|---|
| ATTACHMENT 1 | MAXIMUM HORIZONTAL ACCELERATION & DESIGN EARTHQUAKE |
| ATTACHMENT 1A | USGS MAPPING, REFERENCE B |
| ATTACHMENT 1B | SOIL CONSISTENCY, REFERENCE D |
| ATTACHMENT 2 | SLOPE STABILITY CASES AND RUNS |
| ATTACHMENT 2A | PLAN VIEWS, CROSS SECTIONS, AND DETAILS |
| ATTACHMENT 2B | DISPLACEMENT CHART, REFERENCE A |
| ATTACHMENT 2C | SLOPE STABILITY RUNS & RESULTS |
| ATTACHMENT 2C-1 | SLOPE STABILITY RUNS & RESULTS – CUT SLOPE |
| ATTACHMENT 2C-2 | SLOPE STABILITY RUNS & RESULTS – FILL SLOPE |
| ATTACHMENT 2C-3 | SLOPE STABILITY RUNS & RESULTS – WASTE MASS SLIDING BLOCK |
| ATTACHMENT 3 | SETTLEMENT CALCULATIONS |
| ATTACHMENT 3A | SETTLEMENT AND CONSOLIDATION CALCULATIONS |

SECTION 1.0 INTRODUCTION

1.1 PURPOSE

This technical memorandum presents the results of slope stability and settlement analyses as part of the 2010 Permit Application for the Intermountain Regional Landfill (the Site) in Fairfield, Utah. The purpose of this work is to

- Evaluate the stability of the maximum cut and fill slopes
- Evaluate the settlement along the leachate collection and recovery system (LCRS) piping alignments

The Site is located in a seismic impact zone as defined by the State of Utah Administrative Code (UAC) R315-301-2. This report provides analyses demonstrating that "all containment structures, including liners, leachate collection systems, and surface water control systems, are designed to resist the maximum horizontal acceleration in lithified earth material for the site." In addition, this report provides analyses demonstrating that the LCRS piping alignment maintains positive drainage toward the sumps.

These analyses have been conducted in accordance with the State of Utah Administrative Code and U.S. Environmental Protection Agency (EPA) guidance presented in Resource Conservation and Recovery Act (RCRA) Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities (EPA 1995).

1.2 SCOPE

The scope of this report includes a literature review of regional and local seismicity, demonstration analyses of the seismic performance and settlement of the site features, and findings and conclusions. This report is divided into the following sections:

- Section 2.0, Site Conditions, presents soils, geology, and site-specific seismicity data for the Site.
- Section 3.0, Static and Pseudo-Static Stability Analyses and Deformation Analyses, presents stability analyses for maximum cut and maximum fill slopes.
- Section 4.0, Settlement and Liner Strain, presents estimates of settlement along the LCRS piping alignment.
- Section 5.0, Findings and Conclusions, discusses the impact of the estimated deformations and settlement on the function of the landfill features.

SECTION 2.0 SITE CONDITIONS

2.1 LOCATION

The Site is located in Township 7 South, Range 2 West, west half of Section 16 (Salt Lake Base and Meridian) in Utah County. The Site is located southeast of the intersection of county roads 800 South and 18150 West. The approximate latitude and longitude of the site are 40 21 degrees and -112 07 degrees, respectively. This location is in Cedar Valley between the Thorpe Hills on the west and the Lake Mountains on the east.

2.2 SOILS

Information on the site soils has been obtained from regional references and on-site soil borings. The locations of the on-site borings are shown on the Site Plan & Location of Explorations, Figure 2 of Reference 1.

The surficial soils consist of mostly lacustrine fine-grained deposits (Qlf, see Reference 2). Twenty test pit excavations and two test holes were advanced during the Geotechnical Study (Reference 1) to depths ranging from 10 feet to 41 feet below grade. The soil borings indicate that the soils consist mostly of very stiff to hard fat clay (CH) with a few layers of dense silty sand (SM) and very stiff elastic silt (MH). Standard penetration blow counts range from 15 to refusal in the fat clay.

2.3 SEISMICITY

The probabilistic bedrock maximum (peak) horizontal acceleration for a return period of 2% in 50 years (10% in 250 years) at the Site is 0.25g, as determined from the U.S. Geological Survey (USGS), National Seismic Hazard Mapping Project Probabilistic Seismic Hazards Assessment, Custom Mapping and Analysis Tools, Interactive Deaggregation Tool (2008) (<http://eqint.cr.usgs.gov/deaggint/2008/>).

Using the Interactive Deaggregation Tool and adjusting the shear wave velocity based on the site-specific soil characteristics, the maximum (peak) horizontal acceleration for the Site was determined to be 0.28g. This value was used to evaluate the cut slope and the waste mass stability. See Attachment 1.

The peak maximum credible earthquake was also determined probabilistically using the same source and methodology. A magnitude 7.0 was used for slope stability evaluation. See Attachment 1.

The design accelerations (above the bedrock at bottom of waste) for Short Period, S_{DS} , and for 1-Second Period, S_{D1} , were determined to be 0.55g and 0.31g, respectively. These were determined by Earthtec in accordance with International Building Code (IBC) using a Site Class D classification. See Reference 1. These values are appropriate to evaluate structural components that are not part of this analysis.

2.4 ADOPTED DESIGN VALUES

The regional soil stratigraphy and site-specific boring logs were reviewed to establish a design profile for use in stability and settlement analyses. Soil shear strengths were based on the laboratory soil testing program and correlations with the Standard Penetration Test results, Attachment 1, Reference D. Waste shear strengths were based on EPA data (EPA 1995).

The adopted stratigraphy and corresponding physical properties for stability are summarized in Table 2.1 below from Attachment 2.

Table 2 1
Adopted Soil Properties (Attachment 2)

| Feature | Depth (ft) | Total Unit Weight (PCF) | Saturated Unit Weight (PCF) | Cohesion (PSF)* | Phi (degrees) | Material |
|-----------------------|------------|-------------------------|-----------------------------|----------------------------------|-------------------------------|----------|
| Upper very stiff clay | 0-10 | 113.5 | 121.0 | 3000 short term, 50 long term | 0 short term, 29 long term | CH |
| Less stiff clay | 10-20 | 121.0 | 125.5 | 1500 short term, 50 long term | 0 short term, 29 long term | CH |
| Stiff clay | 20-30 | 121.0 | 125.5 | 2000 short term, 50 long term | 0 short term, 29 long term | CH |
| Lower very stiff clay | 30+ | 121.0 | 125.5 | 3000 short term, 50 long term | 0 short term, 50 long term | CH |
| Waste | Vanes | 50.0 | 60.0 | 150 | 22 | Waste* |
| LCRS | | 100.0 | 110.0 | 0 | 32 | Sand |
| Cap | | 110.0 | 120.0 | 1000 | 0 | Clay |

*EPA Reference 4

The adopted seismic properties for stability, as discussed in the previous section, are summarized in Table 2 2 from Attachment 2

Table 2 2
Maximum Horizontal Acceleration and Design Earthquake (Attachment 2)

| Location | Maximum Horizontal Acceleration | Design Earthquake Intensity |
|-----------------------------|---------------------------------|-----------------------------|
| Bottom of waste (cut slope) | 0.28g | 7.0 |
| Waste mass (fill slope) | 0.28g | 7.0 |

SECTION 3.0 STATIC AND PSEUDO-STATIC STABILITY ANALYSES AND DEFORMATION ANALYSES

3.1 METHOD OF ANALYSIS

The stability analyses were performed using the computer program PCSTABL7 (Purdue University 2002) and STEDwin Smart Editor (Van Aller 2007). The STABL program is an analytical tool developed by Purdue University that uses limit equilibrium techniques to search for and identify the critical failure surface and provides estimates of the factor of safety against instability. Failure surfaces can be circular, block, or random in shape depending on the geometry of the slope, loading condition, and subsurface details. STEDwin is a user interface for STABL that allows on-screen data entry and modifications and generates graphics.

3.2 CASES CONSIDERED

Stability analyses were conducted to determine the factor of safety against slope failures under static and pseudo-static loading conditions. The following landfill features, which are shown on Figure 2-1, were considered:

3.2.1 Maximum Cut Slope (Excavation)

The proposed excavation will be 1V 4H (25%) slopes to a maximum depth of nominally 45 feet at the east portion of the cells. To be conservative, a maximum depth of 50 feet was evaluated.

3.2.2 Maximum Fill Slope (Waste)

The proposed waste fill slopes are about 2.5% north and south and about 5% east and west from the crest at El 4950+ to a variable slope break, ranging between from El 4898 to 4905. The side slopes are 1V 4H (25%) from the slope break to original grade. Maximum waste fill heights in Cell 4 are 130 feet above the cell bottom and 100 feet above original grade. These slopes are consistent with UAC R315-303-4(4).

3.2.3 Waste Fill over Liner and Leachate Collection System (Sliding Block)

The proposed liner system will consist of a lower cushion nonwoven geotextile (or a sand cushion) placed on the subgrade. A geosynthetic clay liner (GCL) will be placed over the lower cushion with a 60-mil textured high-density polyethylene (HDPE) geomembrane overlying the GCL. The leachate collection/protective cover layer will consist of 2 feet of protective soil cover (granular leachate collection material) placed over an upper cushion geotextile placed over the HDPE geomembrane.

It is anticipated that the Cell 4 waste fills could reach a maximum of 130 feet above the liner/leachate collection system in the adjacent Cell 5 area. For analysis, a waste/intermediate soil cover slope of 1V 3H (33%) was evaluated.

3.3 METHODOLOGY

Both static and pseudo-static conditions were evaluated. The generalized factor of safety against a slope failure is defined as $FS = s/t$, where s is the available shear strength of the slope and t is the shear strength required for unity ($FS = 1.0$).

The Simplified Bishop circular arc method was used to evaluate the global stability of the excavated and filled slopes. The computer program PCSTABL7 (Purdue University 2002) was used to conduct these analyses. This program searches for the potential failure surface that produces the lowest factor of safety. The location of this failure surface is a function of the site geometry (slope angle and height), material stratigraphy and physical properties, and loadings (weight of soil and/or waste above the failure surface).

The sliding block (wedge) method was used to evaluate the sliding stability along the bottom liner and the LCRS system. The computer program PCSTABL7 (Purdue University 2002) was also used to conduct these analyses. The failure surface is defined by the bottom of the cell. For a given slope geometry, the interface friction angle, δ , between adjacent materials normally controls slope stability, with the lowest interface friction angle controlling overall slope stability. Adopted friction values for the geosynthetic interfaces are presented in Table 3.1.

A minimum static safety factor of 1.3 was adopted (EPA 1995). The pseudo-static seismic coefficient (a_y) was iterated for both the circular arc and sliding block analyses to determine the yield acceleration (a_y) corresponding to a factor of safety of 1.0. This yield acceleration is used to estimate the excavation, closure cap, and leachate collection system deformations cell (Section 5).

Table 3.1
Adopted Interface Friction Angles

| Lower | Upper | Interface Friction Angle (degrees) |
|---|---|------------------------------------|
| Soil subgrade | Lower cushion nonwoven geotextile or sand cushion | 25 |
| Lower cushion nonwoven geotextile or sand cushion | Geosynthetic clay liner (GCL) | 25 |
| Geosynthetic clay liner (GCL) | 60-mil textured HDPE geomembrane | 18 |
| 60-mil textured HDPE geomembrane | Upper cushion nonwoven geotextile | 18 |
| Upper cushion nonwoven geotextile | 2-ft leachate collection/protective soil cover | 18 |

The results of the static and pseudo-static stability analyses for the excavations and waste fills are presented in Attachment 2 and summarized below in Table 3.2. The results indicate that the static factor of safety is adequate for the existing and proposed cut and fill slope geometry. The yield accelerations at a safety factor of 1.0 are near the adopted peak bedrock acceleration, suggesting minimal permanent deformation (EPA 1995).

Table 3.2
Global Stability Results

| Feature | Static Factor of Safety | Yield Acceleration | Displacement, U (cm) |
|--|----------------------------------|--------------------|----------------------|
| Maximum excavation slope, 1V 4H (short-term controls) | 2.95 | 0.10g | 14.0 |
| Maximum fill slope, 1V 4H | 2.19 | 0.28g | 0.05 |
| Waste fill over liner and leachate collection system (sliding block) | 1.46 (18° interface friction) | 0.13g | 8.0 |

SECTION 4 0 SETTLEMENT AND LINER STRAIN

4 1 SETTLEMENT

For this analysis, settlement was calculated along the Cell 3 leachate collection pipe alignment for the worst-case scenario. Points along the alignment were evaluated to determine if the slope toward the sump would be positive after final waste has been placed. The results are shown in Table 4 1.

Table 4 1
Differential Settlement Results

| Point | Location | Thickness of Waste (ft) | Settlement (ft) | Final Slope between Points (%) |
|-------|---|-------------------------|-----------------|--------------------------------|
| 1 | Interior west toe of slope | 42 | 1 6 | NA |
| 2 | 120 ft east of west toe of slope | 72 | 1 8 | 1 69 |
| 3 | 560 ft east of west toe of slope | 100 | 2 0 | 1 54 |
| 4 | 1110 ft east of west toe of slope | 134 | 2 2 | 1 53 |
| 5 | 1660 ft east of west toe of slope | 73 | 1 8 | 1 44 |
| 6 | 2160 ft east of west toe of slope (east sump) | 46 | 1 6 | 1 45 |

4 2 LINER STRAIN

The strain in the liner between the points above was also determined based on the initial and final (after settlement) slope information. The calculated strains were much less than the 17% allowable. See Attachment 3.

SECTION 5.0 FINDINGS AND CONCLUSIONS

5.1 FINDINGS

The Intermountain Regional Landfill site is located in a seismic impact zone. Probabilistic methods indicate a peak bedrock acceleration of 0.25g. Factoring the on-site soils and waste properties, the maximum bottom of waste and waste mass accelerations were both determined to be 0.28g.

The cut and fill slopes have adequate static factor of safety and indicate minimal permanent deformations ($U < 30$ cm) in response to the design seismic event. The upper limit of 30 cm (1 ft) was established as the maximum tolerable deformation of the geosynthetic components (EPA 1995).

Settlement along the leachate collection line (worst case) was evaluated in Attachment 3 and was determined to range from 1.6 ft to 2.2 ft. Differential settlement calculations indicate that positive slopes toward the sumps will be maintained and liner strains ($< 1\%$) will be less than allowable (17%).

5.2 CONCLUSIONS

The analyses show that the proposed Intermountain Regional Landfill components are designed to resist the "maximum horizontal acceleration" at the site.

SECTION 6 0 REFERENCES

Earthtec 2009 Geotechnical Study Intermountain Regional Landfill, Fairfield, Utah October 13

[EPA] U S Environmental Protection Agency 1995 RCRA Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities EPA/600/R-95/051 Prepared by G N Richardson and E Kavazanjan

Purdue University 2002 PCSTABL7 Slope Stability Computer Program

Van Aller, H W 2007 STEDwin Smart Editor for PCSTABL

**ATTACHMENT 1: MAXIMUM HORIZONTAL
ACCELERATION & DESIGN EARTHQUAKE**

| | | | | | |
|---------|---------------------------------|-------------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PJP</i> | Date | 4.6.10 |
| Task | Slope Stability MHA & Design EQ | Page 1 of 2 | | | |
| Job # | Dept 00143 | No | 125184 | | |

1.1 Task

- A Determine the maximum (peak) horizontal acceleration (MHA) for the site
 - a At bedrock
 - b At bottom of waste
 - c At top of waste
- B Determine the design earthquake for the site

1.2 References

- A EPA, Richardson, G N and Kavazanjian, E (1995), RCRA Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities, EPA/600/R-95/051
- B USGS, National Seismic Hazard Mapping Project Probabilistic Seismic Hazards Assessment , Custom Mapping and Analysis Tools, Interactive Deaggregation Tool [http //eqint cr usgs gov/deaggint/2008/index php](http://eqint.cr.usgs.gov/deaggint/2008/index.php)
- C Earthtec Testing & Engineering, P C (2006) Geotechnical Study Intermountain Regional Landfill
- D Das, B , (1990) Principles of Foundation Engineering, 2nd Ed

1.3 Summary

- A Site location 40 21 degrees latitude, -112 07 degrees longitude Ref C
- B Determine the shear wave velocity
 - a Below the waste
 - b Depth & N, Standard Penetration values

| TH-1, Ref C, Figure No's 23a & 23b | | | | |
|------------------------------------|-------------|--|--------------|-----------------------------|
| Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* | Shear Wave Velocity** (m/s) |
| 2.5-4.0 | 25 | 3.0 | Very Stiff | 650 |
| 5.0-6.5 | 26 | 3.0 | Very Stiff | 650 |
| 7.5-9.0 | 35 | 4.0+ | Hard | 700 |
| 10.0-11.5 | 15 | 1.5 | Stiff | 550 |
| 20.0-21.5 | 40 | 4.0+ | Hard | 700 |
| 25.0-26.5 | 20 | 2.0 | Stiff | 550 |
| 30.0-31.5 | 80+ | 4.0+ | Hard | 700 |

| | | | | | |
|---------|---------------------------------|----------|-------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PJP</i> | Date | 11-26-10 |
| Task | Slope Stability MHA & Design EQ | | Page 2 of 2 | | |
| Job # | Dept 00143 | No | 125184 | | |

| TH-2, Ref C, Figure No's 24a & 24b | | | | |
|------------------------------------|-------------|--|--------------|-----------------------------|
| Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* | Shear Wave Velocity** (m/s) |
| 5 0-6 5 | 47 | 4 0+ | Hard | 700 |
| 10 0-11 5 | 24 | 3 0 | Very Stiff | 650 |
| 15 0-16 5 | 45 | 4 0+ | Hard | 700 |
| 20 0-21 5 | 38 | 4 0+ | Hard | 700 |
| 30 0-31 5 | 60 | 4 0+ | Hard | 700 |
| 40 0-41 5 | 80+ | 4 0+ | Hard | 700 |

Notes

* Reference D, pg 87

** Reference A, Section 4

1.4 Results

A Maximum (peak) Horizontal Acceleration (MHA)

- a At bedrock = 0.2467g (Vs=760 m/s) Reference B, see attached
- b At the bottom of the waste = 0.2747g (Vs=500 m/s) Reference B, see attached Note that Reference A indicates to use the bedrock acceleration based on the site specific shear wave velocities (stiff soils, page 45 of Ref A) Therefore this value is conservative
- c From Reference C (Earthtec) These accelerations to be used for evaluation of structures on the site and not the slopes or waste mass The evaluation of structures was not part of this analysis
 - i $S_{DS} = 0.55g$, Short Period Acceleration (bottom of waste)
 - ii $S_{DI} = 0.31g$, 1-Second Acceleration (bottom of waste)
- d For slope stability evaluation (worst case, maximum accelerations)
 - i Bottom of Waste (cut slope) = 0.28g
 - ii The average acceleration of the failure mass (waste fill slope) = 0.28g See Reference A, pages 46 and 47

B Maximum (peak) horizontal acceleration (MHA)

- a Magnitude of the design earthquake for the site 7.0 Reference B, see Attachment 1A

ATTACHMENT 1A: USGS MAPPING, REFERENCE B

PSH Deaggregation on NEHRP BC rock
Intermountain R 112.070° W, 40.210 N.

Peak Horiz. Ground Accel. ≥ 0.2467 g


Ann. Exceedance Rate .409E-03. Mean Return Time 2475 years

Mean (R,M, ϵ_0) 20.4 km, 6.54, 0.87

Modal (R,M, ϵ_0) = 24.8 km, 6.99, 1.07 (from peak R,M bin)

Modal (R,M, ϵ^*) = 24.8 km, 6.99, 1 to 2 sigma (from peak R,M, ϵ bin)

Binning: DeltaR 10. km, deltaM=0.2, Delta ϵ =1.0



PSH Deaggregation on NEHRP C soil
 Intermountain R 112.070° W, 40.210 N.

Peak Horiz. Ground Accel. ≥ 0.2747 g


Ann. Exceedance Rate $.410E-03$. Mean Return Time 2475 years

Mean (R,M, ϵ_0) 19.7 km, 6.57, 0.90

Modal (R,M, ϵ_0) = 24.9 km, 6.99, 1.05 (from peak R,M bin)

Modal (R,M, ϵ^*) = 24.9 km, 6.99, 1 to 2 sigma (from peak R,M, ϵ bin)

Binning: DeltaR 10. km, deltaM=0.2, Delta ϵ =1.0



**ATTACHMENT 1B: SOIL CONSISTENCY,
REFERENCE D**

From Ref D

where A_R = area ratio
 D_o = outside diameter of the sampling tube
 D_i = inside diameter of the sampling tube

When the area ratio is 10% or less, the sample is generally considered to be undisturbed For a standard split-spoon sampler

$$A_R(\%) = \frac{(50.8)^2 - (34.93)^2}{(34.93)^2} (100) = 111.5\%$$

Hence, these samples are highly disturbed Split-spoon samples are generally taken at intervals of about 1.53 m (5 ft)

When the material encountered on the field is sand (particularly fine sand below the water table), sample recovery by a split-spoon sampler may be difficult In that case, a device such as a spring core catcher may have to be placed inside the split spoon (Figure 2.7b)

Besides obtaining soil samples, standard penetration tests provide several useful correlations For example, the consistency of clayey soils can often be estimated from the standard penetration number (N) This is shown in Table 2.3

Table 2.3 Consistency of Clays and Approximate Correlation to the Standard Penetration Number N

| Standard penetration number, N | Consistency | Unconfined compression strength, q_u (kN/m ²) | q_u TSF |
|----------------------------------|--------------|---|-----------|
| 0-2 | Very soft | 0-25 | 0-0.26 |
| 2-5 | Soft | 25-50 | 0.26-0.52 |
| 5-10 | Medium stiff | 50-100 | 0.52-1.04 |
| 10-20 | Stiff | 100-200 | 1.04-2.09 |
| 20-30 | Very stiff | 200-400 | 2.09-4.17 |
| >30 | Hard | >400 | >4.17 |

1 kN/m² = 0.01044 tons/ft²
 pg 719


In granular soils, the N -value is affected by the effective overburden pressure, a'_v . For that reason, the N -value obtained from field exploration at different effective overburden pressures should be changed to correspond to a standard value of a'_v . This means that

$$N_{cor} = C_N N_F \quad (2.4)$$

N_{cor} = corrected N -value to a standard value of a'_v [95.6 kN/m² (1 ton/ft²)]

C_N = correction factor

N_F = N -value obtained from the field



ing
 ie

er is driven into
 d The standard
 low, the hammer
 s required for
 e recorded The
 dded to give the
 referred to as the
 986, Designation
 and the couple
 be is then plac

y expressed by

**ATTACHMENT 2: SLOPE STABILITY CASES AND
RUNS**

| | | | | | |
|---------|---------------------------------|----------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PHF</i> | Date | 4-26-12 |
| Task | Slope Stability Cases | Page | 1 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |

2.1 Task

- A Determine the Static Factor of Safety (FS) and Seismic Yield Acceleration (a_y) for
 - a Case 1 Maximum Cut Slope
 - b Case 2 Maximum Fill Slope
 - c Case 3 Maximum Operational Waste Fill Slope (sliding block)
- B Determine the maximum displacement and verify less than 30 CM

2.2 References

- A EPA, Richardson, G N and Kavazanjian, E (1995), RCRA Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities, EPA/600/R-95/051
- B Salgado, R , Purdue University (2002) PCSTABL7 Slope Stability Computer Program, Joint Highway Research Program FHWA, and Van Aller, H W (2007) STEDwin Smart Editor for PCSTABL
- C Earthtec Testing & Engineering, P C (2006) Geotechnical Study Intermountain Regional Landfill
- D Das, B , (1990) Principles of Foundation Engineering, 2nd Ed
- E HDR (2010) Determination of the MHA and Design EQ Calculations

2.3 Soil Profile and Matenal Properties (Reference C and E)

- A Unit weight/classification

| <u>Sample, Depth (FT)</u> | <u>Dry Density (PCF)</u> | <u>Water Content (%)</u> | <u>Total Unit Weight (PCF)</u> | <u>Classification</u> |
|---------------------------|--------------------------|--------------------------|--------------------------------|-----------------------|
| TP-14, 6' | 93 | 20 | 111.7 | CH |
| TP-15, 7.5' | 93 | 19 | 110.7 | CH |
| TP-10, 8.5' | 91 | 26 | 114.7 | CH |
| TP-7, 9' | 90 | 23 | 110.7 | CH |
| TH-1, 15'-17' | 97 | 21 | 117.4 | CH |

Unit weight relationship

$$Y_d = \frac{(G_s \cdot Y_w)}{(1+e)}, \quad e = \frac{(G_s \cdot Y_w)}{Y_d} - 1, \quad Y_{sat} = \frac{(G_s + e) \cdot (Y_w)}{(1+e)}, \quad \text{Reference D}$$

Where

Y_d = Dry Density

e = void ratio

Y_{sat} = saturated unit weight

G_s = 2.70 (assumed)

| | | | | | |
|---------|---------------------------------|-------------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>RHP</i> | Date | 4 16 10 |
| Task | Slope Stability Cases | Page 2 of 6 | | | |
| Job # | Dept 00143 | No | 125184 | | |

$\gamma_w = 62.4 \text{ PCF}$

- i) Depth 0-10' $\gamma_d = 93 \text{ PCF}$, $w = 22.0$, $\gamma_{total} = 113.5$, $e = 0.8$, $\gamma_{sat} = 121.0 \text{ PCF}$
- ii) Depth 10+ For $\gamma_d = 100 \text{ PCF}$, $w = 21.0$, $\gamma_{total} = 121.0$, $e = 0.68$, $\gamma_{sat} = 125.5 \text{ PCF}$

B Strength

| TH-1, Ref C, Figure No's 23a & 23b | | | |
|------------------------------------|-------------|--|-----------------|
| Sample Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* |
| 2.5-4.0 | 25 | 3.0 | Very Stiff (CH) |
| 5.0-6.5 | 26 | 3.0 | Very Stiff (CH) |
| 7.5-9.0 | 35 | 4.0+ | Hard (CH) |
| 10.0-11.5 | 15 | 1.5 | Stiff (CH) |
| 20.0-21.5 | 40 | 4.0+ | Hard (CH) |
| 25.0-26.5 | 20 | 2.0 | Stiff (CH) |
| 30.0-31.5 | 80+ | 4.0+ | Hard (CH) |

| TH-2, Ref C, Figure No's 24a & 24b | | | |
|------------------------------------|-------------|--|-----------------|
| Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* |
| 5.0-6.5 | 47 | 4.0+ | Hard (CH) |
| 10.0-11.5 | 24 | 3.0 | Very Stiff (CH) |
| 15.0-16.5 | 45 | 4.0+ | Hard (CH) |
| 20.0-21.5 | 38 | 4.0+ | Hard (CH) |
| 30.0-31.5 | 60 | 4.0+ | Hard (CH) |
| 40.0-41.5 | 80+ | 4.0+ | Hard (CH) |

Notes

* Reference D, pg 87

| | | | | | |
|---------|---------------------------------|-------------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | PHD | Date | 4/26/10 |
| Task | Slope Stability Cases | Page 3 of 6 | | | |
| Job # | Dept 00143 | No | 125184 | | |

C Design values

| Feature | Depth (FT) | Total Unit Weight (PCF) | Saturated Unit Weight (PCF) | Cohesion (PSF)* | Phi (Degrees) | Material |
|-----------------------|------------|-------------------------|-----------------------------|----------------------------------|-------------------------------|----------|
| Upper Very Stiff Clay | 0-10 | 113.5 | 121.0 | 3000 Short Term, 50 Long Term | 0 Short Term, 29 Long Term | CH |
| Less Stiff Clay | 10-20 | 121.0 | 125.5 | 1500 Short Term, 50 Long Term | 0 Short Term, 29 Long Term | CH |
| Stiff Clay | 20-30 | 121.0 | 125.5 | 2000 Short Term, 50 Long Term | 0 Short Term, 29 Long Term | CH |
| Lower Very Stiff Clay | 30+ | 121.0 | 125.5 | 3000 Short Term, 50 Long Term | 0 Short Term, 50 Long Term | CH |
| Waste | Vanes | 50.0 | 60.0 | 150 | 22 | Waste** |
| LCRS | | 100.0 | 110.0 | 0 | 32 | Sand |
| Cap | | 110.0 | 120.0 | 1000 | 0 | Clay |


* Reference D, pg 87

**EPA, Reference 4

| | | | | | |
|---------|---------------------------------|----------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | PHH | Date | 4/26/10 |
| Task | Slope Stability Cases | Page | 4 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |


2.4 Cross Sections

A West-East Cross Section (see attached)



| | | | | | |
|---------|---------------------------------|----------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PHF</i> | Date | 4 16 10 |
| Task | Slope Stability Gases | Page | 5 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |

B North-South Cross Sections (see attached)



| | | | | | |
|---------|---------------------------------|----------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | PHP | Date | 4 26 10 |
| Task | Slope Stability Gases | Page | 6 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |

- C Case 1 - Maximum Cut Slope
 - i) East end of East-West cross-section (Cell 1, Phase 3) Depth of cut=45 FT
Use 50 FT for analysis
 - ii) Slope = 4H 1V
 - iii) See Attachment 2C-1 for stability output
- D Case 2 - Maximum Fill Slope (Waste)
 - i) East end of the East-West cross section (Cell 1, Phase 3) Height above existing grade = 80 FT Use 100 FT for analysis
 - ii) Slope = 4H 1V
 - iii) See Attachment 2C-2 for stability output
- E Case 3 – Maximum Operational Fill Slope (Cell 4/Cell 5)
 - i) Maximum waste height = 130 FT above cell floor
 - ii) Waste slope = 3H 1V
 - iii) See Attachment 2C-3 for stability output

2.5 Results

| Feature | Static Factor of Safety | Yield Acceleration | Displacement, U (CM) |
|--|----------------------------------|--------------------|----------------------|
| Maximum Excavation Slope, 1V 4H (Short Term controls) | 2.95 | 0.10g | 14.0 |
| Maximum Fill Slope, 1V 4H | 2.19 | 0.28g | 0.05 |
| Waste Fill Over Liner and Leachate Collection System (Sliding Block) | 1.46 (18° Interface Friction) | 0.13g | 8.0 |


**ATTACHMENT 2A: PLAN VIEWS, CROSS SECTIONS,
AND DETAILS**



1/6

NOTES:
EXISTING TOPOGRAPHIC DATA IS FROM
AERIAL SURVEYS INC. NOVEMBER 18,

| BENCHMARKS | | | |
|------------|------------|------------|---|
| BM | N | E | I |
| 8633 | 7248525.12 | 1477789.21 | |
| 8634 | 7248548.22 | 1480525.47 | |
| 8635 | 7243226.01 | 1480483.01 | |
| 8636 | 7243237.28 | 1477790.04 | |
| 8637 | 7245607.75 | 1477851.32 | |
| 8638 | 7245688.82 | 1480470.15 | |



LEGEND

- - - - - EXISTING CONTOURS
- _____ CELL FOOTPRINT BOUNDARY
- _____ PROPOSED 1 DRAWN LINE
- - - - - LITTER CONTROL FENCE LOC.

C:\pwworking\h1\h201\8408501\0003.dwg Plot: 3/1/2010 1:44:13 PM ghafer



| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |
| | | |



| | | |
|----------------|-----------|-----------|
| PROJECT | MM4001 | T. WARNER |
| CHECKED BY | S. WDMACK | |
| DESIGNED BY | C. HODARY | |
| DRAWN BY | C. HODARY | |
| PROJECT NUMBER | | |

INTERMOUNTAIN
REGIONAL
LANDFILL

SITE PLAN

| | |
|----------|-----------|
| FILENAME | D1003.DWG |
| SCALE | 1"=200' |

2/6



| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |


| | |
|-----------------|------------|
| PROJECT MANAGER | T. WINKLER |
| CHECKED BY | S. WORMACK |
| DESIGNED BY | C. MCCARTY |
| DRAWN BY | C. MCCARTY |
| PROJECT NUMBER | |

INTERMOUNTAIN
REGIONAL
LANDFILL

FINAL COVER PLAN

| | | |
|----------|------------|---------|
| 0 | 1 | 2' |
| FILENAME | 010005.DWG | SHEET |
| SCALE | 1"=200' | 5 OF 13 |


3/6



CROSS SECTION EAST-WEST
ALL CELLS

| | | | | | | | | | | | | |
|---|--|-------------|-----------------|-----------|--|------------|-----------|------------|----------------|-------|--|----------------------|
| | <table border="1"> <tr> <td>PROJECT MANAGER</td> <td>T. WINKER</td> </tr> <tr> <td>DESIGNED BY</td> <td>S. WORMACK</td> </tr> <tr> <td>DRAWN BY</td> <td>C. MCCARTY</td> </tr> <tr> <td>PROJECT NUMBER</td> <td></td> </tr> </table> | | PROJECT MANAGER | T. WINKER | DESIGNED BY | S. WORMACK | DRAWN BY | C. MCCARTY | PROJECT NUMBER | | <p>INTERMOUNTAIN REGIONAL LANDFILL</p> | <p>CROSS SECTION</p> |
| | PROJECT MANAGER | T. WINKER | | | | | | | | | | |
| DESIGNED BY | S. WORMACK | | | | | | | | | | | |
| DRAWN BY | C. MCCARTY | | | | | | | | | | | |
| PROJECT NUMBER | | | | | | | | | | | | |
| <table border="1"> <tr> <td>DATE</td> <td></td> <td>DESCRIPTION</td> <td></td> </tr> </table> | DATE | | DESCRIPTION | | <table border="1"> <tr> <td>SCALE</td> <td>1" = 100'</td> </tr> <tr> <td>FILENAME</td> <td>010007.DWG</td> </tr> <tr> <td>SHEET</td> <td>7 OF 12</td> </tr> </table> | SCALE | 1" = 100' | FILENAME | 010007.DWG | SHEET | 7 OF 12 | |
| DATE | | DESCRIPTION | | | | | | | | | | |
| SCALE | 1" = 100' | | | | | | | | | | | |
| FILENAME | 010007.DWG | | | | | | | | | | | |
| SHEET | 7 OF 12 | | | | | | | | | | | |

4/6



CROSS SECTION NORTH-SOUTH
ALL CELLS




| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |
| | | |

| | |
|-----------------|------------|
| PROJECT MANAGER | T. WARNER |
| CHECKED BY | S. WISNACK |
| DESIGNED BY | C. MCCARTY |
| DRAWN BY | C. MCCARTY |
| PROJECT NUMBER | |

INTERMOUNTAIN
REGIONAL
LANDFILL

| | | |
|---------------|--|-------------------------|
| CROSS SECTION | | SHEET 8 OF 13 |
| | FILENAME: 010000 CRG SCALE: 1"=100' | |

5/6



CROSS SECTION NORTH-SOUTH
ALL CELLS




| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| | |
|----------------|------------|
| PROJECT NUMBER | T 10000 |
| CHECKED BY | S. WIMACK |
| DESIGNED BY | C. MCCARTY |
| DRAWN BY | C. MCCARTY |
| | |
| PROJECT NUMBER | |


INTERMOUNTAIN
REGIONAL
LANDFILL

| | | |
|---------------|------------|------------------------------------|
| CROSS SECTION | | SCALE 1"=100' SHEET 9 OF 13 |
| FILENAME | 01000E.DWG | |

6/6




TYPICAL LANDFILL LINER DETAIL
NOT TO SCALE



LINER SYSTEM ANCHOR TRENCH
NOT TO SCALE

NOTE
1. AREA BETWEEN TOP 2 OF EXCAVATION AND BACK OF ANCHOR TRENCH TO BE GRADED SMOOTH AND EVEN PRIOR TO PLACING UPPER GEOTEXTILE. REMOVE ANGULAR STONES.



LINER AT SLOPE TRANSITION
NOT TO SCALE

NOTE: THICKNESS MEASURED PERPENDICULAR TO EXCAVATION SURFACE.

NOTES:

1. TEMPORARY STORMWATER INTERCEPTOR BERM TO BE PLACED IN FRONT OF WORKING AREA TO DIVERT STORMWATER AWAY FROM ACTIVE FACE. OWNER WILL RELOCATE AS NEEDED.
2. STAGE 2 GEOMEMBRANE TO BE WELDED TO STAGE 1 FUTURE GEOSYNTHETIC COMPONENTS TO BE OVERLAPPED AND SECURED.
3. PIPE 1 GEOTEXTILE IS REINFORCED AND REQUIRED ON SEE SLOPES ONLY ABOVE HOPE LINER. TYPE 2 GEOTEXTILE IS NON-REINFORCED (NON-WOVEN) AND IS TO BE USED ABOVE HOPE LINER ON SLOTTING AND BETWEEN SUBGRADE AND CCL. A SAND CUSHION MAY BE USED IN LIEU OF THE LOWER TYPE 2 GEOTEXTILE WITH PRIOR APPROVAL OF ENGINEER AND OWNER.
4. SEE SPECIFICATION 02240 FOR PROTECTIVE COVER MATERIAL REQUIREMENTS.
5. SEE SPECIFICATION 02776 FOR REQUIRED MINIMUM INTERFACE FRICTION VALUES.

| GEOTEXTILE SCHEDULE | | |
|------------------------------------|------|---|
| LOCATION | TYPE | COMMENTS |
| ALL | ALL | REMOVE ALL ANGULAR STONES GREATER THAN 0.5 INCHES |
| LOWER GEOTEXTILE | 2 | USE 16 OZ/SY NON-WOVEN IF ROUNDED STONES GREATER THAN 2 INCHES ARE REMOVED. USE 20 OZ/SY NON-WOVEN IF ONLY ROUNDED STONES GREATER THAN 4 INCHES ARE REMOVED. NO HORIZONTAL SEAMS ON SIDESLOPES. |
| UPPER GEOTEXTILE ON SIDESLOPES | 1 | REINFORCED GEOTEXTILE. NO HORIZONTAL SEAMS ON SIDESLOPES. |
| UPPER GEOTEXTILE ON BOTTOM (FLOOR) | 2 | USE 12 OZ/SY NON-WOVEN BENEATH DUNE SAND (PROTECTIVE SOIL COVER). |

C:\PW\working\PHX\014\085\01\0009.dwg Plot: 3/1/2010 2:07:11 PM gahar:

| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |

| | |
|-----------------|------------|
| PROJECT MANAGER | T. WARNER |
| CHECKED BY | S. WOMACK |
| DESIGNED BY | C. MCCARTY |
| DRAWN BY | C. MCCARTY |
| PROJECT NUMBER | |

INTERMOUNTAIN REGIONAL LANDFILL

LINER DETAILS

| | | |
|--|------------------------------------|----------------|
| | FILENAME: 010009.DWG SCALE: NTS | SHEET: 9 OF 12 |
|--|------------------------------------|----------------|

**ATTACHMENT 2B: DISPLACEMENT CHART,
REFERENCE A**

Ref. A





Figure 6 6 Makdisi and Seed Permanent Displacement Chart (Makdisi and Seed, 1978)

**ATTACHMENT 2C: SLOPE STABILITY RUNS &
RESULTS**

**ATTACHMENT 2C-1: SLOPE STABILITY RUNS &
RESULTS – CUT SLOPE**


Cut slope (Max)
H=50'



H 1"=50'
V 1"=20'

| Horizontal Acceleration | Short Term FS | Long Term FS |
|-------------------------|---------------|--------------|
| static | 2.95 | 2.49 |
| 0.1g | 1.00 ← | 1.75 |
| 0.2g | 0.57 | 1.33 |

↑
Controls



| | | | | | |
|---------|-----------------|----------|-----|------|---------|
| Project | IRL | Computed | GMS | Date | 4/20/10 |
| Subject | slope stability | Checked | PHR | Date | 4-26-10 |
| Task | Cut slope | Page | 2 | of | 130 |
| Job # | 125184 | Dist | 143 | No | |

Maximum Cut slope results / Displacement

$$a_{max} = 0.28g \text{ (Reference E)}$$

$$a_y = 0.1g \text{ (Previous page)}$$


$$\frac{a_y}{a_{max}} = \frac{0.1g}{0.28g} = 0.36 \text{ @ } M=70$$

Attachment 2B (Reference A)

$$U_{max} = 14 \text{ cm} < 30 \text{ cm (max allow)} \quad \underline{\underline{OK}}$$

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\lrf1 pl2 Run By Greg Shafer HDR 4/20/2010 02 22PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Piez Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|--------------|
| a | 2.85 | | | | | | No |
| b | 2.85 | | | | | | No |
| c | 2.86 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | W1 |
| d | 2.86 | LSC | 2 | 121.0 | 125.5 | 1500.0 | W1 |
| e | 2.87 | SC | 3 | 121.0 | 125.5 | 2000.0 | W1 |
| f | 2.87 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | W1 |
| g | 2.87 | | | | | | |
| h | 2.88 | | | | | | |
| i | 2.89 | | | | | | |
| j | 2.89 | | | | | | |

PCSTABL7 FSmin=2.85

Safety Factors Are Calculated By The Modified Bishop Method

STED



3/150

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 02 22PM
Run By Greg Shafer, HDR
Input Data Filename C 1 in
Output Filename C 1 OUT
Unit ENGLISH
Plotted Output Filename C 1 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below End |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param (psf) | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 280 00 ft
and X = 770 00 ft
Each Surface Terminates Between X = 950 00 ft
and X =2000 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 341 25 | 615 01 |
| 2 | 348 38 | 508 00 |
| 3 | 355 61 | 601 09 |
| 4 | 362 94 | 594 29 |
| 5 | 370 37 | 587 59 |
| 6 | 377 89 | 580 99 |
| 7 | 385 50 | 574 51 |
| 8 | 393 20 | 568 13 |
| 9 | 400 99 | 561 87 |
| 10 | 408 88 | 555 71 |
| 11 | 416 85 | 549 67 |
| 12 | 424 90 | 543 74 |
| 13 | 433 04 | 537 93 |

| | | |
|----|---------|--------|
| 14 | 441 26 | 532 24 |
| 15 | 449 56 | 526 66 |
| 16 | 457 93 | 521 20 |
| 17 | 466 39 | 515 86 |
| 18 | 474 92 | 510 64 |
| 19 | 483 52 | 505 54 |
| 20 | 492 20 | 500 57 |
| 21 | 500 94 | 495 72 |
| 22 | 509 75 | 490 99 |
| 23 | 518 63 | 486 39 |
| 24 | 527 58 | 481 92 |
| 25 | 536 58 | 477 57 |
| 26 | 545 65 | 473 36 |
| 27 | 554 78 | 469 27 |
| 28 | 563 96 | 465 31 |
| 29 | 573 20 | 461 49 |
| 30 | 582 49 | 457 79 |
| 31 | 591 84 | 454 23 |
| 32 | 601 23 | 450 80 |
| 33 | 610 68 | 447 51 |
| 34 | 620 16 | 444 35 |
| 35 | 629 69 | 441 33 |
| 36 | 639 27 | 438 44 |
| 37 | 648 88 | 435 69 |
| 38 | 658 53 | 433 07 |
| 39 | 668 22 | 430 60 |
| 40 | 677 95 | 428 26 |
| 41 | 687 70 | 426 06 |
| 42 | 697 49 | 424 00 |
| 43 | 707 30 | 422 07 |
| 44 | 717 14 | 420 29 |
| 45 | 727 00 | 418 65 |
| 46 | 736 89 | 417 15 |
| 47 | 746 80 | 415 79 |
| 48 | 756 72 | 414 57 |
| 49 | 766 66 | 413 49 |
| 50 | 776 62 | 412 56 |
| 51 | 786 59 | 411 76 |
| 52 | 796 57 | 411 11 |
| 53 | 806 55 | 410 60 |
| 54 | 816 55 | 410 23 |
| 55 | 826 55 | 410 00 |
| 56 | 836 55 | 409 92 |
| 57 | 846 54 | 409 98 |
| 58 | 856 54 | 410 18 |
| 59 | 866 54 | 410 52 |
| 60 | 876 53 | 411 00 |
| 61 | 886 51 | 411 63 |
| 62 | 896 48 | 412 40 |
| 63 | 906 43 | 413 31 |
| 64 | 916 38 | 414 36 |
| 65 | 926 31 | 415 56 |
| 66 | 936 22 | 416 89 |
| 67 | 946 11 | 418 37 |
| 68 | 955 98 | 419 98 |
| 69 | 965 82 | 421 74 |
| 70 | 975 64 | 423 64 |
| 71 | 985 43 | 425 67 |
| 72 | 995 19 | 427 85 |
| 73 | 1004 92 | 430 16 |
| 74 | 1014 61 | 432 51 |
| 75 | 1024 27 | 435 20 |
| 76 | 1033 89 | 437 93 |
| 77 | 1043 48 | 440 79 |
| 78 | 1053 02 | 443 79 |
| 79 | 1062 51 | 446 92 |
| 80 | 1071 96 | 450 19 |
| 81 | 1081 37 | 453 60 |

6/130

| | | | | |
|-----|------|----|-----|----|
| 82 | 1090 | 72 | 457 | 13 |
| 83 | 1100 | 02 | 460 | 80 |
| 84 | 1109 | 27 | 464 | 61 |
| 85 | 1118 | 46 | 468 | 54 |
| 86 | 1127 | 60 | 472 | 60 |
| 87 | 1136 | 68 | 476 | 80 |
| 88 | 1145 | 70 | 481 | 12 |
| 89 | 1154 | 65 | 485 | 57 |
| 90 | 1163 | 54 | 490 | 14 |
| 91 | 1172 | 37 | 494 | 85 |
| 92 | 1181 | 13 | 499 | 67 |
| 93 | 1189 | 82 | 504 | 63 |
| 94 | 1198 | 43 | 509 | 70 |
| 95 | 1206 | 98 | 514 | 90 |
| 96 | 1215 | 44 | 520 | 22 |
| 97 | 1223 | 84 | 525 | 65 |
| 98 | 1232 | 15 | 531 | 21 |
| 99 | 1240 | 38 | 536 | 89 |
| 100 | 1248 | 54 | 542 | 68 |
| 101 | 1255 | 61 | 548 | 58 |
| 102 | 1264 | 59 | 554 | 60 |
| 103 | 1272 | 49 | 560 | 74 |
| 104 | 1280 | 30 | 566 | 98 |
| 105 | 1288 | 02 | 573 | 34 |
| 106 | 1295 | 55 | 579 | 80 |
| 107 | 1303 | 18 | 586 | 38 |
| 108 | 1310 | 62 | 593 | 06 |
| 109 | 1317 | 97 | 599 | 84 |
| 110 | 1325 | 22 | 606 | 73 |
| 111 | 1332 | 37 | 613 | 72 |
| 112 | 1339 | 42 | 620 | 81 |
| 113 | 1346 | 37 | 628 | 01 |
| 114 | 1353 | 21 | 635 | 30 |
| 115 | 1359 | 95 | 642 | 68 |
| 116 | 1366 | 59 | 650 | 16 |
| 117 | 1373 | 12 | 657 | 74 |
| 118 | 1379 | 54 | 665 | 41 |
| 119 | 1383 | 27 | 670 | 00 |

Circle Center At X = 837 5 , Y = 1112 7 and Radius, 702 8
 *** 2 850 ***

Individual data on the 126 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Sot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 7 1 | 3062 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 7 2 | 9269 | 7 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 7 3 | 15552 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 7 4 | 21902 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 7 5 | 28311 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 7 6 | 34769 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 7 7 | 41268 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 7 8 | 47800 | 7 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 7 9 | 54356 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 8 0 | 60927 | 7 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 8 1 | 67506 | 3 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 12 | 8 1 | 74083 | 2 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 8 2 | 80650 | 6 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 8 3 | 87200 | 2 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 8 4 | 93723 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 8 5 | 100212 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 8 5 | 106658 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 8 6 | 113055 | 3 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 8 7 | 119393 | 6 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 8 7 | 125666 | 0 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 8 8 | 131865 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 22 | 8 9 | 137983 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 23 | 8 9 | 144013 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

| | | | | | | | | | |
|----|------|----------|-----|-----|-----|-----|-----|-----|-----|
| 24 | 9 0 | 149947 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 25 | 9 1 | 155779 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 26 | 9 1 | 161502 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 27 | 9 2 | 167109 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 28 | 9 2 | 172592 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 29 | 9 3 | 177946 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 30 | 9 3 | 183165 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 31 | 9 4 | 188242 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 32 | 9 4 | 193171 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 33 | 9 5 | 197947 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 34 | 9 5 | 202565 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 35 | 9 6 | 207019 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 36 | 9 6 | 211304 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 37 | 9 7 | 215413 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 38 | 9 7 | 219345 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 39 | 9 7 | 223092 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 40 | 9 8 | 226652 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 41 | 9 8 | 230021 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 42 | 9 8 | 233194 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 43 | 9 8 | 236168 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 44 | 9 9 | 238940 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 45 | 9 9 | 241505 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 46 | 9 9 | 243863 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 47 | 3 2 | 79195 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 48 | 6 7 | 157083 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 49 | 9 9 | 235711 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 50 | 10 0 | 240000 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 51 | 10 0 | 244094 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 52 | 10 0 | 247990 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 53 | 10 0 | 251684 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 54 | 10 0 | 255174 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 55 | 10 0 | 258454 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 56 | 3 5 | 90014 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 57 | 5 5 | 182803 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 58 | 10 0 | 281635 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 59 | 10 0 | 284263 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 60 | 10 0 | 286660 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 61 | 3 5 | 99879 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 62 | 6 5 | 189432 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 63 | 10 0 | 291499 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 64 | 10 0 | 293189 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 65 | 10 0 | 294641 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 66 | 3 6 | 105898 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 67 | 6 4 | 190434 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 68 | 9 9 | 297575 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 69 | 9 9 | 298309 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 70 | 9 9 | 298803 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 71 | 3 9 | 117829 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 72 | 6 0 | 180724 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 73 | 9 8 | 296033 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 74 | 9 8 | 293082 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 75 | 9 8 | 289918 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 76 | 9 8 | 286544 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 77 | 9 7 | 282965 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 78 | 9 7 | 279183 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 79 | 9 7 | 275204 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 80 | 9 6 | 271033 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 81 | 9 6 | 266671 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 82 | 9 5 | 262129 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 83 | 9 5 | 257404 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 84 | 9 5 | 252509 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 85 | 9 4 | 247444 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 86 | 9 4 | 242215 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 87 | 9 3 | 236831 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 88 | 9 2 | 231299 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 89 | 9 2 | 225619 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 90 | 9 1 | 219803 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 91 | 9 1 | 213856 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

8/130

| | | | | | | | | | | |
|-----|-----|----------|-----|-----|-----|-----|-----|-----|-----|-----|
| 92 | 9 0 | 207784 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 93 | 9 0 | 201592 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 94 | 8 9 | 195291 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 95 | 8 8 | 188889 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 96 | 8 8 | 182387 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 97 | 8 7 | 175797 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 98 | 8 6 | 169128 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 99 | 8 5 | 162383 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 100 | 8 5 | 155573 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 101 | 8 4 | 148706 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 102 | 8 3 | 141792 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 103 | 8 2 | 134833 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 104 | 8 2 | 127843 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 105 | 8 1 | 120826 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 106 | 8 0 | 113794 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 107 | 7 9 | 106755 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 108 | 7 8 | 99714 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 109 | 7 7 | 92685 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 110 | 7 6 | 85671 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 111 | 7 5 | 78686 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 112 | 7 4 | 71734 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 113 | 7 3 | 54826 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 114 | 7 2 | 57972 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 115 | 7 2 | 51178 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 116 | 7 0 | 44453 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 117 | 6 9 | 37808 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 118 | 6 8 | 31250 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 119 | 4 3 | 16484 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 120 | 2 4 | 8304 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 121 | 6 5 | 18091 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 122 | 0 1 | 339 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 123 | 6 5 | 12186 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 124 | 1 9 | 2407 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 125 | 4 5 | 3748 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 126 | 3 7 | 973 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By139 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 280 00 | 514 26 |
| 2 | 287 20 | 607 32 |
| 3 | 294 49 | 600 47 |
| 4 | 301 86 | 593 71 |
| 5 | 309 30 | 587 03 |
| 6 | 316 83 | 580 45 |
| 7 | 324 43 | 573 95 |
| 8 | 332 11 | 567 55 |
| 9 | 339 87 | 561 24 |
| 10 | 347 70 | 555 02 |
| 11 | 355 60 | 548 89 |
| 12 | 363 58 | 542 86 |
| 13 | 371 62 | 536 92 |
| 14 | 379 74 | 531 08 |
| 15 | 387 93 | 525 34 |
| 16 | 396 18 | 519 70 |
| 17 | 404 50 | 514 15 |
| 18 | 412 89 | 508 70 |
| 19 | 421 34 | 503 36 |
| 20 | 429 86 | 498 11 |
| 21 | 438 43 | 492 97 |
| 22 | 447 07 | 487 93 |
| 23 | 455 76 | 482 99 |
| 24 | 464 52 | 478 16 |
| 25 | 473 33 | 473 43 |
| 26 | 482 19 | 468 80 |
| 27 | 491 12 | 464 28 |
| 28 | 500 09 | 459 87 |
| 29 | 509 12 | 455 57 |
| 30 | 518 19 | 451 37 |

9/130

| | | |
|----|---------|--------|
| 31 | 527 32 | 447 28 |
| 32 | 536 49 | 443 30 |
| 33 | 545 71 | 439 44 |
| 34 | 554 98 | 435 68 |
| 35 | 564 29 | 432 03 |
| 36 | 573 65 | 428 49 |
| 37 | 583 04 | 425 06 |
| 38 | 592 47 | 421 75 |
| 39 | 601 95 | 418 55 |
| 40 | 611 46 | 415 46 |
| 41 | 621 01 | 412 48 |
| 42 | 630 59 | 409 62 |
| 43 | 640 20 | 406 88 |
| 44 | 649 85 | 404 25 |
| 45 | 659 53 | 401 73 |
| 46 | 669 24 | 399 33 |
| 47 | 678 97 | 397 04 |
| 48 | 688 73 | 394 87 |
| 49 | 698 52 | 392 82 |
| 50 | 708 33 | 390 88 |
| 51 | 718 17 | 389 06 |
| 52 | 728 02 | 387 36 |
| 53 | 737 89 | 385 78 |
| 54 | 747 78 | 384 31 |
| 55 | 757 69 | 382 96 |
| 56 | 767 62 | 381 73 |
| 57 | 777 56 | 380 62 |
| 58 | 787 51 | 379 62 |
| 59 | 797 47 | 378 75 |
| 60 | 807 44 | 377 99 |
| 61 | 817 42 | 377 35 |
| 62 | 827 40 | 376 83 |
| 63 | 837 40 | 376 43 |
| 64 | 847 39 | 376 15 |
| 65 | 857 39 | 375 99 |
| 66 | 867 39 | 375 95 |
| 67 | 877 39 | 376 02 |
| 68 | 887 39 | 376 22 |
| 69 | 897 38 | 376 53 |
| 70 | 907 37 | 376 97 |
| 71 | 917 36 | 377 52 |
| 72 | 927 34 | 378 19 |
| 73 | 937 31 | 378 98 |
| 74 | 947 26 | 379 89 |
| 75 | 957 21 | 380 91 |
| 76 | 967 15 | 382 06 |
| 77 | 977 07 | 383 32 |
| 78 | 986 97 | 384 71 |
| 79 | 996 85 | 386 21 |
| 80 | 1006 73 | 387 82 |
| 81 | 1016 57 | 389 56 |
| 82 | 1026 40 | 391 41 |
| 83 | 1036 20 | 393 38 |
| 84 | 1045 98 | 395 46 |
| 85 | 1055 74 | 397 66 |
| 86 | 1065 47 | 399 98 |
| 87 | 1075 17 | 402 42 |
| 88 | 1084 84 | 404 96 |
| 89 | 1094 48 | 407 63 |
| 90 | 1104 08 | 410 41 |
| 91 | 1113 65 | 413 30 |
| 92 | 1123 19 | 416 31 |
| 93 | 1132 69 | 419 43 |
| 94 | 1142 16 | 422 66 |
| 95 | 1151 58 | 426 00 |
| 96 | 1160 96 | 429 46 |
| 97 | 1170 30 | 433 03 |
| 98 | 1179 60 | 436 71 |

10/
130

| | | |
|-----|---------|--------|
| 99 | 1188 86 | 440 50 |
| 100 | 1198 06 | 444 40 |
| 101 | 1207 23 | 448 41 |
| 102 | 1216 34 | 452 53 |
| 103 | 1225 40 | 456 75 |
| 104 | 1234 41 | 461 09 |
| 105 | 1243 37 | 465 53 |
| 106 | 1252 28 | 470 08 |
| 107 | 1251 13 | 474 73 |
| 108 | 1269 93 | 479 49 |
| 109 | 1278 66 | 484 35 |
| 110 | 1287 34 | 489 32 |
| 111 | 1295 96 | 494 39 |
| 112 | 1304 52 | 499 56 |
| 113 | 1313 02 | 504 83 |
| 114 | 1321 45 | 510 21 |
| 115 | 1329 82 | 515 68 |
| 116 | 1338 12 | 521 25 |
| 117 | 1346 36 | 526 93 |
| 118 | 1354 53 | 532 70 |
| 119 | 1362 62 | 538 56 |
| 120 | 1370 65 | 544 53 |
| 121 | 1378 61 | 550 58 |
| 122 | 1386 49 | 556 74 |
| 123 | 1394 30 | 562 98 |
| 124 | 1402 04 | 569 32 |
| 125 | 1409 70 | 575 75 |
| 126 | 1417 28 | 582 27 |
| 127 | 1424 78 | 588 88 |
| 128 | 1432 20 | 595 58 |
| 129 | 1439 55 | 602 37 |
| 130 | 1446 81 | 609 24 |
| 131 | 1453 99 | 616 20 |
| 132 | 1461 09 | 623 25 |
| 133 | 1468 10 | 630 38 |
| 134 | 1475 03 | 537 59 |
| 135 | 1481 87 | 644 88 |
| 136 | 1488 62 | 652 26 |
| 137 | 1495 29 | 659 71 |
| 138 | 1501 86 | 667 25 |
| 139 | 1504 21 | 670 00 |

Circle Center At X = 866 0 , Y = 1215 6 and Radius, 839 6
*** 2 851 ***

Failure Surface Specified By127 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 361 67 | 615 26 |
| 2 | 368 76 | 608 20 |
| 3 | 375 94 | 601 25 |
| 4 | 383 21 | 594 38 |
| 5 | 390 58 | 587 62 |
| 6 | 398 04 | 580 96 |
| 7 | 405 58 | 574 40 |
| 8 | 413 21 | 567 93 |
| 9 | 420 93 | 561 58 |
| 10 | 428 73 | 555 32 |
| 11 | 436 62 | 549 17 |
| 12 | 444 59 | 543 13 |
| 13 | 452 63 | 537 19 |
| 14 | 460 76 | 531 36 |
| 15 | 468 96 | 525 64 |
| 16 | 477 24 | 520 03 |
| 17 | 485 60 | 514 54 |
| 18 | 494 02 | 509 15 |
| 19 | 502 52 | 503 88 |
| 20 | 511 09 | 498 72 |
| 21 | 519 72 | 493 68 |
| 22 | 528 43 | 488 76 |

11/130

| | | |
|----|---------|--------|
| 23 | 537 19 | 483 95 |
| 24 | 546 03 | 479 26 |
| 25 | 554 92 | 474 68 |
| 26 | 563 87 | 470 23 |
| 27 | 572 89 | 465 90 |
| 28 | 581 96 | 461 69 |
| 29 | 591 08 | 457 60 |
| 30 | 600 26 | 453 63 |
| 31 | 609 49 | 449 79 |
| 32 | 618 77 | 446 07 |
| 33 | 628 11 | 442 47 |
| 34 | 637 48 | 439 00 |
| 35 | 646 91 | 435 66 |
| 36 | 656 38 | 432 44 |
| 37 | 665 89 | 429 35 |
| 38 | 675 44 | 426 39 |
| 39 | 685 03 | 423 55 |
| 40 | 694 65 | 420 84 |
| 41 | 704 32 | 418 27 |
| 42 | 714 01 | 415 82 |
| 43 | 723 74 | 413 50 |
| 44 | 733 50 | 411 32 |
| 45 | 743 28 | 409 25 |
| 46 | 753 10 | 407 34 |
| 47 | 762 94 | 405 54 |
| 48 | 772 80 | 403 88 |
| 49 | 782 68 | 402 35 |
| 50 | 792 58 | 400 96 |
| 51 | 802 50 | 399 69 |
| 52 | 812 44 | 398 56 |
| 53 | 822 39 | 397 56 |
| 54 | 832 35 | 396 70 |
| 55 | 842 32 | 395 97 |
| 56 | 852 30 | 395 37 |
| 57 | 862 29 | 394 91 |
| 58 | 872 29 | 394 58 |
| 59 | 882 29 | 394 38 |
| 60 | 892 29 | 394 32 |
| 61 | 902 29 | 394 39 |
| 62 | 912 28 | 394 60 |
| 63 | 922 28 | 394 93 |
| 64 | 932 27 | 395 41 |
| 65 | 942 25 | 396 01 |
| 66 | 952 22 | 396 76 |
| 67 | 962 18 | 397 63 |
| 68 | 972 13 | 398 64 |
| 69 | 982 07 | 399 78 |
| 70 | 991 99 | 401 05 |
| 71 | 1001 89 | 402 46 |
| 72 | 1011 77 | 404 00 |
| 73 | 1021 63 | 405 67 |
| 74 | 1031 46 | 407 47 |
| 75 | 1041 27 | 409 40 |
| 76 | 1051 06 | 411 47 |
| 77 | 1060 81 | 413 67 |
| 78 | 1070 54 | 415 99 |
| 79 | 1080 23 | 418 45 |
| 80 | 1089 89 | 421 03 |
| 81 | 1099 52 | 423 75 |
| 82 | 1109 10 | 426 59 |
| 83 | 1118 65 | 429 57 |
| 84 | 1128 16 | 432 67 |
| 85 | 1137 62 | 435 89 |
| 86 | 1147 05 | 439 25 |
| 87 | 1156 42 | 442 73 |
| 88 | 1165 75 | 446 33 |
| 89 | 1175 03 | 450 06 |
| 90 | 1184 26 | 453 91 |

12/130

| | | |
|-----|---------|--------|
| 91 | 1193 43 | 457 89 |
| 92 | 1202 55 | 461 99 |
| 93 | 1211 62 | 466 21 |
| 94 | 1220 63 | 470 55 |
| 95 | 1229 58 | 475 01 |
| 96 | 1238 47 | 479 59 |
| 97 | 1247 29 | 484 29 |
| 98 | 1256 06 | 489 11 |
| 99 | 1264 75 | 494 04 |
| 100 | 1273 38 | 499 09 |
| 101 | 1281 95 | 504 26 |
| 102 | 1290 44 | 509 54 |
| 103 | 1298 86 | 514 93 |
| 104 | 1307 21 | 520 43 |
| 105 | 1315 48 | 526 05 |
| 106 | 1323 68 | 531 78 |
| 107 | 1331 80 | 537 61 |
| 108 | 1339 84 | 543 56 |
| 109 | 1347 80 | 549 61 |
| 110 | 1355 68 | 555 77 |
| 111 | 1363 48 | 562 03 |
| 112 | 1371 19 | 568 39 |
| 113 | 1378 82 | 574 86 |
| 114 | 1386 36 | 581 43 |
| 115 | 1393 81 | 588 10 |
| 116 | 1401 17 | 594 87 |
| 117 | 1408 43 | 601 74 |
| 118 | 1415 61 | 608 71 |
| 119 | 1422 69 | 615 77 |
| 120 | 1429 58 | 622 92 |
| 121 | 1436 57 | 630 17 |
| 122 | 1443 36 | 637 51 |
| 123 | 1450 06 | 644 94 |
| 124 | 1456 65 | 652 45 |
| 125 | 1463 14 | 650 06 |
| 126 | 1469 53 | 667 75 |
| 127 | 1471 35 | 570 00 |

Circle Center At X = 891 9 , Y = 1141 1 and Radius, 746 8
*** 2 858 ***

Failure Surface Specified By123 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 382 08 | 615 51 |
| 2 | 389 16 | 608 44 |
| 3 | 396 33 | 601 46 |
| 4 | 403 59 | 594 59 |
| 5 | 410 95 | 587 82 |
| 6 | 418 40 | 581 16 |
| 7 | 425 95 | 574 59 |
| 8 | 433 58 | 568 13 |
| 9 | 441 31 | 561 78 |
| 10 | 449 12 | 555 54 |
| 11 | 457 01 | 549 40 |
| 12 | 464 99 | 543 37 |
| 13 | 473 06 | 537 46 |
| 14 | 481 20 | 531 66 |
| 15 | 489 42 | 525 97 |
| 16 | 497 73 | 520 39 |
| 17 | 506 10 | 514 93 |
| 18 | 514 56 | 509 59 |
| 19 | 523 08 | 504 37 |
| 20 | 531 68 | 499 26 |
| 21 | 540 35 | 494 27 |
| 22 | 549 08 | 489 40 |
| 23 | 557 89 | 484 66 |
| 24 | 566 75 | 480 04 |
| 25 | 575 58 | 475 54 |
| 26 | 584 68 | 471 16 |

| | | |
|----|---------|--------|
| 27 | 593 73 | 466 91 |
| 28 | 602 84 | 462 79 |
| 29 | 612 00 | 458 79 |
| 30 | 621 22 | 454 92 |
| 31 | 630 50 | 451 17 |
| 32 | 639 82 | 447 56 |
| 33 | 649 19 | 444 08 |
| 34 | 658 62 | 440 72 |
| 35 | 668 08 | 437 50 |
| 36 | 677 59 | 434 40 |
| 37 | 687 14 | 431 44 |
| 38 | 696 74 | 428 62 |
| 39 | 705 37 | 425 92 |
| 40 | 716 03 | 423 36 |
| 41 | 725 73 | 420 93 |
| 42 | 735 47 | 418 64 |
| 43 | 745 23 | 415 48 |
| 44 | 755 02 | 414 46 |
| 45 | 764 84 | 412 58 |
| 46 | 774 69 | 410 83 |
| 47 | 784 56 | 409 21 |
| 48 | 794 45 | 407 74 |
| 49 | 804 36 | 405 40 |
| 50 | 814 29 | 405 19 |
| 51 | 824 23 | 404 13 |
| 52 | 834 19 | 403 20 |
| 53 | 844 16 | 402 41 |
| 54 | 854 14 | 401 76 |
| 55 | 864 12 | 401 25 |
| 56 | 874 11 | 400 88 |
| 57 | 884 11 | 400 64 |
| 58 | 894 11 | 400 54 |
| 59 | 904 11 | 400 59 |
| 60 | 914 11 | 400 77 |
| 61 | 924 10 | 401 08 |
| 62 | 934 09 | 401 54 |
| 63 | 944 08 | 402 13 |
| 64 | 954 05 | 402 87 |
| 65 | 964 01 | 403 74 |
| 66 | 973 96 | 404 75 |
| 67 | 983 89 | 405 89 |
| 68 | 993 81 | 407 18 |
| 69 | 1003 71 | 408 60 |
| 70 | 1013 59 | 410 16 |
| 71 | 1023 44 | 411 85 |
| 72 | 1033 27 | 413 58 |
| 73 | 1043 08 | 415 55 |
| 74 | 1052 86 | 417 75 |
| 75 | 1062 60 | 419 99 |
| 76 | 1072 32 | 422 37 |
| 77 | 1082 00 | 424 87 |
| 78 | 1091 64 | 427 51 |
| 79 | 1101 25 | 430 29 |
| 80 | 1110 82 | 433 19 |
| 81 | 1120 34 | 436 23 |
| 82 | 1129 83 | 439 40 |
| 83 | 1139 27 | 442 71 |
| 84 | 1148 66 | 446 14 |
| 85 | 1158 00 | 449 70 |
| 86 | 1167 30 | 453 39 |
| 87 | 1176 54 | 457 21 |
| 88 | 1185 73 | 461 16 |
| 89 | 1194 86 | 465 23 |
| 90 | 1203 94 | 459 43 |
| 91 | 1212 95 | 473 76 |
| 92 | 1221 91 | 478 21 |
| 93 | 1230 80 | 482 78 |
| 94 | 1239 63 | 487 47 |

A/130

| | | |
|-----|---------|--------|
| 95 | 1248 39 | 492 29 |
| 96 | 1257 09 | 497 23 |
| 97 | 1265 71 | 502 29 |
| 98 | 1274 27 | 507 47 |
| 99 | 1282 75 | 512 76 |
| 100 | 1291 16 | 518 17 |
| 101 | 1299 49 | 523 70 |
| 102 | 1307 75 | 529 35 |
| 103 | 1315 93 | 535 10 |
| 104 | 1324 02 | 540 97 |
| 105 | 1332 04 | 546 95 |
| 106 | 1339 97 | 553 05 |
| 107 | 1347 81 | 559 25 |
| 108 | 1355 57 | 555 56 |
| 109 | 1363 24 | 571 97 |
| 110 | 1370 82 | 578 49 |
| 111 | 1378 31 | 585 12 |
| 112 | 1385 71 | 591 85 |
| 113 | 1393 01 | 598 68 |
| 114 | 1400 22 | 605 61 |
| 115 | 1407 33 | 612 64 |
| 116 | 1414 35 | 619 77 |
| 117 | 1421 26 | 626 99 |
| 118 | 1428 07 | 634 31 |
| 119 | 1434 79 | 641 73 |
| 120 | 1441 39 | 549 23 |
| 121 | 1447 90 | 656 83 |
| 122 | 1454 30 | 664 51 |
| 123 | 1458 74 | 670 00 |

Circle Center At X = 896 1 , Y = 1122 6 and Radius, 722 1
 *** 2 864 ***

Failure Surface Specified By 121 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 280 00 | 614 26 |
| 2 | 287 10 | 607 21 |
| 3 | 294 29 | 600 27 |
| 4 | 301 58 | 593 43 |
| 5 | 308 97 | 586 59 |
| 6 | 316 45 | 580 05 |
| 7 | 324 03 | 573 52 |
| 8 | 331 69 | 567 10 |
| 9 | 339 45 | 560 79 |
| 10 | 347 29 | 554 58 |
| 11 | 355 22 | 548 49 |
| 12 | 353 23 | 542 51 |
| 13 | 371 33 | 536 64 |
| 14 | 379 51 | 530 89 |
| 15 | 387 77 | 525 25 |
| 16 | 396 11 | 519 73 |
| 17 | 404 52 | 514 32 |
| 18 | 413 01 | 509 04 |
| 19 | 421 57 | 503 87 |
| 20 | 430 21 | 498 83 |
| 21 | 438 91 | 493 91 |
| 22 | 447 69 | 489 11 |
| 23 | 456 52 | 484 43 |
| 24 | 465 43 | 479 88 |
| 25 | 474 40 | 475 45 |
| 26 | 483 43 | 471 16 |
| 27 | 492 51 | 466 98 |
| 28 | 501 66 | 452 94 |
| 29 | 510 86 | 459 03 |
| 30 | 520 12 | 455 24 |
| 31 | 529 43 | 451 59 |
| 32 | 538 79 | 448 07 |
| 33 | 548 19 | 444 67 |
| 34 | 557 65 | 441 42 |

| | | |
|-----|---------|--------|
| 35 | 567 15 | 438 29 |
| 36 | 576 69 | 435 30 |
| 37 | 586 27 | 432 44 |
| 38 | 595 89 | 429 72 |
| 39 | 605 55 | 427 13 |
| 40 | 615 25 | 424 68 |
| 41 | 624 98 | 422 37 |
| 42 | 634 74 | 420 19 |
| 43 | 644 53 | 418 15 |
| 44 | 654 35 | 416 25 |
| 45 | 664 19 | 414 49 |
| 46 | 674 06 | 412 86 |
| 47 | 683 94 | 411 38 |
| 48 | 693 85 | 410 03 |
| 49 | 703 78 | 408 82 |
| 50 | 713 72 | 407 76 |
| 51 | 723 68 | 406 83 |
| 52 | 733 65 | 406 04 |
| 53 | 743 63 | 405 39 |
| 54 | 753 62 | 404 89 |
| 55 | 763 61 | 404 52 |
| 56 | 773 61 | 404 29 |
| 57 | 783 61 | 404 21 |
| 58 | 793 61 | 404 26 |
| 59 | 803 60 | 404 46 |
| 60 | 813 60 | 404 79 |
| 61 | 823 59 | 405 27 |
| 62 | 833 57 | 405 89 |
| 63 | 843 54 | 406 64 |
| 64 | 853 50 | 407 54 |
| 65 | 863 44 | 408 58 |
| 66 | 873 38 | 409 75 |
| 67 | 883 29 | 411 07 |
| 68 | 893 18 | 412 52 |
| 69 | 903 05 | 414 12 |
| 70 | 912 90 | 415 85 |
| 71 | 922 73 | 417 72 |
| 72 | 932 52 | 419 73 |
| 73 | 942 29 | 421 88 |
| 74 | 952 02 | 424 16 |
| 75 | 961 73 | 425 58 |
| 76 | 971 40 | 429 14 |
| 77 | 981 03 | 431 83 |
| 78 | 990 62 | 434 66 |
| 79 | 1000 17 | 437 62 |
| 80 | 1009 68 | 440 72 |
| 81 | 1019 14 | 443 94 |
| 82 | 1028 56 | 447 31 |
| 83 | 1037 93 | 450 80 |
| 84 | 1047 25 | 454 43 |
| 85 | 1056 52 | 458 18 |
| 86 | 1065 73 | 462 07 |
| 87 | 1074 89 | 465 08 |
| 88 | 1083 99 | 470 23 |
| 89 | 1093 03 | 474 50 |
| 90 | 1102 01 | 478 89 |
| 91 | 1110 93 | 483 42 |
| 92 | 1119 79 | 488 07 |
| 93 | 1128 58 | 492 84 |
| 94 | 1137 29 | 497 73 |
| 95 | 1145 95 | 502 75 |
| 96 | 1154 52 | 507 89 |
| 97 | 1163 03 | 513 15 |
| 98 | 1171 46 | 518 53 |
| 99 | 1179 82 | 524 02 |
| 100 | 1188 09 | 529 63 |
| 101 | 1196 29 | 535 36 |
| 102 | 1204 40 | 541 20 |

16/130

| | | |
|-----|---------|--------|
| 103 | 1212 44 | 547 16 |
| 104 | 1220 38 | 553 23 |
| 105 | 1228 25 | 559 41 |
| 106 | 1236 02 | 565 70 |
| 107 | 1243 71 | 572 10 |
| 108 | 1251 30 | 578 60 |
| 109 | 1258 80 | 585 22 |
| 110 | 1266 21 | 591 93 |
| 111 | 1273 52 | 598 75 |
| 112 | 1280 74 | 605 68 |
| 113 | 1287 85 | 612 70 |
| 114 | 1294 88 | 619 82 |
| 115 | 1301 80 | 527 04 |
| 116 | 1308 61 | 634 36 |
| 117 | 1315 33 | 641 77 |
| 118 | 1321 93 | 549 28 |
| 119 | 1328 44 | 656 87 |
| 120 | 1334 83 | 664 56 |
| 121 | 1339 22 | 670 00 |

Circle Center At X = 784 7 , Y = 1115 6 and Radius, 711 4
*** 2 865 ***

Failure Surface Specified By 117 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 402 50 | 615 76 |
| 2 | 409 58 | 608 69 |
| 3 | 416 75 | 601 73 |
| 4 | 424 03 | 594 87 |
| 5 | 431 41 | 588 12 |
| 6 | 438 89 | 581 48 |
| 7 | 446 46 | 574 95 |
| 8 | 454 13 | 568 53 |
| 9 | 461 89 | 562 22 |
| 10 | 459 74 | 556 03 |
| 11 | 477 68 | 549 95 |
| 12 | 485 71 | 543 99 |
| 13 | 493 83 | 538 15 |
| 14 | 502 03 | 532 43 |
| 15 | 510 31 | 526 82 |
| 16 | 518 68 | 521 34 |
| 17 | 527 12 | 515 99 |
| 18 | 535 64 | 510 75 |
| 19 | 544 24 | 505 55 |
| 20 | 552 91 | 500 66 |
| 21 | 561 65 | 495 81 |
| 22 | 570 46 | 491 08 |
| 23 | 579 35 | 486 49 |
| 24 | 588 29 | 482 02 |
| 25 | 597 30 | 477 69 |
| 26 | 606 38 | 473 48 |
| 27 | 615 51 | 469 41 |
| 28 | 624 71 | 455 48 |
| 29 | 533 96 | 461 68 |
| 30 | 643 26 | 458 01 |
| 31 | 652 52 | 454 49 |
| 32 | 662 02 | 451 10 |
| 33 | 671 48 | 447 84 |
| 34 | 580 98 | 444 73 |
| 35 | 690 53 | 441 75 |
| 35 | 700 12 | 438 92 |
| 37 | 709 75 | 436 22 |
| 38 | 719 42 | 433 67 |
| 39 | 729 12 | 431 26 |
| 40 | 738 86 | 428 99 |
| 41 | 748 63 | 426 85 |
| 42 | 758 44 | 424 88 |
| 43 | 768 27 | 423 04 |
| 44 | 778 12 | 421 35 |

| | | |
|-----|---------|--------|
| 45 | 788 00 | 419 79 |
| 46 | 797 90 | 418 39 |
| 47 | 807 82 | 417 13 |
| 48 | 817 76 | 416 01 |
| 49 | 827 71 | 415 04 |
| 50 | 837 68 | 414 21 |
| 51 | 847 65 | 413 53 |
| 52 | 857 64 | 413 00 |
| 53 | 867 63 | 412 61 |
| 54 | 877 63 | 412 37 |
| 55 | 887 63 | 412 28 |
| 56 | 897 63 | 412 33 |
| 57 | 907 63 | 412 53 |
| 58 | 917 62 | 412 87 |
| 59 | 927 61 | 413 36 |
| 60 | 937 59 | 414 00 |
| 61 | 947 56 | 414 78 |
| 62 | 957 51 | 415 71 |
| 63 | 967 46 | 416 78 |
| 64 | 977 38 | 418 00 |
| 65 | 987 29 | 419 36 |
| 66 | 997 17 | 420 87 |
| 67 | 1007 04 | 422 53 |
| 68 | 1016 87 | 424 32 |
| 69 | 1026 68 | 426 26 |
| 70 | 1036 46 | 428 35 |
| 71 | 1045 21 | 430 57 |
| 72 | 1055 93 | 432 94 |
| 73 | 1055 61 | 435 46 |
| 74 | 1075 25 | 438 11 |
| 75 | 1084 85 | 440 90 |
| 76 | 1094 41 | 443 84 |
| 77 | 1103 93 | 446 91 |
| 78 | 1113 40 | 450 12 |
| 79 | 1122 82 | 453 47 |
| 80 | 1132 19 | 456 96 |
| 81 | 1141 51 | 460 58 |
| 82 | 1150 78 | 454 34 |
| 83 | 1159 99 | 468 24 |
| 84 | 1169 14 | 472 27 |
| 85 | 1178 23 | 476 43 |
| 86 | 1187 26 | 480 73 |
| 87 | 1196 23 | 485 15 |
| 88 | 1205 13 | 489 71 |
| 89 | 1213 96 | 494 40 |
| 90 | 1222 73 | 499 22 |
| 91 | 1231 42 | 504 16 |
| 92 | 1240 04 | 509 23 |
| 93 | 1248 58 | 514 43 |
| 94 | 1257 05 | 519 75 |
| 95 | 1265 44 | 525 19 |
| 96 | 1273 74 | 530 76 |
| 97 | 1281 97 | 536 45 |
| 98 | 1290 11 | 542 25 |
| 99 | 1298 17 | 548 18 |
| 100 | 1306 13 | 554 22 |
| 101 | 1314 01 | 560 38 |
| 102 | 1321 80 | 566 65 |
| 103 | 1329 49 | 573 04 |
| 104 | 1337 10 | 579 54 |
| 105 | 1344 60 | 586 15 |
| 106 | 1352 01 | 592 87 |
| 107 | 1359 32 | 599 59 |
| 108 | 1366 52 | 606 62 |
| 109 | 1373 63 | 513 66 |
| 110 | 1380 63 | 520 80 |
| 111 | 1387 53 | 628 04 |
| 112 | 1394 32 | 635 38 |

18/130

| | | |
|-----|---------|--------|
| 113 | 1401 00 | 642 82 |
| 114 | 1407 57 | 650 35 |
| 115 | 1414 03 | 657 99 |
| 116 | 1420 38 | 665 72 |
| 117 | 1423 80 | 670 00 |

Circle Center At X = 889 1 , Y = 1095 8 and Radius, 683 6
 *** 2 867 ***

Failure Surface Specified By 127 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 300 42 | 614 51 |
| 2 | 307 68 | 607 64 |
| 3 | 315 03 | 600 86 |
| 4 | 322 47 | 594 17 |
| 5 | 330 00 | 587 59 |
| 6 | 337 61 | 581 10 |
| 7 | 345 30 | 574 71 |
| 8 | 353 07 | 568 42 |
| 9 | 350 93 | 562 23 |
| 10 | 368 86 | 556 15 |
| 11 | 376 88 | 550 17 |
| 12 | 384 97 | 544 29 |
| 13 | 393 13 | 538 51 |
| 14 | 401 37 | 532 84 |
| 15 | 409 58 | 527 28 |
| 16 | 418 06 | 521 83 |
| 17 | 426 52 | 516 49 |
| 18 | 435 04 | 511 25 |
| 19 | 443 63 | 506 13 |
| 20 | 452 28 | 501 12 |
| 21 | 461 00 | 496 22 |
| 22 | 469 78 | 491 43 |
| 23 | 478 62 | 486 76 |
| 24 | 487 52 | 482 20 |
| 25 | 496 48 | 477 76 |
| 26 | 505 49 | 473 43 |
| 27 | 514 56 | 469 22 |
| 28 | 523 69 | 465 13 |
| 29 | 532 86 | 461 16 |
| 30 | 542 09 | 457 30 |
| 31 | 551 37 | 453 57 |
| 32 | 560 69 | 449 95 |
| 33 | 570 06 | 445 45 |
| 34 | 579 48 | 443 09 |
| 35 | 588 93 | 439 84 |
| 36 | 598 43 | 436 71 |
| 37 | 607 97 | 433 71 |
| 38 | 617 55 | 430 83 |
| 39 | 627 16 | 428 07 |
| 40 | 636 81 | 425 44 |
| 41 | 645 49 | 422 93 |
| 42 | 656 20 | 420 55 |
| 43 | 665 94 | 418 29 |
| 44 | 675 71 | 416 16 |
| 45 | 685 51 | 414 16 |
| 46 | 695 33 | 412 28 |
| 47 | 705 18 | 410 53 |
| 48 | 715 04 | 408 91 |
| 49 | 724 93 | 407 42 |
| 50 | 734 84 | 406 05 |
| 51 | 744 76 | 404 81 |
| 52 | 754 70 | 403 70 |
| 53 | 764 65 | 402 72 |
| 54 | 774 51 | 401 87 |
| 55 | 784 59 | 401 15 |
| 56 | 794 57 | 400 55 |
| 57 | 804 56 | 400 09 |
| 58 | 814 55 | 399 75 |

19/130

| | | | | |
|-----|------|----|-----|----|
| 59 | 824 | 55 | 399 | 54 |
| 50 | 834 | 55 | 399 | 47 |
| 51 | 844 | 55 | 399 | 52 |
| 62 | 854 | 55 | 399 | 70 |
| 63 | 864 | 55 | 400 | 01 |
| 64 | 874 | 54 | 400 | 45 |
| 65 | 884 | 52 | 401 | 02 |
| 66 | 894 | 50 | 401 | 72 |
| 67 | 904 | 46 | 402 | 54 |
| 68 | 914 | 42 | 403 | 50 |
| 69 | 924 | 36 | 404 | 58 |
| 70 | 934 | 28 | 405 | 79 |
| 71 | 944 | 19 | 407 | 14 |
| 72 | 954 | 08 | 408 | 60 |
| 73 | 963 | 96 | 410 | 20 |
| 74 | 973 | 81 | 411 | 93 |
| 75 | 983 | 63 | 413 | 78 |
| 76 | 993 | 44 | 415 | 76 |
| 77 | 1003 | 21 | 417 | 86 |
| 78 | 1012 | 96 | 420 | 09 |
| 79 | 1022 | 68 | 422 | 45 |
| 80 | 1032 | 36 | 424 | 93 |
| 81 | 1042 | 02 | 427 | 54 |
| 82 | 1051 | 64 | 430 | 27 |
| 83 | 1051 | 22 | 433 | 13 |
| 84 | 1070 | 77 | 436 | 11 |
| 85 | 1080 | 27 | 439 | 21 |
| 86 | 1089 | 74 | 442 | 44 |
| 87 | 1099 | 16 | 445 | 78 |
| 88 | 1108 | 54 | 449 | 25 |
| 89 | 1117 | 87 | 452 | 84 |
| 90 | 1127 | 16 | 456 | 56 |
| 91 | 1136 | 40 | 460 | 39 |
| 92 | 1145 | 58 | 454 | 34 |
| 93 | 1154 | 72 | 468 | 40 |
| 94 | 1153 | 80 | 472 | 59 |
| 95 | 1172 | 83 | 476 | 89 |
| 95 | 1181 | 80 | 481 | 31 |
| 97 | 1190 | 71 | 485 | 85 |
| 98 | 1199 | 56 | 490 | 50 |
| 99 | 1208 | 35 | 495 | 26 |
| 100 | 1217 | 08 | 500 | 14 |
| 101 | 1225 | 75 | 505 | 13 |
| 102 | 1234 | 35 | 510 | 23 |
| 103 | 1242 | 89 | 515 | 44 |
| 104 | 1251 | 35 | 520 | 77 |
| 105 | 1259 | 75 | 526 | 20 |
| 106 | 1268 | 07 | 531 | 74 |
| 107 | 1276 | 33 | 537 | 38 |
| 108 | 1284 | 51 | 543 | 14 |
| 109 | 1292 | 61 | 548 | 99 |
| 110 | 1300 | 64 | 554 | 96 |
| 111 | 1308 | 59 | 561 | 02 |
| 112 | 1316 | 46 | 567 | 19 |
| 113 | 1324 | 25 | 573 | 46 |
| 114 | 1331 | 96 | 579 | 83 |
| 115 | 1339 | 59 | 586 | 30 |
| 116 | 1347 | 13 | 592 | 86 |
| 117 | 1354 | 58 | 599 | 53 |
| 118 | 1361 | 95 | 606 | 29 |
| 119 | 1369 | 24 | 613 | 14 |
| 120 | 1376 | 43 | 620 | 09 |
| 121 | 1383 | 53 | 627 | 13 |
| 122 | 1390 | 54 | 634 | 25 |
| 123 | 1397 | 46 | 641 | 48 |
| 124 | 1404 | 28 | 648 | 79 |
| 125 | 1411 | 01 | 656 | 19 |
| 126 | 1417 | 64 | 563 | 68 |

20/130

127 1423 10 670 00
Circle Center At X = 835 5 , Y = 1172 8 and Radius, 773 3
*** 2 873 ***

Failure Surface Specified By 126 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 382 08 | 615 51 |
| 2 | 389 15 | 608 44 |
| 3 | 396 32 | 601 46 |
| 4 | 403 58 | 594 58 |
| 5 | 410 93 | 587 80 |
| 6 | 418 38 | 581 13 |
| 7 | 425 91 | 574 55 |
| 8 | 433 53 | 568 07 |
| 9 | 441 24 | 561 70 |
| 10 | 449 03 | 555 44 |
| 11 | 456 91 | 549 28 |
| 12 | 464 87 | 543 22 |
| 13 | 472 91 | 537 28 |
| 14 | 481 03 | 531 44 |
| 15 | 489 23 | 525 71 |
| 16 | 497 50 | 520 10 |
| 17 | 505 85 | 514 60 |
| 18 | 514 27 | 509 21 |
| 19 | 522 77 | 503 93 |
| 20 | 531 34 | 498 77 |
| 21 | 539 97 | 493 73 |
| 22 | 548 67 | 488 81 |
| 23 | 557 44 | 484 00 |
| 24 | 565 28 | 479 31 |
| 25 | 575 17 | 474 74 |
| 26 | 584 13 | 470 29 |
| 27 | 593 14 | 465 97 |
| 28 | 602 22 | 461 76 |
| 29 | 611 35 | 457 68 |
| 30 | 620 53 | 453 72 |
| 31 | 629 76 | 449 89 |
| 32 | 639 05 | 446 18 |
| 33 | 648 39 | 442 50 |
| 34 | 657 77 | 439 14 |
| 35 | 667 20 | 435 82 |
| 36 | 676 68 | 432 52 |
| 37 | 686 19 | 429 54 |
| 38 | 695 75 | 426 50 |
| 39 | 705 35 | 423 79 |
| 40 | 714 98 | 421 10 |
| 41 | 724 65 | 418 55 |
| 42 | 734 35 | 416 13 |
| 43 | 744 08 | 413 83 |
| 44 | 753 85 | 411 68 |
| 45 | 763 64 | 409 65 |
| 46 | 773 46 | 407 75 |
| 47 | 783 30 | 405 99 |
| 48 | 793 17 | 404 36 |
| 49 | 803 06 | 402 87 |
| 50 | 812 96 | 401 51 |
| 51 | 822 89 | 400 28 |
| 52 | 832 83 | 399 19 |
| 53 | 842 78 | 398 23 |
| 54 | 852 75 | 397 40 |
| 55 | 862 72 | 396 72 |
| 56 | 872 71 | 395 16 |
| 57 | 882 70 | 395 74 |
| 58 | 892 70 | 395 46 |
| 59 | 902 69 | 395 31 |
| 60 | 912 69 | 395 30 |
| 61 | 922 69 | 395 42 |
| 62 | 932 69 | 395 67 |

21/130

| | | |
|-----|---------|--------|
| 63 | 942 68 | 396 07 |
| 64 | 952 67 | 396 59 |
| 65 | 962 65 | 397 25 |
| 55 | 972 62 | 398 05 |
| 67 | 982 57 | 398 98 |
| 68 | 992 52 | 400 05 |
| 69 | 1002 44 | 401 25 |
| 70 | 1012 35 | 402 58 |
| 71 | 1022 25 | 404 05 |
| 72 | 1032 12 | 405 65 |
| 73 | 1041 96 | 407 39 |
| 74 | 1051 79 | 409 25 |
| 75 | 1061 59 | 411 25 |
| 76 | 1071 36 | 413 39 |
| 77 | 1081 10 | 415 65 |
| 78 | 1090 81 | 418 05 |
| 79 | 1100 48 | 420 57 |
| 80 | 1110 12 | 423 23 |
| 81 | 1119 72 | 426 02 |
| 82 | 1129 29 | 428 94 |
| 83 | 1138 81 | 431 98 |
| 84 | 1148 30 | 435 15 |
| 85 | 1157 74 | 438 45 |
| 86 | 1167 13 | 441 89 |
| 87 | 1176 48 | 445 45 |
| 88 | 1185 77 | 449 13 |
| 89 | 1195 02 | 452 94 |
| 90 | 1204 21 | 456 87 |
| 91 | 1213 35 | 450 92 |
| 92 | 1222 44 | 465 10 |
| 93 | 1231 47 | 469 41 |
| 94 | 1240 43 | 473 83 |
| 95 | 1249 34 | 478 37 |
| 96 | 1258 19 | 483 04 |
| 97 | 1266 97 | 487 82 |
| 98 | 1275 69 | 492 72 |
| 99 | 1284 34 | 497 74 |
| 100 | 1292 92 | 502 88 |
| 101 | 1301 43 | 508 13 |
| 102 | 1309 86 | 513 50 |
| 103 | 1318 23 | 518 97 |
| 104 | 1326 52 | 524 57 |
| 105 | 1334 73 | 530 27 |
| 106 | 1342 87 | 536 08 |
| 107 | 1350 93 | 542 01 |
| 108 | 1358 90 | 548 04 |
| 109 | 1366 80 | 554 18 |
| 110 | 1374 61 | 560 42 |
| 111 | 1382 33 | 565 77 |
| 112 | 1389 97 | 573 23 |
| 113 | 1397 52 | 579 78 |
| 114 | 1404 98 | 586 44 |
| 115 | 1412 35 | 593 20 |
| 116 | 1419 53 | 600 06 |
| 117 | 1426 82 | 607 01 |
| 118 | 1433 91 | 614 06 |
| 119 | 1440 90 | 621 21 |
| 120 | 1447 80 | 628 45 |
| 121 | 1454 60 | 635 79 |
| 122 | 1461 30 | 643 21 |
| 123 | 1467 89 | 650 72 |
| 124 | 1474 39 | 658 33 |
| 125 | 1480 78 | 665 02 |
| 126 | 1484 00 | 670 00 |

Circle Center At X = 908 7 , Y = 1135 0 and Radius, 739 8

*** 2 875 ***

Failure Surface Specified By 90 Coordinate Points

| Point | X-Surf | Y-Surf |
|-------|--------|--------|
|-------|--------|--------|

22/130

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 504 58 | 617 00 |
| 2 | 511 67 | 609 95 |
| 3 | 518 90 | 603 04 |
| 4 | 526 26 | 596 26 |
| 5 | 533 74 | 589 64 |
| 6 | 541 36 | 583 16 |
| 7 | 549 10 | 576 82 |
| 8 | 556 96 | 570 64 |
| 9 | 564 94 | 564 62 |
| 10 | 573 04 | 558 74 |
| 11 | 581 24 | 553 03 |
| 12 | 589 55 | 547 48 |
| 13 | 597 98 | 542 09 |
| 14 | 606 51 | 536 87 |
| 15 | 615 14 | 531 81 |
| 16 | 623 86 | 526 92 |
| 17 | 632 68 | 522 20 |
| 18 | 641 58 | 517 65 |
| 19 | 650 57 | 513 28 |
| 20 | 659 65 | 509 08 |
| 21 | 668 81 | 505 05 |
| 22 | 678 04 | 501 21 |
| 23 | 687 34 | 497 55 |
| 24 | 596 72 | 494 07 |
| 25 | 706 16 | 490 77 |
| 26 | 715 66 | 487 65 |
| 27 | 725 22 | 484 72 |
| 28 | 734 84 | 481 98 |
| 29 | 744 50 | 479 42 |
| 30 | 754 22 | 477 05 |
| 31 | 763 98 | 474 87 |
| 32 | 773 78 | 472 88 |
| 33 | 783 62 | 471 09 |
| 34 | 793 49 | 469 48 |
| 35 | 803 39 | 468 06 |
| 36 | 813 31 | 466 84 |
| 37 | 823 26 | 465 81 |
| 38 | 833 22 | 464 97 |
| 39 | 843 20 | 464 33 |
| 40 | 853 19 | 463 88 |
| 41 | 863 19 | 463 62 |
| 42 | 873 19 | 463 56 |
| 43 | 883 19 | 463 69 |
| 44 | 893 18 | 454 02 |
| 45 | 903 17 | 464 54 |
| 46 | 913 14 | 465 26 |
| 47 | 923 10 | 466 15 |
| 48 | 933 04 | 467 27 |
| 49 | 942 96 | 468 56 |
| 50 | 952 85 | 470 05 |
| 51 | 952 70 | 471 72 |
| 52 | 972 53 | 473 59 |
| 53 | 982 31 | 475 65 |
| 54 | 992 06 | 477 90 |
| 55 | 1001 75 | 480 34 |
| 56 | 1011 40 | 482 97 |
| 57 | 1021 00 | 485 78 |
| 58 | 1030 54 | 488 78 |
| 59 | 1040 02 | 491 96 |
| 60 | 1049 44 | 495 33 |
| 61 | 1058 79 | 498 88 |
| 62 | 1068 06 | 502 60 |
| 63 | 1077 27 | 505 51 |
| 64 | 1086 40 | 510 60 |
| 65 | 1095 44 | 514 86 |
| 66 | 1104 40 | 519 30 |
| 67 | 1113 28 | 523 91 |

| | | |
|----|---------|--------|
| 68 | 1122 06 | 528 70 |
| 69 | 1130 74 | 533 65 |
| 70 | 1139 33 | 538 77 |
| 71 | 1147 82 | 544 05 |
| 72 | 1156 21 | 549 50 |
| 73 | 1164 49 | 555 12 |
| 74 | 1172 65 | 560 89 |
| 75 | 1180 71 | 566 81 |
| 76 | 1188 64 | 572 90 |
| 77 | 1196 46 | 579 14 |
| 78 | 1204 15 | 585 52 |
| 79 | 1211 72 | 592 06 |
| 80 | 1219 16 | 598 74 |
| 81 | 1226 47 | 605 56 |
| 82 | 1233 65 | 612 53 |
| 83 | 1240 69 | 619 63 |
| 84 | 1247 59 | 626 87 |
| 85 | 1254 34 | 634 24 |
| 86 | 1260 96 | 641 74 |
| 87 | 1267 42 | 649 37 |
| 88 | 1273 74 | 657 12 |
| 89 | 1279 91 | 664 99 |
| 90 | 1283 57 | 670 00 |

Circle Center At X = 871 3 , Y = 978 6 and Radius, 515 0
 *** 2 890 ***

Failure Surface Specified By100 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 402 50 | 615 76 |
| 2 | 409 55 | 608 76 |
| 3 | 416 92 | 501 90 |
| 4 | 424 31 | 595 15 |
| 5 | 431 81 | 588 54 |
| 6 | 439 42 | 582 06 |
| 7 | 447 14 | 575 71 |
| 8 | 454 97 | 569 49 |
| 9 | 462 91 | 563 40 |
| 10 | 470 95 | 557 46 |
| 11 | 479 09 | 551 65 |
| 12 | 487 33 | 545 98 |
| 13 | 495 66 | 540 46 |
| 14 | 504 09 | 535 07 |
| 15 | 512 61 | 529 84 |
| 16 | 521 22 | 524 75 |
| 17 | 529 92 | 519 81 |
| 18 | 538 69 | 515 02 |
| 19 | 547 55 | 510 38 |
| 20 | 556 49 | 505 89 |
| 21 | 565 50 | 501 56 |
| 22 | 574 59 | 497 38 |
| 23 | 583 74 | 493 36 |
| 24 | 592 97 | 489 50 |
| 25 | 602 26 | 485 79 |
| 26 | 611 61 | 482 25 |
| 27 | 621 02 | 478 87 |
| 28 | 630 48 | 475 64 |
| 29 | 640 00 | 472 59 |
| 30 | 649 58 | 469 69 |
| 31 | 659 20 | 466 96 |
| 32 | 668 86 | 454 40 |
| 33 | 678 57 | 462 00 |
| 34 | 688 32 | 459 77 |
| 35 | 698 10 | 457 70 |
| 36 | 707 92 | 455 81 |
| 37 | 717 77 | 454 08 |
| 38 | 727 65 | 452 52 |
| 39 | 737 55 | 451 13 |
| 40 | 747 48 | 449 91 |


24/130

| | | |
|-----|---------|--------|
| 41 | 757 42 | 448 87 |
| 42 | 767 38 | 447 99 |
| 43 | 777 36 | 447 28 |
| 44 | 787 34 | 446 75 |
| 45 | 797 34 | 446 39 |
| 46 | 807 34 | 446 19 |
| 47 | 817 34 | 446 17 |
| 48 | 827 33 | 446 33 |
| 49 | 837 33 | 446 65 |
| 50 | 847 32 | 447 14 |
| 51 | 857 29 | 447 81 |
| 52 | 867 26 | 448 65 |
| 53 | 877 21 | 449 65 |
| 54 | 887 14 | 450 83 |
| 55 | 897 05 | 452 18 |
| 56 | 906 93 | 453 70 |
| 57 | 916 79 | 455 39 |
| 58 | 926 61 | 457 24 |
| 59 | 936 41 | 459 27 |
| 60 | 946 16 | 461 46 |
| 61 | 955 88 | 463 82 |
| 62 | 965 56 | 466 35 |
| 63 | 975 19 | 469 04 |
| 64 | 984 77 | 471 90 |
| 65 | 994 30 | 474 92 |
| 66 | 1003 78 | 478 10 |
| 67 | 1013 21 | 481 45 |
| 68 | 1022 57 | 484 95 |
| 69 | 1031 88 | 488 62 |
| 70 | 1041 11 | 492 45 |
| 71 | 1050 29 | 495 43 |
| 72 | 1059 39 | 500 57 |
| 73 | 1068 42 | 504 87 |
| 74 | 1077 37 | 509 32 |
| 75 | 1086 25 | 513 92 |
| 76 | 1095 05 | 518 68 |
| 77 | 1103 75 | 523 58 |
| 78 | 1112 39 | 528 64 |
| 79 | 1120 93 | 533 84 |
| 80 | 1129 38 | 539 19 |
| 81 | 1137 74 | 544 68 |
| 82 | 1146 00 | 550 31 |
| 83 | 1154 16 | 556 09 |
| 84 | 1162 23 | 562 00 |
| 85 | 1170 19 | 568 06 |
| 86 | 1178 04 | 574 24 |
| 87 | 1185 79 | 580 56 |
| 88 | 1193 43 | 587 02 |
| 89 | 1200 96 | 593 60 |
| 90 | 1208 37 | 600 31 |
| 91 | 1215 67 | 607 15 |
| 92 | 1222 85 | 614 11 |
| 93 | 1229 90 | 621 20 |
| 94 | 1236 84 | 628 40 |
| 95 | 1243 65 | 635 73 |
| 96 | 1250 33 | 643 16 |
| 97 | 1256 89 | 650 72 |
| 98 | 1263 31 | 658 38 |
| 99 | 1269 61 | 666 15 |
| 100 | 1272 61 | 670 00 |

Circle Center At X = 813 5 , Y = 1028 9 and Radius, 582 8
*** 2 893 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\12 pl2 Run By Greg Shafer, HDR 4/20/2010 02:04PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Piez. Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|---------------|
| a | 1 00 | | | | | | No |
| b | 1 02 | | | | | | No |
| c | 1 03 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | W1 |
| d | 1 04 | LSC | 2 | 121.0 | 125.5 | 1500.0 | W1 |
| e | 1 05 | SC | 3 | 121.0 | 125.5 | 2000.0 | W1 |
| f | 1 05 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | W1 |
| g | 1 06 | | | | | | |
| h | 1 07 | | | | | | |
| i | 1 07 | | | | | | |
| j | 1 08 | | | | | | |

| Load | Value |
|----------------------|----------|
| Honz Eqk | 0 100 g< |
| <i>✓ RHP 4-26-10</i> | |

STED



PCSTABL7 FSmin=1.00
Safety Factors Are Calculated By The Modified Bishop Method

25/30

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 02 04PM
Run By Greg Shafer, HDR
Input Data Filename C 2 in
Output Filename C 2 OUT
Unit ENGLISH
Plotted Output Filename C 2 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 550 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of 0 100 Has Been Assigned

A Vertical Earthquake Loading Coefficient
Of 0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 500 00 ft

and X = 770 00 ft

Each Surface Terminates Between X = 950 00 ft

and X = 2250 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 188 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 511 25 | 617 08 |
| 2 | 518 40 | 610 09 |
| 3 | 525 61 | 603 16 |
| 4 | 532 88 | 596 30 |
| 5 | 540 21 | 589 49 |
| 6 | 547 60 | 582 75 |
| 7 | 555 04 | 576 08 |
| 8 | 562 55 | 569 47 |

| | | |
|----|---------|--------|
| 9 | 570 11 | 562 93 |
| 10 | 577 73 | 556 45 |
| 11 | 585 40 | 550 04 |
| 12 | 593 13 | 543 69 |
| 13 | 600 92 | 537 41 |
| 14 | 608 75 | 531 20 |
| 15 | 616 65 | 525 06 |
| 16 | 624 59 | 518 99 |
| 17 | 632 59 | 512 99 |
| 18 | 640 64 | 507 05 |
| 19 | 648 74 | 501 19 |
| 20 | 656 89 | 495 40 |
| 21 | 665 09 | 489 68 |
| 22 | 673 34 | 484 03 |
| 23 | 681 64 | 478 45 |
| 24 | 689 99 | 472 94 |
| 25 | 598 39 | 467 51 |
| 26 | 706 83 | 462 15 |
| 27 | 715 32 | 456 86 |
| 28 | 723 85 | 451 65 |
| 29 | 732 43 | 446 51 |
| 30 | 741 05 | 441 45 |
| 31 | 749 72 | 436 46 |
| 32 | 758 43 | 431 55 |
| 33 | 767 18 | 426 71 |
| 34 | 775 98 | 421 95 |
| 35 | 784 81 | 417 27 |
| 36 | 793 69 | 412 66 |
| 37 | 802 60 | 408 13 |
| 38 | 811 55 | 403 68 |
| 39 | 820 55 | 399 30 |
| 40 | 829 58 | 395 00 |
| 41 | 838 64 | 390 79 |
| 42 | 847 75 | 386 65 |
| 43 | 856 89 | 382 59 |
| 44 | 866 06 | 378 61 |
| 45 | 875 27 | 374 71 |
| 46 | 884 51 | 370 89 |
| 47 | 893 79 | 367 15 |
| 48 | 903 09 | 363 49 |
| 49 | 912 43 | 359 91 |
| 50 | 921 80 | 356 42 |
| 51 | 931 20 | 353 00 |
| 52 | 940 63 | 349 67 |
| 53 | 950 08 | 346 42 |
| 54 | 959 57 | 343 25 |
| 55 | 959 08 | 340 17 |
| 56 | 978 62 | 337 16 |
| 57 | 988 18 | 334 24 |
| 58 | 997 77 | 331 40 |
| 59 | 1007 38 | 328 65 |
| 60 | 1017 02 | 325 98 |
| 61 | 1026 68 | 323 39 |
| 62 | 1036 36 | 320 89 |
| 63 | 1046 07 | 318 47 |
| 64 | 1055 79 | 316 14 |
| 65 | 1065 53 | 313 89 |
| 66 | 1075 30 | 311 73 |
| 67 | 1085 08 | 309 65 |
| 68 | 1094 88 | 307 65 |
| 69 | 1104 69 | 305 74 |
| 70 | 1114 53 | 303 92 |
| 71 | 1124 37 | 302 18 |
| 72 | 1134 24 | 300 53 |
| 73 | 1144 11 | 298 96 |
| 74 | 1154 00 | 297 48 |
| 75 | 1163 90 | 296 09 |
| 76 | 1173 82 | 294 78 |

28/130

| | | |
|-----|---------|--------|
| 77 | 1183 74 | 293 55 |
| 78 | 1193 68 | 292 42 |
| 79 | 1203 62 | 291 37 |
| 80 | 1213 58 | 290 40 |
| 81 | 1223 54 | 289 53 |
| 82 | 1233 51 | 288 74 |
| 83 | 1243 48 | 288 03 |
| 84 | 1253 46 | 287 42 |
| 85 | 1263 45 | 286 88 |
| 86 | 1273 44 | 286 44 |
| 87 | 1283 43 | 286 08 |
| 88 | 1293 43 | 285 81 |
| 89 | 1303 43 | 285 63 |
| 90 | 1313 43 | 285 53 |
| 91 | 1323 43 | 285 52 |
| 92 | 1333 43 | 285 60 |
| 93 | 1343 43 | 285 77 |
| 94 | 1353 42 | 286 02 |
| 95 | 1363 42 | 285 36 |
| 96 | 1373 41 | 286 78 |
| 97 | 1383 39 | 287 29 |
| 98 | 1393 38 | 287 89 |
| 99 | 1403 35 | 288 58 |
| 100 | 1413 32 | 289 35 |
| 101 | 1423 29 | 290 21 |
| 102 | 1433 24 | 291 15 |
| 103 | 1443 19 | 292 18 |
| 104 | 1453 13 | 293 30 |
| 105 | 1453 05 | 294 50 |
| 106 | 1472 97 | 295 79 |
| 107 | 1482 87 | 297 17 |
| 108 | 1492 77 | 298 63 |
| 109 | 1502 65 | 300 18 |
| 110 | 1512 51 | 301 81 |
| 111 | 1522 36 | 303 53 |
| 112 | 1532 20 | 305 34 |
| 113 | 1542 02 | 307 23 |
| 114 | 1551 82 | 309 21 |
| 115 | 1561 61 | 311 27 |
| 116 | 1571 37 | 313 41 |
| 117 | 1581 12 | 315 64 |
| 118 | 1590 85 | 317 96 |
| 119 | 1600 56 | 320 36 |
| 120 | 1610 24 | 322 84 |
| 121 | 1619 91 | 325 41 |
| 122 | 1629 55 | 328 06 |
| 123 | 1639 17 | 330 80 |
| 124 | 1648 76 | 333 62 |
| 125 | 1658 33 | 335 52 |
| 126 | 1557 88 | 339 50 |
| 127 | 1677 40 | 342 57 |
| 128 | 1686 89 | 345 72 |
| 129 | 1596 35 | 348 96 |
| 130 | 1705 78 | 352 27 |
| 131 | 1715 19 | 355 67 |
| 132 | 1724 56 | 359 15 |
| 133 | 1733 91 | 362 71 |
| 134 | 1743 22 | 366 35 |
| 135 | 1752 50 | 370 07 |
| 136 | 1761 75 | 373 87 |
| 137 | 1770 97 | 377 75 |
| 138 | 1780 15 | 381 72 |
| 139 | 1789 30 | 385 76 |
| 140 | 1798 41 | 389 88 |
| 141 | 1807 48 | 394 08 |
| 142 | 1816 52 | 398 36 |
| 143 | 1825 52 | 402 72 |
| 144 | 1834 48 | 407 15 |

29/30

| | | | | |
|-----|------|----|-----|----|
| 145 | 1843 | 41 | 411 | 67 |
| 146 | 1852 | 29 | 416 | 26 |
| 147 | 1861 | 14 | 420 | 92 |
| 148 | 1869 | 94 | 425 | 67 |
| 149 | 1878 | 70 | 430 | 49 |
| 150 | 1887 | 42 | 435 | 38 |
| 151 | 1896 | 10 | 440 | 36 |
| 152 | 1904 | 73 | 445 | 40 |
| 153 | 1913 | 32 | 450 | 53 |
| 154 | 1921 | 86 | 455 | 72 |
| 155 | 1930 | 36 | 460 | 99 |
| 156 | 1938 | 81 | 466 | 34 |
| 157 | 1947 | 22 | 471 | 75 |
| 158 | 1955 | 58 | 477 | 24 |
| 159 | 1963 | 89 | 482 | 81 |
| 160 | 1972 | 15 | 488 | 44 |
| 161 | 1980 | 36 | 494 | 15 |
| 162 | 1988 | 52 | 499 | 92 |
| 163 | 1996 | 63 | 505 | 77 |
| 164 | 2004 | 69 | 511 | 59 |
| 165 | 2012 | 70 | 517 | 68 |
| 166 | 2020 | 66 | 523 | 74 |
| 167 | 2028 | 56 | 529 | 86 |
| 168 | 2036 | 41 | 536 | 06 |
| 169 | 2044 | 21 | 542 | 32 |
| 170 | 2051 | 95 | 548 | 65 |
| 171 | 2059 | 64 | 555 | 05 |
| 172 | 2067 | 27 | 561 | 51 |
| 173 | 2074 | 84 | 568 | 04 |
| 174 | 2082 | 36 | 574 | 64 |
| 175 | 2089 | 82 | 581 | 30 |
| 176 | 2097 | 22 | 588 | 02 |
| 177 | 2104 | 56 | 594 | 81 |
| 178 | 2111 | 84 | 601 | 65 |
| 179 | 2119 | 07 | 608 | 58 |
| 180 | 2125 | 23 | 615 | 56 |
| 181 | 2133 | 33 | 622 | 60 |
| 182 | 2140 | 37 | 629 | 70 |
| 183 | 2147 | 35 | 636 | 86 |
| 184 | 2154 | 27 | 644 | 08 |
| 185 | 2151 | 12 | 651 | 37 |
| 186 | 2167 | 91 | 658 | 71 |
| 187 | 2174 | 63 | 666 | 11 |
| 188 | 2178 | 11 | 670 | 00 |

Circle Center At X = 1319 5 , Y = 1436 4 and Radius, 1150 9
 *** 0 997 ***

Individual data on the 195 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 7 1 | 3062 0 | 0 0 | 0 0 | 0 0 | 0 0 | 306 2 | 0 0 | 0 0 |
| 2 | 7 2 | 9236 9 | 0 0 | 0 0 | 0 0 | 0 0 | 923 7 | 0 0 | 0 0 |
| 3 | 7 3 | 15459 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1545 9 | 0 0 | 0 0 |
| 4 | 7 3 | 21725 9 | 0 0 | 0 0 | 0 0 | 0 0 | 2172 6 | 0 0 | 0 0 |
| 5 | 7 4 | 28033 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2803 4 | 0 0 | 0 0 |
| 6 | 7 4 | 34379 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3438 0 | 0 0 | 0 0 |
| 7 | 7 5 | 40759 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4076 0 | 0 0 | 0 0 |
| 8 | 7 6 | 47171 9 | 0 0 | 0 0 | 0 0 | 0 0 | 4717 2 | 0 0 | 0 0 |
| 9 | 7 6 | 53612 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5351 2 | 0 0 | 0 0 |
| 10 | 7 7 | 60077 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6007 7 | 0 0 | 0 0 |
| 11 | 7 7 | 66564 4 | 0 0 | 0 0 | 0 0 | 0 0 | 6656 4 | 0 0 | 0 0 |
| 12 | 7 8 | 73069 9 | 0 0 | 0 0 | 0 0 | 0 0 | 7307 0 | 0 0 | 0 0 |
| 13 | 7 8 | 79591 4 | 0 0 | 0 0 | 0 0 | 0 0 | 7959 1 | 0 0 | 0 0 |
| 14 | 7 9 | 86125 1 | 0 0 | 0 0 | 0 0 | 0 0 | 8612 5 | 0 0 | 0 0 |
| 15 | 7 9 | 92668 5 | 0 0 | 0 0 | 0 0 | 0 0 | 9266 8 | 0 0 | 0 0 |
| 16 | 8 0 | 99217 1 | 0 0 | 0 0 | 0 0 | 0 0 | 9921 7 | 0 0 | 0 0 |
| 17 | 8 0 | 105769 2 | 0 0 | 0 0 | 0 0 | 0 0 | 10576 9 | 0 0 | 0 0 |

| | | | | | | | | | |
|----|------|----------|-----|-----|-----|-----|---------|-----|-----|
| 18 | 8 1 | 112320 3 | 0 0 | 0 0 | 0 0 | 0 0 | 11232 0 | 0 0 | 0 0 |
| 19 | 8 2 | 118868 8 | 0 0 | 0 0 | 0 0 | 0 0 | 11886 9 | 0 0 | 0 0 |
| 20 | 8 2 | 125411 0 | 0 0 | 0 0 | 0 0 | 0 0 | 12541 1 | 0 0 | 0 0 |
| 21 | 8 3 | 131942 9 | 0 0 | 0 0 | 0 0 | 0 0 | 13194 3 | 0 0 | 0 0 |
| 22 | 8 3 | 138462 3 | 0 0 | 0 0 | 0 0 | 0 0 | 13846 2 | 0 0 | 0 0 |
| 23 | 8 3 | 144966 4 | 0 0 | 0 0 | 0 0 | 0 0 | 14496 5 | 0 0 | 0 0 |
| 24 | 8 4 | 151452 1 | 0 0 | 0 0 | 0 0 | 0 0 | 15145 2 | 0 0 | 0 0 |
| 25 | 8 4 | 157915 5 | 0 0 | 0 0 | 0 0 | 0 0 | 15791 5 | 0 0 | 0 0 |
| 26 | 8 5 | 164354 6 | 0 0 | 0 0 | 0 0 | 0 0 | 16435 5 | 0 0 | 0 0 |
| 27 | 8 5 | 170765 5 | 0 0 | 0 0 | 0 0 | 0 0 | 17076 6 | 0 0 | 0 0 |
| 28 | 8 6 | 177146 4 | 0 0 | 0 0 | 0 0 | 0 0 | 17714 6 | 0 0 | 0 0 |
| 29 | 8 5 | 183493 3 | 0 0 | 0 0 | 0 0 | 0 0 | 18349 3 | 0 0 | 0 0 |
| 30 | 8 7 | 189803 4 | 0 0 | 0 0 | 0 0 | 0 0 | 18980 3 | 0 0 | 0 0 |
| 31 | 0 3 | 6244 7 | 0 0 | 0 0 | 0 0 | 0 0 | 624 5 | 0 0 | 0 0 |
| 32 | 8 4 | 179022 8 | 0 0 | 0 0 | 0 0 | 0 0 | 17902 3 | 0 0 | 0 0 |
| 33 | 8 8 | 192789 5 | 0 0 | 0 0 | 0 0 | 0 0 | 19279 0 | 0 0 | 0 0 |
| 34 | 8 8 | 200586 8 | 0 0 | 0 0 | 0 0 | 0 0 | 20068 7 | 0 0 | 0 0 |
| 35 | 8 8 | 208568 1 | 0 0 | 0 0 | 0 0 | 0 0 | 20856 8 | 0 0 | 0 0 |
| 36 | 8 9 | 215432 1 | 0 0 | 0 0 | 0 0 | 0 0 | 21643 2 | 0 0 | 0 0 |
| 37 | 8 9 | 224272 5 | 0 0 | 0 0 | 0 0 | 0 0 | 22427 3 | 0 0 | 0 0 |
| 38 | 9 0 | 232088 1 | 0 0 | 0 0 | 0 0 | 0 0 | 23208 8 | 0 0 | 0 0 |
| 39 | 9 0 | 239877 3 | 0 0 | 0 0 | 0 0 | 0 0 | 23987 7 | 0 0 | 0 0 |
| 40 | 9 0 | 247634 2 | 0 0 | 0 0 | 0 0 | 0 0 | 24763 4 | 0 0 | 0 0 |
| 41 | 0 4 | 11750 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1175 0 | 0 0 | 0 0 |
| 42 | 8 6 | 259534 3 | 0 0 | 0 0 | 0 0 | 0 0 | 25963 4 | 0 0 | 0 0 |
| 43 | 9 1 | 280200 2 | 0 0 | 0 0 | 0 0 | 0 0 | 28020 0 | 0 0 | 0 0 |
| 44 | 9 1 | 288193 5 | 0 0 | 0 0 | 0 0 | 0 0 | 28819 3 | 0 0 | 0 0 |
| 45 | 9 2 | 296139 8 | 0 0 | 0 0 | 0 0 | 0 0 | 29614 0 | 0 0 | 0 0 |
| 46 | 3 9 | 129228 5 | 0 0 | 0 0 | 0 0 | 0 0 | 12922 9 | 0 0 | 0 0 |
| 47 | 5 3 | 175202 9 | 0 0 | 0 0 | 0 0 | 0 0 | 17520 3 | 0 0 | 0 0 |
| 48 | 9 2 | 312573 1 | 0 0 | 0 0 | 0 0 | 0 0 | 31257 3 | 0 0 | 0 0 |
| 49 | 9 3 | 320361 6 | 0 0 | 0 0 | 0 0 | 0 0 | 32036 2 | 0 0 | 0 0 |
| 50 | 9 3 | 328089 4 | 0 0 | 0 0 | 0 0 | 0 0 | 32808 9 | 0 0 | 0 0 |
| 51 | 6 9 | 247739 7 | 0 0 | 0 0 | 0 0 | 0 0 | 24774 0 | 0 0 | 0 0 |
| 52 | 2 4 | 88198 4 | 0 0 | 0 0 | 0 0 | 0 0 | 8819 8 | 0 0 | 0 0 |
| 53 | 9 4 | 344060 7 | 0 0 | 0 0 | 0 0 | 0 0 | 34405 1 | 0 0 | 0 0 |
| 54 | 9 4 | 351595 0 | 0 0 | 0 0 | 0 0 | 0 0 | 35159 6 | 0 0 | 0 0 |
| 55 | 9 4 | 359059 3 | 0 0 | 0 0 | 0 0 | 0 0 | 35905 9 | 0 0 | 0 0 |
| 56 | 9 4 | 363192 0 | 0 0 | 0 0 | 0 0 | 0 0 | 36319 2 | 0 0 | 0 0 |
| 57 | 0 1 | 3258 0 | 0 0 | 0 0 | 0 0 | 0 0 | 325 8 | 0 0 | 0 0 |
| 58 | 9 5 | 372462 4 | 0 0 | 0 0 | 0 0 | 0 0 | 37246 2 | 0 0 | 0 0 |
| 59 | 9 5 | 377130 8 | 0 0 | 0 0 | 0 0 | 0 0 | 37713 1 | 0 0 | 0 0 |
| 60 | 9 5 | 381692 7 | 0 0 | 0 0 | 0 0 | 0 0 | 38169 3 | 0 0 | 0 0 |
| 61 | 9 6 | 386151 1 | 0 0 | 0 0 | 0 0 | 0 0 | 38615 1 | 0 0 | 0 0 |
| 62 | 9 6 | 390501 5 | 0 0 | 0 0 | 0 0 | 0 0 | 39050 2 | 0 0 | 0 0 |
| 63 | 9 6 | 394740 1 | 0 0 | 0 0 | 0 0 | 0 0 | 39474 0 | 0 0 | 0 0 |
| 64 | 9 6 | 398872 3 | 0 0 | 0 0 | 0 0 | 0 0 | 39887 2 | 0 0 | 0 0 |
| 65 | 9 7 | 402886 5 | 0 0 | 0 0 | 0 0 | 0 0 | 40288 7 | 0 0 | 0 0 |
| 66 | 9 7 | 406791 2 | 0 0 | 0 0 | 0 0 | 0 0 | 40679 1 | 0 0 | 0 0 |
| 67 | 9 7 | 410577 2 | 0 0 | 0 0 | 0 0 | 0 0 | 41057 7 | 0 0 | 0 0 |
| 68 | 9 7 | 414245 5 | 0 0 | 0 0 | 0 0 | 0 0 | 41424 5 | 0 0 | 0 0 |
| 69 | 9 7 | 417794 6 | 0 0 | 0 0 | 0 0 | 0 0 | 41779 5 | 0 0 | 0 0 |
| 70 | 9 8 | 421223 2 | 0 0 | 0 0 | 0 0 | 0 0 | 42122 3 | 0 0 | 0 0 |
| 71 | 9 8 | 424529 8 | 0 0 | 0 0 | 0 0 | 0 0 | 42453 0 | 0 0 | 0 0 |
| 72 | 9 8 | 427713 1 | 0 0 | 0 0 | 0 0 | 0 0 | 42771 3 | 0 0 | 0 0 |
| 73 | 9 8 | 430771 9 | 0 0 | 0 0 | 0 0 | 0 0 | 43077 2 | 0 0 | 0 0 |
| 74 | 9 8 | 433704 9 | 0 0 | 0 0 | 0 0 | 0 0 | 43370 5 | 0 0 | 0 0 |
| 75 | 9 8 | 436511 0 | 0 0 | 0 0 | 0 0 | 0 0 | 43651 1 | 0 0 | 0 0 |
| 76 | 9 9 | 439189 1 | 0 0 | 0 0 | 0 0 | 0 0 | 43918 9 | 0 0 | 0 0 |
| 77 | 9 9 | 441732 5 | 0 0 | 0 0 | 0 0 | 0 0 | 44173 3 | 0 0 | 0 0 |
| 78 | 9 9 | 444151 3 | 0 0 | 0 0 | 0 0 | 0 0 | 44415 1 | 0 0 | 0 0 |
| 79 | 9 9 | 446433 5 | 0 0 | 0 0 | 0 0 | 0 0 | 44643 4 | 0 0 | 0 0 |
| 80 | 9 9 | 448583 7 | 0 0 | 0 0 | 0 0 | 0 0 | 44858 4 | 0 0 | 0 0 |
| 81 | 9 9 | 450601 0 | 0 0 | 0 0 | 0 0 | 0 0 | 45060 1 | 0 0 | 0 0 |
| 82 | 9 9 | 452484 6 | 0 0 | 0 0 | 0 0 | 0 0 | 45248 5 | 0 0 | 0 0 |
| 83 | 9 9 | 454233 8 | 0 0 | 0 0 | 0 0 | 0 0 | 45423 4 | 0 0 | 0 0 |
| 84 | 10 0 | 455848 0 | 0 0 | 0 0 | 0 0 | 0 0 | 45584 8 | 0 0 | 0 0 |
| 85 | 10 0 | 457320 8 | 0 0 | 0 0 | 0 0 | 0 0 | 45732 1 | 0 0 | 0 0 |

34/170

| | | | | | | | | | |
|-----|------|----------|-----|-----|-----|-----|---------|-----|-----|
| 86 | 10 0 | 458662 9 | 0 0 | 0 0 | 0 0 | 0 0 | 45866 3 | 0 0 | 0 0 |
| 87 | 10 0 | 459862 6 | 0 0 | 0 0 | 0 0 | 0 0 | 45986 3 | 0 0 | 0 0 |
| 88 | 10 0 | 460924 8 | 0 0 | 0 0 | 0 0 | 0 0 | 46092 5 | 0 0 | 0 0 |
| 89 | 10 0 | 461849 4 | 0 0 | 0 0 | 0 0 | 0 0 | 46184 9 | 0 0 | 0 0 |
| 90 | 10 0 | 462630 1 | 0 0 | 0 0 | 0 0 | 0 0 | 46263 0 | 0 0 | 0 0 |
| 91 | 10 0 | 463278 2 | 0 0 | 0 0 | 0 0 | 0 0 | 46327 8 | 0 0 | 0 0 |
| 92 | 10 0 | 463781 9 | 0 0 | 0 0 | 0 0 | 0 0 | 46378 2 | 0 0 | 0 0 |
| 93 | 10 0 | 454146 8 | 0 0 | 0 0 | 0 0 | 0 0 | 46414 7 | 0 0 | 0 0 |
| 94 | 10 0 | 464372 6 | 0 0 | 0 0 | 0 0 | 0 0 | 46437 3 | 0 0 | 0 0 |
| 95 | 10 0 | 464459 2 | 0 0 | 0 0 | 0 0 | 0 0 | 46445 9 | 0 0 | 0 0 |
| 96 | 10 0 | 464406 8 | 0 0 | 0 0 | 0 0 | 0 0 | 46440 7 | 0 0 | 0 0 |
| 97 | 10 0 | 464209 5 | 0 0 | 0 0 | 0 0 | 0 0 | 46421 0 | 0 0 | 0 0 |
| 98 | 10 0 | 463873 2 | 0 0 | 0 0 | 0 0 | 0 0 | 46387 3 | 0 0 | 0 0 |
| 99 | 10 0 | 463398 0 | 0 0 | 0 0 | 0 0 | 0 0 | 46339 8 | 0 0 | 0 0 |
| 100 | 10 0 | 462784 0 | 0 0 | 0 0 | 0 0 | 0 0 | 46278 4 | 0 0 | 0 0 |
| 101 | 10 0 | 462031 7 | 0 0 | 0 0 | 0 0 | 0 0 | 46203 2 | 0 0 | 0 0 |
| 102 | 10 0 | 461135 4 | 0 0 | 0 0 | 0 0 | 0 0 | 46113 5 | 0 0 | 0 0 |
| 103 | 10 0 | 460107 0 | 0 0 | 0 0 | 0 0 | 0 0 | 46010 7 | 0 0 | 0 0 |
| 104 | 10 0 | 458935 4 | 0 0 | 0 0 | 0 0 | 0 0 | 45893 5 | 0 0 | 0 0 |
| 105 | 10 0 | 457627 0 | 0 0 | 0 0 | 0 0 | 0 0 | 45762 7 | 0 0 | 0 0 |
| 105 | 10 0 | 456176 5 | 0 0 | 0 0 | 0 0 | 0 0 | 45617 6 | 0 0 | 0 0 |
| 107 | 9 9 | 454595 7 | 0 0 | 0 0 | 0 0 | 0 0 | 45459 6 | 0 0 | 0 0 |
| 108 | 9 9 | 452879 6 | 0 0 | 0 0 | 0 0 | 0 0 | 45288 0 | 0 0 | 0 0 |
| 109 | 9 9 | 451023 5 | 0 0 | 0 0 | 0 0 | 0 0 | 45102 4 | 0 0 | 0 0 |
| 110 | 9 9 | 449033 5 | 0 0 | 0 0 | 0 0 | 0 0 | 44903 4 | 0 0 | 0 0 |
| 111 | 9 9 | 446910 4 | 0 0 | 0 0 | 0 0 | 0 0 | 44691 0 | 0 0 | 0 0 |
| 112 | 9 9 | 444655 2 | 0 0 | 0 0 | 0 0 | 0 0 | 44465 5 | 0 0 | 0 0 |
| 113 | 9 9 | 442268 7 | 0 0 | 0 0 | 0 0 | 0 0 | 44226 9 | 0 0 | 0 0 |
| 114 | 9 9 | 439751 8 | 0 0 | 0 0 | 0 0 | 0 0 | 43975 2 | 0 0 | 0 0 |
| 115 | 9 9 | 437105 5 | 0 0 | 0 0 | 0 0 | 0 0 | 43710 6 | 0 0 | 0 0 |
| 115 | 9 8 | 434325 6 | 0 0 | 0 0 | 0 0 | 0 0 | 43432 6 | 0 0 | 0 0 |
| 117 | 9 8 | 431423 8 | 0 0 | 0 0 | 0 0 | 0 0 | 43142 4 | 0 0 | 0 0 |
| 118 | 9 8 | 428390 7 | 0 0 | 0 0 | 0 0 | 0 0 | 42839 1 | 0 0 | 0 0 |
| 119 | 9 8 | 425232 7 | 0 0 | 0 0 | 0 0 | 0 0 | 42523 3 | 0 0 | 0 0 |
| 120 | 9 8 | 421956 5 | 0 0 | 0 0 | 0 0 | 0 0 | 42195 6 | 0 0 | 0 0 |
| 121 | 9 7 | 418552 7 | 0 0 | 0 0 | 0 0 | 0 0 | 41855 3 | 0 0 | 0 0 |
| 122 | 9 7 | 415028 1 | 0 0 | 0 0 | 0 0 | 0 0 | 41502 8 | 0 0 | 0 0 |
| 123 | 9 7 | 411384 0 | 0 0 | 0 0 | 0 0 | 0 0 | 41138 4 | 0 0 | 0 0 |
| 124 | 9 7 | 407627 1 | 0 0 | 0 0 | 0 0 | 0 0 | 40762 7 | 0 0 | 0 0 |
| 125 | 9 7 | 403748 5 | 0 0 | 0 0 | 0 0 | 0 0 | 40374 9 | 0 0 | 0 0 |
| 126 | 9 5 | 399755 0 | 0 0 | 0 0 | 0 0 | 0 0 | 39975 5 | 0 0 | 0 0 |
| 127 | 9 6 | 395648 2 | 0 0 | 0 0 | 0 0 | 0 0 | 39564 8 | 0 0 | 0 0 |
| 128 | 9 6 | 391434 7 | 0 0 | 0 0 | 0 0 | 0 0 | 39143 5 | 0 0 | 0 0 |
| 129 | 9 6 | 387106 3 | 0 0 | 0 0 | 0 0 | 0 0 | 38710 6 | 0 0 | 0 0 |
| 130 | 9 5 | 382659 9 | 0 0 | 0 0 | 0 0 | 0 0 | 38267 0 | 0 0 | 0 0 |
| 131 | 9 5 | 378131 8 | 0 0 | 0 0 | 0 0 | 0 0 | 37813 2 | 0 0 | 0 0 |
| 132 | 9 5 | 373489 3 | 0 0 | 0 0 | 0 0 | 0 0 | 37348 9 | 0 0 | 0 0 |
| 133 | 9 5 | 368739 2 | 0 0 | 0 0 | 0 0 | 0 0 | 36873 9 | 0 0 | 0 0 |
| 134 | 9 4 | 363893 4 | 0 0 | 0 0 | 0 0 | 0 0 | 36389 3 | 0 0 | 0 0 |
| 135 | 9 4 | 358953 4 | 0 0 | 0 0 | 0 0 | 0 0 | 35895 3 | 0 0 | 0 0 |
| 136 | 9 4 | 353912 1 | 0 0 | 0 0 | 0 0 | 0 0 | 35391 2 | 0 0 | 0 0 |
| 137 | 9 3 | 348776 2 | 0 0 | 0 0 | 0 0 | 0 0 | 34877 5 | 0 0 | 0 0 |
| 138 | 9 3 | 343552 3 | 0 0 | 0 0 | 0 0 | 0 0 | 34355 2 | 0 0 | 0 0 |
| 139 | 9 3 | 338238 2 | 0 0 | 0 0 | 0 0 | 0 0 | 33823 8 | 0 0 | 0 0 |
| 140 | 9 2 | 332835 9 | 0 0 | 0 0 | 0 0 | 0 0 | 33283 6 | 0 0 | 0 0 |
| 141 | 9 2 | 327352 1 | 0 0 | 0 0 | 0 0 | 0 0 | 32735 2 | 0 0 | 0 0 |
| 142 | 9 2 | 321784 6 | 0 0 | 0 0 | 0 0 | 0 0 | 32178 5 | 0 0 | 0 0 |
| 143 | 9 1 | 316136 0 | 0 0 | 0 0 | 0 0 | 0 0 | 31613 6 | 0 0 | 0 0 |
| 144 | 9 1 | 310408 4 | 0 0 | 0 0 | 0 0 | 0 0 | 31040 8 | 0 0 | 0 0 |
| 145 | 9 1 | 304608 4 | 0 0 | 0 0 | 0 0 | 0 0 | 30460 8 | 0 0 | 0 0 |
| 146 | 9 0 | 298734 4 | 0 0 | 0 0 | 0 0 | 0 0 | 29873 4 | 0 0 | 0 0 |
| 147 | 9 0 | 292792 9 | 0 0 | 0 0 | 0 0 | 0 0 | 29279 3 | 0 0 | 0 0 |
| 148 | 9 0 | 286782 2 | 0 0 | 0 0 | 0 0 | 0 0 | 28678 2 | 0 0 | 0 0 |
| 149 | 8 9 | 280709 0 | 0 0 | 0 0 | 0 0 | 0 0 | 28070 9 | 0 0 | 0 0 |
| 150 | 8 9 | 274571 7 | 0 0 | 0 0 | 0 0 | 0 0 | 27457 2 | 0 0 | 0 0 |
| 151 | 8 8 | 268373 1 | 0 0 | 0 0 | 0 0 | 0 0 | 26837 3 | 0 0 | 0 0 |
| 152 | 8 8 | 252119 8 | 0 0 | 0 0 | 0 0 | 0 0 | 25212 0 | 0 0 | 0 0 |
| 153 | 8 8 | 255814 0 | 0 0 | 0 0 | 0 0 | 0 0 | 25581 4 | 0 0 | 0 0 |

| | | | | | | | | | |
|-----|-----|----------|-----|-----|-----|-----|---------|-----|-----|
| 154 | 8 7 | 249455 0 | 0 0 | 0 0 | 0 0 | 0 0 | 24945 5 | 0 0 | 0 0 |
| 155 | 8 7 | 243049 1 | 0 0 | 0 0 | 0 0 | 0 0 | 24304 9 | 0 0 | 0 0 |
| 156 | 8 6 | 236595 4 | 0 0 | 0 0 | 0 0 | 0 0 | 23659 5 | 0 0 | 0 0 |
| 157 | 8 6 | 230100 3 | 0 0 | 0 0 | 0 0 | 0 0 | 23010 0 | 0 0 | 0 0 |
| 158 | 8 5 | 223566 5 | 0 0 | 0 0 | 0 0 | 0 0 | 22356 7 | 0 0 | 0 0 |
| 159 | 8 5 | 216996 6 | 0 0 | 0 0 | 0 0 | 0 0 | 21699 7 | 0 0 | 0 0 |
| 160 | 8 5 | 210390 5 | 0 0 | 0 0 | 0 0 | 0 0 | 21039 1 | 0 0 | 0 0 |
| 161 | 8 4 | 203754 2 | 0 0 | 0 0 | 0 0 | 0 0 | 20375 4 | 0 0 | 0 0 |
| 162 | 8 4 | 197090 6 | 0 0 | 0 0 | 0 0 | 0 0 | 19709 1 | 0 0 | 0 0 |
| 163 | 8 3 | 190399 5 | 0 0 | 0 0 | 0 0 | 0 0 | 19040 0 | 0 0 | 0 0 |
| 164 | 8 3 | 183689 9 | 0 0 | 0 0 | 0 0 | 0 0 | 18359 0 | 0 0 | 0 0 |
| 165 | 8 2 | 176958 9 | 0 0 | 0 0 | 0 0 | 0 0 | 17695 9 | 0 0 | 0 0 |
| 166 | 8 2 | 170215 0 | 0 0 | 0 0 | 0 0 | 0 0 | 17021 5 | 0 0 | 0 0 |
| 167 | 8 1 | 163455 9 | 0 0 | 0 0 | 0 0 | 0 0 | 16345 6 | 0 0 | 0 0 |
| 168 | 8 1 | 156687 2 | 0 0 | 0 0 | 0 0 | 0 0 | 15668 7 | 0 0 | 0 0 |
| 169 | 8 0 | 149912 0 | 0 0 | 0 0 | 0 0 | 0 0 | 14991 2 | 0 0 | 0 0 |
| 170 | 8 0 | 143135 8 | 0 0 | 0 0 | 0 0 | 0 0 | 14313 6 | 0 0 | 0 0 |
| 171 | 7 9 | 136355 8 | 0 0 | 0 0 | 0 0 | 0 0 | 13635 7 | 0 0 | 0 0 |
| 172 | 7 9 | 129582 7 | 0 0 | 0 0 | 0 0 | 0 0 | 12958 3 | 0 0 | 0 0 |
| 173 | 7 8 | 122812 3 | 0 0 | 0 0 | 0 0 | 0 0 | 12281 2 | 0 0 | 0 0 |
| 174 | 7 7 | 115054 9 | 0 0 | 0 0 | 0 0 | 0 0 | 11605 5 | 0 0 | 0 0 |
| 175 | 7 7 | 109305 6 | 0 0 | 0 0 | 0 0 | 0 0 | 10930 6 | 0 0 | 0 0 |
| 176 | 7 6 | 102573 6 | 0 0 | 0 0 | 0 0 | 0 0 | 10257 4 | 0 0 | 0 0 |
| 177 | 7 6 | 95861 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9586 2 | 0 0 | 0 0 |
| 178 | 7 5 | 89169 9 | 0 0 | 0 0 | 0 0 | 0 0 | 8917 0 | 0 0 | 0 0 |
| 179 | 7 5 | 82507 2 | 0 0 | 0 0 | 0 0 | 0 0 | 8250 7 | 0 0 | 0 0 |
| 180 | 7 4 | 75868 4 | 0 0 | 0 0 | 0 0 | 0 0 | 7586 8 | 0 0 | 0 0 |
| 181 | 7 3 | 69264 7 | 0 0 | 0 0 | 0 0 | 0 0 | 6926 5 | 0 0 | 0 0 |
| 182 | 7 3 | 62694 3 | 0 0 | 0 0 | 0 0 | 0 0 | 6269 4 | 0 0 | 0 0 |
| 183 | 7 2 | 56162 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5616 3 | 0 0 | 0 0 |
| 184 | 7 2 | 49672 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4967 3 | 0 0 | 0 0 |
| 185 | 7 1 | 43228 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4322 8 | 0 0 | 0 0 |
| 186 | 7 0 | 36830 1 | 0 0 | 0 0 | 0 0 | 0 0 | 3683 0 | 0 0 | 0 0 |
| 187 | 7 0 | 30483 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3048 3 | 0 0 | 0 0 |
| 188 | 3 0 | 11256 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1125 7 | 0 0 | 0 0 |
| 189 | 3 9 | 12934 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1293 5 | 0 0 | 0 0 |
| 190 | 5 6 | 15048 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1504 8 | 0 0 | 0 0 |
| 191 | 1 3 | 2908 6 | 0 0 | 0 0 | 0 0 | 0 0 | 290 9 | 0 0 | 0 0 |
| 192 | 6 8 | 11783 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1178 3 | 0 0 | 0 0 |
| 193 | 1 2 | 1424 3 | 0 0 | 0 0 | 0 0 | 0 0 | 142 4 | 0 0 | 0 0 |
| 194 | 5 6 | 4376 3 | 0 0 | 0 0 | 0 0 | 0 0 | 437 6 | 0 0 | 0 0 |
| 195 | 3 5 | 767 5 | 0 0 | 0 0 | 0 0 | 0 0 | 76 7 | 0 0 | 0 0 |

Failure Surface Specified By 184 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 545 00 | 617 50 |
| 2 | 552 09 | 610 44 |
| 3 | 559 23 | 603 45 |
| 4 | 566 45 | 596 52 |
| 5 | 573 72 | 589 66 |
| 6 | 581 05 | 582 86 |
| 7 | 588 45 | 576 13 |
| 8 | 595 90 | 569 46 |
| 9 | 503 42 | 562 87 |
| 10 | 610 99 | 556 34 |
| 11 | 618 63 | 549 88 |
| 12 | 625 32 | 543 48 |
| 13 | 634 07 | 537 16 |
| 14 | 641 87 | 530 91 |
| 15 | 649 73 | 524 73 |
| 16 | 657 65 | 518 62 |
| 17 | 665 62 | 512 58 |
| 18 | 673 64 | 506 61 |
| 19 | 581 72 | 500 72 |
| 20 | 689 85 | 494 89 |
| 21 | 698 03 | 489 15 |
| 22 | 706 27 | 483 47 |
| 23 | 714 55 | 477 87 |

| | | |
|----|---------|--------|
| 24 | 722 88 | 472 34 |
| 25 | 731 27 | 466 89 |
| 26 | 739 70 | 461 52 |
| 27 | 748 18 | 456 22 |
| 28 | 756 71 | 451 00 |
| 29 | 765 29 | 445 85 |
| 30 | 773 91 | 440 78 |
| 31 | 782 57 | 435 79 |
| 32 | 791 28 | 430 88 |
| 33 | 800 04 | 426 05 |
| 34 | 808 83 | 421 29 |
| 35 | 817 67 | 416 62 |
| 36 | 826 56 | 412 02 |
| 37 | 835 48 | 407 51 |
| 38 | 844 44 | 403 07 |
| 39 | 853 44 | 398 72 |
| 40 | 862 48 | 394 45 |
| 41 | 871 56 | 390 25 |
| 42 | 880 68 | 386 15 |
| 43 | 889 83 | 382 12 |
| 44 | 899 02 | 378 17 |
| 45 | 908 25 | 374 31 |
| 46 | 917 50 | 370 53 |
| 47 | 925 80 | 365 84 |
| 48 | 936 12 | 363 22 |
| 49 | 945 48 | 359 70 |
| 50 | 954 87 | 356 25 |
| 51 | 964 29 | 352 89 |
| 52 | 973 74 | 349 62 |
| 53 | 983 21 | 346 43 |
| 54 | 992 72 | 343 33 |
| 55 | 1002 25 | 340 31 |
| 56 | 1011 81 | 337 38 |
| 57 | 1021 40 | 334 53 |
| 58 | 1031 01 | 331 77 |
| 59 | 1040 65 | 329 10 |
| 60 | 1050 31 | 326 52 |
| 61 | 1059 99 | 324 02 |
| 62 | 1069 70 | 321 61 |
| 63 | 1079 42 | 319 28 |
| 64 | 1089 17 | 317 04 |
| 65 | 1098 94 | 314 90 |
| 66 | 1108 72 | 312 83 |
| 67 | 1118 52 | 310 86 |
| 68 | 1128 34 | 308 98 |
| 69 | 1138 18 | 307 18 |
| 70 | 1148 04 | 305 47 |
| 71 | 1157 90 | 303 85 |
| 72 | 1167 79 | 302 32 |
| 73 | 1177 68 | 300 88 |
| 74 | 1187 59 | 299 53 |
| 75 | 1197 51 | 298 27 |
| 76 | 1207 44 | 297 10 |
| 77 | 1217 38 | 296 01 |
| 78 | 1227 33 | 295 02 |
| 79 | 1237 29 | 294 11 |
| 80 | 1247 26 | 293 30 |
| 81 | 1257 23 | 292 57 |
| 82 | 1267 21 | 291 94 |
| 83 | 1277 20 | 291 39 |
| 84 | 1287 19 | 290 93 |
| 85 | 1297 18 | 290 57 |
| 86 | 1307 17 | 290 29 |
| 87 | 1317 17 | 290 10 |
| 88 | 1327 17 | 290 01 |
| 89 | 1337 17 | 290 00 |
| 90 | 1347 17 | 290 08 |
| 91 | 1357 17 | 290 26 |

| | | |
|-----|---------|--------|
| 92 | 1367 17 | 290 52 |
| 93 | 1377 16 | 290 87 |
| 94 | 1387 15 | 291 32 |
| 95 | 1397 14 | 291 85 |
| 96 | 1407 12 | 292 47 |
| 97 | 1417 09 | 293 19 |
| 98 | 1427 06 | 293 99 |
| 99 | 1437 02 | 294 88 |
| 100 | 1446 97 | 295 86 |
| 101 | 1456 91 | 296 93 |
| 102 | 1466 85 | 298 09 |
| 103 | 1476 77 | 299 34 |
| 104 | 1485 68 | 300 68 |
| 105 | 1496 58 | 302 11 |
| 106 | 1506 46 | 303 63 |
| 107 | 1516 33 | 305 23 |
| 108 | 1526 19 | 306 93 |
| 109 | 1536 03 | 308 71 |
| 110 | 1545 85 | 310 58 |
| 111 | 1555 65 | 312 54 |
| 112 | 1565 44 | 314 59 |
| 113 | 1575 21 | 316 73 |
| 114 | 1584 96 | 318 95 |
| 115 | 1594 69 | 321 26 |
| 116 | 1604 40 | 323 66 |
| 117 | 1614 08 | 326 15 |
| 118 | 1623 75 | 328 72 |
| 119 | 1633 39 | 331 38 |
| 120 | 1643 00 | 334 13 |
| 121 | 1652 59 | 336 96 |
| 122 | 1662 16 | 339 88 |
| 123 | 1671 70 | 342 88 |
| 124 | 1681 21 | 345 98 |
| 125 | 1690 69 | 349 15 |
| 126 | 1700 14 | 352 41 |
| 127 | 1709 56 | 355 76 |
| 128 | 1718 96 | 359 19 |
| 129 | 1728 32 | 362 71 |
| 130 | 1737 65 | 366 31 |
| 131 | 1746 95 | 369 99 |
| 132 | 1756 21 | 373 76 |
| 133 | 1765 44 | 377 61 |
| 134 | 1774 63 | 381 54 |
| 135 | 1783 79 | 385 55 |
| 136 | 1792 91 | 389 65 |
| 137 | 1802 00 | 393 83 |
| 138 | 1811 04 | 398 09 |
| 139 | 1820 05 | 402 43 |
| 140 | 1829 02 | 406 86 |
| 141 | 1837 95 | 411 36 |
| 142 | 1846 84 | 415 95 |
| 143 | 1855 68 | 420 61 |
| 144 | 1864 49 | 425 35 |
| 145 | 1873 25 | 430 17 |
| 146 | 1881 96 | 435 07 |
| 147 | 1890 64 | 440 05 |
| 148 | 1899 25 | 445 11 |
| 149 | 1907 85 | 450 24 |
| 150 | 1916 38 | 455 46 |
| 151 | 1924 87 | 460 74 |
| 152 | 1933 31 | 466 11 |
| 153 | 1941 70 | 471 55 |
| 154 | 1950 04 | 477 06 |
| 155 | 1958 33 | 482 65 |
| 156 | 1966 57 | 488 31 |
| 157 | 1974 76 | 494 05 |
| 158 | 1982 90 | 499 86 |
| 159 | 1990 99 | 505 75 |

| | | |
|-----|---------|--------|
| 160 | 1999 02 | 511 71 |
| 161 | 2007 00 | 517 73 |
| 162 | 2014 92 | 523 83 |
| 163 | 2022 79 | 530 01 |
| 164 | 2030 60 | 536 25 |
| 165 | 2038 36 | 542 56 |
| 166 | 2046 06 | 548 94 |
| 167 | 2053 70 | 555 39 |
| 168 | 2061 28 | 561 91 |
| 169 | 2068 81 | 568 50 |
| 170 | 2076 27 | 575 15 |
| 171 | 2083 68 | 581 87 |
| 172 | 2091 02 | 588 66 |
| 173 | 2098 30 | 595 52 |
| 174 | 2105 52 | 602 43 |
| 175 | 2112 68 | 609 42 |
| 176 | 2119 77 | 616 47 |
| 177 | 2126 80 | 623 58 |
| 178 | 2133 77 | 630 75 |
| 179 | 2140 67 | 637 99 |
| 180 | 2147 51 | 645 28 |
| 181 | 2154 28 | 652 64 |
| 182 | 2160 98 | 660 06 |
| 183 | 2167 62 | 567 54 |
| 184 | 2169 76 | 670 00 |

Circle Center At X = 1332 9 , Y = 1401 5 and Radius, 1111 5
 *** 1 021 ***

Failure Surface Specified By 187 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 545 00 | 617 50 |
| 2 | 552 32 | 610 69 |
| 3 | 559 70 | 603 94 |
| 4 | 567 14 | 597 25 |
| 5 | 574 63 | 590 63 |
| 6 | 582 18 | 584 07 |
| 7 | 589 78 | 577 58 |
| 8 | 597 44 | 571 15 |
| 9 | 605 16 | 564 78 |
| 10 | 612 92 | 558 48 |
| 11 | 620 74 | 552 25 |
| 12 | 628 61 | 546 08 |
| 13 | 636 54 | 539 98 |
| 14 | 644 51 | 533 95 |
| 15 | 652 54 | 527 98 |
| 15 | 660 61 | 522 08 |
| 17 | 658 74 | 516 25 |
| 18 | 676 91 | 510 49 |
| 19 | 685 14 | 504 80 |
| 20 | 693 41 | 499 18 |
| 21 | 701 72 | 493 63 |
| 22 | 710 09 | 488 15 |
| 23 | 718 50 | 482 74 |
| 24 | 726 96 | 477 41 |
| 25 | 735 46 | 472 14 |
| 26 | 744 00 | 466 95 |
| 27 | 752 59 | 461 82 |
| 28 | 761 22 | 456 78 |
| 29 | 769 90 | 451 80 |
| 30 | 778 62 | 446 90 |
| 31 | 787 37 | 442 07 |
| 32 | 796 17 | 437 32 |
| 33 | 805 01 | 432 64 |
| 34 | 813 89 | 428 04 |
| 35 | 822 80 | 423 51 |
| 36 | 831 76 | 419 05 |
| 37 | 840 75 | 414 68 |
| 38 | 849 78 | 410 38 |

36/130

| | | |
|-----|---------|--------|
| 39 | 858 84 | 406 15 |
| 40 | 867 94 | 402 00 |
| 41 | 877 07 | 397 93 |
| 42 | 886 24 | 393 94 |
| 43 | 895 44 | 390 03 |
| 44 | 904 68 | 386 19 |
| 45 | 913 94 | 382 43 |
| 46 | 923 24 | 378 75 |
| 47 | 932 57 | 375 15 |
| 48 | 941 93 | 371 63 |
| 49 | 951 32 | 368 18 |
| 50 | 960 74 | 364 82 |
| 51 | 970 18 | 361 54 |
| 52 | 979 55 | 358 33 |
| 53 | 989 15 | 355 21 |
| 54 | 998 68 | 352 17 |
| 55 | 1008 23 | 349 20 |
| 56 | 1017 81 | 346 32 |
| 57 | 1027 41 | 343 52 |
| 58 | 1037 03 | 340 80 |
| 59 | 1046 68 | 338 17 |
| 60 | 1056 34 | 335 61 |
| 61 | 1065 03 | 333 14 |
| 62 | 1075 74 | 330 74 |
| 63 | 1085 47 | 328 44 |
| 64 | 1095 22 | 326 21 |
| 65 | 1104 99 | 324 06 |
| 66 | 1114 77 | 322 00 |
| 67 | 1124 58 | 320 02 |
| 68 | 1134 40 | 318 13 |
| 69 | 1144 23 | 316 32 |
| 70 | 1154 08 | 314 59 |
| 71 | 1163 94 | 312 94 |
| 72 | 1173 82 | 311 38 |
| 73 | 1183 71 | 309 90 |
| 74 | 1193 61 | 308 50 |
| 75 | 1203 53 | 307 19 |
| 76 | 1213 45 | 305 97 |
| 77 | 1223 38 | 304 82 |
| 78 | 1233 33 | 303 76 |
| 79 | 1243 28 | 302 79 |
| 80 | 1253 24 | 301 90 |
| 81 | 1253 21 | 301 09 |
| 82 | 1273 18 | 300 37 |
| 83 | 1283 16 | 299 73 |
| 84 | 1293 15 | 299 18 |
| 85 | 1303 14 | 298 71 |
| 86 | 1313 13 | 298 33 |
| 87 | 1323 12 | 298 03 |
| 88 | 1333 12 | 297 81 |
| 89 | 1343 12 | 297 68 |
| 90 | 1353 12 | 297 63 |
| 91 | 1363 12 | 297 67 |
| 92 | 1373 12 | 297 80 |
| 93 | 1383 12 | 298 01 |
| 94 | 1393 11 | 298 30 |
| 95 | 1403 11 | 298 68 |
| 96 | 1413 10 | 299 14 |
| 97 | 1423 08 | 299 68 |
| 98 | 1433 06 | 300 31 |
| 99 | 1443 04 | 301 03 |
| 100 | 1453 00 | 301 83 |
| 101 | 1462 96 | 302 71 |
| 102 | 1472 92 | 303 68 |
| 103 | 1482 86 | 304 73 |
| 104 | 1492 80 | 305 87 |
| 105 | 1502 72 | 307 09 |
| 106 | 1512 64 | 308 39 |

| | | |
|-----|---------|--------|
| 107 | 1522 54 | 309 78 |
| 108 | 1532 43 | 311 25 |
| 109 | 1542 31 | 312 81 |
| 110 | 1652 17 | 314 45 |
| 111 | 1552 02 | 316 17 |
| 112 | 1571 86 | 317 98 |
| 113 | 1581 68 | 319 87 |
| 114 | 1591 48 | 321 84 |
| 115 | 1601 27 | 323 89 |
| 116 | 1611 04 | 326 03 |
| 117 | 1620 79 | 328 25 |
| 118 | 1630 52 | 330 55 |
| 119 | 1640 23 | 332 94 |
| 120 | 1649 92 | 335 41 |
| 121 | 1559 59 | 337 96 |
| 122 | 1669 24 | 340 59 |
| 123 | 1678 87 | 343 30 |
| 124 | 1688 47 | 346 09 |
| 125 | 1698 05 | 348 97 |
| 126 | 1707 60 | 351 92 |
| 127 | 1717 13 | 354 96 |
| 128 | 1726 63 | 358 08 |
| 129 | 1736 10 | 361 27 |
| 130 | 1745 55 | 364 55 |
| 131 | 1754 97 | 367 91 |
| 132 | 1764 36 | 371 34 |
| 133 | 1773 72 | 374 86 |
| 134 | 1783 05 | 378 46 |
| 135 | 1792 35 | 382 13 |
| 136 | 1801 62 | 385 88 |
| 137 | 1810 86 | 389 71 |
| 138 | 1820 07 | 393 62 |
| 139 | 1829 24 | 397 61 |
| 140 | 1838 37 | 401 67 |
| 141 | 1847 48 | 405 81 |
| 142 | 1856 54 | 410 03 |
| 143 | 1865 57 | 414 33 |
| 144 | 1874 57 | 418 70 |
| 145 | 1883 52 | 423 14 |
| 146 | 1892 44 | 427 67 |
| 147 | 1901 32 | 432 26 |
| 148 | 1910 17 | 436 94 |
| 149 | 1918 97 | 441 68 |
| 150 | 1927 73 | 446 51 |
| 151 | 1936 45 | 451 40 |
| 152 | 1945 12 | 456 37 |
| 153 | 1953 76 | 461 41 |
| 154 | 1962 35 | 466 53 |
| 155 | 1970 90 | 471 72 |
| 156 | 1979 41 | 476 98 |
| 157 | 1987 87 | 482 31 |
| 158 | 1996 28 | 487 71 |
| 159 | 2004 65 | 493 19 |
| 160 | 2012 97 | 498 73 |
| 161 | 2021 25 | 504 35 |
| 162 | 2029 47 | 510 03 |
| 163 | 2037 65 | 515 79 |
| 164 | 2045 78 | 521 61 |
| 165 | 2053 86 | 527 50 |
| 166 | 2061 89 | 533 45 |
| 167 | 2069 87 | 539 49 |
| 168 | 2077 80 | 545 58 |
| 169 | 2085 67 | 551 75 |
| 170 | 2093 50 | 557 97 |
| 171 | 2101 27 | 564 27 |
| 172 | 2108 98 | 570 63 |
| 173 | 2116 65 | 577 05 |
| 174 | 2124 26 | 583 54 |

| | | |
|-----|---------|--------|
| 175 | 2131 81 | 590 10 |
| 176 | 2139 31 | 596 71 |
| 177 | 2145 75 | 503 39 |
| 178 | 2154 13 | 610 14 |
| 179 | 2161 46 | 616 94 |
| 180 | 2168 73 | 623 81 |
| 181 | 2175 94 | 630 74 |
| 182 | 2183 09 | 637 73 |
| 183 | 2190 18 | 544 78 |
| 184 | 2197 22 | 651 89 |
| 185 | 2204 19 | 659 06 |
| 185 | 2211 10 | 665 28 |
| 187 | 2214 59 | 670 00 |

Circle Center At X = 1353 5 Y = 1479 4 and Radius, 1181 8
 *** 1 026 ***

Failure Surface Specified By 184 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 578 75 | 617 91 |
| 2 | 585 86 | 510 87 |
| 3 | 593 03 | 603 91 |
| 4 | 600 26 | 597 00 |
| 5 | 607 56 | 590 16 |
| 6 | 614 91 | 583 39 |
| 7 | 622 33 | 576 68 |
| 8 | 629 81 | 570 04 |
| 9 | 637 34 | 563 46 |
| 10 | 644 93 | 556 95 |
| 11 | 652 59 | 550 52 |
| 12 | 660 29 | 544 15 |
| 13 | 668 06 | 537 85 |
| 14 | 675 88 | 531 62 |
| 15 | 683 76 | 525 46 |
| 16 | 691 69 | 519 37 |
| 17 | 699 68 | 513 35 |
| 18 | 707 72 | 507 40 |
| 19 | 715 81 | 501 53 |
| 20 | 723 96 | 495 73 |
| 21 | 732 15 | 490 00 |
| 22 | 740 40 | 484 34 |
| 23 | 748 70 | 478 76 |
| 24 | 757 05 | 473 26 |
| 25 | 765 44 | 467 83 |
| 26 | 773 89 | 462 47 |
| 27 | 782 38 | 457 19 |
| 28 | 790 92 | 451 99 |
| 29 | 799 51 | 446 86 |
| 30 | 808 14 | 441 81 |
| 31 | 816 82 | 436 84 |
| 32 | 825 54 | 431 95 |
| 33 | 834 30 | 427 13 |
| 34 | 843 11 | 422 39 |
| 35 | 851 96 | 417 74 |
| 36 | 860 85 | 413 16 |
| 37 | 869 78 | 408 66 |
| 38 | 878 75 | 404 24 |
| 39 | 887 76 | 399 90 |
| 40 | 896 81 | 395 64 |
| 41 | 905 89 | 391 47 |
| 42 | 915 02 | 387 37 |
| 43 | 924 18 | 383 36 |
| 44 | 933 37 | 379 43 |
| 45 | 942 60 | 375 58 |
| 46 | 951 87 | 371 82 |
| 47 | 961 16 | 368 14 |
| 48 | 970 49 | 364 54 |
| 49 | 979 85 | 361 02 |
| 50 | 989 25 | 357 59 |

| | | |
|-----|---------|--------|
| 51 | 998 67 | 354 25 |
| 52 | 1008 12 | 350 98 |
| 53 | 1017 61 | 347 81 |
| 54 | 1027 12 | 344 72 |
| 55 | 1036 55 | 341 71 |
| 55 | 1045 22 | 338 79 |
| 57 | 1055 81 | 335 95 |
| 58 | 1065 42 | 333 20 |
| 59 | 1075 06 | 330 54 |
| 60 | 1084 72 | 327 96 |
| 61 | 1094 41 | 325 47 |
| 62 | 1104 11 | 323 07 |
| 63 | 1113 84 | 320 75 |
| 64 | 1123 59 | 318 52 |
| 55 | 1133 36 | 316 38 |
| 66 | 1143 15 | 314 33 |
| 67 | 1152 95 | 312 36 |
| 68 | 1162 77 | 310 48 |
| 69 | 1172 61 | 308 69 |
| 70 | 1182 47 | 306 99 |
| 71 | 1192 33 | 305 38 |
| 72 | 1202 22 | 303 85 |
| 73 | 1212 11 | 302 42 |
| 74 | 1222 02 | 301 07 |
| 75 | 1231 94 | 299 81 |
| 76 | 1241 87 | 298 64 |
| 77 | 1251 82 | 297 56 |
| 78 | 1261 77 | 296 57 |
| 79 | 1271 72 | 295 66 |
| 80 | 1281 69 | 294 85 |
| 81 | 1291 67 | 294 12 |
| 82 | 1301 65 | 293 49 |
| 83 | 1311 63 | 292 94 |
| 84 | 1321 62 | 292 49 |
| 85 | 1331 61 | 292 12 |
| 86 | 1341 61 | 291 84 |
| 87 | 1351 61 | 291 65 |
| 88 | 1361 61 | 291 56 |
| 89 | 1371 61 | 291 55 |
| 90 | 1381 61 | 291 63 |
| 91 | 1391 51 | 291 80 |
| 92 | 1401 50 | 292 06 |
| 93 | 1411 60 | 292 41 |
| 94 | 1421 59 | 292 85 |
| 95 | 1431 57 | 293 38 |
| 96 | 1441 55 | 293 99 |
| 97 | 1451 53 | 294 70 |
| 98 | 1461 50 | 295 50 |
| 99 | 1471 46 | 296 38 |
| 100 | 1481 41 | 297 36 |
| 101 | 1491 35 | 298 42 |
| 102 | 1501 29 | 299 58 |
| 103 | 1511 21 | 300 82 |
| 104 | 1521 12 | 302 15 |
| 105 | 1531 02 | 303 57 |
| 106 | 1540 90 | 305 08 |
| 107 | 1550 78 | 306 67 |
| 108 | 1560 63 | 308 36 |
| 109 | 1570 47 | 310 13 |
| 110 | 1580 30 | 311 99 |
| 111 | 1590 11 | 313 94 |
| 112 | 1599 90 | 315 98 |
| 113 | 1509 67 | 318 11 |
| 114 | 1519 42 | 320 32 |
| 115 | 1629 15 | 322 62 |
| 116 | 1638 86 | 325 00 |
| 117 | 1648 55 | 327 48 |
| 118 | 1558 22 | 330 04 |

40/130

| | | |
|-----|---------|--------|
| 119 | 1667 86 | 332 68 |
| 120 | 1677 48 | 335 42 |
| 121 | 1687 08 | 338 24 |
| 122 | 1696 65 | 341 14 |
| 123 | 1706 19 | 344 13 |
| 124 | 1715 70 | 347 21 |
| 125 | 1725 19 | 350 37 |
| 126 | 1734 65 | 353 61 |
| 127 | 1744 08 | 356 94 |
| 128 | 1753 48 | 360 36 |
| 129 | 1752 85 | 363 86 |
| 130 | 1772 18 | 367 44 |
| 131 | 1781 49 | 371 10 |
| 132 | 1790 76 | 374 85 |
| 133 | 1799 99 | 378 68 |
| 134 | 1809 20 | 382 60 |
| 135 | 1818 36 | 386 60 |
| 136 | 1827 49 | 390 67 |
| 137 | 1836 59 | 394 83 |
| 138 | 1845 64 | 399 08 |
| 139 | 1854 66 | 403 40 |
| 140 | 1863 64 | 407 80 |
| 141 | 1872 58 | 412 29 |
| 142 | 1881 48 | 416 85 |
| 143 | 1890 33 | 421 49 |
| 144 | 1899 15 | 426 21 |
| 145 | 1907 92 | 431 01 |
| 146 | 1916 65 | 435 89 |
| 147 | 1925 33 | 440 85 |
| 148 | 1933 97 | 445 88 |
| 149 | 1942 57 | 451 00 |
| 150 | 1951 12 | 456 18 |
| 151 | 1959 62 | 461 45 |
| 152 | 1968 07 | 466 79 |
| 153 | 1976 48 | 472 21 |
| 154 | 1984 84 | 477 70 |
| 155 | 1993 14 | 483 26 |
| 156 | 2001 40 | 488 90 |
| 157 | 2009 61 | 494 62 |
| 158 | 2017 76 | 500 41 |
| 159 | 2025 87 | 506 27 |
| 160 | 2033 92 | 512 20 |
| 161 | 2041 91 | 518 20 |
| 162 | 2049 86 | 524 28 |
| 163 | 2057 75 | 530 42 |
| 164 | 2055 58 | 536 64 |
| 165 | 2073 35 | 542 93 |
| 166 | 2081 07 | 549 28 |
| 167 | 2088 74 | 555 71 |
| 168 | 2096 34 | 562 20 |
| 169 | 2103 89 | 568 76 |
| 170 | 2111 38 | 575 39 |
| 171 | 2118 80 | 582 09 |
| 172 | 2126 17 | 588 85 |
| 173 | 2133 46 | 595 68 |
| 174 | 2140 72 | 602 57 |
| 175 | 2147 91 | 609 53 |
| 176 | 2155 03 | 616 55 |
| 177 | 2162 08 | 623 63 |
| 178 | 2169 08 | 630 78 |
| 179 | 2176 01 | 637 99 |
| 180 | 2182 87 | 645 26 |
| 181 | 2189 67 | 652 60 |
| 132 | 2196 40 | 659 99 |
| 183 | 2203 07 | 667 44 |
| 184 | 2205 31 | 670 00 |

Circle Center At X = 1367 6 , Y = 1408 0 and Radius, 1116 4
*** 1 040 ***

Failure Surface Specified By 170 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 500 00 | 616 95 |
| 2 | 507 07 | 609 88 |
| 3 | 514 21 | 602 87 |
| 4 | 521 42 | 595 94 |
| 5 | 528 70 | 589 08 |
| 6 | 536 04 | 582 30 |
| 7 | 543 45 | 575 58 |
| 8 | 550 93 | 568 94 |
| 9 | 558 47 | 562 37 |
| 10 | 566 07 | 555 88 |
| 11 | 573 74 | 549 46 |
| 12 | 581 47 | 543 12 |
| 13 | 589 26 | 535 85 |
| 14 | 597 12 | 530 66 |
| 15 | 605 03 | 524 55 |
| 16 | 613 01 | 518 51 |
| 17 | 621 04 | 512 56 |
| 18 | 629 13 | 506 68 |
| 19 | 637 28 | 500 89 |
| 20 | 645 49 | 495 17 |
| 21 | 653 75 | 489 54 |
| 22 | 662 06 | 483 98 |
| 23 | 670 43 | 478 51 |
| 24 | 678 86 | 473 12 |
| 25 | 687 33 | 467 82 |
| 26 | 695 86 | 452 59 |
| 27 | 704 44 | 457 46 |
| 28 | 713 07 | 452 40 |
| 29 | 721 75 | 447 43 |
| 30 | 730 48 | 442 55 |
| 31 | 739 25 | 437 75 |
| 32 | 748 07 | 433 04 |
| 33 | 756 94 | 428 42 |
| 34 | 765 85 | 423 88 |
| 35 | 774 81 | 419 44 |
| 35 | 783 81 | 415 07 |
| 37 | 792 85 | 410 80 |
| 38 | 801 93 | 406 62 |
| 39 | 811 05 | 402 53 |
| 40 | 820 22 | 398 53 |
| 41 | 829 42 | 394 61 |
| 42 | 838 66 | 390 79 |
| 43 | 847 94 | 387 06 |
| 44 | 857 25 | 383 42 |
| 45 | 866 60 | 379 87 |
| 46 | 875 99 | 376 42 |
| 47 | 885 40 | 373 05 |
| 48 | 894 85 | 369 78 |
| 49 | 904 34 | 366 60 |
| 50 | 913 85 | 363 52 |
| 51 | 923 39 | 360 53 |
| 52 | 932 96 | 357 63 |
| 53 | 942 56 | 354 83 |
| 54 | 952 19 | 352 12 |
| 55 | 961 84 | 349 51 |
| 56 | 971 52 | 346 99 |
| 57 | 981 22 | 344 57 |
| 58 | 990 95 | 342 24 |
| 59 | 1000 69 | 340 01 |
| 60 | 1010 45 | 337 87 |
| 61 | 1020 25 | 335 83 |
| 62 | 1030 06 | 333 89 |
| 63 | 1039 89 | 332 04 |
| 64 | 1049 74 | 330 29 |
| 65 | 1059 60 | 328 64 |

| | | |
|-----|---------|--------|
| 66 | 1059 48 | 327 08 |
| 67 | 1079 37 | 325 62 |
| 68 | 1089 28 | 324 26 |
| 59 | 1099 20 | 323 00 |
| 70 | 1109 13 | 321 83 |
| 71 | 1119 07 | 320 76 |
| 72 | 1129 02 | 319 79 |
| 73 | 1138 99 | 318 92 |
| 74 | 1148 96 | 318 14 |
| 75 | 1158 93 | 317 46 |
| 76 | 1168 92 | 316 89 |
| 77 | 1178 90 | 316 40 |
| 78 | 1188 90 | 315 02 |
| 79 | 1198 89 | 315 74 |
| 80 | 1208 89 | 315 55 |
| 81 | 1218 89 | 315 46 |
| 82 | 1228 89 | 315 47 |
| 83 | 1238 89 | 315 58 |
| 84 | 1248 89 | 315 79 |
| 85 | 1258 88 | 316 09 |
| 86 | 1268 87 | 316 50 |
| 87 | 1278 86 | 317 00 |
| 88 | 1288 84 | 317 60 |
| 89 | 1298 82 | 318 30 |
| 90 | 1308 79 | 319 09 |
| 91 | 1318 75 | 319 98 |
| 92 | 1328 70 | 320 98 |
| 93 | 1338 64 | 322 07 |
| 94 | 1348 57 | 323 25 |
| 95 | 1358 49 | 324 54 |
| 96 | 1368 39 | 325 92 |
| 97 | 1378 28 | 327 40 |
| 98 | 1388 15 | 328 97 |
| 99 | 1398 01 | 330 65 |
| 100 | 1407 86 | 332 42 |
| 101 | 1417 68 | 334 29 |
| 102 | 1427 49 | 336 25 |
| 103 | 1437 27 | 338 31 |
| 104 | 1447 04 | 340 46 |
| 105 | 1456 78 | 342 72 |
| 106 | 1466 50 | 345 06 |
| 107 | 1476 20 | 347 51 |
| 108 | 1485 87 | 350 04 |
| 109 | 1495 52 | 352 68 |
| 110 | 1505 14 | 355 40 |
| 111 | 1514 73 | 358 23 |
| 112 | 1524 30 | 361 14 |
| 113 | 1533 83 | 364 15 |
| 114 | 1543 34 | 367 26 |
| 115 | 1552 81 | 370 45 |
| 116 | 1562 26 | 373 74 |
| 117 | 1571 67 | 377 13 |
| 118 | 1581 04 | 380 60 |
| 119 | 1590 39 | 384 17 |
| 120 | 1599 69 | 387 83 |
| 121 | 1608 96 | 391 58 |
| 122 | 1618 20 | 395 42 |
| 123 | 1627 39 | 399 35 |
| 124 | 1636 55 | 403 37 |
| 125 | 1645 66 | 407 48 |
| 126 | 1654 74 | 411 68 |
| 127 | 1663 77 | 415 97 |
| 128 | 1672 76 | 420 35 |
| 129 | 1681 71 | 424 82 |
| 130 | 1690 61 | 429 37 |
| 131 | 1699 47 | 434 01 |
| 132 | 1708 28 | 438 74 |
| 133 | 1717 04 | 443 56 |

| | | |
|-----|---------|--------|
| 134 | 1725 76 | 448 46 |
| 135 | 1734 43 | 453 44 |
| 136 | 1743 05 | 458 51 |
| 137 | 1751 62 | 463 67 |
| 138 | 1760 13 | 468 91 |
| 139 | 1768 60 | 474 23 |
| 140 | 1777 01 | 479 64 |
| 141 | 1785 37 | 485 13 |
| 142 | 1793 68 | 490 70 |
| 143 | 1801 93 | 496 35 |
| 144 | 1810 12 | 502 08 |
| 145 | 1818 26 | 507 90 |
| 146 | 1826 34 | 513 79 |
| 147 | 1834 36 | 519 76 |
| 148 | 1842 32 | 525 81 |
| 149 | 1850 22 | 531 94 |
| 150 | 1858 06 | 538 14 |
| 151 | 1865 84 | 544 43 |
| 152 | 1873 56 | 550 79 |
| 153 | 1881 22 | 557 22 |
| 154 | 1888 81 | 563 73 |
| 155 | 1896 33 | 570 31 |
| 156 | 1903 80 | 576 97 |
| 157 | 1911 19 | 583 70 |
| 158 | 1918 52 | 590 50 |
| 159 | 1925 79 | 597 38 |
| 160 | 1932 98 | 604 32 |
| 161 | 1940 11 | 611 34 |
| 162 | 1947 16 | 618 42 |
| 163 | 1954 15 | 625 58 |
| 164 | 1951 07 | 632 80 |
| 165 | 1967 91 | 640 09 |
| 166 | 1974 68 | 647 45 |
| 167 | 1981 38 | 654 87 |
| 168 | 1988 01 | 662 35 |
| 169 | 1994 56 | 669 91 |
| 170 | 1994 64 | 670 00 |

Circle Center At X = 1222 9 , Y = 1332 8 and Radius, 1017 3
 *** 1 046 ***

Failure Surface Specified By 178 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 533 75 | 517 36 |
| 2 | 541 11 | 610 59 |
| 3 | 548 54 | 603 89 |
| 4 | 556 02 | 597 26 |
| 5 | 563 56 | 590 69 |
| 6 | 571 16 | 584 19 |
| 7 | 578 81 | 577 75 |
| 8 | 586 52 | 571 38 |
| 9 | 594 29 | 565 09 |
| 10 | 602 11 | 558 86 |
| 11 | 609 99 | 552 70 |
| 12 | 617 92 | 546 61 |
| 13 | 625 91 | 540 59 |
| 14 | 633 94 | 534 64 |
| 15 | 642 03 | 528 76 |
| 16 | 650 18 | 522 95 |
| 17 | 558 37 | 517 22 |
| 18 | 666 61 | 511 56 |
| 19 | 674 90 | 505 97 |
| 20 | 683 24 | 500 45 |
| 21 | 691 63 | 495 01 |
| 22 | 700 07 | 489 64 |
| 23 | 708 56 | 484 36 |
| 24 | 717 09 | 479 13 |
| 25 | 725 67 | 473 99 |
| 26 | 734 29 | 468 93 |

| | | |
|----|---------|--------|
| 27 | 742 95 | 463 94 |
| 28 | 751 66 | 459 02 |
| 29 | 760 42 | 454 19 |
| 30 | 769 21 | 449 43 |
| 31 | 778 05 | 444 75 |
| 32 | 786 93 | 440 15 |
| 33 | 795 85 | 435 63 |
| 34 | 804 80 | 431 18 |
| 35 | 813 80 | 426 82 |
| 36 | 822 84 | 422 53 |
| 37 | 831 91 | 418 32 |
| 38 | 841 02 | 414 20 |
| 39 | 850 16 | 410 15 |
| 40 | 859 34 | 406 19 |
| 41 | 858 56 | 402 31 |
| 42 | 877 81 | 398 51 |
| 43 | 887 09 | 394 79 |
| 44 | 896 41 | 391 15 |
| 45 | 905 75 | 387 60 |
| 46 | 915 13 | 384 12 |
| 47 | 924 54 | 380 74 |
| 48 | 933 98 | 377 43 |
| 49 | 943 45 | 374 21 |
| 50 | 952 94 | 371 07 |
| 51 | 962 46 | 358 01 |
| 52 | 972 01 | 365 04 |
| 53 | 981 58 | 362 16 |
| 54 | 991 18 | 359 36 |
| 55 | 1000 81 | 356 64 |
| 56 | 1010 46 | 354 01 |
| 57 | 1020 13 | 351 46 |
| 58 | 1029 82 | 349 00 |
| 59 | 1039 63 | 346 63 |
| 60 | 1049 27 | 344 34 |
| 61 | 1059 02 | 342 14 |
| 62 | 1058 80 | 340 02 |
| 63 | 1078 59 | 337 99 |
| 64 | 1088 40 | 336 05 |
| 65 | 1098 22 | 334 19 |
| 66 | 1108 06 | 332 42 |
| 67 | 1117 92 | 330 74 |
| 68 | 1127 79 | 329 14 |
| 69 | 1137 68 | 327 53 |
| 70 | 1147 58 | 326 21 |
| 71 | 1157 49 | 324 87 |
| 72 | 1167 41 | 323 63 |
| 73 | 1177 34 | 322 47 |
| 74 | 1187 29 | 321 40 |
| 75 | 1197 24 | 320 42 |
| 76 | 1207 20 | 319 52 |
| 77 | 1217 16 | 318 71 |
| 78 | 1227 14 | 317 99 |
| 79 | 1237 12 | 317 36 |
| 80 | 1247 10 | 316 82 |
| 81 | 1257 09 | 316 37 |
| 82 | 1267 09 | 316 00 |
| 83 | 1277 08 | 315 72 |
| 84 | 1287 08 | 315 53 |
| 85 | 1297 08 | 315 43 |
| 86 | 1307 08 | 315 42 |
| 87 | 1317 08 | 315 49 |
| 88 | 1327 08 | 315 65 |
| 89 | 1337 08 | 315 91 |
| 90 | 1347 07 | 316 25 |
| 91 | 1357 06 | 316 67 |
| 92 | 1367 05 | 317 19 |
| 93 | 1377 03 | 317 80 |
| 94 | 1387 00 | 318 49 |

| | | |
|-----|---------|--------|
| 95 | 1396 97 | 319 27 |
| 96 | 1406 94 | 320 14 |
| 97 | 1416 89 | 321 09 |
| 98 | 1426 84 | 322 14 |
| 99 | 1436 77 | 323 27 |
| 100 | 1446 70 | 324 49 |
| 101 | 1456 61 | 325 80 |
| 102 | 1466 51 | 327 19 |
| 103 | 1476 40 | 328 68 |
| 104 | 1486 28 | 330 25 |
| 105 | 1496 14 | 331 90 |
| 106 | 1505 99 | 333 65 |
| 107 | 1515 82 | 335 48 |
| 108 | 1525 63 | 337 40 |
| 109 | 1535 43 | 339 40 |
| 110 | 1545 21 | 341 49 |
| 111 | 1554 97 | 343 67 |
| 112 | 1564 71 | 345 93 |
| 113 | 1574 43 | 348 28 |
| 114 | 1584 13 | 350 72 |
| 115 | 1593 81 | 353 24 |
| 115 | 1603 46 | 355 84 |
| 117 | 1613 09 | 358 53 |
| 118 | 1622 70 | 361 31 |
| 119 | 1632 28 | 364 17 |
| 120 | 1641 84 | 367 11 |
| 121 | 1651 37 | 370 14 |
| 122 | 1660 87 | 373 26 |
| 123 | 1670 35 | 376 45 |
| 124 | 1679 79 | 379 73 |
| 125 | 1689 21 | 383 10 |
| 126 | 1698 60 | 386 55 |
| 127 | 1707 95 | 390 08 |
| 128 | 1717 28 | 393 69 |
| 129 | 1726 57 | 397 38 |
| 130 | 1735 83 | 401 16 |
| 131 | 1745 05 | 405 02 |
| 132 | 1754 25 | 408 96 |
| 133 | 1763 40 | 412 98 |
| 134 | 1772 52 | 417 08 |
| 135 | 1781 61 | 421 26 |
| 136 | 1790 65 | 425 52 |
| 137 | 1799 66 | 429 86 |
| 138 | 1808 63 | 434 28 |
| 139 | 1817 56 | 438 78 |
| 140 | 1826 45 | 443 36 |
| 141 | 1836 30 | 448 02 |
| 142 | 1844 11 | 452 75 |
| 143 | 1852 88 | 457 56 |
| 144 | 1861 60 | 452 45 |
| 145 | 1870 28 | 467 42 |
| 146 | 1878 91 | 472 46 |
| 147 | 1887 51 | 477 58 |
| 148 | 1896 05 | 482 78 |
| 149 | 1904 55 | 488 05 |
| 150 | 1913 00 | 493 39 |
| 151 | 1921 41 | 498 81 |
| 152 | 1929 75 | 504 30 |
| 153 | 1938 07 | 509 87 |
| 154 | 1946 33 | 515 51 |
| 155 | 1954 53 | 521 22 |
| 156 | 1962 69 | 527 01 |
| 157 | 1970 80 | 532 86 |
| 158 | 1978 85 | 538 79 |
| 159 | 1986 85 | 544 79 |
| 160 | 1994 80 | 550 86 |
| 161 | 2002 69 | 557 00 |
| 162 | 2010 53 | 563 21 |

46/130

| | | |
|-----|---------|--------|
| 153 | 2018 32 | 569 49 |
| 164 | 2026 04 | 575 83 |
| 165 | 2033 72 | 582 25 |
| 166 | 2041 33 | 588 73 |
| 167 | 2048 89 | 595 28 |
| 168 | 2056 39 | 601 89 |
| 169 | 2063 83 | 608 57 |
| 170 | 2071 21 | 615 32 |
| 171 | 2078 53 | 622 13 |
| 172 | 2085 79 | 529 01 |
| 173 | 2092 99 | 535 95 |
| 174 | 2100 13 | 542 95 |
| 175 | 2107 21 | 650 02 |
| 176 | 2114 22 | 557 14 |
| 177 | 2121 17 | 664 33 |
| 178 | 2126 55 | 670 00 |

Circle Center At X = 1303 6 , Y = 1447 7 and Radius, 1132 3
 *** 1 052 ***

Failure Surface Specified By 185 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 601 25 | 618 18 |
| 2 | 608 54 | 611 34 |
| 3 | 615 89 | 604 56 |
| 4 | 623 30 | 597 85 |
| 5 | 630 77 | 591 20 |
| 6 | 638 30 | 584 61 |
| 7 | 645 88 | 578 09 |
| 8 | 653 51 | 571 63 |
| 9 | 661 20 | 565 24 |
| 10 | 668 95 | 558 92 |
| 11 | 676 75 | 552 66 |
| 12 | 684 61 | 546 47 |
| 13 | 592 51 | 540 35 |
| 14 | 700 47 | 534 29 |
| 15 | 708 48 | 528 31 |
| 16 | 716 55 | 522 39 |
| 17 | 724 65 | 516 55 |
| 18 | 732 82 | 510 77 |
| 19 | 741 04 | 505 07 |
| 20 | 749 30 | 499 43 |
| 21 | 757 61 | 493 87 |
| 22 | 765 97 | 488 38 |
| 23 | 774 37 | 482 96 |
| 24 | 782 82 | 477 61 |
| 25 | 791 32 | 472 34 |
| 26 | 799 86 | 467 14 |
| 27 | 808 44 | 462 01 |
| 28 | 817 07 | 456 96 |
| 29 | 825 75 | 451 98 |
| 30 | 834 46 | 447 08 |
| 31 | 843 22 | 442 25 |
| 32 | 852 02 | 437 50 |
| 33 | 860 86 | 432 82 |
| 34 | 869 74 | 428 22 |
| 35 | 878 66 | 423 70 |
| 36 | 887 61 | 419 25 |
| 37 | 896 61 | 414 88 |
| 38 | 905 64 | 410 59 |
| 39 | 914 71 | 406 38 |
| 40 | 923 81 | 402 24 |
| 41 | 932 95 | 398 19 |
| 42 | 942 13 | 394 21 |
| 43 | 951 34 | 390 31 |
| 44 | 960 58 | 386 49 |
| 45 | 969 85 | 382 75 |
| 46 | 979 16 | 379 09 |
| 47 | 988 50 | 375 51 |

| | | |
|-----|---------|--------|
| 48 | 997 86 | 372 01 |
| 49 | 1007 26 | 368 59 |
| 50 | 1016 69 | 365 26 |
| 51 | 1026 14 | 362 00 |
| 52 | 1035 63 | 358 83 |
| 53 | 1045 14 | 355 73 |
| 54 | 1054 67 | 352 72 |
| 55 | 1064 23 | 349 79 |
| 56 | 1073 82 | 346 95 |
| 57 | 1083 43 | 344 18 |
| 58 | 1093 07 | 341 50 |
| 59 | 1102 72 | 338 91 |
| 60 | 1112 40 | 336 39 |
| 51 | 1122 10 | 333 96 |
| 62 | 1131 82 | 331 61 |
| 63 | 1141 56 | 329 35 |
| 64 | 1151 32 | 327 17 |
| 65 | 1161 10 | 325 03 |
| 66 | 1170 90 | 323 06 |
| 67 | 1180 71 | 321 14 |
| 68 | 1190 54 | 319 30 |
| 69 | 1200 38 | 317 54 |
| 70 | 1210 24 | 315 87 |
| 71 | 1220 11 | 314 28 |
| 72 | 1230 00 | 312 78 |
| 73 | 1239 90 | 311 36 |
| 74 | 1249 81 | 310 03 |
| 75 | 1259 73 | 308 78 |
| 76 | 1269 66 | 307 62 |
| 77 | 1279 61 | 306 54 |
| 78 | 1289 56 | 305 55 |
| 79 | 1299 52 | 304 65 |
| 80 | 1309 48 | 303 83 |
| 81 | 1319 46 | 303 10 |
| 82 | 1329 43 | 302 45 |
| 83 | 1339 42 | 301 89 |
| 84 | 1349 41 | 301 41 |
| 85 | 1359 40 | 301 02 |
| 86 | 1369 40 | 300 72 |
| 87 | 1379 39 | 300 50 |
| 88 | 1389 39 | 300 37 |
| 89 | 1399 39 | 300 33 |
| 90 | 1409 39 | 300 37 |
| 91 | 1419 39 | 300 50 |
| 92 | 1429 39 | 300 71 |
| 93 | 1439 38 | 301 01 |
| 94 | 1449 38 | 301 40 |
| 95 | 1459 37 | 301 87 |
| 96 | 1469 35 | 302 43 |
| 97 | 1479 33 | 303 07 |
| 98 | 1489 30 | 303 80 |
| 99 | 1499 27 | 304 61 |
| 100 | 1509 23 | 305 52 |
| 101 | 1519 18 | 306 50 |
| 102 | 1529 12 | 307 58 |
| 103 | 1539 06 | 308 73 |
| 104 | 1548 98 | 309 98 |
| 105 | 1558 89 | 311 31 |
| 106 | 1568 79 | 312 72 |
| 107 | 1578 68 | 314 22 |
| 108 | 1588 55 | 315 80 |
| 109 | 1598 41 | 317 47 |
| 110 | 1608 25 | 319 23 |
| 111 | 1618 08 | 321 07 |
| 112 | 1627 90 | 322 99 |
| 113 | 1637 69 | 325 00 |
| 114 | 1647 47 | 327 09 |
| 115 | 1657 23 | 329 27 |

| | | | | |
|-----|------|----|-----|----|
| 116 | 1666 | 97 | 331 | 53 |
| 117 | 1576 | 69 | 333 | 87 |
| 118 | 1686 | 40 | 336 | 30 |
| 119 | 1696 | 07 | 338 | 81 |
| 120 | 1705 | 73 | 341 | 40 |
| 121 | 1715 | 37 | 344 | 08 |
| 122 | 1724 | 98 | 346 | 84 |
| 123 | 1734 | 57 | 349 | 68 |
| 124 | 1744 | 13 | 352 | 61 |
| 125 | 1753 | 67 | 355 | 62 |
| 125 | 1763 | 18 | 358 | 71 |
| 127 | 1772 | 66 | 361 | 88 |
| 128 | 1782 | 12 | 365 | 13 |
| 129 | 1791 | 54 | 368 | 46 |
| 130 | 1800 | 94 | 371 | 88 |
| 131 | 1810 | 31 | 375 | 38 |
| 132 | 1819 | 65 | 378 | 95 |
| 133 | 1828 | 96 | 382 | 61 |
| 134 | 1838 | 23 | 386 | 35 |
| 135 | 1847 | 48 | 390 | 15 |
| 136 | 1856 | 69 | 394 | 06 |
| 137 | 1865 | 86 | 398 | 03 |
| 138 | 1875 | 00 | 402 | 09 |
| 139 | 1884 | 11 | 406 | 22 |
| 140 | 1893 | 18 | 410 | 43 |
| 141 | 1902 | 21 | 414 | 72 |
| 142 | 1911 | 21 | 419 | 08 |
| 143 | 1920 | 17 | 423 | 53 |
| 144 | 1929 | 09 | 428 | 05 |
| 145 | 1937 | 97 | 432 | 65 |
| 146 | 1946 | 81 | 437 | 32 |
| 147 | 1955 | 61 | 442 | 07 |
| 148 | 1964 | 37 | 446 | 89 |
| 149 | 1973 | 09 | 451 | 79 |
| 150 | 1981 | 76 | 456 | 77 |
| 151 | 1990 | 39 | 461 | 82 |
| 152 | 1998 | 98 | 466 | 94 |
| 153 | 2007 | 52 | 472 | 14 |
| 154 | 2016 | 02 | 477 | 41 |
| 155 | 2024 | 47 | 482 | 75 |
| 156 | 2032 | 88 | 488 | 17 |
| 157 | 2041 | 24 | 493 | 66 |
| 158 | 2049 | 55 | 499 | 22 |
| 159 | 2057 | 82 | 504 | 85 |
| 160 | 2066 | 03 | 510 | 55 |
| 161 | 2074 | 20 | 516 | 33 |
| 162 | 2082 | 31 | 522 | 17 |
| 163 | 2090 | 38 | 528 | 08 |
| 164 | 2098 | 39 | 534 | 06 |
| 165 | 2106 | 35 | 540 | 12 |
| 166 | 2114 | 26 | 546 | 23 |
| 167 | 2122 | 12 | 552 | 42 |
| 168 | 2129 | 92 | 558 | 68 |
| 169 | 2137 | 67 | 565 | 00 |
| 170 | 2145 | 36 | 571 | 38 |
| 171 | 2153 | 00 | 577 | 84 |
| 172 | 2160 | 58 | 584 | 36 |
| 173 | 2168 | 11 | 590 | 94 |
| 174 | 2175 | 58 | 597 | 59 |
| 175 | 2182 | 99 | 604 | 30 |
| 176 | 2190 | 34 | 611 | 08 |
| 177 | 2197 | 64 | 617 | 92 |
| 178 | 2204 | 87 | 624 | 82 |
| 179 | 2212 | 05 | 631 | 79 |
| 180 | 2219 | 17 | 638 | 81 |
| 181 | 2226 | 22 | 645 | 90 |
| 182 | 2233 | 22 | 653 | 05 |
| 183 | 2240 | 15 | 650 | 25 |

184 2247 02 667 52
 185 2249 32 670 00
 Circle Center At X = 1399 6 , Y = 1461 8 and Radius, 1161 5
 *** 1 060 ***

Failure Surface Specified By180 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 533 75 | 617 36 |
| 2 | 541 38 | 610 90 |
| 3 | 549 07 | 504 50 |
| 4 | 556 80 | 598 16 |
| 5 | 564 59 | 591 89 |
| 6 | 572 43 | 585 68 |
| 7 | 580 32 | 579 54 |
| 8 | 588 26 | 573 46 |
| 9 | 596 25 | 567 45 |
| 10 | 604 30 | 561 51 |
| 11 | 612 39 | 555 63 |
| 12 | 620 52 | 549 82 |
| 13 | 628 71 | 544 07 |
| 14 | 636 94 | 538 40 |
| 15 | 645 22 | 532 79 |
| 16 | 653 55 | 527 25 |
| 17 | 661 92 | 521 78 |
| 18 | 670 34 | 516 38 |
| 19 | 678 80 | 511 05 |
| 20 | 587 30 | 505 79 |
| 21 | 695 85 | 500 60 |
| 22 | 704 44 | 495 48 |
| 23 | 713 07 | 490 43 |
| 24 | 721 75 | 485 45 |
| 25 | 730 46 | 480 55 |
| 26 | 739 22 | 475 72 |
| 27 | 748 01 | 470 96 |
| 28 | 756 84 | 466 27 |
| 29 | 765 72 | 461 55 |
| 30 | 774 62 | 457 11 |
| 31 | 783 57 | 452 65 |
| 32 | 792 56 | 448 25 |
| 33 | 801 57 | 443 94 |
| 34 | 810 63 | 439 59 |
| 35 | 819 72 | 435 52 |
| 36 | 828 84 | 431 43 |
| 37 | 838 00 | 427 41 |
| 38 | 847 19 | 423 47 |
| 39 | 856 41 | 419 60 |
| 40 | 865 67 | 415 81 |
| 41 | 874 95 | 412 10 |
| 42 | 884 27 | 408 47 |
| 43 | 893 61 | 404 91 |
| 44 | 902 99 | 401 42 |
| 45 | 912 39 | 398 02 |
| 46 | 921 82 | 394 69 |
| 47 | 931 28 | 391 45 |
| 48 | 940 76 | 388 28 |
| 49 | 950 27 | 385 18 |
| 50 | 959 81 | 382 17 |
| 51 | 969 37 | 379 24 |
| 52 | 978 95 | 376 38 |
| 53 | 988 56 | 373 61 |
| 54 | 998 19 | 370 91 |
| 55 | 1007 84 | 368 30 |
| 56 | 1017 51 | 365 76 |
| 57 | 1027 21 | 363 30 |
| 58 | 1036 92 | 360 93 |
| 59 | 1046 65 | 358 63 |
| 60 | 1056 40 | 356 41 |
| 51 | 1056 17 | 354 28 |

| | | | | |
|-----|------|----|-----|----|
| 62 | 1075 | 96 | 352 | 23 |
| 63 | 1085 | 75 | 350 | 25 |
| 64 | 1095 | 58 | 348 | 35 |
| 65 | 1105 | 42 | 345 | 55 |
| 66 | 1115 | 27 | 344 | 82 |
| 67 | 1125 | 13 | 343 | 17 |
| 68 | 1135 | 01 | 341 | 61 |
| 69 | 1144 | 90 | 340 | 12 |
| 70 | 1154 | 80 | 338 | 72 |
| 71 | 1164 | 71 | 337 | 40 |
| 72 | 1174 | 63 | 336 | 16 |
| 73 | 1184 | 67 | 335 | 00 |
| 74 | 1194 | 51 | 333 | 93 |
| 75 | 1204 | 46 | 332 | 94 |
| 76 | 1214 | 42 | 332 | 03 |
| 77 | 1224 | 38 | 331 | 20 |
| 78 | 1234 | 36 | 330 | 45 |
| 79 | 1244 | 33 | 329 | 79 |
| 80 | 1254 | 32 | 329 | 21 |
| 81 | 1264 | 30 | 328 | 71 |
| 82 | 1274 | 30 | 328 | 29 |
| 83 | 1284 | 29 | 327 | 96 |
| 84 | 1294 | 29 | 327 | 71 |
| 85 | 1304 | 29 | 327 | 54 |
| 86 | 1314 | 28 | 327 | 46 |
| 87 | 1324 | 28 | 327 | 46 |
| 88 | 1334 | 28 | 327 | 54 |
| 89 | 1344 | 28 | 327 | 70 |
| 90 | 1354 | 28 | 327 | 94 |
| 91 | 1364 | 27 | 328 | 27 |
| 92 | 1374 | 27 | 328 | 68 |
| 93 | 1384 | 25 | 329 | 18 |
| 94 | 1394 | 24 | 329 | 75 |
| 95 | 1404 | 22 | 330 | 41 |
| 96 | 1414 | 19 | 331 | 15 |
| 97 | 1424 | 15 | 331 | 97 |
| 98 | 1434 | 11 | 332 | 88 |
| 99 | 1444 | 06 | 333 | 87 |
| 100 | 1454 | 01 | 334 | 94 |
| 101 | 1463 | 94 | 336 | 09 |
| 102 | 1473 | 86 | 337 | 32 |
| 103 | 1483 | 78 | 338 | 64 |
| 104 | 1493 | 68 | 340 | 04 |
| 105 | 1503 | 57 | 341 | 52 |
| 106 | 1513 | 45 | 343 | 08 |
| 107 | 1523 | 31 | 344 | 72 |
| 108 | 1533 | 16 | 346 | 44 |
| 109 | 1543 | 00 | 348 | 25 |
| 110 | 1552 | 82 | 350 | 14 |
| 111 | 1562 | 62 | 352 | 10 |
| 112 | 1572 | 41 | 354 | 15 |
| 113 | 1582 | 18 | 356 | 28 |
| 114 | 1591 | 93 | 358 | 49 |
| 115 | 1601 | 67 | 360 | 78 |
| 116 | 1611 | 38 | 353 | 16 |
| 117 | 1621 | 08 | 365 | 61 |
| 118 | 1630 | 75 | 368 | 14 |
| 119 | 1640 | 40 | 370 | 75 |
| 120 | 1650 | 03 | 373 | 44 |
| 121 | 1659 | 64 | 376 | 21 |
| 122 | 1669 | 23 | 379 | 06 |
| 123 | 1678 | 79 | 381 | 99 |
| 124 | 1688 | 33 | 385 | 00 |
| 125 | 1697 | 84 | 388 | 09 |
| 126 | 1707 | 32 | 391 | 25 |
| 127 | 1716 | 78 | 394 | 50 |
| 128 | 1726 | 21 | 397 | 82 |
| 129 | 1735 | 62 | 401 | 22 |

5/130

| | | |
|-----|---------|--------|
| 130 | 1745 00 | 404 69 |
| 131 | 1754 34 | 408 25 |
| 132 | 1763 65 | 411 88 |
| 133 | 1772 95 | 415 59 |
| 134 | 1782 20 | 419 37 |
| 135 | 1791 43 | 423 23 |
| 136 | 1800 62 | 427 17 |
| 137 | 1809 78 | 431 19 |
| 138 | 1818 90 | 435 27 |
| 139 | 1828 00 | 439 44 |
| 140 | 1837 05 | 443 68 |
| 141 | 1846 07 | 447 99 |
| 142 | 1855 06 | 452 38 |
| 143 | 1864 01 | 455 84 |
| 144 | 1872 92 | 461 38 |
| 145 | 1881 80 | 465 99 |
| 146 | 1890 63 | 470 67 |
| 147 | 1899 43 | 475 43 |
| 148 | 1908 18 | 480 25 |
| 149 | 1916 90 | 485 16 |
| 150 | 1925 58 | 490 13 |
| 151 | 1934 21 | 495 17 |
| 152 | 1942 81 | 500 29 |
| 153 | 1951 35 | 505 47 |
| 154 | 1959 86 | 510 73 |
| 155 | 1968 33 | 516 05 |
| 156 | 1976 75 | 521 45 |
| 157 | 1985 12 | 526 92 |
| 158 | 1993 45 | 532 45 |
| 159 | 2001 73 | 538 06 |
| 160 | 2009 97 | 543 73 |
| 161 | 2018 16 | 549 47 |
| 162 | 2025 30 | 555 27 |
| 163 | 2034 39 | 561 15 |
| 164 | 2042 43 | 567 09 |
| 165 | 2050 43 | 573 10 |
| 166 | 2058 37 | 579 17 |
| 167 | 2066 27 | 585 31 |
| 168 | 2074 11 | 591 51 |
| 169 | 2081 90 | 597 78 |
| 170 | 2089 64 | 604 11 |
| 171 | 2097 33 | 610 51 |
| 172 | 2104 96 | 616 97 |
| 173 | 2112 54 | 623 49 |
| 174 | 2120 07 | 630 07 |
| 175 | 2127 54 | 636 72 |
| 176 | 2134 96 | 643 43 |
| 177 | 2142 32 | 650 20 |
| 178 | 2149 62 | 657 03 |
| 179 | 2156 87 | 663 92 |
| 180 | 2163 17 | 670 00 |

Circle Center At X = 1319 6 , Y = 1537 4 and Radius, 1210 0
 *** 1 068 ***

Failure Surface Specified By 181 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 623 75 | 618 46 |
| 2 | 630 82 | 511 39 |
| 3 | 637 96 | 604 39 |
| 4 | 546 16 | 597 45 |
| 5 | 652 43 | 590 58 |
| 6 | 659 76 | 583 77 |
| 7 | 667 15 | 577 03 |
| 8 | 674 60 | 570 36 |
| 9 | 682 11 | 563 76 |
| 10 | 689 68 | 557 23 |
| 11 | 697 31 | 550 77 |
| 12 | 705 00 | 544 38 |

| | | |
|----|---------|--------|
| 13 | 712 75 | 538 05 |
| 14 | 720 55 | 531 80 |
| 15 | 728 42 | 526 63 |
| 16 | 735 34 | 519 52 |
| 17 | 744 31 | 513 49 |
| 18 | 752 34 | 507 53 |
| 19 | 760 43 | 501 64 |
| 20 | 768 56 | 495 83 |
| 21 | 776 75 | 490 09 |
| 22 | 785 00 | 484 43 |
| 23 | 793 29 | 478 84 |
| 24 | 801 64 | 473 33 |
| 25 | 810 03 | 467 90 |
| 26 | 818 48 | 462 54 |
| 27 | 826 97 | 457 26 |
| 28 | 835 51 | 452 06 |
| 29 | 844 10 | 446 94 |
| 30 | 852 73 | 441 90 |
| 31 | 861 41 | 436 93 |
| 32 | 870 14 | 432 05 |
| 33 | 878 91 | 427 24 |
| 34 | 887 72 | 422 52 |
| 35 | 896 58 | 417 88 |
| 36 | 905 48 | 413 31 |
| 37 | 914 42 | 408 83 |
| 38 | 923 40 | 404 44 |
| 39 | 932 42 | 400 12 |
| 40 | 941 48 | 395 89 |
| 41 | 950 58 | 391 74 |
| 42 | 959 72 | 387 67 |
| 43 | 968 89 | 383 69 |
| 44 | 978 10 | 379 79 |
| 45 | 987 34 | 375 98 |
| 46 | 996 62 | 372 25 |
| 47 | 1005 93 | 368 61 |
| 48 | 1015 28 | 365 05 |
| 49 | 1024 66 | 361 58 |
| 50 | 1034 07 | 358 19 |
| 51 | 1043 51 | 354 89 |
| 52 | 1052 98 | 351 68 |
| 53 | 1062 48 | 348 55 |
| 54 | 1072 00 | 345 51 |
| 55 | 1081 56 | 342 56 |
| 56 | 1091 14 | 339 70 |
| 57 | 1100 74 | 336 92 |
| 58 | 1110 38 | 334 23 |
| 59 | 1120 03 | 331 63 |
| 60 | 1129 71 | 329 12 |
| 61 | 1139 41 | 326 70 |
| 62 | 1149 14 | 324 36 |
| 63 | 1158 88 | 322 12 |
| 64 | 1158 65 | 319 96 |
| 65 | 1178 43 | 317 90 |
| 66 | 1188 24 | 315 92 |
| 67 | 1198 06 | 314 04 |
| 68 | 1207 89 | 312 24 |
| 69 | 1217 75 | 310 63 |
| 70 | 1227 62 | 308 92 |
| 71 | 1237 50 | 307 39 |
| 72 | 1247 39 | 305 96 |
| 73 | 1257 30 | 304 61 |
| 74 | 1267 23 | 303 36 |
| 75 | 1277 16 | 302 20 |
| 76 | 1287 10 | 301 13 |
| 77 | 1297 05 | 300 15 |
| 78 | 1307 01 | 299 26 |
| 79 | 1316 98 | 298 46 |
| 80 | 1325 96 | 297 75 |

| | | |
|-----|---------|--------|
| 81 | 1336 94 | 297 14 |
| 82 | 1345 92 | 296 62 |
| 83 | 1356 91 | 296 18 |
| 84 | 1366 91 | 295 84 |
| 85 | 1376 90 | 295 59 |
| 86 | 1386 90 | 295 44 |
| 87 | 1396 90 | 295 37 |
| 88 | 1406 90 | 295 40 |
| 89 | 1416 90 | 295 51 |
| 90 | 1426 90 | 295 72 |
| 91 | 1436 90 | 296 02 |
| 92 | 1446 89 | 296 42 |
| 93 | 1456 88 | 295 90 |
| 94 | 1466 86 | 297 47 |
| 95 | 1476 84 | 298 14 |
| 96 | 1486 81 | 298 90 |
| 97 | 1496 77 | 299 75 |
| 98 | 1506 73 | 300 69 |
| 99 | 1516 68 | 301 72 |
| 100 | 1526 61 | 302 84 |
| 101 | 1636 54 | 304 05 |
| 102 | 1546 45 | 305 36 |
| 103 | 1556 35 | 306 75 |
| 104 | 1566 24 | 308 24 |
| 105 | 1576 12 | 309 82 |
| 106 | 1585 98 | 311 48 |
| 107 | 1595 82 | 313 24 |
| 108 | 1605 65 | 315 09 |
| 109 | 1615 46 | 317 02 |
| 110 | 1625 25 | 319 05 |
| 111 | 1635 03 | 321 16 |
| 112 | 1644 78 | 323 37 |
| 113 | 1654 52 | 325 67 |
| 114 | 1664 23 | 328 05 |
| 115 | 1673 92 | 330 52 |
| 116 | 1683 58 | 333 08 |
| 117 | 1693 23 | 335 73 |
| 118 | 1702 84 | 338 47 |
| 119 | 1712 44 | 341 30 |
| 120 | 1722 00 | 344 21 |
| 121 | 1731 54 | 347 21 |
| 122 | 1741 05 | 350 30 |
| 123 | 1750 53 | 353 48 |
| 124 | 1759 99 | 356 74 |
| 125 | 1769 41 | 360 09 |
| 126 | 1778 80 | 363 52 |
| 127 | 1788 16 | 367 04 |
| 128 | 1797 49 | 370 65 |
| 129 | 1806 78 | 374 34 |
| 130 | 1816 04 | 378 11 |
| 131 | 1825 27 | 381 98 |
| 132 | 1834 46 | 385 92 |
| 133 | 1843 61 | 389 95 |
| 134 | 1852 72 | 394 06 |
| 135 | 1861 80 | 398 26 |
| 136 | 1870 84 | 402 54 |
| 137 | 1879 84 | 406 90 |
| 138 | 1888 79 | 411 34 |
| 139 | 1897 71 | 415 87 |
| 140 | 1906 59 | 420 48 |
| 141 | 1915 42 | 425 17 |
| 142 | 1924 21 | 429 94 |
| 143 | 1932 95 | 434 79 |
| 144 | 1941 66 | 439 71 |
| 145 | 1950 31 | 444 72 |
| 146 | 1958 92 | 449 81 |
| 147 | 1967 48 | 454 98 |
| 148 | 1976 00 | 460 22 |

| | | |
|-----|---------|--------|
| 149 | 1984 46 | 465 55 |
| 150 | 1992 88 | 470 95 |
| 151 | 2001 25 | 476 42 |
| 152 | 2009 56 | 481 97 |
| 153 | 2017 83 | 487 60 |
| 154 | 2025 04 | 493 31 |
| 155 | 2034 20 | 499 09 |
| 155 | 2042 31 | 504 94 |
| 157 | 2050 35 | 510 87 |
| 158 | 2058 36 | 516 87 |
| 159 | 2066 30 | 522 95 |
| 150 | 2074 19 | 629 09 |
| 161 | 2082 02 | 535 31 |
| 162 | 2089 80 | 541 50 |
| 163 | 2097 51 | 547 96 |
| 164 | 2105 17 | 554 39 |
| 165 | 2112 77 | 560 90 |
| 166 | 2120 31 | 567 47 |
| 167 | 2127 78 | 574 11 |
| 168 | 2135 20 | 580 81 |
| 169 | 2142 66 | 587 59 |
| 170 | 2149 85 | 594 43 |
| 171 | 2157 08 | 601 34 |
| 172 | 2164 24 | 608 32 |
| 173 | 2171 34 | 615 36 |
| 174 | 2178 38 | 622 46 |
| 175 | 2185 35 | 629 63 |
| 176 | 2192 26 | 536 86 |
| 177 | 2199 10 | 644 16 |
| 178 | 2205 87 | 651 52 |
| 179 | 2212 57 | 658 94 |
| 180 | 2219 21 | 666 42 |
| 181 | 2222 33 | 670 00 |

Circle Center At X = 1399 1 , Y = 1387 2 and Radius, 1091 9
 *** 1 074 ***

Failure Surface Specified By 167 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 533 76 | 617 36 |
| 2 | 540 98 | 610 45 |
| 3 | 548 27 | 603 61 |
| 4 | 655 63 | 596 84 |
| 5 | 563 06 | 590 14 |
| 6 | 570 55 | 583 51 |
| 7 | 578 10 | 576 96 |
| 8 | 685 71 | 570 48 |
| 9 | 593 39 | 564 07 |
| 10 | 601 13 | 557 74 |
| 11 | 608 94 | 551 48 |
| 12 | 616 80 | 545 30 |
| 13 | 624 72 | 539 20 |
| 14 | 632 70 | 533 17 |
| 15 | 640 74 | 527 23 |
| 16 | 648 83 | 521 36 |
| 17 | 655 98 | 515 55 |
| 18 | 665 19 | 509 85 |
| 19 | 673 45 | 504 22 |
| 20 | 681 77 | 498 67 |
| 21 | 690 14 | 493 19 |
| 22 | 698 56 | 487 80 |
| 23 | 707 04 | 482 49 |
| 24 | 715 56 | 477 27 |
| 25 | 724 14 | 472 12 |
| 26 | 732 77 | 467 06 |
| 27 | 741 44 | 462 09 |
| 28 | 750 16 | 457 20 |
| 29 | 758 93 | 452 39 |
| 30 | 767 75 | 447 67 |

| | | |
|----|---------|--------|
| 31 | 776 61 | 443 03 |
| 32 | 785 51 | 438 48 |
| 33 | 794 46 | 434 02 |
| 34 | 803 45 | 429 54 |
| 36 | 812 48 | 425 36 |
| 36 | 821 56 | 421 15 |
| 37 | 830 67 | 417 04 |
| 38 | 839 83 | 413 01 |
| 39 | 849 02 | 409 07 |
| 40 | 858 25 | 405 23 |
| 41 | 867 52 | 401 47 |
| 42 | 876 82 | 397 80 |
| 43 | 886 16 | 394 23 |
| 44 | 895 53 | 390 74 |
| 45 | 904 94 | 387 34 |
| 45 | 914 38 | 384 04 |
| 47 | 923 85 | 380 83 |
| 48 | 933 35 | 377 71 |
| 49 | 942 88 | 374 68 |
| 50 | 952 44 | 371 74 |
| 51 | 962 02 | 368 90 |
| 52 | 971 64 | 366 15 |
| 53 | 981 28 | 363 49 |
| 54 | 990 94 | 350 93 |
| 55 | 1000 63 | 358 46 |
| 56 | 1010 35 | 356 08 |
| 57 | 1020 08 | 353 80 |
| 58 | 1029 84 | 351 61 |
| 59 | 1039 62 | 349 62 |
| 60 | 1049 42 | 347 52 |
| 61 | 1059 24 | 345 62 |
| 62 | 1069 07 | 343 82 |
| 63 | 1078 92 | 342 10 |
| 64 | 1088 79 | 340 49 |
| 65 | 1098 68 | 338 97 |
| 66 | 1108 57 | 337 54 |
| 67 | 1118 49 | 336 21 |
| 68 | 1128 41 | 334 98 |
| 69 | 1138 34 | 333 84 |
| 70 | 1148 29 | 332 80 |
| 71 | 1158 25 | 331 86 |
| 72 | 1168 21 | 331 01 |
| 73 | 1178 18 | 330 25 |
| 74 | 1188 16 | 329 61 |
| 75 | 1198 15 | 329 05 |
| 76 | 1208 13 | 328 69 |
| 77 | 1218 13 | 328 23 |
| 78 | 1228 12 | 327 96 |
| 79 | 1238 12 | 327 79 |
| 80 | 1248 12 | 327 72 |
| 81 | 1258 12 | 327 74 |
| 82 | 1258 12 | 327 86 |
| 83 | 1278 12 | 328 08 |
| 84 | 1288 11 | 328 39 |
| 85 | 1298 11 | 328 81 |
| 86 | 1308 09 | 329 31 |
| 87 | 1318 07 | 329 92 |
| 88 | 1328 05 | 330 62 |
| 89 | 1338 02 | 331 42 |
| 90 | 1347 98 | 332 31 |
| 91 | 1357 93 | 333 30 |
| 92 | 1367 87 | 334 39 |
| 93 | 1377 80 | 335 58 |
| 94 | 1387 72 | 336 86 |
| 95 | 1397 62 | 338 23 |
| 96 | 1407 51 | 339 70 |
| 97 | 1417 39 | 341 27 |
| 98 | 1427 26 | 342 93 |

56/30


| | | |
|-----|---------|--------|
| 99 | 1437 09 | 344 69 |
| 100 | 1446 92 | 346 65 |
| 101 | 1456 73 | 348 50 |
| 102 | 1466 52 | 350 64 |
| 103 | 1476 29 | 352 68 |
| 104 | 1486 03 | 354 91 |
| 105 | 1495 76 | 357 24 |
| 106 | 1505 46 | 359 66 |
| 107 | 1515 14 | 362 18 |
| 108 | 1524 79 | 364 79 |
| 109 | 1534 42 | 367 49 |
| 110 | 1544 02 | 370 29 |
| 111 | 1553 60 | 373 18 |
| 112 | 1563 14 | 376 15 |
| 113 | 1572 66 | 379 23 |
| 114 | 1582 14 | 382 40 |
| 115 | 1591 60 | 386 66 |
| 116 | 1601 02 | 389 00 |
| 117 | 1610 41 | 392 44 |
| 118 | 1619 77 | 395 98 |
| 119 | 1629 09 | 399 60 |
| 120 | 1638 37 | 403 31 |
| 121 | 1647 62 | 407 11 |
| 122 | 1656 83 | 411 00 |
| 123 | 1665 01 | 414 98 |
| 124 | 1675 14 | 419 05 |
| 125 | 1684 24 | 423 21 |
| 125 | 1693 29 | 427 45 |
| 127 | 1702 30 | 431 79 |
| 128 | 1711 27 | 436 21 |
| 129 | 1720 20 | 440 71 |
| 130 | 1729 08 | 445 30 |
| 131 | 1737 92 | 449 98 |
| 132 | 1746 71 | 454 75 |
| 133 | 1755 46 | 459 60 |
| 134 | 1764 16 | 464 53 |
| 135 | 1772 81 | 469 55 |
| 136 | 1781 41 | 474 55 |
| 137 | 1789 96 | 479 83 |
| 138 | 1798 46 | 485 10 |
| 139 | 1806 91 | 490 45 |
| 140 | 1815 31 | 495 88 |
| 141 | 1823 65 | 501 39 |
| 142 | 1831 94 | 506 98 |
| 143 | 1840 18 | 512 65 |
| 144 | 1848 36 | 518 41 |
| 145 | 1856 48 | 524 24 |
| 146 | 1864 55 | 530 15 |
| 147 | 1872 56 | 536 13 |
| 148 | 1880 51 | 542 20 |
| 149 | 1888 40 | 548 34 |
| 150 | 1896 23 | 554 56 |
| 151 | 1904 01 | 550 85 |
| 152 | 1911 72 | 567 22 |
| 153 | 1919 36 | 573 66 |
| 154 | 1926 95 | 580 18 |
| 155 | 1934 47 | 586 77 |
| 156 | 1941 93 | 593 43 |
| 157 | 1949 32 | 600 16 |
| 158 | 1956 65 | 606 97 |
| 159 | 1963 91 | 613 84 |
| 160 | 1971 10 | 520 79 |
| 161 | 1978 23 | 627 80 |
| 162 | 1985 29 | 634 89 |
| 163 | 1992 28 | 642 04 |
| 164 | 1999 20 | 649 26 |
| 165 | 2006 05 | 656 55 |
| 166 | 2012 83 | 663 90 |

57/30

167 2018 34 670 00
Circle Center At X = 1250 7 , Y = 1359 8 and Radius, 1032 0
*** 1 080 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\irf\3 pl2 Run By: Greg Shafer, HDR 4/20/2010 02:12PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Piez Surface | Load Horiz Eqk | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|--------------|----------------|-------|
| a | 0.57 | | | | | | | 0.200 | g< |
| b | 0.58 | | | | | | | | |
| c | 0.58 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | W1 | | |
| d | 0.59 | LSC | 2 | 121.0 | 125.5 | 1500.0 | W1 | | |
| e | 0.59 | SC | 3 | 121.0 | 125.5 | 2000.0 | W1 | | |
| f | 0.59 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | W1 | | |
| g | 0.60 | | | | | | | | |
| h | 0.60 | | | | | | | | |
| i | 0.61 | | | | | | | | |
| j | 0.61 | | | | | | | | |

PCSTABL7 FSmin=0.57

Safety Factors Are Calculated By The Modified Bishop Method

STED



4/28/10

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 02 12PM
Run By Greg Shafer, HDR
Input Data Filename C 3 in
Output Filename C 3 OUT
Unit ENGLISH
Plotted Output Filename C 3 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 550 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param (psf) | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of 0 200 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 480 00 ft
and X = 770 00 ft
Each Surface Termlnates Between X = 950 00 ft
and X =2220 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial
Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 183 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 504 17 | 617 00 |
| 2 | 511 29 | 609 98 |
| 3 | 518 48 | 603 03 |
| 4 | 525 73 | 596 14 |
| 5 | 533 04 | 589 32 |
| 6 | 540 41 | 582 56 |
| 7 | 547 84 | 575 87 |
| 8 | 555 33 | 569 24 |

| | | |
|----|---------|--------|
| 9 | 562 88 | 562 69 |
| 10 | 570 49 | 556 20 |
| 11 | 578 16 | 549 78 |
| 12 | 585 88 | 543 43 |
| 13 | 593 57 | 537 15 |
| 14 | 601 50 | 630 93 |
| 15 | 609 39 | 524 79 |
| 16 | 617 34 | 518 72 |
| 17 | 625 34 | 512 72 |
| 18 | 533 40 | 505 80 |
| 19 | 641 50 | 500 94 |
| 20 | 649 66 | 495 16 |
| 21 | 657 87 | 489 45 |
| 22 | 666 13 | 483 82 |
| 23 | 674 45 | 478 26 |
| 24 | 682 81 | 472 77 |
| 25 | 691 22 | 467 36 |
| 26 | 699 68 | 462 03 |
| 27 | 708 18 | 455 77 |
| 28 | 716 73 | 451 59 |
| 29 | 725 33 | 446 48 |
| 30 | 733 98 | 441 45 |
| 31 | 742 67 | 435 50 |
| 32 | 751 40 | 431 63 |
| 33 | 760 17 | 426 84 |
| 34 | 768 99 | 422 12 |
| 35 | 777 85 | 417 49 |
| 36 | 786 75 | 412 93 |
| 37 | 796 70 | 408 45 |
| 38 | 804 68 | 404 06 |
| 39 | 813 70 | 399 74 |
| 40 | 822 76 | 395 51 |
| 41 | 831 86 | 391 35 |
| 42 | 840 99 | 387 28 |
| 43 | 860 16 | 383 29 |
| 44 | 859 37 | 379 39 |
| 45 | 868 60 | 375 56 |
| 46 | 877 88 | 371 82 |
| 47 | 887 19 | 368 16 |
| 48 | 896 53 | 364 59 |
| 49 | 905 90 | 361 10 |
| 50 | 915 30 | 367 69 |
| 51 | 924 73 | 354 37 |
| 52 | 934 19 | 351 13 |
| 53 | 943 68 | 347 98 |
| 54 | 953 20 | 344 91 |
| 55 | 952 74 | 341 93 |
| 55 | 972 32 | 339 04 |
| 57 | 981 91 | 336 23 |
| 58 | 991 53 | 333 50 |
| 59 | 1001 18 | 330 86 |
| 60 | 1010 85 | 328 31 |
| 61 | 1020 54 | 325 85 |
| 62 | 1030 25 | 323 47 |
| 63 | 1039 99 | 321 18 |
| 64 | 1049 74 | 318 98 |
| 65 | 1059 52 | 316 86 |
| 66 | 1069 31 | 314 83 |
| 67 | 1079 12 | 312 89 |
| 68 | 1088 95 | 311 04 |
| 69 | 1098 79 | 309 28 |
| 70 | 1108 65 | 307 50 |
| 71 | 1118 52 | 306 01 |
| 72 | 1128 41 | 304 52 |
| 73 | 1138 31 | 303 11 |
| 74 | 1148 22 | 301 78 |
| 75 | 1158 14 | 300 55 |
| 75 | 1168 08 | 299 41 |

| | | |
|-----|---------|--------|
| 77 | 1178 02 | 298 35 |
| 78 | 1187 98 | 297 39 |
| 79 | 1197 94 | 296 51 |
| 80 | 1207 91 | 295 73 |
| 81 | 1217 88 | 295 03 |
| 82 | 1227 86 | 294 42 |
| 83 | 1237 85 | 293 90 |
| 84 | 1247 84 | 293 48 |
| 85 | 1257 84 | 293 14 |
| 86 | 1267 83 | 292 89 |
| 87 | 1277 83 | 292 73 |
| 88 | 1287 83 | 292 56 |
| 89 | 1297 83 | 292 68 |
| 90 | 1307 83 | 292 79 |
| 91 | 1317 83 | 292 98 |
| 92 | 1327 83 | 293 27 |
| 93 | 1337 82 | 293 65 |
| 94 | 1347 81 | 294 12 |
| 95 | 1357 79 | 294 57 |
| 96 | 1367 77 | 295 32 |
| 97 | 1377 74 | 296 06 |
| 98 | 1387 71 | 296 88 |
| 99 | 1397 57 | 297 79 |
| 100 | 1407 62 | 298 80 |
| 101 | 1417 56 | 299 89 |
| 102 | 1427 49 | 301 07 |
| 103 | 1437 41 | 302 34 |
| 104 | 1447 31 | 303 70 |
| 105 | 1457 21 | 305 15 |
| 106 | 1467 09 | 306 69 |
| 107 | 1476 96 | 308 31 |
| 108 | 1486 81 | 310 03 |
| 109 | 1496 64 | 311 83 |
| 110 | 1506 46 | 313 72 |
| 111 | 1516 27 | 315 70 |
| 112 | 1526 05 | 317 76 |
| 113 | 1535 82 | 319 92 |
| 114 | 1545 56 | 322 16 |
| 115 | 1555 29 | 324 48 |
| 116 | 1564 99 | 325 90 |
| 117 | 1574 67 | 329 40 |
| 118 | 1584 33 | 331 99 |
| 119 | 1593 97 | 334 66 |
| 120 | 1603 58 | 337 43 |
| 121 | 1613 17 | 340 27 |
| 122 | 1622 73 | 343 21 |
| 123 | 1632 26 | 346 23 |
| 124 | 1541 77 | 349 33 |
| 125 | 1651 24 | 352 52 |
| 126 | 1660 69 | 355 79 |
| 127 | 1670 11 | 359 15 |
| 128 | 1679 50 | 362 59 |
| 129 | 1688 86 | 356 12 |
| 130 | 1698 18 | 369 73 |
| 131 | 1707 48 | 373 42 |
| 132 | 1716 73 | 377 20 |
| 133 | 1725 96 | 381 06 |
| 134 | 1735 15 | 385 00 |
| 135 | 1744 30 | 389 03 |
| 136 | 1753 42 | 393 13 |
| 137 | 1762 50 | 397 32 |
| 138 | 1771 55 | 401 59 |
| 139 | 1780 55 | 405 94 |
| 140 | 1789 52 | 410 37 |
| 141 | 1798 44 | 414 88 |
| 142 | 1807 32 | 419 47 |
| 143 | 1816 17 | 424 14 |
| 144 | 1824 97 | 428 89 |

60/130

| | | |
|-----|---------|--------|
| 77 | 1178 02 | 298 35 |
| 78 | 1187 98 | 297 39 |
| 79 | 1197 94 | 296 51 |
| 80 | 1207 91 | 295 73 |
| 81 | 1217 88 | 295 03 |
| 82 | 1227 86 | 294 42 |
| 83 | 1237 85 | 293 90 |
| 84 | 1247 84 | 293 48 |
| 85 | 1257 84 | 293 14 |
| 86 | 1257 83 | 292 89 |
| 87 | 1277 83 | 292 73 |
| 88 | 1287 83 | 292 56 |
| 89 | 1297 83 | 292 68 |
| 90 | 1307 83 | 292 79 |
| 91 | 1317 83 | 292 98 |
| 92 | 1327 83 | 293 27 |
| 93 | 1337 82 | 293 65 |
| 94 | 1347 81 | 294 12 |
| 95 | 1367 79 | 294 67 |
| 96 | 1367 77 | 295 32 |
| 97 | 1377 74 | 296 06 |
| 98 | 1387 71 | 296 88 |
| 99 | 1397 67 | 297 79 |
| 100 | 1407 62 | 298 80 |
| 101 | 1417 56 | 299 89 |
| 102 | 1427 49 | 301 07 |
| 103 | 1437 41 | 302 34 |
| 104 | 1447 31 | 303 70 |
| 105 | 1457 21 | 305 15 |
| 106 | 1467 09 | 306 69 |
| 107 | 1476 96 | 308 31 |
| 108 | 1486 81 | 310 03 |
| 109 | 1496 64 | 311 83 |
| 110 | 1506 46 | 313 72 |
| 111 | 1516 27 | 315 70 |
| 112 | 1526 05 | 317 76 |
| 113 | 1535 82 | 319 92 |
| 114 | 1545 56 | 322 16 |
| 115 | 1565 29 | 324 48 |
| 116 | 1564 99 | 326 90 |
| 117 | 1574 67 | 329 40 |
| 118 | 1584 33 | 331 99 |
| 119 | 1593 97 | 334 66 |
| 120 | 1603 58 | 337 43 |
| 121 | 1613 17 | 340 27 |
| 122 | 1622 73 | 343 21 |
| 123 | 1632 26 | 346 23 |
| 124 | 1641 77 | 349 33 |
| 125 | 1651 24 | 352 52 |
| 126 | 1660 59 | 355 79 |
| 127 | 1670 11 | 359 15 |
| 128 | 1679 50 | 362 59 |
| 129 | 1688 86 | 366 12 |
| 130 | 1698 18 | 359 73 |
| 131 | 1707 48 | 373 42 |
| 132 | 1716 73 | 377 20 |
| 133 | 1725 96 | 381 06 |
| 134 | 1735 15 | 385 00 |
| 135 | 1744 30 | 389 03 |
| 136 | 1753 42 | 393 13 |
| 137 | 1762 50 | 397 32 |
| 138 | 1771 55 | 401 59 |
| 139 | 1780 55 | 405 94 |
| 140 | 1789 52 | 410 37 |
| 141 | 1798 44 | 414 88 |
| 142 | 1807 32 | 419 47 |
| 143 | 1816 17 | 424 14 |
| 144 | 1824 97 | 428 89 |

| | | | | |
|-----|------|----|-----|----|
| 145 | 1833 | 72 | 433 | 72 |
| 146 | 1842 | 44 | 438 | 63 |
| 147 | 1861 | 11 | 443 | 61 |
| 148 | 1859 | 73 | 448 | 57 |
| 149 | 1868 | 31 | 453 | 81 |
| 150 | 1876 | 84 | 459 | 03 |
| 151 | 1885 | 33 | 464 | 32 |
| 152 | 1893 | 77 | 469 | 68 |
| 153 | 1902 | 16 | 475 | 13 |
| 154 | 1910 | 50 | 480 | 66 |
| 155 | 1918 | 79 | 486 | 24 |
| 156 | 1927 | 03 | 491 | 90 |
| 157 | 1935 | 21 | 497 | 64 |
| 158 | 1943 | 35 | 503 | 46 |
| 159 | 1951 | 43 | 509 | 34 |
| 160 | 1959 | 47 | 615 | 30 |
| 161 | 1967 | 44 | 521 | 33 |
| 162 | 1975 | 37 | 527 | 43 |
| 163 | 1983 | 24 | 533 | 50 |
| 164 | 1991 | 05 | 539 | 84 |
| 165 | 1998 | 80 | 546 | 16 |
| 166 | 2006 | 50 | 552 | 54 |
| 167 | 2014 | 15 | 558 | 99 |
| 168 | 2021 | 73 | 565 | 51 |
| 169 | 2029 | 25 | 572 | 09 |
| 170 | 2036 | 72 | 578 | 74 |
| 171 | 2044 | 13 | 585 | 46 |
| 172 | 2051 | 47 | 592 | 25 |
| 173 | 2058 | 75 | 599 | 10 |
| 174 | 2065 | 98 | 606 | 02 |
| 175 | 2073 | 14 | 613 | 00 |
| 176 | 2080 | 24 | 620 | 04 |
| 177 | 2087 | 27 | 627 | 15 |
| 178 | 2094 | 24 | 634 | 32 |
| 179 | 2101 | 15 | 641 | 55 |
| 180 | 2107 | 99 | 648 | 85 |
| 181 | 2114 | 76 | 656 | 20 |
| 182 | 2121 | 47 | 663 | 62 |
| 183 | 2127 | 14 | 670 | 00 |

Circle Center At X = 1290 7 , Y = 1408 4 and Radius, 1115 8
 *** 0 574 ***

Individual data on the 190 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 7 1 | 3062 2 | 0 0 | 0 0 | 0 0 | 0 0 | 612 4 | 0 0 | 0 0 |
| 2 | 7 2 | 9239 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1847 9 | 0 0 | 0 0 |
| 3 | 7 2 | 15457 2 | 0 0 | 0 0 | 0 0 | 0 0 | 3093 4 | 0 0 | 0 0 |
| 4 | 7 3 | 21741 4 | 0 0 | 0 0 | 0 0 | 0 0 | 4348 3 | 0 0 | 0 0 |
| 5 | 7 4 | 28058 9 | 0 0 | 0 0 | 0 0 | 0 0 | 5611 8 | 0 0 | 0 0 |
| 6 | 7 4 | 34416 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6883 2 | 0 0 | 0 0 |
| 7 | 7 6 | 40810 0 | 0 0 | 0 0 | 0 0 | 0 0 | 8162 0 | 0 0 | 0 0 |
| 8 | 7 5 | 47236 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9447 4 | 0 0 | 0 0 |
| 9 | 7 6 | 53592 7 | 0 0 | 0 0 | 0 0 | 0 0 | 10738 5 | 0 0 | 0 0 |
| 10 | 7 7 | 60175 4 | 0 0 | 0 0 | 0 0 | 0 0 | 12035 1 | 0 0 | 0 0 |
| 11 | 7 7 | 66580 7 | 0 0 | 0 0 | 0 0 | 0 0 | 13336 1 | 0 0 | 0 0 |
| 12 | 7 8 | 73205 1 | 0 0 | 0 0 | 0 0 | 0 0 | 14641 0 | 0 0 | 0 0 |
| 13 | 7 8 | 79746 2 | 0 0 | 0 0 | 0 0 | 0 0 | 15949 2 | 0 0 | 0 0 |
| 14 | 7 9 | 86299 5 | 0 0 | 0 0 | 0 0 | 0 0 | 17259 9 | 0 0 | 0 0 |
| 15 | 7 9 | 92861 6 | 0 0 | 0 0 | 0 0 | 0 0 | 18572 3 | 0 0 | 0 0 |
| 16 | 8 0 | 99429 9 | 0 0 | 0 0 | 0 0 | 0 0 | 19886 0 | 0 0 | 0 0 |
| 17 | 8 1 | 106001 1 | 0 0 | 0 0 | 0 0 | 0 0 | 21200 2 | 0 0 | 0 0 |
| 18 | 8 1 | 112571 3 | 0 0 | 0 0 | 0 0 | 0 0 | 22514 3 | 0 0 | 0 0 |
| 19 | 8 2 | 119137 1 | 0 0 | 0 0 | 0 0 | 0 0 | 23827 4 | 0 0 | 0 0 |
| 20 | 8 2 | 125696 2 | 0 0 | 0 0 | 0 0 | 0 0 | 25139 2 | 0 0 | 0 0 |
| 21 | 8 3 | 132243 4 | 0 0 | 0 0 | 0 0 | 0 0 | 26448 7 | 0 0 | 0 0 |
| 22 | 8 3 | 138777 6 | 0 0 | 0 0 | 0 0 | 0 0 | 27755 5 | 0 0 | 0 0 |

| | | | | | | | | | |
|----|------|----------|-----|-----|-----|-----|---------|-----|-----|
| 23 | 8 4 | 145294 5 | 0 0 | 0 0 | 0 0 | 0 0 | 29058 9 | 0 0 | 0 0 |
| 24 | 8 4 | 151791 1 | 0 0 | 0 0 | 0 0 | 0 0 | 30358 2 | 0 0 | 0 0 |
| 25 | 8 6 | 158264 1 | 0 0 | 0 0 | 0 0 | 0 0 | 31652 8 | 0 0 | 0 0 |
| 26 | 8 5 | 164710 5 | 0 0 | 0 0 | 0 0 | 0 0 | 32942 1 | 0 0 | 0 0 |
| 27 | 8 6 | 171127 2 | 0 0 | 0 0 | 0 0 | 0 0 | 34225 4 | 0 0 | 0 0 |
| 28 | 8 5 | 177510 0 | 0 0 | 0 0 | 0 0 | 0 0 | 35502 0 | 0 0 | 0 0 |
| 29 | 8 6 | 183856 9 | 0 0 | 0 0 | 0 0 | 0 0 | 35771 4 | 0 0 | 0 0 |
| 30 | 8 7 | 190154 0 | 0 0 | 0 0 | 0 0 | 0 0 | 38032 8 | 0 0 | 0 0 |
| 31 | 7 3 | 164631 9 | 0 0 | 0 0 | 0 0 | 0 0 | 32926 4 | 0 0 | 0 0 |
| 32 | 1 4 | 29854 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5970 8 | 0 0 | 0 0 |
| 33 | 8 8 | 191469 2 | 0 0 | 0 0 | 0 0 | 0 0 | 38291 8 | 0 0 | 0 0 |
| 34 | 8 8 | 199348 8 | 0 0 | 0 0 | 0 0 | 0 0 | 39869 8 | 0 0 | 0 0 |
| 35 | 8 9 | 207221 0 | 0 0 | 0 0 | 0 0 | 0 0 | 41444 2 | 0 0 | 0 0 |
| 36 | 8 9 | 215071 4 | 0 0 | 0 0 | 0 0 | 0 0 | 43014 3 | 0 0 | 0 0 |
| 37 | 8 9 | 222896 7 | 0 0 | 0 0 | 0 0 | 0 0 | 44579 3 | 0 0 | 0 0 |
| 38 | 9 0 | 230693 5 | 0 0 | 0 0 | 0 0 | 0 0 | 46138 7 | 0 0 | 0 0 |
| 39 | 9 0 | 238460 5 | 0 0 | 0 0 | 0 0 | 0 0 | 47592 1 | 0 0 | 0 0 |
| 40 | 9 1 | 246193 0 | 0 0 | 0 0 | 0 0 | 0 0 | 49238 6 | 0 0 | 0 0 |
| 41 | 7 2 | 201544 0 | 0 0 | 0 0 | 0 0 | 0 0 | 40308 8 | 0 0 | 0 0 |
| 42 | 1 9 | 55799 6 | 0 0 | 0 0 | 0 0 | 0 0 | 11159 9 | 0 0 | 0 0 |
| 43 | 9 1 | 278712 8 | 0 0 | 0 0 | 0 0 | 0 0 | 55742 6 | 0 0 | 0 0 |
| 44 | 9 2 | 286668 3 | 0 0 | 0 0 | 0 0 | 0 0 | 57333 7 | 0 0 | 0 0 |
| 45 | 9 2 | 294572 3 | 0 0 | 0 0 | 0 0 | 0 0 | 58914 5 | 0 0 | 0 0 |
| 46 | 9 2 | 302419 3 | 0 0 | 0 0 | 0 0 | 0 0 | 60483 9 | 0 0 | 0 0 |
| 47 | 1 4 | 46241 5 | 0 0 | 0 0 | 0 0 | 0 0 | 9248 3 | 0 0 | 0 0 |
| 48 | 7 9 | 264560 1 | 0 0 | 0 0 | 0 0 | 0 0 | 52912 0 | 0 0 | 0 0 |
| 49 | 9 3 | 318537 0 | 0 0 | 0 0 | 0 0 | 0 0 | 63727 4 | 0 0 | 0 0 |
| 50 | 9 3 | 326303 8 | 0 0 | 0 0 | 0 0 | 0 0 | 65260 8 | 0 0 | 0 0 |
| 51 | 9 4 | 333903 5 | 0 0 | 0 0 | 0 0 | 0 0 | 66780 7 | 0 0 | 0 0 |
| 52 | 4 1 | 148249 9 | 0 0 | 0 0 | 0 0 | 0 0 | 29650 0 | 0 0 | 0 0 |
| 53 | 5 3 | 193678 7 | 0 0 | 0 0 | 0 0 | 0 0 | 38715 7 | 0 0 | 0 0 |
| 54 | 9 4 | 349693 4 | 0 0 | 0 0 | 0 0 | 0 0 | 69918 7 | 0 0 | 0 0 |
| 55 | 9 5 | 356974 8 | 0 0 | 0 0 | 0 0 | 0 0 | 71395 0 | 0 0 | 0 0 |
| 56 | 9 5 | 364275 1 | 0 0 | 0 0 | 0 0 | 0 0 | 72855 0 | 0 0 | 0 0 |
| 57 | 6 3 | 245928 8 | 0 0 | 0 0 | 0 0 | 0 0 | 49185 8 | 0 0 | 0 0 |
| 58 | 3 2 | 125420 0 | 0 0 | 0 0 | 0 0 | 0 0 | 25084 0 | 0 0 | 0 0 |
| 59 | 9 5 | 376467 4 | 0 0 | 0 0 | 0 0 | 0 0 | 75293 5 | 0 0 | 0 0 |
| 60 | 9 6 | 380908 7 | 0 0 | 0 0 | 0 0 | 0 0 | 76181 7 | 0 0 | 0 0 |
| 61 | 9 6 | 385239 6 | 0 0 | 0 0 | 0 0 | 0 0 | 77047 9 | 0 0 | 0 0 |
| 62 | 9 6 | 389458 5 | 0 0 | 0 0 | 0 0 | 0 0 | 77891 7 | 0 0 | 0 0 |
| 63 | 9 6 | 393558 5 | 0 0 | 0 0 | 0 0 | 0 0 | 78711 7 | 0 0 | 0 0 |
| 64 | 9 7 | 397642 8 | 0 0 | 0 0 | 0 0 | 0 0 | 79508 6 | 0 0 | 0 0 |
| 65 | 9 7 | 401409 7 | 0 0 | 0 0 | 0 0 | 0 0 | 80281 9 | 0 0 | 0 0 |
| 65 | 9 7 | 405155 1 | 0 0 | 0 0 | 0 0 | 0 0 | 81031 0 | 0 0 | 0 0 |
| 67 | 9 7 | 408772 2 | 0 0 | 0 0 | 0 0 | 0 0 | 81754 4 | 0 0 | 0 0 |
| 68 | 9 8 | 412269 8 | 0 0 | 0 0 | 0 0 | 0 0 | 82454 0 | 0 0 | 0 0 |
| 69 | 9 8 | 415643 7 | 0 0 | 0 0 | 0 0 | 0 0 | 83128 7 | 0 0 | 0 0 |
| 70 | 9 8 | 418887 4 | 0 0 | 0 0 | 0 0 | 0 0 | 83777 5 | 0 0 | 0 0 |
| 71 | 9 8 | 422004 8 | 0 0 | 0 0 | 0 0 | 0 0 | 84401 0 | 0 0 | 0 0 |
| 72 | 9 8 | 424989 3 | 0 0 | 0 0 | 0 0 | 0 0 | 84997 9 | 0 0 | 0 0 |
| 73 | 9 8 | 427844 7 | 0 0 | 0 0 | 0 0 | 0 0 | 85568 9 | 0 0 | 0 0 |
| 74 | 9 9 | 430564 7 | 0 0 | 0 0 | 0 0 | 0 0 | 86112 9 | 0 0 | 0 0 |
| 75 | 9 9 | 433153 4 | 0 0 | 0 0 | 0 0 | 0 0 | 86630 7 | 0 0 | 0 0 |
| 76 | 9 9 | 435604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 87120 9 | 0 0 | 0 0 |
| 77 | 9 9 | 437922 0 | 0 0 | 0 0 | 0 0 | 0 0 | 87584 4 | 0 0 | 0 0 |
| 78 | 9 9 | 440099 8 | 0 0 | 0 0 | 0 0 | 0 0 | 88020 0 | 0 0 | 0 0 |
| 79 | 9 9 | 442142 3 | 0 0 | 0 0 | 0 0 | 0 0 | 88428 5 | 0 0 | 0 0 |
| 80 | 9 9 | 444043 3 | 0 0 | 0 0 | 0 0 | 0 0 | 88808 7 | 0 0 | 0 0 |
| 81 | 9 9 | 445807 3 | 0 0 | 0 0 | 0 0 | 0 0 | 89161 5 | 0 0 | 0 0 |
| 82 | 10 0 | 447428 2 | 0 0 | 0 0 | 0 0 | 0 0 | 89485 5 | 0 0 | 0 0 |
| 83 | 10 0 | 448905 2 | 0 0 | 0 0 | 0 0 | 0 0 | 89781 1 | 0 0 | 0 0 |
| 84 | 10 0 | 450243 4 | 0 0 | 0 0 | 0 0 | 0 0 | 90048 7 | 0 0 | 0 0 |
| 86 | 10 0 | 451441 9 | 0 0 | 0 0 | 0 0 | 0 0 | 90288 4 | 0 0 | 0 0 |
| 86 | 10 0 | 452495 1 | 0 0 | 0 0 | 0 0 | 0 0 | 90499 0 | 0 0 | 0 0 |
| 87 | 10 0 | 453402 2 | 0 0 | 0 0 | 0 0 | 0 0 | 90680 4 | 0 0 | 0 0 |
| 88 | 10 0 | 454168 5 | 0 0 | 0 0 | 0 0 | 0 0 | 90833 7 | 0 0 | 0 0 |
| 89 | 10 0 | 454788 1 | 0 0 | 0 0 | 0 0 | 0 0 | 90957 6 | 0 0 | 0 0 |
| 90 | 10 0 | 455250 8 | 0 0 | 0 0 | 0 0 | 0 0 | 91052 2 | 0 0 | 0 0 |

| | | | | | | | | | | | | | | | | | | |
|-----|----|---|--------|---|---|---|---|---|---|---|---|---|-------|---|---|---|---|---|
| 91 | 10 | 0 | 455597 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 91119 | 5 | 0 | 0 | 0 | 0 |
| 92 | 10 | 0 | 455781 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 91155 | 2 | 0 | 0 | 0 | 0 |
| 93 | 10 | 0 | 455823 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 91164 | 6 | 0 | 0 | 0 | 0 |
| 94 | 10 | 0 | 455717 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 91143 | 6 | 0 | 0 | 0 | 0 |
| 95 | 10 | 0 | 455470 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 91094 | 1 | 0 | 0 | 0 | 0 |
| 96 | 10 | 0 | 455076 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 91015 | 2 | 0 | 0 | 0 | 0 |
| 97 | 10 | 0 | 454640 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 90908 | 0 | 0 | 0 | 0 | 0 |
| 98 | 10 | 0 | 453867 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 90771 | 5 | 0 | 0 | 0 | 0 |
| 99 | 10 | 0 | 453028 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 90605 | 6 | 0 | 0 | 0 | 0 |
| 100 | 10 | 0 | 452058 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 90411 | 6 | 0 | 0 | 0 | 0 |
| 101 | 10 | 0 | 450942 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 90188 | 5 | 0 | 0 | 0 | 0 |
| 102 | 10 | 0 | 449686 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 89937 | 4 | 0 | 0 | 0 | 0 |
| 103 | 10 | 0 | 448286 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 89657 | 3 | 0 | 0 | 0 | 0 |
| 104 | 9 | 9 | 445741 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 89348 | 4 | 0 | 0 | 0 | 0 |
| 105 | 9 | 9 | 445064 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 89012 | 9 | 0 | 0 | 0 | 0 |
| 106 | 9 | 9 | 443239 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 88647 | 9 | 0 | 0 | 0 | 0 |
| 107 | 9 | 9 | 441277 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 88255 | 5 | 0 | 0 | 0 | 0 |
| 108 | 9 | 9 | 439174 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 87834 | 8 | 0 | 0 | 0 | 0 |
| 109 | 9 | 9 | 435936 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 87387 | 2 | 0 | 0 | 0 | 0 |
| 110 | 9 | 9 | 434564 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 86912 | 8 | 0 | 0 | 0 | 0 |
| 111 | 9 | 9 | 432053 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 86410 | 7 | 0 | 0 | 0 | 0 |
| 112 | 9 | 9 | 429406 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 85881 | 2 | 0 | 0 | 0 | 0 |
| 113 | 9 | 8 | 425627 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 85325 | 5 | 0 | 0 | 0 | 0 |
| 114 | 9 | 8 | 423719 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 84743 | 9 | 0 | 0 | 0 | 0 |
| 115 | 9 | 8 | 420677 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 84135 | 5 | 0 | 0 | 0 | 0 |
| 116 | 9 | 8 | 417503 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 83500 | 7 | 0 | 0 | 0 | 0 |
| 117 | 9 | 8 | 414203 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 82840 | 7 | 0 | 0 | 0 | 0 |
| 118 | 9 | 7 | 410779 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 82155 | 8 | 0 | 0 | 0 | 0 |
| 119 | 9 | 7 | 407226 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 81445 | 3 | 0 | 0 | 0 | 0 |
| 120 | 9 | 7 | 403552 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 80710 | 5 | 0 | 0 | 0 | 0 |
| 121 | 9 | 7 | 399758 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 79951 | 7 | 0 | 0 | 0 | 0 |
| 122 | 9 | 7 | 395841 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 79168 | 3 | 0 | 0 | 0 | 0 |
| 123 | 9 | 6 | 391807 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 78361 | 5 | 0 | 0 | 0 | 0 |
| 124 | 9 | 6 | 387553 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 77530 | 7 | 0 | 0 | 0 | 0 |
| 125 | 9 | 6 | 383386 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 76577 | 3 | 0 | 0 | 0 | 0 |
| 126 | 9 | 6 | 379008 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 75801 | 7 | 0 | 0 | 0 | 0 |
| 127 | 9 | 5 | 374515 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 74903 | 1 | 0 | 0 | 0 | 0 |
| 128 | 9 | 5 | 369920 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 73984 | 0 | 0 | 0 | 0 | 0 |
| 129 | 9 | 5 | 366214 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 73042 | 9 | 0 | 0 | 0 | 0 |
| 130 | 9 | 4 | 360400 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 72080 | 1 | 0 | 0 | 0 | 0 |
| 131 | 9 | 4 | 365489 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 71097 | 9 | 0 | 0 | 0 | 0 |
| 132 | 9 | 4 | 350474 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 70094 | 9 | 0 | 0 | 0 | 0 |
| 133 | 9 | 4 | 345362 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 69072 | 5 | 0 | 0 | 0 | 0 |
| 134 | 9 | 3 | 340155 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 68031 | 0 | 0 | 0 | 0 | 0 |
| 135 | 9 | 3 | 334855 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 66971 | 1 | 0 | 0 | 0 | 0 |
| 136 | 9 | 3 | 329465 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 55893 | 0 | 0 | 0 | 0 | 0 |
| 137 | 9 | 2 | 323986 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 64797 | 3 | 0 | 0 | 0 | 0 |
| 138 | 9 | 2 | 318418 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 53683 | 6 | 0 | 0 | 0 | 0 |
| 139 | 9 | 2 | 312770 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 62564 | 1 | 0 | 0 | 0 | 0 |
| 140 | 9 | 1 | 307038 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 51407 | 7 | 0 | 0 | 0 | 0 |
| 141 | 9 | 1 | 301231 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 60246 | 4 | 0 | 0 | 0 | 0 |
| 142 | 9 | 0 | 296345 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 59069 | 1 | 0 | 0 | 0 | 0 |
| 143 | 9 | 0 | 289390 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 57878 | 0 | 0 | 0 | 0 | 0 |
| 144 | 9 | 0 | 283364 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 56672 | 9 | 0 | 0 | 0 | 0 |
| 145 | 8 | 9 | 277267 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 56453 | 4 | 0 | 0 | 0 | 0 |
| 146 | 8 | 9 | 271108 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 54221 | 7 | 0 | 0 | 0 | 0 |
| 147 | 8 | 8 | 264887 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 52977 | 6 | 0 | 0 | 0 | 0 |
| 148 | 8 | 8 | 268607 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 51721 | 6 | 0 | 0 | 0 | 0 |
| 149 | 8 | 8 | 252274 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 50454 | 9 | 0 | 0 | 0 | 0 |
| 150 | 8 | 7 | 245887 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 49177 | 5 | 0 | 0 | 0 | 0 |
| 151 | 8 | 7 | 239449 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 47890 | 0 | 0 | 0 | 0 | 0 |
| 152 | 8 | 6 | 232954 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 46592 | 9 | 0 | 0 | 0 | 0 |
| 153 | 8 | 6 | 226433 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 45286 | 8 | 0 | 0 | 0 | 0 |
| 154 | 8 | 5 | 219864 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 43972 | 9 | 0 | 0 | 0 | 0 |
| 155 | 8 | 6 | 213259 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 42652 | 0 | 0 | 0 | 0 | 0 |
| 156 | 8 | 4 | 206616 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 41323 | 3 | 0 | 0 | 0 | 0 |
| 157 | 8 | 4 | 199943 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 39988 | 6 | 0 | 0 | 0 | 0 |
| 158 | 8 | 3 | 193243 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 38648 | 6 | 0 | 0 | 0 | 0 |

67/130

| | | | | | | | | | |
|-----|-----|----------|-----|-----|-----|-----|---------|-----|-----|
| 159 | 8 3 | 186517 1 | 0 0 | 0 0 | 0 0 | 0 0 | 37303 4 | 0 0 | 0 0 |
| 160 | 8 2 | 179770 3 | 0 0 | 0 0 | 0 0 | 0 0 | 35954 1 | 0 0 | 0 0 |
| 161 | 8 2 | 173003 6 | 0 0 | 0 0 | 0 0 | 0 0 | 34600 7 | 0 0 | 0 0 |
| 162 | 8 1 | 166222 9 | 0 0 | 0 0 | 0 0 | 0 0 | 33244 6 | 0 0 | 0 0 |
| 163 | 8 1 | 159431 1 | 0 0 | 0 0 | 0 0 | 0 0 | 31886 2 | 0 0 | 0 0 |
| 164 | 8 0 | 152629 1 | 0 0 | 0 0 | 0 0 | 0 0 | 30525 8 | 0 0 | 0 0 |
| 165 | 8 0 | 145822 6 | 0 0 | 0 0 | 0 0 | 0 0 | 29164 6 | 0 0 | 0 0 |
| 166 | 7 9 | 139012 5 | 0 0 | 0 0 | 0 0 | 0 0 | 27802 5 | 0 0 | 0 0 |
| 167 | 7 9 | 132206 6 | 0 0 | 0 0 | 0 0 | 0 0 | 26441 3 | 0 0 | 0 0 |
| 168 | 7 8 | 125403 7 | 0 0 | 0 0 | 0 0 | 0 0 | 25080 7 | 0 0 | 0 0 |
| 169 | 7 8 | 118609 4 | 0 0 | 0 0 | 0 0 | 0 0 | 23721 9 | 0 0 | 0 0 |
| 170 | 7 7 | 111827 0 | 0 0 | 0 0 | 0 0 | 0 0 | 22365 4 | 0 0 | 0 0 |
| 171 | 7 6 | 105059 7 | 0 0 | 0 0 | 0 0 | 0 0 | 21011 9 | 0 0 | 0 0 |
| 172 | 7 6 | 98311 1 | 0 0 | 0 0 | 0 0 | 0 0 | 19662 2 | 0 0 | 0 0 |
| 173 | 7 5 | 91584 2 | 0 0 | 0 0 | 0 0 | 0 0 | 18316 8 | 0 0 | 0 0 |
| 174 | 7 5 | 84882 5 | 0 0 | 0 0 | 0 0 | 0 0 | 16976 5 | 0 0 | 0 0 |
| 175 | 7 4 | 78209 5 | 0 0 | 0 0 | 0 0 | 0 0 | 15641 9 | 0 0 | 0 0 |
| 176 | 7 3 | 71558 4 | 0 0 | 0 0 | 0 0 | 0 0 | 14313 7 | 0 0 | 0 0 |
| 177 | 7 3 | 64964 9 | 0 0 | 0 0 | 0 0 | 0 0 | 12993 0 | 0 0 | 0 0 |
| 178 | 7 2 | 58398 2 | 0 0 | 0 0 | 0 0 | 0 0 | 11679 6 | 0 0 | 0 0 |
| 179 | 7 2 | 51874 8 | 0 0 | 0 0 | 0 0 | 0 0 | 10375 0 | 0 0 | 0 0 |
| 180 | 7 1 | 45396 1 | 0 0 | 0 0 | 0 0 | 0 0 | 9079 2 | 0 0 | 0 0 |
| 181 | 7 0 | 38968 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7793 8 | 0 0 | 0 0 |
| 182 | 7 0 | 32592 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6518 4 | 0 0 | 0 0 |
| 183 | 5 4 | 21141 6 | 0 0 | 0 0 | 0 0 | 0 0 | 4228 3 | 0 0 | 0 0 |
| 184 | 1 5 | 5131 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1026 3 | 0 0 | 0 0 |
| 185 | 6 8 | 20013 2 | 0 0 | 0 0 | 0 0 | 0 0 | 4002 6 | 0 0 | 0 0 |
| 186 | 1 1 | 2563 3 | 0 0 | 0 0 | 0 0 | 0 0 | 512 7 | 0 0 | 0 0 |
| 187 | 5 7 | 11253 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2250 8 | 0 0 | 0 0 |
| 188 | 3 4 | 4687 9 | 0 0 | 0 0 | 0 0 | 0 0 | 937 6 | 0 0 | 0 0 |
| 189 | 3 3 | 3043 1 | 0 0 | 0 0 | 0 0 | 0 0 | 608 6 | 0 0 | 0 0 |
| 190 | 5 7 | 2053 1 | 0 0 | 0 0 | 0 0 | 0 0 | 410 6 | 0 0 | 0 0 |

Failure Surface Specified By192 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 480 00 | 616 70 |
| 2 | 487 72 | 510 34 |
| 3 | 496 49 | 604 04 |
| 4 | 503 30 | 597 80 |
| 5 | 511 16 | 591 62 |
| 6 | 519 07 | 585 50 |
| 7 | 527 02 | 579 44 |
| 8 | 535 02 | 573 44 |
| 9 | 543 07 | 567 51 |
| 10 | 561 16 | 561 63 |
| 11 | 559 30 | 555 81 |
| 12 | 567 48 | 550 06 |
| 13 | 575 70 | 544 37 |
| 14 | 583 97 | 638 74 |
| 15 | 692 27 | 533 18 |
| 16 | 600 62 | 627 68 |
| 17 | 609 02 | 622 24 |
| 18 | 617 45 | 516 87 |
| 19 | 625 92 | 511 55 |
| 20 | 634 44 | 506 31 |
| 21 | 642 99 | 501 13 |
| 22 | 651 59 | 496 02 |
| 23 | 660 22 | 490 97 |
| 24 | 658 89 | 485 99 |
| 25 | 677 60 | 481 07 |
| 26 | 686 34 | 476 22 |
| 27 | 695 12 | 471 43 |
| 28 | 703 94 | 466 72 |
| 29 | 712 79 | 462 07 |
| 30 | 721 68 | 457 48 |
| 31 | 730 60 | 452 97 |
| 32 | 739 56 | 448 52 |
| 33 | 748 55 | 444 15 |

6/6/30

| | | |
|-----|---------|--------|
| 34 | 757 58 | 439 84 |
| 35 | 766 63 | 435 60 |
| 36 | 775 72 | 431 42 |
| 37 | 784 84 | 427 32 |
| 38 | 793 99 | 423 29 |
| 39 | 803 17 | 419 32 |
| 40 | 812 38 | 415 43 |
| 41 | 821 62 | 411 61 |
| 42 | 830 89 | 407 86 |
| 43 | 840 19 | 404 17 |
| 44 | 849 51 | 400 55 |
| 45 | 858 87 | 397 02 |
| 46 | 858 25 | 393 55 |
| 47 | 877 65 | 390 16 |
| 48 | 887 08 | 386 83 |
| 49 | 896 54 | 383 58 |
| 50 | 906 02 | 380 40 |
| 51 | 915 52 | 377 29 |
| 52 | 925 06 | 374 25 |
| 53 | 934 60 | 371 28 |
| 54 | 944 17 | 368 39 |
| 55 | 953 77 | 365 57 |
| 56 | 963 38 | 362 83 |
| 57 | 973 02 | 350 16 |
| 58 | 982 68 | 357 56 |
| 59 | 992 35 | 355 03 |
| 60 | 1002 05 | 352 58 |
| 61 | 1011 76 | 350 20 |
| 62 | 1021 49 | 347 90 |
| 63 | 1031 24 | 345 67 |
| 64 | 1041 00 | 343 51 |
| 65 | 1050 78 | 341 43 |
| 66 | 1060 58 | 339 42 |
| 67 | 1070 39 | 337 49 |
| 68 | 1080 22 | 335 63 |
| 69 | 1090 06 | 333 85 |
| 70 | 1099 91 | 332 14 |
| 71 | 1109 78 | 330 51 |
| 72 | 1119 66 | 328 95 |
| 73 | 1129 55 | 327 47 |
| 74 | 1139 45 | 326 06 |
| 75 | 1149 36 | 324 73 |
| 76 | 1159 28 | 323 48 |
| 77 | 1169 21 | 322 30 |
| 78 | 1179 16 | 321 19 |
| 79 | 1189 09 | 320 16 |
| 80 | 1199 05 | 319 21 |
| 81 | 1209 01 | 318 33 |
| 82 | 1218 98 | 317 53 |
| 83 | 1228 95 | 316 80 |
| 84 | 1238 93 | 316 15 |
| 85 | 1248 91 | 315 58 |
| 86 | 1258 90 | 315 08 |
| 87 | 1268 89 | 314 66 |
| 88 | 1278 89 | 314 31 |
| 89 | 1288 88 | 314 04 |
| 90 | 1298 88 | 313 85 |
| 91 | 1308 88 | 313 73 |
| 92 | 1318 88 | 313 69 |
| 93 | 1328 88 | 313 72 |
| 94 | 1338 88 | 313 83 |
| 95 | 1348 88 | 314 02 |
| 96 | 1358 87 | 314 28 |
| 97 | 1368 87 | 314 62 |
| 98 | 1378 86 | 316 03 |
| 99 | 1388 85 | 315 52 |
| 100 | 1398 83 | 315 09 |
| 101 | 1408 81 | 316 73 |

| | | |
|-----|---------|--------|
| 102 | 1418 78 | 317 45 |
| 103 | 1428 75 | 318 24 |
| 104 | 1438 71 | 319 11 |
| 105 | 1448 67 | 320 06 |
| 106 | 1458 62 | 321 08 |
| 107 | 1458 56 | 322 18 |
| 108 | 1478 49 | 323 35 |
| 109 | 1488 41 | 324 60 |
| 110 | 1498 32 | 325 92 |
| 111 | 1508 22 | 327 32 |
| 112 | 1518 11 | 328 80 |
| 113 | 1527 99 | 330 35 |
| 114 | 1537 86 | 331 97 |
| 115 | 1547 72 | 333 67 |
| 116 | 1557 56 | 335 45 |
| 117 | 1567 38 | 337 30 |
| 118 | 1577 20 | 339 22 |
| 119 | 1586 99 | 341 22 |
| 120 | 1596 78 | 343 29 |
| 121 | 1606 54 | 345 44 |
| 122 | 1616 29 | 347 66 |
| 123 | 1626 03 | 349 96 |
| 124 | 1635 74 | 352 33 |
| 125 | 1645 44 | 354 77 |
| 126 | 1655 12 | 357 29 |
| 127 | 1654 77 | 359 88 |
| 128 | 1674 41 | 362 55 |
| 129 | 1684 03 | 365 29 |
| 130 | 1693 63 | 368 10 |
| 131 | 1703 20 | 370 98 |
| 132 | 1712 76 | 373 94 |
| 133 | 1722 29 | 376 97 |
| 134 | 1731 79 | 380 07 |
| 135 | 1741 28 | 383 24 |
| 135 | 1750 73 | 386 49 |
| 137 | 1760 17 | 389 81 |
| 138 | 1769 57 | 393 20 |
| 139 | 1778 96 | 396 66 |
| 140 | 1788 31 | 400 19 |
| 141 | 1797 54 | 403 80 |
| 142 | 1806 94 | 407 47 |
| 143 | 1816 21 | 411 22 |
| 144 | 1825 46 | 415 03 |
| 145 | 1834 67 | 418 92 |
| 146 | 1843 86 | 422 88 |
| 147 | 1853 01 | 426 90 |
| 148 | 1862 13 | 431 00 |
| 149 | 1871 22 | 435 16 |
| 150 | 1880 28 | 439 39 |
| 151 | 1889 31 | 443 70 |
| 152 | 1898 30 | 448 07 |
| 153 | 1907 26 | 452 51 |
| 154 | 1916 19 | 457 02 |
| 155 | 1925 08 | 461 59 |
| 156 | 1933 94 | 466 23 |
| 167 | 1942 76 | 470 94 |
| 158 | 1951 56 | 475 72 |
| 169 | 1960 29 | 480 56 |
| 160 | 1969 01 | 485 47 |
| 161 | 1977 68 | 490 45 |
| 162 | 1986 32 | 496 49 |
| 163 | 1994 91 | 500 60 |
| 164 | 2003 47 | 505 77 |
| 165 | 2011 99 | 511 01 |
| 166 | 2020 47 | 516 31 |
| 167 | 2028 90 | 521 68 |
| 168 | 2037 30 | 527 11 |
| 159 | 2045 66 | 532 61 |

68/130

| | | |
|-----|---------|--------|
| 170 | 2053 97 | 538 17 |
| 171 | 2062 24 | 543 79 |
| 172 | 2070 47 | 549 47 |
| 173 | 2078 65 | 555 22 |
| 174 | 2086 79 | 561 03 |
| 175 | 2094 89 | 566 90 |
| 176 | 2102 94 | 672 83 |
| 177 | 2110 94 | 578 82 |
| 178 | 2118 90 | 584 88 |
| 179 | 2126 82 | 590 99 |
| 180 | 2134 68 | 597 16 |
| 181 | 2142 50 | 603 40 |
| 182 | 2160 27 | 609 59 |
| 183 | 2158 00 | 616 04 |
| 184 | 2165 67 | 622 45 |
| 185 | 2173 30 | 628 92 |
| 186 | 2180 87 | 635 45 |
| 187 | 2188 40 | 542 03 |
| 188 | 2195 88 | 648 67 |
| 189 | 2203 30 | 655 37 |
| 190 | 2210 68 | 662 13 |
| 191 | 2218 00 | 668 94 |
| 192 | 2219 12 | 670 00 |

Circle Center At X = 1319 4 , Y = 1627 8 and Radius, 1314 1
*** 0 576 ***

Failure Surface Specified By183 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 516 25 | 617 14 |
| 2 | 523 44 | 610 20 |
| 3 | 530 69 | 603 31 |
| 4 | 538 00 | 596 49 |
| 5 | 546 38 | 589 73 |
| 6 | 552 81 | 583 04 |
| 7 | 560 30 | 675 42 |
| 8 | 567 85 | 569 86 |
| 9 | 575 46 | 563 37 |
| 10 | 583 12 | 566 94 |
| 11 | 590 84 | 550 59 |
| 12 | 598 62 | 544 30 |
| 13 | 606 45 | 538 08 |
| 14 | 614 34 | 531 93 |
| 15 | 622 28 | 525 86 |
| 16 | 630 27 | 519 85 |
| 17 | 638 32 | 513 91 |
| 18 | 646 42 | 508 05 |
| 19 | 654 57 | 502 25 |
| 20 | 662 77 | 496 53 |
| 21 | 671 02 | 490 88 |
| 22 | 679 32 | 485 31 |
| 23 | 687 67 | 479 81 |
| 24 | 696 07 | 474 38 |
| 25 | 704 52 | 469 03 |
| 26 | 713 01 | 463 75 |
| 27 | 721 66 | 458 55 |
| 28 | 730 14 | 453 42 |
| 29 | 738 77 | 448 37 |
| 30 | 747 46 | 443 40 |
| 31 | 756 17 | 438 50 |
| 32 | 764 93 | 433 68 |
| 33 | 773 73 | 428 94 |
| 34 | 782 58 | 424 28 |
| 35 | 791 47 | 419 69 |
| 36 | 800 39 | 415 18 |
| 37 | 809 36 | 410 75 |
| 38 | 818 35 | 406 41 |
| 39 | 827 41 | 402 14 |
| 40 | 836 49 | 397 96 |

| | | | | |
|-----|------|----|-----|----|
| 41 | 845 | 51 | 393 | 85 |
| 42 | 854 | 76 | 389 | 82 |
| 43 | 863 | 96 | 385 | 88 |
| 44 | 873 | 17 | 382 | 01 |
| 45 | 882 | 43 | 378 | 23 |
| 46 | 891 | 72 | 374 | 53 |
| 47 | 901 | 04 | 370 | 91 |
| 48 | 910 | 40 | 367 | 38 |
| 49 | 919 | 78 | 363 | 93 |
| 50 | 929 | 20 | 350 | 56 |
| 51 | 938 | 64 | 357 | 28 |
| 52 | 948 | 12 | 354 | 07 |
| 53 | 967 | 62 | 350 | 95 |
| 54 | 967 | 15 | 347 | 92 |
| 55 | 976 | 70 | 344 | 97 |
| 55 | 986 | 29 | 342 | 11 |
| 57 | 995 | 89 | 339 | 33 |
| 58 | 1005 | 52 | 336 | 64 |
| 59 | 1015 | 18 | 334 | 03 |
| 60 | 1024 | 85 | 331 | 51 |
| 61 | 1034 | 55 | 329 | 07 |
| 62 | 1044 | 27 | 326 | 72 |
| 63 | 1064 | 01 | 324 | 45 |
| 64 | 1063 | 77 | 322 | 27 |
| 65 | 1073 | 55 | 320 | 18 |
| 66 | 1083 | 34 | 318 | 17 |
| 67 | 1093 | 16 | 316 | 25 |
| 68 | 1102 | 99 | 314 | 42 |
| 69 | 1112 | 84 | 312 | 68 |
| 70 | 1122 | 70 | 311 | 02 |
| 71 | 1132 | 57 | 309 | 45 |
| 72 | 1142 | 46 | 307 | 97 |
| 73 | 1152 | 36 | 306 | 57 |
| 74 | 1162 | 28 | 305 | 26 |
| 75 | 1172 | 20 | 304 | 04 |
| 76 | 1182 | 14 | 302 | 91 |
| 77 | 1192 | 09 | 301 | 86 |
| 78 | 1202 | 04 | 300 | 91 |
| 79 | 1212 | 00 | 300 | 04 |
| 80 | 1221 | 97 | 299 | 26 |
| 81 | 1231 | 95 | 298 | 57 |
| 82 | 1241 | 93 | 297 | 97 |
| 83 | 1251 | 92 | 297 | 45 |
| 84 | 1261 | 91 | 297 | 02 |
| 85 | 1271 | 90 | 296 | 69 |
| 86 | 1281 | 90 | 296 | 44 |
| 87 | 1291 | 90 | 296 | 28 |
| 88 | 1301 | 90 | 296 | 20 |
| 89 | 1311 | 90 | 296 | 22 |
| 90 | 1321 | 90 | 295 | 32 |
| 91 | 1331 | 89 | 296 | 52 |
| 92 | 1341 | 89 | 296 | 80 |
| 93 | 1351 | 88 | 297 | 17 |
| 94 | 1361 | 87 | 297 | 62 |
| 95 | 1371 | 86 | 298 | 17 |
| 96 | 1381 | 84 | 298 | 81 |
| 97 | 1391 | 81 | 299 | 53 |
| 98 | 1401 | 78 | 300 | 34 |
| 99 | 1411 | 74 | 301 | 24 |
| 100 | 1421 | 69 | 302 | 23 |
| 101 | 1431 | 63 | 303 | 30 |
| 102 | 1441 | 56 | 304 | 47 |
| 103 | 1451 | 48 | 305 | 72 |
| 104 | 1461 | 39 | 307 | 06 |
| 105 | 1471 | 29 | 308 | 48 |
| 106 | 1481 | 18 | 310 | 00 |
| 107 | 1491 | 05 | 311 | 60 |
| 108 | 1600 | 90 | 313 | 29 |

70/120

| | | |
|-----|---------|--------|
| 109 | 1510 74 | 315 07 |
| 110 | 1520 57 | 316 93 |
| 111 | 1530 38 | 318 88 |
| 112 | 1540 17 | 320 92 |
| 113 | 1549 94 | 323 04 |
| 114 | 1559 69 | 325 25 |
| 115 | 1569 43 | 327 55 |
| 116 | 1579 14 | 329 93 |
| 117 | 1588 83 | 332 40 |
| 118 | 1598 50 | 334 95 |
| 119 | 1608 14 | 337 59 |
| 120 | 1517 76 | 340 31 |
| 121 | 1527 36 | 343 12 |
| 122 | 1635 93 | 346 02 |
| 123 | 1646 48 | 349 00 |
| 124 | 1656 00 | 352 06 |
| 125 | 1655 49 | 355 21 |
| 126 | 1674 95 | 358 44 |
| 127 | 1684 39 | 361 75 |
| 128 | 1693 79 | 365 15 |
| 129 | 1703 17 | 368 63 |
| 130 | 1712 51 | 372 20 |
| 131 | 1721 82 | 375 84 |
| 132 | 1731 10 | 379 57 |
| 133 | 1740 35 | 383 38 |
| 134 | 1749 56 | 387 28 |
| 135 | 1758 73 | 391 25 |
| 136 | 1767 88 | 395 30 |
| 137 | 1776 98 | 399 44 |
| 138 | 1785 05 | 403 66 |
| 139 | 1795 08 | 407 95 |
| 140 | 1804 07 | 412 33 |
| 141 | 1813 02 | 416 78 |
| 142 | 1821 94 | 421 32 |
| 143 | 1830 81 | 425 93 |
| 144 | 1839 54 | 430 62 |
| 145 | 1848 43 | 435 39 |
| 146 | 1857 18 | 440 24 |
| 147 | 1865 88 | 445 16 |
| 148 | 1874 54 | 450 17 |
| 149 | 1883 16 | 455 24 |
| 150 | 1891 72 | 450 40 |
| 151 | 1900 25 | 465 63 |
| 152 | 1908 72 | 470 93 |
| 153 | 1917 15 | 476 31 |
| 154 | 1925 54 | 481 75 |
| 155 | 1933 87 | 487 29 |
| 155 | 1942 15 | 492 89 |
| 157 | 1950 39 | 498 57 |
| 158 | 1958 57 | 504 31 |
| 159 | 1966 70 | 510 13 |
| 160 | 1974 78 | 516 02 |
| 161 | 1982 81 | 521 99 |
| 152 | 1990 79 | 528 02 |
| 163 | 1998 71 | 634 12 |
| 164 | 2006 58 | 540 30 |
| 165 | 2014 39 | 546 54 |
| 166 | 2022 16 | 552 85 |
| 167 | 2029 85 | 559 23 |
| 168 | 2037 49 | 565 68 |
| 169 | 2045 08 | 572 19 |
| 170 | 2052 60 | 578 77 |
| 171 | 2050 07 | 585 42 |
| 172 | 2057 49 | 592 14 |
| 173 | 2074 84 | 598 92 |
| 174 | 2082 13 | 605 76 |
| 175 | 2089 36 | 612 67 |
| 175 | 2096 53 | 619 64 |

71/130

177 2103 63 626 68
 178 2110 68 633 77
 179 2117 66 640 93
 180 2124 57 648 16
 181 2131 43 555 44
 182 2138 22 662 78
 183 2144 77 670 00
 Circle Center At X = 1305 1 , Y = 1426 1 and Radius, 1130 0
 *** 0 577 ***

Failure Surface Specified By187 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 504 17 | 617 00 |
| 2 | 511 82 | 610 57 |
| 3 | 519 53 | 604 20 |
| 4 | 527 29 | 597 89 |
| 5 | 535 10 | 591 64 |
| 6 | 542 95 | 685 45 |
| 7 | 550 86 | 579 33 |
| 8 | 558 82 | 573 27 |
| 9 | 566 82 | 567 27 |
| 10 | 574 87 | 561 34 |
| 11 | 582 96 | 566 47 |
| 12 | 591 10 | 549 66 |
| 13 | 599 29 | 643 92 |
| 14 | 607 52 | 538 24 |
| 15 | 615 80 | 532 63 |
| 16 | 624 12 | 527 08 |
| 17 | 632 49 | 521 60 |
| 18 | 640 90 | 516 19 |
| 19 | 649 35 | 510 84 |
| 20 | 657 84 | 505 56 |
| 21 | 665 37 | 500 35 |
| 22 | 674 95 | 495 21 |
| 23 | 683 56 | 490 13 |
| 24 | 592 22 | 485 12 |
| 25 | 700 91 | 480 18 |
| 26 | 709 65 | 475 31 |
| 27 | 718 42 | 470 51 |
| 28 | 727 23 | 465 78 |
| 29 | 736 07 | 461 11 |
| 30 | 744 96 | 456 52 |
| 31 | 753 88 | 452 00 |
| 32 | 762 83 | 447 55 |
| 33 | 771 82 | 443 17 |
| 34 | 780 84 | 438 86 |
| 35 | 789 90 | 434 62 |
| 35 | 798 99 | 430 45 |
| 37 | 808 12 | 426 36 |
| 38 | 817 27 | 422 34 |
| 39 | 826 46 | 418 39 |
| 40 | 835 68 | 414 51 |
| 41 | 844 93 | 410 71 |
| 42 | 854 20 | 406 98 |
| 43 | 863 51 | 403 32 |
| 44 | 872 85 | 399 74 |
| 45 | 882 21 | 396 23 |
| 46 | 891 60 | 392 79 |
| 47 | 901 02 | 389 43 |
| 48 | 910 47 | 386 16 |
| 49 | 919 94 | 382 94 |
| 50 | 929 43 | 379 80 |
| 51 | 938 95 | 376 74 |
| 62 | 948 50 | 373 75 |
| 53 | 958 06 | 370 84 |
| 64 | 967 65 | 368 01 |
| 55 | 977 26 | 365 25 |
| 56 | 985 90 | 362 57 |

| | | |
|-----|---------|--------|
| 67 | 996 55 | 359 96 |
| 58 | 1006 23 | 357 43 |
| 69 | 1015 92 | 354 98 |
| 60 | 1025 64 | 352 60 |
| 61 | 1035 37 | 360 30 |
| 62 | 1045 12 | 348 08 |
| 63 | 1054 88 | 345 94 |
| 64 | 1064 67 | 343 87 |
| 65 | 1074 47 | 341 88 |
| 56 | 1084 28 | 339 97 |
| 67 | 1094 11 | 338 13 |
| 68 | 1103 96 | 336 37 |
| 69 | 1113 82 | 334 59 |
| 70 | 1123 69 | 333 09 |
| 71 | 1133 57 | 331 57 |
| 72 | 1143 47 | 330 12 |
| 73 | 1153 37 | 328 76 |
| 74 | 1153 29 | 327 47 |
| 75 | 1173 21 | 326 26 |
| 76 | 1183 15 | 325 12 |
| 77 | 1193 09 | 324 07 |
| 78 | 1203 05 | 323 10 |
| 79 | 1213 01 | 322 20 |
| 80 | 1222 97 | 321 39 |
| 81 | 1232 95 | 320 65 |
| 82 | 1242 92 | 319 99 |
| 83 | 1252 91 | 319 41 |
| 84 | 1262 90 | 318 91 |
| 85 | 1272 89 | 318 48 |
| 86 | 1282 88 | 318 14 |
| 87 | 1292 88 | 317 88 |
| 88 | 1302 88 | 317 69 |
| 89 | 1312 87 | 317 59 |
| 90 | 1322 87 | 317 56 |
| 91 | 1332 87 | 317 61 |
| 92 | 1342 87 | 317 74 |
| 93 | 1352 87 | 317 95 |
| 94 | 1362 87 | 318 24 |
| 95 | 1372 86 | 318 61 |
| 96 | 1382 86 | 319 06 |
| 97 | 1392 84 | 319 58 |
| 98 | 1402 82 | 320 19 |
| 99 | 1412 79 | 320 87 |
| 100 | 1422 77 | 321 64 |
| 101 | 1432 73 | 322 48 |
| 102 | 1442 69 | 323 40 |
| 103 | 1452 64 | 324 40 |
| 104 | 1462 58 | 325 47 |
| 105 | 1472 51 | 326 63 |
| 106 | 1482 44 | 327 87 |
| 107 | 1492 35 | 329 18 |
| 108 | 1602 25 | 330 57 |
| 109 | 1612 14 | 332 04 |
| 110 | 1522 02 | 333 59 |
| 111 | 1531 89 | 336 22 |
| 112 | 1541 74 | 336 92 |
| 113 | 1551 58 | 338 70 |
| 114 | 1561 41 | 340 55 |
| 115 | 1671 22 | 342 50 |
| 116 | 1581 01 | 344 52 |
| 117 | 1590 79 | 346 61 |
| 118 | 1600 56 | 348 78 |
| 119 | 1610 30 | 351 02 |
| 120 | 1620 02 | 353 35 |
| 121 | 1629 73 | 355 75 |
| 122 | 1639 42 | 368 23 |
| 123 | 1649 09 | 360 78 |
| 124 | 1658 74 | 363 41 |

73/30

| | | | | |
|-----|------|----|-----|----|
| 125 | 1568 | 36 | 366 | 12 |
| 126 | 1677 | 97 | 368 | 90 |
| 127 | 1687 | 55 | 371 | 76 |
| 128 | 1697 | 11 | 374 | 69 |
| 129 | 1706 | 65 | 377 | 70 |
| 130 | 1716 | 16 | 380 | 79 |
| 131 | 1725 | 65 | 383 | 95 |
| 132 | 1735 | 11 | 387 | 18 |
| 133 | 1744 | 55 | 390 | 49 |
| 134 | 1753 | 96 | 393 | 87 |
| 135 | 1763 | 34 | 397 | 33 |
| 136 | 1772 | 69 | 400 | 87 |
| 137 | 1782 | 02 | 404 | 47 |
| 138 | 1791 | 32 | 408 | 15 |
| 139 | 1800 | 59 | 411 | 91 |
| 140 | 1809 | 83 | 415 | 73 |
| 141 | 1819 | 04 | 419 | 63 |
| 142 | 1828 | 21 | 423 | 60 |
| 143 | 1837 | 36 | 427 | 65 |
| 144 | 1846 | 47 | 431 | 76 |
| 145 | 1855 | 55 | 435 | 95 |
| 146 | 1854 | 60 | 440 | 21 |
| 147 | 1873 | 61 | 444 | 55 |
| 148 | 1882 | 59 | 448 | 95 |
| 149 | 1891 | 53 | 463 | 42 |
| 150 | 1900 | 44 | 457 | 97 |
| 151 | 1909 | 31 | 452 | 68 |
| 152 | 1918 | 15 | 467 | 27 |
| 153 | 1926 | 95 | 472 | 02 |
| 154 | 1935 | 71 | 476 | 85 |
| 155 | 1944 | 43 | 481 | 74 |
| 156 | 1953 | 11 | 486 | 70 |
| 157 | 1961 | 75 | 491 | 73 |
| 158 | 1970 | 35 | 496 | 83 |
| 159 | 1978 | 92 | 502 | 00 |
| 150 | 1987 | 44 | 507 | 23 |
| 161 | 1995 | 92 | 512 | 53 |
| 162 | 2004 | 35 | 517 | 90 |
| 163 | 2012 | 75 | 523 | 33 |
| 164 | 2021 | 10 | 528 | 83 |
| 165 | 2029 | 41 | 534 | 40 |
| 166 | 2037 | 67 | 540 | 03 |
| 157 | 2045 | 89 | 545 | 73 |
| 168 | 2054 | 06 | 551 | 49 |
| 159 | 2062 | 19 | 557 | 32 |
| 170 | 2070 | 27 | 563 | 21 |
| 171 | 2078 | 30 | 569 | 16 |
| 172 | 2086 | 29 | 575 | 18 |
| 173 | 2094 | 23 | 581 | 25 |
| 174 | 2102 | 12 | 587 | 41 |
| 175 | 2109 | 96 | 593 | 61 |
| 176 | 2117 | 75 | 599 | 88 |
| 177 | 2125 | 50 | 606 | 21 |
| 178 | 2133 | 19 | 612 | 60 |
| 179 | 2140 | 83 | 619 | 05 |
| 180 | 2148 | 42 | 626 | 56 |
| 181 | 2155 | 96 | 632 | 13 |
| 182 | 2163 | 45 | 638 | 76 |
| 183 | 2170 | 88 | 646 | 45 |
| 184 | 2178 | 26 | 652 | 19 |
| 185 | 2185 | 59 | 659 | 00 |
| 186 | 2192 | 86 | 655 | 86 |
| 187 | 2197 | 18 | 670 | 00 |

Circle Center At X = 1321 3 , Y = 1582 2 and Radius, 1264 6
*** 0 586 ***

Failure Surface Specified By 186 Coordinate Points
Point X-Surf Y-Surf
No (ft) (ft)

| | | |
|----|---------|--------|
| 1 | 540 42 | 617 44 |
| 2 | 547 95 | 610 85 |
| 3 | 555 54 | 604 35 |
| 4 | 563 18 | 597 89 |
| 5 | 570 87 | 591 50 |
| 6 | 578 61 | 585 18 |
| 7 | 586 41 | 578 91 |
| 8 | 694 26 | 572 71 |
| 9 | 602 15 | 566 58 |
| 10 | 610 09 | 560 50 |
| 11 | 618 09 | 554 50 |
| 12 | 626 13 | 548 55 |
| 13 | 534 22 | 542 68 |
| 14 | 642 35 | 536 87 |
| 15 | 650 55 | 531 13 |
| 16 | 558 78 | 525 45 |
| 17 | 667 06 | 519 84 |
| 18 | 676 39 | 514 30 |
| 19 | 683 76 | 508 83 |
| 20 | 692 17 | 503 43 |
| 21 | 700 63 | 498 09 |
| 22 | 709 13 | 492 83 |
| 23 | 717 67 | 487 63 |
| 24 | 726 26 | 482 50 |
| 25 | 734 89 | 477 45 |
| 26 | 743 55 | 472 46 |
| 27 | 752 26 | 467 55 |
| 28 | 761 01 | 462 70 |
| 29 | 769 80 | 457 93 |
| 30 | 778 63 | 453 23 |
| 31 | 787 49 | 448 60 |
| 32 | 796 39 | 444 05 |
| 33 | 805 33 | 439 66 |
| 34 | 814 31 | 435 15 |
| 35 | 823 32 | 430 82 |
| 36 | 832 36 | 426 55 |
| 37 | 841 44 | 422 36 |
| 38 | 850 56 | 418 25 |
| 39 | 859 71 | 414 21 |
| 40 | 868 89 | 410 24 |
| 41 | 878 10 | 405 35 |
| 42 | 887 34 | 402 54 |
| 43 | 895 62 | 398 80 |
| 44 | 905 92 | 395 14 |
| 45 | 915 26 | 391 55 |
| 46 | 924 52 | 388 04 |
| 47 | 934 01 | 384 50 |
| 48 | 943 43 | 381 24 |
| 49 | 952 88 | 377 96 |
| 50 | 962 35 | 374 76 |
| 51 | 971 85 | 371 63 |
| 52 | 981 37 | 368 58 |
| 53 | 990 92 | 365 61 |
| 54 | 1000 49 | 362 72 |
| 55 | 1010 09 | 359 90 |
| 56 | 1019 70 | 357 16 |
| 57 | 1029 34 | 354 51 |
| 58 | 1039 01 | 351 93 |
| 59 | 1048 59 | 349 43 |
| 60 | 1058 39 | 347 00 |
| 61 | 1068 11 | 344 66 |
| 62 | 1077 85 | 342 40 |
| 63 | 1087 61 | 340 21 |
| 64 | 1097 39 | 338 11 |
| 66 | 1107 18 | 336 09 |
| 66 | 1116 99 | 334 14 |
| 67 | 1126 82 | 332 28 |
| 68 | 1136 66 | 330 50 |

| | | |
|-----|---------|--------|
| 69 | 1145 51 | 328 79 |
| 70 | 1156 38 | 327 17 |
| 71 | 1166 26 | 325 63 |
| 72 | 1176 15 | 324 17 |
| 73 | 1186 05 | 322 78 |
| 74 | 1195 97 | 321 48 |
| 75 | 1205 89 | 320 26 |
| 76 | 1215 83 | 319 13 |
| 77 | 1225 77 | 318 07 |
| 78 | 1235 73 | 317 09 |
| 79 | 1245 69 | 316 20 |
| 80 | 1255 65 | 315 39 |
| 81 | 1265 63 | 314 65 |
| 82 | 1275 60 | 314 00 |
| 83 | 1285 59 | 313 43 |
| 84 | 1295 58 | 312 95 |
| 85 | 1305 57 | 312 54 |
| 86 | 1315 56 | 312 21 |
| 87 | 1325 56 | 311 97 |
| 88 | 1335 56 | 311 81 |
| 89 | 1345 56 | 311 73 |
| 90 | 1355 56 | 311 73 |
| 91 | 1365 56 | 311 81 |
| 92 | 1375 56 | 311 98 |
| 93 | 1385 55 | 312 22 |
| 94 | 1395 55 | 312 55 |
| 95 | 1405 54 | 312 96 |
| 96 | 1415 53 | 313 45 |
| 97 | 1425 51 | 314 02 |
| 98 | 1435 49 | 314 68 |
| 99 | 1445 46 | 315 41 |
| 100 | 1455 43 | 316 23 |
| 101 | 1465 39 | 317 13 |
| 102 | 1475 34 | 318 11 |
| 103 | 1485 28 | 319 17 |
| 104 | 1495 22 | 320 31 |
| 105 | 1505 14 | 321 53 |
| 106 | 1515 06 | 322 83 |
| 107 | 1524 96 | 324 22 |
| 108 | 1534 85 | 325 68 |
| 109 | 1544 73 | 327 22 |
| 110 | 1554 60 | 328 85 |
| 111 | 1564 45 | 330 55 |
| 112 | 1574 29 | 332 34 |
| 113 | 1584 12 | 334 21 |
| 114 | 1593 93 | 336 16 |
| 115 | 1603 72 | 338 18 |
| 116 | 1613 50 | 340 29 |
| 117 | 1623 25 | 342 48 |
| 118 | 1632 99 | 344 74 |
| 119 | 1642 71 | 347 09 |
| 120 | 1652 42 | 349 51 |
| 121 | 1662 10 | 352 02 |
| 122 | 1671 76 | 354 60 |
| 123 | 1681 40 | 357 26 |
| 124 | 1691 01 | 360 00 |
| 125 | 1700 61 | 362 82 |
| 126 | 1710 18 | 365 71 |
| 127 | 1719 73 | 368 69 |
| 128 | 1729 25 | 371 74 |
| 129 | 1738 75 | 374 87 |
| 130 | 1748 22 | 378 08 |
| 131 | 1757 67 | 381 36 |
| 132 | 1767 08 | 384 72 |
| 133 | 1776 47 | 388 16 |
| 134 | 1785 84 | 391 67 |
| 135 | 1795 17 | 395 26 |
| 136 | 1804 47 | 398 93 |

76/130

| | | |
|-----|---------|--------|
| 137 | 1813 75 | 402 57 |
| 138 | 1822 99 | 406 49 |
| 139 | 1832 20 | 410 38 |
| 140 | 1841 38 | 414 35 |
| 141 | 1850 53 | 418 39 |
| 142 | 1859 64 | 422 51 |
| 143 | 1868 72 | 425 70 |
| 144 | 1877 76 | 430 97 |
| 145 | 1886 77 | 435 31 |
| 145 | 1895 75 | 439 72 |
| 147 | 1904 68 | 444 20 |
| 148 | 1913 58 | 448 76 |
| 149 | 1922 45 | 463 39 |
| 150 | 1931 27 | 468 10 |
| 151 | 1940 06 | 462 87 |
| 152 | 1948 81 | 467 72 |
| 153 | 1957 51 | 472 64 |
| 154 | 1966 18 | 477 62 |
| 155 | 1974 81 | 482 68 |
| 156 | 1983 39 | 487 81 |
| 157 | 1991 93 | 493 01 |
| 158 | 2000 43 | 498 28 |
| 159 | 2008 89 | 503 62 |
| 160 | 2017 30 | 609 02 |
| 161 | 2025 67 | 514 50 |
| 152 | 2033 99 | 520 04 |
| 153 | 2042 27 | 525 65 |
| 164 | 2050 50 | 531 33 |
| 165 | 2058 69 | 537 07 |
| 155 | 2066 83 | 542 89 |
| 167 | 2074 92 | 548 76 |
| 168 | 2082 96 | 554 71 |
| 169 | 2090 95 | 550 72 |
| 170 | 2098 90 | 556 79 |
| 171 | 2106 79 | 572 93 |
| 172 | 2114 63 | 579 13 |
| 173 | 2122 43 | 585 40 |
| 174 | 2130 17 | 591 73 |
| 175 | 2137 86 | 598 12 |
| 176 | 2145 50 | 604 58 |
| 177 | 2153 08 | 611 09 |
| 178 | 2160 51 | 617 67 |
| 179 | 2168 09 | 624 31 |
| 180 | 2175 51 | 631 01 |
| 181 | 2182 88 | 637 77 |
| 182 | 2190 19 | 644 60 |
| 183 | 2197 45 | 551 48 |
| 184 | 2204 65 | 658 42 |
| 185 | 2211 79 | 665 41 |
| 185 | 2216 39 | 670 00 |

Circle Center At X = 1350 4 , Y = 1537 5 and Radius, 1225 8
*** 0 587 ***

Failure Surface Specified By 175 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 480 00 | 616 70 |
| 2 | 487 13 | 609 69 |
| 3 | 494 33 | 602 76 |
| 4 | 501 60 | 595 88 |
| 5 | 508 93 | 589 08 |
| 6 | 616 32 | 582 35 |
| 7 | 523 78 | 575 68 |
| 8 | 531 30 | 669 09 |
| 9 | 538 88 | 562 57 |
| 10 | 546 52 | 555 12 |
| 11 | 564 22 | 549 74 |
| 12 | 551 98 | 543 44 |
| 13 | 569 81 | 537 20 |

| | | |
|----|---------|--------|
| 14 | 577 68 | 531 05 |
| 15 | 585 62 | 524 96 |
| 16 | 593 62 | 518 95 |
| 17 | 601 67 | 513 02 |
| 18 | 609 77 | 507 17 |
| 19 | 617 93 | 501 39 |
| 20 | 626 15 | 495 69 |
| 21 | 634 42 | 490 06 |
| 22 | 642 74 | 484 52 |
| 23 | 651 11 | 479 05 |
| 24 | 659 54 | 473 66 |
| 25 | 668 01 | 468 35 |
| 26 | 676 54 | 463 13 |
| 27 | 685 11 | 457 98 |
| 28 | 693 73 | 452 91 |
| 29 | 702 40 | 447 93 |
| 30 | 711 11 | 443 02 |
| 31 | 719 88 | 438 20 |
| 32 | 728 68 | 433 46 |
| 33 | 737 53 | 428 81 |
| 34 | 746 43 | 424 24 |
| 35 | 755 36 | 419 75 |
| 35 | 764 34 | 415 35 |
| 37 | 773 36 | 411 03 |
| 38 | 782 42 | 406 80 |
| 39 | 791 52 | 402 65 |
| 40 | 800 56 | 398 59 |
| 41 | 809 84 | 394 62 |
| 42 | 819 05 | 390 73 |
| 43 | 828 30 | 386 93 |
| 44 | 837 58 | 383 21 |
| 45 | 846 90 | 379 59 |
| 46 | 856 26 | 376 05 |
| 47 | 865 64 | 372 60 |
| 48 | 875 06 | 369 24 |
| 49 | 884 51 | 365 97 |
| 50 | 893 99 | 362 78 |
| 51 | 903 50 | 359 69 |
| 52 | 913 04 | 356 69 |
| 53 | 922 60 | 363 78 |
| 54 | 932 20 | 350 95 |
| 55 | 941 82 | 348 22 |
| 56 | 951 46 | 345 58 |
| 57 | 951 13 | 343 03 |
| 58 | 970 82 | 340 57 |
| 59 | 980 54 | 338 20 |
| 60 | 990 28 | 335 93 |
| 61 | 1000 04 | 333 74 |
| 62 | 1009 81 | 331 65 |
| 63 | 1019 61 | 329 65 |
| 64 | 1029 43 | 327 74 |
| 65 | 1039 26 | 325 93 |
| 66 | 1049 11 | 324 21 |
| 67 | 1058 98 | 322 58 |
| 68 | 1068 86 | 321 04 |
| 69 | 1078 76 | 319 60 |
| 70 | 1088 57 | 318 25 |
| 71 | 1098 59 | 316 99 |
| 72 | 1108 52 | 315 83 |
| 73 | 1118 46 | 314 76 |
| 74 | 1128 41 | 313 79 |
| 75 | 1138 38 | 312 91 |
| 76 | 1148 34 | 312 12 |
| 77 | 1158 32 | 311 43 |
| 78 | 1168 30 | 310 83 |
| 79 | 1178 29 | 310 32 |
| 80 | 1188 28 | 309 91 |
| 81 | 1198 28 | 309 60 |

| | | | | |
|-----|------|----|-----|----|
| 82 | 1208 | 27 | 309 | 38 |
| 83 | 1218 | 27 | 309 | 25 |
| 84 | 1228 | 27 | 309 | 22 |
| 85 | 1238 | 27 | 309 | 28 |
| 86 | 1248 | 27 | 309 | 43 |
| 87 | 1258 | 27 | 309 | 68 |
| 88 | 1268 | 26 | 310 | 02 |
| 89 | 1278 | 25 | 310 | 46 |
| 90 | 1288 | 24 | 310 | 99 |
| 91 | 1298 | 22 | 311 | 62 |
| 92 | 1308 | 19 | 312 | 34 |
| 93 | 1318 | 16 | 313 | 16 |
| 94 | 1328 | 12 | 314 | 06 |
| 95 | 1338 | 07 | 315 | 07 |
| 96 | 1348 | 01 | 316 | 16 |
| 97 | 1357 | 94 | 317 | 35 |
| 98 | 1367 | 85 | 318 | 63 |
| 99 | 1377 | 76 | 320 | 01 |
| 100 | 1387 | 56 | 321 | 48 |
| 101 | 1397 | 63 | 323 | 04 |
| 102 | 1407 | 39 | 324 | 70 |
| 103 | 1417 | 24 | 326 | 45 |
| 104 | 1427 | 06 | 328 | 29 |
| 105 | 1436 | 88 | 330 | 22 |
| 106 | 1446 | 67 | 332 | 25 |
| 107 | 1456 | 44 | 334 | 37 |
| 108 | 1466 | 19 | 336 | 58 |
| 109 | 1475 | 92 | 338 | 88 |
| 110 | 1485 | 63 | 341 | 28 |
| 111 | 1495 | 32 | 343 | 76 |
| 112 | 1504 | 98 | 346 | 34 |
| 113 | 1514 | 62 | 349 | 01 |
| 114 | 1524 | 23 | 351 | 77 |
| 115 | 1533 | 82 | 354 | 62 |
| 116 | 1543 | 37 | 357 | 56 |
| 117 | 1552 | 90 | 360 | 59 |
| 118 | 1562 | 41 | 363 | 71 |
| 119 | 1571 | 88 | 366 | 92 |
| 120 | 1581 | 32 | 370 | 21 |
| 121 | 1590 | 73 | 373 | 60 |
| 122 | 1600 | 10 | 377 | 08 |
| 123 | 1609 | 45 | 380 | 64 |
| 124 | 1618 | 76 | 384 | 29 |
| 125 | 1628 | 03 | 388 | 03 |
| 126 | 1637 | 27 | 391 | 86 |
| 127 | 1646 | 47 | 396 | 77 |
| 128 | 1655 | 64 | 399 | 77 |
| 129 | 1664 | 76 | 403 | 86 |
| 130 | 1673 | 85 | 408 | 03 |
| 131 | 1682 | 90 | 412 | 28 |
| 132 | 1691 | 91 | 416 | 63 |
| 133 | 1700 | 88 | 421 | 05 |
| 134 | 1709 | 80 | 425 | 57 |
| 135 | 1718 | 68 | 430 | 16 |
| 136 | 1727 | 52 | 434 | 84 |
| 137 | 1735 | 31 | 439 | 60 |
| 138 | 1745 | 06 | 444 | 45 |
| 139 | 1753 | 76 | 449 | 38 |
| 140 | 1762 | 42 | 454 | 38 |
| 141 | 1771 | 03 | 459 | 47 |
| 142 | 1779 | 58 | 464 | 65 |
| 143 | 1788 | 09 | 469 | 90 |
| 144 | 1796 | 55 | 475 | 23 |
| 145 | 1804 | 95 | 480 | 64 |
| 146 | 1813 | 32 | 486 | 13 |
| 147 | 1821 | 63 | 491 | 70 |
| 148 | 1829 | 88 | 497 | 35 |
| 149 | 1838 | 08 | 503 | 07 |

79/130

| | | |
|-----|---------|--------|
| 150 | 1845 22 | 508 87 |
| 151 | 1864 31 | 514 75 |
| 152 | 1862 35 | 520 71 |
| 153 | 1870 33 | 526 74 |
| 154 | 1878 25 | 532 84 |
| 155 | 1886 11 | 539 02 |
| 156 | 1893 91 | 545 27 |
| 157 | 1901 66 | 551 60 |
| 168 | 1909 34 | 558 00 |
| 159 | 1916 97 | 564 47 |
| 160 | 1924 53 | 571 01 |
| 161 | 1932 03 | 577 62 |
| 162 | 1939 47 | 584 31 |
| 153 | 1945 84 | 691 06 |
| 164 | 1954 15 | 597 89 |
| 165 | 1961 40 | 604 78 |
| 166 | 1968 58 | 611 74 |
| 167 | 1975 69 | 618 76 |
| 168 | 1982 74 | 625 86 |
| 169 | 1989 72 | 633 02 |
| 170 | 1996 64 | 640 24 |
| 171 | 2003 48 | 647 53 |
| 172 | 2010 26 | 654 89 |
| 173 | 2016 96 | 662 31 |
| 174 | 2023 60 | 669 79 |
| 175 | 2023 78 | 670 00 |

Circle Center At X = 1226 8 , Y = 1369 9 and Radius, 1060 7
 *** 0 593 ***

Failure Surface Specified By 180 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 625 00 | 618 47 |
| 2 | 632 07 | 611 40 |
| 3 | 639 21 | 604 40 |
| 4 | 646 41 | 597 46 |
| 5 | 653 68 | 590 59 |
| 6 | 651 00 | 583 78 |
| 7 | 668 39 | 577 05 |
| 8 | 675 85 | 570 38 |
| 9 | 683 36 | 563 78 |
| 10 | 690 93 | 557 25 |
| 11 | 698 57 | 550 79 |
| 12 | 706 26 | 544 40 |
| 13 | 714 01 | 538 08 |
| 14 | 721 82 | 531 83 |
| 15 | 729 68 | 525 56 |
| 16 | 737 60 | 519 66 |
| 17 | 745 58 | 513 53 |
| 18 | 753 62 | 507 57 |
| 19 | 761 70 | 501 59 |
| 20 | 769 84 | 495 88 |
| 21 | 778 04 | 490 15 |
| 22 | 786 29 | 484 49 |
| 23 | 794 58 | 478 91 |
| 24 | 802 93 | 473 41 |
| 25 | 811 33 | 467 98 |
| 26 | 819 78 | 462 63 |
| 27 | 828 28 | 457 35 |
| 28 | 836 83 | 452 17 |
| 29 | 845 42 | 447 05 |
| 30 | 864 05 | 442 02 |
| 31 | 862 75 | 437 07 |
| 32 | 871 48 | 432 19 |
| 33 | 880 25 | 427 40 |
| 34 | 889 07 | 422 69 |
| 35 | 897 94 | 418 06 |
| 36 | 906 84 | 413 61 |
| 37 | 915 79 | 409 04 |

| | | |
|-----|---------|--------|
| 38 | 924 77 | 404 65 |
| 39 | 933 80 | 400 35 |
| 40 | 942 87 | 396 13 |
| 41 | 951 97 | 391 99 |
| 42 | 961 11 | 387 94 |
| 43 | 970 29 | 383 97 |
| 44 | 979 51 | 380 09 |
| 45 | 988 75 | 376 29 |
| 46 | 998 05 | 372 68 |
| 47 | 1007 36 | 368 95 |
| 48 | 1016 72 | 365 41 |
| 49 | 1026 10 | 361 95 |
| 50 | 1035 52 | 358 59 |
| 51 | 1044 96 | 355 31 |
| 52 | 1054 44 | 352 11 |
| 53 | 1063 94 | 349 01 |
| 54 | 1073 48 | 345 99 |
| 55 | 1083 04 | 343 05 |
| 55 | 1092 62 | 340 21 |
| 57 | 1102 24 | 337 45 |
| 58 | 1111 87 | 334 79 |
| 59 | 1121 54 | 332 21 |
| 50 | 1131 22 | 329 72 |
| 61 | 1140 93 | 327 32 |
| 62 | 1150 66 | 325 01 |
| 63 | 1160 41 | 322 79 |
| 54 | 1170 18 | 320 66 |
| 65 | 1179 97 | 318 62 |
| 66 | 1189 78 | 316 67 |
| 57 | 1199 60 | 314 80 |
| 68 | 1209 44 | 313 03 |
| 69 | 1219 30 | 311 35 |
| 70 | 1229 18 | 309 77 |
| 71 | 1239 05 | 308 27 |
| 72 | 1248 96 | 306 86 |
| 73 | 1258 88 | 305 55 |
| 74 | 1268 80 | 304 32 |
| 75 | 1278 74 | 303 19 |
| 76 | 1288 68 | 302 15 |
| 77 | 1298 64 | 301 20 |
| 78 | 1308 60 | 300 34 |
| 79 | 1318 57 | 299 57 |
| 80 | 1328 55 | 298 90 |
| 81 | 1338 53 | 298 31 |
| 82 | 1348 52 | 297 82 |
| 83 | 1358 51 | 297 42 |
| 84 | 1368 51 | 297 11 |
| 85 | 1378 50 | 296 90 |
| 86 | 1388 50 | 296 77 |
| 87 | 1398 60 | 296 74 |
| 88 | 1408 50 | 296 80 |
| 89 | 1418 50 | 296 96 |
| 90 | 1428 50 | 297 20 |
| 91 | 1438 49 | 297 54 |
| 92 | 1448 48 | 297 95 |
| 93 | 1458 47 | 298 49 |
| 94 | 1468 46 | 299 10 |
| 95 | 1478 43 | 299 80 |
| 96 | 1488 39 | 300 60 |
| 97 | 1498 36 | 301 48 |
| 98 | 1508 31 | 302 46 |
| 99 | 1518 25 | 303 53 |
| 100 | 1528 18 | 304 70 |
| 101 | 1638 10 | 305 95 |
| 102 | 1548 01 | 307 29 |
| 103 | 1557 91 | 308 73 |
| 104 | 1567 79 | 310 25 |
| 105 | 1577 66 | 311 87 |

81/130

| | | |
|-----|---------|--------|
| 106 | 1587 51 | 313 68 |
| 107 | 1597 35 | 315 38 |
| 108 | 1607 17 | 317 27 |
| 109 | 1615 97 | 319 25 |
| 110 | 1525 76 | 321 32 |
| 111 | 1636 52 | 323 48 |
| 112 | 1545 26 | 325 73 |
| 113 | 1655 99 | 328 06 |
| 114 | 1665 69 | 330 49 |
| 115 | 1675 36 | 333 01 |
| 116 | 1685 02 | 335 62 |
| 117 | 1694 65 | 338 31 |
| 118 | 1704 25 | 341 09 |
| 119 | 1713 83 | 343 96 |
| 120 | 1723 38 | 346 92 |
| 121 | 1732 91 | 349 97 |
| 122 | 1742 41 | 353 11 |
| 123 | 1751 87 | 356 33 |
| 124 | 1751 31 | 359 64 |
| 125 | 1770 71 | 363 03 |
| 126 | 1780 09 | 366 52 |
| 127 | 1789 43 | 370 08 |
| 128 | 1798 74 | 373 74 |
| 129 | 1808 01 | 377 48 |
| 130 | 1817 25 | 381 30 |
| 131 | 1826 46 | 385 21 |
| 132 | 1835 62 | 389 21 |
| 133 | 1844 76 | 393 28 |
| 134 | 1853 85 | 397 45 |
| 135 | 1862 90 | 401 69 |
| 136 | 1871 92 | 406 02 |
| 137 | 1880 89 | 410 43 |
| 138 | 1889 82 | 414 92 |
| 139 | 1898 72 | 419 50 |
| 140 | 1907 57 | 424 16 |
| 141 | 1916 37 | 428 90 |
| 142 | 1925 13 | 433 72 |
| 143 | 1933 85 | 438 61 |
| 144 | 1942 52 | 443 59 |
| 145 | 1951 15 | 448 65 |
| 146 | 1959 73 | 453 79 |
| 147 | 1968 26 | 459 01 |
| 148 | 1976 74 | 464 31 |
| 149 | 1985 18 | 469 68 |
| 150 | 1993 56 | 475 13 |
| 151 | 2001 89 | 480 66 |
| 152 | 2010 18 | 486 26 |
| 153 | 2018 41 | 491 94 |
| 154 | 2026 58 | 497 70 |
| 155 | 2034 71 | 503 53 |
| 156 | 2042 78 | 509 43 |
| 157 | 2050 79 | 515 41 |
| 158 | 2058 75 | 521 46 |
| 159 | 2066 66 | 527 59 |
| 160 | 2074 51 | 533 79 |
| 161 | 2082 30 | 540 06 |
| 162 | 2090 03 | 546 40 |
| 163 | 2097 70 | 552 81 |
| 164 | 2105 32 | 559 29 |
| 166 | 2112 87 | 565 84 |
| 166 | 2120 36 | 572 47 |
| 167 | 2127 80 | 579 16 |
| 168 | 2135 17 | 595 91 |
| 169 | 2142 48 | 592 74 |
| 170 | 2149 72 | 599 53 |
| 171 | 2156 90 | 606 59 |
| 172 | 2164 02 | 613 62 |
| 173 | 2171 07 | 620 71 |

82/130

| | | |
|-----|---------|--------|
| 174 | 2178 06 | 627 85 |
| 175 | 2184 98 | 635 08 |
| 176 | 2191 83 | 542 36 |
| 177 | 2198 62 | 649 70 |
| 178 | 2205 34 | 657 11 |
| 179 | 2211 99 | 664 68 |
| 180 | 2216 73 | 670 00 |

Circle Center At X = 1396 9 , Y = 1383 6 and Radius, 1086 9

*** 0 598 ***

Failure Surface Specified By 172 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 628 33 | 617 29 |
| 2 | 535 45 | 610 26 |
| 3 | 542 63 | 603 30 |
| 4 | 649 87 | 596 41 |
| 5 | 567 19 | 589 59 |
| 6 | 564 56 | 582 84 |
| 7 | 572 01 | 576 16 |
| 8 | 579 51 | 569 55 |
| 9 | 587 08 | 663 02 |
| 10 | 594 71 | 556 56 |
| 11 | 602 41 | 550 17 |
| 12 | 610 16 | 543 85 |
| 13 | 617 97 | 537 61 |
| 14 | 625 85 | 531 45 |
| 16 | 633 78 | 525 36 |
| 16 | 641 77 | 519 35 |
| 17 | 649 82 | 613 41 |
| 18 | 657 92 | 507 55 |
| 19 | 656 08 | 501 77 |
| 20 | 674 30 | 496 07 |
| 21 | 682 57 | 490 45 |
| 22 | 690 89 | 484 91 |
| 23 | 699 27 | 479 44 |
| 24 | 707 70 | 474 06 |
| 26 | 716 18 | 468 76 |
| 25 | 724 70 | 453 54 |
| 27 | 733 28 | 458 40 |
| 28 | 741 91 | 463 35 |
| 29 | 750 59 | 448 38 |
| 30 | 759 31 | 443 49 |
| 31 | 768 08 | 438 68 |
| 32 | 776 90 | 433 96 |
| 33 | 785 76 | 429 33 |
| 34 | 794 57 | 424 78 |
| 35 | 803 51 | 420 31 |
| 36 | 812 60 | 415 94 |
| 37 | 821 64 | 411 64 |
| 38 | 830 71 | 407 44 |
| 39 | 839 82 | 403 32 |
| 40 | 848 97 | 399 29 |
| 41 | 868 16 | 396 35 |
| 42 | 867 39 | 391 50 |
| 43 | 876 66 | 387 73 |
| 44 | 886 96 | 384 06 |
| 45 | 895 29 | 380 47 |
| 46 | 904 66 | 376 97 |
| 47 | 914 06 | 373 57 |
| 48 | 923 50 | 370 25 |
| 49 | 932 95 | 367 02 |
| 50 | 942 46 | 363 89 |
| 51 | 961 98 | 350 85 |
| 52 | 961 64 | 367 89 |
| 53 | 971 12 | 355 03 |
| 54 | 980 73 | 352 27 |
| 55 | 990 36 | 349 69 |
| 66 | 1000 03 | 347 01 |

| | | |
|-----|---------|--------|
| 67 | 1009 71 | 344 52 |
| 58 | 1019 42 | 342 12 |
| 59 | 1029 15 | 339 82 |
| 60 | 1038 90 | 337 61 |
| 61 | 1048 68 | 335 49 |
| 62 | 1058 47 | 333 47 |
| 63 | 1068 28 | 331 54 |
| 64 | 1078 11 | 329 70 |
| 65 | 1087 96 | 327 96 |
| 66 | 1097 82 | 326 32 |
| 67 | 1107 70 | 324 77 |
| 68 | 1117 60 | 323 31 |
| 69 | 1127 50 | 321 95 |
| 70 | 1137 42 | 320 68 |
| 71 | 1147 35 | 319 51 |
| 72 | 1157 29 | 318 44 |
| 73 | 1167 25 | 317 46 |
| 74 | 1177 21 | 316 57 |
| 75 | 1187 18 | 315 78 |
| 76 | 1197 15 | 315 09 |
| 77 | 1207 13 | 314 49 |
| 78 | 1217 12 | 313 99 |
| 79 | 1227 11 | 313 59 |
| 80 | 1237 11 | 313 28 |
| 81 | 1247 11 | 313 06 |
| 82 | 1257 11 | 312 95 |
| 83 | 1267 11 | 312 92 |
| 84 | 1277 11 | 313 00 |
| 85 | 1287 10 | 313 17 |
| 86 | 1297 10 | 313 43 |
| 87 | 1307 09 | 313 80 |
| 88 | 1317 08 | 314 25 |
| 89 | 1327 07 | 314 81 |
| 90 | 1337 05 | 315 46 |
| 91 | 1347 02 | 316 20 |
| 92 | 1356 98 | 317 04 |
| 93 | 1366 94 | 317 98 |
| 94 | 1376 89 | 319 01 |
| 95 | 1386 82 | 320 14 |
| 96 | 1396 75 | 321 36 |
| 97 | 1406 66 | 322 68 |
| 98 | 1416 56 | 324 09 |
| 99 | 1426 45 | 325 60 |
| 100 | 1436 32 | 327 20 |
| 101 | 1445 17 | 328 90 |
| 102 | 1456 01 | 330 69 |
| 103 | 1466 83 | 332 57 |
| 104 | 1475 63 | 334 55 |
| 105 | 1485 42 | 336 63 |
| 106 | 1495 18 | 338 80 |
| 107 | 1504 92 | 341 06 |
| 108 | 1514 64 | 343 41 |
| 109 | 1524 33 | 345 86 |
| 110 | 1534 01 | 348 40 |
| 111 | 1543 65 | 351 03 |
| 112 | 1553 27 | 353 76 |
| 113 | 1562 87 | 356 58 |
| 114 | 1572 44 | 359 49 |
| 115 | 1581 97 | 362 49 |
| 116 | 1591 48 | 365 58 |
| 117 | 1600 96 | 368 77 |
| 118 | 1610 41 | 372 04 |
| 119 | 1619 83 | 375 41 |
| 120 | 1629 21 | 378 86 |
| 121 | 1638 56 | 382 41 |
| 122 | 1647 88 | 386 04 |
| 123 | 1657 16 | 389 77 |
| 124 | 1656 40 | 393 58 |

| | | |
|-----|---------|--------|
| 125 | 1575 61 | 397 48 |
| 126 | 1684 78 | 401 47 |
| 127 | 1593 91 | 405 55 |
| 128 | 1703 00 | 409 71 |
| 129 | 1712 05 | 413 97 |
| 130 | 1721 06 | 418 30 |
| 131 | 1730 03 | 422 73 |
| 132 | 1738 96 | 427 24 |
| 133 | 1747 84 | 431 84 |
| 134 | 1756 67 | 436 52 |
| 135 | 1765 47 | 441 28 |
| 136 | 1774 21 | 446 13 |
| 137 | 1782 91 | 451 07 |
| 138 | 1791 56 | 456 08 |
| 139 | 1800 16 | 461 18 |
| 140 | 1808 71 | 466 37 |
| 141 | 1817 22 | 471 63 |
| 142 | 1825 67 | 476 97 |
| 143 | 1834 07 | 482 40 |
| 144 | 1842 42 | 487 91 |
| 145 | 1850 71 | 493 49 |
| 145 | 1858 95 | 499 16 |
| 147 | 1867 14 | 504 90 |
| 148 | 1875 27 | 510 73 |
| 149 | 1883 34 | 516 63 |
| 150 | 1891 36 | 522 60 |
| 151 | 1899 32 | 528 66 |
| 152 | 1907 22 | 534 79 |
| 153 | 1915 06 | 540 99 |
| 154 | 1922 84 | 547 27 |
| 155 | 1930 56 | 553 63 |
| 156 | 1938 22 | 660 06 |
| 157 | 1945 82 | 556 56 |
| 158 | 1953 35 | 573 14 |
| 159 | 1960 82 | 579 78 |
| 160 | 1968 23 | 586 50 |
| 161 | 1975 57 | 593 29 |
| 162 | 1982 85 | 500 15 |
| 163 | 1990 06 | 607 08 |
| 154 | 1997 20 | 614 07 |
| 165 | 2004 28 | 621 14 |
| 166 | 2011 29 | 628 27 |
| 167 | 2018 23 | 636 47 |
| 168 | 2025 10 | 642 74 |
| 169 | 2031 90 | 650 07 |
| 170 | 2038 63 | 657 47 |
| 171 | 2045 29 | 664 93 |
| 172 | 2049 73 | 570 00 |

Circle Center At X = 1264 4 , Y = 1355 1 and Radius, 1042 2
 *** 0 604 ***

Failure Surface Specified By 177 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 625 00 | 618 47 |
| 2 | 632 12 | 611 46 |
| 3 | 639 31 | 604 50 |
| 4 | 646 57 | 597 62 |
| 5 | 653 88 | 590 80 |
| 6 | 661 26 | 584 05 |
| 7 | 668 70 | 577 37 |
| 8 | 676 21 | 570 76 |
| 9 | 683 77 | 554 22 |
| 10 | 691 39 | 567 75 |
| 11 | 699 08 | 551 36 |
| 12 | 706 82 | 545 02 |
| 13 | 714 62 | 538 77 |
| 14 | 722 48 | 532 58 |
| 15 | 730 40 | 626 47 |

| | | |
|----|---------|--------|
| 16 | 738 37 | 520 44 |
| 17 | 746 40 | 514 47 |
| 18 | 764 48 | 508 59 |
| 19 | 752 62 | 502 77 |
| 20 | 770 81 | 497 04 |
| 21 | 779 05 | 491 38 |
| 22 | 787 35 | 485 79 |
| 23 | 795 70 | 480 29 |
| 24 | 804 09 | 474 86 |
| 25 | 812 54 | 469 50 |
| 26 | 821 04 | 464 23 |
| 27 | 829 58 | 459 04 |
| 28 | 838 18 | 453 92 |
| 29 | 846 82 | 448 89 |
| 30 | 855 50 | 443 93 |
| 31 | 864 24 | 439 06 |
| 32 | 873 01 | 434 27 |
| 33 | 881 83 | 429 56 |
| 34 | 890 70 | 424 93 |
| 36 | 899 60 | 420 38 |
| 36 | 908 66 | 415 92 |
| 37 | 917 54 | 411 54 |
| 38 | 926 57 | 407 24 |
| 39 | 935 64 | 403 03 |
| 40 | 944 75 | 398 90 |
| 41 | 953 89 | 394 85 |
| 42 | 963 08 | 390 90 |
| 43 | 972 30 | 387 02 |
| 44 | 981 55 | 383 23 |
| 45 | 990 84 | 379 53 |
| 46 | 1000 15 | 375 91 |
| 47 | 1009 52 | 372 38 |
| 48 | 1018 91 | 368 94 |
| 49 | 1028 33 | 365 59 |
| 50 | 1037 78 | 362 32 |
| 51 | 1047 26 | 359 14 |
| 52 | 1056 77 | 366 05 |
| 53 | 1066 31 | 353 04 |
| 54 | 1075 87 | 350 13 |
| 55 | 1085 47 | 347 30 |
| 56 | 1095 08 | 344 55 |
| 57 | 1104 73 | 341 91 |
| 58 | 1114 39 | 339 35 |
| 59 | 1124 08 | 336 88 |
| 60 | 1133 80 | 334 51 |
| 61 | 1143 53 | 332 22 |
| 62 | 1153 29 | 330 02 |
| 63 | 1163 06 | 327 91 |
| 64 | 1172 86 | 325 89 |
| 65 | 1182 67 | 323 97 |
| 66 | 1192 50 | 322 13 |
| 67 | 1202 35 | 320 39 |
| 68 | 1212 21 | 318 73 |
| 69 | 1222 09 | 317 17 |
| 70 | 1231 98 | 315 70 |
| 71 | 1241 88 | 314 32 |
| 72 | 1251 80 | 313 04 |
| 73 | 1261 73 | 311 84 |
| 74 | 1271 67 | 310 74 |
| 75 | 1281 61 | 309 73 |
| 76 | 1291 57 | 308 81 |
| 77 | 1301 54 | 307 99 |
| 78 | 1311 51 | 307 25 |
| 79 | 1321 49 | 306 61 |
| 80 | 1331 48 | 306 06 |
| 81 | 1341 47 | 305 61 |
| 82 | 1351 45 | 305 25 |
| 83 | 1361 46 | 304 98 |

| | | |
|-----|---------|--------|
| 84 | 1371 45 | 304 80 |
| 85 | 1381 45 | 304 71 |
| 86 | 1391 45 | 304 72 |
| 87 | 1401 45 | 304 82 |
| 88 | 1411 45 | 306 01 |
| 89 | 1421 45 | 305 30 |
| 90 | 1431 44 | 305 68 |
| 91 | 1441 43 | 306 15 |
| 92 | 1451 41 | 306 71 |
| 93 | 1461 39 | 307 37 |
| 94 | 1471 36 | 308 12 |
| 95 | 1481 33 | 308 95 |
| 96 | 1491 28 | 309 89 |
| 97 | 1501 23 | 310 92 |
| 98 | 1511 17 | 312 04 |
| 99 | 1521 10 | 313 25 |
| 100 | 1531 01 | 314 55 |
| 101 | 1640 91 | 315 94 |
| 102 | 1550 80 | 317 43 |
| 103 | 1560 68 | 319 01 |
| 104 | 1570 54 | 320 67 |
| 105 | 1580 38 | 322 43 |
| 106 | 1590 21 | 324 28 |
| 107 | 1600 02 | 326 23 |
| 108 | 1609 81 | 328 26 |
| 109 | 1619 58 | 330 38 |
| 110 | 1629 33 | 332 60 |
| 111 | 1639 06 | 334 90 |
| 112 | 1648 77 | 337 30 |
| 113 | 1658 46 | 339 78 |
| 114 | 1668 12 | 342 35 |
| 115 | 1677 76 | 345 02 |
| 116 | 1687 37 | 347 77 |
| 117 | 1696 96 | 350 61 |
| 118 | 1706 52 | 353 54 |
| 119 | 1716 06 | 356 56 |
| 120 | 1725 56 | 359 67 |
| 121 | 1735 04 | 362 87 |
| 122 | 1744 48 | 366 15 |
| 123 | 1753 90 | 369 52 |
| 124 | 1763 28 | 372 98 |
| 125 | 1772 63 | 376 52 |
| 126 | 1781 95 | 380 15 |
| 127 | 1791 23 | 383 87 |
| 128 | 1800 48 | 387 67 |
| 129 | 1809 69 | 391 56 |
| 130 | 1818 87 | 395 53 |
| 131 | 1828 01 | 399 59 |
| 132 | 1837 11 | 403 74 |
| 133 | 1846 17 | 407 96 |
| 134 | 1855 20 | 412 27 |
| 135 | 1864 18 | 416 67 |
| 136 | 1873 12 | 421 15 |
| 137 | 1882 02 | 425 71 |
| 138 | 1890 88 | 430 35 |
| 139 | 1899 69 | 435 07 |
| 140 | 1908 46 | 439 88 |
| 141 | 1917 18 | 444 77 |
| 142 | 1925 85 | 449 74 |
| 143 | 1934 50 | 454 78 |
| 144 | 1943 08 | 459 91 |
| 145 | 1951 62 | 465 12 |
| 146 | 1960 11 | 470 40 |
| 147 | 1968 55 | 475 77 |
| 148 | 1976 93 | 481 21 |
| 149 | 1985 27 | 486 73 |
| 150 | 1993 56 | 492 33 |
| 151 | 2001 79 | 498 00 |

87/30

| | | |
|-----|---------|--------|
| 152 | 2009 98 | 503 75 |
| 153 | 2018 10 | 509 58 |
| 154 | 2026 18 | 515 48 |
| 155 | 2034 20 | 521 45 |
| 156 | 2042 16 | 527 50 |
| 157 | 2050 07 | 533 63 |
| 158 | 2057 91 | 539 82 |
| 159 | 2065 71 | 546 09 |
| 160 | 2073 44 | 552 43 |
| 161 | 2081 11 | 558 84 |
| 162 | 2088 73 | 566 32 |
| 153 | 2096 28 | 671 88 |
| 164 | 2103 77 | 578 50 |
| 165 | 2111 21 | 585 19 |
| 166 | 2118 57 | 691 95 |
| 167 | 2125 88 | 598 78 |
| 168 | 2133 12 | 605 68 |
| 159 | 2140 30 | 612 64 |
| 170 | 2147 41 | 619 67 |
| 171 | 2154 46 | 626 76 |
| 172 | 2161 44 | 633 92 |
| 173 | 2168 35 | 641 15 |
| 174 | 2175 20 | 648 43 |
| 175 | 2181 98 | 665 78 |
| 176 | 2188 70 | 663 20 |
| 177 | 2194 74 | 670 00 |

Circle Center At X = 1385 6 , Y = 1383 5 and Radius, 1078 8
 *** 0 506 ***

Failure Surface Specified By 178 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 625 00 | 618 47 |
| 2 | 632 19 | 611 52 |
| 3 | 639 44 | 604 64 |
| 4 | 646 76 | 597 82 |
| 5 | 654 14 | 591 07 |
| 6 | 661 57 | 584 39 |
| 7 | 669 07 | 577 77 |
| 8 | 676 63 | 571 22 |
| 9 | 684 25 | 564 75 |
| 10 | 691 93 | 558 34 |
| 11 | 699 67 | 562 00 |
| 12 | 707 45 | 545 74 |
| 13 | 715 31 | 539 64 |
| 14 | 723 22 | 533 42 |
| 15 | 731 18 | 527 37 |
| 15 | 739 20 | 521 39 |
| 17 | 747 27 | 515 49 |
| 18 | 755 39 | 509 66 |
| 19 | 763 57 | 503 90 |
| 20 | 771 80 | 498 22 |
| 21 | 780 08 | 492 62 |
| 22 | 788 41 | 487 09 |
| 23 | 796 80 | 481 64 |
| 24 | 805 23 | 476 26 |
| 25 | 813 71 | 470 96 |
| 26 | 822 24 | 465 74 |
| 27 | 830 81 | 450 60 |
| 28 | 839 44 | 465 53 |
| 29 | 848 10 | 450 55 |
| 30 | 856 82 | 445 54 |
| 31 | 865 58 | 440 81 |
| 32 | 874 38 | 436 07 |
| 33 | 883 22 | 431 40 |
| 34 | 892 11 | 426 82 |
| 35 | 901 04 | 422 31 |
| 36 | 910 01 | 417 89 |
| 37 | 919 02 | 413 55 |

| | | |
|-----|---------|--------|
| 38 | 928 06 | 409 29 |
| 39 | 937 15 | 405 12 |
| 40 | 946 28 | 401 03 |
| 41 | 955 44 | 397 02 |
| 42 | 964 64 | 393 10 |
| 43 | 973 87 | 389 26 |
| 44 | 983 14 | 385 50 |
| 45 | 992 44 | 381 83 |
| 46 | 1001 77 | 378 24 |
| 47 | 1011 14 | 374 74 |
| 48 | 1020 54 | 371 33 |
| 49 | 1029 97 | 368 00 |
| 50 | 1039 43 | 364 76 |
| 51 | 1048 92 | 361 60 |
| 52 | 1058 44 | 358 53 |
| 53 | 1067 98 | 355 55 |
| 54 | 1077 55 | 352 66 |
| 55 | 1087 15 | 349 85 |
| 56 | 1096 77 | 347 13 |
| 57 | 1106 42 | 344 50 |
| 58 | 1116 09 | 341 95 |
| 59 | 1125 79 | 339 50 |
| 60 | 1136 50 | 337 13 |
| 61 | 1145 24 | 334 86 |
| 62 | 1155 00 | 332 67 |
| 63 | 1164 77 | 330 57 |
| 64 | 1174 67 | 328 56 |
| 65 | 1184 38 | 326 64 |
| 66 | 1194 22 | 324 81 |
| 67 | 1204 05 | 323 07 |
| 68 | 1213 93 | 321 42 |
| 69 | 1223 80 | 319 85 |
| 70 | 1233 69 | 318 38 |
| 71 | 1243 60 | 317 00 |
| 72 | 1253 51 | 315 71 |
| 73 | 1263 44 | 314 52 |
| 74 | 1273 38 | 313 41 |
| 75 | 1283 33 | 312 39 |
| 76 | 1293 29 | 311 46 |
| 77 | 1303 25 | 310 63 |
| 78 | 1313 22 | 309 88 |
| 79 | 1323 20 | 309 23 |
| 80 | 1333 19 | 308 67 |
| 81 | 1343 17 | 308 19 |
| 82 | 1353 17 | 307 81 |
| 83 | 1363 16 | 307 63 |
| 84 | 1373 16 | 307 33 |
| 85 | 1383 16 | 307 22 |
| 85 | 1393 16 | 307 21 |
| 87 | 1403 16 | 307 28 |
| 88 | 1413 16 | 307 46 |
| 89 | 1423 16 | 307 71 |
| 90 | 1433 15 | 308 06 |
| 91 | 1443 14 | 308 50 |
| 92 | 1453 13 | 309 03 |
| 93 | 1463 11 | 309 66 |
| 94 | 1473 08 | 310 37 |
| 96 | 1483 05 | 311 18 |
| 96 | 1493 01 | 312 08 |
| 97 | 1502 96 | 313 06 |
| 98 | 1512 90 | 314 14 |
| 99 | 1522 83 | 315 31 |
| 100 | 1532 75 | 316 57 |
| 101 | 1542 66 | 317 92 |
| 102 | 1552 56 | 319 36 |
| 103 | 1562 44 | 320 89 |
| 104 | 1572 31 | 322 52 |
| 105 | 1682 16 | 324 23 |

89/130

| | | |
|-----|---------|--------|
| 106 | 1592 00 | 326 03 |
| 107 | 1601 81 | 327 92 |
| 108 | 1611 62 | 329 90 |
| 109 | 1621 40 | 331 97 |
| 110 | 1631 16 | 334 13 |
| 111 | 1640 91 | 336 38 |
| 112 | 1650 63 | 338 71 |
| 113 | 1660 33 | 341 14 |
| 114 | 1670 01 | 343 65 |
| 115 | 1679 67 | 346 26 |
| 116 | 1689 30 | 348 95 |
| 117 | 1698 90 | 351 73 |
| 118 | 1708 48 | 354 59 |
| 119 | 1718 04 | 357 55 |
| 120 | 1727 56 | 360 59 |
| 121 | 1737 06 | 363 71 |
| 122 | 1746 53 | 366 93 |
| 123 | 1755 97 | 370 23 |
| 124 | 1765 38 | 373 61 |
| 126 | 1774 76 | 377 09 |
| 126 | 1784 11 | 380 64 |
| 127 | 1793 42 | 384 29 |
| 128 | 1802 70 | 388 02 |
| 129 | 1811 94 | 391 83 |
| 130 | 1821 15 | 395 72 |
| 131 | 1830 33 | 399 70 |
| 132 | 1839 46 | 403 77 |
| 133 | 1848 55 | 407 92 |
| 134 | 1857 62 | 412 15 |
| 135 | 1866 65 | 416 46 |
| 136 | 1875 63 | 420 85 |
| 137 | 1884 57 | 425 33 |
| 138 | 1893 47 | 429 89 |
| 139 | 1902 33 | 434 53 |
| 140 | 1911 14 | 439 25 |
| 141 | 1919 92 | 444 05 |
| 142 | 1928 65 | 448 93 |
| 143 | 1937 33 | 453 89 |
| 144 | 1945 97 | 458 93 |
| 145 | 1954 56 | 464 05 |
| 146 | 1963 10 | 469 24 |
| 147 | 1971 60 | 474 51 |
| 148 | 1980 05 | 479 87 |
| 149 | 1988 45 | 485 29 |
| 150 | 1996 79 | 490 80 |
| 151 | 2005 09 | 496 38 |
| 152 | 2013 34 | 502 03 |
| 153 | 2021 53 | 507 76 |
| 154 | 2029 68 | 513 57 |
| 155 | 2037 77 | 519 45 |
| 156 | 2045 80 | 525 40 |
| 157 | 2053 78 | 531 43 |
| 158 | 2061 71 | 537 53 |
| 159 | 2069 57 | 543 70 |
| 160 | 2077 39 | 549 94 |
| 161 | 2085 14 | 556 25 |
| 162 | 2092 84 | 562 64 |
| 163 | 2100 48 | 569 09 |
| 164 | 2108 06 | 675 62 |
| 165 | 2115 57 | 582 21 |
| 166 | 2123 03 | 588 87 |
| 167 | 2130 43 | 595 60 |
| 168 | 2137 77 | 602 40 |
| 169 | 2145 04 | 609 26 |
| 170 | 2162 25 | 616 19 |
| 171 | 2159 40 | 623 18 |
| 172 | 2155 48 | 630 24 |
| 173 | 2173 50 | 637 35 |


90/130

| | | |
|-----|---------|--------|
| 174 | 2180 45 | 644 55 |
| 175 | 2187 34 | 651 80 |
| 176 | 2194 16 | 659 12 |
| 177 | 2200 91 | 666 49 |
| 178 | 2204 07 | 670 00 |

Circle Center At X = 1389 8 , Y = 1402 4 and Radius, 1095 2
*** 0 607 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\ir\4 pl2 Run By: Greg Shafer, HDR 4/20/2010 02:56PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|
| a | 2.49 | | | | | | | |
| b | 2.53 | | | | | | | |
| c | 2.54 | UVSC | 1 | 113.5 | 121.0 | 50.0 | 29.0 | W1 |
| d | 2.59 | LSC | 2 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| e | 2.60 | SC | 3 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| f | 2.61 | LVSC | 4 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| g | 2.63 | | | | | | | |
| h | 2.68 | | | | | | | |
| i | 2.74 | | | | | | | |
| i | 2.75 | | | | | | | |

✓ PMP 4-26-10

STED



PCSTABL7 FS_{min}=2.49
Safety Factors Are Calculated By The Modified Bishop Method

9/1/10

** PCSTABL7 **

by

Purdue University

--Slope Stability Analysis--

Simplified Janbu, Simplified Bishop

or Spencer s Method of Slices

Run Date 4/20/2010

Time of Run 02 56PM

Run By Greg Shafer, HDR

Input Data Filename C 4 in

Output Filename C 4 OUT

Unit ENGLISH

Plotted Output Filename C 4 PLT

PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified

Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries

6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 760 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |

93/130

| | | | | | |
|---|--------|--------|---------|--------|---|
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 6 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 6 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified
525 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced Along The Ground Surface Between X = 280 00 ft and X = 800 00 ft

Each Surface Terminates Between X = 850 00 ft and X = 2000 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 67 | 621 67 |
| 2 | 766 61 | 620 61 |
| 3 | 776 59 | 619 96 |
| 4 | 786 59 | 619 70 |
| 5 | 796 59 | 619 85 |
| 6 | 806 57 | 620 40 |
| 7 | 816 53 | 621 34 |
| 8 | 826 44 | 622 68 |
| 9 | 836 28 | 624 42 |
| 10 | 846 05 | 626 66 |
| 11 | 855 73 | 629 08 |
| 12 | 865 30 | 631 98 |
| 13 | 874 74 | 635 27 |
| 14 | 884 05 | 638 94 |
| 15 | 893 20 | 642 97 |
| 16 | 902 18 | 547 36 |
| 17 | 910 98 | 652 12 |
| 18 | 919 58 | 657 22 |
| 19 | 927 97 | 662 66 |
| 20 | 931 98 | 555 50 |

Circle Center At X = 788 0 , Y = 869 0 and Radius, 249 3
*** 2 493 ***

Individual data on the 25 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | Surcharge Load (lbs) |
| 1 | 9 9 | 1997 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 10 0 | 6792 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 10 0 | 9152 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 10 0 | 12052 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 10 0 | 14474 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 10 0 | 16405 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 9 9 | 17835 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 3 6 | 6697 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 6 3 | 12824 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 9 8 | 20250 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 9 7 | 20002 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

94/130

| | | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|-----|-----|-----|-----|
| 12 | 9 6 | 19247 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 4 7 | 9117 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 4 7 | 9244 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 9 3 | 17000 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 2 4 | 4124 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 6 7 | 10729 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 9 0 | 12309 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 4 9 | 5571 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 2 9 | 2960 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 1 0 | 977 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 22 | 8 5 | 6838 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 23 | 4 3 | 2149 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 24 | 4 1 | 1233 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 25 | 4 0 | 417 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 521 67 |
| 2 | 766 43 | 619 52 |
| 3 | 775 29 | 517 82 |
| 4 | 785 21 | 616 59 |
| 5 | 796 18 | 615 82 |
| 6 | 806 18 | 615 51 |
| 7 | 815 18 | 616 66 |
| 8 | 826 16 | 615 28 |
| 9 | 836 10 | 617 37 |
| 10 | 845 98 | 618 91 |
| 11 | 855 78 | 620 91 |
| 12 | 865 47 | 623 36 |
| 13 | 875 04 | 626 26 |
| 14 | 884 47 | 629 61 |
| 15 | 893 73 | 633 38 |
| 16 | 902 80 | 637 58 |
| 17 | 911 67 | 642 20 |
| 18 | 920 31 | 647 23 |
| 19 | 928 72 | 652 65 |
| 20 | 936 86 | 658 46 |
| 21 | 944 72 | 664 64 |
| 22 | 950 93 | 670 00 |

Circle Center At X = 807 8 Y = 830 6 and Radius, 215 1
*** 2 533 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 67 | 621 67 |
| 2 | 766 67 | 621 53 |
| 3 | 776 66 | 621 75 |
| 4 | 786 65 | 522 32 |
| 5 | 796 60 | 523 24 |
| 6 | 806 62 | 624 52 |
| 7 | 816 39 | 626 14 |
| 8 | 826 19 | 628 12 |
| 9 | 835 92 | 630 44 |
| 10 | 846 56 | 633 11 |
| 11 | 855 10 | 636 11 |
| 12 | 864 52 | 639 45 |
| 13 | 873 82 | 543 12 |
| 14 | 882 99 | 547 12 |
| 15 | 892 01 | 651 44 |
| 16 | 900 87 | 656 08 |
| 17 | 906 00 | 659 00 |

Circle Center At X = 765 5 , Y = 903 8 and Radius, 282 3
*** 2 536 ***

Failure Surface Specified By 15 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 621 67 |
| 2 | 765 67 | 621 88 |

75/130

| | | |
|----|--------|--------|
| 3 | 776 65 | 622 43 |
| 4 | 786 61 | 623 33 |
| 5 | 796 53 | 624 57 |
| 6 | 806 41 | 626 14 |
| 7 | 816 22 | 628 06 |
| 8 | 825 97 | 630 30 |
| 9 | 836 63 | 632 88 |
| 10 | 845 20 | 635 79 |
| 11 | 854 56 | 639 02 |
| 12 | 854 01 | 642 58 |
| 13 | 873 23 | 646 46 |
| 14 | 882 31 | 650 64 |
| 16 | 891 24 | 655 13 |
| 16 | 891 83 | 655 46 |

Circle Center At X = 755 5 , Y = 913 7 and Radius, 292 0
*** 2 591 ***

Failure Surface Specified By 14 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 778 33 | 527 08 |
| 2 | 788 33 | 626 88 |
| 3 | 798 33 | 627 15 |
| 4 | 808 30 | 627 90 |
| 5 | 818 23 | 629 11 |
| 6 | 828 09 | 630 78 |
| 7 | 837 85 | 632 92 |
| 8 | 847 51 | 635 52 |
| 9 | 857 04 | 638 57 |
| 10 | 866 41 | 642 06 |
| 11 | 875 60 | 645 99 |
| 12 | 884 60 | 650 35 |
| 13 | 893 38 | 655 13 |
| 14 | 895 39 | 656 35 |

Circle Center At X = 787 6 , Y = 838 6 and Radius, 211 8
*** 2 604 ***

Failure Surface Specified By 13 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 67 | 621 67 |
| 2 | 766 56 | 620 20 |
| 3 | 776 53 | 619 44 |
| 4 | 786 53 | 619 41 |
| 5 | 796 51 | 620 10 |
| 6 | 806 41 | 621 50 |
| 7 | 816 18 | 623 61 |
| 8 | 825 78 | 626 42 |
| 9 | 835 15 | 629 92 |
| 10 | 844 24 | 634 08 |
| 11 | 853 01 | 638 88 |
| 12 | 861 41 | 644 31 |
| 13 | 868 47 | 649 62 |

Circle Center At X = 782 0 , Y = 758 1 and Radius, 138 8
*** 2 609 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 800 00 | 532 50 |
| 2 | 809 68 | 630 00 |
| 3 | 819 51 | 628 15 |
| 4 | 829 44 | 626 96 |
| 5 | 839 43 | 626 42 |
| 6 | 849 42 | 626 55 |
| 7 | 859 39 | 627 33 |
| 8 | 869 29 | 628 77 |
| 9 | 879 07 | 630 87 |
| 10 | 888 69 | 633 60 |
| 11 | 898 10 | 636 97 |
| 12 | 907 28 | 640 95 |

9/6/30

| | | |
|----|--------|--------|
| 13 | 916 17 | 645 53 |
| 14 | 924 73 | 650 69 |
| 16 | 932 94 | 556 40 |
| 16 | 940 75 | 662 64 |
| 17 | 948 14 | 569 39 |
| 18 | 948 32 | 569 58 |

Circle Center At X = 842 6 , Y = 777 5 and Radius, 151 1
 *** 2 631 ***

Failure Surface Specified By 12 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 800 00 | 632 50 |
| 2 | 809 84 | 630 69 |
| 3 | 819 80 | 629 82 |
| 4 | 829 80 | 629 89 |
| 5 | 839 75 | 630 90 |
| 6 | 849 55 | 532 86 |
| 7 | 859 14 | 535 71 |
| 8 | 868 40 | 639 46 |
| 9 | 877 28 | 644 07 |
| 10 | 885 68 | 649 50 |
| 11 | 893 52 | 655 70 |
| 12 | 893 78 | 655 95 |

Circle Center At X = 824 1 , Y = 735 5 and Radius, 105 8
 *** 2 678 ***

Failure Surface Specified By 25 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 735 00 | 619 82 |
| 2 | 744 09 | 615 66 |
| 3 | 753 41 | 612 03 |
| 4 | 762 92 | 608 94 |
| 5 | 772 60 | 606 40 |
| 6 | 782 40 | 604 43 |
| 7 | 792 30 | 603 02 |
| 8 | 802 26 | 602 19 |
| 9 | 812 26 | 601 93 |
| 10 | 822 26 | 602 24 |
| 11 | 832 22 | 603 13 |
| 12 | 842 11 | 604 60 |
| 13 | 861 90 | 606 63 |
| 14 | 861 56 | 609 22 |
| 15 | 871 05 | 612 36 |
| 16 | 880 35 | 616 04 |
| 17 | 889 42 | 520 25 |
| 18 | 898 23 | 624 98 |
| 19 | 906 76 | 530 21 |
| 20 | 914 97 | 636 92 |
| 21 | 922 84 | 642 09 |
| 22 | 930 34 | 648 70 |
| 23 | 937 44 | 655 74 |
| 24 | 944 13 | 663 17 |
| 25 | 949 50 | 659 88 |

Circle Center At X = 811 8 , Y = 775 6 and Radius, 173 6
 *** 2 736 ***

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 713 33 | 619 55 |
| 2 | 722 97 | 616 87 |
| 3 | 732 72 | 614 66 |
| 4 | 742 57 | 612 95 |
| 5 | 752 50 | 611 72 |
| 6 | 762 47 | 610 99 |
| 7 | 772 47 | 610 76 |
| 8 | 782 46 | 611 02 |
| 9 | 792 44 | 611 78 |
| 10 | 802 36 | 613 04 |


97/130

| | | |
|----|--------|--------|
| 11 | 812 20 | 614 79 |
| 12 | 821 95 | 617 02 |
| 13 | 831 67 | 619 73 |
| 14 | 841 05 | 622 92 |
| 15 | 850 35 | 626 58 |
| 16 | 859 47 | 630 69 |
| 17 | 868 37 | 635 26 |
| 18 | 877 03 | 640 26 |
| 19 | 885 44 | 645 68 |
| 20 | 893 56 | 651 51 |
| 21 | 901 38 | 657 74 |
| 22 | 901 54 | 657 89 |

Circle Center At X = 772 2 , Y = 811 9 and Radius, 201 2
*** 2 749 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\l15 pl2 Run By Greg Shafer, HDR 4/20/2010 03:00PM



PCSTABL7 FSmin=1.75

Safety Factors Are Calculated By The Modified Bishop Method

STED



98/30

99/130

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 00PM
Run By Greg Shafer, HDR
Input Data Filename C 5 in
Output Filename C 5 OUT
Unit ENGLISH
Plotted Output Filename C 5 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
5 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 650 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 6 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of 0 100 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 500 00 ft
and X = 800 00 ft
Each Surface Terminates Between X = 850 00 ft
and X =1500 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial
Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 619 69 |
| 2 | 734 94 | 518 63 |
| 3 | 744 91 | 617 82 |
| 4 | 754 90 | 617 27 |
| 5 | 764 89 | 616 97 |
| 6 | 774 89 | 616 94 |
| 7 | 784 89 | 617 16 |
| 8 | 794 88 | 617 64 |

100/130

| | | |
|----|--------|--------|
| 9 | 804 85 | 618 37 |
| 10 | 814 80 | 619 37 |
| 11 | 824 72 | 620 62 |
| 12 | 834 61 | 622 12 |
| 13 | 844 45 | 623 88 |
| 14 | 854 25 | 625 89 |
| 15 | 863 99 | 628 16 |
| 16 | 873 67 | 630 67 |
| 17 | 883 28 | 633 44 |
| 18 | 892 81 | 636 45 |
| 19 | 902 27 | 639 70 |
| 20 | 911 54 | 643 20 |
| 21 | 920 91 | 646 94 |
| 22 | 930 09 | 650 92 |
| 23 | 939 16 | 655 13 |
| 24 | 948 11 | 659 58 |
| 25 | 956 95 | 564 26 |
| 26 | 965 67 | 669 15 |
| 27 | 957 10 | 670 00 |

Circle Center At X = 771 3 , Y = 1004 7 and Radius, 387 8
 *** 1 754 ***

Individual data on the 34 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 9 | 714 3 | 0 0 | 0 0 | 0 0 | 0 0 | 71 4 | 0 0 | 0 0 |
| 2 | 10 0 | 1993 6 | 0 0 | 0 0 | 0 0 | 0 0 | 199 4 | 0 0 | 0 0 |
| 3 | 5 1 | 1410 4 | 0 0 | 0 0 | 0 0 | 0 0 | 141 0 | 0 0 | 0 0 |
| 4 | 4 9 | 1783 2 | 0 0 | 0 0 | 0 0 | 0 0 | 178 3 | 0 0 | 0 0 |
| 5 | 10 0 | 6073 3 | 0 0 | 0 0 | 0 0 | 0 0 | 607 3 | 0 0 | 0 0 |
| 6 | 10 0 | 9100 5 | 0 0 | 0 0 | 0 0 | 0 0 | 910 1 | 0 0 | 0 0 |
| 7 | 10 0 | 11830 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1183 0 | 0 0 | 0 0 |
| 8 | 10 0 | 14254 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1425 4 | 0 0 | 0 0 |
| 9 | 10 0 | 16368 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1636 8 | 0 0 | 0 0 |
| 10 | 10 0 | 18167 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1816 7 | 0 0 | 0 0 |
| 11 | 9 9 | 19649 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1964 9 | 0 0 | 0 0 |
| 12 | 5 3 | 10975 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1097 6 | 0 0 | 0 0 |
| 13 | 4 6 | 10465 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1046 6 | 0 0 | 0 0 |
| 14 | 9 8 | 22909 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2290 9 | 0 0 | 0 0 |
| 15 | 9 8 | 23289 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2329 0 | 0 0 | 0 0 |
| 16 | 9 7 | 23337 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2333 8 | 0 0 | 0 0 |
| 17 | 6 0 | 14357 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1435 7 | 0 0 | 0 0 |
| 18 | 3 7 | 8975 2 | 0 0 | 0 0 | 0 0 | 0 0 | 897 5 | 0 0 | 0 0 |
| 19 | 9 6 | 23176 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2317 7 | 0 0 | 0 0 |
| 20 | 9 5 | 22256 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2225 6 | 0 0 | 0 0 |
| 21 | 9 5 | 21029 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2103 0 | 0 0 | 0 0 |
| 22 | 0 8 | 1704 4 | 0 0 | 0 0 | 0 0 | 0 0 | 170 4 | 0 0 | 0 0 |
| 23 | 6 9 | 14505 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1450 5 | 0 0 | 0 0 |
| 24 | 1 6 | 3423 1 | 0 0 | 0 0 | 0 0 | 0 0 | 342 3 | 0 0 | 0 0 |
| 26 | 9 3 | 18403 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1840 3 | 0 0 | 0 0 |
| 26 | 7 1 | 12733 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1273 3 | 0 0 | 0 0 |
| 27 | 2 1 | 3591 4 | 0 0 | 0 0 | 0 0 | 0 0 | 359 1 | 0 0 | 0 0 |
| 28 | 9 1 | 13990 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1399 1 | 0 0 | 0 0 |
| 29 | 9 0 | 11418 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1141 8 | 0 0 | 0 0 |
| 30 | 0 8 | 898 2 | 0 0 | 0 0 | 0 0 | 0 0 | 89 8 | 0 0 | 0 0 |
| 31 | 1 1 | 1178 0 | 0 0 | 0 0 | 0 0 | 0 0 | 117 8 | 0 0 | 0 0 |
| 32 | 7 0 | 5989 5 | 0 0 | 0 0 | 0 0 | 0 0 | 598 9 | 0 0 | 0 0 |
| 33 | 8 7 | 3265 2 | 0 0 | 0 0 | 0 0 | 0 0 | 326 5 | 0 0 | 0 0 |
| 34 | 1 4 | 68 7 | 0 0 | 0 0 | 0 0 | 0 0 | 6 9 | 0 0 | 0 0 |

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 42 | 521 87 |
| 3 | 782 39 | 621 08 |
| 4 | 792 38 | 620 74 |
| 5 | 802 38 | 520 85 |

101/130

| | | |
|----|--------|--------|
| 6 | 812 37 | 621 43 |
| 7 | 822 31 | 622 45 |
| 8 | 832 20 | 623 94 |
| 9 | 842 02 | 625 87 |
| 10 | 851 73 | 628 24 |
| 11 | 861 32 | 631 06 |
| 12 | 870 78 | 634 31 |
| 13 | 880 08 | 637 99 |
| 14 | 889 20 | 642 10 |
| 15 | 898 12 | 646 61 |
| 16 | 906 83 | 551 53 |
| 17 | 915 30 | 656 84 |
| 18 | 923 53 | 662 53 |
| 19 | 925 20 | 663 80 |

Circle Center At X = 794 8 , Y = 839 7 and Radius, 219 0
*** 1 762 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 769 73 | 517 68 |
| 3 | 769 58 | 615 95 |
| 4 | 779 51 | 614 82 |
| 5 | 789 50 | 614 28 |
| 6 | 799 50 | 614 35 |
| 7 | 809 48 | 615 01 |
| 8 | 819 40 | 616 27 |
| 9 | 829 22 | 618 13 |
| 10 | 838 92 | 620 57 |
| 11 | 848 45 | 623 59 |
| 12 | 857 79 | 627 17 |
| 13 | 866 89 | 631 31 |
| 14 | 875 73 | 635 99 |
| 15 | 884 27 | 641 19 |
| 16 | 892 48 | 646 90 |
| 17 | 900 34 | 653 08 |
| 18 | 907 38 | 659 34 |

Circle Center At X = 793 4 , Y = 780 7 and Radius, 166 5
*** 1 810 ***

Failure Surface Specified By 24 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 92 | 621 23 |
| 3 | 769 83 | 622 57 |
| 4 | 779 73 | 623 99 |
| 5 | 789 62 | 625 52 |
| 6 | 799 48 | 627 14 |
| 7 | 809 33 | 628 86 |
| 8 | 819 17 | 630 58 |
| 9 | 828 98 | 632 59 |
| 10 | 838 78 | 634 60 |
| 11 | 848 56 | 636 70 |
| 12 | 858 31 | 638 90 |
| 13 | 868 04 | 641 20 |
| 14 | 877 75 | 643 59 |
| 15 | 887 44 | 645 08 |
| 16 | 897 10 | 648 66 |
| 17 | 906 74 | 651 34 |
| 18 | 916 34 | 654 11 |
| 19 | 925 92 | 656 97 |
| 20 | 935 48 | 659 93 |
| 21 | 945 00 | 662 98 |
| 22 | 954 49 | 666 13 |
| 23 | 963 95 | 669 37 |
| 24 | 965 75 | 670 00 |

Circle Center At X = 629 3 , Y = 1631 4 and Radius, 1018 5
*** 1 818 ***

102/170

Failure Surface Specified By 16 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 42 | 618 58 |
| 3 | 767 39 | 617 84 |
| 4 | 767 39 | 617 63 |
| 6 | 777 39 | 617 95 |
| 6 | 787 35 | 618 81 |
| 7 | 797 25 | 620 19 |
| 8 | 807 07 | 622 10 |
| 9 | 815 77 | 624 52 |
| 10 | 826 33 | 627 45 |
| 11 | 835 72 | 630 89 |
| 12 | 844 92 | 634 82 |
| 13 | 853 89 | 639 24 |
| 14 | 862 62 | 644 12 |
| 15 | 871 07 | 649 46 |
| 16 | 872 83 | 650 71 |

Circle Center At X = 766 3 , Y = 805 6 and Radius, 188 0
*** 1 823 ***

Failure Surface Specified By 13 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 45 | 628 36 |
| 3 | 807 44 | 628 03 |
| 4 | 817 44 | 628 38 |
| 5 | 827 38 | 629 41 |
| 6 | 837 24 | 631 12 |
| 7 | 846 95 | 533 51 |
| 8 | 856 47 | 636 55 |
| 9 | 865 77 | 640 23 |
| 10 | 874 79 | 644 54 |
| 11 | 883 50 | 649 46 |
| 12 | 891 86 | 654 96 |
| 13 | 892 83 | 655 71 |

Circle Center At X = 807 3 , Y = 774 2 and Radius, 146 1
*** 1 833 ***

Failure Surface Specified By 25 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 50 | 622 98 |
| 3 | 782 50 | 623 02 |
| 4 | 792 50 | 623 25 |
| 5 | 802 49 | 623 67 |
| 6 | 812 47 | 624 28 |
| 7 | 822 44 | 525 07 |
| 8 | 832 39 | 626 06 |
| 9 | 842 32 | 627 22 |
| 10 | 852 23 | 628 58 |
| 11 | 862 11 | 630 12 |
| 12 | 871 95 | 631 85 |
| 13 | 881 77 | 633 75 |
| 14 | 891 55 | 636 85 |
| 16 | 901 29 | 638 13 |
| 16 | 910 98 | 540 59 |
| 17 | 920 63 | 643 24 |
| 18 | 930 22 | 646 06 |
| 19 | 939 76 | 649 07 |
| 20 | 949 24 | 552 25 |
| 21 | 958 66 | 655 61 |
| 22 | 968 01 | 659 15 |
| 23 | 977 30 | 662 86 |
| 24 | 986 51 | 566 74 |
| 25 | 993 84 | 670 00 |

Circle Center At X = 775 2 , Y = 1154 9 and Radius, 532 0

*** 1 850 ***
 Failure Surface Specified By 14 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 775 00 | 626 26 |
| 2 | 784 73 | 623 95 |
| 3 | 794 62 | 622 44 |
| 4 | 804 59 | 621 74 |
| 5 | 814 59 | 621 85 |
| 5 | 824 55 | 522 77 |
| 7 | 834 40 | 624 49 |
| 8 | 844 08 | 627 00 |
| 9 | 853 52 | 630 29 |
| 10 | 862 67 | 634 33 |
| 11 | 871 46 | 639 10 |
| 12 | 879 83 | 544 57 |
| 13 | 887 74 | 650 70 |
| 14 | 893 37 | 655 84 |

Circle Center At X = 808 2 , Y = 744 8 and Radius, 123 1

*** 1 851 ***
 Failure Surface Specified By 32 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 675 00 | 619 08 |
| 2 | 684 96 | 618 20 |
| 3 | 594 94 | 617 49 |
| 4 | 704 92 | 616 96 |
| 5 | 714 92 | 616 60 |
| 6 | 724 91 | 616 42 |
| 7 | 734 91 | 616 42 |
| 8 | 744 91 | 616 60 |
| 9 | 754 91 | 616 96 |
| 10 | 764 89 | 617 48 |
| 11 | 774 87 | 618 18 |
| 12 | 784 83 | 619 07 |
| 13 | 794 77 | 620 12 |
| 14 | 804 70 | 621 36 |
| 15 | 814 60 | 622 77 |
| 16 | 824 47 | 624 35 |
| 17 | 834 31 | 626 11 |
| 18 | 844 13 | 628 04 |
| 19 | 853 90 | 630 15 |
| 20 | 863 64 | 632 42 |
| 21 | 873 33 | 634 87 |
| 22 | 882 98 | 637 50 |
| 23 | 892 59 | 640 29 |
| 24 | 902 14 | 643 25 |
| 25 | 911 64 | 646 38 |
| 26 | 921 08 | 649 67 |
| 27 | 930 46 | 653 14 |
| 28 | 939 78 | 656 77 |
| 29 | 949 03 | 660 56 |
| 30 | 958 21 | 664 52 |
| 31 | 967 33 | 668 63 |
| 32 | 970 21 | 670 00 |

Circle Center At X = 730 0 , Y = 1181 4 and Radius, 565 0

*** 1 856 ***
 Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 523 13 |
| 2 | 771 98 | 619 93 |
| 3 | 781 62 | 617 30 |
| 4 | 791 41 | 615 22 |
| 5 | 801 29 | 613 72 |
| 6 | 811 25 | 612 80 |
| 7 | 821 24 | 612 46 |
| 8 | 831 24 | 612 69 |


102/130

| | | |
|----|--------|--------|
| 9 | 841 21 | 513 51 |
| 10 | 851 11 | 614 91 |
| 11 | 860 91 | 616 88 |
| 12 | 870 59 | 619 41 |
| 13 | 880 10 | 522 50 |
| 14 | 889 41 | 626 14 |
| 15 | 898 50 | 630 32 |
| 16 | 907 33 | 535 01 |
| 17 | 915 87 | 540 21 |
| 18 | 924 09 | 645 90 |
| 19 | 931 98 | 652 06 |
| 20 | 939 48 | 658 66 |
| 21 | 946 60 | 665 69 |
| 22 | 950 48 | 670 00 |

Circle Center At X = 822 1 , Y = 784 3 and Radius, 171 9
*** 1 858 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\l16 pl2 Run By Greg Shafer, HDR 4/20/2010 03 03PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez. Surface | Load | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|---------------|------|-------|
| a | 1.33 | | | | | | | | | |
| b | 1.33 | | | | | | | | | |
| c | 1.34 | UVSC | 1 | 113.5 | 121.0 | 50.0 | 29.0 | W1 | | |
| d | 1.34 | LSC | 2 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| e | 1.35 | SC | 3 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| f | 1.35 | LVSC | 4 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| g | 1.36 | | | | | | | | | |
| h | 1.36 | | | | | | | | | |
| i | 1.36 | | | | | | | | | |
| j | 1.38 | | | | | | | | | |

✓ Prop 4 26-10

STED



PCSTABL7 FSmin=1.33
Safety Factors Are Calculated By The Modified Bishop Method

04/20/10

106/130

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 03PM
Run By Greg Shafer, HDR
Input Data Filename C 6 in
Output Filename C 6 OUT
Unit ENGLISH
Plotted Output Filename C 5 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below End |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 60 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 570 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 660 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient

Of 0 200 Has Been Assigned

A Vertical Earthquake Loading Coefficient

Of 0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random

Technique For Generating Circular Surfaces, Has Been Specified

626 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced

Along The Ground Surface Between X = 500 00 ft

and X = 800 00 ft

Each Surface Terminates Between X = 850 00 ft

and X =1500 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation

At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 23 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 40 | 618 45 |
| 3 | 757 35 | 617 41 |
| 4 | 767 33 | 616 75 |
| 5 | 777 32 | 616 45 |
| 6 | 787 32 | 616 52 |
| 7 | 797 31 | 616 96 |
| 8 | 807 28 | 617 77 |

| | | |
|----|--------|--------|
| 9 | 817 21 | 618 95 |
| 10 | 827 09 | 620 49 |
| 11 | 836 91 | 622 40 |
| 12 | 846 65 | 624 67 |
| 13 | 856 29 | 527 30 |
| 14 | 865 84 | 630 28 |
| 15 | 875 27 | 633 61 |
| 16 | 884 57 | 637 28 |
| 17 | 893 73 | 641 30 |
| 18 | 902 73 | 645 66 |
| 19 | 911 56 | 650 34 |
| 20 | 920 22 | 655 34 |
| 21 | 928 59 | 660 67 |
| 22 | 936 95 | 666 30 |
| 23 | 937 86 | 666 96 |

Circle Center At X = 780 4 , Y = 887 2 and Radius, 270 8

*** 1 331 ***

Individual data on the 29 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 9 | 911 2 | 0 0 | 0 0 | 0 0 | 0 0 | 182 2 | 0 0 | 0 0 |
| 2 | 2 6 | 525 6 | 0 0 | 0 0 | 0 0 | 0 0 | 105 1 | 0 0 | 0 0 |
| 3 | 7 3 | 2605 1 | 0 0 | 0 0 | 0 0 | 0 0 | 521 0 | 0 0 | 0 0 |
| 4 | 10 0 | 6799 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1359 9 | 0 0 | 0 0 |
| 6 | 10 0 | 10190 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2038 1 | 0 0 | 0 0 |
| 6 | 10 0 | 13158 9 | 0 0 | 0 0 | 0 0 | 0 0 | 2631 8 | 0 0 | 0 0 |
| 7 | 10 0 | 15688 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3137 7 | 0 0 | 0 0 |
| 8 | 10 0 | 17766 5 | 0 0 | 0 0 | 0 0 | 0 0 | 3553 3 | 0 0 | 0 0 |
| 9 | 9 9 | 19384 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3876 9 | 0 0 | 0 0 |
| 10 | 9 9 | 20537 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4107 6 | 0 0 | 0 0 |
| 11 | 2 9 | 6229 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1246 0 | 0 0 | 0 0 |
| 12 | 6 9 | 15942 9 | 0 0 | 0 0 | 0 0 | 0 0 | 3188 6 | 0 0 | 0 0 |
| 13 | 9 7 | 22656 9 | 0 0 | 0 0 | 0 0 | 0 0 | 4531 4 | 0 0 | 0 0 |
| 14 | 9 6 | 22243 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4448 7 | 0 0 | 0 0 |
| 15 | 9 5 | 21366 5 | 0 0 | 0 0 | 0 0 | 0 0 | 4273 3 | 0 0 | 0 0 |
| 16 | 4 2 | 9000 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1800 2 | 0 0 | 0 0 |
| 17 | 5 3 | 11437 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2287 5 | 0 0 | 0 0 |
| 18 | 9 3 | 18993 9 | 0 0 | 0 0 | 0 0 | 0 0 | 3798 8 | 0 0 | 0 0 |
| 19 | 6 2 | 11607 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2321 5 | 0 0 | 0 0 |
| 20 | 3 0 | 5231 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1046 2 | 0 0 | 0 0 |
| 21 | 9 0 | 14314 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2862 9 | 0 0 | 0 0 |
| 22 | 7 3 | 9630 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1926 1 | 0 0 | 0 0 |
| 23 | 0 9 | 1160 9 | 0 0 | 0 0 | 0 0 | 0 0 | 232 2 | 0 0 | 0 0 |
| 24 | 0 6 | 781 3 | 0 0 | 0 0 | 0 0 | 0 0 | 156 3 | 0 0 | 0 0 |
| 25 | 8 7 | 8946 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1789 4 | 0 0 | 0 0 |
| 26 | 7 4 | 5013 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1002 8 | 0 0 | 0 0 |
| 27 | 1 1 | 505 5 | 0 0 | 0 0 | 0 0 | 0 0 | 101 1 | 0 0 | 0 0 |
| 28 | 8 3 | 2086 2 | 0 0 | 0 0 | 0 0 | 0 0 | 417 2 | 0 0 | 0 0 |
| 29 | 0 9 | 22 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4 5 | 0 0 | 0 0 |

Failure Surface Specified By 21 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 520 00 |
| 2 | 759 99 | 620 33 |
| 3 | 769 98 | 620 89 |
| 4 | 779 95 | 621 67 |
| 5 | 789 90 | 622 59 |
| 6 | 799 82 | 623 92 |
| 7 | 809 71 | 625 38 |
| 8 | 819 57 | 627 06 |
| 9 | 829 39 | 628 97 |
| 10 | 839 16 | 631 10 |
| 11 | 848 88 | 533 45 |
| 12 | 858 54 | 635 02 |
| 13 | 868 15 | 638 81 |
| 14 | 877 68 | 541 81 |

| | | |
|----|--------|--------|
| 15 | 887 15 | 645 03 |
| 16 | 896 54 | 648 47 |
| 17 | 905 85 | 552 11 |
| 18 | 915 08 | 655 97 |
| 19 | 924 22 | 660 03 |
| 20 | 933 26 | 664 30 |
| 21 | 939 31 | 667 33 |

Circle Center At X = 740 4 , Y = 1061 1 and Radius, 441 2
 *** 1 333 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 775 00 | 626 25 |
| 2 | 784 95 | 625 29 |
| 3 | 794 94 | 624 75 |
| 4 | 804 94 | 624 61 |
| 5 | 814 94 | 624 89 |
| 6 | 824 91 | 625 57 |
| 7 | 834 85 | 626 67 |
| 8 | 844 74 | 628 17 |
| 9 | 854 55 | 630 08 |
| 10 | 864 28 | 632 38 |
| 11 | 873 91 | 635 09 |
| 12 | 883 42 | 638 19 |
| 13 | 892 79 | 641 68 |
| 14 | 902 01 | 645 54 |
| 15 | 911 07 | 649 79 |
| 15 | 919 94 | 654 40 |
| 17 | 928 62 | 559 37 |
| 18 | 937 08 | 664 70 |
| 19 | 941 82 | 667 96 |

Circle Center At X = 803 2 , Y = 858 1 and Radius, 243 5
 *** 1 337 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 99 | 619 63 |
| 3 | 769 99 | 619 62 |
| 4 | 779 99 | 519 99 |
| 5 | 789 96 | 620 72 |
| 6 | 799 90 | 621 82 |
| 7 | 809 79 | 623 29 |
| 8 | 819 62 | 625 13 |
| 9 | 829 38 | 627 32 |
| 10 | 839 04 | 629 88 |
| 11 | 848 61 | 632 79 |
| 12 | 858 06 | 636 06 |
| 13 | 867 39 | 639 66 |
| 14 | 876 58 | 643 61 |
| 16 | 885 61 | 647 90 |
| 16 | 894 48 | 652 52 |
| 17 | 903 17 | 657 47 |
| 18 | 906 41 | 658 85 |

Circle Center At X = 765 1 , Y = 889 7 and Radius, 270 1
 *** 1 342 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 88 | 618 44 |
| 3 | 769 82 | 617 35 |
| 4 | 779 80 | 616 74 |
| 6 | 789 80 | 616 61 |
| 6 | 799 79 | 616 95 |
| 7 | 809 75 | 517 78 |
| 8 | 819 67 | 619 08 |
| 9 | 829 52 | 620 85 |

109/130

| | | |
|----|--------|--------|
| 10 | 839 26 | 623 09 |
| 11 | 848 89 | 625.79 |
| 12 | 858 38 | 628 95 |
| 13 | 867 70 | 632 56 |
| 14 | 876 85 | 636 61 |
| 15 | 885 79 | 641 10 |
| 16 | 894 50 | 646 00 |
| 17 | 902 97 | 651 32 |
| 18 | 911 18 | 657 03 |
| 19 | 917 45 | 661 86 |

Circle Center At X = 787 6 , Y = 825 8 and Radius, 209 2
*** 1 348 ***

Failure Surface Specified By 26 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 619 19 |
| 3 | 769 95 | 618 63 |
| 4 | 779 95 | 618 32 |
| 5 | 789 95 | 618 26 |
| 5 | 799 94 | 618 45 |
| 7 | 809 93 | 618 90 |
| 8 | 819 91 | 619 60 |
| 9 | 829 86 | 620 56 |
| 10 | 839 79 | 621 75 |
| 11 | 849 69 | 623 20 |
| 12 | 859 54 | 624 91 |
| 13 | 869 35 | 626 86 |
| 14 | 879 10 | 629 05 |
| 15 | 888 80 | 631 49 |
| 16 | 898 43 | 634 18 |
| 17 | 908 00 | 637 11 |
| 18 | 917 48 | 640 27 |
| 19 | 926 88 | 643 68 |
| 20 | 936 20 | 647 32 |
| 21 | 945 41 | 651 20 |
| 22 | 954 53 | 655 31 |
| 23 | 963 64 | 659 64 |
| 24 | 972 44 | 664 21 |
| 25 | 981 22 | 668 99 |
| 26 | 982 97 | 670 00 |

Circle Center At X = 787 2 , Y = 1014 3 and Radius, 396 1
*** 1 348 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 50 | 623 22 |
| 3 | 782 49 | 623 63 |
| 4 | 792 47 | 624 36 |
| 5 | 802 41 | 625 40 |
| 6 | 812 32 | 626 75 |
| 7 | 822 18 | 628 42 |
| 8 | 831 98 | 630 40 |
| 9 | 841 72 | 632 69 |
| 10 | 851 37 | 635 28 |
| 11 | 850 94 | 638 18 |
| 12 | 870 42 | 641 38 |
| 13 | 879 79 | 644 88 |
| 14 | 889 04 | 648 67 |
| 15 | 898 17 | 652 76 |
| 16 | 907 16 | 657 13 |
| 17 | 915 00 | 661 25 |

Circle Center At X = 764 5 , Y = 939 2 and Radius, 316 1
*** 1 356 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
|----------|-------------|-------------|

110/130

| | | |
|----|--------|--------|
| 1 | 800 00 | 632 50 |
| 2 | 809 99 | 532 02 |
| 3 | 819 99 | 631 87 |
| 4 | 829 99 | 632 03 |
| 5 | 839 97 | 632 51 |
| 6 | 849 94 | 633 32 |
| 7 | 859 88 | 634 44 |
| 8 | 869 78 | 635 88 |
| 9 | 879 62 | 637 63 |
| 10 | 889 40 | 639 70 |
| 11 | 899 12 | 642 09 |
| 12 | 908 75 | 644 78 |
| 13 | 918 29 | 647 78 |
| 14 | 927 73 | 651 08 |
| 15 | 937 05 | 654 68 |
| 16 | 945 26 | 658 58 |
| 17 | 955 34 | 662 77 |
| 18 | 964 28 | 667 26 |
| 19 | 959 35 | 670 00 |

Circle Center At X = 819 9 , Y = 944 2 and Radius, 312 3
*** 1 361 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 38 | 621 60 |
| 3 | 782 34 | 620 62 |
| 4 | 792 33 | 620 19 |
| 5 | 802 33 | 620 30 |
| 6 | 812 30 | 620 96 |
| 7 | 822 23 | 622 17 |
| 8 | 832 08 | 623 92 |
| 9 | 841 81 | 626 20 |
| 10 | 861 41 | 629 02 |
| 11 | 860 84 | 632 35 |
| 12 | 870 07 | 636 20 |
| 13 | 879 07 | 640 55 |
| 14 | 887 83 | 645 38 |
| 15 | 895 30 | 660 68 |
| 16 | 904 48 | 656 44 |
| 17 | 908 51 | 559 63 |

Circle Center At X = 795 2 , Y = 802 8 and Radius, 182 6
*** 1 361 ***


Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 800 00 | 632 50 |
| 2 | 809 98 | 633 11 |
| 3 | 819 95 | 633 91 |
| 4 | 829 90 | 634 90 |
| 5 | 839 83 | 636 09 |
| 6 | 849 73 | 637 47 |
| 7 | 859 61 | 639 05 |
| 8 | 859 45 | 640 81 |
| 9 | 879 26 | 642 77 |
| 10 | 889 03 | 644 92 |
| 11 | 898 75 | 647 25 |
| 12 | 908 42 | 649 78 |
| 13 | 918 05 | 652 49 |
| 14 | 927 62 | 656 39 |
| 16 | 937 13 | 658 47 |
| 16 | 946 58 | 661 74 |
| 17 | 955 97 | 665 19 |
| 18 | 965 29 | 668 83 |
| 19 | 968 13 | 670 00 |

Circle Center At X = 773 7 , Y = 1146 1 and Radius, 514 3
*** 1 381 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\17 pl2 Run By Greg Shafer HDR 4/20/2010 03:06PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|
| a | 1.06 | | | | | | | |
| b | 1.07 | | | | | | | |
| c | 1.07 | UVSC | 1 | 113.5 | 121.0 | 50.0 | 29.0 | W1 |
| d | 1.08 | LSC | 2 | 121.0 | 125.6 | 50.0 | 29.0 | W1 |
| e | 1.09 | SC | 3 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| f | 1.09 | LVSC | 4 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| g | 1.10 | | | | | | | |
| h | 1.10 | | | | | | | |
| i | 1.10 | | | | | | | |
| j | 1.12 | | | | | | | |

| Load | Value |
|----------|----------|
| Honz Eqk | 0.300 g< |

1.2 up 4.26.10

STED



PCSTABL7 FSmin=1.06
Safety Factors Are Calculated By The Modified Bishop Method

11/1/10

112/30

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 06PM
Run By Greg Shafer, HDR
Input Data Filename C 7 in
Output Filename C 7 OUT
Unit ENGLISH
Plotted Output Filename C 7 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

| 3 Top Boundaries | | 5 Total Boundaries | | | |
|------------------|-------------|--------------------|--------------|--------------|---------------------|
| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
| 1 | 60 00 | 611 45 | 760 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 540 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

| 4 Type(s) of Soil | | | | | | | | | |
|-------------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|--|--|
| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No | | |
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |
| 3 | 121 0 | 125 6 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |

A Horizontal Earthquake Loading Coefficient
Of0 300 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 500 00 ft
and X = 800 00 ft
Each Surface Terminates Between X = 850 00 ft
and X =1500 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial
Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 23 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 49 | 622 60 |
| 3 | 782 48 | 622 34 |
| 4 | 792 48 | 622 36 |
| 5 | 802 48 | 622 63 |
| 6 | 812 46 | 623 18 |
| 7 | 822 43 | 623 99 |
| 8 | 832 37 | 625 08 |

113/130

| | | |
|----|--------|--------|
| 9 | 842 28 | 626 42 |
| 10 | 852 15 | 628 04 |
| 11 | 861 97 | 529 92 |
| 12 | 871 74 | 632 06 |
| 13 | 881 45 | 634 46 |
| 14 | 891 09 | 637 12 |
| 15 | 900 65 | 640 04 |
| 16 | 910 13 | 643 21 |
| 17 | 919 63 | 646 64 |
| 18 | 928 83 | 650 32 |
| 19 | 938 02 | 654 25 |
| 20 | 947 11 | 658 42 |
| 21 | 956 08 | 662 84 |
| 22 | 964 93 | 667 49 |
| 23 | 969 41 | 670 00 |

Circle Center At X = 787 1 , Y = 995 0 and Radius, 372 6

*** 1 060 ***

Individual data on the 29 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 10 0 | 1712 8 | 0 0 | 0 0 | 0 0 | 0 0 | 513 8 | 0 0 | 0 0 |
| 2 | 10 0 | 4993 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1498 0 | 0 0 | 0 0 |
| 3 | 10 0 | 7972 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2391 6 | 0 0 | 0 0 |
| 4 | 10 0 | 10640 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3192 2 | 0 0 | 0 0 |
| 5 | 10 0 | 12991 2 | 0 0 | 0 0 | 0 0 | 0 0 | 3897 4 | 0 0 | 0 0 |
| 6 | 10 0 | 15018 3 | 0 0 | 0 0 | 0 0 | 0 0 | 4505 5 | 0 0 | 0 0 |
| 7 | 7 6 | 12584 2 | 0 0 | 0 0 | 0 0 | 0 0 | 3775 2 | 0 0 | 0 0 |
| 8 | 2 4 | 4401 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1320 4 | 0 0 | 0 0 |
| 9 | 9 9 | 19145 8 | 0 0 | 0 0 | 0 0 | 0 0 | 5743 7 | 0 0 | 0 0 |
| 10 | 9 9 | 20069 7 | 0 0 | 0 0 | 0 0 | 0 0 | 6020 9 | 0 0 | 0 0 |
| 11 | 9 8 | 20643 4 | 0 0 | 0 0 | 0 0 | 0 0 | 6193 0 | 0 0 | 0 0 |
| 12 | 8 0 | 17138 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5141 6 | 0 0 | 0 0 |
| 13 | 1 7 | 3861 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1158 5 | 0 0 | 0 0 |
| 14 | 9 7 | 21482 0 | 0 0 | 0 0 | 0 0 | 0 0 | 6444 6 | 0 0 | 0 0 |
| 15 | 9 6 | 21024 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6307 3 | 0 0 | 0 0 |
| 16 | 9 4 | 19969 9 | 0 0 | 0 0 | 0 0 | 0 0 | 6991 0 | 0 0 | 0 0 |
| 17 | 0 1 | 267 3 | 0 0 | 0 0 | 0 0 | 0 0 | 80 2 | 0 0 | 0 0 |
| 18 | 9 3 | 18868 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5660 4 | 0 0 | 0 0 |
| 19 | 0 1 | 272 1 | 0 0 | 0 0 | 0 0 | 0 0 | 81 6 | 0 0 | 0 0 |
| 20 | 9 4 | 18418 9 | 0 0 | 0 0 | 0 0 | 0 0 | 5525 7 | 0 0 | 0 0 |
| 21 | 8 5 | 15305 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4591 7 | 0 0 | 0 0 |
| 22 | 0 8 | 1393 7 | 0 0 | 0 0 | 0 0 | 0 0 | 418 1 | 0 0 | 0 0 |
| 23 | 9 2 | 14697 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4409 1 | 0 0 | 0 0 |
| 24 | 9 1 | 12427 3 | 0 0 | 0 0 | 0 0 | 0 0 | 3728 2 | 0 0 | 0 0 |
| 25 | 2 9 | 3464 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1039 3 | 0 0 | 0 0 |
| 26 | 0 3 | 363 4 | 0 0 | 0 0 | 0 0 | 0 0 | 109 0 | 0 0 | 0 0 |
| 27 | 5 8 | 5515 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1684 7 | 0 0 | 0 0 |
| 28 | 8 9 | 4857 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1457 4 | 0 0 | 0 0 |
| 29 | 4 5 | 637 1 | 0 0 | 0 0 | 0 0 | 0 0 | 191 1 | 0 0 | 0 0 |

Failure Surface Specified By 28 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 712 50 | 519 54 |
| 2 | 722 44 | 618 46 |
| 3 | 732 41 | 617 61 |
| 4 | 742 39 | 617 01 |
| 5 | 752 38 | 616 66 |
| 6 | 762 38 | 616 53 |
| 7 | 772 38 | 616 65 |
| 8 | 782 37 | 617 02 |
| 9 | 792 35 | 617 63 |
| 10 | 802 32 | 618 48 |
| 11 | 812 26 | 519 57 |
| 12 | 822 17 | 620 90 |
| 13 | 832 04 | 622 47 |
| 14 | 841 88 | 624 28 |

114/130

| | | |
|----|--------|--------|
| 15 | 851 67 | 626 33 |
| 16 | 861 40 | 628 61 |
| 17 | 871 08 | 631 13 |
| 18 | 880 69 | 633 89 |
| 19 | 890 24 | 535 87 |
| 20 | 899 71 | 640 09 |
| 21 | 909 09 | 643 53 |
| 22 | 918 40 | 647 20 |
| 23 | 927 61 | 651 10 |
| 24 | 936 72 | 655 22 |
| 25 | 945 73 | 659 55 |
| 26 | 954 63 | 554 11 |
| 27 | 963 42 | 668 88 |
| 28 | 965 38 | 670 00 |

Circle Center At X = 762 3 , Y = 1028 9 and Radius, 412 4
 *** 1 068 ***

Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 619 69 |
| 2 | 734 91 | 618 33 |
| 3 | 744 85 | 617 24 |
| 4 | 754 81 | 516 42 |
| 5 | 764 80 | 615 87 |
| 6 | 774 79 | 615 59 |
| 7 | 784 79 | 616 58 |
| 8 | 794 79 | 615 85 |
| 9 | 804 78 | 616 39 |
| 10 | 814 74 | 617 19 |
| 11 | 824 69 | 618 28 |
| 12 | 834 59 | 619 63 |
| 13 | 844 46 | 621 25 |
| 14 | 854 28 | 623 13 |
| 15 | 864 05 | 525 29 |
| 16 | 873 75 | 627 71 |
| 17 | 883 38 | 630 39 |
| 18 | 892 94 | 633 33 |
| 19 | 902 41 | 636 54 |
| 20 | 911 80 | 640 00 |
| 21 | 921 08 | 543 71 |
| 22 | 930 26 | 647 68 |
| 23 | 939 33 | 651 89 |
| 24 | 948 28 | 656 35 |
| 25 | 957 11 | 661 05 |
| 26 | 955 80 | 665 99 |
| 27 | 972 44 | 670 00 |

Circle Center At X = 780 0 , Y = 982 9 and Radius, 367 4
 *** 1 070 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 760 00 | 520 00 |
| 2 | 759 95 | 619 01 |
| 3 | 769 94 | 618 50 |
| 4 | 779 94 | 518 47 |
| 5 | 789 93 | 618 90 |
| 6 | 799 89 | 619 82 |
| 7 | 809 79 | 621 20 |
| 8 | 819 62 | 623 06 |
| 9 | 829 34 | 625 38 |
| 10 | 838 95 | 528 16 |
| 11 | 848 41 | 631 40 |
| 12 | 857 71 | 635 08 |
| 13 | 866 82 | 639 19 |
| 14 | 876 73 | 643 74 |
| 15 | 884 41 | 548 71 |
| 16 | 892 84 | 664 08 |
| 17 | 896 42 | 555 60 |

115/30

Circle Center At X = 775 7 , Y = 828 7 and Radius, 210 2
*** 1 083 ***

Failure Surface Specified By 21 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 620 76 |
| 3 | 769 93 | 621 70 |
| 4 | 779 86 | 622 82 |
| 5 | 789 78 | 624 13 |
| 6 | 799 67 | 625 61 |
| 7 | 809 53 | 627 28 |
| 8 | 819 36 | 629 12 |
| 9 | 829 15 | 631 15 |
| 10 | 838 90 | 633 35 |
| 11 | 848 61 | 635 74 |
| 12 | 858 28 | 638 30 |
| 13 | 867 90 | 641 03 |
| 14 | 877 47 | 643 94 |
| 15 | 886 98 | 647 03 |
| 16 | 896 43 | 650 29 |
| 17 | 905 83 | 653 72 |
| 18 | 915 15 | 657 32 |
| 19 | 924 42 | 661 10 |
| 20 | 933 61 | 665 04 |
| 21 | 937 91 | 666 98 |

Circle Center At X = 713 5 , Y = 1166 5 and Radius, 546 7
*** 1 088 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 81 | 618 06 |
| 3 | 769 70 | 616 60 |
| 4 | 779 66 | 615 64 |
| 5 | 789 65 | 515 18 |
| 6 | 799 65 | 615 22 |
| 7 | 809 63 | 615 75 |
| 8 | 819 58 | 516 78 |
| 9 | 829 45 | 518 31 |
| 10 | 839 26 | 620 32 |
| 11 | 848 94 | 622 82 |
| 12 | 858 49 | 625 80 |
| 13 | 857 87 | 629 25 |
| 14 | 877 08 | 633 15 |
| 15 | 886 07 | 637 63 |
| 16 | 894 84 | 642 33 |
| 17 | 903 36 | 647 57 |
| 18 | 911 60 | 663 23 |
| 19 | 919 56 | 659 29 |
| 20 | 924 78 | 653 70 |

Circle Center At X = 793 9 , Y = 815 7 and Radius, 200 6
*** 1 090 ***

Failure Surface Specified By 15 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 760 00 | 619 82 |
| 3 | 770 00 | 620 04 |
| 4 | 779 98 | 620 67 |
| 6 | 789 92 | 621 69 |
| 6 | 799 82 | 623 11 |
| 7 | 809 66 | 624 92 |
| 8 | 819 41 | 527 13 |
| 9 | 829 07 | 529 72 |
| 10 | 838 61 | 632 70 |
| 11 | 848 03 | 636 05 |
| 12 | 857 31 | 639 79 |

11/6/130

13 866 43 643 89
 14 875 38 648 36
 15 884 14 653 17
 16 885 17 653 79
 Circle Center At X = 759 5 , Y = 869 4 and Radius, 249 5
 *** 1 095 ***

Failure Surface Specified By 15 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 752 50 | 623 13 |
| 2 | 772 44 | 621 99 |
| 3 | 782 42 | 621 43 |
| 4 | 792 42 | 621 44 |
| 5 | 802 40 | 622 03 |
| 5 | 812 33 | 623 20 |
| 7 | 822 18 | 624 93 |
| 8 | 831 92 | 627 23 |
| 9 | 841 50 | 630 08 |
| 10 | 850 90 | 633 48 |
| 11 | 860 10 | 637 42 |
| 12 | 869 05 | 641 88 |
| 13 | 877 72 | 646 85 |
| 14 | 886 10 | 652 31 |
| 15 | 889 63 | 654 91 |

Circle Center At X = 787 2 , Y = 795 0 and Radius, 173 6
 *** 1 099 ***

Failure Surface Specified By 25 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 48 | 622 51 |
| 3 | 782 47 | 622 12 |
| 4 | 792 47 | 621 96 |
| 5 | 802 47 | 622 02 |
| 5 | 812 47 | 622 30 |
| 7 | 822 46 | 622 81 |
| 8 | 832 43 | 623 54 |
| 9 | 842 38 | 624 49 |
| 10 | 852 31 | 625 57 |
| 11 | 862 22 | 527 06 |
| 12 | 872 08 | 628 68 |
| 13 | 881 91 | 630 52 |
| 14 | 891 70 | 532 58 |
| 15 | 901 44 | 634 86 |
| 16 | 911 12 | 637 35 |
| 17 | 920 75 | 640 06 |
| 18 | 930 31 | 642 99 |
| 19 | 939 80 | 646 12 |
| 20 | 949 23 | 649 47 |
| 21 | 958 57 | 653 03 |
| 22 | 967 83 | 656 80 |
| 23 | 977 01 | 660 78 |
| 24 | 986 10 | 654 96 |
| 25 | 995 08 | 669 34 |
| 26 | 996 37 | 670 00 |

Circle Center At X = 794 8 , Y = 1068 6 and Radius, 446 7
 *** 1 099 ***

Failure Surface Specified By 14 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 750 00 | 619 92 |
| 3 | 769 99 | 620 29 |
| 4 | 779 96 | 621 10 |
| 5 | 789 88 | 622 36 |
| 6 | 799 74 | 624 06 |
| 7 | 809 51 | 625 19 |
| 8 | 819 17 | 628 76 |

| | | | |
|----|--------|--------|--|
| 9 | 828 71 | 531 76 | |
| 10 | 838 11 | 635 18 | |
| 11 | 847 34 | 639 01 | |
| 12 | 856 40 | 543 25 | |
| 13 | 865 25 | 647 90 | |
| 14 | 868 00 | 649 50 | |

Circle Center At X = 756 8 , Y = 843 5 and Radius, 223 6
*** 1 116 ***

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 08PM
Run By Greg Shafer, HDR
Input Data Filename C 8 in
Output Filename C 8 OUT
Unit ENGLISH
Plotted Output Filename C 8 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 126 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient Of0 400 Has Been Assigned
 A Vertical Earthquake Loading Coefficient Of0 000 Has Been Assigned
 Cavitation Pressure = 0 0 (psf)
 A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified
 625 Trial Surfaces Have Been Generated
 25 Surfaces Initiate From Each Of 25 Points Equally Spaced Along The Ground Surface Between X = 500 00 ft and X = 800 00 ft
 Each Surface Terminates Between X = 850 00 ft and X =1500 00 ft
 Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is Y = 0 00 ft
 10 00 ft Line Segments Define Each Trial Failure Surface
 Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 24 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 619 26 |
| 3 | 769 96 | 618 81 |
| 4 | 779 95 | 618 64 |
| 5 | 789 96 | 618 77 |
| 6 | 799 95 | 619 17 |
| 7 | 809 93 | 619 87 |

| | | |
|----|--------|--------|
| 8 | 819 88 | 620 85 |
| 9 | 829 80 | 622 11 |
| 10 | 839 68 | 623 66 |
| 11 | 849 51 | 625 49 |
| 12 | 859 28 | 627 60 |
| 13 | 868 99 | 630 00 |
| 14 | 878 63 | 632 66 |
| 15 | 888 19 | 635 61 |
| 16 | 897 65 | 638 83 |
| 17 | 907 03 | 642 31 |
| 18 | 916 30 | 546 07 |
| 19 | 925 45 | 650 09 |
| 20 | 934 49 | 654 37 |
| 21 | 943 40 | 658 90 |
| 22 | 952 18 | 563 69 |
| 23 | 960 82 | 668 73 |
| 24 | 962 85 | 670 00 |

Circle Center At X = 780 8 , Y = 967 1 and Radius, 348 5
 *** 0 870 ***

Individual data on the 30 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 10 0 | 1828 9 | 0 0 | 0 0 | 0 0 | 0 0 | 731 6 | 0 0 | 0 0 |
| 2 | 10 0 | 5336 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2134 5 | 0 0 | 0 0 |
| 3 | 10 0 | 8527 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3410 8 | 0 0 | 0 0 |
| 4 | 10 0 | 11389 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4555 9 | 0 0 | 0 0 |
| 5 | 10 0 | 13915 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5566 0 | 0 0 | 0 0 |
| 6 | 10 0 | 16095 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6438 1 | 0 0 | 0 0 |
| 7 | 10 0 | 17924 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7169 9 | 0 0 | 0 0 |
| 8 | 9 9 | 19399 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7759 9 | 0 0 | 0 0 |
| 9 | 0 2 | 405 0 | 0 0 | 0 0 | 0 0 | 0 0 | 162 0 | 0 0 | 0 0 |
| 10 | 9 7 | 21354 9 | 0 0 | 0 0 | 0 0 | 0 0 | 8542 0 | 0 0 | 0 0 |
| 11 | 9 8 | 22418 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8967 4 | 0 0 | 0 0 |
| 12 | 9 8 | 22676 4 | 0 0 | 0 0 | 0 0 | 0 0 | 9070 6 | 0 0 | 0 0 |
| 13 | 9 7 | 22564 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9025 9 | 0 0 | 0 0 |
| 14 | 1 0 | 2327 4 | 0 0 | 0 0 | 0 0 | 0 0 | 931 0 | 0 0 | 0 0 |
| 15 | 8 6 | 20410 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8164 2 | 0 0 | 0 0 |
| 16 | 9 6 | 21979 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8791 9 | 0 0 | 0 0 |
| 17 | 9 5 | 20802 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8321 0 | 0 0 | 0 0 |
| 18 | 3 2 | 6656 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2562 5 | 0 0 | 0 0 |
| 19 | 6 2 | 12638 8 | 0 0 | 0 0 | 0 0 | 0 0 | 5055 5 | 0 0 | 0 0 |
| 20 | 3 0 | 5793 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2317 5 | 0 0 | 0 0 |
| 21 | 6 3 | 12150 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4860 0 | 0 0 | 0 0 |
| 22 | 9 0 | 15710 1 | 0 0 | 0 0 | 0 0 | 0 0 | 6284 0 | 0 0 | 0 0 |
| 23 | 0 2 | 325 5 | 0 0 | 0 0 | 0 0 | 0 0 | 130 2 | 0 0 | 0 0 |
| 24 | 9 0 | 13522 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5449 1 | 0 0 | 0 0 |
| 25 | 8 9 | 10948 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4379 2 | 0 0 | 0 0 |
| 25 | 2 0 | 2094 2 | 0 0 | 0 0 | 0 0 | 0 0 | 837 7 | 0 0 | 0 0 |
| 27 | 4 6 | 4256 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1702 6 | 0 0 | 0 0 |
| 23 | 2 2 | 1708 7 | 0 0 | 0 0 | 0 0 | 0 0 | 683 5 | 0 0 | 0 0 |
| 29 | 8 6 | 3710 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1484 3 | 0 0 | 0 0 |
| 30 | 2 0 | 145 9 | 0 0 | 0 0 | 0 0 | 0 0 | 58 4 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 760 00 | 620 00 |
| 2 | 759 97 | 619 22 |
| 3 | 769 96 | 618 82 |
| 4 | 779 95 | 618 79 |
| 5 | 789 95 | 619 13 |
| 6 | 799 93 | 619 84 |
| 7 | 809 87 | 620 92 |
| 8 | 819 77 | 622 37 |
| 9 | 829 60 | 624 19 |
| 10 | 839 36 | 626 38 |
| 11 | 849 03 | 628 92 |

120/130

| | | |
|----|--------|--------|
| 12 | 858 50 | 631 82 |
| 13 | 868 05 | 635 08 |
| 14 | 877 38 | 638 69 |
| 15 | 886 57 | 642 64 |
| 16 | 895 60 | 645 93 |
| 17 | 904 47 | 651 55 |
| 18 | 913 16 | 556 50 |
| 19 | 921 65 | 661 77 |
| 20 | 924 36 | 663 59 |

Circle Center At X = 775 8 , Y = 887 1 and Radius, 268 4
*** 0 882 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 43 | 621 95 |
| 3 | 782 40 | 621 21 |
| 4 | 792 40 | 620 91 |
| 5 | 802 40 | 621 04 |
| 6 | 812 38 | 621 61 |
| 7 | 822 33 | 622 62 |
| 8 | 832 23 | 624 06 |
| 9 | 842 05 | 625 93 |
| 10 | 851 78 | 628 22 |
| 11 | 861 41 | 630 94 |
| 12 | 870 90 | 634 08 |
| 13 | 880 25 | 637 63 |
| 14 | 889 44 | 641 58 |
| 15 | 898 44 | 645 93 |
| 16 | 907 25 | 650 67 |
| 17 | 915 84 | 655 79 |
| 18 | 924 20 | 661 28 |
| 19 | 929 01 | 664 75 |

Circle Center At X = 794 3 , Y = 849 9 and Radius 229 0
*** 0 890 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 49 | 629 79 |
| 3 | 807 47 | 630 44 |
| 4 | 817 43 | 631 33 |
| 5 | 827 37 | 632 46 |
| 6 | 837 27 | 533 82 |
| 7 | 847 14 | 635 42 |
| 8 | 856 97 | 637 26 |
| 9 | 866 76 | 539 34 |
| 10 | 876 49 | 641 64 |
| 11 | 886 16 | 644 18 |
| 12 | 895 77 | 646 95 |
| 13 | 905 31 | 649 95 |
| 14 | 914 77 | 653 18 |
| 15 | 924 16 | 655 63 |
| 16 | 933 45 | 660 31 |
| 17 | 942 67 | 664 21 |
| 18 | 951 78 | 668 33 |
| 19 | 955 26 | 670 00 |

Circle Center At X = 775 3 , Y = 1046 7 and Radius, 417 5
*** 0 894 ***

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 35 | 621 39 |
| 3 | 782 26 | 620 08 |
| 4 | 792 22 | 619 18 |
| 5 | 802 21 | 618 70 |
| 5 | 812 21 | 618 65 |

121/130

| | | |
|----|--------|--------|
| 7 | 822 20 | 619 01 |
| 8 | 832 17 | 619 80 |
| 9 | 842 10 | 621 01 |
| 10 | 851 97 | 622 63 |
| 11 | 861 76 | 624 67 |
| 12 | 871 45 | 627 12 |
| 13 | 881 04 | 629 97 |
| 14 | 890 49 | 633 23 |
| 15 | 899 80 | 636 88 |
| 16 | 908 95 | 640 92 |
| 17 | 917 92 | 645 34 |
| 18 | 926 69 | 650 14 |
| 19 | 935 26 | 555 30 |
| 20 | 943 60 | 660 82 |
| 21 | 951 70 | 666 68 |
| 22 | 955 89 | 570 00 |

Circle Center At X = 808 5 , Y = 855 6 and Radius, 237 0
*** 0 894 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 523 13 |
| 2 | 772 38 | 621 57 |
| 3 | 782 32 | 620 52 |
| 4 | 792 31 | 619 99 |
| 5 | 802 31 | 619 97 |
| 6 | 812 30 | 620 46 |
| 7 | 822 25 | 621 47 |
| 8 | 832 13 | 622 98 |
| 9 | 841 93 | 625 00 |
| 10 | 851 60 | 627 52 |
| 11 | 861 14 | 630 54 |
| 12 | 870 50 | 634 04 |
| 13 | 879 68 | 538 01 |
| 14 | 888 64 | 642 45 |
| 15 | 897 36 | 647 35 |
| 16 | 905 81 | 652 69 |
| 17 | 913 99 | 558 45 |
| 18 | 918 73 | 662 18 |

Circle Center At X = 797 7 , Y = 814 2 and Radius, 194 3
*** 0 902 ***

Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 30 | 617 87 |
| 3 | 757 17 | 616 23 |
| 4 | 767 08 | 614 91 |
| 5 | 777 03 | 613 91 |
| 6 | 787 01 | 613 26 |
| 7 | 797 00 | 612 91 |
| 8 | 807 00 | 612 91 |
| 9 | 817 00 | 613 23 |
| 10 | 826 98 | 613 89 |
| 11 | 836 93 | 614 87 |
| 12 | 846 84 | 616 19 |
| 13 | 856 71 | 617 83 |
| 14 | 856 51 | 619 79 |
| 15 | 876 25 | 622 08 |
| 16 | 885 90 | 624 68 |
| 17 | 895 46 | 627 61 |
| 18 | 904 92 | 630 84 |
| 19 | 914 27 | 634 39 |
| 20 | 923 50 | 638 25 |
| 21 | 932 60 | 642 40 |
| 22 | 941 55 | 645 86 |
| 23 | 950 35 | 651 61 |
| 24 | 958 99 | 656 55 |

122/130

25 967 46 651 96
 26 975 74 657 56
 27 979 11 570 00
 Circle Center At X = 802 1 , Y = 915 8 and Radius, 302 9
 *** 0 903 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 34 | 521 34 |
| 3 | 782 25 | 520 10 |
| 4 | 792 24 | 619 39 |
| 5 | 802 24 | 619 24 |
| 6 | 812 23 | 619 62 |
| 7 | 822 19 | 620 56 |
| 8 | 832 08 | 622 03 |
| 9 | 841 87 | 624 04 |
| 10 | 851 54 | 626 58 |
| 11 | 861 06 | 629 64 |
| 12 | 870 40 | 633 22 |
| 13 | 879 53 | 637 30 |
| 14 | 888 42 | 641 87 |
| 15 | 897 06 | 646 92 |
| 16 | 905 40 | 652 44 |
| 17 | 913 43 | 658 40 |
| 18 | 917 67 | 661 92 |

Circle Center At X = 800 1 , Y = 802 3 and Radius, 183 1
 *** 0 909 ***

Failure Surface Specified By 31 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 519 69 |
| 2 | 734 88 | 618 14 |
| 3 | 744 79 | 616 83 |
| 4 | 754 73 | 615 75 |
| 5 | 764 70 | 614 90 |
| 6 | 774 68 | 614 30 |
| 7 | 784 67 | 613 93 |
| 8 | 794 67 | 613 79 |
| 9 | 804 67 | 613 90 |
| 10 | 814 67 | 614 24 |
| 11 | 824 65 | 614 82 |
| 12 | 834 52 | 615 53 |
| 13 | 844 56 | 616 68 |
| 14 | 854 48 | 617 97 |
| 15 | 864 36 | 619 49 |
| 16 | 874 21 | 621 24 |
| 17 | 884 01 | 523 23 |
| 18 | 893 76 | 625 46 |
| 19 | 903 45 | 627 90 |
| 20 | 913 09 | 630 58 |
| 21 | 922 65 | 633 49 |
| 22 | 932 15 | 636 63 |
| 23 | 941 57 | 639 98 |
| 24 | 950 91 | 643 56 |
| 25 | 960 16 | 647 37 |
| 26 | 969 31 | 651 39 |
| 27 | 978 37 | 655 62 |
| 28 | 987 33 | 650 07 |
| 29 | 996 17 | 664 73 |
| 30 | 1004 91 | 669 60 |
| 31 | 1005 59 | 670 00 |

Circle Center At X = 795 3 , Y = 1035 4 and Radius, 421 6
 *** 0 917 ***

Failure Surface Specified By 21 Coordinate Points


| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |

| | | |
|----|--------|--------|
| 2 | 772 45 | 624 11 |
| 3 | 782 39 | 626 25 |
| 4 | 792 30 | 626 56 |
| 5 | 802 19 | 628 02 |
| 6 | 812 06 | 629 65 |
| 7 | 821 90 | 631 43 |
| 8 | 831 71 | 633 37 |
| 9 | 841 49 | 635 46 |
| 10 | 851 23 | 637 72 |
| 11 | 860 94 | 640 13 |
| 12 | 870 60 | 642 70 |
| 13 | 880 22 | 645 42 |
| 14 | 889 80 | 648 30 |
| 15 | 899 33 | 651 33 |
| 16 | 908 81 | 654 51 |
| 17 | 918 24 | 657 85 |
| 18 | 927 61 | 661 34 |
| 19 | 936 92 | 664 97 |
| 20 | 946 18 | 668 75 |
| 21 | 947 76 | 669 44 |

Circle Center At X = 706 4 , Y = 1241 5 and Radius, 621 0
*** 0 918 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\irl\8 pl2 Run By Greg Shafer, HDR 4/20/2010 03:08PM




| # | FS | Soil Desc | Soil Type No | Total Unit WL (pcf) | Saturated Unit WL (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface No | Load | Value |
|---|------|-----------|--------------|---------------------|-------------------------|--------------------------|----------------------|-----------------|------|-------|
| a | 0.87 | | | | | | | | | |
| b | 0.88 | | | | | | | | | |
| c | 0.89 | UVSC | 1 | 113.5 | 121.0 | 50.0 | 29.0 | W1 | | |
| d | 0.89 | LSC | 2 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| e | 0.89 | SC | 3 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| f | 0.90 | LVSC | 4 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| g | 0.90 | | | | | | | | | |
| h | 0.91 | | | | | | | | | |
| i | 0.92 | | | | | | | | | |
| j | 0.92 | | | | | | | | | |

| | |
|----------|----------|
| Load | Value |
| Honz Eqk | 0.400 g< |

PCSTABL7 FSmm=0.87

Safety Factors Are Calculated By The Modified Bishop Method

STED



124/130

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 08PM
Run By Greg Shafer, HDR
Input Data Filename C 8 in
Output Filename C 8 OUT
Unit ENGLISH
Plotted Output Filename C 8 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 540 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param (psf) | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 60 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient

Of0 400 Has Been Assigned

A Vertical Earthquake Loading Coefficient

Of0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random

Technique For Generating Circular Surfaces, Has Been Specified

525 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced

Along The Ground Surface Between X = 500 00 ft

and X = 800 00 ft

Each Surface Terminates Between X = 850 00 ft

and X =1500 00 ft

Unless Further Limitations Were Imposed The Minimum Elevation

At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical

First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 24 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 769 97 | 619 26 |
| 3 | 769 95 | 618 81 |
| 4 | 779 95 | 618 54 |
| 5 | 789 96 | 518 77 |
| 6 | 799 95 | 619 17 |
| 7 | 809 93 | 519 87 |

126/130

| | | |
|----|--------|--------|
| 8 | 819 88 | 620 85 |
| 9 | 829 80 | 622 11 |
| 10 | 839 68 | 623 66 |
| 11 | 849 51 | 625 49 |
| 12 | 859 28 | 627 60 |
| 13 | 868 99 | 630 00 |
| 14 | 878 63 | 632 66 |
| 15 | 888 19 | 635 61 |
| 16 | 897 66 | 638 83 |
| 17 | 907 03 | 642 31 |
| 18 | 916 30 | 546 07 |
| 19 | 925 45 | 650 09 |
| 20 | 934 49 | 654 37 |
| 21 | 943 40 | 658 90 |
| 22 | 952 18 | 663 69 |
| 23 | 960 82 | 668 73 |
| 24 | 962 85 | 670 00 |

Circle Center At X = 780 8 , Y = 967 1 and Radius, 348 5
 *** 0 870 ***

Individual data on the 30 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force Surcharge Load | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|---------------------------------|-----------|------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | Load (lbs) |
| 1 | 10 0 | 1828 9 | 0 0 | 0 0 | 0 0 | 0 0 | 731 6 | 0 0 | 0 0 |
| 2 | 10 0 | 5336 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2134 5 | 0 0 | 0 0 |
| 3 | 10 0 | 8527 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3410 8 | 0 0 | 0 0 |
| 4 | 10 0 | 11389 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4555 9 | 0 0 | 0 0 |
| 5 | 10 0 | 13915 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5566 0 | 0 0 | 0 0 |
| 6 | 10 0 | 16095 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6438 1 | 0 0 | 0 0 |
| 7 | 10 0 | 17924 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7169 9 | 0 0 | 0 0 |
| 8 | 9 9 | 19399 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7759 9 | 0 0 | 0 0 |
| 9 | 0 2 | 405 0 | 0 0 | 0 0 | 0 0 | 0 0 | 162 0 | 0 0 | 0 0 |
| 10 | 9 7 | 21354 9 | 0 0 | 0 0 | 0 0 | 0 0 | 8542 0 | 0 0 | 0 0 |
| 11 | 9 8 | 22418 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8967 4 | 0 0 | 0 0 |
| 12 | 9 8 | 22676 4 | 0 0 | 0 0 | 0 0 | 0 0 | 9070 6 | 0 0 | 0 0 |
| 13 | 9 7 | 22554 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9025 9 | 0 0 | 0 0 |
| 14 | 1 0 | 2327 4 | 0 0 | 0 0 | 0 0 | 0 0 | 931 0 | 0 0 | 0 0 |
| 15 | 8 6 | 20410 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8164 2 | 0 0 | 0 0 |
| 15 | 9 6 | 21979 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8791 9 | 0 0 | 0 0 |
| 17 | 9 5 | 20802 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8321 0 | 0 0 | 0 0 |
| 18 | 3 2 | 6656 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2662 5 | 0 0 | 0 0 |
| 19 | 6 2 | 12638 8 | 0 0 | 0 0 | 0 0 | 0 0 | 5055 5 | 0 0 | 0 0 |
| 20 | 3 0 | 5793 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2317 5 | 0 0 | 0 0 |
| 21 | 6 3 | 12150 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4860 0 | 0 0 | 0 0 |
| 22 | 9 0 | 15710 1 | 0 0 | 0 0 | 0 0 | 0 0 | 6284 0 | 0 0 | 0 0 |
| 23 | 0 2 | 325 5 | 0 0 | 0 0 | 0 0 | 0 0 | 130 2 | 0 0 | 0 0 |
| 24 | 9 0 | 13622 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5449 1 | 0 0 | 0 0 |
| 25 | 8 9 | 10948 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4379 2 | 0 0 | 0 0 |
| 26 | 2 0 | 2094 2 | 0 0 | 0 0 | 0 0 | 0 0 | 837 7 | 0 0 | 0 0 |
| 27 | 4 6 | 4255 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1702 6 | 0 0 | 0 0 |
| 28 | 2 2 | 1708 7 | 0 0 | 0 0 | 0 0 | 0 0 | 683 5 | 0 0 | 0 0 |
| 29 | 8 6 | 3710 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1484 3 | 0 0 | 0 0 |
| 30 | 2 0 | 145 9 | 0 0 | 0 0 | 0 0 | 0 0 | 58 4 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 619 22 |
| 3 | 769 96 | 618 82 |
| 4 | 779 96 | 618 79 |
| 5 | 789 96 | 619 13 |
| 6 | 799 93 | 619 84 |
| 7 | 809 87 | 620 92 |
| 8 | 819 77 | 622 37 |
| 9 | 829 60 | 624 19 |
| 10 | 839 36 | 626 38 |
| 11 | 849 03 | 628 92 |

| | | |
|----|--------|--------|
| 12 | 858 60 | 631 82 |
| 13 | 868 05 | 635 08 |
| 14 | 877 38 | 638 69 |
| 15 | 886 57 | 642 64 |
| 16 | 895 60 | 646 93 |
| 17 | 904 47 | 651 55 |
| 18 | 913 16 | 656 50 |
| 19 | 921 65 | 661 77 |
| 20 | 924 36 | 663 59 |

Circle Center At X = 775 8 , Y = 887 1 and Radius, 268 4
*** 0 882 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 43 | 621 95 |
| 3 | 782 40 | 621 21 |
| 4 | 792 40 | 520 91 |
| 5 | 802 40 | 621 04 |
| 6 | 812 38 | 521 51 |
| 7 | 822 33 | 622 62 |
| 8 | 832 23 | 624 06 |
| 9 | 842 05 | 625 93 |
| 10 | 851 78 | 628 22 |
| 11 | 861 41 | 630 94 |
| 12 | 870 90 | 634 08 |
| 13 | 880 25 | 637 63 |
| 14 | 889 44 | 641 58 |
| 15 | 898 44 | 645 93 |
| 16 | 907 25 | 650 57 |
| 17 | 915 84 | 655 79 |
| 18 | 924 20 | 661 28 |
| 19 | 929 01 | 654 75 |

Circle Center At X = 794 3 , Y = 849 9 and Radius, 229 0
*** 0 890 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 49 | 629 79 |
| 3 | 807 47 | 630 44 |
| 4 | 817 43 | 631 33 |
| 5 | 827 37 | 632 45 |
| 5 | 837 27 | 633 82 |
| 7 | 847 14 | 635 42 |
| 8 | 856 97 | 637 25 |
| 9 | 866 76 | 639 34 |
| 10 | 876 49 | 641 64 |
| 11 | 885 16 | 644 18 |
| 12 | 895 77 | 646 95 |
| 13 | 905 31 | 649 95 |
| 14 | 914 77 | 653 18 |
| 15 | 924 16 | 656 63 |
| 16 | 933 46 | 660 31 |
| 17 | 942 67 | 664 21 |
| 18 | 951 78 | 668 33 |
| 19 | 955 26 | 670 00 |

Circle Center At X = 775 3 , Y = 1046 7 and Radius, 417 5
*** 0 894 ***

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 35 | 621 39 |
| 3 | 782 26 | 620 08 |
| 4 | 792 22 | 619 18 |
| 5 | 802 21 | 618 70 |
| 5 | 812 21 | 618 65 |

| | | |
|----|--------|--------|
| 7 | 822 20 | 619 01 |
| 8 | 832 17 | 619 80 |
| 9 | 842 10 | 621 01 |
| 10 | 851 97 | 622 63 |
| 11 | 861 76 | 624 67 |
| 12 | 871 45 | 627 12 |
| 13 | 881 04 | 629 97 |
| 14 | 890 49 | 633 23 |
| 15 | 899 80 | 636 88 |
| 16 | 908 95 | 640 92 |
| 17 | 917 92 | 645 34 |
| 18 | 925 69 | 650 14 |
| 19 | 936 26 | 655 30 |
| 20 | 943 60 | 660 82 |
| 21 | 951 70 | 666 68 |
| 22 | 955 89 | 670 00 |

Circle Center At X = 808 5 , Y = 855 6 and Radius, 237 0
 *** 0 894 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 38 | 621 57 |
| 3 | 782 32 | 620 52 |
| 4 | 792 31 | 619 99 |
| 5 | 802 31 | 519 97 |
| 6 | 812 30 | 620 46 |
| 7 | 822 25 | 621 47 |
| 8 | 832 13 | 622 98 |
| 9 | 841 93 | 625 00 |
| 10 | 851 60 | 627 52 |
| 11 | 861 14 | 630 54 |
| 12 | 870 50 | 634 04 |
| 13 | 879 58 | 638 01 |
| 14 | 888 64 | 642 45 |
| 15 | 897 36 | 647 35 |
| 16 | 905 81 | 652 69 |
| 17 | 913 99 | 658 45 |
| 18 | 918 73 | 662 18 |

Circle Center At X = 797 7 , Y = 814 2 and Radius, 194 3
 *** 0 902 ***

Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 30 | 617 87 |
| 3 | 757 17 | 616 23 |
| 4 | 767 08 | 614 91 |
| 5 | 777 03 | 613 91 |
| 6 | 787 01 | 613 25 |
| 7 | 797 00 | 612 91 |
| 8 | 807 00 | 612 91 |
| 9 | 817 00 | 613 23 |
| 10 | 826 98 | 613 89 |
| 11 | 836 93 | 614 87 |
| 12 | 846 84 | 615 19 |
| 13 | 856 71 | 517 83 |
| 14 | 866 51 | 619 79 |
| 15 | 876 25 | 622 08 |
| 16 | 885 90 | 624 68 |
| 17 | 895 46 | 627 61 |
| 18 | 904 92 | 630 84 |
| 19 | 914 27 | 634 39 |
| 20 | 923 60 | 538 25 |
| 21 | 932 60 | 642 40 |
| 22 | 941 55 | 646 86 |
| 23 | 960 35 | 651 61 |
| 24 | 958 99 | 556 65 |

| | | |
|----|--------|--------|
| 25 | 957 46 | 661 96 |
| 26 | 975 74 | 657 56 |
| 27 | 979 11 | 670 00 |

Circle Center At X = 802 1 , Y = 915 8 and Radius, 302 9
 *** 0 903 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 34 | 621 34 |
| 3 | 782 26 | 520 10 |
| 4 | 792 24 | 619 39 |
| 5 | 802 24 | 619 24 |
| 6 | 812 23 | 619 62 |
| 7 | 822 19 | 620 56 |
| 8 | 832 08 | 622 03 |
| 9 | 841 87 | 624 04 |
| 10 | 851 54 | 626 58 |
| 11 | 861 06 | 629 64 |
| 12 | 870 40 | 633 22 |
| 13 | 879 53 | 637 30 |
| 14 | 888 42 | 641 87 |
| 15 | 897 05 | 645 92 |
| 16 | 905 40 | 652 44 |
| 17 | 913 43 | 658 40 |
| 18 | 917 67 | 661 92 |

Circle Center At X = 800 1 , Y = 802 3 and Radius, 183 1
 *** 0 909 ***

Failure Surface Specified By 31 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 619 69 |
| 2 | 734 88 | 618 14 |
| 3 | 744 79 | 616 83 |
| 4 | 754 73 | 615 75 |
| 5 | 764 70 | 614 90 |
| 6 | 774 68 | 614 30 |
| 7 | 784 67 | 613 93 |
| 8 | 794 57 | 613 79 |
| 9 | 804 67 | 613 90 |
| 10 | 814 67 | 614 24 |
| 11 | 824 65 | 614 82 |
| 12 | 834 62 | 615 63 |
| 13 | 844 56 | 616 68 |
| 14 | 854 48 | 617 97 |
| 15 | 864 36 | 619 49 |
| 15 | 874 21 | 621 24 |
| 17 | 884 01 | 623 23 |
| 18 | 893 76 | 625 45 |
| 19 | 903 45 | 627 90 |
| 20 | 913 09 | 630 58 |
| 21 | 922 65 | 633 49 |
| 22 | 932 15 | 636 63 |
| 23 | 941 57 | 639 98 |
| 24 | 950 91 | 643 56 |
| 25 | 960 16 | 647 37 |
| 26 | 969 31 | 651 39 |
| 27 | 978 37 | 665 62 |
| 28 | 987 33 | 660 07 |
| 29 | 996 17 | 664 73 |
| 30 | 1004 91 | 659 60 |
| 31 | 1005 59 | 670 00 |

Circle Center At X = 795 3 , Y = 1035 4 and Radius, 421 6
 *** 0 917 ***

Failure Surface Specified By 21 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 60 | 623 13 |

130/130

| | | |
|----|--------|--------|
| 2 | 772 45 | 624 11 |
| 3 | 782 39 | 625 25 |
| 4 | 792 30 | 626 56 |
| 5 | 802 19 | 628 02 |
| 6 | 812 06 | 629 65 |
| 7 | 821 90 | 531 43 |
| 8 | 831 71 | 533 37 |
| 9 | 841 49 | 635 46 |
| 10 | 851 23 | 637 72 |
| 11 | 860 94 | 640 13 |
| 12 | 870 60 | 642 70 |
| 13 | 880 22 | 645 42 |
| 14 | 889 80 | 548 30 |
| 15 | 899 33 | 651 33 |
| 16 | 908 81 | 654 51 |
| 17 | 918 24 | 657 85 |
| 18 | 927 61 | 661 34 |
| 19 | 936 92 | 664 97 |
| 20 | 946 18 | 668 76 |
| 21 | 947 76 | 669 44 |


Circle Center At X = 706 4 , Y = 1241 5 and Radius, 621 0
*** 0 918 ***

**ATTACHMENT 2C-3: SLOPE STABILITY RUNS &
RESULTS – WASTE MASS SLIDING BLOCK**

| | | | | | |
|---------|------------------|----------|------|------|--------------------|
| Project | IRL | Computed | LRMS | Date | 3/20/10 4/20/10 |
| Subject | slope stability | Checked | POP | Date | 4-9-10 |
| Task | Sliding Block | Page | 1 | of | 22 |
| Job # | 125124 Dept. 143 | No | | | |


Liner stability - Sliding Block

Worst case @ Cell 3 / Cell 4 - 130 FT from top of Waste to cell floors



| Interface | Flow angles | ✓ S |
|--|-------------|--------|
| 2' Protective Cover / Upper Geotextile | 25° | |
| Upper Geo / Textured HDPE | 25° | |
| Textured HDPE / GCL | * 18° | |
| GCL / Lower Geotextile | * 18° | |
| Lower Geotextile / Subgrade | 25° | |


* Anticipated critical Interface to be verified.



- 2' Protective Soil / LCRS
- Upper Geotextile (Nonwoven on cell floor, Re. forced woven on sideslope)
- Texture 60 mil HDPE Geomembrane
- Geosynthetic Clay Liner (GCL)
- Lower Geotextile (Nonwoven)
- Subgrade

| | | | | | |
|---------|-----------------|----------|-----|------|---------|
| Project | IRL | Computed | Gms | Date | 3/20/10 |
| Subject | Slope Stability | Checked | PDP | Date | 4-9-10 |
| Task | Sliding Block | Page | 2 | of | 22 |
| Job # | 125184 | Dept. | 143 | No | |

Results



| acceleration, g | FS |
|----------------------|----------------------|
| 0 (stat.) | 14 |
| x \rightarrow 0.1g | 10.7 \leftarrow 10 |
| 0.2g | 0.83 |

@ $FS = 10$

$$\frac{1.07 - 0.83}{0.1 - 0.2} = \frac{1.07 - 1.0}{0.1 - x} \Rightarrow \frac{0.24}{-0.1} = \frac{0.07}{0.1 - x}$$

$$0.22(0.1 - x) = (-0.1)(0.07) \Rightarrow 0.022 - 0.22x = -0.007$$

$$-0.22x = -0.029 \quad x = 0.13$$

| | | | | | |
|---------|-----------------|----------|---------|------|--------|
| Project | IRL | Computed | 6/11/05 | Date | 3/2010 |
| Subject | Slope Stability | Checked | | Date | 4/2010 |
| Task | Sliding Block | Page | 3 | of | 22 |
| Job # | 125184 | Dept | 143 | No | |

Linear stability, Max Waste - Sliding Block / Displacement

$$a_{max} = 0.28 \text{ (Reference E)}$$

$$a_y = 0.13 \text{ (Previous page)}$$

$$\frac{a_y}{a_{max}} = \frac{0.13}{0.28} = 0.46 \quad @ M=7.0$$


See Attachment 2B (Reference A)

$$@ M=7.0 \quad U_{max} = 80 \text{ cm} < 30 \text{ cm (allow)} \quad \underline{\underline{OK}}$$

(Blank)

Intermountain Regional Landfill Sliding Block

c:\program files\stedwin\rt21 pl2 Run By Greg Shafer, HDR 4/20/2010 04 10PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez. Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|---------------|
| a | 1.44 | | | | | | | |
| b | 1.45 | | No | | | | | No |
| c | 1.46 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 |
| d | 1.46 | Waste | 2 | 50.0 | 60.0 | 150.0 | 22.0 | W1 |
| e | 1.47 | Liner | 3 | 50.0 | 50.0 | 0.0 | 18.0 | W1 |
| f | 1.47 | | | | | | | |
| g | 1.47 | | | | | | | |
| h | 1.47 | | | | | | | |
| i | 1.47 | | | | | | | |
| j | 1.48 | | | | | | | |

STED



PCSTABL7 FSmin=1.44
Safety Factors Are Calculated By The Modified Janbu Method

5/22

6/22

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 04 10PM
Run By Greg Shafer, HDR
Input Data Filename C 21 in
Output Filename C 21 OUT
Unit ENGLISH
Plotted Output Filename C 21 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Sliding Block

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

5 Top Boundaries
12 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 550 00 | 750 00 | 558 75 | 1 |
| 2 | 750 00 | 558 75 | 1140 00 | 688 75 | 2 |
| 3 | 1140 00 | 688 75 | 1440 00 | 688 75 | 2 |
| 4 | 1440 00 | 688 75 | 1760 00 | 608 75 | 2 |
| 5 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |
| 6 | 750 00 | 558 75 | 750 30 | 558 85 | 3 |
| 7 | 750 30 | 558 85 | 1560 00 | 558 85 | 3 |
| 8 | 1560 00 | 558 85 | 1759 90 | 608 75 | 3 |
| 9 | 1759 90 | 608 75 | 1760 00 | 608 75 | 3 |
| 10 | 750 00 | 558 75 | 1560 00 | 558 75 | 1 |
| 11 | 1560 00 | 558 75 | 1760 00 | 608 75 | 1 |
| 12 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |

ISOTROPIC SOIL PARAMETERS

3 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |
| 3 | 50 0 | 50 0 | 0 0 | 18 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random Technique For Generating Sliding Block Surfaces, Has Been Specified

1000 Trial Surfaces Have Been Generated

6 Boxes Specified For Generation Of Central Block Base Length Of Line Segments For Active And Passive Portions Of Sliding Block Is 10 0

| Box No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Height (ft) |
|--------|-------------|-------------|--------------|--------------|-------------|
| 1 | 751 00 | 558 84 | 751 00 | 558 84 | 0 00 |
| 2 | 800 00 | 558 84 | 800 00 | 558 84 | 0 00 |
| 3 | 850 00 | 558 84 | 850 00 | 558 84 | 0 00 |
| 4 | 900 00 | 558 84 | 900 00 | 558 84 | 0 00 |
| 5 | 950 00 | 558 84 | 950 00 | 558 84 | 0 00 |
| 6 | 960 00 | 558 84 | 960 00 | 558 84 | 0 00 |

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Janbu Method * *
Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |

7/22

| | | |
|----|---------|--------|
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 00 | 565 99 |
| 9 | 972 39 | 574 41 |
| 10 | 979 45 | 581 49 |
| 11 | 986 45 | 588 63 |
| 12 | 993 17 | 596 04 |
| 13 | 1000 13 | 603 22 |
| 14 | 1007 18 | 610 31 |
| 15 | 1013 23 | 618 27 |
| 16 | 1019 88 | 625 74 |
| 17 | 1026 86 | 632 90 |
| 18 | 1032 31 | 641 28 |
| 19 | 1039 31 | 648 42 |
| 20 | 1041 75 | 656 00 |

*** 1 444 ***

Individual data on the 21 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 0 2 | 1 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 0 0 | 0 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 49 0 | 20604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 50 0 | 62274 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 50 0 | 103941 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 50 0 | 145608 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 10 0 | 34121 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 0 0 | 34 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 7 0 | 23575 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 5 4 | 16663 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 7 1 | 19811 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 12 | 7 0 | 17977 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 6 7 | 15558 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 7 0 | 14385 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 7 1 | 12879 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 6 1 | 9449 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 6 6 | 8500 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 7 0 | 7178 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 5 5 | 4050 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 7 0 | 3208 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 2 4 | 411 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 09 | 566 78 |
| 9 | 972 91 | 574 08 |
| 10 | 978 87 | 582 11 |
| 11 | 985 69 | 589 43 |
| 12 | 991 48 | 597 58 |
| 13 | 998 08 | 605 09 |
| 14 | 1004 94 | 612 37 |
| 15 | 1012 01 | 619 44 |
| 16 | 1019 08 | 626 51 |
| 17 | 1026 15 | 633 59 |
| 18 | 1033 20 | 640 68 |
| 19 | 1038 93 | 648 87 |
| 20 | 1044 53 | 656 93 |

*** 1 449 ***

Failure Surface Specified By 20 Coordinate Points

8/22

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 96 | 566 02 |
| 9 | 972 37 | 574 43 |
| 10 | 977 89 | 582 77 |
| 11 | 984 95 | 589 85 |
| 12 | 992 02 | 596 92 |
| 13 | 998 89 | 604 19 |
| 14 | 1005 95 | 611 27 |
| 15 | 1012 08 | 619 17 |
| 16 | 1018 78 | 626 59 |
| 17 | 1024 95 | 634 47 |
| 18 | 1030 69 | 642 65 |
| 19 | 1036 37 | 650 88 |
| 20 | 1036 89 | 654 38 |

*** 1 458 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 98 | 566 00 |
| 9 | 972 83 | 574 11 |
| 10 | 979 85 | 581 24 |
| 11 | 985 80 | 589 27 |
| 12 | 992 85 | 596 36 |
| 13 | 999 92 | 603 43 |
| 14 | 1005 88 | 611 47 |
| 15 | 1012 34 | 619 10 |
| 16 | 1016 21 | 628 32 |
| 17 | 1022 75 | 635 89 |
| 18 | 1029 67 | 643 11 |
| 19 | 1034 59 | 651 81 |
| 20 | 1034 59 | 653 61 |

*** 1 464 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 99 | 565 99 |
| 9 | 974 05 | 573 08 |
| 10 | 979 99 | 581 12 |
| 11 | 986 46 | 588 74 |
| 12 | 992 33 | 596 84 |
| 13 | 997 72 | 605 26 |
| 14 | 1004 76 | 612 36 |
| 15 | 1011 22 | 620 00 |
| 16 | 1018 02 | 627 33 |
| 17 | 1024 85 | 634 63 |
| 18 | 1031 80 | 641 83 |

9/22

| | | |
|---|-------------|-------------|
| 19 | 1038 73 | 649 03 |
| 20 | 1038 81 | 655 02 |
| *** | 1 465 | *** |
| Failure Surface Specified By 19 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 17 | 566 71 |
| 9 | 973 11 | 573 91 |
| 10 | 980 18 | 580 99 |
| 11 | 987 03 | 588 27 |
| 12 | 994 10 | 595 34 |
| 13 | 1000 41 | 603 10 |
| 14 | 1007 31 | 610 33 |
| 15 | 1011 73 | 619 31 |
| 16 | 1015 48 | 628 58 |
| 17 | 1022 13 | 636 04 |
| 18 | 1028 64 | 643 63 |
| 19 | 1030 87 | 652 38 |
| *** | 1 469 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 66 | 558 97 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 70 | 566 26 |
| 9 | 973 14 | 573 91 |
| 10 | 979 70 | 581 46 |
| 11 | 986 77 | 588 53 |
| 12 | 992 71 | 596 58 |
| 13 | 999 27 | 604 12 |
| 14 | 1004 68 | 612 54 |
| 15 | 1008 95 | 621 58 |
| 16 | 1015 71 | 628 95 |
| 17 | 1020 46 | 637 75 |
| 18 | 1027 53 | 644 82 |
| 19 | 1034 58 | 651 91 |
| 20 | 1035 07 | 653 77 |
| *** | 1 469 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 82 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 84 | 566 14 |
| 9 | 973 87 | 573 25 |
| 10 | 980 90 | 580 36 |
| 11 | 987 03 | 588 26 |
| 12 | 992 93 | 596 33 |
| 13 | 999 90 | 603 50 |
| 14 | 1004 94 | 612 14 |
| 15 | 1011 74 | 619 48 |

10/22

| | | |
|----|---------|--------|
| 16 | 1018 69 | 626 66 |
| 17 | 1024 54 | 634 77 |
| 18 | 1026 24 | 644 63 |
| 19 | 1032 55 | 652 38 |
| 20 | 1033 11 | 653 12 |

*** 1 471 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 49 | 558 91 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 72 | 566 25 |
| 9 | 973 01 | 574 02 |
| 10 | 980 01 | 581 16 |
| 11 | 987 06 | 588 25 |
| 12 | 993 57 | 595 84 |
| 13 | 997 83 | 604 89 |
| 14 | 1002 99 | 613 46 |
| 15 | 1009 75 | 620 83 |
| 16 | 1016 68 | 628 03 |
| 17 | 1022 52 | 636 15 |
| 18 | 1029 27 | 643 53 |
| 19 | 1031 89 | 652 71 |

*** 1 472 ***


Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 58 | 558 94 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 965 21 | 567 38 |
| 9 | 971 78 | 574 91 |
| 10 | 977 37 | 583 21 |
| 11 | 983 95 | 590 74 |
| 12 | 990 76 | 598 06 |
| 13 | 997 83 | 605 13 |
| 14 | 1004 42 | 612 65 |
| 15 | 1010 81 | 620 34 |
| 16 | 1016 86 | 628 30 |
| 17 | 1022 82 | 636 33 |
| 18 | 1027 05 | 645 40 |
| 19 | 1034 11 | 652 47 |
| 20 | 1034 17 | 653 47 |

*** 1 476 ***

Intermountain Regional Landfill Sliding Block

c:\program files\stedwin\lrf122 pl2 Run By Greg Shafer HDR 4/20/2010 04 14PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez. Surface | Load Horiz | Value Eqk |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|---------------|------------|-----------|
| a | 1.07 | | | | | | | | 0 | 100 g< |
| b | 1.07 | | No | | | | | No | | |
| c | 1.07 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 | | |
| d | 1.08 | Waste | 2 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| e | 1.08 | Liner | 3 | 50.0 | 50.0 | 0.0 | 18.0 | W1 | | |
| f | 1.08 | | | | | | | | | |
| g | 1.08 | | | | | | | | | |
| h | 1.08 | | | | | | | | | |
| i | 1.08 | | | | | | | | | |
| j | 1.09 | | | | | | | | | |

PCSTABL7 FSmin=1.07

Safety Factors Are Calculated By The Modified Janbu Method

STED



11/22

12/22

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 04 14PM
Run By Greg Shafer, HDR
Input Data Filename C 22 in
Output Filename C 22 OUT
Unit ENGLISH
Plotted Output Filename C 22 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Sliding Block

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

5 Top Boundaries
12 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 550 00 | 750 00 | 558 75 | 1 |
| 2 | 750 00 | 558 75 | 1140 00 | 688 75 | 2 |
| 3 | 1140 00 | 688 75 | 1440 00 | 688 75 | 2 |
| 4 | 1440 00 | 688 75 | 1760 00 | 608 75 | 2 |
| 5 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |
| 6 | 750 00 | 558 75 | 750 30 | 558 85 | 3 |
| 7 | 750 30 | 558 85 | 1560 00 | 558 85 | 3 |
| 8 | 1560 00 | 558 85 | 1759 90 | 608 75 | 3 |
| 9 | 1759 90 | 608 75 | 1760 00 | 608 75 | 3 |
| 10 | 750 00 | 558 75 | 1560 00 | 558 75 | 1 |
| 11 | 1560 00 | 558 75 | 1760 00 | 608 75 | 1 |
| 12 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |

ISOTROPIC SOIL PARAMETERS

3 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |
| 3 | 50 0 | 50 0 | 0 0 | 18 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient Of 0 100 Has Been Assigned
A Vertical Earthquake Loading Coefficient Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random Technique For Generating Sliding Block Surfaces, Has Been Specified
1000 Trial Surfaces Have Been Generated
6 Boxes Specified For Generation Of Central Block Base
Length Of Line Segments For Active And Passive Portions Of Sliding Block Is 10 0

| Box No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Height (ft) |
|--------|-------------|-------------|--------------|--------------|-------------|
| 1 | 751 00 | 558 84 | 751 00 | 558 84 | 0 00 |
| 2 | 800 00 | 558 84 | 800 00 | 558 84 | 0 00 |
| 3 | 850 00 | 558 84 | 850 00 | 558 84 | 0 00 |
| 4 | 900 00 | 558 84 | 900 00 | 558 84 | 0 00 |
| 5 | 950 00 | 558 84 | 950 00 | 558 84 | 0 00 |
| 6 | 960 00 | 558 84 | 960 00 | 558 84 | 0 00 |

Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Janbu Method * *
Failure Surface Specified By 20 Coordinate Points
Point X-Surf Y-Surf

13/22

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 750 44 | 558 90 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 07 | 565 91 |
| 9 | 972 96 | 573 99 |
| 10 | 979 03 | 581 94 |
| 11 | 985 98 | 589 13 |
| 12 | 992 75 | 596 49 |
| 13 | 999 58 | 603 80 |
| 14 | 1005 98 | 611 48 |
| 15 | 1012 13 | 619 37 |
| 16 | 1017 76 | 627 63 |
| 17 | 1024 20 | 635 28 |
| 18 | 1031 24 | 642 38 |
| 19 | 1037 61 | 650 09 |
| 20 | 1039 59 | 655 28 |

*** 1 067 ***

Individual data on the 21 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 0 5 | 2 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 2 | 0 0 | 0 0 |
| 2 | 0 1 | 1 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 1 | 0 0 | 0 0 |
| 3 | 49 0 | 20604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2060 4 | 0 0 | 0 0 |
| 4 | 50 0 | 62274 9 | 0 0 | 0 0 | 0 0 | 0 0 | 6227 5 | 0 0 | 0 0 |
| 5 | 50 0 | 103941 6 | 0 0 | 0 0 | 0 0 | 0 0 | 10394 2 | 0 0 | 0 0 |
| 6 | 50 0 | 145608 2 | 0 0 | 0 0 | 0 0 | 0 0 | 14560 8 | 0 0 | 0 0 |
| 7 | 10 0 | 34121 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3412 2 | 0 0 | 0 0 |
| 8 | 0 0 | 34 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3 5 | 0 0 | 0 0 |
| 9 | 7 1 | 23844 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2384 5 | 0 0 | 0 0 |
| 10 | 5 9 | 18298 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1829 9 | 0 0 | 0 0 |
| 11 | 6 1 | 17020 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1702 0 | 0 0 | 0 0 |
| 12 | 7 0 | 17640 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1764 1 | 0 0 | 0 0 |
| 13 | 6 8 | 15483 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1548 4 | 0 0 | 0 0 |
| 14 | 6 8 | 13874 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1387 5 | 0 0 | 0 0 |
| 15 | 6 4 | 11318 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1131 9 | 0 0 | 0 0 |
| 16 | 6 1 | 9124 3 | 0 0 | 0 0 | 0 0 | 0 0 | 912 4 | 0 0 | 0 0 |
| 17 | 5 6 | 6637 1 | 0 0 | 0 0 | 0 0 | 0 0 | 663 7 | 0 0 | 0 0 |
| 18 | 6 4 | 5678 5 | 0 0 | 0 0 | 0 0 | 0 0 | 567 8 | 0 0 | 0 0 |
| 19 | 7 0 | 4393 2 | 0 0 | 0 0 | 0 0 | 0 0 | 439 3 | 0 0 | 0 0 |
| 20 | 6 4 | 2331 1 | 0 0 | 0 0 | 0 0 | 0 0 | 233 1 | 0 0 | 0 0 |
| 21 | 2 0 | 224 2 | 0 0 | 0 0 | 0 0 | 0 0 | 22 4 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 02 | 565 96 |
| 9 | 973 57 | 573 52 |
| 10 | 979 85 | 581 30 |
| 11 | 986 80 | 588 49 |
| 12 | 992 13 | 596 95 |
| 13 | 998 36 | 604 78 |
| 14 | 1004 16 | 612 92 |
| 15 | 1011 21 | 620 01 |
| 16 | 1017 54 | 627 75 |
| 17 | 1024 59 | 634 85 |

14/22

| | | |
|----|---------|--------|
| 18 | 1031 59 | 641 99 |
| 19 | 1037 22 | 650 25 |
| 20 | 1038 88 | 655 04 |

*** 1 070 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 74 | 559 00 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 03 | 565 95 |
| 9 | 974 09 | 573 03 |
| 10 | 981 04 | 580 23 |
| 11 | 987 13 | 588 16 |
| 12 | 993 04 | 596 23 |
| 13 | 1000 11 | 603 30 |
| 14 | 1006 29 | 611 16 |
| 15 | 1011 81 | 619 49 |
| 16 | 1018 14 | 627 24 |
| 17 | 1025 16 | 634 36 |
| 18 | 1032 23 | 641 43 |
| 19 | 1034 13 | 651 25 |
| 20 | 1037 42 | 654 56 |

*** 1 071 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 04 | 565 95 |
| 9 | 974 09 | 573 03 |
| 10 | 980 44 | 580 76 |
| 11 | 987 42 | 587 92 |
| 12 | 992 15 | 596 73 |
| 13 | 999 19 | 603 83 |
| 14 | 1005 67 | 611 45 |
| 15 | 1012 16 | 619 05 |
| 16 | 1017 96 | 627 20 |
| 17 | 1024 95 | 634 35 |
| 18 | 1028 08 | 643 85 |
| 19 | 1034 26 | 651 71 |
| 20 | 1034 46 | 653 57 |

*** 1 075 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 74 | 559 00 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 91 | 566 07 |
| 9 | 973 88 | 573 24 |
| 10 | 980 94 | 580 32 |
| 11 | 987 13 | 588 17 |
| 12 | 994 17 | 595 28 |
| 13 | 999 01 | 604 03 |

15/22

| | | |
|----|---------|--------|
| 14 | 1006 02 | 611 16 |
| 15 | 1012 22 | 619 00 |
| 16 | 1017 65 | 627 40 |
| 17 | 1021 36 | 636 69 |
| 18 | 1025 70 | 645 70 |
| 19 | 1032 66 | 652 88 |
| 20 | 1032 74 | 653 00 |

*** 1 077 ***
 Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 71 | 558 99 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 77 | 566 20 |
| 9 | 973 81 | 573 30 |
| 10 | 980 05 | 581 11 |
| 11 | 986 97 | 588 33 |
| 12 | 994 04 | 595 41 |
| 13 | 998 15 | 604 52 |
| 14 | 1005 13 | 611 69 |
| 15 | 1010 93 | 619 83 |
| 16 | 1015 61 | 628 67 |
| 17 | 1021 50 | 636 75 |
| 18 | 1026 92 | 645 15 |
| 19 | 1030 58 | 652 28 |

*** 1 079 ***
 Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 82 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 06 | 565 92 |
| 9 | 972 30 | 574 44 |
| 10 | 978 94 | 581 92 |
| 11 | 984 16 | 590 44 |
| 12 | 990 56 | 598 13 |
| 13 | 997 56 | 605 27 |
| 14 | 1004 43 | 612 54 |
| 15 | 1011 27 | 619 83 |
| 16 | 1018 27 | 626 98 |
| 17 | 1023 57 | 635 46 |
| 18 | 1028 88 | 643 93 |
| 19 | 1035 95 | 651 01 |
| 20 | 1039 21 | 655 15 |

*** 1 079 ***
 Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 60 | 558 95 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 83 | 566 14 |
| 9 | 973 63 | 573 48 |
| 10 | 980 29 | 580 93 |

10/22

| | | |
|----|---------|--------|
| 11 | 986 44 | 588 82 |
| 12 | 993 27 | 596 13 |
| 13 | 1000 10 | 603 43 |
| 14 | 1004 83 | 612 24 |
| 15 | 1011 89 | 619 32 |
| 16 | 1015 00 | 628 83 |
| 17 | 1022 01 | 635 96 |
| 18 | 1027 79 | 644 12 |
| 19 | 1030 10 | 652 12 |

*** 1 082 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 61 | 558 95 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 49 | 566 45 |
| 9 | 972 06 | 574 75 |
| 10 | 978 99 | 581 96 |
| 11 | 985 95 | 589 15 |
| 12 | 992 90 | 596 33 |
| 13 | 999 57 | 603 78 |
| 14 | 1003 98 | 612 76 |
| 15 | 1010 23 | 620 57 |
| 16 | 1017 26 | 627 68 |
| 17 | 1023 65 | 635 37 |
| 18 | 1030 72 | 642 45 |
| 19 | 1032 14 | 652 34 |
| 20 | 1032 64 | 652 96 |

*** 1 084 ***


Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 37 | 558 87 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 01 | 565 98 |
| 9 | 973 01 | 573 97 |
| 10 | 977 24 | 583 04 |
| 11 | 984 24 | 590 17 |
| 12 | 990 47 | 598 00 |
| 13 | 997 46 | 605 14 |
| 14 | 1004 10 | 612 62 |
| 15 | 1011 17 | 619 70 |
| 16 | 1017 47 | 627 46 |
| 17 | 1022 70 | 635 98 |
| 18 | 1028 48 | 644 15 |
| 19 | 1035 55 | 651 22 |
| 20 | 1039 41 | 655 22 |

*** 1 085 ***

Intermountain Regional Landfill Sliding Block

c:\program files\stedwin\lrf\23 pl2 Run By Greg Shafer, HDR 4/20/2010 04:18PM




| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Prez Surface | Load | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|------|--------|
| a | 0.83 | | | | | | | | Honz | Eqk |
| b | 0.83 | | | | | | | | 0 | 200 g< |
| c | 0.84 | UVSC | 1 | 113.6 | 121.0 | 3000.0 | 0.0 | W1 | | |
| d | 0.84 | Waste | 2 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| e | 0.84 | Liner | 3 | 50.0 | 50.0 | 0.0 | 18.0 | W1 | | |
| f | 0.84 | | | | | | | | | |
| g | 0.84 | | | | | | | | | |
| h | 0.84 | | | | | | | | | |
| i | 0.84 | | | | | | | | | |
| j | 0.84 | | | | | | | | | |

PCSTABL7 FSmin=0.83

Safety Factors Are Calculated By The Modified Janbu Method

STED



17/22

18/22

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 04 18PM
Run By Greg Shafer, HDR
Input Data Filename C 23 in
Output Filename C 23 OUT
Unit ENGLISH
Plotted Output Filename C 23 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Sliding Block

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

5 Top Boundaries
12 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 550 00 | 750 00 | 558 75 | 1 |
| 2 | 750 00 | 558 75 | 1140 00 | 688 75 | 2 |
| 3 | 1140 00 | 688 75 | 1440 00 | 688 75 | 2 |
| 4 | 1440 00 | 688 75 | 1760 00 | 608 75 | 2 |
| 5 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |
| 6 | 750 00 | 558 75 | 750 30 | 558 85 | 3 |
| 7 | 750 30 | 558 85 | 1560 00 | 558 85 | 3 |
| 8 | 1560 00 | 558 85 | 1759 90 | 608 75 | 3 |
| 9 | 1759 90 | 608 75 | 1760 00 | 608 75 | 3 |
| 10 | 750 00 | 558 75 | 1560 00 | 558 75 | 1 |
| 11 | 1560 00 | 558 75 | 1760 00 | 608 75 | 1 |
| 12 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |

ISOTROPIC SOIL PARAMETERS

3 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |
| 3 | 50 0 | 50 0 | 0 0 | 18 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient Of 0 200 Has Been Assigned
A Vertical Earthquake Loading Coefficient Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random Technique For Generating Sliding Block Surfaces, Has Been Specified

1000 Trial Surfaces Have Been Generated
6 Boxes Specified For Generation Of Central Block Base
Length Of Line Segments For Active And Passive Portions Of Sliding Block Is 10 0

| Box No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Height (ft) |
|--------|-------------|-------------|--------------|--------------|-------------|
| 1 | 751 00 | 558 84 | 751 00 | 558 84 | 0 00 |
| 2 | 800 00 | 558 84 | 800 00 | 558 84 | 0 00 |
| 3 | 850 00 | 558 84 | 850 00 | 558 84 | 0 00 |
| 4 | 900 00 | 558 84 | 900 00 | 558 84 | 0 00 |
| 5 | 950 00 | 558 84 | 950 00 | 558 84 | 0 00 |
| 6 | 960 00 | 558 84 | 960 00 | 558 84 | 0 00 |

Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Janbu Method * *
Failure Surface Specified By 20 Coordinate Points
Point X-Surf Y-Surf

19/22

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 00 | 565 99 |
| 9 | 972 39 | 574 41 |
| 10 | 979 45 | 581 49 |
| 11 | 986 45 | 588 63 |
| 12 | 993 17 | 596 04 |
| 13 | 1000 13 | 603 22 |
| 14 | 1007 18 | 610 31 |
| 15 | 1013 23 | 618 27 |
| 16 | 1019 88 | 625 74 |
| 17 | 1026 86 | 632 90 |
| 18 | 1032 31 | 641 28 |
| 19 | 1039 31 | 648 42 |
| 20 | 1041 75 | 656 00 |

*** 0 830 ***

Individual data on the 21 slices

| Slice No | Width (ft) | Weight (lbs) | Water | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake | | |
|----------|------------|--------------|-----------------|-----------------|-------------------|------------------|-----------------|-----------------|----------------------|
| | | | Force Top (lbs) | Force Bot (lbs) | | | Force Hor (lbs) | Force Ver (lbs) | Surcharge Load (lbs) |
| 1 | 0 2 | 1 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 2 | 0 0 | 0 0 |
| 2 | 0 0 | 0 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 49 0 | 20604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 4120 9 | 0 0 | 0 0 |
| 4 | 50 0 | 62274 9 | 0 0 | 0 0 | 0 0 | 0 0 | 12455 0 | 0 0 | 0 0 |
| 5 | 50 0 | 103941 6 | 0 0 | 0 0 | 0 0 | 0 0 | 20788 3 | 0 0 | 0 0 |
| 6 | 50 0 | 145608 2 | 0 0 | 0 0 | 0 0 | 0 0 | 29121 6 | 0 0 | 0 0 |
| 7 | 10 0 | 34121 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6824 3 | 0 0 | 0 0 |
| 8 | 0 0 | 34 1 | 0 0 | 0 0 | 0 0 | 0 0 | 6 8 | 0 0 | 0 0 |
| 9 | 7 0 | 23575 6 | 0 0 | 0 0 | 0 0 | 0 0 | 4715 1 | 0 0 | 0 0 |
| 10 | 5 4 | 16663 3 | 0 0 | 0 0 | 0 0 | 0 0 | 3332 7 | 0 0 | 0 0 |
| 11 | 7 1 | 19811 5 | 0 0 | 0 0 | 0 0 | 0 0 | 3962 3 | 0 0 | 0 0 |
| 12 | 7 0 | 17977 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3595 5 | 0 0 | 0 0 |
| 13 | 6 7 | 15558 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3111 7 | 0 0 | 0 0 |
| 14 | 7 0 | 14385 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2877 1 | 0 0 | 0 0 |
| 15 | 7 1 | 12879 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2575 9 | 0 0 | 0 0 |
| 16 | 6 1 | 9449 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1889 9 | 0 0 | 0 0 |
| 17 | 6 6 | 8500 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1700 0 | 0 0 | 0 0 |
| 18 | 7 0 | 7178 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1435 7 | 0 0 | 0 0 |
| 19 | 5 5 | 4050 2 | 0 0 | 0 0 | 0 0 | 0 0 | 810 0 | 0 0 | 0 0 |
| 20 | 7 0 | 3208 7 | 0 0 | 0 0 | 0 0 | 0 0 | 641 7 | 0 0 | 0 0 |
| 21 | 2 4 | 411 4 | 0 0 | 0 0 | 0 0 | 0 0 | 82 3 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 09 | 566 78 |
| 9 | 972 91 | 574 08 |
| 10 | 978 87 | 582 11 |
| 11 | 985 69 | 589 43 |
| 12 | 991 48 | 597 58 |
| 13 | 998 08 | 605 09 |
| 14 | 1004 94 | 612 37 |
| 15 | 1012 01 | 619 44 |
| 16 | 1019 08 | 626 51 |
| 17 | 1026 15 | 633 59 |

20/22

| | | |
|---|-------------|-------------|
| 18 | 1033 20 | 640 68 |
| 19 | 1038 93 | 648 87 |
| 20 | 1044 53 | 656 93 |
| *** | 0 833 | *** |
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 96 | 566 02 |
| 9 | 972 37 | 574 43 |
| 10 | 977 89 | 582 77 |
| 11 | 984 95 | 589 85 |
| 12 | 992 02 | 596 92 |
| 13 | 998 89 | 604 19 |
| 14 | 1005 95 | 611 27 |
| 15 | 1012 08 | 619 17 |
| 16 | 1018 78 | 626 59 |
| 17 | 1024 95 | 634 47 |
| 18 | 1030 69 | 642 65 |
| 19 | 1036 37 | 650 88 |
| 20 | 1036 89 | 654 38 |
| *** | 0 836 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 99 | 565 99 |
| 9 | 974 05 | 573 08 |
| 10 | 979 99 | 581 12 |
| 11 | 986 46 | 588 74 |
| 12 | 992 33 | 596 84 |
| 13 | 997 72 | 605 26 |
| 14 | 1004 76 | 612 36 |
| 15 | 1011 22 | 620 00 |
| 16 | 1018 02 | 627 33 |
| 17 | 1024 85 | 634 63 |
| 18 | 1031 80 | 641 83 |
| 19 | 1038 73 | 649 03 |
| 20 | 1038 81 | 655 02 |
| *** | 0 837 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 98 | 566 00 |
| 9 | 972 83 | 574 11 |
| 10 | 979 85 | 581 24 |
| 11 | 985 80 | 589 27 |
| 12 | 992 85 | 596 36 |
| 13 | 999 92 | 603 43 |

2/22

| | | |
|----|---------|--------|
| 14 | 1005 88 | 611 47 |
| 15 | 1012 34 | 619 10 |
| 16 | 1016 21 | 628 32 |
| 17 | 1022 75 | 635 89 |
| 18 | 1029 67 | 643 11 |
| 19 | 1034 59 | 651 81 |
| 20 | 1034 59 | 653 61 |

*** 0 838 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 17 | 566 71 |
| 9 | 973 11 | 573 91 |
| 10 | 980 18 | 580 99 |
| 11 | 987 03 | 588 27 |
| 12 | 994 10 | 595 34 |
| 13 | 1000 41 | 603 10 |
| 14 | 1007 31 | 610 33 |
| 15 | 1011 73 | 619 31 |
| 16 | 1015 48 | 628 58 |
| 17 | 1022 13 | 636 04 |
| 18 | 1028 64 | 643 63 |
| 19 | 1030 87 | 652 38 |

*** 0 840 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 82 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 84 | 566 14 |
| 9 | 973 87 | 573 25 |
| 10 | 980 90 | 580 36 |
| 11 | 987 03 | 588 26 |
| 12 | 992 93 | 596 33 |
| 13 | 999 90 | 603 50 |
| 14 | 1004 94 | 612 14 |
| 15 | 1011 74 | 619 48 |
| 16 | 1018 69 | 626 66 |
| 17 | 1024 54 | 634 77 |
| 18 | 1026 24 | 644 63 |
| 19 | 1032 55 | 652 38 |
| 20 | 1033 11 | 653 12 |

*** 0 840 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 66 | 558 97 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 70 | 566 26 |
| 9 | 973 14 | 573 91 |
| 10 | 979 70 | 581 46 |

| | | |
|----|---------|--------|
| 11 | 986 77 | 588 53 |
| 12 | 992 71 | 596 58 |
| 13 | 999 27 | 604 12 |
| 14 | 1004 68 | 612 54 |
| 15 | 1008 95 | 621 58 |
| 16 | 1015 71 | 628 95 |
| 17 | 1020 46 | 637 75 |
| 18 | 1027 53 | 644 82 |
| 19 | 1034 58 | 651 91 |
| 20 | 1035 07 | 653 77 |

*** 0 842 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 49 | 558 91 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 72 | 566 25 |
| 9 | 973 01 | 574 02 |
| 10 | 980 01 | 581 16 |
| 11 | 987 06 | 588 25 |
| 12 | 993 57 | 595 84 |
| 13 | 997 83 | 604 89 |
| 14 | 1002 99 | 613 46 |
| 15 | 1009 75 | 620 83 |
| 16 | 1016 68 | 628 03 |
| 17 | 1022 52 | 635 15 |
| 18 | 1029 27 | 643 53 |
| 19 | 1031 89 | 652 71 |


*** 0 842 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 965 59 | 566 36 |
| 9 | 973 16 | 573 90 |
| 10 | 979 21 | 581 86 |
| 11 | 986 24 | 588 98 |
| 12 | 991 11 | 597 71 |
| 13 | 997 67 | 605 26 |
| 14 | 1003 09 | 613 66 |
| 15 | 1010 12 | 620 78 |
| 16 | 1016 97 | 628 06 |
| 17 | 1022 16 | 636 61 |
| 18 | 1026 22 | 645 75 |
| 19 | 1026 69 | 650 98 |


*** 0 844 ***

**ATTACHMENT 2C-2: SLOPE STABILITY RUNS &
RESULTS – FILL SLOPE**



⑤
 $\gamma = 50 \text{ PLF}$
 $C = 150 \text{ PSF}$
 $\phi = 22^\circ$

| Horizontal Accel. | α | F.S. |
|-------------------|----------|------|
| Static | | 2.18 |
| 0.1 | | 1.75 |
| 0.2 | | 1.33 |
| 0.3 | | 0.94 |



1" = 200' H
 1" = 50' V

$\frac{-0.033}{0.39} = 0.2 - x$
 $x = 0.28$

$\rightarrow \frac{1.33 - 0.94}{0.2 - 0.3} = \frac{1.33 - 1.0}{0.2 - x} \rightarrow \frac{0.39}{-0.1} = \frac{0.33}{0.2 - x}$

| | | | | | |
|---------|-----------------|----------|-----|------|------------------|
| Project | IRL | Computed | GMS | Date | 3/2010 4/2010 |
| Subject | Slope Stability | Checked | | Date | |
| Task | Waste mass | Page | 2 | of | 46 |
| Job # | 125184 | Dept | 143 | No | |

Maximum Fill Slope Results / Displacement

$$a_{max} = 0.28 \text{ (Reference E)}$$

$$a_y = 0.28 \text{ (Previous page)}$$


$$\frac{a_y}{a_{max}} = \frac{0.28}{0.28} = 1.0 \quad @ \quad M=70$$

See Attachment 273 (Reference A)

$$U_{max} = 0.05 \text{ cm} < 30 \text{ cm (allowable)} \quad \underline{\underline{OK}}$$

Intermountain Regional Landfill Fill Slope 1

c:\program files\stedwin\l11 pi2 Run By Greg Shafer HDR 4/20/2010 03 35PM




| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|
| a | 2.18 | | | | | | | |
| b | 2.20 | | | | | | | |
| c | 2.21 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 |
| d | 2.22 | LSC | 2 | 121.0 | 125.5 | 1500.0 | 0.0 | W1 |
| e | 2.23 | SC | 3 | 121.0 | 125.5 | 2000.0 | 0.0 | W1 |
| f | 2.23 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | 0.0 | W1 |
| g | 2.23 | Waste | 5 | 50.0 | 60.0 | 150.0 | 22.0 | W1 |
| h | 2.24 | | | | | | | |
| i | 2.24 | | | | | | | |

PCSTABL7 FSmin=2.18

Safety Factors Are Calculated By The Modified Bishop Method

STED



3/46

4/26

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 35PM
Run By Greg Shafer, HDR
Input Data Filename C 11 in
Output Filename C 11 OUT
Unit ENGLISH
Plotted Output Filename C 11 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 600 00 ft
and X = 850 00 ft

Each Surface Terminates Between X =1100 00 ft
and X =1250 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 47 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 92 | 619 02 |
| 3 | 775 65 | 616 69 |
| 4 | 785 42 | 614 58 |
| 5 | 795 24 | 612 67 |
| 6 | 805 10 | 610 99 |
| 7 | 814 99 | 609 52 |
| 8 | 824 91 | 608 26 |
| 9 | 834 85 | 607 22 |
| 10 | 844 82 | 606 40 |

5/40

| | | |
|----|---------|--------|
| 11 | 854 80 | 605 80 |
| 12 | 864 79 | 605 42 |
| 13 | 874 79 | 605 25 |
| 14 | 884 79 | 605 30 |
| 15 | 894 79 | 605 58 |
| 16 | 904 78 | 606 07 |
| 17 | 914 75 | 606 77 |
| 18 | 924 71 | 607 70 |
| 19 | 934 64 | 608 84 |
| 20 | 944 55 | 610 20 |
| 21 | 954 43 | 611 78 |
| 22 | 964 26 | 613 57 |
| 23 | 974 06 | 615 57 |
| 24 | 983 81 | 617 79 |
| 25 | 993 51 | 620 23 |
| 26 | 1003 16 | 622 87 |
| 27 | 1012 74 | 625 72 |
| 28 | 1022 26 | 628 78 |
| 29 | 1031 71 | 632 05 |
| 30 | 1041 09 | 635 53 |
| 31 | 1050 39 | 639 21 |
| 32 | 1059 60 | 643 09 |
| 33 | 1068 73 | 647 17 |
| 34 | 1077 77 | 651 45 |
| 35 | 1086 71 | 655 93 |
| 36 | 1095 55 | 660 60 |
| 37 | 1104 29 | 665 46 |
| 38 | 1112 92 | 670 51 |
| 39 | 1121 44 | 675 75 |
| 40 | 1129 84 | 681 18 |
| 41 | 1138 12 | 586 78 |
| 42 | 1146 27 | 692 57 |
| 43 | 1154 30 | 698 53 |
| 44 | 1162 20 | 704 67 |
| 45 | 1169 96 | 710 98 |
| 46 | 1177 58 | 717 46 |
| 47 | 1182 47 | 721 80 |

Circle Center At X = 877 4 , Y = 1062 9 and Radius, 457 7

*** 2 184 ***

Individual data on the 47 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 7 | 1199 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 9 7 | 3568 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 9 8 | 5863 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 9 8 | 8078 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 9 9 | 10206 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 9 9 | 12244 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 9 9 | 14185 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 9 9 | 16026 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 10 0 | 17762 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 10 0 | 19389 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 10 0 | 20904 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 12 | 10 0 | 22303 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 10 0 | 23584 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 10 0 | 24744 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 10 0 | 25781 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 10 0 | 26693 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 10 0 | 27479 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 9 9 | 28138 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 9 9 | 28670 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 9 9 | 29073 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 9 8 | 29349 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 22 | 9 8 | 29497 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 23 | 9 8 | 29520 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 24 | 9 7 | 29417 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

6/46

| | | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|-----|-----|-----|-----|
| 25 | 9 6 | 29191 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 26 | 9 6 | 28845 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 27 | 9 5 | 28379 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 28 | 9 5 | 27797 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 29 | 9 4 | 27103 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 30 | 9 3 | 26300 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 31 | 9 2 | 25391 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 32 | 9 1 | 24381 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 33 | 9 0 | 23273 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 34 | 8 9 | 22074 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 35 | 8 8 | 20789 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 36 | 8 7 | 19421 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 37 | 8 6 | 17978 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 38 | 8 5 | 16465 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 39 | 8 4 | 14888 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 40 | 8 3 | 13254 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 41 | 8 2 | 11570 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 42 | 3 7 | 4764 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 43 | 4 3 | 4986 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 44 | 7 9 | 7443 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 45 | 7 8 | 5070 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 46 | 7 6 | 2706 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 47 | 4 9 | 499 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 83 | 624 51 |
| 3 | 796 61 | 622 47 |
| 4 | 806 44 | 620 63 |
| 5 | 816 31 | 619 01 |
| 6 | 826 21 | 617 61 |
| 7 | 836 14 | 616 42 |
| 8 | 846 10 | 615 45 |
| 9 | 856 07 | 614 69 |
| 10 | 866 05 | 614 15 |
| 11 | 876 05 | 613 83 |
| 12 | 886 05 | 613 72 |
| 13 | 896 05 | 613 84 |
| 14 | 906 04 | 614 16 |
| 15 | 916 03 | 614 71 |
| 16 | 926 00 | 615 47 |
| 17 | 935 95 | 616 45 |
| 18 | 945 88 | 617 65 |
| 19 | 955 78 | 619 06 |
| 20 | 965 64 | 620 69 |
| 21 | 975 47 | 622 53 |
| 22 | 985 26 | 624 58 |
| 23 | 995 00 | 626 84 |
| 24 | 1004 69 | 629 32 |
| 25 | 1014 32 | 632 01 |
| 26 | 1023 89 | 634 90 |
| 27 | 1033 40 | 638 00 |
| 28 | 1042 84 | 641 31 |
| 29 | 1052 20 | 644 82 |
| 30 | 1061 48 | 648 54 |
| 31 | 1070 69 | 652 45 |
| 32 | 1079 80 | 656 57 |
| 33 | 1088 82 | 660 88 |
| 34 | 1097 75 | 665 39 |
| 35 | 1106 58 | 670 09 |
| 36 | 1115 30 | 674 98 |
| 37 | 1123 91 | 680 05 |
| 38 | 1132 41 | 685 32 |
| 39 | 1140 80 | 690 77 |
| 40 | 1149 07 | 696 40 |
| 41 | 1157 21 | 702 20 |
| 42 | 1165 22 | 708 19 |

7/26

43 1173 10 714 34
 44 1180 85 720 67
 45 1182 16 721 79
 Circle Center At X = 885 9 , Y = 1073 9 and Radius, 460 2
 *** 2 200 ***

Failure Surface Specified By 46 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 16 | 621 03 |
| 3 | 785 74 | 618 15 |
| 4 | 795 38 | 615 50 |
| 5 | 805 09 | 613 11 |
| 6 | 814 86 | 610 96 |
| 7 | 824 68 | 609 07 |
| 8 | 834 54 | 607 42 |
| 9 | 844 44 | 606 03 |
| 10 | 854 38 | 604 89 |
| 11 | 864 34 | 604 01 |
| 12 | 874 32 | 603 38 |
| 13 | 884 31 | 603 01 |
| 14 | 894 31 | 602 89 |
| 15 | 904 31 | 603 03 |
| 16 | 914 30 | 603 43 |
| 17 | 924 28 | 604 08 |
| 18 | 934 24 | 604 98 |
| 19 | 944 17 | 606 14 |
| 20 | 954 07 | 607 56 |
| 21 | 963 93 | 609 22 |
| 22 | 973 75 | 611 14 |
| 23 | 983 51 | 613 31 |
| 24 | 993 21 | 615 73 |
| 25 | 1002 85 | 618 39 |
| 26 | 1012 42 | 621 31 |
| 27 | 1021 91 | 624 46 |
| 28 | 1031 31 | 627 86 |
| 29 | 1040 63 | 631 49 |
| 30 | 1049 85 | 635 36 |
| 31 | 1058 97 | 639 47 |
| 32 | 1067 98 | 643 81 |
| 33 | 1076 87 | 648 38 |
| 34 | 1085 65 | 653 17 |
| 35 | 1094 30 | 658 19 |
| 36 | 1102 82 | 663 43 |
| 37 | 1111 20 | 668 88 |
| 38 | 1119 44 | 674 55 |
| 39 | 1127 53 | 680 42 |
| 40 | 1135 47 | 686 50 |
| 41 | 1143 25 | 692 78 |
| 42 | 1150 87 | 699 26 |
| 43 | 1158 32 | 705 93 |
| 44 | 1165 60 | 712 79 |
| 45 | 1172 70 | 719 83 |
| 46 | 1174 14 | 721 34 |

Circle Center At X = 893 9 , Y = 993 7 and Radius, 390 8
 *** 2 214 ***

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 70 | 618 30 |
| 3 | 775 24 | 615 30 |
| 4 | 784 86 | 612 56 |
| 5 | 794 55 | 610 09 |
| 6 | 804 30 | 607 87 |
| 7 | 814 11 | 605 92 |
| 8 | 823 97 | 604 24 |
| 9 | 833 87 | 602 83 |

8/46

| | | |
|----|---------|--------|
| 10 | 843 80 | 601 69 |
| 11 | 853 76 | 600 81 |
| 12 | 863 75 | 600 21 |
| 13 | 873 74 | 599 88 |
| 14 | 883 74 | 599 82 |
| 15 | 893 74 | 600 04 |
| 16 | 903 73 | 600 52 |
| 17 | 913 70 | 601 28 |
| 18 | 923 64 | 602 30 |
| 19 | 933 56 | 603 60 |
| 20 | 943 44 | 605 16 |
| 21 | 953 27 | 607 00 |
| 22 | 963 04 | 609 10 |
| 23 | 972 76 | 611 46 |
| 24 | 982 41 | 614 09 |
| 25 | 991 98 | 616 98 |
| 26 | 1001 47 | 620 13 |
| 27 | 1010 88 | 623 53 |
| 28 | 1020 18 | 627 19 |
| 29 | 1029 39 | 631 10 |
| 30 | 1038 48 | 635 26 |
| 31 | 1047 46 | 639 66 |
| 32 | 1056 32 | 644 31 |
| 33 | 1065 04 | 649 19 |
| 34 | 1073 63 | 654 31 |
| 35 | 1082 08 | 659 67 |
| 36 | 1090 38 | 665 25 |
| 37 | 1098 52 | 671 05 |
| 38 | 1106 50 | 677 07 |
| 39 | 1114 32 | 683 31 |
| 40 | 1121 96 | 689 75 |
| 41 | 1129 43 | 696 41 |
| 42 | 1136 71 | 703 26 |
| 43 | 1143 81 | 710 31 |
| 44 | 1150 71 | 717 55 |
| 45 | 1153 08 | 720 17 |

Circle Center At X = 880 9 , Y = 967 8 and Radius, 368 0
 *** 2 219 ***

Failure Surface Specified By 42 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 57 | 622 80 |
| 3 | 786 51 | 621 63 |
| 4 | 796 46 | 620 65 |
| 5 | 806 43 | 619 86 |
| 6 | 816 41 | 619 27 |
| 7 | 826 40 | 618 86 |
| 8 | 836 40 | 618 65 |
| 9 | 846 40 | 618 63 |
| 10 | 856 40 | 618 80 |
| 11 | 866 39 | 619 16 |
| 12 | 876 37 | 619 71 |
| 13 | 886 35 | 620 46 |
| 14 | 896 30 | 621 40 |
| 15 | 906 24 | 622 53 |
| 16 | 916 15 | 623 85 |
| 17 | 926 04 | 625 36 |
| 18 | 935 89 | 627 06 |
| 19 | 945 71 | 628 94 |
| 20 | 955 49 | 631 02 |
| 21 | 965 23 | 633 29 |
| 22 | 974 93 | 635 74 |
| 23 | 984 57 | 638 37 |
| 24 | 994 17 | 641 20 |
| 25 | 1003 71 | 644 20 |
| 26 | 1013 18 | 647 39 |
| 27 | 1022 60 | 650 76 |

9/26

| | | |
|----|---------|--------|
| 28 | 1031 95 | 654 31 |
| 29 | 1041 23 | 658 04 |
| 30 | 1050 43 | 661 94 |
| 31 | 1059 56 | 666 03 |
| 32 | 1068 61 | 670 28 |
| 33 | 1077 57 | 674 71 |
| 34 | 1086 45 | 679 32 |
| 35 | 1095 24 | 684 09 |
| 36 | 1103 94 | 689 03 |
| 37 | 1112 53 | 694 13 |
| 38 | 1121 03 | 699 40 |
| 39 | 1129 43 | 704 83 |
| 40 | 1137 72 | 710 43 |
| 41 | 1145 90 | 716 18 |
| 42 | 1151 22 | 720 07 |

Circle Center At X = 842 5 , Y = 1139 0 and Radius, 520 3
 *** 2 227 ***

Failure Surface Specified By 40 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 33 | 621 61 |
| 3 | 786 07 | 619 30 |
| 4 | 795 85 | 617 26 |
| 5 | 805 69 | 615 48 |
| 6 | 815 58 | 613 96 |
| 7 | 825 50 | 612 70 |
| 8 | 835 45 | 611 71 |
| 9 | 845 42 | 610 99 |
| 10 | 855 41 | 610 53 |
| 11 | 865 41 | 610 33 |
| 12 | 875 41 | 610 40 |
| 13 | 885 41 | 610 74 |
| 14 | 895 39 | 611 35 |
| 15 | 905 35 | 612 22 |
| 16 | 915 28 | 613 35 |
| 17 | 925 19 | 614 75 |
| 18 | 935 05 | 616 41 |
| 19 | 944 86 | 618 33 |
| 20 | 954 62 | 620 52 |
| 21 | 964 32 | 622 96 |
| 22 | 973 94 | 625 66 |
| 23 | 983 50 | 628 62 |
| 24 | 992 97 | 631 82 |
| 25 | 1002 35 | 635 28 |
| 26 | 1011 64 | 638 99 |
| 27 | 1020 82 | 642 94 |
| 28 | 1029 90 | 647 14 |
| 29 | 1038 86 | 651 58 |
| 30 | 1047 70 | 656 25 |
| 31 | 1056 42 | 661 16 |
| 32 | 1065 00 | 666 30 |
| 33 | 1073 44 | 671 66 |
| 34 | 1081 73 | 677 25 |
| 35 | 1089 87 | 683 05 |
| 36 | 1097 86 | 689 07 |
| 37 | 1105 68 | 695 30 |
| 38 | 1113 33 | 701 74 |
| 39 | 1120 81 | 708 38 |
| 40 | 1127 11 | 714 28 |

Circle Center At X = 867 7 , Y = 986 0 and Radius, 375 6
 *** 2 233 ***

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 06 | 626 45 |
| 3 | 806 69 | 623 75 |

10/
16

| | | |
|----|---------|--------|
| 4 | 816 39 | 621 30 |
| 5 | 826 14 | 619 09 |
| 6 | 835 95 | 517 13 |
| 7 | 845 80 | 615 41 |
| 8 | 855 69 | 613 93 |
| 9 | 865 61 | 612 70 |
| 10 | 875 56 | 611 72 |
| 11 | 885 54 | 610 99 |
| 12 | 895 52 | 610 50 |
| 13 | 905 52 | 610 26 |
| 14 | 915 52 | 610 28 |
| 15 | 925 52 | 610 54 |
| 16 | 935 51 | 611 05 |
| 17 | 945 48 | 611 80 |
| 18 | 955 43 | 612 81 |
| 19 | 965 35 | 614 06 |
| 20 | 975 23 | 615 56 |
| 21 | 985 08 | 617 30 |
| 22 | 994 88 | 619 29 |
| 23 | 1004 63 | 621 52 |
| 24 | 1014 32 | 624 00 |
| 25 | 1023 94 | 626 71 |
| 26 | 1033 50 | 629 67 |
| 27 | 1042 97 | 632 85 |
| 28 | 1052 37 | 636 28 |
| 29 | 1061 68 | 639 94 |
| 30 | 1070 89 | 643 82 |
| 31 | 1080 00 | 647 94 |
| 32 | 1089 01 | 652 28 |
| 33 | 1097 91 | 656 84 |
| 34 | 1106 69 | 661 63 |
| 35 | 1115 35 | 666 63 |
| 36 | 1123 89 | 671 84 |
| 37 | 1132 29 | 677 27 |
| 38 | 1140 55 | 682 90 |
| 39 | 1148 67 | 688 74 |
| 40 | 1156 64 | 694 77 |
| 41 | 1164 46 | 701 00 |
| 42 | 1172 12 | 707 43 |
| 43 | 1179 62 | 714 04 |
| 44 | 1186 96 | 720 84 |
| 45 | 1188 28 | 722 13 |

Circle Center At X = 910 0 , Y = 1012 2 and Radius, 401 9
*** 2 233 ***

Failure Surface Specified By 40 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 47 | 622 17 |
| 3 | 786 31 | 620 41 |
| 4 | 796 19 | 618 89 |
| 5 | 806 11 | 617 61 |
| 6 | 816 06 | 616 56 |
| 7 | 826 02 | 615 76 |
| 8 | 836 01 | 615 19 |
| 9 | 846 00 | 614 87 |
| 10 | 856 00 | 614 78 |
| 11 | 866 00 | 614 94 |
| 12 | 875 99 | 615 33 |
| 13 | 885 97 | 615 97 |
| 14 | 895 93 | 616 85 |
| 15 | 905 87 | 617 97 |
| 16 | 915 78 | 619 32 |
| 17 | 925 65 | 620 92 |
| 18 | 935 48 | 622 75 |
| 19 | 945 27 | 624 81 |
| 20 | 955 00 | 627 11 |
| 21 | 964 67 | 629 65 |

11/26

| | | |
|----|---------|--------|
| 22 | 974 28 | 632 42 |
| 23 | 983 82 | 635 41 |
| 24 | 993 29 | 638 64 |
| 25 | 1002 67 | 642 09 |
| 26 | 1011 97 | 645 77 |
| 27 | 1021 18 | 649 67 |
| 28 | 1030 29 | 653 79 |
| 29 | 1039 30 | 658 13 |
| 30 | 1048 20 | 662 69 |
| 31 | 1055 99 | 667 45 |
| 32 | 1065 67 | 672 43 |
| 33 | 1074 22 | 677 62 |
| 34 | 1082 64 | 683 00 |
| 35 | 1090 93 | 688 59 |
| 36 | 1099 09 | 694 38 |
| 37 | 1107 10 | 700 37 |
| 38 | 1114 97 | 706 54 |
| 39 | 1122 68 | 712 90 |
| 40 | 1123 12 | 713 28 |

Circle Center At X = 854 5 , Y = 1030 3 and Radius, 415 5
*** 2 240 ***

Failure Surface Specified By 40 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 48 | 629 06 |
| 3 | 817 12 | 626 41 |
| 4 | 826 84 | 624 04 |
| 5 | 836 62 | 621 94 |
| 6 | 846 45 | 620 12 |
| 7 | 856 33 | 618 58 |
| 8 | 866 25 | 617 32 |
| 9 | 876 20 | 616 35 |
| 10 | 886 18 | 615 65 |
| 11 | 896 17 | 615 24 |
| 12 | 906 17 | 615 11 |
| 13 | 916 17 | 615 27 |
| 14 | 926 16 | 615 71 |
| 15 | 936 13 | 616 43 |
| 16 | 946 08 | 617 43 |
| 17 | 956 00 | 618 72 |
| 18 | 965 88 | 620 29 |
| 19 | 975 70 | 622 13 |
| 20 | 985 48 | 624 26 |
| 21 | 995 18 | 626 66 |
| 22 | 1004 82 | 629 33 |
| 23 | 1014 37 | 632 28 |
| 24 | 1023 84 | 635 50 |
| 25 | 1033 22 | 638 98 |
| 26 | 1042 49 | 642 73 |
| 27 | 1051 65 | 646 74 |
| 28 | 1060 69 | 651 00 |
| 29 | 1069 61 | 655 53 |
| 30 | 1078 40 | 660 30 |
| 31 | 1087 05 | 665 32 |
| 32 | 1095 55 | 670 59 |
| 33 | 1103 90 | 676 09 |
| 34 | 1112 09 | 681 83 |
| 35 | 1120 11 | 687 79 |
| 36 | 1127 97 | 693 98 |
| 37 | 1135 64 | 700 40 |
| 38 | 1143 13 | 707 02 |
| 39 | 1150 43 | 713 86 |
| 40 | 1157 01 | 720 39 |

Circle Center At X = 905 7 , Y = 967 7 and Radius, 352 6
*** 2 241 ***

Failure Surface Specified By 41 Coordinate Points

| Point | X-Surf | Y-Surf |
|-------|--------|--------|
|-------|--------|--------|


12/10

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 777 08 | 626 77 |
| 2 | 787 00 | 625 49 |
| 3 | 796 94 | 624 40 |
| 4 | 806 90 | 623 50 |
| 5 | 816 88 | 622 80 |
| 6 | 826 86 | 622 29 |
| 7 | 836 86 | 621 97 |
| 8 | 846 86 | 621 84 |
| 9 | 856 86 | 621 90 |
| 10 | 866 85 | 622 16 |
| 11 | 876 84 | 622 61 |
| 12 | 886 82 | 623 26 |
| 13 | 896 79 | 624 09 |
| 14 | 906 74 | 625 12 |
| 15 | 916 66 | 626 34 |
| 16 | 926 56 | 627 75 |
| 17 | 936 43 | 629 35 |
| 18 | 946 27 | 631 14 |
| 19 | 956 07 | 633 12 |
| 20 | 965 83 | 635 29 |
| 21 | 975 55 | 637 64 |
| 22 | 985 22 | 640 18 |
| 23 | 994 85 | 642 91 |
| 24 | 1004 41 | 645 83 |
| 25 | 1013 92 | 648 92 |
| 26 | 1023 37 | 652 21 |
| 27 | 1032 75 | 655 67 |
| 28 | 1042 06 | 659 31 |
| 29 | 1051 30 | 663 13 |
| 30 | 1060 47 | 667 13 |
| 31 | 1069 56 | 671 30 |
| 32 | 1078 56 | 675 65 |
| 33 | 1087 48 | 680 17 |
| 34 | 1096 31 | 684 87 |
| 35 | 1105 05 | 689 73 |
| 36 | 1113 69 | 694 76 |
| 37 | 1122 24 | 699 95 |
| 38 | 1130 68 | 705 31 |
| 39 | 1139 02 | 710 83 |
| 40 | 1147 25 | 716 51 |
| 41 | 1152 28 | 720 13 |

Circle Center At X = 848 5 , Y = 1140 6 and Radius, 518 8
*** 2 244 ***

Intermountain Regional Landfill Fill Slope 1

c:\program files\stedwin\lrl\12 pl2 Run By Greg Shafer, HDR 4/20/2010 03:39PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt. (pcf) | Saturated Unit Wt. (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface | Load | Value |
|---|------|-----------|-----------|----------------------|--------------------------|--------------------------|----------------------|--------------|----------|----------|
| a | 1.53 | | | | | | | | | |
| b | 1.54 | | | | | | | | | |
| c | 1.54 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 | Honz Eqk | 0.100 g< |
| d | 1.55 | LSC | 2 | 121.0 | 125.5 | 1500.0 | 0.0 | W1 | | |
| e | 1.55 | SC | 3 | 121.0 | 125.5 | 2000.0 | 0.0 | W1 | | |
| f | 1.55 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | 0.0 | W1 | | |
| g | 1.55 | Waste | 5 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| h | 1.55 | | | | | | | | | |
| i | 1.55 | | | | | | | | | |
| 1 | 1.55 | | | | | | | | | |

PCSTABL7 FSmin=1.53

Safety Factors Are Calculated By The Modified Bishop Method

STED



13/A6

**** PCSTABL7 ****

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 39PM
Run By Greg Shafer, HDR
Input Data Filename C 12 in
Output Filename C 12 OUT
Unit ENGLISH
Plotted Output Filename C 12 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient

Of 0 100 Has Been Assigned

A Vertical Earthquake Loading Coefficient

Of 0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced

Along The Ground Surface Between X = 600 00 ft
and X = 850 00 ft

Each Surface Terminates Between X =1100 00 ft
and X =1250 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation

At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 11 | 619 87 |
| 3 | 775 99 | 618 37 |
| 4 | 785 91 | 617 06 |
| 5 | 795 84 | 615 93 |

15/A6

| | | |
|----|---------|--------|
| 6 | 805 80 | 615 00 |
| 7 | 815 77 | 614 27 |
| 8 | 825 76 | 613 72 |
| 9 | 835 75 | 613 36 |
| 10 | 845 75 | 613 20 |
| 11 | 855 75 | 613 23 |
| 12 | 865 75 | 613 45 |
| 13 | 875 74 | 613 87 |
| 14 | 885 72 | 614 47 |
| 15 | 895 69 | 615 27 |
| 16 | 905 64 | 616 26 |
| 17 | 915 57 | 617 44 |
| 18 | 925 48 | 618 81 |
| 19 | 935 35 | 620 37 |
| 20 | 945 20 | 622 12 |
| 21 | 955 01 | 624 06 |
| 22 | 964 78 | 626 18 |
| 23 | 974 51 | 628 50 |
| 24 | 984 19 | 631 00 |
| 25 | 993 82 | 633 68 |
| 26 | 1003 40 | 636 56 |
| 27 | 1012 92 | 639 61 |
| 28 | 1022 39 | 642 85 |
| 29 | 1031 78 | 646 26 |
| 30 | 1041 11 | 649 86 |
| 31 | 1050 37 | 653 64 |
| 32 | 1059 56 | 557 59 |
| 33 | 1068 67 | 661 72 |
| 34 | 1077 69 | 666 03 |
| 35 | 1086 63 | 670 50 |
| 36 | 1095 49 | 675 15 |
| 37 | 1104 25 | 679 97 |
| 38 | 1112 92 | 684 95 |
| 39 | 1121 49 | 690 10 |
| 40 | 1129 96 | 695 42 |
| 41 | 1138 33 | 700 89 |
| 42 | 1146 59 | 706 53 |
| 43 | 1154 74 | 712 32 |
| 44 | 1162 78 | 718 27 |
| 45 | 1166 19 | 720 90 |

Circle Center At X = 849 2 , Y = 1133 5 and Radius, 520 4
 *** 1 528 ***

Individual data on the 45 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force Surcharge | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|----------------------------|-----------|------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | Load (lbs) |
| 1 | 9 9 | 1024 0 | 0 0 | 0 0 | 0 0 | 0 0 | 102 4 | 0 0 | 0 0 |
| 2 | 9 9 | 3036 7 | 0 0 | 0 0 | 0 0 | 0 0 | 303 7 | 0 0 | 0 0 |
| 3 | 9 9 | 4969 3 | 0 0 | 0 0 | 0 0 | 0 0 | 496 9 | 0 0 | 0 0 |
| 4 | 9 9 | 6818 5 | 0 0 | 0 0 | 0 0 | 0 0 | 681 8 | 0 0 | 0 0 |
| 5 | 10 0 | 8580 7 | 0 0 | 0 0 | 0 0 | 0 0 | 858 1 | 0 0 | 0 0 |
| 6 | 10 0 | 10252 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1025 3 | 0 0 | 0 0 |
| 7 | 10 0 | 11831 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1183 2 | 0 0 | 0 0 |
| 8 | 10 0 | 13315 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1331 5 | 0 0 | 0 0 |
| 9 | 10 0 | 14700 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1470 1 | 0 0 | 0 0 |
| 10 | 10 0 | 15985 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1598 6 | 0 0 | 0 0 |
| 11 | 10 0 | 17169 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1716 9 | 0 0 | 0 0 |
| 12 | 10 0 | 18248 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1824 8 | 0 0 | 0 0 |
| 13 | 10 0 | 19221 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1922 2 | 0 0 | 0 0 |
| 14 | 10 0 | 20089 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2008 9 | 0 0 | 0 0 |
| 15 | 10 0 | 20849 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2084 9 | 0 0 | 0 0 |
| 16 | 9 9 | 21501 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2150 1 | 0 0 | 0 0 |
| 17 | 9 9 | 22044 9 | 0 0 | 0 0 | 0 0 | 0 0 | 2204 5 | 0 0 | 0 0 |
| 18 | 9 9 | 22479 7 | 0 0 | 0 0 | 0 0 | 0 0 | 2248 0 | 0 0 | 0 0 |
| 19 | 9 8 | 22806 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2280 6 | 0 0 | 0 0 |
| 20 | 9 8 | 23024 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2302 5 | 0 0 | 0 0 |
| 21 | 9 8 | 23135 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2313 6 | 0 0 | 0 0 |

16/16

| | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|--------|-----|-----|
| 22 | 9 7 | 23140 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2314 0 | 0 0 | 0 0 |
| 23 | 9 7 | 23039 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2303 9 | 0 0 | 0 0 |
| 24 | 9 6 | 22834 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2283 4 | 0 0 | 0 0 |
| 25 | 9 6 | 22526 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2252 7 | 0 0 | 0 0 |
| 26 | 9 5 | 22119 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2211 9 | 0 0 | 0 0 |
| 27 | 9 5 | 21613 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2161 3 | 0 0 | 0 0 |
| 28 | 9 4 | 21011 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2101 1 | 0 0 | 0 0 |
| 29 | 9 3 | 20315 7 | 0 0 | 0 0 | 0 0 | 0 0 | 2031 6 | 0 0 | 0 0 |
| 30 | 9 3 | 19530 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1953 0 | 0 0 | 0 0 |
| 31 | 9 2 | 18656 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1865 7 | 0 0 | 0 0 |
| 32 | 9 1 | 17699 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1770 0 | 0 0 | 0 0 |
| 33 | 9 0 | 16662 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1666 2 | 0 0 | 0 0 |
| 34 | 8 9 | 15547 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1554 7 | 0 0 | 0 0 |
| 35 | 8 9 | 14360 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1436 0 | 0 0 | 0 0 |
| 36 | 8 8 | 13103 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1310 4 | 0 0 | 0 0 |
| 37 | 8 7 | 11783 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1178 3 | 0 0 | 0 0 |
| 38 | 8 6 | 10402 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1040 3 | 0 0 | 0 0 |
| 39 | 8 5 | 8966 9 | 0 0 | 0 0 | 0 0 | 0 0 | 896 7 | 0 0 | 0 0 |
| 40 | 8 4 | 7480 7 | 0 0 | 0 0 | 0 0 | 0 0 | 748 1 | 0 0 | 0 0 |
| 41 | 8 3 | 5949 0 | 0 0 | 0 0 | 0 0 | 0 0 | 594 9 | 0 0 | 0 0 |
| 42 | 3 4 | 2016 2 | 0 0 | 0 0 | 0 0 | 0 0 | 201 6 | 0 0 | 0 0 |
| 43 | 4 7 | 2251 5 | 0 0 | 0 0 | 0 0 | 0 0 | 225 1 | 0 0 | 0 0 |
| 44 | 8 0 | 2085 4 | 0 0 | 0 0 | 0 0 | 0 0 | 208 5 | 0 0 | 0 0 |
| 45 | 3 4 | 207 8 | 0 0 | 0 0 | 0 0 | 0 0 | 20 8 | 0 0 | 0 0 |

Failure Surface Specified By 49 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 81 | 618 62 |
| 3 | 775 43 | 615 89 |
| 4 | 785 11 | 613 38 |
| 5 | 794 84 | 611 09 |
| 6 | 804 62 | 609 02 |
| 7 | 814 45 | 607 17 |
| 8 | 824 32 | 605 55 |
| 9 | 834 22 | 604 15 |
| 10 | 844 15 | 602 97 |
| 11 | 854 11 | 602 02 |
| 12 | 864 08 | 601 30 |
| 13 | 874 07 | 600 80 |
| 14 | 884 06 | 600 53 |
| 15 | 894 06 | 600 48 |
| 16 | 904 06 | 600 66 |
| 17 | 914 05 | 601 07 |
| 18 | 924 03 | 601 70 |
| 19 | 934 00 | 602 56 |
| 20 | 943 94 | 603 65 |
| 21 | 953 85 | 604 96 |
| 22 | 963 73 | 606 49 |
| 23 | 973 58 | 608 25 |
| 24 | 983 38 | 610 23 |
| 25 | 993 13 | 612 43 |
| 26 | 1002 84 | 614 86 |
| 27 | 1012 48 | 617 50 |
| 28 | 1022 06 | 620 36 |
| 29 | 1031 58 | 623 43 |
| 30 | 1041 02 | 626 72 |
| 31 | 1050 39 | 630 23 |
| 32 | 1059 67 | 633 94 |
| 33 | 1068 87 | 637 87 |
| 34 | 1077 98 | 642 00 |
| 35 | 1085 99 | 546 34 |
| 36 | 1095 90 | 650 88 |
| 37 | 1104 70 | 655 62 |
| 38 | 1113 40 | 660 55 |
| 39 | 1121 98 | 665 69 |
| 40 | 1130 44 | 671 02 |
| 41 | 1138 78 | 676 54 |

17/86

| | | |
|----|---------|--------|
| 42 | 1146 99 | 682 24 |
| 43 | 1155 08 | 688 13 |
| 44 | 1163 02 | 694 20 |
| 45 | 1170 83 | 700 45 |
| 46 | 1178 49 | 706 88 |
| 47 | 1186 00 | 713 48 |
| 48 | 1193 37 | 720 24 |
| 49 | 1195 76 | 722 54 |

Circle Center At X = 891 1 Y = 1041 9 and Radius, 441 4
 *** 1 540 ***

Failure Surface Specified By 52 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 07 | 619 66 |
| 3 | 775 91 | 617 91 |
| 4 | 785 79 | 616 33 |
| 5 | 795 69 | 614 91 |
| 6 | 805 61 | 613 65 |
| 7 | 815 55 | 612 55 |
| 8 | 825 50 | 611 62 |
| 9 | 835 47 | 610 85 |
| 10 | 845 45 | 610 24 |
| 11 | 855 44 | 609 79 |
| 12 | 865 44 | 609 51 |
| 13 | 875 44 | 609 39 |
| 14 | 885 44 | 609 44 |
| 15 | 895 44 | 609 65 |
| 16 | 905 43 | 610 02 |
| 17 | 915 42 | 610 55 |
| 18 | 925 39 | 611 25 |
| 19 | 935 36 | 612 11 |
| 20 | 945 30 | 613 13 |
| 21 | 955 23 | 614 32 |
| 22 | 965 14 | 615 67 |
| 23 | 975 03 | 617 18 |
| 24 | 984 89 | 618 85 |
| 25 | 994 72 | 620 68 |
| 26 | 1004 52 | 622 67 |
| 27 | 1014 28 | 624 83 |
| 28 | 1024 01 | 627 14 |
| 29 | 1033 70 | 629 61 |
| 30 | 1043 35 | 632 23 |
| 31 | 1052 95 | 635 02 |
| 32 | 1062 51 | 637 96 |
| 33 | 1072 02 | 641 06 |
| 34 | 1081 48 | 644 31 |
| 35 | 1090 88 | 647 72 |
| 36 | 1100 22 | 651 28 |
| 37 | 1109 51 | 654 99 |
| 38 | 1118 73 | 658 86 |
| 39 | 1127 89 | 662 87 |
| 40 | 1136 98 | 667 03 |
| 41 | 1146 01 | 671 34 |
| 42 | 1154 96 | 675 80 |
| 43 | 1163 83 | 680 40 |
| 44 | 1172 64 | 685 15 |
| 45 | 1181 36 | 690 04 |
| 46 | 1190 00 | 695 08 |
| 47 | 1198 56 | 700 25 |
| 48 | 1207 03 | 705 56 |
| 49 | 1215 41 | 711 01 |
| 50 | 1223 71 | 716 60 |
| 51 | 1231 91 | 722 32 |
| 52 | 1235 25 | 724 74 |

Circle Center At X = 877 7 , Y = 1221 2 and Radius, 611 8
 *** 1 541 ***

Failure Surface Specified By 44 Coordinate Points

18/46

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 59 | 622 95 |
| 3 | 786 54 | 621 89 |
| 4 | 796 50 | 621 01 |
| 5 | 806 47 | 520 30 |
| 6 | 816 46 | 619 76 |
| 7 | 826 45 | 619 39 |
| 8 | 836 45 | 619 20 |
| 9 | 845 45 | 619 17 |
| 10 | 856 45 | 619 31 |
| 11 | 866 44 | 619 63 |
| 12 | 876 43 | 620 12 |
| 13 | 886 41 | 620 77 |
| 14 | 896 38 | 621 60 |
| 15 | 906 33 | 622 60 |
| 16 | 916 26 | 623 77 |
| 17 | 926 17 | 625 11 |
| 18 | 936 05 | 626 61 |
| 19 | 945 91 | 628 29 |
| 20 | 955 74 | 630 13 |
| 21 | 965 54 | 632 15 |
| 22 | 975 30 | 634 33 |
| 23 | 985 02 | 636 67 |
| 24 | 994 70 | 639 19 |
| 25 | 1004 33 | 641 86 |
| 26 | 1013 92 | 644 71 |
| 27 | 1023 46 | 647 71 |
| 28 | 1032 94 | 650 88 |
| 29 | 1042 37 | 654 21 |
| 30 | 1051 74 | 657 70 |
| 31 | 1061 05 | 661 35 |
| 32 | 1070 30 | 665 16 |
| 33 | 1079 47 | 669 13 |
| 34 | 1088 59 | 673 25 |
| 35 | 1097 62 | 677 53 |
| 36 | 1106 59 | 681 96 |
| 37 | 1115 47 | 686 55 |
| 38 | 1124 28 | 691 29 |
| 39 | 1133 01 | 696 17 |
| 40 | 1141 64 | 701 21 |
| 41 | 1150 20 | 706 39 |
| 42 | 1158 66 | 711 72 |
| 43 | 1167 03 | 717 19 |
| 44 | 1173 05 | 721 28 |

Circle Center At X = 843 0 , Y = 1203 5 and Radius, 584 4
 *** 1 545 ***

Failure Surface Specified By 48 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 91 | 624 91 |
| 3 | 796 77 | 623 23 |
| 4 | 806 65 | 621 72 |
| 5 | 816 56 | 620 39 |
| 6 | 826 50 | 619 24 |
| 7 | 836 45 | 618 27 |
| 8 | 846 42 | 617 47 |
| 9 | 856 40 | 616 85 |
| 10 | 866 39 | 616 41 |
| 11 | 876 39 | 616 14 |
| 12 | 886 39 | 616 06 |
| 13 | 896 39 | 616 15 |
| 14 | 906 38 | 616 42 |
| 15 | 916 37 | 616 87 |
| 16 | 926 35 | 617 50 |
| 17 | 936 32 | 618 31 |

19/10

| | | |
|----|---------|--------|
| 18 | 946 27 | 619 29 |
| 19 | 956 20 | 620 45 |
| 20 | 966 11 | 621 79 |
| 21 | 976 00 | 623 31 |
| 22 | 985 85 | 625 00 |
| 23 | 995 68 | 626 86 |
| 24 | 1005 47 | 628 91 |
| 25 | 1016 22 | 631 12 |
| 26 | 1024 93 | 633 51 |
| 27 | 1034 59 | 636 07 |
| 28 | 1044 21 | 638 81 |
| 29 | 1053 78 | 641 71 |
| 30 | 1063 30 | 644 79 |
| 31 | 1072 76 | 648 04 |
| 32 | 1082 16 | 651 45 |
| 33 | 1091 49 | 655 03 |
| 34 | 1100 76 | 658 78 |
| 35 | 1109 97 | 662 69 |
| 36 | 1119 10 | 666 76 |
| 37 | 1128 16 | 671 00 |
| 38 | 1137 14 | 675 40 |
| 39 | 1146 04 | 679 95 |
| 40 | 1154 86 | 684 67 |
| 41 | 1163 59 | 689 54 |
| 42 | 1172 24 | 694 57 |
| 43 | 1180 79 | 699 75 |
| 44 | 1189 25 | 705 08 |
| 45 | 1197 61 | 710 56 |
| 46 | 1205 88 | 716 20 |
| 47 | 1214 04 | 721 97 |
| 48 | 1216 37 | 723 69 |

Circle Center At X = 886 1 , Y = 1176 5 and Radius, 560 4
*** 1 545 ***

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 22 | 621 21 |
| 3 | 785 85 | 618 51 |
| 4 | 795 54 | 616 04 |
| 5 | 805 29 | 613 83 |
| 6 | 815 10 | 611 86 |
| 7 | 824 95 | 610 14 |
| 8 | 834 84 | 608 68 |
| 9 | 844 77 | 607 46 |
| 10 | 854 72 | 606 50 |
| 11 | 864 69 | 605 80 |
| 12 | 874 68 | 605 34 |
| 13 | 884 68 | 605 14 |
| 14 | 894 68 | 605 20 |
| 15 | 904 68 | 605 51 |
| 16 | 914 66 | 606 07 |
| 17 | 924 63 | 606 89 |
| 18 | 934 57 | 607 96 |
| 19 | 944 48 | 609 28 |
| 20 | 954 36 | 610 86 |
| 21 | 964 19 | 612 68 |
| 22 | 973 97 | 614 76 |
| 23 | 983 70 | 617 08 |
| 24 | 993 36 | 619 65 |
| 25 | 1002 96 | 622 46 |
| 26 | 1012 48 | 625 52 |
| 27 | 1021 92 | 628 82 |
| 28 | 1031 27 | 632 35 |
| 29 | 1040 53 | 636 13 |
| 30 | 1049 70 | 640 14 |
| 31 | 1058 75 | 644 38 |
| 32 | 1067 70 | 648 85 |

20/46

| | | |
|----|---------|--------|
| 33 | 1076 53 | 653 54 |
| 34 | 1086 23 | 658 46 |
| 35 | 1093 81 | 663 60 |
| 36 | 1102 25 | 668 95 |
| 37 | 1110 57 | 674 52 |
| 38 | 1118 73 | 680 30 |
| 39 | 1126 74 | 686 28 |
| 40 | 1134 60 | 692 46 |
| 41 | 1142 30 | 698 84 |
| 42 | 1149 83 | 705 42 |
| 43 | 1157 20 | 712 19 |
| 44 | 1164 39 | 719 14 |
| 45 | 1166 12 | 720 90 |

Circle Center At X = 887 5 , Y = 998 3 and Radius, 393 2
 *** 1 546 ***

Failure Surface Specified By 52 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 93 | 619 04 |
| 3 | 775 65 | 616 69 |
| 4 | 785 41 | 614 54 |
| 5 | 795 22 | 612 56 |
| 6 | 805 06 | 610 78 |
| 7 | 814 93 | 609 18 |
| 8 | 824 83 | 607 77 |
| 9 | 834 75 | 606 55 |
| 10 | 844 70 | 605 51 |
| 11 | 854 66 | 604 67 |
| 12 | 864 64 | 604 01 |
| 13 | 874 63 | 603 54 |
| 14 | 884 63 | 603 27 |
| 15 | 894 63 | 603 18 |
| 16 | 904 63 | 603 28 |
| 17 | 914 62 | 603 57 |
| 18 | 924 61 | 604 06 |
| 19 | 934 59 | 604 73 |
| 20 | 944 55 | 605 59 |
| 21 | 954 49 | 606 64 |
| 22 | 964 42 | 607 88 |
| 23 | 974 32 | 609 30 |
| 24 | 984 18 | 610 91 |
| 25 | 994 02 | 612 71 |
| 26 | 1003 82 | 614 70 |
| 27 | 1013 58 | 616 87 |
| 28 | 1023 30 | 619 23 |
| 29 | 1032 97 | 621 77 |
| 30 | 1042 59 | 624 50 |
| 31 | 1052 16 | 627 40 |
| 32 | 1061 67 | 630 49 |
| 33 | 1071 13 | 633 76 |
| 34 | 1080 51 | 637 20 |
| 35 | 1089 83 | 640 83 |
| 36 | 1099 08 | 644 63 |
| 37 | 1108 26 | 648 60 |
| 38 | 1117 36 | 652 75 |
| 39 | 1126 38 | 657 07 |
| 40 | 1135 31 | 661 56 |
| 41 | 1144 16 | 666 22 |
| 42 | 1152 92 | 671 05 |
| 43 | 1161 58 | 676 04 |
| 44 | 1170 15 | 681 19 |
| 45 | 1178 62 | 686 51 |
| 46 | 1186 99 | 691 99 |
| 47 | 1195 25 | 697 62 |
| 48 | 1203 40 | 703 41 |
| 49 | 1211 45 | 709 35 |
| 50 | 1219 37 | 715 45 |

2/26

51 1227 18 721 69
 52 1230 53 724 47
 Circle Center At X = 894 2 , Y = 1130 0 and Radius, 526 9
 *** 1 546 ***

Failure Surface Specified By 51 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 47 | 622 18 |
| 3 | 786 30 | 620 35 |
| 4 | 796 16 | 618 69 |
| 5 | 806 05 | 617 20 |
| 6 | 815 96 | 615 88 |
| 7 | 825 89 | 614 72 |
| 3 | 835 84 | 613 73 |
| 9 | 845 81 | 612 90 |
| 10 | 855 79 | 612 25 |
| 11 | 865 78 | 611 75 |
| 12 | 875 77 | 611 44 |
| 13 | 885 77 | 611 29 |
| 14 | 895 77 | 611 30 |
| 15 | 905 77 | 611 49 |
| 16 | 915 76 | 611 84 |
| 17 | 925 75 | 612 36 |
| 18 | 935 73 | 613 05 |
| 19 | 945 69 | 613 91 |
| 20 | 955 64 | 614 93 |
| 21 | 965 56 | 616 12 |
| 22 | 975 47 | 617 48 |
| 23 | 985 36 | 619 00 |
| 24 | 995 21 | 620 69 |
| 25 | 1005 04 | 622 55 |
| 26 | 1014 83 | 624 57 |
| 27 | 1024 59 | 626 76 |
| 28 | 1034 31 | 629 11 |
| 29 | 1043 99 | 631 62 |
| 30 | 1053 62 | 634 30 |
| 31 | 1063 21 | 637 13 |
| 32 | 1072 75 | 640 13 |
| 33 | 1082 24 | 643 29 |
| 34 | 1091 67 | 646 61 |
| 35 | 1101 05 | 650 08 |
| 36 | 1110 37 | 653 72 |
| 37 | 1119 62 | 657 51 |
| 38 | 1128 81 | 661 45 |
| 39 | 1137 93 | 665 55 |
| 40 | 1146 98 | 669 80 |
| 41 | 1155 96 | 674 20 |
| 42 | 1164 87 | 678 76 |
| 43 | 1173 69 | 683 46 |
| 44 | 1182 44 | 688 31 |
| 45 | 1191 10 | 693 31 |
| 46 | 1199 67 | 698 45 |
| 47 | 1208 16 | 703 73 |
| 48 | 1216 56 | 709 15 |
| 49 | 1224 87 | 714 73 |
| 50 | 1233 08 | 720 44 |
| 51 | 1239 36 | 724 96 |

Circle Center At X = 889 8 , Y = 1205 6 and Radius, 594 3
 *** 1 553 ***

Failure Surface Specified By 42 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 02 | 619 41 |
| 3 | 775 83 | 617 48 |
| 4 | 785 68 | 615 78 |
| 5 | 795 58 | 614 32 |

22/46

| | | |
|----|---------|--------|
| 6 | 805 50 | 613 09 |
| 7 | 815 45 | 612 10 |
| 8 | 825 42 | 611 34 |
| 9 | 835 41 | 610 81 |
| 10 | 845 40 | 610 53 |
| 11 | 855 40 | 610 47 |
| 12 | 865 40 | 610 65 |
| 13 | 875 39 | 611 07 |
| 14 | 885 37 | 611 72 |
| 15 | 895 33 | 612 61 |
| 16 | 905 27 | 613 73 |
| 17 | 915 18 | 615 09 |
| 18 | 925 05 | 616 68 |
| 19 | 934 88 | 618 50 |
| 20 | 944 67 | 620 55 |
| 21 | 954 41 | 622 84 |
| 22 | 964 08 | 625 35 |
| 23 | 973 70 | 628 09 |
| 24 | 983 25 | 631 05 |
| 25 | 992 73 | 634 24 |
| 26 | 1002 13 | 637 65 |
| 27 | 1011 45 | 641 28 |
| 28 | 1020 68 | 645 13 |
| 29 | 1029 81 | 649 20 |
| 30 | 1038 85 | 653 48 |
| 31 | 1047 78 | 657 97 |
| 32 | 1056 61 | 662 68 |
| 33 | 1065 32 | 667 58 |
| 34 | 1073 92 | 672 70 |
| 35 | 1082 39 | 678 01 |
| 36 | 1090 73 | 683 52 |
| 37 | 1098 94 | 689 23 |
| 38 | 1107 02 | 695 13 |
| 39 | 1114 95 | 701 21 |
| 40 | 1122 74 | 707 49 |
| 41 | 1130 38 | 713 94 |
| 42 | 1132 19 | 715 55 |

Circle Center At X = 852 7 , Y = 1034 7 and Radius, 424 3
 *** 1 553 ***

Failure Surface Specified By 49 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 91 | 624 89 |
| 3 | 796 76 | 623 18 |
| 4 | 806 64 | 621 64 |
| 5 | 816 54 | 620 26 |
| 6 | 826 47 | 619 06 |
| 7 | 836 42 | 618 03 |
| 8 | 846 38 | 617 17 |
| 9 | 856 36 | 616 49 |
| 10 | 866 34 | 615 97 |
| 11 | 876 34 | 615 63 |
| 12 | 886 34 | 615 45 |
| 13 | 896 34 | 615 45 |
| 14 | 906 34 | 615 63 |
| 15 | 916 33 | 615 97 |
| 16 | 926 32 | 616 49 |
| 17 | 936 29 | 617 17 |
| 18 | 946 26 | 618 03 |
| 19 | 956 20 | 619 06 |
| 20 | 966 13 | 620 26 |
| 21 | 976 04 | 621 64 |
| 22 | 985 92 | 623 18 |
| 23 | 995 77 | 624 89 |
| 24 | 1005 59 | 626 77 |
| 25 | 1015 38 | 628 82 |
| 26 | 1025 13 | 631 04 |


23/46

| | | |
|----|---------|--------|
| 27 | 1034 84 | 633 42 |
| 28 | 1044 51 | 635 97 |
| 29 | 1054 13 | 638 69 |
| 30 | 1063 71 | 641 58 |
| 31 | 1073 23 | 644 62 |
| 32 | 1082 70 | 647 83 |
| 33 | 1092 12 | 651 21 |
| 34 | 1101 47 | 654 74 |
| 35 | 1110 76 | 658 44 |
| 36 | 1119 99 | 662 29 |
| 37 | 1129 15 | 666 30 |
| 38 | 1138 24 | 670 47 |
| 39 | 1147 26 | 674 80 |
| 40 | 1156 20 | 679 28 |
| 41 | 1165 06 | 683 91 |
| 42 | 1173 84 | 688 69 |
| 43 | 1182 54 | 693 63 |
| 44 | 1191 15 | 698 71 |
| 45 | 1199 67 | 703 94 |
| 46 | 1208 10 | 709 32 |
| 47 | 1216 44 | 714 84 |
| 48 | 1224 68 | 720 51 |
| 49 | 1230 22 | 724 46 |

Circle Center At X = 891 3 , Y = 1196 7 and Radius, 581 3
*** 1 554 ***

Intermountain Regional Landfill Fill Slope 1

c:\program files\stedwin\ir\13 pl2 Run By Greg Shafer HDR 4/20/2010 03:44PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface | Load Horz Eqk | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|---------------|----------|
| a | 1.17 | | | | | | | | | 0.200 g< |
| b | 1.17 | | | | | | | | | |
| c | 1.19 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 | | |
| d | 1.19 | LSC | 2 | 121.0 | 125.5 | 1500.0 | 0.0 | W1 | | |
| e | 1.19 | SC | 3 | 121.0 | 125.5 | 2000.0 | 0.0 | W1 | | |
| f | 1.19 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | 0.0 | W1 | | |
| g | 1.19 | Waste | 5 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| h | 1.19 | | | | | | | | | |
| i | 1.20 | | | | | | | | | |
| j | 1.20 | | | | | | | | | |

PCSTABL7 FSmin=1.17

Safety Factors Are Calculated By The Modified Bishop Method

STED



Handwritten signature/initials

25/46

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 44PM
Run By Greg Shafer, HDR
Input Data Filename C 13 in
Output Filename C 13 OUT
Unit ENGLISH
Plotted Output Filename C 13 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient Of 0 200 Has Been Assigned
 A Vertical Earthquake Loading Coefficient Of 0 000 Has Been Assigned
 Cavitation Pressure = 0 0 (psf)
 A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified
 625 Trial Surfaces Have Been Generated
 25 Surfaces Initiate From Each Of 25 Points Equally Spaced Along The Ground Surface Between X = 600 00 ft and X = 850 00 ft
 Each Surface Terminates Between X =1100 00 ft and X =1300 00 ft
 Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is Y = 0 00 ft
 10 00 ft Line Segments Define Each Trial Failure Surface
 Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 98 | 619 23 |
| 3 | 775 75 | 617 12 |
| 4 | 785 57 | 615 23 |
| 5 | 795 43 | 613 55 |

26/26

| | | |
|----|---------|--------|
| 6 | 805 32 | 612 10 |
| 7 | 815 24 | 610 86 |
| 8 | 825 19 | 609 85 |
| 9 | 835 16 | 609 06 |
| 10 | 845 15 | 608 49 |
| 11 | 855 14 | 608 15 |
| 12 | 865 14 | 608 03 |
| 13 | 875 14 | 608 13 |
| 14 | 885 13 | 608 45 |
| 15 | 895 12 | 609 00 |
| 16 | 905 09 | 609 77 |
| 17 | 915 04 | 610 76 |
| 18 | 924 97 | 611 97 |
| 19 | 934 86 | 613 41 |
| 20 | 944 73 | 615 06 |
| 21 | 954 55 | 616 93 |
| 22 | 964 33 | 619 03 |
| 23 | 974 06 | 621 34 |
| 24 | 983 73 | 623 86 |
| 25 | 993 35 | 626 60 |
| 26 | 1002 90 | 629 56 |
| 27 | 1012 39 | 632 72 |
| 28 | 1021 80 | 636 10 |
| 29 | 1031 13 | 639 69 |
| 30 | 1040 39 | 643 48 |
| 31 | 1049 55 | 647 48 |
| 32 | 1058 63 | 651 69 |
| 33 | 1067 60 | 656 09 |
| 34 | 1076 48 | 660 69 |
| 35 | 1085 25 | 665 49 |
| 36 | 1093 92 | 670 49 |
| 37 | 1102 47 | 675 67 |
| 38 | 1110 90 | 681 05 |
| 39 | 1119 21 | 686 61 |
| 40 | 1127 40 | 692 36 |
| 41 | 1135 45 | 698 28 |
| 42 | 1143 37 | 704 39 |
| 43 | 1151 15 | 710 67 |
| 44 | 1158 79 | 717 12 |
| 45 | 1162 86 | 720 71 |

Circle Center At X = 865 6 , Y = 1056 5 and Radius, 448 5

*** 1 168 ***
Individual data on the 45 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force Surchage Load | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|--------------------------------|-----------|-------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | (lbs) |
| 1 | 9 7 | 1157 5 | 0 0 | 0 0 | 0 0 | 0 0 | 231 5 | 0 0 | 0 0 |
| 2 | 9 8 | 3440 2 | 0 0 | 0 0 | 0 0 | 0 0 | 688 0 | 0 0 | 0 0 |
| 3 | 9 8 | 5641 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1128 4 | 0 0 | 0 0 |
| 4 | 9 9 | 7756 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1551 4 | 0 0 | 0 0 |
| 5 | 9 9 | 9779 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1955 9 | 0 0 | 0 0 |
| 6 | 9 9 | 11705 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2341 1 | 0 0 | 0 0 |
| 7 | 9 9 | 13529 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2705 8 | 0 0 | 0 0 |
| 8 | 10 0 | 15246 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3049 3 | 0 0 | 0 0 |
| 9 | 10 0 | 16853 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3370 7 | 0 0 | 0 0 |
| 10 | 10 0 | 18346 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3669 3 | 0 0 | 0 0 |
| 11 | 10 0 | 19722 1 | 0 0 | 0 0 | 0 0 | 0 0 | 3944 4 | 0 0 | 0 0 |
| 12 | 10 0 | 20977 6 | 0 0 | 0 0 | 0 0 | 0 0 | 4195 5 | 0 0 | 0 0 |
| 13 | 10 0 | 22110 4 | 0 0 | 0 0 | 0 0 | 0 0 | 4422 1 | 0 0 | 0 0 |
| 14 | 10 0 | 23118 5 | 0 0 | 0 0 | 0 0 | 0 0 | 4623 7 | 0 0 | 0 0 |
| 15 | 10 0 | 24000 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4800 0 | 0 0 | 0 0 |
| 16 | 10 0 | 24753 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4950 8 | 0 0 | 0 0 |
| 17 | 9 9 | 25378 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5075 7 | 0 0 | 0 0 |
| 18 | 9 9 | 25874 6 | 0 0 | 0 0 | 0 0 | 0 0 | 5174 9 | 0 0 | 0 0 |
| 19 | 9 9 | 26241 2 | 0 0 | 0 0 | 0 0 | 0 0 | 5248 2 | 0 0 | 0 0 |
| 20 | 9 8 | 26478 6 | 0 0 | 0 0 | 0 0 | 0 0 | 5295 7 | 0 0 | 0 0 |
| 21 | 9 8 | 26588 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5317 6 | 0 0 | 0 0 |

27/1/16

| | | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|-----|--------|-----|-----|
| 22 | 9 7 | 26570 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5314 0 | 0 0 | 0 0 |
| 23 | 9 7 | 26426 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5285 4 | 0 0 | 0 0 |
| 24 | 9 6 | 26159 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5231 9 | 0 0 | 0 0 |
| 25 | 9 6 | 25771 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5154 2 | 0 0 | 0 0 |
| 26 | 9 5 | 25264 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5052 8 | 0 0 | 0 0 |
| 27 | 9 4 | 24641 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4928 3 | 0 0 | 0 0 |
| 28 | 9 3 | 23906 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4781 3 | 0 0 | 0 0 |
| 29 | 9 3 | 23063 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4612 7 | 0 0 | 0 0 |
| 30 | 9 2 | 22116 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4423 2 | 0 0 | 0 0 |
| 31 | 9 1 | 21069 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4213 8 | 0 0 | 0 0 |
| 32 | 9 0 | 19927 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3985 5 | 0 0 | 0 0 |
| 33 | 8 9 | 18696 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3739 3 | 0 0 | 0 0 |
| 34 | 8 8 | 17381 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3476 3 | 0 0 | 0 0 |
| 35 | 8 7 | 15987 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3197 5 | 0 0 | 0 0 |
| 35 | 8 6 | 14522 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2904 4 | 0 0 | 0 0 |
| 37 | 8 4 | 12990 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2598 1 | 0 0 | 0 0 |
| 38 | 8 3 | 11400 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2280 0 | 0 0 | 0 0 |
| 39 | 8 2 | 9757 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1951 4 | 0 0 | 0 0 |
| 40 | 8 1 | 8069 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1613 8 | 0 0 | 0 0 |
| 41 | 7 9 | 6343 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1268 6 | 0 0 | 0 0 |
| 42 | 6 6 | 4014 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 802 8 | 0 0 | 0 0 |
| 43 | 1 2 | 566 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 113 2 | 0 0 | 0 0 |
| 44 | 7 6 | 2438 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 487 6 | 0 0 | 0 0 |
| 45 | 4 1 | 342 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 68 5 | 0 0 | 0 0 |

Failure Surface Specified By 47 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 84 | 624 58 |
| 3 | 796 64 | 622 59 |
| 4 | 806 48 | 620 79 |
| 5 | 816 35 | 619 19 |
| 6 | 826 25 | 617 79 |
| 7 | 836 18 | 616 59 |
| 8 | 846 13 | 615 58 |
| 9 | 856 10 | 614 78 |
| 10 | 866 08 | 614 17 |
| 11 | 876 07 | 613 76 |
| 12 | 886 07 | 613 55 |
| 13 | 896 07 | 613 55 |
| 14 | 906 06 | 613 74 |
| 15 | 916 06 | 614 13 |
| 16 | 926 04 | 614 72 |
| 17 | 936 01 | 615 51 |
| 18 | 945 96 | 616 50 |
| 19 | 955 89 | 617 69 |
| 20 | 965 79 | 619 07 |
| 21 | 975 67 | 620 66 |
| 22 | 985 51 | 622 44 |
| 23 | 995 31 | 624 41 |
| 24 | 1005 07 | 626 58 |
| 25 | 1014 79 | 628 95 |
| 26 | 1024 45 | 631 51 |
| 27 | 1034 07 | 634 26 |
| 28 | 1043 62 | 637 21 |
| 29 | 1053 12 | 640 34 |
| 30 | 1062 55 | 643 67 |
| 31 | 1071 91 | 647 18 |
| 32 | 1081 20 | 650 88 |
| 33 | 1090 42 | 654 76 |
| 34 | 1099 56 | 658 83 |
| 35 | 1108 61 | 663 07 |
| 36 | 1117 57 | 667 50 |
| 37 | 1126 45 | 672 11 |
| 38 | 1135 23 | 676 89 |
| 39 | 1143 92 | 681 85 |
| 40 | 1152 50 | 686 98 |
| 41 | 1160 98 | 692 28 |

28/46

| | | |
|----|---------|--------|
| 42 | 1169 35 | 697 75 |
| 43 | 1177 62 | 703 38 |
| 44 | 1185 75 | 709 18 |
| 45 | 1193 79 | 715 14 |
| 46 | 1201 70 | 721 26 |
| 47 | 1203 85 | 722 99 |

Circle Center At X = 891 5 , Y = 1114 1 and Radius, 500 5
 *** 1 170 ***

Failure Surface Specified By 52 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 79 | 624 37 |
| 3 | 796 54 | 622 15 |
| 4 | 806 33 | 620 10 |
| 5 | 816 15 | 618 23 |
| 6 | 826 01 | 616 53 |
| 7 | 835 89 | 615 01 |
| 8 | 845 80 | 613 68 |
| 9 | 855 73 | 612 52 |
| 10 | 865 69 | 611 54 |
| 11 | 875 65 | 610 74 |
| 12 | 885 64 | 610 12 |
| 13 | 895 63 | 609 67 |
| 14 | 905 62 | 609 41 |
| 15 | 915 62 | 609 33 |
| 16 | 925 62 | 609 43 |
| 17 | 935 62 | 609 71 |
| 18 | 945 61 | 610 17 |
| 19 | 955 59 | 610 81 |
| 20 | 965 55 | 611 63 |
| 21 | 975 50 | 612 63 |
| 22 | 985 43 | 613 81 |
| 23 | 995 34 | 615 17 |
| 24 | 1005 22 | 616 70 |
| 25 | 1015 07 | 618 41 |
| 26 | 1024 89 | 620 30 |
| 27 | 1034 68 | 622 37 |
| 28 | 1044 42 | 624 61 |
| 29 | 1054 13 | 627 03 |
| 30 | 1063 78 | 629 62 |
| 31 | 1073 39 | 632 39 |
| 32 | 1082 95 | 635 33 |
| 33 | 1092 46 | 638 44 |
| 34 | 1101 90 | 641 72 |
| 35 | 1111 29 | 645 17 |
| 36 | 1120 61 | 648 79 |
| 37 | 1129 86 | 652 58 |
| 38 | 1139 05 | 656 54 |
| 39 | 1148 16 | 660 65 |
| 40 | 1157 20 | 664 94 |
| 41 | 1166 16 | 669 38 |
| 42 | 1175 03 | 673 99 |
| 43 | 1183 83 | 678 75 |
| 44 | 1192 53 | 683 67 |
| 45 | 1201 15 | 688 75 |
| 46 | 1209 67 | 693 98 |
| 47 | 1218 09 | 699 37 |
| 48 | 1226 42 | 704 90 |
| 49 | 1234 65 | 710 59 |
| 50 | 1242 77 | 716 42 |
| 51 | 1250 79 | 722 40 |
| 52 | 1255 24 | 725 85 |

Circle Center At X = 915 1 , Y = 1164 1 and Radius, 554 8
 *** 1 189 ***

Failure Surface Specified By 57 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
|----------|-------------|-------------|

29/46

| | | |
|----|---------|--------|
| 1 | 756 25 | 621 56 |
| 2 | 766 18 | 620 42 |
| 3 | 776 13 | 619 38 |
| 4 | 786 09 | 618 45 |
| 5 | 796 06 | 617 65 |
| 6 | 806 03 | 616 96 |
| 7 | 816 01 | 616 38 |
| 8 | 826 00 | 615 91 |
| 9 | 836 00 | 615 55 |
| 10 | 845 99 | 615 31 |
| 11 | 855 99 | 615 19 |
| 12 | 865 99 | 615 18 |
| 13 | 875 99 | 615 28 |
| 14 | 885 99 | 615 49 |
| 15 | 895 99 | 615 82 |
| 16 | 905 98 | 616 26 |
| 17 | 915 96 | 616 82 |
| 18 | 925 94 | 617 49 |
| 19 | 935 91 | 618 27 |
| 20 | 945 87 | 619 16 |
| 21 | 955 82 | 620 17 |
| 22 | 965 75 | 621 29 |
| 23 | 975 68 | 622 53 |
| 24 | 985 59 | 623 88 |
| 25 | 995 48 | 625 34 |
| 26 | 1005 35 | 626 91 |
| 27 | 1015 21 | 628 59 |
| 28 | 1025 05 | 630 39 |
| 29 | 1034 86 | 632 30 |
| 30 | 1044 66 | 634 32 |
| 31 | 1054 43 | 636 45 |
| 32 | 1064 17 | 638 69 |
| 33 | 1073 89 | 641 04 |
| 34 | 1083 58 | 643 51 |
| 35 | 1093 25 | 646 08 |
| 36 | 1102 88 | 648 76 |
| 37 | 1112 48 | 651 56 |
| 38 | 1122 05 | 654 46 |
| 39 | 1131 59 | 657 47 |
| 40 | 1141 09 | 660 59 |
| 41 | 1150 56 | 663 81 |
| 42 | 1159 99 | 667 14 |
| 43 | 1169 37 | 670 58 |
| 44 | 1178 72 | 674 13 |
| 45 | 1188 03 | 677 78 |
| 46 | 1197 30 | 681 54 |
| 47 | 1206 52 | 685 41 |
| 48 | 1215 70 | 689 38 |
| 49 | 1224 84 | 693 45 |
| 50 | 1233 92 | 697 62 |
| 51 | 1242 96 | 701 90 |
| 52 | 1251 95 | 706 28 |
| 53 | 1260 89 | 710 77 |
| 54 | 1269 77 | 715 35 |
| 55 | 1278 61 | 720 04 |
| 56 | 1287 39 | 724 82 |
| 57 | 1292 96 | 727 94 |

Circle Center At X = 862 1 Y = 1494 6 and Radius 879 5
*** 1 191 ***

Failure Surface Specified By 46 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 83 | 630 69 |
| 3 | 817 77 | 629 55 |
| 4 | 827 72 | 628 57 |
| 5 | 837 69 | 627 74 |
| 6 | 847 66 | 627 08 |

30/10

| | | |
|----|---------|--------|
| 7 | 857 65 | 626 57 |
| 8 | 867 65 | 625 22 |
| 9 | 877 64 | 626 03 |
| 10 | 887 64 | 626 00 |
| 11 | 897 64 | 626 12 |
| 12 | 907 64 | 626 41 |
| 13 | 917 63 | 626 85 |
| 14 | 927 51 | 627 44 |
| 15 | 937 58 | 628 20 |
| 16 | 947 54 | 629 11 |
| 17 | 957 48 | 630 19 |
| 18 | 967 41 | 631 41 |
| 19 | 977 31 | 632 80 |
| 20 | 987 19 | 634 34 |
| 21 | 997 05 | 636 04 |
| 22 | 1006 87 | 637 89 |
| 23 | 1016 67 | 639 90 |
| 24 | 1026 43 | 642 06 |
| 25 | 1036 16 | 644 38 |
| 26 | 1045 85 | 646 84 |
| 27 | 1055 50 | 649 47 |
| 28 | 1065 11 | 652 24 |
| 29 | 1074 67 | 655 17 |
| 30 | 1084 19 | 658 25 |
| 31 | 1093 65 | 661 47 |
| 32 | 1103 06 | 664 85 |
| 33 | 1112 42 | 668 37 |
| 34 | 1121 72 | 672 05 |
| 35 | 1130 97 | 675 86 |
| 36 | 1140 15 | 679 83 |
| 37 | 1149 26 | 683 94 |
| 38 | 1158 31 | 688 19 |
| 39 | 1167 30 | 692 58 |
| 40 | 1176 21 | 697 12 |
| 41 | 1185 05 | 701 80 |
| 42 | 1193 81 | 706 61 |
| 43 | 1202 50 | 711 57 |
| 44 | 1211 11 | 716 66 |
| 45 | 1219 63 | 721 88 |
| 46 | 1223 06 | 724 06 |

Circle Center At X = 884 8 Y = 1258 5 and Radius, 632 5

*** 1 191 ***

Failure Surface Specified By 43 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 24 | 621 28 |
| 3 | 785 89 | 618 64 |
| 4 | 795 60 | 616 27 |
| 5 | 805 38 | 614 15 |
| 6 | 815 20 | 612 30 |
| 7 | 825 08 | 610 71 |
| 8 | 834 99 | 609 39 |
| 9 | 844 93 | 608 33 |
| 10 | 854 90 | 607 53 |
| 11 | 864 89 | 607 00 |
| 12 | 874 88 | 606 74 |
| 13 | 884 88 | 606 75 |
| 14 | 894 88 | 607 03 |
| 15 | 904 86 | 607 57 |
| 16 | 914 83 | 608 37 |
| 17 | 924 77 | 609 45 |
| 18 | 934 68 | 610 79 |
| 19 | 944 55 | 612 39 |
| 20 | 954 38 | 614 26 |
| 21 | 964 15 | 616 38 |
| 22 | 973 86 | 618 77 |
| 23 | 983 50 | 621 42 |

31/260

| | | |
|----|---------|--------|
| 24 | 993 07 | 624 32 |
| 25 | 1002 56 | 627 48 |
| 26 | 1011 96 | 630 89 |
| 27 | 1021 27 | 634 55 |
| 28 | 1030 47 | 638 46 |
| 29 | 1039 57 | 642 61 |
| 30 | 1048 55 | 647 01 |
| 31 | 1057 41 | 651 64 |
| 32 | 1066 15 | 656 51 |
| 33 | 1074 75 | 661 60 |
| 34 | 1083 21 | 666 93 |
| 35 | 1091 53 | 672 48 |
| 36 | 1099 70 | 678 25 |
| 37 | 1107 71 | 684 24 |
| 38 | 1115 55 | 690 44 |
| 39 | 1123 23 | 696 85 |
| 40 | 1130 74 | 703 46 |
| 41 | 1138 06 | 710 27 |
| 42 | 1145 20 | 717 27 |
| 43 | 1147 16 | 719 29 |

Circle Center At X = 879 6 Y = 981 0 and Radius 374 3
*** 1 192 ***

Failure Surface Specified By 41 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 31 | 627 45 |
| 3 | 807 17 | 625 76 |
| 4 | 817 06 | 624 29 |
| 5 | 826 98 | 623 04 |
| 6 | 836 93 | 622 02 |
| 7 | 846 90 | 621 23 |
| 8 | 856 88 | 620 67 |
| 9 | 866 88 | 620 34 |
| 10 | 876 88 | 620 23 |
| 11 | 886 88 | 620 36 |
| 12 | 896 87 | 620 71 |
| 13 | 906 85 | 621 29 |
| 14 | 916 82 | 622 10 |
| 15 | 926 77 | 623 14 |
| 16 | 936 69 | 624 40 |
| 17 | 946 58 | 625 89 |
| 18 | 956 43 | 627 61 |
| 19 | 966 24 | 629 55 |
| 20 | 976 00 | 631 71 |
| 21 | 985 71 | 634 10 |
| 22 | 995 37 | 636 70 |
| 23 | 1004 96 | 639 53 |
| 24 | 1014 48 | 642 58 |
| 25 | 1023 93 | 645 84 |
| 26 | 1033 31 | 649 32 |
| 27 | 1042 60 | 653 01 |
| 28 | 1051 81 | 656 91 |
| 29 | 1060 93 | 661 03 |
| 30 | 1069 94 | 665 35 |
| 31 | 1078 86 | 669 87 |
| 32 | 1087 67 | 674 60 |
| 33 | 1096 38 | 679 53 |
| 34 | 1104 96 | 684 65 |
| 35 | 1113 43 | 689 97 |
| 36 | 1121 77 | 695 49 |
| 37 | 1129 99 | 701 19 |
| 38 | 1138 07 | 707 08 |
| 39 | 1146 02 | 713 15 |
| 40 | 1153 82 | 719 40 |
| 41 | 1154 86 | 720 27 |

Circle Center At X = 876 5 Y = 1057 7 and Radius 437 5
*** 1 193 ***

32/A6

Failure Surface Specified By 54 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 62 | 623 23 |
| 3 | 786 59 | 622 40 |
| 4 | 796 56 | 621 69 |
| 5 | 806 55 | 621 09 |
| 6 | 816 53 | 620 61 |
| 7 | 826 53 | 620 24 |
| 8 | 836 52 | 619 99 |
| 9 | 846 52 | 619 85 |
| 10 | 856 52 | 619 83 |
| 11 | 866 52 | 619 92 |
| 12 | 876 52 | 620 13 |
| 13 | 886 52 | 620 45 |
| 14 | 896 51 | 620 89 |
| 15 | 906 49 | 621 44 |
| 16 | 916 47 | 622 11 |
| 17 | 926 44 | 622 89 |
| 18 | 936 40 | 623 78 |
| 19 | 946 35 | 624 79 |
| 20 | 956 28 | 625 91 |
| 21 | 966 21 | 627 15 |
| 22 | 976 12 | 628 50 |
| 23 | 986 01 | 629 97 |
| 24 | 995 88 | 631 55 |
| 25 | 1005 74 | 633 24 |
| 26 | 1015 57 | 635 04 |
| 27 | 1025 39 | 636 96 |
| 28 | 1035 18 | 638 99 |
| 29 | 1044 95 | 641 13 |
| 30 | 1054 69 | 643 39 |
| 31 | 1064 41 | 645 75 |
| 32 | 1074 09 | 648 23 |
| 33 | 1083 75 | 650 82 |
| 34 | 1093 38 | 653 52 |
| 35 | 1102 98 | 656 33 |
| 36 | 1112 54 | 659 25 |
| 37 | 1122 07 | 662 28 |
| 38 | 1131 57 | 665 41 |
| 39 | 1141 03 | 668 66 |
| 40 | 1150 45 | 672 02 |
| 41 | 1159 83 | 675 48 |
| 42 | 1169 17 | 679 05 |
| 43 | 1178 47 | 682 73 |
| 44 | 1187 72 | 686 52 |
| 45 | 1196 94 | 690 41 |
| 46 | 1206 10 | 694 40 |
| 47 | 1215 22 | 698 50 |
| 48 | 1224 30 | 702 71 |
| 49 | 1233 32 | 707 02 |
| 50 | 1242 29 | 711 43 |
| 51 | 1251 21 | 715 95 |
| 52 | 1260 08 | 720 57 |
| 53 | 1268 90 | 725 29 |
| 54 | 1271 57 | 726 75 |

Circle Center At X = 853 5 , Y = 1490 5 and Radius 870 7
*** 1 193 ***

Failure Surface Specified By 58 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 20 | 620 53 |
| 3 | 776 15 | 619 61 |
| 4 | 786 12 | 618 79 |
| 5 | 796 10 | 618 08 |
| 6 | 806 08 | 617 48 |

33/46

| | | |
|----|---------|--------|
| 7 | 816 07 | 616 99 |
| 8 | 826 06 | 616 60 |
| 9 | 836 05 | 616 32 |
| 10 | 846 05 | 616 15 |
| 11 | 856 05 | 616 09 |
| 12 | 866 05 | 616 14 |
| 13 | 876 05 | 616 30 |
| 14 | 886 05 | 616 56 |
| 15 | 896 04 | 616 93 |
| 16 | 906 03 | 617 41 |
| 17 | 916 01 | 618 00 |
| 18 | 925 99 | 618 69 |
| 19 | 935 96 | 619 49 |
| 20 | 945 91 | 620 40 |
| 21 | 955 86 | 621 42 |
| 22 | 965 80 | 622 55 |
| 23 | 975 72 | 623 78 |
| 24 | 985 63 | 625 12 |
| 25 | 995 53 | 526 57 |
| 26 | 1005 41 | 628 12 |
| 27 | 1015 27 | 629 78 |
| 28 | 1025 11 | 631 55 |
| 29 | 1034 93 | 633 42 |
| 30 | 1044 74 | 635 40 |
| 31 | 1054 52 | 637 48 |
| 32 | 1064 27 | 639 67 |
| 33 | 1074 01 | 641 97 |
| 34 | 1083 71 | 644 37 |
| 35 | 1093 39 | 646 88 |
| 36 | 1103 05 | 649 49 |
| 37 | 1112 67 | 652 20 |
| 38 | 1122 27 | 655 02 |
| 39 | 1131 83 | 657 94 |
| 40 | 1141 36 | 660 97 |
| 41 | 1150 86 | 664 09 |
| 42 | 1160 32 | 667 32 |
| 43 | 1169 75 | 670 66 |
| 44 | 1179 14 | 674 09 |
| 45 | 1188 50 | 677 63 |
| 46 | 1197 81 | 681 26 |
| 47 | 1207 09 | 685 00 |
| 48 | 1216 32 | 688 84 |
| 49 | 1225 52 | 692 77 |
| 50 | 1234 67 | 696 81 |
| 51 | 1243 77 | 700 94 |
| 52 | 1252 83 | 705 17 |
| 53 | 1261 85 | 709 50 |
| 54 | 1270 81 | 713 93 |
| 55 | 1279 73 | 718 45 |
| 56 | 1288 60 | 723 07 |
| 57 | 1297 42 | 727 79 |
| 58 | 1298 23 | 728 23 |

Circle Center At X = 856 7 Y = 1541 3 and Radius 925 2
 *** 1 196 ***

Failure Surface Specified By 51 Coordinate Points


| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 61 | 623 73 |
| 3 | 796 20 | 620 90 |
| 4 | 805 85 | 618 28 |
| 5 | 815 55 | 615 86 |
| 6 | 825 31 | 613 65 |
| 7 | 835 10 | 611 64 |
| 8 | 844 94 | 609 85 |
| 9 | 854 82 | 608 27 |
| 10 | 864 72 | 606 90 |
| 11 | 874 66 | 605 74 |

| | | |
|----|---------|--------|
| 12 | 884 61 | 604 80 |
| 13 | 894 58 | 604 07 |
| 14 | 904 57 | 603 55 |
| 15 | 914 57 | 603 25 |
| 16 | 924 57 | 603 16 |
| 17 | 934 56 | 603 28 |
| 18 | 944 56 | 603 62 |
| 19 | 954 54 | 604 17 |
| 20 | 964 51 | 604 94 |
| 21 | 974 47 | 605 91 |
| 22 | 984 40 | 607 11 |
| 23 | 994 30 | 608 51 |
| 24 | 1004 17 | 610 12 |
| 25 | 1014 00 | 611 95 |
| 26 | 1023 79 | 613 98 |
| 27 | 1033 53 | 616 23 |
| 28 | 1043 23 | 618 68 |
| 29 | 1052 87 | 621 34 |
| 30 | 1062 45 | 624 20 |
| 31 | 1071 97 | 627 27 |
| 32 | 1081 42 | 630 54 |
| 33 | 1090 79 | 634 02 |
| 34 | 1100 09 | 637 69 |
| 35 | 1109 31 | 641 56 |
| 36 | 1118 45 | 645 63 |
| 37 | 1127 50 | 649 89 |
| 38 | 1136 45 | 654 35 |
| 39 | 1145 30 | 658 99 |
| 40 | 1154 06 | 663 83 |
| 41 | 1162 71 | 668 84 |
| 42 | 1171 25 | 674 05 |
| 43 | 1179 67 | 679 43 |
| 44 | 1187 98 | 685 00 |
| 45 | 1196 17 | 690 74 |
| 46 | 1204 23 | 696 65 |
| 47 | 1212 17 | 702 74 |
| 48 | 1219 97 | 708 99 |
| 49 | 1227 64 | 715 41 |
| 50 | 1235 17 | 721 99 |
| 51 | 1238 36 | 724 91 |

Circle Center At X = 923 8 Y = 1070 6 and Radius 467 4
 *** 1 197 ***

Intermountain Regional Landfill Fill Slope 1

c:\program files\stedwin\ir\14 pl2 Run By Greg Shafer HDR 4/20/2010 03 48PM



STED



PCSTABL7 FSmin=0.94
Safety Factors Are Calculated By The Modified Bishop Method

35/A6

36/40

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 48PM
Run By Greg Shafer HDR
Input Data Filename C 14 in
Output Filename C 14 OUT
Unit ENGLISH
Plotted Output Filename C 14 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of 0 300 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method Using A Random
Technique For Generating Circular Surfaces Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 600 00 ft
and X = 850 00 ft
Each Surface Terminates Between X =1100 00 ft
and X =1300 00 ft

Unless Further Limitations Were Imposed The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 47 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 84 | 624 58 |
| 3 | 796 64 | 622 59 |
| 4 | 806 48 | 620 79 |
| 5 | 816 35 | 619 19 |

| | | |
|----|---------|--------|
| 6 | 826 25 | 617 79 |
| 7 | 836 18 | 616 59 |
| 8 | 846 13 | 615 58 |
| 9 | 856 10 | 614 78 |
| 10 | 866 08 | 614 17 |
| 11 | 876 07 | 613 76 |
| 12 | 886 07 | 613 55 |
| 13 | 896 07 | 613 55 |
| 14 | 906 06 | 613 74 |
| 15 | 916 06 | 614 13 |
| 16 | 926 04 | 614 72 |
| 17 | 936 01 | 615 51 |
| 18 | 945 96 | 616 50 |
| 19 | 955 89 | 617 69 |
| 20 | 965 79 | 619 07 |
| 21 | 975 67 | 620 66 |
| 22 | 985 51 | 622 44 |
| 23 | 995 31 | 624 41 |
| 24 | 1005 07 | 626 58 |
| 25 | 1014 79 | 628 95 |
| 26 | 1024 45 | 631 51 |
| 27 | 1034 07 | 634 26 |
| 28 | 1043 62 | 637 21 |
| 29 | 1053 12 | 640 34 |
| 30 | 1062 55 | 643 67 |
| 31 | 1071 91 | 647 18 |
| 32 | 1081 20 | 650 88 |
| 33 | 1090 42 | 654 76 |
| 34 | 1099 56 | 658 83 |
| 35 | 1108 61 | 663 07 |
| 36 | 1117 57 | 667 50 |
| 37 | 1126 45 | 672 11 |
| 38 | 1135 23 | 676 89 |
| 39 | 1143 92 | 681 85 |
| 40 | 1152 50 | 686 98 |
| 41 | 1160 98 | 692 28 |
| 42 | 1169 35 | 697 75 |
| 43 | 1177 62 | 703 38 |
| 44 | 1185 76 | 709 18 |
| 45 | 1193 79 | 715 14 |
| 46 | 1201 70 | 721 26 |
| 47 | 1203 85 | 722 99 |

Circle Center At X = 891 5 Y = 1114 1 and Radius 500 5
 *** 0 938 ***

Individual data on the 47 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 8 | 1128 8 | 0 0 | 0 0 | 0 0 | 0 0 | 338 6 | 0 0 | 0 0 |
| 2 | 9 8 | 3355 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1006 7 | 0 0 | 0 0 |
| 3 | 9 8 | 5507 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1652 4 | 0 0 | 0 0 |
| 4 | 9 9 | 7580 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2274 3 | 0 0 | 0 0 |
| 5 | 9 9 | 9570 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2871 1 | 0 0 | 0 0 |
| 6 | 9 9 | 11472 7 | 0 0 | 0 0 | 0 0 | 0 0 | 3441 8 | 0 0 | 0 0 |
| 7 | 9 9 | 13283 8 | 0 0 | 0 0 | 0 0 | 0 0 | 3985 1 | 0 0 | 0 0 |
| 8 | 10 0 | 15000 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4500 0 | 0 0 | 0 0 |
| 9 | 10 0 | 16618 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4985 6 | 0 0 | 0 0 |
| 10 | 10 0 | 18136 4 | 0 0 | 0 0 | 0 0 | 0 0 | 5440 9 | 0 0 | 0 0 |
| 11 | 10 0 | 19550 5 | 0 0 | 0 0 | 0 0 | 0 0 | 5865 2 | 0 0 | 0 0 |
| 12 | 10 0 | 20858 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6257 6 | 0 0 | 0 0 |
| 13 | 10 0 | 22058 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6617 6 | 0 0 | 0 0 |
| 14 | 10 0 | 23148 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6944 6 | 0 0 | 0 0 |
| 15 | 10 0 | 24127 0 | 0 0 | 0 0 | 0 0 | 0 0 | 7238 1 | 0 0 | 0 0 |
| 16 | 10 0 | 24992 5 | 0 0 | 0 0 | 0 0 | 0 0 | 7497 8 | 0 0 | 0 0 |
| 17 | 10 0 | 25744 0 | 0 0 | 0 0 | 0 0 | 0 0 | 7723 2 | 0 0 | 0 0 |
| 18 | 9 9 | 26381 2 | 0 0 | 0 0 | 0 0 | 0 0 | 7914 3 | 0 0 | 0 0 |
| 19 | 9 9 | 26903 2 | 0 0 | 0 0 | 0 0 | 0 0 | 8071 0 | 0 0 | 0 0 |

38/46

| | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|--------|-----|-----|
| 20 | 9 9 | 27310 2 | 0 0 | 0 0 | 0 0 | 0 0 | 8193 1 | 0 0 | 0 0 |
| 21 | 9 8 | 27602 0 | 0 0 | 0 0 | 0 0 | 0 0 | 8280 6 | 0 0 | 0 0 |
| 22 | 9 8 | 27779 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8333 8 | 0 0 | 0 0 |
| 23 | 9 8 | 27843 1 | 0 0 | 0 0 | 0 0 | 0 0 | 8352 9 | 0 0 | 0 0 |
| 24 | 9 7 | 27794 0 | 0 0 | 0 0 | 0 0 | 0 0 | 8338 2 | 0 0 | 0 0 |
| 25 | 9 7 | 27633 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8290 1 | 0 0 | 0 0 |
| 26 | 9 6 | 27363 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8209 1 | 0 0 | 0 0 |
| 27 | 9 6 | 26985 1 | 0 0 | 0 0 | 0 0 | 0 0 | 8095 5 | 0 0 | 0 0 |
| 28 | 9 5 | 26501 3 | 0 0 | 0 0 | 0 0 | 0 0 | 7950 4 | 0 0 | 0 0 |
| 29 | 9 4 | 25913 9 | 0 0 | 0 0 | 0 0 | 0 0 | 7774 2 | 0 0 | 0 0 |
| 30 | 9 4 | 25226 3 | 0 0 | 0 0 | 0 0 | 0 0 | 7567 9 | 0 0 | 0 0 |
| 31 | 9 3 | 24440 9 | 0 0 | 0 0 | 0 0 | 0 0 | 7332 3 | 0 0 | 0 0 |
| 32 | 9 2 | 23561 2 | 0 0 | 0 0 | 0 0 | 0 0 | 7068 4 | 0 0 | 0 0 |
| 33 | 9 1 | 22590 3 | 0 0 | 0 0 | 0 0 | 0 0 | 6777 1 | 0 0 | 0 0 |
| 34 | 9 1 | 21532 5 | 0 0 | 0 0 | 0 0 | 0 0 | 6459 8 | 0 0 | 0 0 |
| 35 | 9 0 | 20391 5 | 0 0 | 0 0 | 0 0 | 0 0 | 6117 4 | 0 0 | 0 0 |
| 36 | 8 9 | 19171 2 | 0 0 | 0 0 | 0 0 | 0 0 | 5751 4 | 0 0 | 0 0 |
| 37 | 8 8 | 17876 6 | 0 0 | 0 0 | 0 0 | 0 0 | 5363 0 | 0 0 | 0 0 |
| 38 | 8 7 | 16512 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4953 6 | 0 0 | 0 0 |
| 39 | 6 1 | 10818 3 | 0 0 | 0 0 | 0 0 | 0 0 | 3245 5 | 0 0 | 0 0 |
| 40 | 2 5 | 4233 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1270 0 | 0 0 | 0 0 |
| 41 | 8 5 | 13036 7 | 0 0 | 0 0 | 0 0 | 0 0 | 3911 0 | 0 0 | 0 0 |
| 42 | 8 4 | 10813 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3244 0 | 0 0 | 0 0 |
| 43 | 8 3 | 8567 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2570 3 | 0 0 | 0 0 |
| 44 | 8 1 | 6306 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1891 9 | 0 0 | 0 0 |
| 45 | 8 0 | 4035 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1210 6 | 0 0 | 0 0 |
| 46 | 7 9 | 1761 3 | 0 0 | 0 0 | 0 0 | 0 0 | 528 4 | 0 0 | 0 0 |
| 47 | 2 2 | 86 7 | 0 0 | 0 0 | 0 0 | 0 0 | 26 0 | 0 0 | 0 0 |

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 98 | 619 23 |
| 3 | 775 75 | 617 12 |
| 4 | 785 57 | 615 23 |
| 5 | 795 43 | 613 55 |
| 6 | 805 32 | 612 10 |
| 7 | 815 24 | 610 86 |
| 8 | 825 19 | 609 85 |
| 9 | 835 16 | 609 06 |
| 10 | 845 15 | 608 49 |
| 11 | 855 14 | 608 15 |
| 12 | 865 14 | 608 03 |
| 13 | 875 14 | 608 13 |
| 14 | 885 13 | 608 45 |
| 15 | 895 12 | 609 00 |
| 16 | 905 09 | 609 77 |
| 17 | 915 04 | 610 76 |
| 18 | 924 97 | 611 97 |
| 19 | 934 86 | 613 41 |
| 20 | 944 73 | 615 06 |
| 21 | 954 55 | 616 93 |
| 22 | 964 33 | 619 03 |
| 23 | 974 06 | 621 34 |
| 24 | 983 73 | 623 86 |
| 25 | 993 35 | 626 60 |
| 26 | 1002 90 | 629 56 |
| 27 | 1012 39 | 632 72 |
| 28 | 1021 80 | 636 10 |
| 29 | 1031 13 | 639 69 |
| 30 | 1040 39 | 643 48 |
| 31 | 1049 55 | 647 48 |
| 32 | 1058 63 | 651 69 |
| 33 | 1067 60 | 656 09 |
| 34 | 1076 48 | 660 69 |
| 35 | 1085 25 | 665 49 |
| 36 | 1093 92 | 670 49 |
| 37 | 1102 47 | 675 67 |

| | | | | |
|----|------|----|-----|----|
| 38 | 1110 | 90 | 681 | 05 |
| 39 | 1119 | 21 | 686 | 61 |
| 40 | 1127 | 40 | 692 | 36 |
| 41 | 1135 | 45 | 698 | 28 |
| 42 | 1143 | 37 | 704 | 39 |
| 43 | 1151 | 15 | 710 | 67 |
| 44 | 1158 | 79 | 717 | 12 |
| 45 | 1162 | 86 | 720 | 71 |

Circle Center At X = 865 6 Y = 1056 5 and Radius 448 5
 *** 0 939 ***

Failure Surface Specified By 57 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 18 | 620 42 |
| 3 | 776 13 | 619 38 |
| 4 | 786 09 | 618 46 |
| 5 | 796 06 | 617 65 |
| 6 | 806 03 | 616 96 |
| 7 | 816 01 | 616 38 |
| 8 | 826 00 | 615 91 |
| 9 | 836 00 | 615 55 |
| 10 | 845 99 | 615 31 |
| 11 | 855 99 | 615 19 |
| 12 | 865 99 | 615 18 |
| 13 | 875 99 | 615 28 |
| 14 | 885 99 | 615 49 |
| 15 | 895 99 | 615 82 |
| 16 | 905 98 | 616 26 |
| 17 | 915 96 | 616 82 |
| 18 | 925 94 | 617 49 |
| 19 | 935 91 | 618 27 |
| 20 | 945 87 | 619 16 |
| 21 | 955 82 | 620 17 |
| 22 | 965 75 | 621 29 |
| 23 | 975 68 | 622 53 |
| 24 | 985 59 | 623 88 |
| 25 | 995 48 | 625 34 |
| 26 | 1005 35 | 626 91 |
| 27 | 1015 21 | 628 59 |
| 28 | 1025 05 | 630 39 |
| 29 | 1034 86 | 632 30 |
| 30 | 1044 66 | 634 32 |
| 31 | 1054 43 | 636 45 |
| 32 | 1064 17 | 638 69 |
| 33 | 1073 89 | 641 04 |
| 34 | 1083 58 | 643 51 |
| 35 | 1093 25 | 646 08 |
| 36 | 1102 88 | 648 76 |
| 37 | 1112 48 | 651 56 |
| 38 | 1122 05 | 654 46 |
| 39 | 1131 59 | 657 47 |
| 40 | 1141 09 | 660 59 |
| 41 | 1150 56 | 663 81 |
| 42 | 1159 99 | 667 14 |
| 43 | 1169 37 | 670 58 |
| 44 | 1178 72 | 674 13 |
| 45 | 1188 03 | 677 78 |
| 46 | 1197 30 | 681 54 |
| 47 | 1206 52 | 685 41 |
| 48 | 1215 70 | 689 38 |
| 49 | 1224 84 | 693 45 |
| 50 | 1233 92 | 697 62 |
| 51 | 1242 96 | 701 90 |
| 52 | 1251 95 | 706 28 |
| 53 | 1260 89 | 710 77 |
| 54 | 1269 77 | 715 35 |
| 55 | 1278 61 | 720 04 |

40/46

56 1287 39 724 82
 57 1292 96 727 94
 Circle Center At X = 862 1 Y = 1494 6 and Radius 879 5
 *** 0 943 ***

Failure Surface Specified By 58 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 20 | 620 53 |
| 3 | 776 15 | 619 61 |
| 4 | 786 12 | 618 79 |
| 5 | 796 10 | 618 08 |
| 6 | 806 08 | 617 48 |
| 7 | 816 07 | 616 99 |
| 8 | 826 06 | 616 60 |
| 9 | 836 05 | 616 32 |
| 10 | 846 05 | 616 15 |
| 11 | 856 05 | 616 09 |
| 12 | 866 05 | 616 14 |
| 13 | 876 05 | 616 30 |
| 14 | 886 05 | 616 56 |
| 15 | 896 04 | 616 93 |
| 16 | 906 03 | 617 41 |
| 17 | 916 01 | 618 00 |
| 18 | 925 99 | 618 69 |
| 19 | 935 96 | 619 49 |
| 20 | 945 91 | 620 40 |
| 21 | 955 86 | 621 42 |
| 22 | 965 80 | 622 55 |
| 23 | 975 72 | 623 78 |
| 24 | 985 63 | 625 12 |
| 25 | 995 53 | 626 57 |
| 26 | 1005 41 | 628 12 |
| 27 | 1015 27 | 629 78 |
| 28 | 1025 11 | 631 55 |
| 29 | 1034 93 | 633 42 |
| 30 | 1044 74 | 635 40 |
| 31 | 1054 52 | 637 48 |
| 32 | 1064 27 | 639 67 |
| 33 | 1074 01 | 641 97 |
| 34 | 1083 71 | 644 37 |
| 35 | 1093 39 | 646 88 |
| 36 | 1103 05 | 649 49 |
| 37 | 1112 67 | 652 20 |
| 38 | 1122 27 | 655 02 |
| 39 | 1131 83 | 657 94 |
| 40 | 1141 36 | 660 97 |
| 41 | 1150 86 | 664 09 |
| 42 | 1160 32 | 667 32 |
| 43 | 1169 75 | 670 66 |
| 44 | 1179 14 | 674 09 |
| 45 | 1188 50 | 677 63 |
| 46 | 1197 81 | 681 26 |
| 47 | 1207 09 | 685 00 |
| 48 | 1216 32 | 688 84 |
| 49 | 1225 52 | 692 77 |
| 50 | 1234 67 | 696 81 |
| 51 | 1243 77 | 700 94 |
| 52 | 1252 83 | 705 17 |
| 53 | 1261 85 | 709 50 |
| 54 | 1270 81 | 713 93 |
| 55 | 1279 73 | 718 45 |
| 56 | 1288 60 | 723 07 |
| 57 | 1297 42 | 727 79 |
| 58 | 1298 23 | 728 23 |

Circle Center At X = 856 7 Y = 1541 3 and Radius 925 2
 *** 0 946 ***

Failure Surface Specified By 52 Coordinate Points

21/26

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 79 | 624 37 |
| 3 | 796 54 | 622 15 |
| 4 | 806 33 | 620 10 |
| 5 | 816 15 | 618 23 |
| 6 | 826 01 | 616 53 |
| 7 | 835 89 | 615 01 |
| 8 | 845 80 | 613 68 |
| 9 | 855 73 | 612 52 |
| 10 | 865 69 | 611 54 |
| 11 | 875 65 | 610 74 |
| 12 | 885 64 | 610 12 |
| 13 | 895 63 | 609 67 |
| 14 | 905 62 | 609 41 |
| 15 | 915 62 | 609 33 |
| 16 | 925 62 | 609 43 |
| 17 | 935 62 | 609 71 |
| 18 | 945 61 | 610 17 |
| 19 | 955 59 | 610 81 |
| 20 | 965 55 | 611 63 |
| 21 | 975 50 | 612 63 |
| 22 | 985 43 | 613 81 |
| 23 | 995 34 | 615 17 |
| 24 | 1005 22 | 616 70 |
| 25 | 1015 07 | 618 41 |
| 26 | 1024 89 | 620 30 |
| 27 | 1034 68 | 622 37 |
| 28 | 1044 42 | 624 61 |
| 29 | 1054 13 | 627 03 |
| 30 | 1063 78 | 629 62 |
| 31 | 1073 39 | 632 39 |
| 32 | 1082 95 | 635 33 |
| 33 | 1092 46 | 638 44 |
| 34 | 1101 90 | 641 72 |
| 35 | 1111 29 | 645 17 |
| 36 | 1120 61 | 648 79 |
| 37 | 1129 86 | 652 58 |
| 38 | 1139 05 | 656 54 |
| 39 | 1148 16 | 660 65 |
| 40 | 1157 20 | 664 94 |
| 41 | 1166 16 | 669 38 |
| 42 | 1175 03 | 673 99 |
| 43 | 1183 83 | 678 75 |
| 44 | 1192 53 | 683 67 |
| 45 | 1201 15 | 688 75 |
| 46 | 1209 67 | 693 98 |
| 47 | 1218 09 | 699 37 |
| 48 | 1226 42 | 704 90 |
| 49 | 1234 65 | 710 59 |
| 50 | 1242 77 | 716 42 |
| 51 | 1250 79 | 722 40 |
| 52 | 1255 24 | 725 85 |

Circle Center At X = 915 1 Y = 1164 1 and Radius 554 8
 *** 0 947 ***

Failure Surface Specified By 54 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 62 | 623 23 |
| 3 | 786 59 | 622 40 |
| 4 | 796 56 | 621 69 |
| 5 | 806 55 | 621 09 |
| 6 | 816 53 | 620 61 |
| 7 | 826 53 | 620 24 |
| 8 | 836 52 | 619 99 |
| 9 | 846 52 | 619 85 |

42/No

| | | |
|----|---------|--------|
| 10 | 856 52 | 619 83 |
| 11 | 866 52 | 619 92 |
| 12 | 876 52 | 620 13 |
| 13 | 886 52 | 620 45 |
| 14 | 896 51 | 620 89 |
| 15 | 906 49 | 621 44 |
| 16 | 916 47 | 622 11 |
| 17 | 926 44 | 622 89 |
| 18 | 936 40 | 623 78 |
| 19 | 946 35 | 624 79 |
| 20 | 956 28 | 625 91 |
| 21 | 966 21 | 627 15 |
| 22 | 976 12 | 628 50 |
| 23 | 986 01 | 629 97 |
| 24 | 995 88 | 631 55 |
| 25 | 1005 74 | 633 24 |
| 26 | 1015 57 | 635 04 |
| 27 | 1025 39 | 636 96 |
| 28 | 1035 18 | 638 99 |
| 29 | 1044 95 | 641 13 |
| 30 | 1054 69 | 643 39 |
| 31 | 1064 41 | 645 75 |
| 32 | 1074 09 | 648 23 |
| 33 | 1083 75 | 650 82 |
| 34 | 1093 38 | 653 52 |
| 35 | 1102 98 | 656 33 |
| 36 | 1112 54 | 659 25 |
| 37 | 1122 07 | 662 28 |
| 38 | 1131 57 | 665 41 |
| 39 | 1141 03 | 668 66 |
| 40 | 1150 45 | 672 02 |
| 41 | 1159 83 | 675 48 |
| 42 | 1169 17 | 679 05 |
| 43 | 1178 47 | 682 73 |
| 44 | 1187 72 | 686 52 |
| 45 | 1196 94 | 690 41 |
| 46 | 1206 10 | 694 40 |
| 47 | 1215 22 | 698 50 |
| 48 | 1224 30 | 702 71 |
| 49 | 1233 32 | 707 02 |
| 50 | 1242 29 | 711 43 |
| 51 | 1251 21 | 715 95 |
| 52 | 1260 08 | 720 57 |
| 53 | 1268 90 | 725 29 |
| 54 | 1271 57 | 726 75 |

Circle Center At X = 853 5 , Y = 1490 5 and Radius, 870 7
*** 0 947 ***

Failure Surface Specified By 46 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 83 | 630 69 |
| 3 | 817 77 | 629 55 |
| 4 | 827 72 | 628 57 |
| 5 | 837 69 | 627 74 |
| 6 | 847 66 | 627 08 |
| 7 | 857 65 | 626 57 |
| 8 | 867 65 | 626 22 |
| 9 | 877 64 | 626 03 |
| 10 | 887 64 | 626 00 |
| 11 | 897 64 | 626 12 |
| 12 | 907 64 | 626 41 |
| 13 | 917 63 | 626 85 |
| 14 | 927 61 | 627 44 |
| 15 | 937 58 | 628 20 |
| 16 | 947 54 | 629 11 |
| 17 | 957 48 | 630 19 |
| 18 | 967 41 | 631 41 |

43/46

| | | |
|----|---------|--------|
| 19 | 977 31 | 632 80 |
| 20 | 987 19 | 634 34 |
| 21 | 997 05 | 636 04 |
| 22 | 1006 87 | 637 89 |
| 23 | 1016 67 | 639 90 |
| 24 | 1026 43 | 542 06 |
| 25 | 1036 16 | 544 38 |
| 26 | 1045 85 | 646 84 |
| 27 | 1055 50 | 649 47 |
| 28 | 1065 11 | 652 24 |
| 29 | 1074 67 | 655 17 |
| 30 | 1084 19 | 658 25 |
| 31 | 1093 65 | 661 47 |
| 32 | 1103 06 | 664 85 |
| 33 | 1112 42 | 668 37 |
| 34 | 1121 72 | 672 05 |
| 35 | 1130 97 | 675 86 |
| 36 | 1140 15 | 679 83 |
| 37 | 1149 26 | 683 94 |
| 38 | 1158 31 | 688 19 |
| 39 | 1167 30 | 692 58 |
| 40 | 1176 21 | 697 12 |
| 41 | 1185 05 | 701 80 |
| 42 | 1193 81 | 706 61 |
| 43 | 1202 50 | 711 57 |
| 44 | 1211 11 | 716 66 |
| 45 | 1219 63 | 721 88 |
| 46 | 1223 06 | 724 06 |

Circle Center At X = 884 8 Y = 1258 5 and Radius 632 5
 *** 0 951 ***

Failure Surface Specified By 56 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 23 | 620 99 |
| 3 | 776 22 | 620 50 |
| 4 | 786 22 | 620 12 |
| 5 | 796 21 | 619 83 |
| 6 | 806 21 | 619 63 |
| 7 | 816 21 | 619 54 |
| 8 | 826 21 | 619 53 |
| 9 | 836 21 | 619 63 |
| 10 | 846 21 | 619 82 |
| 11 | 856 20 | 620 10 |
| 12 | 866 19 | 620 48 |
| 13 | 876 18 | 620 96 |
| 14 | 886 17 | 621 53 |
| 15 | 896 14 | 622 20 |
| 16 | 906 12 | 622 96 |
| 17 | 916 08 | 623 82 |
| 18 | 926 03 | 624 78 |
| 19 | 935 98 | 625 83 |
| 20 | 945 91 | 626 98 |
| 21 | 955 83 | 628 22 |
| 22 | 965 74 | 629 55 |
| 23 | 975 64 | 630 99 |
| 24 | 985 52 | 632 51 |
| 25 | 995 39 | 634 13 |
| 26 | 1005 24 | 635 85 |
| 27 | 1015 08 | 637 66 |
| 28 | 1024 90 | 639 56 |
| 29 | 1034 69 | 641 56 |
| 30 | 1044 47 | 643 65 |
| 31 | 1054 23 | 645 84 |
| 32 | 1063 97 | 648 12 |
| 33 | 1073 66 | 650 49 |
| 34 | 1083 37 | 652 95 |
| 35 | 1093 04 | 655 51 |

44/26

| | | |
|----|---------|--------|
| 36 | 1102 68 | 658 16 |
| 37 | 1112 30 | 660 91 |
| 38 | 1121 89 | 663 74 |
| 39 | 1131 45 | 666 67 |
| 40 | 1140 98 | 669 69 |
| 41 | 1150 49 | 672 80 |
| 42 | 1159 96 | 676 00 |
| 43 | 1169 41 | 679 29 |
| 44 | 1178 82 | 682 67 |
| 45 | 1188 19 | 686 15 |
| 46 | 1197 54 | 689 71 |
| 47 | 1206 85 | 693 36 |
| 48 | 1216 12 | 697 10 |
| 49 | 1225 36 | 700 93 |
| 50 | 1234 56 | 704 85 |
| 51 | 1243 72 | 708 85 |
| 52 | 1252 85 | 712 95 |
| 53 | 1261 93 | 717 13 |
| 54 | 1270 97 | 721 39 |
| 55 | 1279 98 | 725 75 |
| 56 | 1283 32 | 727 41 |

Circle Center At X = 821 5 Y = 1662 1 and Radius 1042 6
*** 0 953 ***

Failure Surface Specified By 57 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 23 | 620 93 |
| 3 | 776 22 | 620 39 |
| 4 | 786 21 | 619 95 |
| 5 | 796 20 | 619 60 |
| 6 | 806 20 | 619 34 |
| 7 | 816 20 | 619 18 |
| 8 | 826 20 | 619 11 |
| 9 | 836 20 | 619 14 |
| 10 | 846 19 | 619 26 |
| 11 | 856 19 | 619 47 |
| 12 | 866 19 | 619 77 |
| 13 | 876 18 | 620 17 |
| 14 | 886 17 | 620 67 |
| 15 | 896 15 | 621 25 |
| 16 | 906 13 | 621 93 |
| 17 | 916 10 | 622 71 |
| 18 | 926 06 | 623 57 |
| 19 | 936 01 | 624 53 |
| 20 | 945 96 | 625 59 |
| 21 | 955 89 | 626 73 |
| 22 | 965 81 | 627 97 |
| 23 | 975 73 | 629 31 |
| 24 | 985 62 | 630 73 |
| 25 | 995 51 | 632 25 |
| 26 | 1005 38 | 633 86 |
| 27 | 1015 23 | 635 56 |
| 28 | 1025 07 | 637 36 |
| 29 | 1034 89 | 639 25 |
| 30 | 1044 69 | 641 23 |
| 31 | 1054 47 | 643 30 |
| 32 | 1064 24 | 645 46 |
| 33 | 1073 98 | 647 71 |
| 34 | 1083 70 | 650 06 |
| 35 | 1093 40 | 652 50 |
| 36 | 1103 08 | 655 02 |
| 37 | 1112 73 | 657 64 |
| 38 | 1122 35 | 660 35 |
| 39 | 1131 95 | 663 15 |
| 40 | 1141 53 | 666 03 |
| 41 | 1151 07 | 669 01 |
| 42 | 1160 59 | 672 08 |

45/Me

| | | |
|----|---------|--------|
| 43 | 1170 08 | 675 23 |
| 44 | 1179 54 | 678 48 |
| 45 | 1188 97 | 681 81 |
| 46 | 1198 36 | 685 23 |
| 47 | 1207 73 | 688 74 |
| 48 | 1217 06 | 692 34 |
| 49 | 1226 36 | 696 02 |
| 50 | 1235 62 | 699 79 |
| 51 | 1244 84 | 703 65 |
| 52 | 1254 03 | 707 60 |
| 53 | 1263 19 | 711 63 |
| 54 | 1272 30 | 715 74 |
| 55 | 1281 37 | 719 94 |
| 56 | 1290 41 | 724 23 |
| 57 | 1298 71 | 728 26 |

Circle Center At X = 828 6 Y = 1686 3 and Radius 1067 2
*** 0 954 ***

Failure Surface Specified By 48 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 85 | 630 85 |
| 3 | 817 80 | 629 86 |
| 4 | 827 77 | 629 01 |
| 5 | 837 74 | 628 30 |
| 6 | 847 73 | 627 74 |
| 7 | 857 72 | 627 31 |
| 8 | 867 71 | 627 02 |
| 9 | 877 71 | 626 87 |
| 10 | 887 71 | 626 86 |
| 11 | 897 71 | 626 99 |
| 12 | 907 71 | 627 27 |
| 13 | 917 70 | 627 68 |
| 14 | 927 68 | 628 23 |
| 15 | 937 66 | 628 92 |
| 16 | 947 63 | 629 76 |
| 17 | 957 58 | 630 73 |
| 18 | 967 52 | 631 84 |
| 19 | 977 44 | 633 09 |
| 20 | 987 34 | 634 48 |
| 21 | 997 22 | 636 01 |
| 22 | 1007 08 | 637 68 |
| 23 | 1016 92 | 639 49 |
| 24 | 1026 73 | 641 43 |
| 25 | 1036 51 | 643 51 |
| 26 | 1046 26 | 645 73 |
| 27 | 1055 98 | 648 08 |
| 28 | 1065 66 | 650 58 |
| 29 | 1075 31 | 653 20 |
| 30 | 1084 92 | 655 96 |
| 31 | 1094 49 | 658 86 |
| 32 | 1104 02 | 661 89 |
| 33 | 1113 51 | 665 05 |
| 34 | 1122 95 | 668 35 |
| 35 | 1132 35 | 671 78 |
| 36 | 1141 69 | 675 34 |
| 37 | 1150 98 | 679 03 |
| 38 | 1160 22 | 682 85 |
| 39 | 1169 41 | 686 80 |
| 40 | 1178 54 | 690 88 |
| 41 | 1187 61 | 695 09 |
| 42 | 1196 63 | 699 42 |
| 43 | 1205 58 | 703 88 |
| 44 | 1214 46 | 708 47 |
| 45 | 1223 29 | 713 17 |
| 46 | 1232 04 | 718 01 |
| 47 | 1240 73 | 722 96 |
| 48 | 1244 62 | 725 26 |

46/46

Circle Center At X = 883 3 Y = 1339 4 and Radius 712 5
*** 0 956 ***

ATTACHMENT 3· SETTLEMENT CALCULATIONS

| | | | | | |
|---------|---------------------------------|----------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Leachate Collection | Checked | PHD | Date | 4/24/10 |
| Task | LCRS Settlement | Page | 1 of 2 | | |
| Job # | Dept 00143 | No | 125184 | | |

3.1 Task

- A Determine the settlement along the leachate piping alignments
 - a Verify that positive drainage towards the sumps is maintained after placement of the waste
 - b Verify maximum strains along the leachate do not exceed the maximum allowed

3.2 References

- A Earthtec Testing & Engineering, P C (2006) Geotechnical Study Intermountain Regional Landfill
- B Das, B , (1990) Principles of Foundation Engineering, 2nd Ed
- C HDR (2010) Determination of the MHA and Design EQ Calculations, 1 0
- D HDR (2010) Slope Stability Calculations and determination of soil design values, 2 3 C
- E Koerner, R M (2005) Designing With Geosynthetics, 5th Ed

3.3 Analysis

- A Determine the consolidation values of the compressible zone soil based on Reference A
- B Determine the thickness of the compressible zone, Hc
- C Determine the initial pressure at the center of the compressible zone, P1
- D Determine the pressure at the center of the compressible zone after excavation, P2
- E Determine the final pressure at the center of the compressible zone, after waste placement, P3
- F Calculation of Settlement

$$S_c = \left(\left(\frac{C_s * H_c}{1 + e_0} \right) \text{Log} \frac{P_c}{P_0} \right) + \left(\left(\frac{C_c * H_c}{1 + e_0} \right) \text{Log} \left(\frac{P_0 + \Delta P}{P_c} \right) \right)$$

Where

Sc = Total consolidation settlement

Cs = Swell Index

Cc = Compression Index

P0 = Pressure after excavation (prior to filling with waste), P2

e0 = initial void ratio after excavation

Pc = Preconsolidation pressure, Ref A and attached = 2.4 KSF

He = Thickness of compressive soil = 100 FT

ΔP = Change in pressure, P3 – P2 KSF

Since, P0 > Pc (P2 > Pc), Disregard the settlement on the swell index part of the curve

| | | | | | |
|---------|---------------------------------|-------------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Leachate Collection | Checked | <i>PHD</i> | Date | 4 26 10 |
| Task | LCRS Settlement | Page 2 of 2 | | | |
| Job # | Dept 00143 | No | 125184 | | |

i) Settlement

| Pt # | Depth to Center (FT) | Initial Pressure, P1 (KSF) | Thickness of Excavation (FT) | Pressure after Excavation P2 (KSF) | Thickness of Waste (FT) | Final Pressure, P3 (KSF) | Total Change in Pressure, ΔP (KSF) | Settlement (IN) | Settlement (FT) |
|------|----------------------|----------------------------|------------------------------|------------------------------------|-------------------------|--------------------------|------------------------------------|-----------------|-----------------|
| 1 | 70.0 | 8.47 | 20.0 | 6.05 | 42.0 | 8.57 | 2.52 | 18.7 | 1.6 |
| 2 | 72.0 | 8.71 | 22.0 | 6.05 | 72.0 | 10.37 | 4.32 | 21.5 | 1.8 |
| 3 | 75.0 | 9.08 | 25.0 | 6.05 | 100.0 | 12.05 | 6.00 | 23.7 | 2.0 |
| 4 | 82.0 | 9.92 | 32.0 | 6.05 | 134.0 | 14.09 | 8.04 | 26.0 | 2.2 |
| 5 | 90.0 | 10.89 | 40.0 | 6.05 | 73.0 | 10.43 | 4.38 | 21.6 | 1.8 |
| 6 | 95.0 | 11.50 | 45.0 | 6.05 | 46.0 | 8.81 | 2.76 | 19.1 | 1.6 |

| | |
|------------------|------------------------------|
| Soil M Density = | 121.0 (PCF) |
| Waste Density = | 60.0 (PCF) |
| Cr = Cc = | 0.048 Ref A and see attached |
| Hc = | 100.0 FT (assumed) |
| e0 = | 0.704 Ref A and see attached |
| Pc = | 2.4 KSF |

ii) Slope and Strain Check along Leachate lines See also attached sketch

| Pt # | Distance (FT) | Initial Slope | Initial Elev (FT) | Initial Length (FT) | Settlement at Left Point (FT) | Settlement at Right Point (FT) | Final Elev (FT) | Final Slope | Verify '+=OK '- | Final Length (FT) | Strain |
|------|---------------|---------------|-------------------|---------------------|-------------------------------|--------------------------------|-----------------|-------------|-----------------|-------------------|---------|
| 1-2 | 120.0 | 1.50% | 1.8 | 120.0 | 1.60 | 1.83 | 2.03 | 1.69% | OK | 120.0 | 0.003% |
| 2-3 | 440.0 | 1.50% | 6.6 | 440.0 | 1.83 | 2.00 | 6.77 | 1.54% | OK | 440.1 | 0.001% |
| 3-4 | 550.0 | 1.50% | 8.3 | 550.1 | 2.00 | 2.17 | 8.42 | 1.53% | OK | 550.1 | 0.000% |
| 4-5 | 550.0 | 1.50% | 8.3 | 550.1 | 2.17 | 1.83 | 7.91 | 1.44% | OK | 550.1 | -0.001% |
| 5-6 | 500.0 | 1.50% | 7.5 | 500.1 | 1.83 | 1.58 | 7.25 | 1.45% | OK | 500.1 | -0.001% |


3.4 Conclusions

- A All segments of the leachate collection alignment remain positive towards the sump
- B Strains are less than 1 percent which is much less than maximum of 17%
Reference D, pg 442

**ATTACHMENT 3A: SETTLEMENT AND
CONSOLIDATION CALCULATIONS**

| | | | | | |
|---------|-------------------|----------|-----|------|---------|
| Project | IRL | Computed | Gms | Date | 3/20/10 |
| Subject | Settlement | Checked | PHP | Date | 4 26 10 |
| Task | Verify LCES slope | Page | 1 | of | 8 |
| Job # | 125/84 Dept 143 | No | | | |

Calculations Approach



$$\text{Initial length} = \sqrt{D^2 + \left[(\text{Initial slope}) * D \right]^2}$$

Final length =

$$\Delta_i = \text{Initial } \Delta f = D * (\text{Initial slope}) = \Delta_i$$

$$\Delta_f = \Delta_i + (S_R - S_L)$$

| Point # | Depth to Center | Initial Pressure P_1 (ksf)* | Thickness of Excavation | Pressure after EXCAT (ksf) | Tot Waste | P_3 (ksf) Pressure Final** | ΔP |
|---------|-----------------|-------------------------------|-------------------------|----------------------------|-----------|------------------------------|------------|
| ① | 70' | 8.47 | 20' | 6.05 | 42' | 8.57 | 2.52 |
| ② | 72' | 8.71 | 22' | 6.05 | 72' | 10.37 | 4.32 |
| ③ | 75' | 9.08 | 25' | 6.06 | 100' | 12.06 | 6.00 |
| ④ | 82' | 9.92 | 32' | 6.05 | 134' | 14.09 | 8.04 |
| ⑤ | 90' | 10.89 | 40' | 6.05 | 73' | 10.43 | 4.38 |
| ⑥ | 95' | 11.50 | 45' | 6.06 | 46' | 8.82 | 2.76 |

| # | S' | S'' |
|---|-------|-----|
| ① | 1.56' | 19" |
| ② | 1.79' | 22" |
| ③ | 1.98' | 24" |
| ④ | 2.17' | 26" |
| ⑤ | 1.80' | 22" |
| ⑥ | 1.59' | 19" |

$P_1 = (\text{Depth to Center}) * (\text{Moist unit wt of soil})$

$P_2 = P_1 - [\text{Thickness of Ex} * (\text{Moist unit wt of soil})]$


$P_3 = P_2 + [(\text{Thickness of waste fill}) * (\text{Moist unit wt. of waste})]$

Consolidation settlement

$$s_c = \frac{C_c H_c}{1+e_0} \log \frac{P_c}{P_0} + \frac{C_c H_c}{1+e_0} \log \frac{P_0 + \Delta P}{P_c}$$
 Das

$P_c = 24 \text{ ksf}$
 $P_0 = P_2$
 $\Delta P = P_3 - P_2$
 $C_c = C_r = 0.048$
 $H_c = 100'$
 $P_0 > P_c$
 $e_0 = 0.704$

* Moist Density = 121.0 PCF (soil)
 ** Moist Density = 60 PCF (waste - saturated)




CROSS SECTION EAST-WEST ALL CELLS

| | | | | |
|---|---|--|--|---|
| $\Delta - 170(0.015) = 18$ $22 - 19 = 3' = 0.25'$ $18 + 0.25 = 2.05'$ $\Delta = \frac{2.05}{120} = 1.7\% \text{ OK}$ | $\Delta - (120 \times 0.015) = 6.6$ $24 - 22 = 2' = 0.17$ $6.6 + 0.17 = 6.8$ $\Delta = \frac{6.8}{240} = 1.5\% \text{ OK}$ | $\Delta - (550 \times 0.015) = 8.25'$ $26 - 24 = 2' = 0.17'$ $8.42 = 1.5\% \text{ OK}$ | $\Delta - 550(0.015) = 8.25'$ $22 - 26 = -4' = -0.33'$ $8.25 - 0.33 = 7.92$ $\Delta = \frac{7.92}{550} = 1.44\% \text{ OK}$ | $\Delta - 500(0.015) = 7.5$ $19 - 22 = -3 = -0.25$ $\Delta - 7.5 - 0.25 = 7.25$ $\Delta = \frac{7.25}{50} = 1.45\% \text{ OK}$ |
|---|---|--|--|---|

$s = 20''$
 1-40 V
 1-200 H
 Sheet 7 of 12

CONSOLIDATION - SWELL TEST



$$e_1 = \frac{G_s \gamma_w}{\gamma_d} - 1 = \frac{2.7(62.4)}{97} - 1 = 0.737$$

$$C_s = \frac{0.710 - 0.697}{\log 8} = 0.014$$

| | |
|---------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TH-1 |
| Sample Depth | 15 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 97 |
| Natural Moisture, % | 21 |
| Liquid Limit | 77 |
| Plasticity Index | 51 |
| Water Added at | 1 ksf |
| Percent Swell | 07 |

$$P_0 = \frac{155(1.2)(97)}{1000 \text{ psf}} = 1.8 \text{ tsf}$$

$$C_c = \frac{0.722 - 0.697}{\log \frac{8}{2.4}} = 0.048$$


PROJECT NO 062496



FIGURE NO 30

5/8

CONSOLIDATION - SWELL TEST



0.812

-2.6
(0.974)

-4.1
(0.959)

$$e_L = \frac{27(62.4)}{93} - 1 = 0.812$$

$$C_r = \frac{(0.794 - 0.779)}{\log\left(\frac{8}{4}\right)} = 0.05$$

$$OCR = \frac{4.0 \text{ tsf}}{0.73 \text{ tsf}} = 55$$

$$C_s = \frac{e_3 - e_4}{\log\left(\frac{P_2}{P_1}\right)} = \frac{0.791 - 0.779}{\log\left(\frac{8}{1}\right)} = 0.013$$

$$P_0 = \frac{(6.5)(120)(930)}{1000 \text{ psf}} = 0.73 \text{ tsf}$$

$$LL = 71 \quad 0.0463 \left(\frac{71}{100}\right) 27 = 0.09$$

Project
Location
Sample Depth
Description
Soil Type
Dry Density, pcf
Natural Moisture, %
Liquid Limit
Plasticity Index
Water Added at
Percent Swell


Intermountain Regional Landfill
 TP-14
 6
 Block
 FTA CLAY (CH)
 93
 20
 71
 47
 1 ksf
 0.9

PROJECT NO 062496



FIGURE NO 28

CONSOLIDATION - SWELL TEST



$e_0 = 0.851$
 0.843
 0.834
 0.826

$$e_0 = \frac{C_s \gamma_w}{\gamma_d} - 1 - \frac{27(62.4)}{91} - 1 = 0.85$$

(100 ft) (60 pcf)
 wast

$$\frac{(50')(110)}{100} = 55 \text{ ksf}$$

$$\frac{50(110)}{1000 \text{ LBS}} = 1 \text{ kip}$$

$$C_s = \frac{0.837 - 0.826}{\log 8} = 0.012$$


| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-10 |
| Sample Depth | 8 1/2 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 91 |
| Natural Moisture, % | 26 |
| Liquid Limit | 70 |
| Plasticity Index | 50 |
| Water Added at | 1 ksf |
| Percent Swell | 11 |

$$P_0 = \frac{(9 \text{ Ft})(91)(126)}{1000} = 103 \text{ tsf}$$

$$OCR = \frac{1.7 \text{ tsf}}{10 \text{ tsf}} = 17$$

$$C_c = \frac{0.841 - 0.826}{\log \left(\frac{8}{17} \right)} = 0.022$$

CONSOLIDATION - SWELL TEST



$e_0 = \frac{27(62.4)}{90} = 1 = 0.872$

$C_c = \frac{0.872 - 0.848}{\log(8/30)} = 0.056$


Pressure (ksf) $P_c = 3.0 \text{ tsf}$
 $C_s = \frac{0.865 - 0.848}{\log 8} = 0.019$

| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-7 |
| Sample Depth | 9 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 90 |
| Natural Moisture, % | 23 |
| Liquid Limit | 70 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 15 |

$P_0 = \frac{925(1.23)(900 \text{ pcf})}{1000} = 102 \text{ tsf}$

$OCR = \frac{P_c}{P_0} = \frac{3.0 \text{ tsf}}{1.0 \text{ tsf}} = 3.0$

CONSOLIDATION - SWELL TEST



| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-15 |
| Sample Depth | 7 1/2 |
| Description | Block |
| Soil Type | FTA CLAY (CH) |
| Dry Density, pcf | 93 |
| Natural Moisture, % | 19 |
| Liquid Limit | 61 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 0.9 |

$P_0 = \frac{(8)(93)(19)}{1000} = 1.45 \text{ ksf}$

$P_0 = 0.9 \text{ ksf}$

$OCR = \frac{3.0 \text{ ksf}}{0.9 \text{ ksf}} = 3.3$

$C_{sw} = \frac{0.800 - 0.782}{\log \frac{8}{3}} = 0.042$

PROJECT NO 062496



FIGURE NO 29

APPENDIX D

Differential Settlement Update

Purpose: To recalculate the settlement along the leachate piping alignments to verify positive drainage towards the sumps is maintained and to ensure maximum strains on the HDPE liner along the leachate lines do not exceed the maximum allowable.

Method: The methodology outlined in the following publications were followed, consistent with the analysis completed by HDR for the original design:

Das, B., 2011. Principles of Foundation Engineering, 7th Edition.
Koerner, R M, 1990. Designing with Geosynthetics, 2nd Edition.

The following previous studies were also used as the basis for the analysis:

HDR, 2010. Slope Stability and Settlement Evaluation for Intermountain Regional Landfill, Fairfield, Utah.

Earthtec Testing & Engineering, PC, 2006. Geotechnical Study Intermountain Regional Landfill, Fairfield, Utah.

Required: In order to calculate the differential settlement, the following settlement equation will be used:

$$S_c = \left(\frac{C_s H_c}{1 + e_0} \text{Log} \frac{\sigma_c}{\sigma_0} \right) + \left(\frac{C_c H_c}{1 + e_0} \text{Log} \frac{\sigma_0 + \Delta\sigma}{\sigma_c} \right)$$

Where

H_c = Thickness of the compressible zone, 100 ft

S_c = Total consolidation settlement

C_s = Swelling index, 0

C_c = Compression index, 0.048

σ_0 = Pressure after excavation (prior to filling with waste), KSF

e_0 = Initial void ration after excavation, 0.704 according to Earthtec study

σ_c = Preconsolidation pressure, 2.4 KSF according to Earthtec study

$\Delta\sigma$ = Average increase in effective pressure on the clay layer after filling with waste, KSF

With Soil M density of 121 PCF and waste density of 60 PCF

Calculations:

Differential Settlement along main leachate line in Cell 2 (see attached drawing):


| ID | Depth to Center (ft) | Initial Pressure, σ_c (KSF) | Thickness of Excavation (ft) | Pressure After Excavation, σ_o (KSF) | Thickness of Waste (ft) | Final Pressure (KSF) | Total Change in Pressure, $\Delta\sigma$ (KSF) | Settlement, S_c (ft) |
|---------|----------------------|------------------------------------|------------------------------|---|-------------------------|----------------------|--|------------------------|
| 2+54.2 | 63.2 | 7.64 | 13.2 | 6.05 | 26.3 | 2.31 | -3.74 | -0.046 |
| 4+37.5 | 64.5 | 7.81 | 14.5 | 6.05 | 73.9 | 5.17 | -0.88 | 0.938 |
| 6+24.8 | 65.5 | 7.92 | 15.5 | 6.05 | 115.1 | 7.64 | 1.59 | 1.416 |
| 14+93.3 | 72.0 | 8.71 | 22.0 | 6.05 | 106.5 | 7.12 | 1.07 | 1.330 |
| 23+61.7 | 78.4 | 9.48 | 28.4 | 6.05 | 97.8 | 6.60 | 0.55 | 1.238 |
| 24+44.6 | 82.6 | 9.99 | 32.6 | 6.05 | 64.0 | 4.57 | -1.48 | 0.788 |

Check for positive slope on leachate line and liner strain:

| ID | Initial Length (ft) | Initial Difference Elevation (ft) | Settlement at 1 st Point (ft) | Settlement at 2 nd Point (ft) | Final Dif in Elevation (ft) | Final Slope Post Settlement (ft/ft) | Post Settlement Length (ft) | Liner Strain (%) |
|-----|---------------------|-----------------------------------|--|--|-----------------------------|-------------------------------------|-----------------------------|------------------|
| 1-2 | 183.29 | 1.8437 | -0.046 | 0.938 | 2.828 | 0.01543 | 183.3053 | 0.0068% |
| 2-3 | 187.37 | 1.8847 | 0.938 | 1.416 | 2.363 | 0.01261 | 187.3727 | 0.0029% |
| 3-4 | 868.46 | 8.7357 | 1.416 | 1.330 | 8.650 | 0.00996 | 868.4607 | -0.0001% |
| 4-5 | 868.53 | 8.7364 | 1.330 | 1.238 | 8.644 | 0.00995 | 868.5263 | -0.0001% |
| 5-6 | 132.38 | 1.3322 | 1.238 | 0.933 | 1.027 | 0.00776 | 132.4427 | 0.0492% |

The results of the updated differential settlement analysis confirm that the leachate and floor slopes will remain positive post-settlement. Likewise, liner strain will remain far below 1% which is well within the maximum 17% used as the criteria in the 2010 calculations.

FILE NAME: PROJECTS\373 - INTERMOUNTAIN REGIONAL LANDFILL\02.100 - LF REDESIGN\ENG\CALCULATIONS\APPENDIX D - HAL SETTLEMENT UPDATE\SETTLEMENT CALCULATION DIMENSIONS.DWG
FILE DATE: 10.26.2016 08:45:09 (CAH)



APPENDIX E

Leachate Collection and Removal System

HELP Model

Leachate Collection System Geonet/Leachate Pipe/Sump Sizing

Leachate Withdrawal Pipe and Leachate Collection Pipe Integrity

Geotextile Sizing for Geocomposite Selection

The HELP Model was used to determine leachate quantities for the leachate collection system as well as other useful information. The required input to the model was determined as listed below:

- The evaporation and solar radiation values that were used in the model were generated from default data corresponding to the Salt Lake area as designated in the HELP Model program.
- Precipitation and average temperature data input for Fairfield, Utah were taken from the Western Regional Climate Center database, found at www.wrcc.dri.edu.
- The evaporative zone depth was assumed to be 16 inches for the waste layer and 24 inches for the clay soils used as protective cover over the geosynthetic materials. These numbers were derived based on specific soils information and suggested values from the HELP Model Users Guide.
- The maximum leaf area index was assumed to be zero based on the arid desert conditions that exist in the Fairfield area.
- The Curve number for the protective cover soils was based on both NRCS soils data and geotechnical studies performed by both EARTHTEC Testing and Engineering and Applied Geotechnical Engineering Consultants, Inc. (AGEC). Using methods described in TR-55, it was determined that the majority of the soils that are intended to be used as protective cover over the geosynthetics materials are classified under the hydrologic classification of somewhere between C and D and that the cover type is Desert Shrub with poor coverage.
- The drainage net was applied as the default in the HELP model and then specific parameters altered to match typical geocomposite values
 - Thickness 0.25 inches
 - Hydraulic Conductivity 23.6 cm/sec

The model was set up according to the preliminary designs for the layer system. From the HELP Model manual, Table 4 entitled “Default Soil, Waste, and Geosynthetic Characteristics” was used to determine which layer classification to use. The model used 5-7 layers that are summarized below:

| Layer | Thickness (in.) | Porosity (Vol/Vol) | Hydraulic Conductivity (cm/sec) |
|--|-----------------|--------------------|---------------------------------|
| Soil Cover | 0-24 | 0.479 | 2.5E-5 |
| High Density Polyethylene - HDPE Liner | 0-0.06 | 0 | 2.0E-13 |
| Municipal Waste | 0-1,452 | 0.671 | 1.0E-3 |
| Protective Soil Cover | 24 | 0.479 | 2.5E-5 |
| Drainage Net – Geocomposite | 0.25 | 0.85 | 23.6 |
| HDPE Liner | 0.06 | 0 | 2.0E-13 |
| GCL | 0.25 | 0.75 | 3.0E-9 |

The Help Model was run for different waste heights in order to determine the prevailing condition to apply to the leachate collection system. This was determined to be at about the 10 ft range where from 10 to 121 ft (full waste height) the predicted peak daily value is relatively stable. Once the full waste height was reached, the model was run with and without the closure cap.

The results are summarized in the following table:

| Model Run – Waste Height | Peak Daily Collected at Geonet (in.) | Annual Average Collected at Geonet (in.) | Annual Average Runoff (in.) |
|-------------------------------------|---|---|--|
| No waste | 0.204 | 0.134 | 0.845 |
| 10 ft | 0.161 | 0.571 | 0.120 |
| 50 ft | 0.157 | 0.571 | 0.120 |
| 100 ft | 0.160 | 0.571 | 0.120 |
| 121 ft | 0.158 | 0.571 | 0.120 |
| Closure | 0.001 | 0.0128 | 1.885 |

Back to:

**NOTE:**

To print data frame (right side), click on right frame before printing.

1981 - 2010

- [Daily Temp. & Precip.](#)
- [Daily Tabular data \(~23 KB\)](#)
- [Monthly Tabular data \(~1 KB\)](#)
- [NCDC 1981-2010 Normals \(~3 KB\)](#)

1971 - 2000

- [Daily Temp. & Precip.](#)
- [Daily Tabular data \(~23 KB\)](#)
- [Monthly Tabular data \(~1 KB\)](#)
- [NCDC 1971-2000 Normals \(~3 KB\)](#)

1961 - 1990

- [Daily Temp. & Precip.](#)
- [Daily Tabular data \(~23 KB\)](#)
- [Monthly Tabular data \(~1 KB\)](#)
- [NCDC 1961-1990 Normals \(~3 KB\)](#)

Period of Record

- [Station Metadata](#)

FAIRFIELD, UTAH (422696)

1981-2010 Monthly Climate Summary


| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec |
|-----------------------------------|------|------|------|------|------|------|------|------|------|------|------|------|
| Average Max. Temperature (F) | 38.0 | 43.9 | 54.2 | 62.7 | 71.8 | 81.7 | 89.0 | 87.4 | 78.7 | 65.6 | 49.7 | 39.6 |
| Average Min. Temperature (F) | 12.2 | 17.1 | 24.8 | 30.2 | 37.4 | 44.1 | 50.6 | 49.7 | 40.3 | 29.4 | 20.8 | 13.9 |
| Average Total Precipitation (in.) | 1.07 | 1.05 | 1.15 | 1.20 | 1.31 | 0.78 | 0.90 | 0.96 | 1.02 | 1.18 | 1.04 | 1.06 |

Unofficial values based on averages/sums of smoothed daily data.


Information is computed from available daily data during the 1981-2010 period. Smoothing, missing data and observation-time changes may cause these 1981-2010 values to differ from official NCDC values. This table is presented for use at locations that don't have official NCDC data. No adjustments are made for missing data or time of observation. Check [NCDC normals](#) table for official data.

Western Regional Climate Center, wrcc@dri.edu







Soil Map—Fairfield-Nephi Area, Utah
(Intermountain Regional Landfill)



Warning: Soil Map may not be valid at this scale.



MAP LEGEND

| | |
|--|---|
|  Area of Interest (AOI) |  Spoil Area |
|  Soils |  Stony Spot |
|  Soil Map Unit Polygons |  Very Stony Spot |
|  Soil Map Unit Lines |  Wet Spot |
|  Soil Map Unit Points |  Other |
| Special Point Features |  Special Line Features |
|  Blowout | Water Features |
|  Borrow Pit |  Streams and Canals |
|  Clay Spot | Transportation |
|  Closed Depression |  Rails |
|  Gravel Pit |  Interstate Highways |
|  Gravelly Spot |  US Routes |
|  Landfill |  Major Roads |
|  Lava Flow |  Local Roads |
|  Marsh or swamp | Background |
|  Mine or Quarry |  Aerial Photography |
|  Miscellaneous Water | |
|  Perennial Water | |
|  Rock Outcrop | |
|  Saline Spot | |
|  Sandy Spot | |
|  Severely Eroded Spot | |
|  Sinkhole | |
|  Slide or Slip | |
|  Sodic Spot | |

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Fairfield-Nephi Area, Utah
Survey Area Data: Version 9, Sep 23, 2015

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 2, 2011—Aug 29, 2011

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

| Fairfield-Nephi Area, Utah (UT608) | | | |
|------------------------------------|---|--------------|----------------|
| Map Unit Symbol | Map Unit Name | Acres in AOI | Percent of AOI |
| Ce | Cheebe fine sandy loam | 5.4 | 1.4% |
| Cf | Cheebe silty clay loam | 117.5 | 30.5% |
| GbA | Genola silt loam, 0 to 1 percent slopes | 76.1 | 19.8% |
| GdDP | Goldrun loamy fine sand, hummocky, 0 to 10 percent slopes | 100.9 | 26.2% |
| GeD | Goldrun-Cheebe complex, 0 to 10 percent slopes | 85.3 | 22.1% |
| Totals for Area of Interest | | 385.2 | 100.0% |

Engineering Properties

This table gives the engineering classifications and the range of engineering properties for the layers of each soil in the survey area.

Hydrologic soil group is a group of soils having similar runoff potential under similar storm and cover conditions. The criteria for determining Hydrologic soil group is found in the National Engineering Handbook, Chapter 7 issued May 2007(<http://directives.sc.egov.usda.gov/OpenNonWebContent.aspx?content=17757.wba>). Listing HSGs by soil map unit component and not by soil series is a new concept for the engineers. Past engineering references contained lists of HSGs by soil series. Soil series are continually being defined and redefined, and the list of soil series names changes so frequently as to make the task of maintaining a single national list virtually impossible. Therefore, the criteria is now used to calculate the HSG using the component soil properties and no such national series lists will be maintained. All such references are obsolete and their use should be discontinued. Soil properties that influence runoff potential are those that influence the minimum rate of infiltration for a bare soil after prolonged wetting and when not frozen. These properties are depth to a seasonal high water table, saturated hydraulic conductivity after prolonged wetting, and depth to a layer with a very slow water transmission rate. Changes in soil properties caused by land management or climate changes also cause the hydrologic soil group to change. The influence of ground cover is treated independently. There are four hydrologic soil groups, A, B, C, and D, and three dual groups, A/D, B/D, and C/D. In the dual groups, the first letter is for drained areas and the second letter is for undrained areas.

The four hydrologic soil groups are described in the following paragraphs:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

Depth to the upper and lower boundaries of each layer is indicated.

Texture is given in the standard terms used by the U.S. Department of Agriculture. These terms are defined according to percentages of sand, silt, and clay in the fraction of the soil that is less than 2 millimeters in diameter. "Loam," for example, is soil that is 7 to 27 percent clay, 28 to 50 percent silt, and less than 52 percent sand. If the content of particles coarser than sand is 15 percent or more, an appropriate modifier is added, for example, "gravelly."

Classification of the soils is determined according to the Unified soil classification system (ASTM, 2005) and the system adopted by the American Association of State Highway and Transportation Officials (AASHTO, 2004).

The Unified system classifies soils according to properties that affect their use as construction material. Soils are classified according to particle-size distribution of the fraction less than 3 inches in diameter and according to plasticity index, liquid limit, and organic matter content. Sandy and gravelly soils are identified as GW, GP, GM, GC, SW, SP, SM, and SC; silty and clayey soils as ML, CL, OL, MH, CH, and OH; and highly organic soils as PT. Soils exhibiting engineering properties of two groups can have a dual classification, for example, CL-ML.

The AASHTO system classifies soils according to those properties that affect roadway construction and maintenance. In this system, the fraction of a mineral soil that is less than 3 inches in diameter is classified in one of seven groups from A-1 through A-7 on the basis of particle-size distribution, liquid limit, and plasticity index. Soils in group A-1 are coarse grained and low in content of fines (silt and clay). At the other extreme, soils in group A-7 are fine grained. Highly organic soils are classified in group A-8 on the basis of visual inspection.

If laboratory data are available, the A-1, A-2, and A-7 groups are further classified as A-1-a, A-1-b, A-2-4, A-2-5, A-2-6, A-2-7, A-7-5, or A-7-6. As an additional refinement, the suitability of a soil as subgrade material can be indicated by a group index number. Group index numbers range from 0 for the best subgrade material to 20 or higher for the poorest.

Percentage of rock fragments larger than 10 inches in diameter and 3 to 10 inches in diameter are indicated as a percentage of the total soil on a dry-weight basis. The percentages are estimates determined mainly by converting volume percentage in the field to weight percentage. Three values are provided to identify the expected Low (L), Representative Value (R), and High (H).

Percentage (of soil particles) passing designated sieves is the percentage of the soil fraction less than 3 inches in diameter based on an oven-dry weight. The sieves, numbers 4, 10, 40, and 200 (USA Standard Series), have openings of 4.76, 2.00, 0.420, and 0.074 millimeters, respectively. Estimates are based on laboratory tests of soils sampled in the survey area and in nearby areas and on estimates made in the field. Three values are provided to identify the expected Low (L), Representative Value (R), and High (H).

Liquid limit and *plasticity index* (Atterberg limits) indicate the plasticity characteristics of a soil. The estimates are based on test data from the survey area or from nearby areas and on field examination. Three values are provided to identify the expected Low (L), Representative Value (R), and High (H).

References:

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Report—Engineering Properties

Absence of an entry indicates that the data were not estimated. The asterisk "*" denotes the representative texture; other possible textures follow the dash. The criteria for determining the hydrologic soil group for individual soil components is found in the National Engineering Handbook, Chapter 7 issued May 2007 (<http://directives.sc.egov.usda.gov/OpenNonWebContent.aspx?content=17757.wba>). Three values are provided to identify the expected Low (L), Representative Value (R), and High (H).

| Engineering Properties—Fairfield-Nephi Area, Utah | | | | | | | | | | | | | | |
|---|------------------|------------------|-----------|-----------------|-----------------------------|--------|---------------|-------------|----------------------------------|-----------------|---------------|--------------|--------------|------------------|
| Map unit symbol and soil name | Pct. of map unit | Hydrologic group | Depth | USDA texture | Classification | | Pct Fragments | | Percentage passing sieve number— | | | | Liquid limit | Plasticity index |
| | | | | | Unified | AASHTO | >10 inches | 3-10 inches | 4 | 10 | 40 | 200 | | |
| | | | <i>In</i> | | | | | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H |
| Ce—Cheebe fine sandy loam | | | | | | | | | | | | | | |
| Cheebe | 80 | C | 0-8 | Fine sandy loam | SM, SC- SM, ML, CL-ML | A-4 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 70-78- 85 | 40-48- 55 | 20-23 -25 | NP-3-5 |
| | | | 8-15 | Silty clay | CH | A-7 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 95-98-1 00 | 90-93- 95 | 50-55 -60 | 25-30-3 5 |
| | | | 15-20 | Silty clay | CH | A-7 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 95-98-1 00 | 90-93- 95 | 50-55 -60 | 25-30-3 5 |
| | | | 20-31 | Silty clay | CH | A-7 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 95-98-1 00 | 90-93- 95 | 50-55 -60 | 25-30-3 5 |
| | | | 31-44 | Silty clay | CH | A-7 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 95-98-1 00 | 90-93- 95 | 50-55 -60 | 25-30-3 5 |
| | | | 44-55 | Silty clay loam | CL | A-7 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 95-98-1 00 | 85-90- 95 | 40-45 -50 | 20-23-2 5 |
| | | | 55-65 | Clay | CH | A-7 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 90-95-1 00 | 80-88- 95 | 50-55 -60 | 25-30-3 5 |

| Engineering Properties--Fairfield-Nephi Area, Utah | | | | | | | | | | | | | | |
|--|------------------|------------------|-------|-----------------|----------------|----------|---------------|-------------|-----------------------------------|---------|---------|----------|--------------|------------------|
| Map unit symbol and soil name | Pct. of map unit | Hydrologic group | Depth | USDA texture | Classification | | Pct Fragments | | Percentage passing sieve number-- | | | | Liquid limit | Plasticity index |
| | | | | | Unified | AASHTO | >10 inches | 3-10 inches | 4 | 10 | 40 | 200 | | |
| Cf---Cheebe silty clay loam | | | In | | | | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | |
| Cheebe | 80 | C | 0-2 | Silty clay loam | CL | A-6, A-7 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 85-90-95 | 35-40-45 | 15-20-25 |
| | | | 2-4 | Silty clay loam | CL | A-6, A-7 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 85-90-95 | 35-40-45 | 15-20-25 |
| | | | 4-8 | Silty clay loam | CL | A-6, A-7 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 85-90-95 | 35-40-45 | 15-20-25 |
| | | | 8-15 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 15-20 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 20-31 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 31-44 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 44-55 | Silty clay loam | CL | A-7-6 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 95-98-1 | 85-90-95 | 40-45-50 | 20-23-25 |
| | | | 55-65 | Clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100 | 100-100 | 90-95-1 | 80-88-95 | 50-55-60 | 25-30-35 |



| Engineering Properties---Fairfield-Nephi Area, Utah | | | | | | | | | | | | | | |
|--|------------------|------------------|-------|-----------------|----------------|--------|---------------|-------------|------------------------------------|-----------------|---------------|--------------|--------------|------------------|
| Map unit symbol and soil name | Pct. of map unit | Hydrologic group | Depth | USDA texture | Classification | | Pct Fragments | | Percentage passing sieve number--- | | | | Liquid limit | Plasticity index |
| | | | | | Unified | AASHTO | >10 inches | 3-10 inches | 4 | 10 | 40 | 200 | | |
| GbA---Genolia silt loam, 0 to 1 percent slopes | | | In | | | | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | |
| Genolia | 80 | C | 0-1 | Silt loam | CL-ML | A-4 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 85-93-1 00 | 75-83- 90 | 20-25 -30 | 5-8 -10 |
| | | | 1-6 | Silt loam | CL-ML | A-4 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 85-93-1 00 | 75-83- 90 | 20-25 -30 | 5-8 -10 |
| | | | 6-15 | Silt loam | CL-ML | A-4 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 85-93-1 00 | 75-83- 90 | 20-25 -30 | 5-8 -10 |
| | | | 15-29 | Silt loam | CL-ML | A-4 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 85-93-1 00 | 75-83- 90 | 20-25 -30 | 5-8 -10 |
| | | | 29-42 | Silt loam | CL-ML | A-4 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 85-93-1 00 | 75-83- 90 | 20-25 -30 | 5-8 -10 |
| | | | 42-60 | Silt loam | CL-ML | A-4 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 85-93-1 00 | 75-83- 90 | 20-25 -30 | 5-8 -10 |
| GdDP---Goldrun loamy fine sand, hummocky, 0 to 10 percent slopes | | | | | | | | | | | | | | |
| Goldrun | 85 | A | 0-2 | Loamy fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 75-83- 90 | 15-25- 35 | 10-15 -20 | NP-3 -5 |
| | | | 2-11 | Loamy fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 75-83- 90 | 15-25- 35 | 10-15 -20 | NP-3 -5 |
| | | | 11-26 | Fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 75-83- 90 | 15-25- 35 | 10-15 -20 | NP-3 -5 |
| | | | 26-48 | Fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 75-83- 90 | 10-15- 20 | 10-15 -20 | NP-3 -5 |
| | | | 48-60 | Loamy fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100 -100 | 100-100 -100 | 75-83- 90 | 15-25- 35 | 10-15 -20 | NP-3 -5 |

| Engineering Properties---Fairfield-Nephi Area, Utah | | | | | | | | | | | | | | |
|--|------------------|------------------|-------|-----------------|----------------|----------|---------------|-------------|------------------------------------|-------------|-----------|----------|--------------|------------------|
| Map unit symbol and soil name | Pct. of map unit | Hydrologic group | Depth | USDA texture | Classification | | Pct Fragments | | Percentage passing sieve number--- | | | | Liquid limit | Plasticity index |
| | | | | | Unified | AASHTO | >10 inches | 3-10 inches | 4 | 10 | 40 | 200 | | |
| GeD---Goldrun-Cheebe complex, 0 to 10 percent slopes | | | In | | | | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | L-R-H | |
| Goldrun | 50 | A | 0-2 | Loamy fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 75-83-90 | 15-25-35 | 10-15-20 | NP-3-5 |
| | | | 2-11 | Loamy fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 75-83-90 | 15-25-35 | 10-15-20 | NP-3-5 |
| | | | 11-26 | Fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 75-83-90 | 15-25-35 | 10-15-20 | NP-3-5 |
| | | | 26-48 | Fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 75-83-90 | 10-15-20 | 10-15-20 | NP-3-5 |
| | | | 48-60 | Loamy fine sand | SM | A-2 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 75-83-90 | 15-25-35 | 10-15-20 | NP-3-5 |
| Cheebe | 30 | C | 0-2 | Silty clay loam | CL | A-6, A-7 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 85-90-95 | 35-40-45 | 15-20-25 |
| | | | 2-4 | Silty clay loam | CL | A-6, A-7 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 85-90-95 | 35-40-45 | 15-20-25 |
| | | | 4-8 | Silty clay loam | CL | A-6, A-7 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 85-90-95 | 35-40-45 | 15-20-25 |
| | | | 8-15 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 15-20 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 20-31 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 31-44 | Silty clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 90-93-95 | 50-55-60 | 25-30-35 |
| | | | 44-55 | Silty clay loam | CL | A-7-6 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 95-98-100 | 85-90-95 | 40-45-50 | 20-23-25 |
| | | | 55-65 | Clay | CH | A-7-6 | 0-0-0 | 0-0-0 | 100-100-100 | 100-100-100 | 90-95-100 | 80-88-95 | 50-55-60 | 25-30-35 |

Data Source Information

Soil Survey Area: Fairfield-Nephi Area, Utah
Survey Area Data: Version 9, Sep 23, 2015



0_418.OUT

↑

```

*****
*****
**
**
**          HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE          **
**          HELP MODEL VERSION 3.07 (1 NOVEMBER 1997)              **
**          DEVELOPED BY ENVIRONMENTAL LABORATORY                  **
**          USAE WATERWAYS EXPERIMENT STATION                     **
**          FOR USEPA RISK REDUCTION ENGINEERING LABORATORY       **
**
**
*****
*****

```

```

PRECIPITATION DATA FILE:   C:\HELP3\IRLHELP\DATA4.D4
TEMPERATURE DATA FILE:    C:\HELP3\IRLHELP\DATA7.D7
SOLAR RADIATION DATA FILE: C:\HELP3\IRLHELP\DATA13.D13
EVAPOTRANSPIRATION DATA:  C:\HELP3\IRLHELP\DATA1124.D11
SOIL AND DESIGN DATA FILE: C:\HELP3\IRLHELP\0_418.D10
OUTPUT DATA FILE:         C:\HELP3\IRLHELP\0_418.OUT

```

TIME: 13:15 DATE: 9/28/2016

TITLE: IRL_2016_Redesign

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER

0_418.OUT

MATERIAL TEXTURE NUMBER 14

THICKNESS = 24.00 INCHES
POROSITY = 0.4790 VOL/VOL
FIELD CAPACITY = 0.3710 VOL/VOL
WILTING POINT = 0.2510 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.3399 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.249999994000E-04 CM/SEC

LAYER 2

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 0

THICKNESS = 0.25 INCHES
POROSITY = 0.8500 VOL/VOL
FIELD CAPACITY = 0.0100 VOL/VOL
WILTING POINT = 0.0050 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.0100 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 23.6000004000 CM/SEC
SLOPE = 2.00 PERCENT
DRAINAGE LENGTH = 418.0 FEET

LAYER 3

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

THICKNESS = 0.06 INCHES
POROSITY = 0.0000 VOL/VOL
FIELD CAPACITY = 0.0000 VOL/VOL
WILTING POINT = 0.0000 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.0000 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.199999996000E-12 CM/SEC
FML PINHOLE DENSITY = 1.00 HOLES/ACRE
FML INSTALLATION DEFECTS = 4.00 HOLES/ACRE
FML PLACEMENT QUALITY = 3 - GOOD

LAYER 4

0_418.OUT

TYPE 3 - BARRIER SOIL LINER
MATERIAL TEXTURE NUMBER 17

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 0.25 | INCHES |
| POROSITY | = | 0.7500 | VOL/VOL |
| FIELD CAPACITY | = | 0.7470 | VOL/VOL |
| WILTING POINT | = | 0.4000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0.7500 | VOL/VOL |
| EFFECTIVE SAT. HYD. COND. | = | 0.300000003000E-08 | CM/SEC |

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM A USER-SPECIFIED CURVE NUMBER OF 86.0, A SURFACE SLOPE OF 2.% AND A SLOPE LENGTH OF 418. FEET.

| | | | |
|------------------------------------|---|--------|-------------|
| SCS RUNOFF CURVE NUMBER | = | 85.90 | |
| FRACTION OF AREA ALLOWING RUNOFF | = | 100.0 | PERCENT |
| AREA PROJECTED ON HORIZONTAL PLANE | = | 82.000 | ACRES |
| EVAPORATIVE ZONE DEPTH | = | 24.0 | INCHES |
| INITIAL WATER IN EVAPORATIVE ZONE | = | 8.158 | INCHES |
| UPPER LIMIT OF EVAPORATIVE STORAGE | = | 11.496 | INCHES |
| LOWER LIMIT OF EVAPORATIVE STORAGE | = | 6.024 | INCHES |
| INITIAL SNOW WATER | = | 0.125 | INCHES |
| INITIAL WATER IN LAYER MATERIALS | = | 8.348 | INCHES |
| TOTAL INITIAL WATER | = | 8.473 | INCHES |
| TOTAL SUBSURFACE INFLOW | = | 0.00 | INCHES/YEAR |

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

| | | | |
|---------------------------------------|---|-------|---------|
| STATION LATITUDE | = | 40.76 | DEGREES |
| MAXIMUM LEAF AREA INDEX | = | 0.00 | |
| START OF GROWING SEASON (JULIAN DATE) | = | 117 | |
| END OF GROWING SEASON (JULIAN DATE) | = | 289 | |
| EVAPORATIVE ZONE DEPTH | = | 24.0 | INCHES |
| AVERAGE ANNUAL WIND SPEED | = | 8.80 | MPH |

0_418.OUT

AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67.00 %
AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48.00 %
AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39.00 %
AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 1.07 | 1.05 | 1.15 | 1.20 | 1.31 | 0.78 |
| 0.90 | 0.96 | 1.02 | 1.18 | 1.04 | 1.06 |

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 25.10 | 30.50 | 39.50 | 46.50 | 54.60 | 62.90 |
| 69.80 | 68.60 | 59.50 | 47.50 | 35.30 | 26.80 |

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH
AND STATION LATITUDE = 40.76 DEGREES

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 30

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------------|---------|---------|---------|---------|---------|---------|
| PRECIPITATION | | | | | | |

0_418.OUT

| | | | | | | |
|-----------------|------|------|------|------|------|------|
| ----- | | | | | | |
| TOTALS | 0.92 | 0.95 | 1.33 | 1.11 | 1.11 | 0.83 |
| | 0.84 | 0.89 | 0.96 | 1.09 | 1.12 | 1.13 |
| STD. DEVIATIONS | 0.47 | 0.43 | 0.53 | 0.48 | 0.59 | 0.60 |
| | 0.58 | 0.83 | 0.69 | 0.85 | 0.62 | 0.46 |

RUNOFF

| | | | | | | |
|-----------------|-------|-------|-------|-------|-------|-------|
| ----- | | | | | | |
| TOTALS | 0.115 | 0.279 | 0.240 | 0.001 | 0.001 | 0.003 |
| | 0.049 | 0.029 | 0.004 | 0.030 | 0.009 | 0.086 |
| STD. DEVIATIONS | 0.155 | 0.322 | 0.217 | 0.005 | 0.002 | 0.013 |
| | 0.152 | 0.081 | 0.020 | 0.094 | 0.050 | 0.153 |

EVAPOTRANSPIRATION

| | | | | | | |
|-----------------|-------|-------|-------|-------|-------|-------|
| ----- | | | | | | |
| TOTALS | 0.556 | 0.562 | 1.647 | 1.418 | 1.192 | 0.900 |
| | 0.883 | 0.839 | 0.974 | 0.916 | 0.777 | 0.640 |
| STD. DEVIATIONS | 0.173 | 0.190 | 0.591 | 0.672 | 0.624 | 0.627 |
| | 0.594 | 0.786 | 0.739 | 0.647 | 0.283 | 0.189 |

LATERAL DRAINAGE COLLECTED FROM LAYER 2

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| ----- | | | | | | |
| TOTALS | 0.0000 | 0.0000 | 0.0914 | 0.0031 | 0.0015 | 0.0018 |
| | 0.0005 | 0.0005 | 0.0004 | 0.0003 | 0.0130 | 0.0216 |
| STD. DEVIATIONS | 0.0000 | 0.0001 | 0.2482 | 0.0057 | 0.0042 | 0.0032 |
| | 0.0008 | 0.0009 | 0.0005 | 0.0004 | 0.0688 | 0.1175 |

PERCOLATION/LEAKAGE THROUGH LAYER 4

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| ----- | | | | | | |
| TOTALS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| STD. DEVIATIONS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |

 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 3

| | | | | | | |
|----------|--------|--------|--------|--------|--------|--------|
| ----- | | | | | | |
| AVERAGES | 0.0000 | 0.0000 | 0.0005 | 0.0000 | 0.0000 | 0.0000 |

0_418.OUT

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0001 | 0.0001 |
| STD. DEVIATIONS | 0.0000 | 0.0000 | 0.0013 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0004 | 0.0006 |

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 30

| | INCHES | CU. FEET | PERCENT |
|---|--------------------|------------|---------|
| PRECIPITATION | 12.28 (2.129) | 3655066.5 | 100.00 |
| RUNOFF | 0.845 (0.5193) | 251519.31 | 6.881 |
| EVAPOTRANSPIRATION | 11.305 (1.8950) | 3364966.25 | 92.063 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 2 | 0.13415 (0.30584) | 39931.727 | 1.09250 |
| PERCOLATION/LEAKAGE THROUGH LAYER 4 | 0.00000 (0.00000) | 0.047 | 0.00000 |
| AVERAGE HEAD ON TOP OF LAYER 3 | 0.000 (0.000) | | |
| CHANGE IN WATER STORAGE | -0.005 (1.1961) | -1351.17 | -0.037 |



PEAK DAILY VALUES FOR YEARS 1 THROUGH 30

| | (INCHES) | (CU. FT.) |
|---------------------------------|----------|-------------|
| PRECIPITATION | 1.67 | 497092.187 |
| RUNOFF | 0.716 | 213208.8590 |
| DRAINAGE COLLECTED FROM LAYER 2 | 0.20360 | 60602.12500 |

0_418.OUT

| | | |
|--|----------|-------------|
| PERCOLATION/LEAKAGE THROUGH LAYER 4 | 0.000000 | 0.00466 |
| AVERAGE HEAD ON TOP OF LAYER 3 | 0.032 | |
| MAXIMUM HEAD ON TOP OF LAYER 3 | 0.063 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 2 (DISTANCE FROM DRAIN) | 4.0 FEET | |
| SNOW WATER | 2.36 | 703569.5620 |
| MAXIMUM VEG. SOIL WATER (VOL/VOL) | 0.4414 | |
| MINIMUM VEG. SOIL WATER (VOL/VOL) | 0.2640 | |

*** Maximum heads are computed using McEnroe's equations. ***

Reference: Maximum Saturated Depth over Landfill Liner
by Bruce M. McEnroe, University of Kansas
ASCE Journal of Environmental Engineering
Vol. 119, No. 2, March 1993, pp. 262-270.

↑

FINAL WATER STORAGE AT END OF YEAR 30

| LAYER | (INCHES) | (VOL/VOL) |
|------------|----------|-----------|
| 1 | 8.1190 | 0.3383 |
| 2 | 0.0025 | 0.0100 |
| 3 | 0.0000 | 0.0000 |
| 4 | 0.1875 | 0.7500 |
| SNOW WATER | 0.027 | |

0_418.OUT



```

*****
*****
**
**
**          HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE          **
**          HELP MODEL VERSION 3.07 (1 NOVEMBER 1997)              **
**          DEVELOPED BY ENVIRONMENTAL LABORATORY                   **
**          USAE WATERWAYS EXPERIMENT STATION                       **
**          FOR USEPA RISK REDUCTION ENGINEERING LABORATORY        **
**
**
*****
*****

```

```

PRECIPITATION DATA FILE:   C:\HELP3\IRLHELP\DATA4.D4
TEMPERATURE DATA FILE:    C:\HELP3\IRLHELP\DATA7.D7
SOLAR RADIATION DATA FILE: C:\HELP3\IRLHELP\DATA13.D13
EVAPOTRANSPIRATION DATA:  C:\HELP3\IRLHELP\DATA11.D11
SOIL AND DESIGN DATA FILE: C:\HELP3\IRLHELP\10_418.D10
OUTPUT DATA FILE:         C:\HELP3\IRLHELP\10_418.OUT

```

TIME: 13:26 DATE: 9/28/2016

```
*****
```

TITLE: IRL_2016_Redesign

```
*****
```

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER

10_418.OUT

MATERIAL TEXTURE NUMBER 18

THICKNESS = 120.00 INCHES
POROSITY = 0.6710 VOL/VOL
FIELD CAPACITY = 0.2920 VOL/VOL
WILTING POINT = 0.0770 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.2811 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.100000005000E-02 CM/SEC

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 14

THICKNESS = 24.00 INCHES
POROSITY = 0.4790 VOL/VOL
FIELD CAPACITY = 0.3710 VOL/VOL
WILTING POINT = 0.2510 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.3710 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.249999994000E-04 CM/SEC

LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 0

THICKNESS = 0.25 INCHES
POROSITY = 0.8500 VOL/VOL
FIELD CAPACITY = 0.0100 VOL/VOL
WILTING POINT = 0.0050 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.0100 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 23.6000004000 CM/SEC
SLOPE = 2.00 PERCENT
DRAINAGE LENGTH = 418.0 FEET

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

10_418.OUT

| | | | |
|----------------------------|---|--------------------|------------|
| THICKNESS | = | 0.06 | INCHES |
| POROSITY | = | 0.0000 | VOL/VOL |
| FIELD CAPACITY | = | 0.0000 | VOL/VOL |
| WILTING POINT | = | 0.0000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0.0000 | VOL/VOL |
| EFFECTIVE SAT. HYD. COND. | = | 0.199999996000E-12 | CM/SEC |
| FML PINHOLE DENSITY | = | 1.00 | HOLES/ACRE |
| FML INSTALLATION DEFECTS | = | 4.00 | HOLES/ACRE |
| FML PLACEMENT QUALITY | = | 3 | - GOOD |

LAYER 5

TYPE 3 - BARRIER SOIL LINER
MATERIAL TEXTURE NUMBER 17

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 0.25 | INCHES |
| POROSITY | = | 0.7500 | VOL/VOL |
| FIELD CAPACITY | = | 0.7470 | VOL/VOL |
| WILTING POINT | = | 0.4000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0.7500 | VOL/VOL |
| EFFECTIVE SAT. HYD. COND. | = | 0.300000003000E-08 | CM/SEC |

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT SOIL DATA BASE USING SOIL TEXTURE #18 WITH BARE GROUND CONDITIONS, A SURFACE SLOPE OF 2.% AND A SLOPE LENGTH OF 418. FEET.

| | | | |
|------------------------------------|---|--------|-------------|
| SCS RUNOFF CURVE NUMBER | = | 79.50 | |
| FRACTION OF AREA ALLOWING RUNOFF | = | 100.0 | PERCENT |
| AREA PROJECTED ON HORIZONTAL PLANE | = | 82.000 | ACRES |
| EVAPORATIVE ZONE DEPTH | = | 16.0 | INCHES |
| INITIAL WATER IN EVAPORATIVE ZONE | = | 3.365 | INCHES |
| UPPER LIMIT OF EVAPORATIVE STORAGE | = | 10.736 | INCHES |
| LOWER LIMIT OF EVAPORATIVE STORAGE | = | 1.232 | INCHES |
| INITIAL SNOW WATER | = | 0.125 | INCHES |
| INITIAL WATER IN LAYER MATERIALS | = | 42.827 | INCHES |
| TOTAL INITIAL WATER | = | 42.951 | INCHES |
| TOTAL SUBSURFACE INFLOW | = | 0.00 | INCHES/YEAR |

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40.76 DEGREES
 MAXIMUM LEAF AREA INDEX = 0.00
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16.0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8.80 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67.00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48.00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39.00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 1.07 | 1.05 | 1.15 | 1.20 | 1.31 | 0.78 |
| 0.90 | 0.96 | 1.02 | 1.18 | 1.04 | 1.06 |

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 25.10 | 30.50 | 39.50 | 46.50 | 54.60 | 62.90 |
| 69.80 | 68.60 | 59.50 | 47.50 | 35.30 | 26.80 |

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING

10_418.OUT
 COEFFICIENTS FOR SALT LAKE CITY UTAH
 AND STATION LATITUDE = 40.76 DEGREES

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 30

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---|------------------|------------------|------------------|------------------|------------------|------------------|
| ----- | | | | | | |
| PRECIPITATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.92 0.84 | 0.95 0.89 | 1.33 0.96 | 1.11 1.09 | 1.11 1.12 | 0.83 1.13 |
| STD. DEVIATIONS | 0.47 0.58 | 0.43 0.83 | 0.53 0.69 | 0.48 0.85 | 0.59 0.62 | 0.60 0.46 |
| RUNOFF | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.014 0.000 | 0.045 0.000 | 0.045 0.000 | 0.000 0.001 | 0.000 0.000 | 0.000 0.015 |
| STD. DEVIATIONS | 0.038 0.003 | 0.095 0.000 | 0.054 0.000 | 0.000 0.004 | 0.000 0.000 | 0.000 0.056 |
| EVAPOTRANSPIRATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.556 0.870 | 0.570 0.884 | 1.784 0.939 | 1.499 0.945 | 1.214 0.770 | 0.907 0.647 |
| STD. DEVIATIONS | 0.173 0.615 | 0.198 0.843 | 0.597 0.750 | 0.724 0.671 | 0.643 0.283 | 0.614 0.210 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.0214 0.0097 | 0.0036 0.0030 | 0.0403 0.0019 | 0.2721 0.0041 | 0.1360 0.0153 | 0.0133 0.0505 |
| STD. DEVIATIONS | 0.1014 0.0191 | 0.0136 0.0040 | 0.0888 0.0023 | 0.4075 0.0086 | 0.1350 0.0597 | 0.0257 0.2501 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

10_418.OUT

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| STD. DEVIATIONS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0.0001 | 0.0000 | 0.0002 | 0.0014 | 0.0007 | 0.0001 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0001 | 0.0003 |
| STD. DEVIATIONS | 0.0005 | 0.0001 | 0.0004 | 0.0021 | 0.0007 | 0.0001 |
| | 0.0001 | 0.0000 | 0.0000 | 0.0000 | 0.0003 | 0.0013 |

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 30

| | INCHES | CU. FEET | PERCENT |
|---|--------------------|------------|---------|
| PRECIPITATION | 12.28 (2.129) | 3655066.5 | 100.00 |
| RUNOFF | 0.120 (0.1169) | 35677.98 | 0.976 |
| EVAPOTRANSPIRATION | 11.584 (1.9139) | 3448107.25 | 94.338 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0.57137 (0.71037) | 170074.672 | 4.65312 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0.00000 (0.00000) | 0.153 | 0.00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0.000 (0.000) | | |
| CHANGE IN WATER STORAGE | 0.004 (1.1797) | 1205.93 | 0.033 |



PEAK DAILY VALUES FOR YEARS 1 THROUGH 30

| | (INCHES) | (CU. FT.) |
|--|----------|-------------|
| PRECIPITATION | 1.67 | 497092.187 |
| RUNOFF | 0.303 | 90270.1797 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0.16075 | 47849.55470 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0.000000 | 0.00418 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0.025 | |
| MAXIMUM HEAD ON TOP OF LAYER 4 | 0.049 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN) | 9.4 FEET | |
| SNOW WATER | 2.36 | 703569.5620 |
| MAXIMUM VEG. SOIL WATER (VOL/VOL) | | 0.4024 |
| MINIMUM VEG. SOIL WATER (VOL/VOL) | | 0.0921 |

*** Maximum heads are computed using McEnroe's equations. ***

Reference: Maximum Saturated Depth over Landfill Liner
by Bruce M. McEnroe, University of Kansas
ASCE Journal of Environmental Engineering
Vol. 119, No. 2, March 1993, pp. 262-270.



10_418.OUT

FINAL WATER STORAGE AT END OF YEAR 30

| LAYER | (INCHES) | (VOL/VOL) |
|------------|----------|-----------|
| ---- | ----- | ----- |
| 1 | 33.9517 | 0.2829 |
| 2 | 8.9040 | 0.3710 |
| 3 | 0.0025 | 0.0100 |
| 4 | 0.0000 | 0.0000 |
| 5 | 0.1875 | 0.7500 |
| SNOW WATER | 0.027 | |

50_418.OUT



**
**
** HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE **
** HELP MODEL VERSION 3.07 (1 NOVEMBER 1997) **
** DEVELOPED BY ENVIRONMENTAL LABORATORY **
** USAE WATERWAYS EXPERIMENT STATION **
** FOR USEPA RISK REDUCTION ENGINEERING LABORATORY **
**

PRECIPITATION DATA FILE: C:\HELP3\IRLHELP\DATA4.D4
TEMPERATURE DATA FILE: C:\HELP3\IRLHELP\DATA7.D7
SOLAR RADIATION DATA FILE: C:\HELP3\IRLHELP\DATA13.D13
EVAPOTRANSPIRATION DATA: C:\HELP3\IRLHELP\DATA11.D11
SOIL AND DESIGN DATA FILE: C:\HELP3\IRLHELP\50_418.D10
OUTPUT DATA FILE: C:\HELP3\IRLHELP\50_418.OUT

TIME: 14:43 DATE: 9/28/2016

TITLE: IRL_2016_Redesign

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE
COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER

50_418.OUT

MATERIAL TEXTURE NUMBER 18

THICKNESS = 600.00 INCHES
POROSITY = 0.6710 VOL/VOL
FIELD CAPACITY = 0.2920 VOL/VOL
WILTING POINT = 0.0770 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.2898 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.10000005000E-02 CM/SEC

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 14

THICKNESS = 24.00 INCHES
POROSITY = 0.4790 VOL/VOL
FIELD CAPACITY = 0.3710 VOL/VOL
WILTING POINT = 0.2510 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.3710 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.249999994000E-04 CM/SEC

LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 0

THICKNESS = 0.25 INCHES
POROSITY = 0.8500 VOL/VOL
FIELD CAPACITY = 0.0100 VOL/VOL
WILTING POINT = 0.0050 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.0100 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 23.6000004000 CM/SEC
SLOPE = 2.00 PERCENT
DRAINAGE LENGTH = 418.0 FEET

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

50_418.OUT

| | | | |
|----------------------------|---|--------------------|------------|
| THICKNESS | = | 0.06 | INCHES |
| POROSITY | = | 0.0000 | VOL/VOL |
| FIELD CAPACITY | = | 0.0000 | VOL/VOL |
| WILTING POINT | = | 0.0000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0.0000 | VOL/VOL |
| EFFECTIVE SAT. HYD. COND. | = | 0.199999996000E-12 | CM/SEC |
| FML PINHOLE DENSITY | = | 1.00 | HOLES/ACRE |
| FML INSTALLATION DEFECTS | = | 4.00 | HOLES/ACRE |
| FML PLACEMENT QUALITY | = | 3 | - GOOD |

LAYER 5

TYPE 3 - BARRIER SOIL LINER
MATERIAL TEXTURE NUMBER 17

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 0.25 | INCHES |
| POROSITY | = | 0.7500 | VOL/VOL |
| FIELD CAPACITY | = | 0.7470 | VOL/VOL |
| WILTING POINT | = | 0.4000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0.7500 | VOL/VOL |
| EFFECTIVE SAT. HYD. COND. | = | 0.300000003000E-08 | CM/SEC |

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT SOIL DATA BASE USING SOIL TEXTURE #18 WITH BARE GROUND CONDITIONS, A SURFACE SLOPE OF 2.% AND A SLOPE LENGTH OF 418. FEET.

| | | | |
|------------------------------------|---|---------|-------------|
| SCS RUNOFF CURVE NUMBER | = | 79.50 | |
| FRACTION OF AREA ALLOWING RUNOFF | = | 100.0 | PERCENT |
| AREA PROJECTED ON HORIZONTAL PLANE | = | 82.000 | ACRES |
| EVAPORATIVE ZONE DEPTH | = | 16.0 | INCHES |
| INITIAL WATER IN EVAPORATIVE ZONE | = | 3.365 | INCHES |
| UPPER LIMIT OF EVAPORATIVE STORAGE | = | 10.736 | INCHES |
| LOWER LIMIT OF EVAPORATIVE STORAGE | = | 1.232 | INCHES |
| INITIAL SNOW WATER | = | 0.125 | INCHES |
| INITIAL WATER IN LAYER MATERIALS | = | 182.987 | INCHES |
| TOTAL INITIAL WATER | = | 183.111 | INCHES |
| TOTAL SUBSURFACE INFLOW | = | 0.00 | INCHES/YEAR |

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40.76 DEGREES
 MAXIMUM LEAF AREA INDEX = 0.00
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16.0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8.80 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67.00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48.00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39.00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 1.07 | 1.05 | 1.15 | 1.20 | 1.31 | 0.78 |
| 0.90 | 0.96 | 1.02 | 1.18 | 1.04 | 1.06 |

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 25.10 | 30.50 | 39.50 | 46.50 | 54.60 | 62.90 |
| 69.80 | 68.60 | 59.50 | 47.50 | 35.30 | 26.80 |

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING

50_418.OUT
 COEFFICIENTS FOR SALT LAKE CITY UTAH
 AND STATION LATITUDE = 40.76 DEGREES

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 30

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---|------------------|------------------|------------------|------------------|------------------|------------------|
| ----- | | | | | | |
| PRECIPITATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.92 0.84 | 0.95 0.89 | 1.33 0.96 | 1.11 1.09 | 1.11 1.12 | 0.83 1.13 |
| STD. DEVIATIONS | 0.47 0.58 | 0.43 0.83 | 0.53 0.69 | 0.48 0.85 | 0.59 0.62 | 0.60 0.46 |
| RUNOFF | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.014 0.000 | 0.045 0.000 | 0.045 0.000 | 0.000 0.001 | 0.000 0.000 | 0.000 0.015 |
| STD. DEVIATIONS | 0.038 0.003 | 0.095 0.000 | 0.054 0.000 | 0.000 0.004 | 0.000 0.000 | 0.000 0.056 |
| EVAPOTRANSPIRATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.556 0.870 | 0.570 0.884 | 1.784 0.939 | 1.499 0.945 | 1.214 0.770 | 0.907 0.647 |
| STD. DEVIATIONS | 0.173 0.615 | 0.198 0.843 | 0.597 0.750 | 0.724 0.671 | 0.643 0.283 | 0.614 0.210 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.0228 0.0097 | 0.0040 0.0030 | 0.0206 0.0019 | 0.2846 0.0041 | 0.1430 0.0141 | 0.0135 0.0498 |
| STD. DEVIATIONS | 0.1087 0.0191 | 0.0149 0.0040 | 0.0264 0.0023 | 0.4402 0.0086 | 0.1422 0.0538 | 0.0264 0.2464 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

50_418.OUT

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| STD. DEVIATIONS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0.0001 | 0.0000 | 0.0001 | 0.0015 | 0.0007 | 0.0001 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0001 | 0.0003 |
| STD. DEVIATIONS | 0.0005 | 0.0001 | 0.0001 | 0.0023 | 0.0007 | 0.0001 |
| | 0.0001 | 0.0000 | 0.0000 | 0.0000 | 0.0003 | 0.0012 |

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 30

| | INCHES | CU. FEET | PERCENT |
|---|--------------------|------------|---------|
| PRECIPITATION | 12.28 (2.129) | 3655066.5 | 100.00 |
| RUNOFF | 0.120 (0.1169) | 35677.98 | 0.976 |
| EVAPOTRANSPIRATION | 11.584 (1.9139) | 3448107.25 | 94.338 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0.57137 (0.71065) | 170074.672 | 4.65312 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0.00000 (0.00000) | 0.152 | 0.00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0.000 (0.000) | | |
| CHANGE IN WATER STORAGE | 0.004 (1.1864) | 1205.93 | 0.033 |



| | PEAK DAILY VALUES FOR YEARS 1 THROUGH 30 | |
|--|--|-------------|
| | (INCHES) | (CU. FT.) |
| PRECIPITATION | 1.67 | 497092.187 |
| RUNOFF | 0.303 | 90270.1797 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0.15661 | 46617.22660 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0.000000 | 0.00413 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0.024 | |
| MAXIMUM HEAD ON TOP OF LAYER 4 | 0.048 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN) | 3.8 FEET | |
| SNOW WATER | 2.36 | 703569.5620 |
| MAXIMUM VEG. SOIL WATER (VOL/VOL) | | 0.4024 |
| MINIMUM VEG. SOIL WATER (VOL/VOL) | | 0.0921 |

*** Maximum heads are computed using McEnroe's equations. ***

Reference: Maximum Saturated Depth over Landfill Liner
by Bruce M. McEnroe, University of Kansas
ASCE Journal of Environmental Engineering
Vol. 119, No. 2, March 1993, pp. 262-270.



50_418.OUT

FINAL WATER STORAGE AT END OF YEAR 30

| LAYER | (INCHES) | (VOL/VOL) |
|------------|----------|-----------|
| 1 | 174.1117 | 0.2902 |
| 2 | 8.9040 | 0.3710 |
| 3 | 0.0025 | 0.0100 |
| 4 | 0.0000 | 0.0000 |
| 5 | 0.1875 | 0.7500 |
| SNOW WATER | 0.027 | |



```

*****
*****
**
**
**          HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE          **
**          HELP MODEL VERSION 3.07 (1 NOVEMBER 1997)              **
**          DEVELOPED BY ENVIRONMENTAL LABORATORY                  **
**          USAE WATERWAYS EXPERIMENT STATION                     **
**          FOR USEPA RISK REDUCTION ENGINEERING LABORATORY       **
**
**
*****
*****

```

```

PRECIPITATION DATA FILE:   C:\HELP3\IRLHELP\DATA4.D4
TEMPERATURE DATA FILE:    C:\HELP3\IRLHELP\DATA7.D7
SOLAR RADIATION DATA FILE: C:\HELP3\IRLHELP\DATA13.D13
EVAPOTRANSPIRATION DATA:  C:\HELP3\IRLHELP\DATA11.D11
SOIL AND DESIGN DATA FILE: C:\HELP3\IRLHELP\100_418.D10
OUTPUT DATA FILE:         C:\HELP3\IRLHELP\100_418.OUT

```

TIME: 15:44 DATE: 9/28/2016

TITLE: IRL_2016_Redesign

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER

100_418.OUT

MATERIAL TEXTURE NUMBER 18

THICKNESS = 1200.00 INCHES
POROSITY = 0.6710 VOL/VOL
FIELD CAPACITY = 0.2920 VOL/VOL
WILTING POINT = 0.0770 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.2909 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.100000005000E-02 CM/SEC

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 14

THICKNESS = 24.00 INCHES
POROSITY = 0.4790 VOL/VOL
FIELD CAPACITY = 0.3710 VOL/VOL
WILTING POINT = 0.2510 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.3710 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.249999994000E-04 CM/SEC

LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 0

THICKNESS = 0.25 INCHES
POROSITY = 0.8500 VOL/VOL
FIELD CAPACITY = 0.0100 VOL/VOL
WILTING POINT = 0.0050 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.0100 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 23.60000004000 CM/SEC
SLOPE = 2.00 PERCENT
DRAINAGE LENGTH = 418.0 FEET

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

100_418.OUT

| | | | |
|----------------------------|---|--------------------|------------|
| THICKNESS | = | 0.06 | INCHES |
| POROSITY | = | 0.0000 | VOL/VOL |
| FIELD CAPACITY | = | 0.0000 | VOL/VOL |
| WILTING POINT | = | 0.0000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0.0000 | VOL/VOL |
| EFFECTIVE SAT. HYD. COND. | = | 0.199999996000E-12 | CM/SEC |
| FML PINHOLE DENSITY | = | 1.00 | HOLES/ACRE |
| FML INSTALLATION DEFECTS | = | 4.00 | HOLES/ACRE |
| FML PLACEMENT QUALITY | = | 3 | - GOOD |

LAYER 5

TYPE 3 - BARRIER SOIL LINER
MATERIAL TEXTURE NUMBER 17

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 0.25 | INCHES |
| POROSITY | = | 0.7500 | VOL/VOL |
| FIELD CAPACITY | = | 0.7470 | VOL/VOL |
| WILTING POINT | = | 0.4000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0.7500 | VOL/VOL |
| EFFECTIVE SAT. HYD. COND. | = | 0.300000003000E-08 | CM/SEC |

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT SOIL DATA BASE USING SOIL TEXTURE #18 WITH BARE GROUND CONDITIONS, A SURFACE SLOPE OF 2.% AND A SLOPE LENGTH OF 418. FEET.

| | | | |
|------------------------------------|---|---------|-------------|
| SCS RUNOFF CURVE NUMBER | = | 79.50 | |
| FRACTION OF AREA ALLOWING RUNOFF | = | 100.0 | PERCENT |
| AREA PROJECTED ON HORIZONTAL PLANE | = | 82.000 | ACRES |
| EVAPORATIVE ZONE DEPTH | = | 16.0 | INCHES |
| INITIAL WATER IN EVAPORATIVE ZONE | = | 3.365 | INCHES |
| UPPER LIMIT OF EVAPORATIVE STORAGE | = | 10.736 | INCHES |
| LOWER LIMIT OF EVAPORATIVE STORAGE | = | 1.232 | INCHES |
| INITIAL SNOW WATER | = | 0.125 | INCHES |
| INITIAL WATER IN LAYER MATERIALS | = | 358.187 | INCHES |
| TOTAL INITIAL WATER | = | 358.311 | INCHES |
| TOTAL SUBSURFACE INFLOW | = | 0.00 | INCHES/YEAR |

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40.76 DEGREES
 MAXIMUM LEAF AREA INDEX = 0.00
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16.0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8.80 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67.00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48.00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39.00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 1.07 | 1.05 | 1.15 | 1.20 | 1.31 | 0.78 |
| 0.90 | 0.96 | 1.02 | 1.18 | 1.04 | 1.06 |

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 25.10 | 30.50 | 39.50 | 46.50 | 54.60 | 62.90 |
| 69.80 | 68.60 | 59.50 | 47.50 | 35.30 | 26.80 |

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING

100_418.OUT
 COEFFICIENTS FOR SALT LAKE CITY UTAH
 AND STATION LATITUDE = 40.76 DEGREES

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 30

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---|------------------|------------------|------------------|------------------|------------------|------------------|
| ----- | | | | | | |
| PRECIPITATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.92 0.84 | 0.95 0.89 | 1.33 0.96 | 1.11 1.09 | 1.11 1.12 | 0.83 1.13 |
| STD. DEVIATIONS | 0.47 0.58 | 0.43 0.83 | 0.53 0.69 | 0.48 0.85 | 0.59 0.62 | 0.60 0.46 |
| RUNOFF | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.014 0.000 | 0.045 0.000 | 0.045 0.000 | 0.000 0.001 | 0.000 0.000 | 0.000 0.015 |
| STD. DEVIATIONS | 0.038 0.003 | 0.095 0.000 | 0.054 0.000 | 0.000 0.004 | 0.000 0.000 | 0.000 0.056 |
| EVAPOTRANSPIRATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.556 0.870 | 0.570 0.884 | 1.784 0.939 | 1.499 0.945 | 1.214 0.770 | 0.907 0.647 |
| STD. DEVIATIONS | 0.173 0.615 | 0.198 0.843 | 0.597 0.750 | 0.724 0.671 | 0.643 0.283 | 0.614 0.210 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.0229 0.0097 | 0.0041 0.0030 | 0.0196 0.0019 | 0.2849 0.0041 | 0.1438 0.0140 | 0.0136 0.0497 |
| STD. DEVIATIONS | 0.1094 0.0191 | 0.0151 0.0040 | 0.0254 0.0023 | 0.4410 0.0086 | 0.1431 0.0533 | 0.0264 0.2460 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

100_418.OUT

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| STD. DEVIATIONS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0.0001 | 0.0000 | 0.0001 | 0.0015 | 0.0007 | 0.0001 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0001 | 0.0003 |
| STD. DEVIATIONS | 0.0006 | 0.0001 | 0.0001 | 0.0023 | 0.0007 | 0.0001 |
| | 0.0001 | 0.0000 | 0.0000 | 0.0000 | 0.0003 | 0.0012 |

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 30

| | INCHES | CU. FEET | PERCENT |
|---|--------------------|------------|---------|
| PRECIPITATION | 12.28 (2.129) | 3655066.5 | 100.00 |
| RUNOFF | 0.120 (0.1169) | 35677.98 | 0.976 |
| EVAPOTRANSPIRATION | 11.584 (1.9139) | 3448107.25 | 94.338 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0.57137 (0.71069) | 170074.672 | 4.65312 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0.00000 (0.00000) | 0.152 | 0.00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0.000 (0.000) | | |
| CHANGE IN WATER STORAGE | 0.004 (1.1870) | 1205.78 | 0.033 |



| | PEAK DAILY VALUES FOR YEARS | 1 THROUGH | 30 |
|-----------------------------------|-----------------------------|-----------|-------------|
| | | (INCHES) | (CU. FT.) |
| PRECIPITATION | | 1.67 | 497092.187 |
| RUNOFF | | 0.303 | 90270.1797 |
| DRAINAGE COLLECTED FROM LAYER | 3 | 0.15956 | 47495.00390 |
| PERCOLATION/LEAKAGE THROUGH LAYER | 5 | 0.000000 | 0.00417 |
| AVERAGE HEAD ON TOP OF LAYER | 4 | 0.025 | |
| MAXIMUM HEAD ON TOP OF LAYER | 4 | 0.051 | |
| LOCATION OF MAXIMUM HEAD IN LAYER | 3 | | |
| (DISTANCE FROM DRAIN) | | 0.0 FEET | |
| SNOW WATER | | 2.36 | 703569.5620 |
| MAXIMUM VEG. SOIL WATER (VOL/VOL) | | | 0.4024 |
| MINIMUM VEG. SOIL WATER (VOL/VOL) | | | 0.0921 |

*** Maximum heads are computed using McEnroe's equations. ***

Reference: Maximum Saturated Depth over Landfill Liner
 by Bruce M. McEnroe, University of Kansas
 ASCE Journal of Environmental Engineering
 Vol. 119, No. 2, March 1993, pp. 262-270.



FINAL WATER STORAGE AT END OF YEAR 30

| LAYER | (INCHES) | (VOL/VOL) |
|------------|----------|-----------|
| ---- | ----- | ----- |
| 1 | 349.3116 | 0.2911 |
| 2 | 8.9040 | 0.3710 |
| 3 | 0.0025 | 0.0100 |
| 4 | 0.0000 | 0.0000 |
| 5 | 0.1875 | 0.7500 |
| SNOW WATER | 0.027 | |



```

*****
*****
**
**
**          HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE          **
**          HELP MODEL VERSION 3.07 (1 NOVEMBER 1997)              **
**          DEVELOPED BY ENVIRONMENTAL LABORATORY                   **
**          USAE WATERWAYS EXPERIMENT STATION                      **
**          FOR USEPA RISK REDUCTION ENGINEERING LABORATORY        **
**
**
*****
*****

```

```

PRECIPITATION DATA FILE:   C:\HELP3\IRLHELP\DATA4.D4
TEMPERATURE DATA FILE:    C:\HELP3\IRLHELP\DATA7.D7
SOLAR RADIATION DATA FILE: C:\HELP3\IRLHELP\DATA13.D13
EVAPOTRANSPIRATION DATA:  C:\HELP3\IRLHELP\DATA11.D11
SOIL AND DESIGN DATA FILE: C:\HELP3\IRLHELP\121_418.D10
OUTPUT DATA FILE:         C:\HELP3\IRLHELP\121_418.OUT

```

TIME: 16:21 DATE: 9/28/2016

TITLE: IRL_2016_Redesign

NOTE: INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE COMPUTED AS NEARLY STEADY-STATE VALUES BY THE PROGRAM.

LAYER 1

TYPE 1 - VERTICAL PERCOLATION LAYER

121_418.OUT

MATERIAL TEXTURE NUMBER 18

THICKNESS = 1452.00 INCHES
POROSITY = 0.6710 VOL/VOL
FIELD CAPACITY = 0.2920 VOL/VOL
WILTING POINT = 0.0770 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.2911 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.10000005000E-02 CM/SEC

LAYER 2

TYPE 1 - VERTICAL PERCOLATION LAYER

MATERIAL TEXTURE NUMBER 14

THICKNESS = 24.00 INCHES
POROSITY = 0.4790 VOL/VOL
FIELD CAPACITY = 0.3710 VOL/VOL
WILTING POINT = 0.2510 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.3710 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 0.249999994000E-04 CM/SEC

LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 0

THICKNESS = 0.25 INCHES
POROSITY = 0.8500 VOL/VOL
FIELD CAPACITY = 0.0100 VOL/VOL
WILTING POINT = 0.0050 VOL/VOL
INITIAL SOIL WATER CONTENT = 0.0100 VOL/VOL
EFFECTIVE SAT. HYD. COND. = 23.6000004000 CM/SEC
SLOPE = 2.00 PERCENT
DRAINAGE LENGTH = 418.0 FEET

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

121_418.OUT

THICKNESS = 0.06 INCHES
 POROSITY = 0.0000 VOL/VOL
 FIELD CAPACITY = 0.0000 VOL/VOL
 WILTING POINT = 0.0000 VOL/VOL
 INITIAL SOIL WATER CONTENT = 0.0000 VOL/VOL
 EFFECTIVE SAT. HYD. COND. = 0.199999996000E-12 CM/SEC
 FML PINHOLE DENSITY = 1.00 HOLES/ACRE
 FML INSTALLATION DEFECTS = 4.00 HOLES/ACRE
 FML PLACEMENT QUALITY = 3 - GOOD

LAYER 5

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 17

THICKNESS = 0.25 INCHES
 POROSITY = 0.7500 VOL/VOL
 FIELD CAPACITY = 0.7470 VOL/VOL
 WILTING POINT = 0.4000 VOL/VOL
 INITIAL SOIL WATER CONTENT = 0.7500 VOL/VOL
 EFFECTIVE SAT. HYD. COND. = 0.300000003000E-08 CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE: SCS RUNOFF CURVE NUMBER WAS COMPUTED FROM DEFAULT SOIL DATA BASE USING SOIL TEXTURE #18 WITH BARE GROUND CONDITIONS, A SURFACE SLOPE OF 2.% AND A SLOPE LENGTH OF 418. FEET.

SCS RUNOFF CURVE NUMBER = 79.50
 FRACTION OF AREA ALLOWING RUNOFF = 100.0 PERCENT
 AREA PROJECTED ON HORIZONTAL PLANE = 82.000 ACRES
 EVAPORATIVE ZONE DEPTH = 16.0 INCHES
 INITIAL WATER IN EVAPORATIVE ZONE = 3.365 INCHES
 UPPER LIMIT OF EVAPORATIVE STORAGE = 10.736 INCHES
 LOWER LIMIT OF EVAPORATIVE STORAGE = 1.232 INCHES
 INITIAL SNOW WATER = 0.125 INCHES
 INITIAL WATER IN LAYER MATERIALS = 431.771 INCHES
 TOTAL INITIAL WATER = 431.895 INCHES
 TOTAL SUBSURFACE INFLOW = 0.00 INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE: EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40.76 DEGREES
 MAXIMUM LEAF AREA INDEX = 0.00
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16.0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8.80 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67.00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48.00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39.00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65.00 %

NOTE: PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 1.07 | 1.05 | 1.15 | 1.20 | 1.31 | 0.78 |
| 0.90 | 0.96 | 1.02 | 1.18 | 1.04 | 1.06 |

NOTE: TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| 25.10 | 30.50 | 39.50 | 46.50 | 54.60 | 62.90 |
| 69.80 | 68.60 | 59.50 | 47.50 | 35.30 | 26.80 |

NOTE: SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING

121_418.OUT
 COEFFICIENTS FOR SALT LAKE CITY UTAH
 AND STATION LATITUDE = 40.76 DEGREES

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 30

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---|------------------|------------------|------------------|------------------|------------------|------------------|
| ----- | | | | | | |
| PRECIPITATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.92 0.84 | 0.95 0.89 | 1.33 0.96 | 1.11 1.09 | 1.11 1.12 | 0.83 1.13 |
| STD. DEVIATIONS | 0.47 0.58 | 0.43 0.83 | 0.53 0.69 | 0.48 0.85 | 0.59 0.62 | 0.60 0.46 |
| RUNOFF | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.014 0.000 | 0.045 0.000 | 0.045 0.000 | 0.000 0.001 | 0.000 0.000 | 0.000 0.015 |
| STD. DEVIATIONS | 0.038 0.003 | 0.095 0.000 | 0.054 0.000 | 0.000 0.004 | 0.000 0.000 | 0.000 0.056 |
| EVAPOTRANSPIRATION | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.556 0.870 | 0.570 0.884 | 1.784 0.939 | 1.499 0.945 | 1.214 0.770 | 0.907 0.647 |
| STD. DEVIATIONS | 0.173 0.615 | 0.198 0.843 | 0.597 0.750 | 0.724 0.671 | 0.643 0.283 | 0.614 0.210 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | | | | | | |
| ----- | | | | | | |
| TOTALS | 0.0229 0.0097 | 0.0041 0.0030 | 0.0194 0.0019 | 0.2849 0.0041 | 0.1440 0.0140 | 0.0136 0.0497 |
| STD. DEVIATIONS | 0.1095 0.0191 | 0.0151 0.0040 | 0.0253 0.0023 | 0.4411 0.0086 | 0.1432 0.0533 | 0.0265 0.2459 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

121_418.OUT

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| STD. DEVIATIONS | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|-----------------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0.0001 | 0.0000 | 0.0001 | 0.0015 | 0.0007 | 0.0001 |
| | 0.0000 | 0.0000 | 0.0000 | 0.0000 | 0.0001 | 0.0003 |
| STD. DEVIATIONS | 0.0006 | 0.0001 | 0.0001 | 0.0023 | 0.0007 | 0.0001 |
| | 0.0001 | 0.0000 | 0.0000 | 0.0000 | 0.0003 | 0.0012 |

AVERAGE ANNUAL TOTALS & (STD. DEVIATIONS) FOR YEARS 1 THROUGH 30

| | INCHES | CU. FEET | PERCENT |
|---|--------------------|------------|---------|
| PRECIPITATION | 12.28 (2.129) | 3655066.5 | 100.00 |
| RUNOFF | 0.120 (0.1169) | 35677.98 | 0.976 |
| EVAPOTRANSPIRATION | 11.584 (1.9139) | 3448107.25 | 94.338 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0.57137 (0.71070) | 170074.672 | 4.65312 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0.00000 (0.00000) | 0.152 | 0.00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0.000 (0.000) | | |
| CHANGE IN WATER STORAGE | 0.004 (1.1871) | 1205.78 | 0.033 |



| | PEAK DAILY VALUES FOR YEARS | 1 THROUGH | 30 |
|--|-----------------------------|-----------|-------------|
| | | (INCHES) | (CU. FT.) |
| PRECIPITATION | | 1.67 | 497092.187 |
| RUNOFF | | 0.303 | 90270.1797 |
| DRAINAGE COLLECTED FROM LAYER 3 | | 0.15763 | 46919.11720 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | | 0.000000 | 0.00414 |
| AVERAGE HEAD ON TOP OF LAYER 4 | | 0.025 | |
| MAXIMUM HEAD ON TOP OF LAYER 4 | | 0.048 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN) | | 7.1 FEET | |
| SNOW WATER | | 2.36 | 703569.5620 |
| MAXIMUM VEG. SOIL WATER (VOL/VOL) | | | 0.4024 |
| MINIMUM VEG. SOIL WATER (VOL/VOL) | | | 0.0921 |

*** Maximum heads are computed using McEnroe's equations. ***

Reference: Maximum Saturated Depth over Landfill Liner
by Bruce M. McEnroe, University of Kansas
ASCE Journal of Environmental Engineering
Vol. 119, No. 2, March 1993, pp. 262-270.



FINAL WATER STORAGE AT END OF YEAR 30

| LAYER | (INCHES) | (VOL/VOL) |
|------------|----------|-----------|
| 1 | 422.8956 | 0.2913 |
| 2 | 8.9040 | 0.3710 |
| 3 | 0.0025 | 0.0100 |
| 4 | 0.0000 | 0.0000 |
| 5 | 0.1875 | 0.7500 |
| SNOW WATER | 0.027 | |

1. Determine the required geocomposite transmissivity to provide sufficient capacity to conduct the leachate to the leachate collection pipes.

- a. Bearing pressure over the geocomposite.

The Normal Bearing Pressure (P'):

| | |
|-----------------------------------|-----------------------------|
| 126' Depth above Liner | |
| Soil Cover (2 ft @ 120 pcf) | = 240 psf |
| Closure Material (3 ft @ 120 pcf) | = 360 psf |
| Waste (121 ft @ 60 pcf) | = <u>7,260 psf</u> |
| | = 7,860 psf (use 7,900 psf) |
| N TOTAL | = 54.9 psi |

- b. Required geocomposite capacity

The geocomposite will be required to conduct the greatest amount of water at the low side of the planar slopes just prior to discharging leachate into the leachate collection pipes. The boundary conditions for the composite (from top to bottom) are:

- Closure and Waste Loading (as calculated above)
- 2' protective soil cover comprised of a silty clay soil
- Geocomposite
- 60-mil HDPE geomembrane liner

The geocomposite capacity is dependent on the length of the flow path of the leachate before it enters into the pipe drainage system. The maximum length of the flow path was determined based on a reasonable transmissivity of available geocomposite products. The maximum flow path allowable was calculated to be about 612 feet and the placement of leachate drainage pipe system was designed accordingly for each cell.

Due to the differences between Cells 1, 2 and 3 separate calculations for the geocomposite capacity are included.

The longest one-foot wide flow path along the resultant slope of the wider planar surfaces within the geocomposite for Cells 1, 2 and 3 is approximately 426 ft, 418 ft, and 460 ft respectively.

The HELP Model was used to predict leachate rates from the geocomposite. Several runs were computed at varying waste heights above the geomembrane to determine a governing peak rate. The predicted peak daily leachate rate conveyed through the geocomposite was predicted to be about 0.161 in/day for all of the cells.

The resulting peak daily flow from the longest flow path in each of the cells is:

Cell 1

$$q_{\text{leachate}} = (426 \text{ ft})(0.161 \text{ in/day})(1 \text{ ft/ 12 in})$$
$$q_{\text{leachate}} = 5.72 \text{ ft}^3/\text{ft-day}$$

Cells 2

$$q_{\text{leachate}} = (418 \text{ ft})(0.161 \text{ in/day})(1 \text{ ft/ 12 in})$$
$$q_{\text{leachate}} = 5.61 \text{ ft}^3/\text{ft-day}$$

Cell 3

$$q_{\text{leachate}} = (460 \text{ ft})(0.161 \text{ in/day})(1 \text{ ft/ 12 in})$$
$$q_{\text{leachate}} = 6.17 \text{ ft}^3/\text{ft-day}$$

The minimum slope for the planar surfaces for the geocomposite is 2.0% for all cells. A steeper slope will provide a more conservative design.

The required transmissivity for the geocomposite is given by $q_{\text{req'd}}$ and is related to the leachate rate q_{leachate} by applying necessary safety factors. The combination of all the necessary safety factors is a resulting safety factor (SF_{RES}). Therefore,

$$q_{\text{req'd}} = q_{\text{leachate}} \times SF_{\text{RES}}$$

“Designing with Geosynthetics” by Robert Koerner provides recommended safety factors in the design of geonets as follows:

SF_{IN} = Safety factor for intrusion of adjacent geosynthetic materials into the geonet (1.5)

SF_{CR} = Safety factor for creep deformation of the geonet (1.5)

SF_{BC} = Safety factor for biological (2.0)

SF_{cc} = Safety factor for chemical clogging (1.5)

Because geocomposite testing includes the intrusion of the adjacent geosynthetic materials SF_{IN} is not required.

Combining all of the remaining safety factors presented yields a resulting safety factor of:

$$SF_{\text{RES}} = 1.5 \times 2.0 \times 1.5 = 4.5$$

Using the information presented above, the required geocomposite transmissivity (Θ_{req}) in m^2/sec for each of the cells is:

Cell 1

$$(5.72)(4.5) = (\Theta_{\text{req}} \text{ m}^2/\text{sec})(10.7639 \text{ ft}^2/\text{m}^2)(86400 \text{ sec/day})(0.02)$$

$$\Theta_{\text{req}} = 1.38 \times 10^{-3} \text{ m}^2/\text{sec}$$

Cell 2

$$(5.61)(4.5) = (\Theta_{\text{req}} \text{ m}^2/\text{sec})(10.7639 \text{ ft}^2/\text{m}^2)(86400 \text{ sec/day})(0.02)$$

$$\Theta_{\text{req}} = 1.36 \times 10^{-3} \text{ m}^2/\text{sec}$$

Cell 3

$$(6.17)(4.5) = (\Theta_{\text{req}} \text{ m}^2/\text{sec})(10.7639 \text{ ft}^2/\text{m}^2)(86400 \text{ sec/day})(0.02)$$

$$\Theta_{\text{req}} = 1.49 \times 10^{-3} \text{ m}^2/\text{sec}$$

The geocomposite shall be selected to provide the required hydraulic transmissivity at the loading and boundary conditions provided.

2. Determine the required diameters for the leachate collection pipe system.

a. Max pipe capacity:

Assume 6-inch, 8-inch, and 10-inch diameter corrugated polyethylene pipe on a 1.01% slope after projected potential differential settlement. It was assumed for the purposes of this design that flow at 80% depth represents pipe capacity.

Manning's n = 0.016 ("ADS Specifier Manual - Civil Engineer", Advanced Drainage Systems, Inc.)

$$Q = \frac{1.49}{n} AR^{2/3} S^{1/2}$$

Pipe Capacity (80% flow depth assumed as full capacity)

| Pipe Diameter (in.) | Pipe Area (ft ²) | Hydraulic Radius (ft) | Flow Capacity | |
|------------------------|---------------------------------|--------------------------|---------------|-------|
| | | | (cfs) | (gpm) |
| 6 | 0.17 | 0.15 | 0.45 | 201 |
| 8 | 0.30 | 0.20 | 0.96 | 433 |
| 10 | 0.47 | 0.25 | 1.75 | 785 |

b. Pipe Sizing:

Figure 1 shows the pipe number for each of the Leachate pipes designed for the system. Predicted flows (Q) within the leachate collection pipes were calculated based on HELP model predicted peak daily leachate rates, 0.161 in/day on the cell floor and 0.124 in/day on slopes (4H:1V), applied over the contributing areas to each pipe. The leachate collection pipe system including pipe numbers are identified in Figure 1. The resultant pipe diameter requirements for each cell are shown in tables below:

Cell 1 Pipe Diameter Requirements

| Pipe | Contributing Areas Floor | Contributing Areas Slope | Contributing Q from Upstream Piping (cfs) | Q | | Pipe Diameter (in.) |
|------|--------------------------|--------------------------|--|-------|-------|------------------------|
| | (ft ²) | (ft ²) | | (cfs) | (gpm) | |
| 1 | 232,023 | 41,002 | - | 0.04 | 18 | 6 |
| 2 | 317,526 | 74,465 | - | 0.06 | 26 | 6 |
| 3 | 169,310 | 40,043 | - | 0.03 | 14 | 6 |
| 4 | 249,951 | 69,86 | - | 0.04 | 18 | 6 |
| 5 | 5,845 | 0 | 0.04 | 0.04 | 18 | 6 |
| 6 | 18,637 | 1,025 | 0.17 | 0.17 | 78 | 8* |
| 7 | 643,567 | 3,074 | - | 0.10 | 45 | 6 |
| 8 | 32,382 | 14,442 | 0.27 | 0.28 | 126 | 8* |
| 9 | 1,082,673 | 28,728 | - | 0.17 | 77 | 6 |
| 10 | 72,763 | 28,702 | - | 0.01 | 7 | 6 |
| 11 | 0 | 111,103 | 0.01 | 0.03 | 13 | 6 |

*8 in pipes are used where the modified design of the landfill extended previously installed 8 in pipes from the original design.

Cell 2 Pipe Diameter Requirements

| Pipe | Contributing Areas Floor | Contributing Areas Slope | Contributing Q from Upstream Piping (cfs) | Q | | Pipe Diameter (in.) |
|------|--------------------------|--------------------------|--|-------|-------|------------------------|
| | (ft ²) | (ft ²) | | (cfs) | (gpm) | |
| 1 | 793,909 | 5,192 | - | 0.12 | 55 | 6 |
| 2 | 77,669 | 70,363 | 0.12 | 0.14 | 64 | 6 |
| 3 | 722,346 | 34,034 | - | 0.12 | 52 | 6 |
| 4 | 67,725 | 79,972 | 0.12 | 0.14 | 61 | 6 |
| 5 | 1,555,074 | 28,366 | - | 0.24 | 109 | 6 |

Cell 3 Pipe Diameter Requirements

| Pipe | Contributing Areas Floor | Contributing Areas Slope | Contributing Q from Upstream Piping (cfs) | Q | | Pipe Diameter (in.) |
|------|--------------------------|--------------------------|--|-------|-------|------------------------|
| | (ft ²) | (ft ²) | | (cfs) | (gpm) | |
| 1 | 840,013 | 84,870 | - | 0.14 | 63 | 6 |
| 2 | 81,983 | 97,094 | 0.14 | 0.16 | 74 | 6 |
| 3 | 789973 | 5,362 | - | 0.12 | 55 | 6 |
| 4 | 81857 | 73,979 | 0.12 | 0.14 | 65 | 6 |
| 5 | 1,560,073 | 29,801 | - | 0.24 | 110 | 6 |

3. Determine the required storage capacity for sump design
- a. The Help model predicts an annual average of lateral drainage collected from the geocomposite to be 0.57 in/year.
 - b. The storage volume (V) required within each cell was based on three assumptions:
 - i. The conservative assumption that an entire cell is left open (no final closure applied).
 - ii. A collection time of 1 week
 - iii. A pore space of 0.32% within the gravel being used to fill the leachate pond.

And is calculated for each cell below:

Cell 1

$$\text{Area} = 3,183,564 \text{ ft}^2$$

$$V = (3,183,564 \text{ ft}^2)(0.57 \text{ in/yr})(1 \text{ yr}/52 \text{ weeks})(1 \text{ ft}/12 \text{ in})/(0.32) = 9,088 \text{ ft}^3$$

Cell 2

$$\text{Area} = 3,434,604 \text{ ft}^2$$

$$V = (3,434,604 \text{ ft}^2)(0.57 \text{ in/yr})(1 \text{ yr}/52 \text{ weeks})(1 \text{ ft}/12 \text{ in})/(0.32) = 9,804 \text{ ft}^3$$

Cell 3


$$\text{Area} = 3,642,949 \text{ ft}^2$$

$$V = (3,642,949 \text{ ft}^2)(0.57 \text{ in/yr})(1 \text{ yr}/52 \text{ weeks})(1 \text{ ft}/12 \text{ in})/(0.32) = 10,399 \text{ ft}^3$$

- c. The sumps were designed to fully contain the leachate volume described above at a depth of about 2.5 ft at the deepest point. The design also accommodates between 0.4 and 0.5 ft of freeboard.

LEACHATE PIPE DESIGNATION

N





CLIENT: Intermountain Regional Landfill
PROJECT: LF Redesign
FEATURE: Buried Pipe Design
PROJECT NO.: 373.02.100

SHEET 1 OF 5
COMPUTED: RJG
CHECKED: GLJ
DATE: Oct. 2016

- I. Evaluate the long-term strength of the Polyethylene pipe against failure or significant loss of cross-sectional area.

Reference Manuals: "Plastics Pipe Institute Handbook of Polyethylene Pipe", by Plastics Pipe Institute.

Design Criteria:

Pipe Diameter = 8 inches
Maximum Design Height of Overburden = 126 feet (See attached drawing)
This is the height of the closure material above the inlet of the pipe.

Note: This project uses both 6-inch and 8-inch pipes. Calculations are provided for 8-inch pipe because it will fail at a lower stress than 6-inch pipe.

Unit weight of overburden (126 ft of total height):

| | | |
|-----------------------------------|---|------------------|
| Soil cover (2 ft @ 120 pcf) | = | 240 lbs |
| Closure Material (3 ft @ 120 pcf) | = | 360 lbs |
| Waste (126-2-3=121 ft @ 60 pcf) | = | <u>7,260 lbs</u> |
| Total | = | <u>7,860 lbs</u> |

A. Soil Pressure by components

$$P_T = P_S + P_L$$

where: P_T = Total load pressure
 P_S = Static or dead load pressure
 P_L = Live load pressure

From above, $P_s = 7,860 \text{ psf} = 54.6 \text{ psi}$

Using Boussinesq's Equation from the manual reference above, the live load pressure can be estimated as follows:

$$P_L = \frac{3W_L H^3}{2\pi R^5}$$

W_L = wheel load (lb)
 H = vertical depth of crown
 R = distance from the point load application to the crown

However, the tire load becomes insignificant with the 126 feet of total overburden and the static load governs the design.

B. Evaluate Wall Crushing

The compressive thrust on the pipe walls is given below:

$$S = \frac{P_{RD}D_O}{288A}$$

- S = Compressive stress (psi)
A = Wall thickness = 0.639 in
D_O = Outside diameter of pipe (in)
P_{RD} = Radial directed earth pressure (psf)

$$P_{RD} = (VAF)wH$$

Where

- w = Unit weight of soil, pcf = 62.4 pcf (average)
H = Depth of cover = 126 ft
VAF = Vertical Arching Factor

$$VAF = 0.88 - \frac{0.71(S_A - 1)}{S_A + 2.5}$$

With

$$S_A = \frac{1.43M_s r_{CENT}}{EA}$$

Where

- M_s = One-dimensional modulus of soil = 1000 psi (pg 228 of manual)
r_{CENT} = radius to centroidal axis of pipe = 7.590 in
E = Apparent modulus of elasticity of pipe material = 28,000 psi

Then

$$S_A = \frac{(1.43)(1000\text{psi})(7.950\text{in})}{(28000\text{psi})(0.639\text{in})} = 0.63540$$

$$VAF = 0.88 - \frac{0.71(0.6354 - 1)}{(0.6354 + 2.5)} = 0.9626$$

$$PRD = (0.9626)(62.4\text{pcf})(126\text{ft}) = 7568\text{ psf}$$

And

$$S = \frac{(7568psf)(8.548in)}{(288)(0.639in)} = 351.5 \text{ psi}$$

The maximum long-term compressive design stress value for PE 3408 pipe is 1000 psi (page 102 of engineering manual). Thus, this pipe meets the design criterion for wall crushing.

C. Evaluate Wall Buckling

Wall buckling resistance of pipe is increased when it is buried. The soil and pipe work together to resist buckling. The PPI Handbook recommends using the Moore-Selig Equation to calculate critical buckling pressure of deep buried pipes (more than 50 ft below the soil surface).

$$P_{CR} = \frac{(1.32)}{D_M} (EI)^{\frac{1}{3}} (E_S^*)^{\frac{2}{3}}$$

| | | |
|----------|---|--|
| P_{CR} | = | Critical buckling stress (psi) |
| D_M | = | Mean Pipe Diameter = 7.909 in |
| E | = | Pipe modulus of elasticity = 28,000 psi for 50 years at 73°F (Table B.1.1 Page 99 of engineering manual) |
| I | = | Pipe wall moment of Inertia = $\frac{t^3}{12}$ |
| t | = | Pipe wall thickness = 0.639 in (PE 3408 pipe, 130 psi) |
| E_S^* | = | $\frac{E_S}{1-\mu}$ |
| E_S | = | Secant modulus of soil, psi |
| μ | = | Poisson's Ratio of Soil |

Taking $E_S = 2083$ psi and $\mu = 0.40$ (*Foundation Design*, D.P. Coduto, 1994),

$$E_S^* = \frac{2083}{1-0.40} = 3,472 \text{ psi}$$

$$I = \frac{t^3}{12} = \frac{0.639in^3}{12} = 0.0217 \frac{in^4}{in}$$

$$P_{CR} = \frac{1.32}{7.909in} \left(\left(28000 \frac{lb}{in^2} \right) \left(0.0217 \frac{in^4}{in} \right) \right)^{\frac{1}{3}} \left(3,472 \frac{lb}{in^2} \right)^{\frac{2}{3}} = 324.4 \text{ psi}$$

With an overburden stress of 50 psi, an 8-inch PE 3408, 130 psi-rated pipe will have sufficient buckling resistance.

D. Evaluate Ring Deflection

Ring deflections are calculated using the Watkins-Gaube method. First, the rigidity factor and soil strain are determined.


$$R_F = \frac{12E_s(DR-1)^3}{E} = \frac{(12)(2083psi)(13.38-1)^3}{28,000psi} = 1,693.8$$

Where

- R_F = Rigidity Factor
 E_s = Secant Modulus of Soil = 2083 psi
 DR = Dimension Ratio = $D_o/t = 8.548/0.639 = 13.38$
 E = Modulus of elasticity of pipe material = 28,000 psi

$$\epsilon_s = \frac{wH}{144E_s} = \frac{(62.6pcf)(115ft)}{(144)(2083psi)} = 0.0240$$

Using the Watkins-Gaube Graph (below) and the rigidity factor, the deformation factor D_F was determined to be 1.40.



Finally, ring deflection can be calculated.

$$\frac{\Delta X}{D_m}(100) = D_F \epsilon_s = (1.40)(2.40\%) = 3.36\%$$



CLIENT: Intermountain Regional Landfill
PROJECT: LF Redesign
FEATURE: Buried Pipe Design
PROJECT NO.: 373.02.100

SHEET 5 OF 5
COMPUTED: RJG
CHECKED: GLJ
DATE: Oct. 2016

The PLEXCO design manual references a study by Jansen that states strains of 8% should perform well for at least 50 years. ISCO Industries also lists its polyethylene pipe as having an elongation at yield of 8% (page 62 of the design manual).

The structural envelope around both the 6-inch and the 8-inch diameter corrugated polyethylene pipes should provide the structural support necessary to maintain the integrity of the pipes.

Reference Manuals:

Corrugated Polyethylene Pipe Design Manual & Installation Guide. (n.d.). Retrieved October 3, 2016, from Plastics Pipe Institute: <http://plasticpipe.org/drainage/cppa-design-guide.html>

Modulus of Soil Reaction, E'. (1997, April). Retrieved October 3, 2016, from Rinker Materials: <http://www.rinkerpipe.com/TechnicalInfo/files/InfoBriefs/IB4003ModulusSoilReactionE.pdf>

Plexco/Spirolite Engineering Manual 2. "System Design", by Chevron Chemical Co., April 1996

- I. Objective: Evaluate the long-term strength of the 24-inch DR17 HDPE pipe against failure or significant loss of cross-sectional area.

Design Criteria:

Pipe Diameter = 24 inches
Maximum Design Height of Overburden = 76 feet

Unit weight of overburden (76 ft of total height):

| | | |
|-----------------------------------|---|------------------|
| Soil cover (2 ft @ 120 pcf) | = | 240 psf |
| Closure Material (3 ft @ 120 pcf) | = | 360 psf |
| Waste (76-2-3=71 ft @ 60 pcf) | = | 4,260 psf |
| <u>Total</u> | = | <u>4,860 psf</u> |

A. Soil Loads

In the case of maximum overburden height, the soil and waste will have an average unit weight of 64 pcf. Vehicle loads will be insignificant at this depth. The weight of the soil column above the pipe is given by the following equation:

$$W_C = \frac{H\gamma_S OD}{144} = \frac{76 \text{ ft} * 64 \text{ pcf} * 24 \text{ in}}{144} = 810.7 \text{ lb/inch}$$

| | | |
|------------|---|---|
| W_C | = | Weight of soil column above pipe, lb/inch of pipe |
| H | = | Burial depth to the top of pipe = 76 ft |
| γ_S | = | Average soil density = 64 pcf |
| OD | = | Outside diameter of pipe = 24 in |

Vehicle live loads can have significant effects on shallow buried pipes. Thus, calculations must also be performed for the minimum case of 3 ft of cover and vehicle loads. For this case, the average soil unit weight is 100 pcf and

$$W_C = \frac{3 \text{ ft} * 100 \text{ pcf} * 24 \text{ in}}{144} = 50.0 \text{ lb/inch}$$

The live load transferred to the pipe from a vehicle is given by the equation

$$W_L = OD * P_L = 24 \text{ in} * 26.39 = 633 \text{ lb/inch}$$

$$\begin{aligned} W_L &= \text{Live load, lb/linear inch of pipe} \\ OD &= \text{Outside diameter of pipe} \\ P_L &= \text{Live load factor} = 26.39 \end{aligned}$$

The live load factor was based on a soil cover depth of 3 ft for Cooper E-80. This represents the most extreme case. Since the loads for the extreme live load case are smaller than the case of maximum overburden, further calculations will be based on the deadload case of 76 ft of overburden when the landfill is at maximum capacity.

B. Evaluate Wall Crushing

The compression stress on the pipe walls is given below:

$$S = P_L D_o / 288t$$

$$\begin{aligned} S &= \text{Compressive stress (psi)} \\ P_L &= \text{vertical load applied to pipe (psf)} \\ t &= \text{wall thickness (in)} \\ D_o &= \text{outside diameter of pipe (in)} \end{aligned}$$

The maximum long-term stress value given by Plexco and other publications is 1600 psi, and with a safety factor of 2 this is reduced to 800 psi.

$$D_o/t = 288(800 \text{ psi}) / 4,860 \text{ psf} = 47.4$$

Therefore, an SDR of 47 or lower should be strong enough to avoid crushing failure so the selection of 17 is sufficient.

C. Evaluate Deflection

Ring deflections are calculated using the Modified Iowa Equation. Vertical deflection should be less than 7.5% of the inside diameter.

$$\Delta y = \frac{K(D_L W_C + W_L)}{0.149PS + 0.061E'}$$

Where

| | | |
|------------|---|--|
| Δy | = | Deflection, in |
| K | = | Bedding constant = 0.1 |
| D_L | = | Deflection lag factor = 1.0 |
| W_C | = | Soil column load on pipe, lb/linear inch of pipe |
| W_L | = | Live load, lb/linear inch of pipe (negligible) |
| OD | = | Outside diameter of pipe = 24 in |
| PS | = | Pipe stiffness = 34 pii |
| E' | = | Modulus of soil reaction = 2000 psi |

Notice: A modulus of soil reaction of 2000 psi is necessary for adequate pipe performance, and will only be obtained if the most granular soil on site is used. Calculations are performed assuming that this granular soil is used and compacted to greater than 95% standard Proctor density.

If these parameters are met,

$$\Delta y = \frac{0.1(1.0 * 969.4 \text{ lb/in})}{0.149 * 34 \text{ pii} + 0.061 * 2000 \text{ psi}} = 0.763 \text{ in}$$

And

$$\% \text{ Deflection} = \frac{0.763 \text{ in}}{24 \text{ in}} = 3.17\%$$

This level of deflection is well below the minimum of 7.5%.

D. Evaluate Buckling

The critical buckling pressure is given below:

$$P_{CR} = \frac{0.772}{SF} \left[\left(\frac{E'PS}{1-\nu^2} \right) \right]^{\left(\frac{1}{2} \right)}$$

| | | |
|----------|---|---------------------------------|
| P_{CR} | = | Critical buckling pressure, psi |
| E' | = | Modulus of soil reaction |

PS = Pipe stiffness = 34 pii (Reference Manual Table 5-1)
 ν = Poisson ratio = 0.4 for polyethylene
 SF = Safety Factor = 2.0

With a modulus of soil reaction of 2000 psi, the critical buckling pressure is:

$$P_{cr} = \frac{0.772}{2.0} \left[\frac{2000 \cdot 34}{1 - 0.40^2} \right] = 109.8 \text{ psi}$$

The actual buckling pressure is as follows (if pipe is above water table):

$$P_V = \frac{R_W H \gamma_s}{144} + \frac{W_L}{OD}$$

P_V = Actual buckling pressure, psi
 R_W = Water buoyancy factor
 H = Burial depth to top of pipe, ft
 γ_s = Soil density, pcf
 W_L = Live load (insignificant)
= $OD \cdot P_L$
 OD = Outside diameter of pipe, in

The water buoyancy factor is 1 for pipes above the water table. Using a burial depth of 76 ft, an average soil density of 64 pcf, the actual buckling pressure is:

$$P_v = \frac{(1.0)(76\text{ft})(64\text{pcf})}{144} = 33.8 \text{ psi}$$

Since the actual buckling pressure is less than the critical buckling pressure, the pipe has sufficient strength to avoid buckling.

D. Evaluate Bending

Bending stress should not exceed the long-term tensile strength of polyethylene (900 psi). Bending strain should not exceed 5%.

$$\sigma_b = \frac{(2)(D_f)(E)(\Delta y)(y_o)(SF)}{D_M^2}$$

σ_b = Bending stress, psi
 D_F = Shape factor
 E = Long-term modulus of elasticity of polyethylene, 22,000 psi
 Δy = Deflection, in
 y_o = Distance from centroid of pipe wall to outside surface
= 1.7 in

OD = Outside diameter of pipe = 24 in
 ID = Inside diameter of pipe = 21.007 in
 SF = Safety factor = 1.5
 D_M = Mean pipe diameter, in = 25.3 in

The shape factor for this pipe depends on the backfill material used. The most conservative case in table 5-2 of the manual gives a shape factor of 5.6. Using this value,

$$\sigma_b = \frac{(2)(5.6)(22,000\text{psi})(0.763\text{in})(1.7\text{in})(1.5)}{25.3^2\text{in}^2} = 749\text{ psi}$$

This is below the long-term tensile strength of polyethylene, which is 900 psi.

Bending strain must not exceed 5%. Bending strain is given by the equation

$$\epsilon_B = \frac{2D_f \Delta y y_O SF}{D_M^2} = \frac{2 * 5.6 * 0.763\text{in} * 1.7\text{in} * 1.5}{25.3^2} = 0.034$$

Bending strain is sufficiently low.

1. Geotextile filter fabric is to be placed on top of the drainage net to serve as a filter for the overlying materials. Check design criteria on pages 38 – 45 of "Geotextile Design and Construction Guidelines" by the U.S. Department of Transportation to determine the soil retention and permeability criteria that must be met.

Native Soil Properties will be used to design the filter fabric. Other materials may be used as a cover soil, however due to the high fines content of the native materials they will lead to a more conservative design. Permeability is the exception in that a higher permeability of the cover soil is more conservative. Therefore the conductivity will be based on the highest cover soil conductivity that might be encountered.

A. Soil Retention

A sieve analysis of the native soil was performed by Applied Geotechnical Engineering Consultants¹. The results of this analysis are presented in Table 1 and in Figure 1. From Figure 1 the following soil parameters were estimated.

$$D_{10} < 0.0013$$

$$D_{60} = 0.011$$

$$C_u = D_{10}/D_{60} < 0.091$$


$$D_{85} = .065 \text{ mm}$$

Table 1

| Sieve # | Size (mm) | % Finer |
|---------|-----------|---------|
| 3/4" | 20 | 100 |
| 3/8" | 9.525 | 100 |
| 4 | 4.75 | 100 |
| 10 | 2 | 100 |
| 16 | 1.19 | 100 |
| 40 | 0.42 | 99 |
| 50 | 0.297 | 99 |
| 100 | 0.149 | 97 |
| 200 | 0.074 | 86 |

¹AGEC Lab results

Figure 1: Gradation Curve of Soil at Landfill Site



Criteria from page 39 of design manual for $\geq 50\%$ passing the #200 sieve:

$$\text{AOS No. (Fabric)} \leq 0.3 \text{ mm}$$

$$O_{95} \leq 1.8 * D_{85} \text{ (soil)}$$

$$O_{95} \leq 1.8 * 0.065 \text{ mm}$$

$$O_{95} \leq 0.12 \text{ mm}$$

Geotextiles with O_{95} this small are not commonly available.

Therefore, using AASHTO M 288 Standard Specifications for Geotextiles, the recommended maximum $O_{95} = 0.22 \text{ mm}$ for materials with more than 50% passing the no. 200 sieve.

B. Permeability Criteria

$$k_{v \text{ (fabric)}} \geq 10 * k_{v \text{ (soil)}}$$

$$k_{v \text{ (fabric)}} \geq 10 * (1.35 * 10^{-3} \text{ cm/sec})$$

$$k_{v \text{ (fabric)}} \geq 1.35 * 10^{-2} \text{ cm/sec}$$

C. Clogging Resistance Criterion

$$O_{95 \text{ geotextile}} \geq 3 D_{15 \text{ soil}} \geq 3 * 0.001 = 0.003 \text{ mm} - \text{OK}$$

An 8-oz/yd³ nonwoven geotextile on a GSE 250 geocomposite or equivalent will meet the AASHTO M 288 Standard Specification and the USDOT Criteria.

2. Check the tensile strength requirement. Since the geotextile fabric is part of the geocomposite, the fabric must have sufficient strength to bridge the ridges of the geonet without failure. According to Robert M. Koerner (1990) in "Designing with Geosynthetics" (published by Prentice-Hall, Inc.) the required fabric burst strength to bridge the gap is:

$$T_{req'd} = p'd_v$$

where

| | | |
|-------------|---|--|
| $T_{req'd}$ | = | the required fabric strength |
| p' | = | the stress at the fabric's surface, which in the worst case would equal the overburden stress at closure |
| d_v | = | the maximum void diameter, or in this case the gap distance between ridges of the geonet = 0.4 inches |

The Normal Bearing Pressure (P):

The existing soils to be used for the daily soil cover and protective soil cover have a dry density of 97 pcf (average value of those reported by Earthtec in their original geological study performed in 2006 for Intermountain Regional Landfill and AGEC in a study performed in 2014). The average saturated density of 124 pcf was determined from the dry density based on a soils characteristics chart found in Foundation Engineering, by Peck R.B., W.E. Hanson, and T.H. Thornburn (1974).

| | |
|--------------------------------------|------------------|
| 115' Depth above Liner | |
| 110' of waste at 60 pcf | = 6,600 psf |
| 2' Soil Protective Cover at 124 pcf | = 248 psf |
| 3' Final Protective Cover at 124 pcf | = <u>372 psf</u> |
| | = 7,220 psf |
| TOTAL | = 50.1 psi |

Thus, $T_{req'd} = (50.1)(0.4) = 20.0$ psi

The geotextile will be designed using the design-by-function concept recommended by EPA for the design of hazardous waste facilities. According to EPA seminar publication Requirements for Hazardous Waste Landfill Design, Construction, and Closure (1989, pg. 56), "whatever parameter of a specific material one is evaluating, a required value for the material must be found using a design model and an allowable value for the material must be determined by a test method. The allowable value divided by the required value yields the design ratio, or the resulting factor of safety." Thus in evaluating the tensile strength requirement for the filter fabric, an allowable tensile strength is divided by the required tensile strength to determine the factor of safety for the design, or:

$$\text{Factor of Safety (FS)} = T_{\text{allow}}/T_{\text{req'd}}$$

where

$$\begin{aligned} T_{\text{allow}} &= \text{the allowable tensile strength as obtained from laboratory testing, and} \\ T_{\text{req'd}} &= \text{the required tensile strength as obtained from design of the actual system} \end{aligned}$$

Koerner (1990) in "Designing with Geosynthetics" suggests that additional factors of safety be applied to the tensile strength value found by test method to account for installation damage, creep and for biological and chemical degradation. In accordance with the procedures recommended by Koerner (1990), a factor of safety of 1.2 will be applied to the tensile strength found by test method for installation damage, an additional factor of safety of 1.2 will be applied to the tensile strength value for creep, and an additional factor of safety of 1.5 will be applied to test tensile strength for potential biological and chemical degradation. This value becomes the allowable value to be used in the equation above. This is in addition to the factor of safety to be used in the design-by-function concept discussed above. Thus,

$$T_{\text{allow}} = \frac{T_{\text{given}}}{(1.2 * 1.2 * 1.5)} = \frac{T_{\text{given}} \text{ lbs}}{2.16 \text{ in}^2}$$

Assuming a design-by-function FS of 2, then

$$\begin{aligned} 2 &= T_{\text{allow}}/T_{\text{req'd}} \\ T_{\text{given}}/2.16 &= 2 * T_{\text{req'd}} \\ T_{\text{given}} &= 2 * 2.16 * T_{\text{req'd}} \\ T_{\text{given}} &= 2 * 2.16 * 20.0 \text{ psi} \\ T_{\text{given}} &= 86.4 \text{ lbs} \end{aligned}$$

APPENDIX F

Hydrology

Onsite Run-off

Offsite Run-on

Downspouts



CLIENT: Intermountain Regional Landfill
PROJECT: LF Redesign
FEATURE: Hydrology Runoff for LF Redesign
PROJECT NO.: 373.02.101

SHEET 1 OF 2
COMPUTED: MEN
CHECKED: GLJ
DATE: Oct 2020

Purpose: To determine the runoff from the closure cap of the Intermountain Regional Landfill.

Method: The SCS curve number method was used in a HEC-HMS hydrology model.

Required: In order to calculate the runoff the following steps and information are required:

- A delineation of the tributary area.
- A representative Soil Conservation Service (SCS) curve number (CN) for the tributary area.
- Lag time.
- Storm Distribution.
- 100 year-24 hour precipitation.

Delineation: The delineation of the subbasins, shown in Figure 1, was based on the preliminary cell closure cap design. Each basin would drain into a channel which would convey the runoff to a down spout that would take the water off of the cell.

Curve Numbers: Curve numbers were determined based on the hydrologic soil type, Type C, found in the area because native soils are going to be used for cover. The cover type was assumed to be similar to a dirt road. The cover conditions were combined with the hydrologic soil type to produce a curve number based on Table 2-2a of Technical Release 55. A curve number of 87 was applied to each subbasin.

Precipitation: A 25 year - 24 hour event was used for the design storm. The rainfall amount was taken from the "Point Precipitation Frequency Estimates from NOAA Atlas 14. The value for a 25 year - 24 hour event was 1.74 inches.

Storm Distribution: The distribution used for the 24-hour event was the SCS Type II.

Lag Time: Lag time (T_L) for each subbasin was calculated by using the time of concentration (T_c) and the equation $T_L = 0.6T_c$. T_c was calculated using Worksheet 3 in TR-55. A lag time of 5 minutes was used in the HEC-HMS model in the event that the calculated lag time was less than 5 minutes.

Results: Results are summarized in the table below.



CLIENT: Intermountain Regional Landfill
PROJECT: LF Redesign
FEATURE: Hydrology Runoff for LF Redesign
PROJECT NO.: 373.02.101

SHEET 2 OF 2
COMPUTED: MEN
CHECKED: GLJ
DATE: Oct 2020

Table 1: Peak Discharge for each Downspout

| Outlet | Peak Discharge (cfs) | Contributing Subbasins | Description |
|--------|----------------------|------------------------|--------------------------|
| 1 | 20.2 | 3 | West Side (Top) |
| 2 | 30.7 | 4 | West Side (Top) |
| 3 | 24.8 | 5 | West Side (Top) |
| 4 | 3.7 | 8 | North Side (Bench) |
| 5 | 4.2 | 9 | North Side (Bench) |
| 6 | 3.9 | 10 | Northeast Corner (Bench) |
| 7 | 4.9 | 11 | East Side (Bench) |
| 8 | 3.8 | 12 | Southeast Corner (Bench) |
| 9 | 6.9 | 13 | South Side (Bench) |







Figure 2: HEC-HMS Model



Subbasin and outlet names correspond with labels on Figure 1.

Figure 3: Model Summary Output



Intermountain Regional Landfill
 Lag Time Calculations
 Computed: MEN
 10/26/2020

Sheet flow

| Subbasin Name | Manning N | Flow Length (ft) | Design rainfall (in) | High Elevation | Low Elevation | Slope (ft/ft) | Tt (hr) |
|---------------|-----------|------------------|----------------------|----------------|---------------|---------------|---------|
| 1 | 0.011 | 200 | 1.1 | 4903.0 | 4855.0 | 0.24 | 0.022 |
| 2 | 0.011 | 250 | 1.1 | 4919.0 | 4857.0 | 0.25 | 0.026 |
| 3 | 0.011 | 300 | 1.1 | 4953.0 | 4946.0 | 0.02 | 0.078 |
| 4 | 0.011 | 300 | 1.1 | 4953.0 | 4946.0 | 0.02 | 0.078 |
| 5 | 0.011 | 300 | 1.1 | 4953.0 | 4946.0 | 0.02 | 0.078 |
| 6 | 0.011 | 240 | 1.1 | 4914.0 | 4855.0 | 0.25 | 0.025 |
| 7 | 0.011 | 270 | 1.1 | 4921.0 | 4856.0 | 0.24 | 0.028 |
| 8 | 0.011 | 220 | 1.1 | 4936.0 | 4873.0 | 0.29 | 0.022 |
| 9 | 0.011 | 270 | 1.1 | 4952.0 | 4882.0 | 0.26 | 0.027 |
| 10 | 0.011 | 240 | 1.1 | 4952.0 | 4894.0 | 0.24 | 0.025 |
| 11 | 0.011 | 220 | 1.1 | 4952.0 | 4900.0 | 0.24 | 0.024 |
| 12 | 0.011 | 220 | 1.1 | 4951.0 | 4902.0 | 0.22 | 0.025 |
| 13 | 0.011 | 230 | 1.1 | 4953.0 | 4872.0 | 0.35 | 0.021 |

Equation Used:

$$T_t = \frac{0.007(nL)^{0.8}}{(P_2)^{0.5} s^{0.4}} \quad [\text{eq. 3-3}]$$

where:

- T_t = travel time (hr),
- n = Manning's roughness coefficient (table 3-1)
- L = flow length (ft)
- P₂ = 2-year, 24-hour rainfall (in)
- s = slope of hydraulic grade line
(land slope, ft/ft)

Shallow Concentrated Flow

Velocity taken from Fig 3-1 in TR-55

| Subbasin Name | Manning N | Flow Length (ft) | High Elevation* | Low Elevation* | Slope (ft/ft) | Velocity (ft/sec) | Tt (hr) |
|---------------|-----------|------------------|-----------------|----------------|---------------|-------------------|---------|
| 1 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 2 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 3 | 0.011 | 1,500 | 4946.0 | 4890.0 | 0.037 | 1.1 | 0.379 |
| 4 | 0.011 | 1,500 | 4946.0 | 4890.0 | 0.037 | 1.1 | 0.379 |
| 5 | 0.011 | 1,500 | 4946.0 | 4890.0 | 0.037 | 1.1 | 0.379 |
| 6 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 7 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 8 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 9 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 10 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 11 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 12 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |
| 13 | 0.011 | 0 | N/A | N/A | N/A | 0 | 0 |

* Indicates a subbasin with no anticipated shallow concentrated flow (e.g. distance from any point to channel flow is less than 300 ft)

Equation used:

$$T_t = \frac{L}{3600V} \quad [\text{eq. 3-1}]$$

where:

T_t = travel time (hr)

L = flow length (ft)

V = average velocity (ft/s)

3600 = conversion factor from seconds to hours.

Channel Flow

| Subbasin Name | Manning N | Flow Length (ft) | High Elevation | Low Elevation | Slope (ft/ft) | Hydraulic Radius | Velocity (ft/s) | Tt (hr) |
|---------------|-----------|------------------|----------------|---------------|---------------|------------------|-----------------|---------|
| 1 | 0.02 | 0 | N/A | N/A | N/A | N/A | 0.0 | 0.000 |
| 2 | 0.02 | 0 | N/A | N/A | N/A | N/A | 0.0 | 0.000 |
| 3 | 0.02 | 700 | 4890.0 | 4873.0 | 0.024 | 0.5 | 7.31 | 0.027 |
| 4 | 0.02 | 700 | 4890.0 | 4870.0 | 0.029 | 0.5 | 7.93 | 0.025 |
| 5 | 0.02 | 700 | 4890.0 | 4870.0 | 0.029 | 0.5 | 7.93 | 0.025 |
| 6 | 0.02 | 0 | N/A | N/A | N/A | N/A | 0.0 | 0.000 |
| 7 | 0.02 | 0 | N/A | N/A | N/A | N/A | 0.0 | 0.000 |
| 8 | 0.02 | 560 | 4893.0 | 4873.0 | 0.04 | 0.5 | 8.87 | 0.018 |
| 9 | 0.02 | 580 | 4902.0 | 4882.0 | 0.03 | 0.5 | 8.72 | 0.018 |
| 10 | 0.02 | 830 | 4913.0 | 4894.0 | 0.02 | 0.5 | 7.10 | 0.032 |
| 11 | 0.02 | 700 | 4920.0 | 4900.0 | 0.03 | 0.5 | 7.93 | 0.025 |
| 12 | 0.02 | 700 | 4922.0 | 4902.0 | 0.03 | 0.5 | 7.93 | 0.025 |
| 13 | 0.02 | 1,500 | 4917.0 | 4872.0 | 0.03 | 0.5 | 8.13 | 0.051 |

$$V = \frac{1.49r^{\frac{2}{3}}s^{\frac{1}{2}}}{n} \quad [\text{eq. 3-4}]$$

where:

V = average velocity (ft/s)

r = hydraulic radius (ft) and is equal to a/p_w

a = cross sectional flow area (ft²)

p_w = wetted perimeter (ft)

s = slope of the hydraulic grade line (channel slope, ft/ft)

n = Manning's roughness coefficient for open channel flow.

Results:

| Subbasin Name | Tc (hr) | TI (hr) | Lag Time (min) | HMS Lag Time (min) |
|---------------|---------|---------|----------------|--------------------|
| 1 | 0.022 | 0.013 | 0.80 | 5.0 |
| 2 | 0.026 | 0.016 | 0.94 | 5.0 |
| 3 | 0.483 | 0.290 | 17.39 | 17.0 |
| 4 | 0.481 | 0.289 | 17.31 | 17.0 |
| 5 | 0.481 | 0.289 | 17.31 | 17.0 |
| 6 | 0.025 | 0.015 | 0.91 | 5.0 |
| 7 | 0.028 | 0.017 | 1.01 | 5.0 |
| 8 | 0.040 | 0.024 | 1.43 | 5.0 |
| 9 | 0.046 | 0.027 | 1.65 | 5.0 |
| 10 | 0.058 | 0.035 | 2.09 | 5.0 |
| 11 | 0.049 | 0.029 | 1.75 | 5.0 |
| 12 | 0.049 | 0.029 | 1.77 | 5.0 |
| 13 | 0.072 | 0.043 | 2.61 | 5.0 |



NOAA Atlas 14, Volume 1, Version 5
Location name: Fairfield, Utah, USA*
Latitude: 40.2156°, Longitude: -112.08°
Elevation: 4852.8 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypaluk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aeriels](#)

PF tabular

| PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹ | | | | | | | | | | |
|--|-------------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|------------------------------|
| Duration | Average recurrence interval (years) | | | | | | | | | |
| | 1 | 2 | 5 | 10 | 25 | 50 | 100 | 200 | 500 | 1000 |
| 5-min | 0.114 (0.097-0.135) | 0.144 (0.124-0.172) | 0.201 (0.172-0.241) | 0.252 (0.212-0.303) | 0.329 (0.272-0.397) | 0.400 (0.323-0.486) | 0.481 (0.379-0.586) | 0.576 (0.440-0.710) | 0.724 (0.529-0.906) | 0.855 (0.602-1.08) |
| 10-min | 0.173 (0.147-0.206) | 0.219 (0.189-0.262) | 0.306 (0.261-0.366) | 0.383 (0.322-0.461) | 0.501 (0.413-0.604) | 0.609 (0.492-0.739) | 0.733 (0.577-0.892) | 0.877 (0.669-1.08) | 1.10 (0.805-1.38) | 1.30 (0.916-1.65) |
| 15-min | 0.214 (0.182-0.255) | 0.272 (0.235-0.325) | 0.380 (0.324-0.454) | 0.475 (0.399-0.572) | 0.621 (0.513-0.749) | 0.755 (0.610-0.916) | 0.908 (0.715-1.11) | 1.09 (0.830-1.34) | 1.37 (0.998-1.71) | 1.61 (1.14-2.04) |
| 30-min | 0.288 (0.246-0.343) | 0.366 (0.316-0.437) | 0.511 (0.436-0.612) | 0.640 (0.537-0.770) | 0.836 (0.691-1.01) | 1.02 (0.821-1.23) | 1.22 (0.964-1.49) | 1.46 (1.12-1.80) | 1.84 (1.34-2.30) | 2.17 (1.53-2.75) |
| 60-min | 0.357 (0.304-0.425) | 0.453 (0.391-0.541) | 0.633 (0.540-0.758) | 0.792 (0.665-0.953) | 1.03 (0.855-1.25) | 1.26 (1.02-1.53) | 1.51 (1.19-1.84) | 1.81 (1.38-2.23) | 2.28 (1.66-2.85) | 2.69 (1.89-3.40) |
| 2-hr | 0.438 (0.389-0.506) | 0.551 (0.488-0.643) | 0.724 (0.636-0.842) | 0.887 (0.770-1.03) | 1.14 (0.967-1.32) | 1.36 (1.14-1.60) | 1.63 (1.32-1.92) | 1.93 (1.52-2.31) | 2.41 (1.81-2.92) | 2.83 (2.05-3.51) |
| 3-hr | 0.488 (0.439-0.556) | 0.609 (0.545-0.692) | 0.785 (0.696-0.890) | 0.935 (0.824-1.06) | 1.18 (1.02-1.34) | 1.39 (1.18-1.62) | 1.65 (1.37-1.94) | 1.95 (1.58-2.34) | 2.42 (1.89-2.95) | 2.84 (2.13-3.54) |
| 6-hr | 0.620 (0.569-0.688) | 0.766 (0.700-0.848) | 0.941 (0.853-1.04) | 1.09 (0.991-1.22) | 1.31 (1.17-1.47) | 1.50 (1.32-1.68) | 1.74 (1.50-1.97) | 2.03 (1.72-2.36) | 2.50 (2.06-2.98) | 2.90 (2.34-3.58) |
| 12-hr | 0.761 (0.699-0.837) | 0.935 (0.859-1.03) | 1.13 (1.04-1.25) | 1.30 (1.19-1.43) | 1.53 (1.38-1.69) | 1.70 (1.52-1.89) | 1.89 (1.67-2.12) | 2.16 (1.88-2.44) | 2.58 (2.20-3.01) | 2.94 (2.45-3.61) |
| 24-hr | 0.901 (0.833-0.979) | 1.11 (1.02-1.20) | 1.33 (1.22-1.44) | 1.51 (1.38-1.63) | 1.74 (1.60-1.89) | 1.92 (1.75-2.08) | 2.10 (1.91-2.28) | 2.29 (2.07-2.48) | 2.61 (2.27-3.04) | 2.97 (2.48-3.65) |
| 2-day | 1.01 (0.929-1.10) | 1.23 (1.14-1.34) | 1.48 (1.36-1.60) | 1.68 (1.55-1.82) | 1.95 (1.79-2.11) | 2.16 (1.98-2.33) | 2.37 (2.17-2.57) | 2.59 (2.35-2.81) | 2.88 (2.59-3.13) | 3.10 (2.77-3.69) |
| 3-day | 1.10 (1.01-1.20) | 1.35 (1.24-1.47) | 1.62 (1.49-1.77) | 1.84 (1.70-2.01) | 2.16 (1.98-2.35) | 2.40 (2.19-2.61) | 2.65 (2.41-2.89) | 2.91 (2.63-3.18) | 3.25 (2.91-3.56) | 3.52 (3.13-4.03) |
| 4-day | 1.20 (1.09-1.31) | 1.46 (1.34-1.60) | 1.76 (1.62-1.93) | 2.01 (1.84-2.21) | 2.37 (2.16-2.59) | 2.64 (2.40-2.89) | 2.93 (2.65-3.21) | 3.23 (2.90-3.54) | 3.63 (3.23-4.00) | 3.95 (3.49-4.37) |
| 7-day | 1.40 (1.28-1.53) | 1.72 (1.58-1.88) | 2.06 (1.89-2.25) | 2.35 (2.15-2.56) | 2.73 (2.49-2.97) | 3.03 (2.76-3.29) | 3.33 (3.02-3.62) | 3.63 (3.28-3.95) | 4.03 (3.61-4.40) | 4.33 (3.86-4.75) |
| 10-day | 1.58 (1.45-1.72) | 1.94 (1.78-2.10) | 2.31 (2.13-2.51) | 2.62 (2.41-2.84) | 3.02 (2.77-3.27) | 3.33 (3.04-3.60) | 3.63 (3.31-3.94) | 3.93 (3.58-4.27) | 4.32 (3.90-4.70) | 4.60 (4.14-5.03) |
| 20-day | 2.06 (1.90-2.24) | 2.53 (2.33-2.75) | 3.00 (2.77-3.26) | 3.37 (3.12-3.66) | 3.85 (3.55-4.17) | 4.19 (3.86-4.54) | 4.52 (4.16-4.91) | 4.84 (4.44-5.27) | 5.24 (4.78-5.71) | 5.52 (5.03-6.04) |
| 30-day | 2.43 (2.24-2.63) | 2.98 (2.75-3.22) | 3.54 (3.27-3.83) | 3.99 (3.68-4.30) | 4.58 (4.21-4.94) | 5.01 (4.60-5.41) | 5.44 (4.98-5.88) | 5.86 (5.34-6.34) | 6.39 (5.80-6.94) | 6.77 (6.12-7.37) |
| 45-day | 3.03 (2.81-3.27) | 3.70 (3.44-4.00) | 4.37 (4.05-4.70) | 4.88 (4.53-5.25) | 5.54 (5.14-5.96) | 6.01 (5.57-6.47) | 6.46 (5.98-6.95) | 6.88 (6.36-7.41) | 7.39 (6.81-7.96) | 7.74 (7.12-8.36) |
| 60-day | 3.55 (3.31-3.80) | 4.35 (4.05-4.66) | 5.12 (4.76-5.47) | 5.71 (5.30-6.09) | 6.44 (5.99-6.87) | 6.97 (6.47-7.43) | 7.47 (6.92-7.96) | 7.93 (7.33-8.47) | 8.49 (7.82-9.07) | 8.86 (8.15-9.49) |





¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

PDS-based depth-duration-frequency (DDF) curves


Latitude: 40.2156°, Longitude: -112.0800°




[Back to Top](#)

Maps & aeriels

Small scale terrain



Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)

Purpose: To design the downspout to convey runoff from the closure cap and bench.

Process: Reference: Reference: “ADS Specifier Manual - Civil Engineer”, Advanced Drainage Systems, Inc.)

Each hydrologic subbasin on the landfill closure cap was delineated, its area was measured, and then runoff calculations were performed in accordance with TR-55. See hydrology calculations discussed previously in the report. Maximum runoff from each downspout location is included in the summary table below.

| Outlet | Peak Discharge (cfs) | Contributing Subbasins | Description |
|--------|----------------------|------------------------|--------------------------|
| 1 | 20.2 | 3 | West Side (Top) |
| 2 | 30.7 | 4 | West Side (Top) |
| 3 | 24.8 | 5 | West Side (Top) |
| 4 | 3.7 | 8 | North Side (Bench) |
| 5 | 4.2 | 9 | North Side (Bench) |
| 6 | 3.9 | 10 | Northeast Corner (Bench) |
| 7 | 4.9 | 11 | East Side (Bench) |
| 8 | 3.8 | 12 | Southeast Corner (Bench) |
| 9 | 6.9 | 13 | South Side (Bench) |

Downspouts

An 18-inch pipe was chosen to be used for each downspout to accommodate this flow.

Manning’s n = 0.020

$$Q = (1.49/n)(A)(r)^{2/3}(S)^{1/2}$$

A = cross-sectional area of pipe (ft²)

r = hydraulic radius of pipe (ft)

S = slope of pipe (ft/ft)

$$Q = (1.49/0.020)(\pi(9/12\text{ft})^2)((9/12)/2)^{2/3}(0.25)^{0.5}$$

$$Q = 34.1 \text{ ft}^3/\text{sec}$$

An 18 inch pipe is capable of carrying the maximum projected flows.

Inlet pipes must have sufficient head above the pipe in order to obtain maximum flow. Due to the geometry of the landfill cap design, a maximum of 4 feet of head above the pipe inlet can be obtained. Using the orifice equation with a standard discharge coefficient of 0.61,

$$Q = (C_d) \cdot (A) \cdot (\sqrt{2 \cdot g \cdot h})$$

Cd = Coefficient of discharge

A = Area of orifice

g = 32.2 ft/s²

h = head above orifice

$$Q = (0.61) \cdot (\pi(9/12)^2) \cdot (\sqrt{2 \cdot 32.2 \text{ft/s}^2 \cdot 4 \text{ft}})$$

$$Q = 17.3 \text{ cfs}$$

Results:

To meet the demands of the maximum predicted peak flows, two 18" pipes are necessary for each of the four outlet areas denoted on figure 1. This will provide a capacity of 34.6 cfs, which is sufficient for any of the four downspouts.

- Purpose:** To determine the design flows to use for the run-on control diversions around the facility.
- Method:** The Soil Conservation Service (SCS) curve number method was used with the HEC-HMS hydrology model. The HEC-HMS model was set up using information from ArcGIS.
- Required:** In order to calculate the runoff the following steps and information are required:
- A delineation of the tributary area
 - A weighted or representative curve number for the tributary area
 - Lag time
 - Storm Distribution
 - 25 year-24 hour precipitation
- Delineation:** The delineation of the subbasin, shown in Figure 1, was based on the contours provided from USGS topographic maps. One basin was delineated for the entire site.
- Curve Numbers:** Curve numbers were determined based on the hydrologic soil type and soil cover contained in information given in the NRCS study "Fairfield-Nephi Area, Utah." The cover conditions were combined with the hydrologic soil type to produce a curve number based on Table 2-2d of Technical Release 55. Because the subbasin contained several different soil types and covers, a weighted curve number was applied to the entire subbasin based on area. The calculations of the weighted curve numbers are attached.
- Precipitation:** A 25 year - 24 hour event was used for the design storm according to the EPA regulation in 258.26(a)(1) of Title 40 Chapter 1. The rainfall amount was taken from the "Point Precipitation Frequency Estimates from NOAA Atlas 14". One precipitation value was used for the subbasin due to similar values of rainfall throughout the entire subbasin.
- Storm Distribution:** The distribution used for the 24-hour event was the SCS Type II.
- Lag Time:** The lag times were calculated by using the Time of Concentration and the equation $T_L = 0.6T_c$. T_c was calculated using Worksheet 3 in TR-55. A calculation sheet for the subbasin is attached.
- Areal Reduction:** An areal reduction factor was applied based on the Salt Lake City Hydrology Manual. According to the manual, a 24-hour event has an areal reduction factor of:

$$ARF = 0.01(100 - 2 * Area^{0.46})$$

$$Area = \text{Total Tributary Area, } 6.69 \text{ mi}^2$$

$$ARF = 0.95$$



CLIENT: Intermountain Regional Landfill
PROJECT: LF Redesign
FEATURE: Hydrology Run-on for LF Redesign
PROJECT NO.: 373.02.100

SHEET 2 OF 2
COMPUTED: GLJ
CHECKED: TGA
DATE: October 2016

Results:

The results of the HEC-HMS model predicts a runoff of 61 cfs. Run-on protection should therefore have a capacity for the predicted flow rate.

Project: Intermountain Regional Landfill 2016 Redesign
Feature: Run-on Hydrology Weighted Curve Number Calculation
Computed: CAS
Date: May 2016
Checked: GLJ

| Map Unit Symbol | Acres in AO | Percent Soil Clas | Curve Number | % CN |
|-----------------|---------------|-------------------|--------------|----------------|
| Acf | 1577.9 | 36.9% D | 80 | 29.4969 |
| Ce | 1.1 | 0.0% C | - | 0 |
| Cf | 105.1 | 2.5% C | 63 | 1.54721 |
| GaBP | 50.9 | 1.2% C | 63 | 0.74932 |
| GbA | 455.4 | 10.6% C | 63 | 6.7041 |
| GbA | 151.8 | 3.5% C | 71 | 2.51847 |
| GbB | 148.425 | 3.5% C | 63 | 2.18502 |
| GbB | 49.475 | 1.2% C | 71 | 0.82083 |
| GdDp | 92.7 | 2.2% A | 63 | 1.36467 |
| GeD | 150.2 | 3.5% A | 63 | 2.21115 |
| HdC | 642.3 | 15.0% A | 63 | 9.45552 |
| LaC | 278.6 | 6.5% B | 51 | 3.32015 |
| LaC | 278.6 | 6.5% B | 58 | 3.77586 |
| MfA | 0.6 | 0.0% A | - | 0 |
| MfB | 0.9 | 0.0% A | - | 0 |
| SfC | 221.625 | 5.2% D | 70 | 3.62513 |
| SfC | 73.875 | 1.7% D | 78 | 1.34648 |
| Total | 4279.5 | 100% | | 69.1208 |




United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for Fairfield-Nephi Area, Utah; and Tooele Area, Utah - Tooele County and Parts of Box Elder, Davis and Juab Counties



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<http://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require alternative means

for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

| | |
|---|----|
| Preface | 2 |
| How Soil Surveys Are Made | 5 |
| Soil Map | 7 |
| Soil Map..... | 8 |
| Legend..... | 9 |
| Map Unit Legend..... | 10 |
| Map Unit Descriptions..... | 10 |
| Fairfield-Nephi Area, Utah..... | 13 |
| AcF—Amtoft-Rock outcrop complex, 30 to 70 percent slopes..... | 13 |
| Ce—Cheebe fine sandy loam..... | 14 |
| Cf—Cheebe silty clay loam..... | 15 |
| GaBP—Genola fine sandy loam, hummocky, 1 to 2 percent slopes..... | 17 |
| GbA—Genola silt loam, 0 to 1 percent slopes..... | 18 |
| GbB—Genola silt loam, 1 to 2 percent slopes..... | 19 |
| GdDP—Goldrun loamy fine sand, hummocky, 0 to 10 percent slopes..... | 20 |
| GeD—Goldrun-Cheebe complex, 0 to 10 percent slopes..... | 21 |
| HdC—Hiko Peak stony sandy loam, 4 to 8 percent slopes..... | 23 |
| LaC—Linoyer very fine sandy loam, 2 to 5 percent slopes..... | 25 |
| MfA—Medburn fine sandy loam, 0 to 2 percent slopes..... | 26 |
| MfB—Medburn fine sandy loam, 2 to 4 percent slopes..... | 27 |
| SfC—Shabliss very fine sandy loam, 2 to 5 percent slopes..... | 28 |
| Tooele Area, Utah - Tooele County and Parts of Box Elder, Davis and Juab Counties..... | 30 |
| 4—Amtoft-Rock outcrop complex, 30 to 70 percent slopes..... | 30 |
| References | 32 |

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil scientists classified and named the soils in the survey area, they compared the

Custom Soil Resource Report

individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.


Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map




Map Scale: 1:41,100 if printed on A landscape (11" x 8.5") sheet.




Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 12N WGS84


MAP LEGEND


Area of Interest (AOI)

 Area of Interest (AOI)




















Soils







 Soil Map Unit Polygons

 Soil Map Unit Lines


 Soil Map Unit Points

Special Point Features






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features


Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Fairfield-Nephi Area, Utah
 Survey Area Data: Version 9, Sep 23, 2015

Soil Survey Area: Tooele Area, Utah - Tooele County and Parts of Box Elder, Davis and Juab Counties
 Survey Area Data: Version 9, Sep 23, 2015

Your area of interest (AOI) includes more than one soil survey area. These survey areas may have been mapped at different scales, with a different land use in mind, at different times, or at different levels of detail. This may result in map unit symbols, soil properties, and interpretations that do not completely agree across soil survey area boundaries.

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 2, 2011—Aug 29, 2011

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

| Fairfield-Nephi Area, Utah (UT608) | | | |
|---------------------------------------|---|----------------|----------------|
| Map Unit Symbol | Map Unit Name | Acres in AOI | Percent of AOI |
| AcF | Amtoft-Rock outcrop complex, 30 to 70 percent slopes | 1,577.9 | 36.8% |
| Ce | Cheebe fine sandy loam | 1.1 | 0.0% |
| Cf | Cheebe silty clay loam | 105.1 | 2.5% |
| GaBP | Genola fine sandy loam, hummocky, 1 to 2 percent slopes | 50.9 | 1.2% |
| GbA | Genola silt loam, 0 to 1 percent slopes | 607.2 | 14.2% |
| GbB | Genola silt loam, 1 to 2 percent slopes | 197.9 | 4.6% |
| GdDP | Goldrun loamy fine sand, hummocky, 0 to 10 percent slopes | 92.7 | 2.2% |
| GeD | Goldrun-Cheebe complex, 0 to 10 percent slopes | 150.2 | 3.5% |
| HdC | Hiko Peak stony sandy loam, 4 to 8 percent slopes | 642.3 | 15.0% |
| LaC | Linoyer very fine sandy loam, 2 to 5 percent slopes | 557.2 | 13.0% |
| MfA | Medburn fine sandy loam, 0 to 2 percent slopes | 0.6 | 0.0% |
| MfB | Medburn fine sandy loam, 2 to 4 percent slopes | 0.9 | 0.0% |
| SfC | Shabliss very fine sandy loam, 2 to 5 percent slopes | 295.5 | 6.9% |
| Subtotals for Soil Survey Area | | 4,279.4 | 99.9% |
| Totals for Area of Interest | | 4,285.8 | 100.0% |

| Tooele Area, Utah - Tooele County and Parts of Box Elder, Davis and Juab Counties (UT611) | | | |
|---|--|----------------|----------------|
| Map Unit Symbol | Map Unit Name | Acres in AOI | Percent of AOI |
| 4 | Amtoft-Rock outcrop complex, 30 to 70 percent slopes | 6.4 | 0.1% |
| Subtotals for Soil Survey Area | | 6.4 | 0.1% |
| Totals for Area of Interest | | 4,285.8 | 100.0% |

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

Custom Soil Resource Report

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

Custom Soil Resource Report

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Fairfield-Nephi Area, Utah

AcF—Amtoft-Rock outcrop complex, 30 to 70 percent slopes

Map Unit Setting

National map unit symbol: j60t
Elevation: 4,900 to 6,200 feet
Mean annual precipitation: 8 to 14 inches
Mean annual air temperature: 45 to 51 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Not prime farmland

Map Unit Composition

Amtoft and similar soils: 55 percent
Rock outcrop: 25 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Amtoft

Setting

Landform: Ridges, hills
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Interfluve, crest, side slope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Colluvium derived from sedimentary rock and/or residuum weathered from sedimentary rock

Typical profile

A11 - 0 to 3 inches: stony loam
A12 - 3 to 5 inches: gravelly loam
C1ca - 5 to 14 inches: very cobbly loam
C2ca - 14 to 19 inches: very gravelly fine sandy loam
R - 19 to 23 inches: unweathered bedrock

Properties and qualities

Slope: 30 to 70 percent
Percent of area covered with surface fragments: 13.0 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock
Natural drainage class: Somewhat excessively drained
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately high (0.00 to 0.60 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 80 percent
Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Available water storage in profile: Very low (about 2.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: D
Ecological site: Semidesert Shallow Loam (Black Sagebrush) (R028AY236UT)

Description of Rock Outcrop

Setting

Landform: Ridges, escarpments

Landform position (two-dimensional): Summit

Landform position (three-dimensional): Interfluve, crest

Down-slope shape: Convex, linear

Across-slope shape: Convex, linear

Minor Components

Saxby

Percent of map unit: 10 percent

Amtoft

Percent of map unit: 5 percent

Hiko peak

Percent of map unit: 5 percent

Ce—Cheebe fine sandy loam

Map Unit Setting

National map unit symbol: j61v

Elevation: 4,800 to 4,850 feet

Mean annual precipitation: 8 to 12 inches

Mean annual air temperature: 45 to 52 degrees F

Frost-free period: 100 to 140 days

Farmland classification: Not prime farmland

Map Unit Composition

Cheebe and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Cheebe

Setting

Landform: Lake terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Lake sediment derived from limestone, sandstone & shale

Typical profile

A11 - 0 to 8 inches: fine sandy loam

B1 - 8 to 15 inches: silty clay

B21t - 15 to 20 inches: silty clay

B22t - 20 to 31 inches: silty clay

B3ca - 31 to 44 inches: silty clay

Custom Soil Resource Report

C1ca - 44 to 55 inches: silty clay loam

C2 - 55 to 65 inches: clay

Properties and qualities

Slope: 0 to 1 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 55 percent

Gypsum, maximum in profile: 2 percent

Salinity, maximum in profile: Moderately saline to strongly saline (8.0 to 16.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 40.0

Available water storage in profile: Moderate (about 8.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: C

Ecological site: Semidesert Loam (Wyoming Big Sagebrush) (R028AY220UT)

Minor Components

Harding

Percent of map unit: 5 percent

Goldrun

Percent of map unit: 5 percent

Woodrow

Percent of map unit: 5 percent

Cheebe

Percent of map unit: 5 percent

Cf—Cheebe silty clay loam

Map Unit Setting

National map unit symbol: j61w

Elevation: 4,800 to 4,850 feet

Mean annual precipitation: 8 to 12 inches

Mean annual air temperature: 45 to 52 degrees F

Frost-free period: 100 to 140 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Cheebe and similar soils: 80 percent

Minor components: 20 percent

Custom Soil Resource Report

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Cheebe

Setting

Landform: Lake terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Lake sediment derived from limestone, sandstone & shale

Typical profile

A11 - 0 to 2 inches: silty clay loam

A12 - 2 to 4 inches: silty clay loam

A13 - 4 to 8 inches: silty clay loam

B1 - 8 to 15 inches: silty clay

B21t - 15 to 20 inches: silty clay

B22t - 20 to 31 inches: silty clay

B3ca - 31 to 44 inches: silty clay

C1ca - 44 to 55 inches: silty clay loam

C2 - 55 to 65 inches: clay

Properties and qualities

Slope: 0 to 1 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 55 percent

Gypsum, maximum in profile: 2 percent

Salinity, maximum in profile: Moderately saline to strongly saline (8.0 to 16.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 40.0

Available water storage in profile: Moderate (about 8.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: C

Ecological site: Alkali Flat (Black Greasewood) (R028AY004UT)

Minor Components

Goldrun

Percent of map unit: 5 percent

Woodrow

Percent of map unit: 5 percent

Cheebe

Percent of map unit: 5 percent

Harding

Percent of map unit: 5 percent

GaBP—Genola fine sandy loam, hummocky, 1 to 2 percent slopes

Map Unit Setting

National map unit symbol: j62p
Elevation: 4,500 to 5,700 feet
Mean annual precipitation: 10 to 14 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Genola and similar soils: 75 percent
Minor components: 25 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Genola

Setting

Landform: Flood plains, alluvial fans
Landform position (three-dimensional): Talf, dip
Down-slope shape: Linear, concave
Across-slope shape: Concave, convex
Parent material: Alluvium derived from limestone and sandstone and/or alluvium derived from igneous rock

Typical profile

A11 - 0 to 1 inches: fine sandy loam
A12 - 1 to 6 inches: fine sandy loam
C1 - 6 to 15 inches: silt loam
C2 - 15 to 29 inches: silt loam
C3 - 29 to 42 inches: silt loam
C4 - 42 to 60 inches: silt loam

Properties and qualities

Slope: 1 to 2 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 40 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: High (about 9.8 inches)

Interpretive groups

Land capability classification (irrigated): 2e
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: C

Custom Soil Resource Report

Ecological site: Semidesert Loam (Wyoming Big Sagebrush) (R028AY220UT)

Minor Components

Genola

Percent of map unit: 10 percent

Linoyer

Percent of map unit: 10 percent

Medburn

Percent of map unit: 5 percent

GbA—Genola silt loam, 0 to 1 percent slopes

Map Unit Setting

National map unit symbol: j62q

Elevation: 4,500 to 5,700 feet

Mean annual precipitation: 10 to 14 inches

Mean annual air temperature: 45 to 52 degrees F

Frost-free period: 100 to 140 days

Farmland classification: Prime farmland if irrigated

Map Unit Composition

Genola and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Genola

Setting

Landform: Flood plains, alluvial fans

Landform position (three-dimensional): Dip, talf

Down-slope shape: Linear, concave

Across-slope shape: Concave, convex

Parent material: Alluvium derived from limestone and sandstone and/or alluvium derived from igneous rock

Typical profile

A11 - 0 to 1 inches: silt loam

A12 - 1 to 6 inches: silt loam

C1 - 6 to 15 inches: silt loam

C2 - 15 to 29 inches: silt loam

C3 - 29 to 42 inches: silt loam

C4 - 42 to 60 inches: silt loam

Properties and qualities

Slope: 0 to 1 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)

Custom Soil Resource Report

Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 40 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: High (about 10.2 inches)

Interpretive groups

Land capability classification (irrigated): 2c
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: C
Ecological site: Semidesert Loam (Wyoming Big Sagebrush) (R028AY220UT)

Minor Components

Linoyer

Percent of map unit: 10 percent

Medburn

Percent of map unit: 5 percent

Genola

Percent of map unit: 5 percent

GbB—Genola silt loam, 1 to 2 percent slopes

Map Unit Setting

National map unit symbol: j62r
Elevation: 4,500 to 5,700 feet
Mean annual precipitation: 10 to 14 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Genola and similar soils: 75 percent
Minor components: 25 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Genola

Setting

Landform: Flood plains, alluvial fans
Landform position (three-dimensional): Talf, dip
Down-slope shape: Linear, concave
Across-slope shape: Concave, convex
Parent material: Alluvium derived from igneous rock and/or alluvium derived from limestone and sandstone

Typical profile

A11 - 0 to 1 inches: silt loam
A12 - 1 to 6 inches: silt loam

Custom Soil Resource Report

C1 - 6 to 15 inches: silt loam
C2 - 15 to 29 inches: silt loam
C3 - 29 to 42 inches: silt loam
C4 - 42 to 60 inches: silt loam

Properties and qualities

Slope: 1 to 2 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 40 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: High (about 10.2 inches)

Interpretive groups

Land capability classification (irrigated): 2e
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: C
Ecological site: Semidesert Loam (Wyoming Big Sagebrush) (R028AY220UT)

Minor Components

Linoyer

Percent of map unit: 10 percent

Medburn

Percent of map unit: 5 percent

Genola

Percent of map unit: 5 percent

Genola

Percent of map unit: 5 percent

GdDP—Goldrun loamy fine sand, hummocky, 0 to 10 percent slopes

Map Unit Setting

National map unit symbol: j62x
Elevation: 4,500 to 5,500 feet
Mean annual precipitation: 8 to 12 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Not prime farmland

Map Unit Composition

Goldrun and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Custom Soil Resource Report

Description of Goldrun

Setting

Landform: Lake terraces, alluvial fans

Landform position (three-dimensional): Tread

Down-slope shape: Linear, concave

Across-slope shape: Linear, convex

Parent material: Sand & alluvium derived from sandstone & igneous rocks

Typical profile

A11 - 0 to 2 inches: loamy fine sand

C1 - 2 to 11 inches: loamy fine sand

C2 - 11 to 26 inches: fine sand

C3 - 26 to 48 inches: fine sand

C4 - 48 to 60 inches: loamy fine sand

Properties and qualities

Slope: 0 to 10 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): High to very high (6.00 to 20.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 30 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: Low (about 4.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A

Ecological site: Semidesert Sand (Four-Wing Saltbush) (R028AF222UT)

Minor Components

Linoyer

Percent of map unit: 10 percent

Medburn

Percent of map unit: 5 percent

GeD—Goldrun-Cheebe complex, 0 to 10 percent slopes

Map Unit Setting

National map unit symbol: j62y

Elevation: 4,500 to 5,500 feet

Mean annual precipitation: 8 to 12 inches

Mean annual air temperature: 45 to 52 degrees F

Frost-free period: 100 to 140 days

Custom Soil Resource Report

Farmland classification: Not prime farmland

Map Unit Composition

Goldrun and similar soils: 50 percent

Cheebe and similar soils: 30 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Goldrun

Setting

Landform: Lake terraces, alluvial fans

Landform position (three-dimensional): Tread

Down-slope shape: Linear, concave

Across-slope shape: Linear, convex

Parent material: Sand & alluvium derived from sandstone & igneous rocks

Typical profile

A1 - 0 to 2 inches: loamy fine sand

C1 - 2 to 11 inches: loamy fine sand

C2 - 11 to 26 inches: fine sand

C3 - 26 to 48 inches: fine sand

C4 - 48 to 60 inches: loamy fine sand

Properties and qualities

Slope: 0 to 10 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Somewhat excessively drained

Capacity of the most limiting layer to transmit water (Ksat): High to very high (6.00 to 20.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 30 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: Low (about 4.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A

Ecological site: Semidesert Sand (Four-Wing Saltbush) (R028AF222UT)

Description of Cheebe

Setting

Landform: Lake terraces, alluvial fans

Landform position (three-dimensional): Tread

Down-slope shape: Linear, concave

Across-slope shape: Linear, convex

Parent material: Lacustrine deposits derived from limestone, sandstone, and shale

Typical profile

A11 - 0 to 2 inches: silty clay loam

A12 - 2 to 4 inches: silty clay loam

A13 - 4 to 8 inches: silty clay loam

B1 - 8 to 15 inches: silty clay

Custom Soil Resource Report

B21t - 15 to 20 inches: silty clay
B22t - 20 to 31 inches: silty clay
B3ca - 31 to 44 inches: silty clay
C1ca - 44 to 55 inches: silty clay loam
C2 - 55 to 65 inches: clay

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 55 percent
Gypsum, maximum in profile: 2 percent
Salinity, maximum in profile: Moderately saline to strongly saline (8.0 to 16.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 40.0
Available water storage in profile: Moderate (about 8.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: C
Ecological site: Alkali Flat (Black Greasewood) (R028AY004UT)

Minor Components

Linoyer

Percent of map unit: 10 percent

Genola

Percent of map unit: 5 percent

Medburn

Percent of map unit: 5 percent

HdC—Hiko Peak stony sandy loam, 4 to 8 percent slopes

Map Unit Setting

National map unit symbol: j635
Elevation: 4,800 to 5,800 feet
Mean annual precipitation: 8 to 12 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Not prime farmland

Map Unit Composition

Hiko peak and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hiko Peak

Setting

Landform: Alluvial fans

Down-slope shape: Concave

Across-slope shape: Convex

Parent material: Alluvium derived from limestone and sandstone and/or alluvium derived from quartzite

Typical profile

A11 - 0 to 3 inches: stony sandy loam

A12 - 3 to 7 inches: stony sandy loam

B2 - 7 to 19 inches: gravelly sandy loam

C1ca - 19 to 28 inches: very gravelly sandy loam

C2ca - 28 to 37 inches: very gravelly sandy loam

C3ca - 37 to 44 inches: very gravelly sandy loam

C4 - 44 to 60 inches: extremely gravelly sandy loam

Properties and qualities

Slope: 4 to 8 percent

Percent of area covered with surface fragments: 11.0 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 40 percent

Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 13.0

Available water storage in profile: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A

Ecological site: Semidesert Gravelly Loam (Wyoming Big Sagebrush) North (R028AY215UT)

Minor Components

Hiko peak

Percent of map unit: 5 percent

Spager

Percent of map unit: 5 percent

Medburn

Percent of map unit: 5 percent

Sanpete

Percent of map unit: 5 percent

LaC—Linoyer very fine sandy loam, 2 to 5 percent slopes

Map Unit Setting

National map unit symbol: 2smc4
Elevation: 4,490 to 5,740 feet
Mean annual precipitation: 8 to 12 inches
Mean annual air temperature: 45 to 51 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Linoyer and similar soils: 85 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Linoyer

Setting

Landform: Lake plains, lake terraces, alluvial fans
Landform position (three-dimensional): Tread, rise
Down-slope shape: Linear, concave
Across-slope shape: Linear, convex
Parent material: Alluvium and/or lacustrine deposits

Typical profile

A1 - 0 to 9 inches: very fine sandy loam
A2 - 9 to 15 inches: very fine sandy loam
C1 - 15 to 48 inches: very fine sandy loam
C2 - 48 to 60 inches: very fine sandy loam

Properties and qualities

Slope: 2 to 5 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 40 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 5.0
Available water storage in profile: High (about 9.9 inches)

Interpretive groups

Land capability classification (irrigated): 3e
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: B
Ecological site: Semidesert Sandy Loam (Wyoming Big Sagebrush)
(R028AY226UT)

MfA—Medburn fine sandy loam, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: j647
Elevation: 4,500 to 5,300 feet
Mean annual precipitation: 10 to 12 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Prime farmland if irrigated

Map Unit Composition

Medburn and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Medburn

Setting

Landform: Alluvial fans
Down-slope shape: Concave
Across-slope shape: Convex
Parent material: Alluvium derived from sandstone and/or alluvium derived from igneous rock

Typical profile

A11 - 0 to 4 inches: fine sandy loam
A12 - 4 to 8 inches: fine sandy loam
C1 - 8 to 15 inches: fine sandy loam
C2 - 15 to 24 inches: fine sandy loam
C3 - 24 to 32 inches: fine sandy loam
C4 - 32 to 41 inches: gravelly sandy loam
C5 - 41 to 60 inches: fine sandy loam

Properties and qualities

Slope: 0 to 2 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 15 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water storage in profile: Moderate (about 6.4 inches)

Interpretive groups

Land capability classification (irrigated): 2s
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: A
Ecological site: Semidesert Sandy Loam (Wyoming Big Sagebrush)
(R028AY226UT)

Minor Components

Hiko peak

Percent of map unit: 5 percent

Linoyer

Percent of map unit: 5 percent

Medburn

Percent of map unit: 5 percent

MfB—Medburn fine sandy loam, 2 to 4 percent slopes

Map Unit Setting

*National map unit symbol: j648
Elevation: 4,500 to 5,300 feet
Mean annual precipitation: 10 to 12 inches
Mean annual air temperature: 45 to 52 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Prime farmland if irrigated*

Map Unit Composition

*Medburn and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.*

Description of Medburn

Setting

*Landform: Alluvial fans
Down-slope shape: Concave
Across-slope shape: Convex
Parent material: Alluvium derived from sandstone and/or alluvium derived from igneous rock*

Typical profile

*A11 - 0 to 4 inches: fine sandy loam
A12 - 4 to 8 inches: fine sandy loam
C1 - 8 to 15 inches: fine sandy loam
C2 - 15 to 24 inches: fine sandy loam
C3 - 24 to 32 inches: fine sandy loam
C4 - 32 to 41 inches: gravelly sandy loam
C5 - 41 to 60 inches: fine sandy loam*

Properties and qualities

*Slope: 2 to 4 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None*

Custom Soil Resource Report

Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: Moderate (about 6.4 inches)

Interpretive groups

Land capability classification (irrigated): 2e

Land capability classification (nonirrigated): 6s

Hydrologic Soil Group: A

Ecological site: Semidesert Sandy Loam (Wyoming Big Sagebrush)
(R028AY226UT)

Minor Components

Hiko peak

Percent of map unit: 5 percent

Linoyer

Percent of map unit: 5 percent

Medburn

Percent of map unit: 5 percent

SfC—Shabliss very fine sandy loam, 2 to 5 percent slopes

Map Unit Setting

National map unit symbol: j665

Elevation: 4,700 to 6,000 feet

Mean annual precipitation: 8 to 14 inches

Mean annual air temperature: 45 to 52 degrees F

Frost-free period: 100 to 140 days

Farmland classification: Not prime farmland

Map Unit Composition

Shabliss and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Shabliss

Setting

Landform: Lake terraces, alluvial fans

Landform position (three-dimensional): Tread

Down-slope shape: Linear, concave

Across-slope shape: Linear, convex

Parent material: Alluvium and lake sediment derived dominantly from sedimentary and igneous rocks

Typical profile

A1 - 0 to 4 inches: very fine sandy loam

B1 - 4 to 9 inches: very fine sandy loam

B2 - 9 to 15 inches: very fine sandy loam

Custom Soil Resource Report

C1sica - 15 to 26 inches: cemented

C2sica - 26 to 40 inches: cemented

C3ca - 40 to 60 inches: loam

Properties and qualities

Slope: 2 to 5 percent

Depth to restrictive feature: 10 to 20 inches to duripan

Natural drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 60 percent

Salinity, maximum in profile: Slightly saline to moderately saline (4.0 to 8.0 mmhos/cm)

Available water storage in profile: Very low (about 2.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: D

Ecological site: Semidesert Shallow Hardpan (Black Sagebrush) (R028AY230UT)

Minor Components

Shabliss

Percent of map unit: 5 percent

Medburn

Percent of map unit: 4 percent

Truesdale

Percent of map unit: 3 percent

Spager

Percent of map unit: 3 percent

Tooele Area, Utah - Tooele County and Parts of Box Elder, Davis and Juab Counties

4—Amtoft-Rock outcrop complex, 30 to 70 percent slopes

Map Unit Setting

National map unit symbol: j5q2
Elevation: 5,500 to 7,000 feet
Mean annual precipitation: 10 to 12 inches
Mean annual air temperature: 45 to 48 degrees F
Frost-free period: 100 to 140 days
Farmland classification: Not prime farmland

Map Unit Composition

Amtoft and similar soils: 65 percent
Rock outcrop: 15 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Amtoft

Setting

Landform: Mountainsides, hillsides
Landform position (three-dimensional): Mountainflank, side slope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Colluvium derived from limestone and/or residuum weathered from limestone

Typical profile

A,Bw - 0 to 9 inches: very cobbly loam
Bk - 9 to 16 inches: extremely cobbly loam
R - 16 to 26 inches: bedrock

Properties and qualities

Slope: 30 to 70 percent
Percent of area covered with surface fragments: 2.0 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock
Natural drainage class: Somewhat excessively drained
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately high (0.00 to 0.57 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 80 percent
Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Available water storage in profile: Very low (about 1.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7e
Hydrologic Soil Group: D
Ecological site: Semidesert Shallow Loam (Utah Juniper-Bluebunch Wheatgrass)
(R028AY238UT)

Description of Rock Outcrop

Setting

Landform: Hillsides, mountainsides

Landform position (three-dimensional): Mountainflank, side slope

Down-slope shape: Convex

Across-slope shape: Convex

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8s

Minor Components

Lundy

Percent of map unit: 4 percent

Lodar

Percent of map unit: 4 percent

Cliffdown

Percent of map unit: 3 percent

Spager

Percent of map unit: 3 percent

Hiko peak

Percent of map unit: 3 percent

Checkett

Percent of map unit: 3 percent

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf



NOAA Atlas 14, Volume 1, Version 5
Location name: Cedar Valley, Utah, US*
Latitude: 40.2165°, Longitude: -112.1232°
Elevation: 5057 ft*
 * source: Google Maps



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sarah Dietz, Sarah Heim, Lillian Hiner, Kazungu Maitaria, Deborah Martin, Sandra Pavlovic, Ishani Roy, Carl Trypanuk, Dale Unruh, Fenglin Yan, Michael Yekta, Tan Zhao, Geoffrey Bonnin, Daniel Brewer, Li-Chuan Chen, Tye Parzybok, John Yarchoan

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aeriels](#)

PF tabular





| PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹ | | | | | | | | | | |
|--|--|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|------------------------------|
| Duration | Average recurrence interval (years) | | | | | | | | | |
| | 1 | 2 | 5 | 10 | 25 | 50 | 100 | 200 | 500 | 1000 |
| 5-min | 0.115 (0.098-0.137) | 0.147 (0.127-0.175) | 0.205 (0.175-0.244) | 0.256 (0.215-0.307) | 0.334 (0.276-0.403) | 0.406 (0.328-0.492) | 0.488 (0.385-0.594) | 0.584 (0.446-0.720) | 0.734 (0.536-0.919) | 0.867 (0.610-1.10) |
| 10-min | 0.175 (0.150-0.209) | 0.224 (0.193-0.267) | 0.312 (0.266-0.372) | 0.389 (0.328-0.468) | 0.508 (0.420-0.613) | 0.618 (0.499-0.749) | 0.743 (0.586-0.904) | 0.889 (0.679-1.10) | 1.12 (0.817-1.40) | 1.32 (0.929-1.67) |
| 15-min | 0.217 (0.186-0.259) | 0.277 (0.239-0.330) | 0.387 (0.330-0.462) | 0.483 (0.406-0.580) | 0.630 (0.521-0.760) | 0.766 (0.619-0.928) | 0.921 (0.726-1.12) | 1.10 (0.841-1.36) | 1.39 (1.01-1.73) | 1.64 (1.15-2.07) |
| 30-min | 0.293 (0.250-0.349) | 0.373 (0.322-0.445) | 0.521 (0.444-0.622) | 0.650 (0.547-0.781) | 0.849 (0.702-1.02) | 1.03 (0.834-1.25) | 1.24 (0.978-1.51) | 1.48 (1.13-1.83) | 1.86 (1.36-2.33) | 2.20 (1.55-2.79) |
| 60-min | 0.363 (0.310-0.432) | 0.462 (0.399-0.550) | 0.645 (0.550-0.769) | 0.804 (0.677-0.967) | 1.05 (0.869-1.27) | 1.28 (1.03-1.55) | 1.53 (1.21-1.87) | 1.84 (1.40-2.26) | 2.31 (1.69-2.89) | 2.73 (1.92-3.46) |
| 2-hr | 0.448 (0.397-0.516) | 0.564 (0.498-0.655) | 0.739 (0.650-0.858) | 0.905 (0.787-1.05) | 1.16 (0.988-1.35) | 1.39 (1.16-1.63) | 1.66 (1.35-1.96) | 1.97 (1.55-2.35) | 2.45 (1.84-2.98) | 2.89 (2.09-3.57) |
| 3-hr | 0.501 (0.451-0.571) | 0.625 (0.560-0.709) | 0.804 (0.715-0.910) | 0.958 (0.846-1.09) | 1.20 (1.05-1.37) | 1.42 (1.21-1.64) | 1.69 (1.41-1.98) | 1.99 (1.62-2.38) | 2.47 (1.93-3.00) | 2.90 (2.19-3.61) |
| 6-hr | 0.640 (0.588-0.710) | 0.792 (0.723-0.875) | 0.971 (0.880-1.08) | 1.13 (1.02-1.25) | 1.35 (1.21-1.51) | 1.54 (1.36-1.72) | 1.79 (1.55-2.02) | 2.08 (1.77-2.40) | 2.56 (2.12-3.04) | 2.98 (2.41-3.64) |
| 12-hr | 0.791 (0.728-0.871) | 0.973 (0.893-1.07) | 1.18 (1.08-1.30) | 1.35 (1.23-1.49) | 1.59 (1.44-1.75) | 1.77 (1.58-1.97) | 1.97 (1.74-2.20) | 2.24 (1.95-2.54) | 2.68 (2.28-3.08) | 3.05 (2.54-3.68) |
| 24-hr | 0.942 (0.870-1.02) | 1.16 (1.07-1.26) | 1.39 (1.28-1.50) | 1.58 (1.45-1.71) | 1.83 (1.68-1.98) | 2.02 (1.84-2.19) | 2.21 (2.01-2.40) | 2.41 (2.18-2.61) | 2.71 (2.39-3.11) | 3.08 (2.55-3.72) |
| 2-day | 1.06 (0.975-1.15) | 1.30 (1.19-1.41) | 1.56 (1.44-1.70) | 1.77 (1.63-1.93) | 2.07 (1.90-2.24) | 2.30 (2.10-2.49) | 2.53 (2.31-2.75) | 2.77 (2.50-3.01) | 3.09 (2.77-3.37) | 3.33 (2.96-3.75) |
| 3-day | 1.16 (1.06-1.27) | 1.42 (1.30-1.56) | 1.71 (1.57-1.88) | 1.96 (1.80-2.14) | 2.30 (2.10-2.51) | 2.56 (2.33-2.80) | 2.84 (2.57-3.10) | 3.12 (2.81-3.42) | 3.51 (3.12-3.85) | 3.80 (3.36-4.25) |
| 4-day | 1.26 (1.15-1.39) | 1.54 (1.42-1.70) | 1.87 (1.71-2.06) | 2.14 (1.96-2.35) | 2.53 (2.30-2.77) | 2.83 (2.56-3.11) | 3.15 (2.84-3.46) | 3.47 (3.11-3.82) | 3.92 (3.48-4.33) | 4.28 (3.76-4.75) |
| 7-day | 1.48 (1.36-1.63) | 1.82 (1.67-2.00) | 2.20 (2.02-2.42) | 2.51 (2.30-2.75) | 2.94 (2.68-3.21) | 3.27 (2.97-3.57) | 3.60 (3.26-3.94) | 3.94 (3.55-4.32) | 4.40 (3.93-4.84) | 4.75 (4.21-5.25) |
| 10-day | 1.68 (1.54-1.83) | 2.06 (1.90-2.25) | 2.48 (2.27-2.69) | 2.81 (2.58-3.06) | 3.25 (2.98-3.54) | 3.59 (3.28-3.90) | 3.93 (3.58-4.28) | 4.27 (3.87-4.66) | 4.72 (4.24-5.16) | 5.05 (4.51-5.54) |
| 20-day | 2.20 (2.03-2.39) | 2.71 (2.50-2.95) | 3.23 (2.98-3.51) | 3.63 (3.35-3.94) | 4.15 (3.82-4.51) | 4.53 (4.17-4.92) | 4.91 (4.50-5.34) | 5.27 (4.81-5.75) | 5.73 (5.20-6.26) | 6.06 (5.48-6.64) |
| 30-day | 2.61 (2.40-2.82) | 3.20 (2.96-3.47) | 3.83 (3.53-4.15) | 4.32 (3.98-4.67) | 4.97 (4.57-5.38) | 5.46 (5.00-5.91) | 5.94 (5.43-6.44) | 6.41 (5.83-6.96) | 7.03 (6.35-7.66) | 7.47 (6.72-8.17) |
| 45-day | 3.26 (3.02-3.52) | 4.00 (3.71-4.32) | 4.73 (4.38-5.11) | 5.30 (4.91-5.72) | 6.03 (5.58-6.52) | 6.57 (6.07-7.10) | 7.09 (6.53-7.67) | 7.58 (6.96-8.21) | 8.20 (7.50-8.89) | 8.64 (7.87-9.40) |
| 60-day | 3.84 (3.57-4.12) | 4.71 (4.38-5.06) | 5.57 (5.17-5.97) | 6.22 (5.78-6.66) | 7.05 (6.54-7.55) | 7.65 (7.08-8.19) | 8.22 (7.59-8.81) | 8.76 (8.07-9.40) | 9.43 (8.64-10.1) | 9.89 (9.04-10.7) |

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

PDS-based depth-duration-frequency (DDF) curves
 Latitude: 40.2165°, Longitude: -112.1232°



[Back to Top](#)

Maps & aerials

Small scale terrain





Large scale terrain



Large scale map



Large scale aerial





[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)

Worksheet 3: Time of Concentration (T_c) or Travel Time (T_t)

| | | | | | |
|-----------|------------------|----------|-----|-------|-----------|
| Project: | IRL - Redesign | By: | RJG | Date: | 7/15/2016 |
| Location: | Run-on Hydrology | Checked: | GLJ | Date: | 9/23/2016 |

Check One: Present Developed
 Check One: T_c T_t Through subarea

Notes: Space for as many as two segments per flow type can be used for each worksheet.
 Include a map, schematic, or description of flow segments.

Sheet Flow

| | Segment ID | | | |
|--|------------|---|--|--------|
| 1. Surface Description (table 3-1) | Range | | | |
| 2. Manning's roughness coefficient, n (table 3-1) | 0.13 | | | |
| 3. Flow length, L (total L + 300 ft) | 300 | | | |
| 4. Two-year 24-hour rainfall, P ₂ | 1.16 | | | |
| 5. Land Slope, s | 0.25 | | | |
| 6. $T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5}s^{0.4}}$ Compute T _t | 0.21 | + | | = 0.21 |

Shallow Concentrated Flow

| | Segment ID | | | |
|--|------------|---|--|--------|
| 7. Surface Description (paved or unpaved) | Unpaved | | | |
| 8. Flow Length, L | 960 | | | |
| 9. Watercourse slope, s | 0.10 | | | |
| 10. Average Velocity, V (figure 3-1) | 5 | | | |
| 11. $T_t = \frac{L}{3600V}$ Compute T _t | 0.05 | + | | = 0.05 |

Channel Flow

| | Segment ID | Mtn Chan 1 | Mtn Chan 2 | Fields |
|---|------------|------------|------------|--------|
| 12. Cross section flow area, a | | 2.5 | 2.5 | 50 |
| 13. Wetted Perimeter, p _w | | 6.24 | 6.24 | 101 |
| 14. Hydraulic radius, $r = \frac{a}{p_w}$ Compute r | | 0.40 | 0.40 | 0.495 |
| 15. Channel Slope, s | | 0.07 | 0.04 | 0.01 |
| 16. Manning's roughness coefficient, n | | 0.06 | 0.06 | 0.05 |
| 17. $V = \frac{1.49(r)^{0.8}(s)^{1/2}}{n}$ Compute V | | 3.49 | 2.52 | 1.86 |
| 18. Flow length, L | | 7000 | 7000 | 10000 |
| 19. $T_t = \frac{L}{3600V}$ Compute T _t | | 0.56 | 0.77 | 1.49 |
| | | | | = 2.82 |
| 20. Watershed or subarea T _c or T _t (add T _t in steps 6, 11, and 19) | | | | 3.08 |

APPENDIX G

Erosion Protection

1. Purpose and Procedure.

The purpose of these calculations is determine if erosion protection is needed and if so which measure to use and how to apply it. The closure cap will consist of a 4H:1V slope extending up from the top of the cell embankments. The embankments will consist of a 4H:1V slope from the top of the embankment down to the ground surface. Benches will be constructed in the slopes of the closure cap to intercept precipitation and snow melt runoff from the slopes as needed to control runoff and to minimize erosion.

The procedure used to determine the allowable slope lengths between the bench areas of the closure cap slopes is taken from the publication "Erosion and Sedimentation in Utah - A Guide for Control", Utah Water Research Laboratory, February 1984. This publication is specific to Utah. The figure presented on Sheet 2 presents a cross-section showing the configuration of the area contributing runoff to the slopes of the closure cap. The degree of erosion protection required is based on the steepness and length of the slopes. Erosion protection measures will be determined for the longest slope length and the erosion control measures determined for the longest slope will be conservatively applied to all slopes. According to a 1991 Seminar Publication from the EPA entitled "Design and Construction of RCRA/CERCLA Final Covers", the minimum criteria is a cover soil loss of less than 2 tons/acre/year. This same criteria will be applied to these calculations.


2. The procedure from the above publication uses the Universal Soil Loss Equation (in modified form to represent Utah's climatic and topographic conditions) to estimate the soil erosion potential of the surface soils assuming no application of erosion control measures. Erosion control measures to be implemented are based on the soil erosion potential calculated.

The universal soil loss equation used to calculate soil erosion potential is:

$$A = R * K * LS$$

where;

- A = Computed amount of soil loss per unit area for the time interval represented by factor R, generally in tons per acre per year.
R = Rainfall (precipitation) factor.
K = Soil erodibility factor in tons per acre per year per unit of R.
LS = Topographic factor (length and steepness of slope).



D = Horizontal Distance
V = Vertical Distance
SD = Slope Distance

For 4H:1V Slopes

$$D = 4V$$
$$SD = \sqrt{D^2 + V^2}$$
$$SD = \sqrt{(4^2)(V^2) + V^2}$$
$$SD = \sqrt{17V^2}$$

Calculated erosion after applying erosion control measures is determined by applying an erosion control factor (VM) to the universal soil loss equation. The erosion control factor is dependant upon the type and extent to which the erosion control measure is used (ie. vegetative - type and density, mulches - type and thickness, chemical - type and application amount, mechanical - compactive effort, smoothness of surface, etc.).

- a. The rainfall (precipitation) factor (R) is obtained from mean annual iso-erodent R value maps. The R -value for the facility as obtained from the Tooele area map is:

$$R = 6$$

- b. Soil erodibility factor (K) is determined using the figures on Sheet 6. The gradation of the materials is based on information from AGECE soil testing completed in 2016 (see attached). Samples were taken at the site and in depth hydrometer tests were performed. Information from these two samples were used to determine K.

Parameters obtained from the gradation envelopes of the two samples and parameters assumed for use with the nomographs to determine K are:

North Stockpile

- 53 % silt + very fine sand
- 7 % sand
- 0 % organic material assumed
- slow permeability assumed due to 40% Clay content.

South Stockpile

- 48 % silt + very fine sand
- 10 % sand
- 0 % organic material assumed
- slow permeability assumed due to 42% Clay content.

Applying the above parameters to the nomographs on Sheet 5 gives an average soil erodibility factor (K) equal to 0.265.

- c. The topographic factor (LS) is determined assuming single slopes. The figure on Sheet 2 shows the configuration of the typical slope segment. The closure cap slope is designed at 4H:1V. The LS factor is determined by the following equation:

$$LS = \left(\frac{65.41s^2}{s^2 + 10,000} + \frac{4.56s}{\sqrt{s^2 + 10,000}} + 0.065 \right) \left(\frac{l}{72.6} \right)^m$$

where;

- LS = topographic factor for slope segment n.
l = length of slope segment n.
s = slope gradient of segment n in percent.
m = slope gradient factor, which is:
0.2 for gradients of 0 to 1 percent
0.3 for gradients of 1 to 3 percent
0.4 for gradients of 3.5 to 4.5 percent
0.5 for gradients greater than 5 percent

The following table provides LS factor values for varying lengths of the 4H:1V slopes and potential erosion rates (A) assuming bare soils (without erosion protection measures) where R = 6 and K = 0.265.

| HORIZONTAL DISTANCE ALONG SLOPE (FT) | SLOPE LENGTH (FT) | LS FACTOR | A (tons/ac/yr) |
|--------------------------------------|-------------------|-----------|----------------|
| 50 | 51.539 | 4.228 | 6.72 |
| 100 | 103.078 | 5.980 | 9.51 |
| 150 | 154.617 | 7.324 | 11.64 |
| 200 | 206.155 | 8.457 | 13.45 |
| 250 | 257.694 | 9.455 | 15.03 |
| 300 | 309.233 | 10.358 | 16.47 |
| 350 | 360.772 | 11.187 | 17.79 |
| 400 | 412.311 | 11.960 | 19.02 |

A check on the top of the closed landfill was also performed over the full length of the landfill where the slope is set at 2.0%.

Horizontal Length = 1,710
l = 1,763 ft
LS = 0.47
A = 0.75 tons/ac/yr

While the top of the landfill on the 2% slope shows that it does not require additional erosion protection, the side slopes indicate that additional protection is required. The results also show that it would be unreasonable to create enough benching to alleviate erosion without additional protection.

In order to minimize erosion control protection required on the 4H:1V side slope of the final cover a berm was designed along the east side of the top (2% slope) of the landfill closure to capture the runoff.

- d. Potential erosion rates applying a range of VM where R = 6, K = 0.265, and LS as tabulated above are presented in the table below:

| Horizontal Distance Along Slope (ft) | Slope Length (ft) | A (2 yr storm) (tons/ac/yr) | | |
|--------------------------------------|-------------------|-----------------------------|-------|------|
| | | VM = | | |
| | | 0.1 | 0.133 | 0.15 |
| 50 | 51.54 | 0.67 | 0.89 | 1.01 |
| 100 | 103.08 | 0.95 | 1.26 | 1.43 |
| 150 | 154.62 | 1.16 | 1.55 | 1.75 |
| 200 | 206.16 | 1.34 | 1.79 | 2.02 |
| 250 | 257.69 | 1.50 | 2.00 | 2.26 |
| 300 | 309.23 | 1.65 | 2.19 | 2.47 |
| 350 | 360.77 | 1.78 | 2.37 | 2.67 |
| 400 | 412.31 | 1.90 | 2.53 | 2.85 |

Based on this table the landfill was designed with a single bench that will limit the

maximum flow length (horizontal distance) along the 4H:1V slope to 265 ft. This will also require a grass ground cover (pulled from figure on Sheet 7) with coverage as defined below:

- between 29% (25% canopy of tall weeds) and 32% (0% canopy of tall weeds).

If it is determined that vegetation as described above will not subsist in the natural environment an equivalent alternative erosion protection measure may be applied.




Figure 2-2. Nomograph for determining soil erodibility factor K.

6%
 8% organic Material
 50% silt & fine Sand

- $K = 0.28$ North Stockpile
 - $K = 0.25$ South Stockpile

Average
 $K = 0.265$




Figure 2-8. Relationship between grass density and VM factor.





Figure 2-9. Relationship between forb density and VM factor.

APPLIED GEOTECHNICAL ENGINEERING CONSULTANTS, Inc.
Moisture - Density Relationship, Gradation, & Classification Results



SAMPLE IDENTIFICATION

Project Name: Intermountain Regional Landfill
Project No. 1150743
Sample No. 14190
Sample Location: South Stockpile

Date Sampled: 05/06/16
Sampled By: client

TESTING INFORMATION

Date Tested: 05/07/16
Tested By: RN
Reviewed By: KBB
Test Procedure: ASTM D1557 A
Specific Gravity: Assumed 2.6
Moisture Curing: 16+ hours

ATTERBERG DATA

Plasticity Determined by ASTM D 2488

PROCTOR RESULTS

Maximum Dry Density 100.3 pcf
Optimum Moisture 22.6%
Final Based On Microwave Oven Moisture Contents

VISUAL-MANUAL DESCRIPTION (ASTM D2488)

Lean Clay (CL)

GRADATION RESULTS

| Sieve Designation | Sieve Opening Size (mm) | Percent Passing (%) | Project Specification (%) |
|------------------------|-------------------------|---------------------|---------------------------|
| 5" | 127 | 100 | - |
| 3" | 76.2 | 100 | - |
| 1 1/2" | 38.1 | 100 | - |
| 3/4" | 19.1 | 100 | - |
| 3/8" | 9.52 | 100 | - |
| #4 | 4.76 | 100 | - |
| #10 | 2 | 100 | - |
| #16 | 1.19 | 100 | - |
| #40 | 0.42 | 99 | - |
| #50 | 0.297 | 99 | - |
| #100 | 0.149 | 97 | - |
| #200 | 0.074 | 86 | - |
| GRAVEL | | | |
| 0% | | | |
| SAND | | | |
| 14% | | | |
| SILT & CLAY | | | |
| 86% | | | |

Applied Geotechnical Engineering Consultants, Inc.
SIEVE/HYDROMETER WORKSHEET

Project No. 1150743 Project Name Intermountain Regional Landfill Tested By JG Test Date 5/9/2016
Sample South Stockpile (14190)

| Block A: Material Prior to Break On #10 Sieve | |
|---|--------|
| Dish Name: | PNK |
| Air-Dry Material & Dish Wt: | 331.73 |
| Dish Wt: | 163.2 |
| Air-Dry Material Wt: | 168.53 |

| Block B: Post Wash, Oven-Dried Material Retained On #10 Sieve | |
|---|--------|
| Dish Name: | MEN |
| Post-Wash Oven-Dried + #10 Material & Dish Wt: | 177.3 |
| Dish Wt: | 177.19 |
| Post-Wash, Oven-Dried + #10 Material Wt: | 0.11 |

| Block C: Post Wash, Oven Dried, Retained On #200 Sieve | |
|--|--------|
| Dish Name: | YOLO |
| Post-Wash Oven-Dried + #200 Material & Dish Wt: | 281.85 |
| Dish Wt: | 274.69 |
| Post-Wash, Oven Dried + #200 Material Wt: | 7.16 |

| Block D: | |
|--|------|
| Cum Wt in Pan After Shake of + #10 Material: | 0.07 |

| Block E: | |
|---|------|
| Cum Wt in Pan After Shake of + #200 Material: | 7.12 |

Plus #10

* Sample broken on No. 10 Sieve

| Sieve Size | BLOCK H | |
|------------|-------------------|-----------|
| | Cum. Wt. Retained | % Passing |
| 5" | 0.00 | 100 |
| 3" | 0.00 | 100 |
| 1-1/2" | 0.00 | 100 |
| 3/4" | 0.00 | 100 |
| 3/8" | 0.00 | 100 |
| No. 4* | 0.00 | 100 |
| No. 10* | 0.07 | 100 |

Total Air-Dry Sample Weight, Prior to Break Over #10 Sieve: 168.53

Sample Weights

| | Air-Dry | Oven-Dry |
|-------------------------------------|---------|----------|
| Total Sample | | 168.39 |
| Post-Wash, Oven-Dried, Retained #10 | | 0.07 |
| Passing #10* | 168.46 | 168.32 |

* Sample broken on No. 10 Sieve

Minus #10 / Plus #200

| Sieve Size | BLOCK I | |
|------------|-------------------|-----------|
| | Cum. Wt. Retained | % Passing |
| No. 16 | 0.06 | 100 |
| No. 40 | 0.36 | 99 |
| No. 50 | 0.57 | 99 |
| No. 100 | 1.46 | 97 |
| No. 200 | 6.66 | 86 |

Air-Dried Wt. of -#10 Soil** 51.13
Oven-Dried Wt. of -#10 Soil 47.15

** Soil Used for Hydrometer Test

| BLOCK F: Moisture Content of -#10 Material | |
|--|-------|
| Dish Name: | QBA |
| Dish and Air-Dried -#10 Soil Wt.: | 27.17 |
| Dish and Oven-Dried -#10 Soil Wt.: | 26.10 |
| Dish Wt.: | 13.42 |
| Moisture of Air-Dried -#10 Soil (%) | 8.44% |

* Sample broken on No. 10 Sieve

HYDROMETER

| | |
|------------|-------|
| Cylinder # | 3 |
| Area | 28.08 |

| | |
|------------------|------|
| Specific Gravity | 2.60 |
| Meniscus Corr. | 1 |


| BLOCK G | |
|---------------------------------------|-------|
| Air-Dried Wt of -#10 Soil** | 51.13 |
| Hydroscopic Corrected Wt of -#10 Soil | 47.17 |

** Soil Used for Hydrometer Test

| Time (minutes) | Hydrometer Reading* | Temperature °C | Standard Reading* | Corrected Reading | Percent Finer | Meniscus Corrected | L (cm) (from Table) | K (from Table) | Diameter (mm) |
|----------------|---------------------|----------------|-------------------|-------------------|---------------|--------------------|---------------------|----------------|---------------|
| 2 | 38 | 22.8 | 7 | 31 | 66 | 39 | 9.9 | 0.01353 | 0.030 |
| 5 | 36 | 22.8 | 7 | 29 | 62 | 37 | 10.2 | 0.01353 | 0.019 |
| 15 | 34 | 22.8 | 7 | 27 | 58 | 35 | 10.6 | 0.01353 | 0.011 |
| 30 | 33 | 22.8 | 7 | 26 | 56 | 34 | 10.7 | 0.01353 | 0.008 |
| 60 | 32 | 22.8 | 7 | 25 | 54 | 33 | 10.9 | 0.01353 | 0.006 |
| 250 | 29 | 21.7 | 7 | 22 | 47 | 30 | 11.4 | 0.01369 | 0.003 |
| 1440 | 23 | 21.8 | 7 | 16 | 34 | 24 | 12.4 | 0.01369 | 0.001 |


* All Readings made to TOP of meniscus

GRAPH



*10% Sand
27% fine sand
21% silt
42% clay*

APPLIED GEOTECHNICAL ENGINEERING CONSULTANTS, Inc.
Moisture - Density Relationship, Gradation, & Classification Results



SAMPLE IDENTIFICATION

Project Name: Intermountain Regional Landfill

Project No. 1150743
Sample No. 14189
Sample Location: North Stockpile

Date Sampled: 05/06/16
Sampled By: client

TESTING INFORMATION

Date Tested: 05/07/16
Tested By: RN
Reviewed By: KBB
Test Procedure: ASTM D1557 A
Specific Gravity: Not Used
Moisture Curing: 16+ hours

ATTERBERG DATA

Plasticity Determined by ASTM D 2488

PROCTOR RESULTS

Maximum Dry Density 101.9 pcf
Optimum Moisture 20.3%
Final Based On Microwave Oven Moisture Contents

VISUAL-MANUAL DESCRIPTION (ASTM D2488)

Lean Clay (CL)

GRADATION RESULTS

| Sieve Designation | Sieve Opening Size (mm) | Percent Passing (%) | Project Specification (%) |
|-------------------|-------------------------|---------------------|---------------------------|
| 5" | 127 | 100 | - |
| 3" | 76.2 | 100 | - |
| 1 1/2" | 38.1 | 100 | - |
| 3/4" | 19.1 | 100 | - |
| 3/8" | 9.52 | 100 | - |
| #4 | 4.76 | 100 | - |
| #10 | 2 | 100 | - |
| #16 | 1.19 | 100 | - |
| #40 | 0.42 | 99 | - |
| #50 | 0.297 | 99 | - |
| #100 | 0.149 | 98 | - |
| #200 | 0.074 | 88 | - |

| | | |
|--------|------|-------------|
| GRAVEL | SAND | SILT & CLAY |
| 0% | 12% | 88% |

Applied Geotechnical Engineering Consultants, Inc.

SIEVE/HYDROMETER WORKSHEET

Project No. 1150743 Project Name Intermountain Regional Landfill Tested By JG Test Date 5/9/2016
 Sample North Stockpile (14189)

| Block A: Material Prior to Break On #10 Sieve | |
|---|--------|
| Dish Name: | NAP |
| Air-Dry Material & Dish Wt: | 289.95 |
| Dish Wt: | 159.6 |
| Air-Dry Material Wt: | 130.35 |

| Block B: Post Wash, Oven-Dried Material Retained On #10 Sieve | |
|---|---|
| Dish Name: | - |
| Post-Wash Oven-Dried #10 Material & Dish Wt: | 0 |
| Dish Wt: | 0 |
| Post-Wash, Oven-Dried #10 Material Wt: | 0 |

| Block C: Post Wash, Oven Dried, Retained On #200 Sieve | |
|--|--------|
| Dish Name: | BUG |
| Post-Wash Oven-Dried #200 Material & Dish Wt: | 296.2 |
| Dish Wt: | 289.99 |
| Post-Wash, Oven Dried #200 Material Wt: | 6.21 |

| Block D: | |
|--|---|
| Cum Wt in Pan After Shake of #10 Material: | 0 |

| Block E: | |
|---|-----|
| Cum Wt in Pan After Shake of #200 Material: | 6.1 |

Plus #10

* Sample broken on No. 10 Sieve

| Sieve Size | BLOCK H Cum. Wt. Retained | % Passing |
|------------|------------------------------|-----------|
| 5" | 0.00 | 100 |
| 3" | 0.00 | 100 |
| 1-1/2" | 0.00 | 100 |
| 3/4" | 0.00 | 100 |
| 3/8" | 0.00 | 100 |
| No. 4* | 0.00 | 100 |
| No. 10* | 0.00 | 100 |

Total Air-Dry Sample Weight, Prior to Break Over #10 Sieve: 130.35

Sample Weights

| | Air-Dry | Oven-Dry |
|-------------------------------------|---------|----------|
| Total Sample | | 130.24 |
| Post-Wash, Oven-Dried, Retained #10 | | 0.00 |
| Passing #10* | 130.35 | 130.24 |

* Sample broken on No. 10 Sieve

Minus #10 / Plus #200

| Sieve Size | BLOCK I Cum. Wt. Retained | % Passing |
|------------|------------------------------|-----------|
| No. 16 | 0.04 | 100 |
| No. 40 | 0.30 | 99 |
| No. 50 | 0.46 | 99 |
| No. 100 | 1.01 | 98 |
| No. 200 | 5.43 | 88 |

Air-Dried Wt. of #10 Soil** 50.15
 Oven-Dried Wt. of #10 Soil 46.30

**Soil Used for Hydrometer Test

| BLOCK F: Moisture Content of #10 Material | |
|---|-------|
| Dish Name: | BAA |
| Dish and Air-Dried #10 Soil Wt.: | 25.27 |
| Dish and Oven-Dried #10 Soil Wt.: | 24.40 |
| Dish Wt.: | 13.95 |
| Moisture of Air-Dried #10 Soil (%) | 8.33% |

* Sample broken on No. 10 Sieve


HYDROMETER

| | | | | | | |
|------------|-------|------------------|------|--------------------------------------|------------------|------------------|
| Cylinder # | 2 | Specific Gravity | 2.60 | Air-Dried Wt of #10 Soil** | BLOCK G 50.15 | ** Soil Used for |
| Area | 27.53 | Meniscus Corr. | 1 | Hydroscopic Corrected Wt of #10 Soil | 46.30 | Hydrometer Test |

| Time (minutes) | Hydrometer Reading* | Temperature °C | Standard Reading* | Corrected Reading | Percent Finer | Meniscus Corrected | L (cm) (from Table) | K (from Table) | Diameter (mm) |
|----------------|---------------------|----------------|-------------------|-------------------|---------------|--------------------|---------------------|----------------|---------------|
| 2 | 39 | 22.8 | 7 | 32 | 70 | 40 | 9.7 | 0.01353 | 0.030 |
| 5 | 36 | 22.8 | 7 | 29 | 63 | 37 | 10.2 | 0.01353 | 0.019 |
| 15 | 34 | 22.8 | 7 | 27 | 59 | 35 | 10.5 | 0.01353 | 0.011 |
| 30 | 33 | 22.8 | 7 | 26 | 57 | 34 | 10.7 | 0.01353 | 0.008 |
| 60 | 31 | 22.8 | 7 | 24 | 52 | 32 | 11.0 | 0.01353 | 0.006 |
| 250 | 27 | 21.7 | 7 | 20 | 44 | 28 | 11.7 | 0.01369 | 0.003 |
| 1440 | 23 | 22.8 | 7 | 16 | 35 | 24 | 12.3 | 0.01353 | 0.001 |

* All Readings made to TOP of meniscus

GRAPH



7% sand
 29% fine sand } 53% silt & fine sand
 24% silt
 40% clay

Pinhole Dispersion Report

APPLIED GEOTECHNICAL ENGINEERING CONSULTANTS

Identification and Classification of Dispersive Soils by the Pinhole Test (ASTM D4647-06)

Project Number 1150743

Project Name Intermountain

Date: 5/10/2016

Sample Number 14189

Regional Landfill Tested by: JG/DJ

Sample Description Lean Clay, Remolded to 95% of Maximum Dry Density per ASTM D-1557

Average Flow Rate in Each Trial (mL/sec)

Avg Flow at 2" Head for 5min: 0.40

Avg Flow at 7" Head: 0.95

Avg Flow at 40" Head: 2.86

Avg Flow at 2" Head for 10min: -

Avg Flow at 15" Head: 1.68

| Head (in): | Time (sec): | Flow (mL): | Flow rate: (ml/sec) | Cloudiness of Effluent | Notes |
|------------|-------------|------------|---------------------|---|---|
| 2 | Start | 0 | | Effluent was barely visible for the duration of the trial. Head was raised to 7" | Dispersion Classification: Nondispersive, ND1 Pinhole Size: 2x wire punch diameter |
| | 60 | 21 | 0.35 | | |
| | 60 | 26 | 0.43 | | |
| | 60 | 25 | 0.42 | | |
| | 60 | 23.5 | 0.39 | | |
| | 60 | 24 | 0.40 | | |
| 7 | Start | 0 | | Effluent was clear throughout duration. Head raised to 15" | |
| | 60 | 57 | 0.95 | | |
| | 60 | 56.5 | 0.94 | | |
| | 60 | 58 | 0.97 | | |
| | 60 | 56.5 | 0.94 | | |
| | 60 | 57.5 | 0.96 | | |
| 15 | Start | 0 | | Effluent was completely clear for majority of the trial. Head raised to 40" | |
| | 60 | 92.5 | 1.54 | | |
| | 60 | 100 | 1.67 | | |
| | 30 | 53 | 1.77 | | |
| | 30 | 50.5 | 1.68 | | |
| | 30 | 51.5 | 1.72 | | |
| | 30 | 51 | 1.70 | | |
| | 30 | 50.5 | 1.68 | | |
| 40 | Start | 0 | | Effluent was clear to barely visible for the duration of the trial. Test Concluded. | |
| | 60 | 166 | 2.77 | | |
| | 60 | 173 | 2.88 | | |
| | 60 | 175 | 2.92 | | |
| | 60 | 172 | 2.87 | | |
| | 60 | 173 | 2.88 | | |

**EXHIBIT 3
2010 PERMIT
APPLICATION**

Intermountain Regional Landfill

Class I Landfill Permit Application

Table of Contents

| | | | |
|----|---------------|---|-----------|
| 2 | | | |
| 3 | | | |
| 4 | PART 1 | GENERAL INFORMATION | 1 |
| 5 | PART 2 | GENERAL REPORT | 3 |
| 6 | 2 1 | Facility Description | 3 |
| 7 | | 2 1 1 General | 3 |
| 8 | | 2 1 2 Legal Description | 3 |
| 9 | | 2 1 3 Area Served | 4 |
| 10 | | 2 1 4 Local Jurisdiction | 4 |
| 11 | | 2 1 5 Adjacent Property Owners | 4 |
| 12 | | 2 1 6 Waste Type | 5 |
| 13 | | 2 1 7 Landfill Development | 6 |
| 14 | 2 2 | Location Standards | 7 |
| 15 | | 2 2 1 Historical Survey Requirement | 7 |
| 16 | | 2 2 2 Land Use Compatibility | 7 |
| 17 | | 2 2 3 Geology | 8 |
| 18 | | 2 2 4 Surface Water | 9 |
| 19 | | 2 2 5 Wetlands | 9 |
| 20 | | 2 2 6 Groundwater | 10 |
| 21 | 2 3 | Plan of Operations | 10 |
| 22 | 2 4 | Closure Plan | 10 |
| 23 | | 2 4 1 General | 10 |
| 24 | | 2 4 2 Site Capacity | 10 |
| 25 | | 2 4 3 Grading | 11 |
| 26 | | 2 4 4 Final Cover Placement | 11 |
| 27 | 2 5 | Post-Closure Care Plan | 11 |
| 28 | | 2 5 1 Monitoring and Maintenance | 11 |
| 29 | 2 6 | Closure Cost Estimate and Financial Assurance | 14 |
| 30 | | 2 6 1 Closure Cost Estimate | 14 |
| 31 | | 2 6 2 Proposed Financial Assurance Mechanism | 14 |
| 32 | 2 7 | References | 14 |
| 33 | PART 3 | TECHNICAL AND ENGINEERING REPORT | 15 |
| 34 | 3 1 | Maps | 15 |
| 35 | 3 2 | Geohydrology | 15 |
| 36 | | 3 2 1 General | 15 |
| 37 | | 3 2 2 Geology | 15 |
| 38 | | 3 2 3 Surface Water | 17 |
| 39 | | 3 2 4 Groundwater | 18 |
| 40 | | 3 2 5 Water Rights | 18 |

| | | | |
|---|---------------|--------------------------------|-----------|
| 1 | 3 3 | Background Groundwater Quality | 19 |
| 2 | 3 4 | Engineering Report | 20 |
| 3 | 3 4 1 | Performance Standards | 20 |
| 4 | 3 4 2 | Location Standards | 20 |
| 5 | 3 4 3 | Engineenng Design | 24 |
| 6 | 3 5 | References | 29 |
| 7 | PART 4 | FIGURES | 31 |

8
9




10 **List of Appendices**

| | | |
|----|------------|---|
| 11 | Appendix A | Plan of Operations |
| 12 | Appendix B | Property Ownership and Notice of Intent |
| 13 | Appendix C | Class III Cultural Resources Survey |
| 14 | Appendix D | Cost Breakdown for Closure/Post-Closure |
| 15 | Appendix E | Fairfield Site Geotechnical Study by Earthtec |
| 16 | Appendix F | Slope Stability and Settlement Analysis |
| 17 | Appendix G | Groundwater Monitonng Plan |
| 18 | Appendix H | Leachate Generation Calculatons |
| 19 | Appendix I | Leachate Pond Calculations |
| 20 | Appendix J | Run-on and Run-off Calculations |
| 21 | Appendix K | Water Rights Data |

Part 1: General Information

| I. General Information | | | | APPLICANT: PLEASE COMPLETE ALL SECTIONS. | | | |
|---|--|---|----------------------|--|---|--|--------------------|
| I. Landfill Type | | <input checked="" type="checkbox"/> Class I <input type="checkbox"/> Class V | II. Application Type | | <input checked="" type="checkbox"/> New Application <input type="checkbox"/> Renewal Application | <input type="checkbox"/> Facility Expansion <input type="checkbox"/> Modification | |
| For Renewal Applications, Facility Expansion Applications and Modifications Enter Current Permit Number _____ | | | | | | | |
| III. Facility Name and Location | | | | | | | |
| Legal Name of Facility INTERMOUNTAIN REGIONAL LANDFILL | | | | | | | |
| Site Address (street or directions to site) 800 SOUTH ALLEN RACH ROAD (18150 WEST) | | | | | | County (UTAH) | |
| City FAIRFIELD TOWN | | | | Zip Code 84013 | | Telephone | |
| Township 7 S | | Range 2 W | | Section(s) 16 | | Quarter/Quarter Section NW | Quarter Section SW |
| Main Gate Latitude degrees minutes seconds | | | | Longitude degrees minutes seconds | | | |
| IV. Facility Owner(s) Information | | | | | | | |
| Legal Name of Facility Owner INTERMOUNTAIN REGIONAL LANDFILL | | | | | | | |
| Address (mailing) PO Box 1889 | | | | | | | |
| City SALT LAKE CITY | | | State UT | Zip Code 84110-1889 | | Telephone 801-403-7651 | |
| V. Facility Operator(s) Information | | | | | | | |
| Legal Name of Facility Operator INTERMOUNTAIN REGIONAL LANDFILL | | | | | | | |
| Address (mailing) Box 1889 | | | | | | | |
| City SALT LAKE CITY | | | State UT | Zip Code 84110-1889 | | Telephone 801-403-7651 | |
| VI. Property Owner(s) Information | | | | | | | |
| Legal Name of Property Owner INTERMOUNTAIN REGIONAL LANDFILL | | | | | | | |
| Address (mailing) PO Box 1889 | | | | | | | |
| City SALT LAKE CITY | | | State UT | Zip Code 84110-1889 | | Telephone 801-403-7651 | |
| VII. Contact Information | | | | | | | |
| Owner Contact Rob Richards | | | | Title | | | |
| Address (mailing) PO Box 1889 | | | | | | | |
| City Salt Lake City | | | State UT | Zip Code 84110-1889 | | Telephone 801-403-7651 | |
| Email Address robr890@gmail.com | | | | Alternative Telephone (cell or other) | | | |
| Operator Contact ROB RICHARDS | | | | Title GENERAL MANAGER | | | |
| Address (mailing) SAME AS ABOVE | | | | | | | |
| City | | | | | | | |
| Property Owner Contact | | | | Title | | | |
| Address (mailing) SAME AS ABOVE | | | | | | | |
| City | | | State | Zip Code | | Telephone | |

Part 1 - General Information

| Part I General Information (Continued) | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|--|--|------------------------|---------------|--|--------------------------|--------------------------|--|--------------------------|--------------------------|-------------------------------------|--------------------------|--------------------------|--|--------------------------|--------------------------|----------------------------------|--------------------------|--------------------------|-----------------------------------|--------------------------|--------------------------|---|--------------------------|--------------------------|--------------------------------------|--------------------------|--------------------------|--|
| VIII. Waste Types (check all that apply) <input checked="" type="checkbox"/> All non-hazardous solid waste (see R315-315-7(3) for PCB special requirements) OR the following specific waste types: <table style="width:100%; border: none;"> <tr> <td style="width:33%;">Waste Type</td> <td style="width:33%;">Combined Disposal Unit</td> <td style="width:33%;">Monofill Unit</td> </tr> <tr> <td><input type="checkbox"/> Municipal Waste</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td><input type="checkbox"/> Construction & Demolition</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td><input type="checkbox"/> Industrial</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td><input type="checkbox"/> Incinerator Ash</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td><input type="checkbox"/> Animals</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td><input type="checkbox"/> Asbestos</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td><input type="checkbox"/> PCB's (R315-315-7(3) only)</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> <tr> <td><input type="checkbox"/> Other _____</td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table> | | Waste Type | Combined Disposal Unit | Monofill Unit | <input type="checkbox"/> Municipal Waste | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Construction & Demolition | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Industrial | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Incinerator Ash | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Animals | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Asbestos | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> PCB's (R315-315-7(3) only) | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> Other _____ | <input type="checkbox"/> | <input type="checkbox"/> | IX. Facility Area Facility Area..... <u>330</u> acres Disposal Area..... <u>300</u> acres Design Capacity Years..... <u>50 approx.</u> Cubic Yards..... <u>27,000,000</u> Tons..... <u>17,000,000</u> |
| Waste Type | Combined Disposal Unit | Monofill Unit | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> Municipal Waste | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> Construction & Demolition | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> Industrial | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> Incinerator Ash | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> Animals | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> Asbestos | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> PCB's (R315-315-7(3) only) | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input type="checkbox"/> Other _____ | <input type="checkbox"/> | <input type="checkbox"/> | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| X. Fee and Application Documents | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Indicate Documents Attached To This Application | | <input checked="" type="checkbox"/> Application Fee: Amount \$ | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <input checked="" type="checkbox"/> Facility Map or Maps <input type="checkbox"/> Ground Water Report | <input checked="" type="checkbox"/> Facility Legal Description <input checked="" type="checkbox"/> Closure Design | <input checked="" type="checkbox"/> Plan of Operation <input checked="" type="checkbox"/> Cost Estimates | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | <input checked="" type="checkbox"/> Waste Description <input checked="" type="checkbox"/> Financial Assurance | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | Class V Special Requirements <input type="checkbox"/> Documents required by UCA 19-6-108(9) and (10) | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| I HEREBY CERTIFY THAT THIS INFORMATION AND ALL ATTACHED PAGES ARE CORRECT AND COMPLETE. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Signature of Authorized Owner Representative  _____ Name typed or printed Robert P. Richards | | Title General Manager Date 11/20/10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Signature of Authorized Land Owner Representative (if applicable)  _____ Name typed or printed Robert P. Richards | | Title General Manager Date 11/20/10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Signature of Authorized Operator Representative (if applicable)  _____ Name typed or printed Robert P. Richards | | Title General Manager Date 11/20/10 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Address P.O. Box 1889 Salt Lake City, UT 84110 | | Address P.O. Box 1889 Salt Lake City, UT 84110 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Address P.O. Box 1889 Salt Lake City, UT 84110 | | Address P.O. Box 1889 Salt Lake City, UT 84110 | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Email Address ROBR890@GMAIL.COM | | Alternative Telephone (cell or other) 801-403-7651 | | | | | | | | | | | | | | | | | | | | | | | | | | | |

Part 2: General Report

2.1 Facility Description

2.1.1 General

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. See Figure 1 in Part 4. Once permitted and constructed, the landfill will consist of a single municipal landfill that will be constructed in phases. The major subunits of the landfill are called *cells*, and each cell will be developed in two or more *phases*. Other landfill facilities will include a stormwater/leachate evaporation pond, a scale house, and administrative offices. The perimeter of the active work area will be fenced using a 6-foot-high fence with an 18-inch angled top.

ROC Fund Landfill Holdings, a Utah limited liability company, will operate the Landfill once permits are secured and waste acceptance is authorized by the Division of Solid and Hazardous Waste (DSHW). ROC also owns the Landfill property.

The Intermountain Regional Landfill site is located in Cedar Valley, a large terminal basin typical of the Basin and Range physiographic province. Cedar Valley is generally cool and dry. Average annual precipitation is about 12 inches. Average high temperatures are 64 degrees Fahrenheit, and average low temperatures are 30 degrees Fahrenheit. Land use in Cedar Valley and in the vicinity of the Intermountain Regional Landfill site is agricultural, including livestock grazing and feed crop production. The site is currently undeveloped. A landfill for construction and demolition debris is located to the northwest.

2.1.2 Legal Description

The legal description of the Intermountain Regional Landfill site is

The West half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001)

As mentioned above, The ROC fund currently owns the property. The proof of ownership is attached as Appendix B.

2 1 3 Area Served

ROC is securing a waste disposal contract with Town of Fairfield Over the course of operations, ROC may seek other contracts with other local governments in the State of Utah

2 1 4 Local Jurisdiction

The Town of Fairfield will oversee compliance with local ordinances and any operational considerations and restrictions that will be outlined in an operating agreement for the Landfill The Utah County Health Department also has jurisdiction The contact information for the Health Department is

Utah County Health Department
 Joseph Miner, MD, MSPH
 Executive Director
 151 S University Avenue
 Provo, UT 84601

2 1 5 Adjacent Property Owners

Table 1 provides a list of property owners within 100 feet of the landfill property boundary

Table 1 Surrounding Property Owners

| Name | Address | City and State | Zip |
|--|-------------------|-------------------|-------|
| Corp of the Presiding Bishopnc | 50 E North Temple | SLC, UT | 84150 |
| Utah Trust Lands Administration | 675 E 500 S | SLC, UT | 84102 |
| Myrna B Carter | 13218 S 6200 W | Hemman, UT | 84096 |
| Claude J & Evelyn M Curley | 1409 Bryan Ave | SLC, UT | 84096 |
| Norbert A & Loma A Martinez | 1142 Renders Ln | Draper, UT | 84020 |
| John J & Julie Kolar | 642 Glonetta Blvd | Lafayette, CA | 94549 |
| Brent O Ault | 510 N 1100 E | American Fork, UT | 84003 |
| Richard S Fullmer | 2150 Willow Brook | Sandy, UT | 84092 |
| Larry D & Sheena L Mitchell | 8721 Oakwood Park | Sandy, UT | 84094 |
| Melinda Word | P O Box 301 | American Fork, UT | 84003 |
| Don Kaufer | P O Box 301 | American Fork, UT | 84003 |
| Howard H & Oliver R Holmes, c/o Bonnie Kaufer | P O Box 301 | American Fork, UT | 84003 |

A Notice of Intent to apply for a landfill permit was submitted to the surrounding property owners on August 19, 2010 A copy of the Notice of Intent is included in Appendix B

2 1 6 Waste Type

The waste disposed at the landfill will be solid non-hazardous residential and commercial solid wastes, including yard wastes, but the landfill generally will not accept construction and demolition (C&D) debris. Non-acceptable materials include liquid waste, burning materials, radioactive waste, and hazardous waste. Fairfield Town identified additional categories of wastes that will not be accepted at the landfill:

- 'Hazardous waste' as defined in 40 C F R part 261, as such part may be amended and expanded from time to time, and in Utah Code Ann. Section 19-6-102(9) and the regulations promulgated there under as they may be amended and expanded from time to time,
- Any material that is now or hereafter defined by applicable Federal, State or Local Laws, regulation, or ordinance as radioactive, toxic, hazardous or extremely hazardous waste, excluding household hazardous waste and small quantity generator hazardous waste,
- Vehicle tires in excess of the amount of such tires permitted to be disposed of by applicable Federal, State or Local law, regulation, or ordinance,
- Lead acid batteries,
- Soils contaminated with hazardous, radioactive, or toxic wastes, or hazardous or toxic substances as such terms are defined by applicable Federal or State law or regulations,
- Asbestos, including the asbestiform varieties of serpentinite (chrysotile), riebeckite (crocidolite), cummingtonite-grunite, anthophyllite and actinolite-terramite,
- Any material which contains asbestos ("ACM"), including asbestos waste from control devices, contaminated clothing, asbestos-waste material, materials used to enclose the work area during asbestos project, or bags or containers that previously contained asbestos,
- Dead animal carcasses,
- Any soils from coal mine sites, power plants, rail yards, and other industrial development sites and projects which may be removed as part of any voluntary or governmentally mandated environmental remediation plan or program,
- Infectious waste, medical waste, or sharps, and

- Any material whatsoever that the Permits or any Federal, State, or Local law, regulation, or ordinance may prohibit the disposal of at the Landfill now or in the future, provided, however, that any such future prohibition shall not operate retroactively such that any material previously determined to be Acceptable Waste and disposed of at the Landfill shall be a breach of this CUP [Conditional Use Permit] by virtue of such previous disposal

The anticipated volume of waste to be disposed of at the Intermountain Regional Landfill will average about 2,600 tons annually (8 tons per day, based on about 310 operating days per year) during the initial operation

2 1 7 Landfill Development

The overall site plan consists of one large landfill divided into six units, or cells. These cells are each about 650 feet wide (north to south) and about 2,500 feet long (east to west), or about 37 acres each. Each cell will be developed in 8- to 20-acre phases. The first lined landfill phase will be an 8-acre Cell 1 Phase 1, which will be constructed in the northwest corner of the landfill. Cell 1 will be developed by excavating to an average depth of about 30 feet. The liner grading for Cell 1 will direct leachate generally south and east to leachate collection pipes, which will convey the collected leachate east to a retention pond. An interim leachate retention pond will be constructed along the eastern edge of Cell 1 Phase 1. See Sheet 3 of 13 in Part 4. The total volume of Cell 1 Phase 1 will be about 334,000 cubic yards.

A permanent leachate retention pond will be constructed during subsequent phases of Cell 1 development. This permanent pond will collect and store pumped leachate from the entire landfill. Because the exact size of the next phase has not been determined, the timing for the construction of the permanent leachate pond is undefined. If Cell 2 Phase 2 extends to the eastern limits of Cell 1, the permanent pond will be constructed concurrently with the Phase 2 liner system. If Cell 1 is constructed in three or more phases, the leachate collection piping will be extended and interim leachate retention ponds moved to the eastern limits of Cell 1 Phase 2. Under this scenario, the permanent pond will be constructed with the cell phase that reaches the eastern limits of the excavation.

Cell 1 will be fully developed once the landfill liner system is extended to the eastern limits of the planned Cell 1 excavation. The total volume provided by Cell 1 will be about 2,700,000 cubic yards. Table 2 outlines

the approximate volume provided assuming Cell 1 is constructed in three phases

Table 2 Approximate Phase Volumes

| Landfill Phase | Cumulative Volume (CY) |
|----------------|------------------------|
| Cell 1 Phase 1 | 334,000 |
| Cell 1 Phase 2 | 1,973,000 |
| Cell 1 Phase 3 | 2,700,000 |
| Cell 2 | 5,000,000 |

Cell 1 Phase 1 will be constructed after permits are secured and authorization to receive waste is received from DSHW. The initial liner construction is anticipated in 2011. Cell 1 Phase 1 will be constructed by placing waste in lifts that are about 10 feet deep. Each lift will cover the entire area of Cell 1 Phase 1. See Appendix A, Section 5, for more details on the procedures that will be used to construct the landfill.

Cell 2 development will start on the south side of the Cell 1 along the eastern edge of the excavation. Cell 2 will be graded to use the leachate collection piping installed for Cell 1. Cell 2 will be developed by extending the landfill liner east to west. Cells 3, 4, 5, and 6 will be developed in a similar manner. The landfill will be graded so that leachate generated in Cells 3 and 4 will be collected in common leachate piping installed for Cell 3. Similarly, Cells 5 and 6 will use a common leachate collection system.

2.2 Location Standards

2.2.1 Historical Survey Requirement

A Class III Cultural Resources Survey was performed at the Intermountain Regional Landfill site in April 2010. The results of the survey showed that the site meets the historical survey requirements listed in Utah Administrative Code (UAC) R315-302-1. The completed survey is found in Appendix C, Class III Cultural Resources Survey.

2.2.2 Land Use Compatibility

Maps showing the existing land use and topography within 1,000 feet of the site are presented in Figures 1 and 2 in Part 4 of this report. No residences, parks, monuments, recreation areas, or wilderness areas are within 1,000 feet of the site.

3 The Utah Division of Wildlife Resources (UDWR) maintains a list of the
4 endangered species for all counties in Utah (UDWR 2010) There are
5 three endangered species listed for Utah County, however, none of these
6 species has been recorded in or within a few miles of the Goshen Pass
7 quadrangle according to GIS data provided by UDWR (UNHP 2009) In
8 addition, the site is not located in an ecologically or scientifically significant
9 area

10 On January 8, 2010, the site was investigated by an HDR biologist to
11 determine if the site contained any evidence of biological significance,
12 such as burrowing owl activity or nesting, kit fox dens, or unusual and
13 sensitive desert plant communities The site investigation found no
14 significant biological or ecological resources The site was a typical Utah
15 Great Basin shrub community that has been affected by overgrazing, off-
16 road vehicle (ORV) use, and other human activities Affected shrub lands
17 such as this site are common throughout Utah and are not unusual or
18 significant biological or ecological areas

19 There is one airport within 5 miles of the Intermountain Regional Landfill
20 site West Desert Airpark, which is 1.5 miles (8,000 feet) north-northwest
21 of the site and provides services for piston-type aircraft only

22 West Desert Airpark, LLC
23 614 North 18150 West
24 Fairfield, UT 84013

25 The distance from the Intermountain Regional Landfill site to West Desert
26 Airpark (8,000 feet) meets the required minimum distance from an airport
27 runway listed in UAC R315-302-1 This minimum distance is 10,000 feet
28 from any airport runway end used by turbojet aircraft, or 5,000 feet from
29 any airport runway end used by piston-type aircraft only

28 2.2.3 Geology

29 No known faults, special landslide areas, or subsidence areas were
30 identified on the Intermountain Regional Landfill site Maps showing the
31 geology and seismic activity of the area surrounding the site are found in
32 Part 4 of this report The geologic maps in Part 4 include

- 33 • Figure 3 – Geologic Features This map includes geologic faults
34 and locations of recent earthquakes
- 35 • Figure 4 – Seismicity This map includes earthquake data from
State of Utah Map MF-1856

3 The Intermountain Regional Landfill site is located in a seismic impact
4 zone as defined by the State of Utah Administrative Code (Utah
5 Department of Environmental Quality 2009). Refer to Part 3, Technical and
6 Engineering Report, and Appendix F, Slope Stability and Settlement
Analysis, for more information on the characteristics of the site and the
design considerations used for engineered features of the landfill.

7 **2.2.4 Surface Water**

8 Based on data obtained from the Western Regional Climate Center for the
9 Fairfield, Utah, Station, the average annual total precipitation at the
10 Intermountain Regional Landfill site is about 12 inches (NOAA 2009).
11 Surface water is largely generated from mountain snowmelt and conveyed
12 via intermittent streams to the valley. However, most of the stream
13 channels dissipate as they reach the valley floor. The 24-hour precipitation
14 depths for 25-year and 100-year events are 1.74 inches and 2.10 inches,
15 respectively (NOAA 2009).

16 No defined streams traverse the site. The only stream within 1 mile of the
17 site that is identified on U.S. Geological Survey (USGS) topographic
18 mapping for the area—in the Goshen 7.5-minute Quadrangle—originates
about 1 mile east of the site and travels in a generally northern direction
toward the sinks southeast of Fairfield. In addition, there are no special
21 flood hazard areas defined by the Federal Emergency Management
22 Agency (FERM) within or in the vicinity of the site; therefore no base (1%
23 annual chance or 100-year) flood elevations have been established (FEMA
24 2002). Surface water hydrology is further discussed in Section 3.2.3,
25 Surface Water.

26 **2.2.5 Wetlands**

27 HDR reviewed National Wetland Inventory (NWI) maps produced by the
28 U.S. Fish and Wildlife Service, aerial photographs from 2007, and Natural
29 Resources Conservation Service soils maps. None of these sources
30 indicated that wetlands are present at the Intermountain Regional Landfill
31 site. A subsequent field visit on January 8, 2010 by a wetland scientist
32 certified by the U.S. Army Corps of Engineers found that the site was
33 dominated by upland vegetation typical of the Great Basin, including big
34 sagebrush, rabbit brush, cheat grass, tumble mustard, and Russian thistle
35 and that no wetland vegetation was evident.

2 2 6 **Groundwater**

2 Cedar Valley consists of a basin-fill aquifer and bedrock aquifers. The
3 basin-fill aquifer extends across Cedar Valley and is up to 1,900 feet thick
4 in the center of the valley, with a clay layer of up to 240 feet thick confining
5 the aquifer. Figure 5 shows the Intermountain Regional Landfill site and
6 the groundwater level contours for the area. The groundwater is found 55
7 to 110 feet below the existing ground elevation of the site. Groundwater
8 conditions are discussed further in Section 3 2 4, **Groundwater**, and
9 Section 3 4 2 4, **Groundwater**.

10 **2.3 Plan of Operations**

11 The Plan of Operations for the Intermountain Regional Landfill is included
12 as Appendix A, Plan of Operations. The Plan includes onsite waste
13 screening and handling procedures, alternate waste handling procedures,
14 procedures for excluding prohibited wastes, procedures for minimizing
15 liquids, inspection and monitoring schedules, contingency and corrective
16 action plans, fugitive dust and litter control methods, the training and safety
17 plan for site operation, and procedures for controlling disease vectors.

18 **2.4 Closure Plan**

19 **2 4 1 General**

20 The Intermountain Regional Landfill will be constructed with several landfill
21 cells. The landfill will be closed over time as each cell reaches maximum
22 capacity. Soil from newly excavated landfill cells will be stockpiled onsite
23 and used for cover materials as cells are closed. Final closure of each cell
24 will begin once the landfill reaches the maximum permitted height and
25 within 30 days of the last receipt of waste. Final closure will be completed
26 within 180 days after closure activities begin.

27 **2 4 2 Site Capacity**

28 The Intermountain Regional Landfill will consist of several cells
29 constructed in phases. Cell 1, which will be constructed beginning
30 sometime in 2011, is designed to contain about 2,700,000 million cubic
31 yards when it reaches capacity. The total volume of the landfill is about
32 27,000,000 CY. Assuming a waste density of 1,500 lb/CY and 15% of the
volume taken by soil for daily and intermediate cover, the total capacity is
about 17,000,000 tons of waste.

2 4 3 Grading

Grading plans, including final grades, can be seen on conceptual engineering plans (Sheets 1 to 13) provided in Part 4. In general, the final cover will be graded so that the top slopes at least 2% to provide positive drainage, and the side slopes will not be greater than 4 to 1 (horizontal to vertical).

2 4 4 Final Cover Placement

Final cover will be placed on Cell 1 once the landfill operations are able to reach the maximum waste fill height and within 30 days of the last receipt of waste. It is anticipated that the Cell 1 Phase 2 liner will need to be constructed before waste fill heights can reach the maximum over Cell 1 Phase 1. The closure and post-closure care plan will be updated annually to account for changing conditions of the landfill. The status of closure and post-closure care funding will be reported to the Utah Department of Environmental Quality (UDEQ) with the landfill's annual reports.

A standard-design final cover will be designed, as prescribed by UAC R315-303-3. The standard design for a final cover consists of a minimum of 2 feet of compacted clay under a 60-mil HDPE (high-density polyethylene) synthetic layer. A minimum of 6 inches of topsoil will be placed on the synthetic layer to support vegetation.

2.5 Post-Closure Care Plan

Post-closure care for the Intermountain Regional Landfill will consist of long-term maintenance of the closure cap and ongoing sampling of the groundwater monitoring wells (and gas-monitoring stations when installed) to ensure that the landfill cell has been closed in accordance with regulations. The post-closure care period will be 30 years unless unexpected environmental contamination or continued subsidence occurs, or a shorter period if it can be proven that the landfill is stable and no longer presents a threat to human health or the environment.

The costs for post-closure care for Cell 1 Phase 1 are identified in Section 2.6.1, Closure Cost Estimate.

2 5 1 Monitoring and Maintenance

Semiannual groundwater monitoring and quarterly landfill gas monitoring will occur throughout the post-closure period. This frequency will be increased if data indicate that contamination might have occurred. The

post-closure monitoring frequency will revert to the original schedule if the more-frequent monitoring demonstrates that contamination, if present, is not attributable to the landfill

Leachate generated in the landfill will be collected and treated by a dual-lined evaporation pond. The pond will contain stormwater and process water runoff at the facility. The leachate collection and treatment system will be inspected as part of the routine quarterly monitoring. Since the Intermountain Regional Landfill has no planned discharge of surface water, no surface water monitoring will be required during the post-closure period.

Table 3 provides a schedule for conducting inspections and maintenance and for recording these routine activities. The Landfill Foreman will be responsible for conducting the inspections, scheduling maintenance, and recording these activities on the forms provided in Appendix I, Leachate Pond Calculations. Some of these activities listed below will be carried out as part of the ongoing operations during the active life of the site. These activities will be expanded to include the entire site at final landfill closure and will continue throughout the post-closure monitoring period.

Table 3 Frequency of Inspection and Maintenance of Facilities during Post-Closure Care

| Landfill Facility | Inspection or Maintenance | Frequency |
|--------------------------|---|-----------|
| Landfill cell | Cell perimeter fence integrity | Quarterly |
| Stormwater/leachate pond | Perimeter fence integrity Exposed liner system integrity | Quarterly |
| Other appurtenances | Entrance gate integrity Perimeter fence integrity Monitoring station integrity Berm integrity Run-on and run-off control system integrity | Quarterly |

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

21

A written summary of the activities performed during each inspection will be maintained. Fairfield will retain the right of entry to the closed landfill, maintain all rights-of-way, and conduct maintenance and/or remediation activities as needed. The landfill will be inspected on a quarterly basis for the following conditions:

- Integrity of the final cover (including erosion, subsidence, seeps, and settlement)
- Loss of vegetative cover
- Visible debris, litter, and waste
- Condition of access roads, gates, and fences
- Integrity of onsite structures
- Integrity of the groundwater monitoring system
- Integrity of the landfill gas monitoring system (when constructed)
- Integrity of drainage features
- Integrity of the leachate collection system

The final cover will be inspected for erosion or other maintenance problems. Any problems detected during routine site inspections will be corrected as soon as practicable. All eroded areas will be re-covered with suitable soil to establish erosion-control and infiltration layers and to provide positive drainage that will maintain the integrity of the final cover. All bare areas in the final cover will be revegetated as necessary.

Periodic inspections will determine whether the final cover system needs to be repaired due to differential settlement or subsidence by evaluating whether the final cover in the affected area has been impaired. Any areas where the integrity of the final cover has been compromised will be repaired as necessary.

Eroded areas in drainage ditches will be repaired and re-graded. Sediment buildup will be removed from areas where flow is restricted. Temporary stormwater control structures will be constructed and maintained as needed.

The leachate collection system will be maintained and operated as needed to minimize leachate head on the liner. The Landfill may seek the approval of the UDEQ to stop extracting and storing leachate if it can demonstrate that leachate generation has diminished and no longer poses a threat to human health and the environment.

2.6 Closure Cost Estimate and Financial Assurance

2.6.1 Closure Cost Estimate

The total cost for closure and post-closure for Cell 1 Phase 1 is about \$1,725,000. A cost breakdown is included in Appendix D, Cost Breakdown for Closure/Post-Closure. The closure cost estimate includes costs for engineering design, contractor procurement, permitting, and final cover construction. Post-Closure care includes post-closure plan preparation and 30 years of site inspections, record keeping, environmental monitoring, data analysis, and reporting.

2.6.2 Proposed Financial Assurance Mechanism

Fairfield will secure a Surety Bond as the financial assurance mechanism for the Landfill. The Surety Bond will be secured concurrently with landfill construction and will be submitted to DSHW along with construction certification documents and a request to authorize waste acceptance.

2.7 References

- [NOAA] National Oceanic and Atmospheric Administration. 2009. *Atlas 14 Precipitation-Frequency Atlas of the United States*. National Oceanic and Atmospheric Administration, Volume 1. Available online at http://hdsc.nws.noaa.gov/hdsc/pfds/sa/ut_pfds.html
- [UAC] Utah Administrative Code. 2009. Rule 315, Utah Solid Waste Permitting and Management Rules. Available online at <http://www.hazardouswaste.utah.gov/Rules/SolidWasteRules.htm>
- [UDWR] Utah Division of Wildlife Resources. 2010. *Counties List of Utah's Federally Listed Threatened, Endangered, and Candidate Species*. Available online at http://dwr.cdc.nr.utah.gov/ucdc/iewReports/te_cntv.pdf and <http://dwr.cdc.nr.utah.gov/ucdc/DownloadGIS/disclaim.htm>
- [UNHP] Utah Natural Heritage Program. 2009. E-mail from Sarah Lindsey, Utah Natural Heritage Program, Division of Wildlife Resources. December 15.

Part 3: Technical and Engineering Report

3.1 Maps

Referenced location Figures and Plan Sheets showing the development of the Landfill and associated details are included in Part 4, Figures

3.2 Geohydrology

3.2.1 General

The Intermountain Regional Landfill site is located in the Town of Fairfield in western Utah County, Utah. The site is in the central part of Cedar Valley, which is bounded on the west by the Thorpe Hills and Topliff Hill, on the east by the Lake Mountains and Mosida Hills, on the south by the East Tintic Mountains, on the north by the Traverse Mountains, and on the northwest by the Oquirrh Mountains.

The geology and hydrogeology of Cedar Valley have been described by Feltis (1967), Hurlow (2004), and Jordan and Sabbah (2007). A site-specific geotechnical study was completed by Earthtec Testing & Engineering, PC in 2006 (Appendix E). These sources were used in the evaluations of geology and hydrology presented in the following sections.

3.2.2 Geology

The Intermountain Regional Landfill site is located in Cedar Valley, which is underlain by up to 2,000 feet of basin-fill sediment and about 1,000 feet of basin-fill sediment at the landfill site (Hurlow 2004). The surface materials at the site consist of homogeneous deposits consisting of clay and silt as reported from the onsite geotechnical investigation by Earthtec. Borehole logs and test pit observations from the site are included in the geotechnical investigation in Appendix E, Site Geotechnical Study by Earthtec.

There are geologic faults within 5 miles of the Intermountain Regional Landfill site as shown on Figure 3. The nearest mapped fault is about 2.9 miles west of the site in the Thorpe Hills area. The nearest mapped fault on the basin floor is about 5 miles northeast of the site.

Two sources were consulted to determine historic seismic activity. Figure 3 shows data taken from the Utah Automated Geographic Reference

Center (AGRC) and shows earthquakes from the 1960s to the 1990s with magnitudes ranging from 0.00 to 2.99. Figure 4 is part of the USGS Miscellaneous Field Studies Map MF-1856 and includes seismic activity from the late 1800s through about 1990. Figure 3 shows that three earthquakes, ranging in magnitude from less than 1.00 to as much as 2.99, have occurred within 5 miles of the site within the last 50 years. Figure 4 does not show any seismic activity within 5 miles of the site.

In 2008, the Utah Geological Survey (UGS) prepared a Landslide Special Study Area Map for the Wasatch Front and Nearby Areas. No mapped areas showing susceptibility to landslides are near the Intermountain Regional Landfill site. In addition, no subsidence areas have been mapped near the site. However, no maps showing subsidence have been prepared for Utah County. To the best recollection of representatives from UGS and the Utah County Community Development Department, no subsidence has been reported for the area.

Utah County provides an online hazards map that shows known fault lines, fault rupture zones, slope hazard areas, and liquefaction potential. According to the hazards map, the Intermountain Regional Landfill site is not in a slope hazards area. The site is very flat and does not have any steep slopes that would create slope stability problems. The hazards map also shows that the site is in an area of low liquefaction potential. The fault data on the hazards map are similar to the Utah AGRC data presented above.

The probabilistic maximum (peak) horizontal acceleration for an earthquake with a return period of 2% in 50 years (10% in 250 years) near the site is 0.25g. This was determined from USGS National Seismic Hazard Mapping Project Probabilistic Seismic Hazards Assessment, Custom Mapping and Analysis Tools, Interactive Deaggregation Tool. Using the Interactive Deaggregation Tool and adjusting the shear wave velocity based on the site-specific soil characteristics, the maximum (peak) horizontal acceleration for the site was determined to be 0.28g. This value was used to evaluate the cut slope and the waste mass stability. The complete Slope Stability and Settlement Analysis is included as Appendix F, Slope Stability and Settlement Analysis.

The peak maximum credible earthquake was also determined probabilistically using the same source and methodology. A magnitude 7.0 was used for slope stability evaluation. The design accelerations (above the bedrock at bottom of waste) for short period, S_{DS} , and for 1-second period, S_{D1} , were determined to be 0.55g and 0.31g, respectively.

3 These were also determined by Earthtec (Appendix E) in accordance with
4 the International Building Code (IBC) using a Site Class D classification
5 These values are appropriate to evaluate structural components that are
6 not currently planned for the Intermountain Regional Landfill

3 2 3 Surface Water

6 Although the Oquirrh Mountains to the northwest receive on average over
7 40 inches of precipitation each year, mainly in the form of snow, the
8 Cedar Valley floor receives considerably less (Hurlow 2004) Based on
9 data obtained from the Western Regional Climate Center for the Fairfield,
10 Utah, Station, the average annual total precipitation is about 12 inches
11 (NOAA 2009) Surface water is largely generated from mountain
12 snowmelt and conveyed via intermittent streams to the valley However,
13 most of the stream channels dissipate as they reach the valley floor
14 Precipitation in the valley is received primarily as winter snowfall and late-
15 summer thunderstorms (Hurlow 2004) The 24-hour precipitation depths
16 for 25-year and 100-year events are 1.74 inches and 2.10 inches,
17 respectively (NOAA 2009)

18 No defined streams traverse the site The only stream within 1 mile of the
19 site that is identified on USGS topographic mapping for the area—in the
20 Goshen 7.5-minute Quadrangle—originates about 1 mile east of the site
21 and travels in a generally northern direction toward the sinks southeast of
22 Fairfield Topographic mapping and other geospatial data were obtained
23 from the Utah AGRC, stream data confirm the information provided on the
24 Goshen Quadrangle map (Utah AGRC 2009) Topographic data including
25 2-foot contours for the site were obtained from Olympus Aerial Surveys,
26 Inc Except for minor roadside swales, no defined drainage features are
27 evident on or around the Intermountain Regional Landfill site The
28 roadside swales are most notable along east-west roads near the
29 northern and southern site boundaries Little to no relief is shown near the
30 other unpaved roads within the site The general slope of the site is from
31 west to east with an elevation difference of 6 to 8 feet across the width of
32 the site

33 There are no special flood hazard areas defined by the Federal
34 Emergency Management Agency within or in the vicinity of the site,
35 therefore no base (1% annual chance or 100-year) flood elevations have
36 been established (FEMA 2002)

1 3 2 4 **Groundwater**

2 Cedar Valley consists of a basin-fill aquifer and bedrock aquifers. The
3 basin-fill aquifer extends across Cedar Valley and is up to 1,900 feet thick
4 in the center of the valley. A clay layer up to 240 feet thick confines the
5 aquifer (Jordan 2007). The bedrock aquifers are at the base of the
6 mountain ranges that surround Cedar Valley.

7 Groundwater level contours show that groundwater is at an elevation of
8 about 4,740 to 4,795 feet near the Intermountain Regional Landfill site,
9 which is 55 to 110 feet below the existing ground elevation of 4,850 feet.
10 The clay layer that confines the aquifer is up to 200 feet thick in the area
11 of the proposed landfill site (Jordan 2007). Figure 5 shows the location of
12 the Intermountain Regional Landfill and approximate groundwater levels.
13 In addition, the geotechnical exploration performed by Earthtec in
14 September 2006 included 20 shallow test pits and two test holes. No
15 groundwater was encountered during the geotechnical exploration, test
16 holes 1 and 2 were drilled to depths of about 31 feet and 41 feet,
17 respectively.

18 According to the groundwater contours presented by Jordan (2007),
19 groundwater in the vicinity of the Intermountain Regional Landfill site
20 travels in a south-southeasterly direction. Using the results of aquifer
21 tests performed by UGS and others, Jordan estimated the hydraulic
22 conductivity in the basin-fill aquifer to range from 0.003 to 49 feet per day,
23 with an average of 8 feet per day and a median value of 2.5 feet per day.

24 In April 2010, Lucy Jordan with UGS provided data from a short-duration
25 aquifer test that was performed at a well on the Michael Burch residence
26 in Fairfield about 3.25 miles north of the Intermountain Regional Landfill
27 site. The well is in the principal basin-fill aquifer, which is the primary
28 aquifer below the Intermountain Regional Landfill site. The test consisted
29 of a 7-hour drawdown with a 5-hour recovery. The calculated hydraulic
30 conductivity is about 2 feet per day (Jordan 2010).

31 3 2 5 **Water Rights**

32 Spatial and tabular water rights data were obtained from the Utah Division
33 of Water Rights (2009), and all points of diversion within 2,000 feet of the
34 Intermountain Regional Landfill boundary were identified. There are no
35 wells or other points of diversion (PODs) within the landfill boundary. Five
36 PODs are within 2,000 feet. However, the status of each point is noted as
37 “terminated,” and the water rights might have been consolidated into
38 another POD. For all but one POD, the water right application is either

3 withdrawn or permanently lapsed. One POD is about 1,000 feet east and
4 downgradient of the landfill boundary, and the other four are at a single
5 location about 1,400 feet south of the southwest corner of the landfill
6 boundary. The source at each POD is one or more underground water
7 well. Figure 6 in Part 4 of this report is a map showing the location of the
five PODs. Data on each POD are included in Appendix K, Water Rights
Data.

8 3.3 Background Groundwater Quality

9 Because there are no surface water drainages near the Intermountain
10 Regional Landfill site, general surface water quality was not quantified for
11 this permit application.

12 In the northern parts of Cedar Valley, concentrations of total dissolved
13 solids (TDS) in groundwater are typically less than 1,000 mg/L
14 (micrograms per liter), nitrate concentrations are less than 10 mg/L
15 (except for one privately owned well), and no other chemical constituents
16 exceed the U.S. Environmental Protection Agency's (EPA) standards for
17 drinking water. Groundwater along the northeastern boundary of Cedar
18 Valley has TDS concentrations ranging from about 400 to 1,200 mg/L and
19 is enriched in sodium and chloride relative to the northwestern part of the
20 valley. The groundwater chemistry is different in the northeastern part of
21 the valley because the groundwater mixes with water that is ascending
22 along the Lake Mountains fault on the eastern boundary of Cedar Valley.

23 Groundwater in southeastern Cedar Valley (the area that includes the
24 Intermountain Regional Landfill) has moderate to high salinity and
25 sodium, has TDS concentrations ranging from about 1,700 to 2,000 mg/L,
26 and is enriched in sodium and sulfate relative to groundwater in the
27 northeastern part of the valley. The likely cause of the degraded
28 groundwater quality is chemical reactions between the groundwater and
29 clay-rich, sulfide-bearing sediment of Lake Bonneville, the Tertiary Salt
30 Lake Formation, and/or Oligocene tuff as groundwater moves from
31 northwest to southeast (Hurlow 2004).

32 More site-specific background water quality for the Intermountain
33 Regional Landfill site will be established after monitoring wells are
34 installed. See Appendix G, Groundwater Monitoring Plan, for the
35 Groundwater Monitoring Plan for the Intermountain Regional Landfill.

3.4 Engineering Report

3.4.1 Performance Standards

The Intermountain Regional Landfill will be a lined landfill with a leachate collection system to convey leachate to a lined leachate evaporation pond. See Section 3.4.3.2, Leachate Management, of this report for more information. In addition, a Groundwater Monitoring Plan will be followed to test for groundwater contamination, this plan includes steps for determining the need for remediation if groundwater becomes contaminated. The Groundwater Monitoring Plan is included in Appendix G, Groundwater Monitoring Plan.

All surface water that comes into contact with waste will be considered leachate and will be conveyed to a lined leachate evaporation pond, which will be designed to hold the volume of the 25-year, 24-hour storm as required by UAC R-315-7-19. It is not anticipated that leachate will be discharged off-site. See Section 3.4.3.2, Leachate Management, of this report for more information.

The landfill will likely be subject to a stormwater discharge permit under the Utah Pollutant Discharge Elimination System (UPDES) Multi-Sector General Permit (MSGP) for stormwater discharges associated with industrial activity.

3.4.2 Location Standards

UDEQ has adopted specific location restrictions that include the criteria specified in the federal Subtitle D regulations. The Utah location restrictions for municipal solid waste landfills are outlined below. Subtitle D criteria are indicated with an asterisk (*)

- 1 Land Use Compatibility [R315-302-1(2)(a)]
 - a Parks and protected areas
 - b Ecologically and scientifically significant areas
 - c Prime farmland
 - d Dwellings and structures*
 - e Airport runways*
 - f Archaeological sites
 - g Land use planning or zoning
- 2 Geology [R315-302-1(2)(b)] and Fault Areas*
 - a Seismic impact zones*
 - b Unstable areas*

3 Surface Water [R315-302-1(2)(c)]

- a Floodplains*
- b Wetlands*

4 Groundwater [R315-302-1(2)(e)]

- a Groundwater/landfill separation
- b Sole-source aquifer
- c Groundwater quality
- d Source protection areas

The following sections present the State of Utah location restrictions and discuss the Intermountain Regional Landfill's compliance with those requirements

3 4 2 1 Land Use Compatibility

The Utah Solid Waste Permitting and Management Rules state that no municipal solid waste landfill shall be located within the following restriction zones

- One thousand feet of a national, state, or county park, monument, or recreation area, designated wilderness or wilderness study area, or wild and scenic river area
- Ecologically and scientifically significant natural areas, including wildlife management areas and habitat for listed or proposed endangered species as designated pursuant to the Endangered Species Act of 1982
- Farmland classified as prime, unique, or of statewide importance by the U S Department of Agriculture Soil Conservation Service [now the Natural Resources Conservation Service] under the Prime Farmland Protection Act
- One-quarter mile of existing permanent dwellings, residential areas, and other incompatible structures such as schools, churches, and historic structures or properties listed or eligible to be listed in the State or National Register of Historic Places
- Ten thousand feet of any airport runway end used by turbojet aircraft, or 5,000 feet of any airport runway end used by only piston-type aircraft
- Areas with respect to archeological sites that would violate [UAC] R9-8-404

- An area that is at variance with any locally adopted land use plan or zoning requirement unless otherwise provided by local law or ordinance

The Intermountain Regional Landfill site is not within any of these restriction zones. Part 4 of this document contains figures and maps of the Intermountain Regional Landfill site and nearby facilities, residences, and land features. The land use directly adjacent to the landfill site is agricultural. The nearest residence is more than 2 miles west of the site boundary, and the nearest town, Fairview, is about 3 miles north of the site. The nearest airport runway is about 8,000 feet from the site and is used by only piston-type aircraft. No parks, ecologically significant areas, prime farmland, or archeological sites (see also Appendix C) are known to exist near the site. The Intermountain Regional Landfill site is surrounded on the north and west by land zoned mining and grazing (MEG1) and on the south and east by land zoned agricultural (A1). The landfill is consistent with these zoned land uses.

3.4.2.2 Geology

The Utah Solid Waste Permitting and Management Rules, listed below, state that no municipal solid waste landfill shall be located in a subsidence area, in a dam failure flood area, over an underground mine or salt bed, or on or adjacent to geologic features that could compromise the structural integrity of the facility.

- **Fault Areas** A new facility or a lateral expansion of an existing facility shall not be located within 200 feet of a Holocene fault.
- **Unstable Areas** Unstable areas require demonstration that the site has been engineered to ensure that the integrity of the structural components of the facility will not be damaged by the unstable conditions.
- **Seismic Impact Zones** A new facility or a lateral expansion of an existing facility shall not be located in seismic impact zones unless all containment structures are designed to resist the maximum anticipated horizontal acceleration for the site.

There are no known Holocene faults within 200 feet of the site, and the site is not within a known unstable area as defined in the regulations. However, as described in Section 3.2.2, the probabilistic maximum (peak) horizontal acceleration was determined to be 0.25g, which was determined at bedrock, and the value adjusted based on site-specific

soils to 0.28g. These values exceed 0.1g, which is the minimum per UDEQ and EPA to qualify as a seismic impact zone. The Slope Stability and Settlement Analysis, which is included as Appendix F, evaluated slope stabilities, settlement, and liner system strain and found that adequate safety factors are maintained during design seismic events.

3.4.2.3 Surface Water

The Utah Solid Waste Permitting and Management Rules state that no municipal solid waste landfill shall be located within a public water system watershed, a floodplain, or a wetlands area without specific approval of the Executive Secretary. The Intermountain Regional Landfill site is not within a public water system watershed or 100-year floodplain. USGS topographic maps and a site survey (2-foot contours) were evaluated for surface drainage, and no defined surface drainage features traverse the site. In addition, the site does not contain vegetation or hydrologic features that are characteristic of wetland areas.

3.4.2.4 Groundwater

The Utah Solid Waste Permitting and Management Rules state that no municipal solid waste landfill shall be located within the following restriction zones:

- Within 5 feet of the historical high groundwater elevation
- Within 100 feet of an aquifer that could contain TDS concentrations less than 1,000 mg/L (or 50 feet for TDS between 1,000 and 3,000 mg/L) unless the landfill is constructed with a composite liner system
- Over an aquifer designated as a sole-source aquifer or groundwater classified as 1B (irreplaceable groundwater)
- In a drinking water source protection area

Landfill cells will not be constructed within 5 feet of the historical high groundwater elevation. The geotechnical exploration performed at the site in September 2006 included 20 shallow test pits and two test holes. No groundwater was encountered during the geotechnical exploration, test holes drilled to depths of about 31 to 41 feet. Figure 5 shows the Intermountain Regional Landfill site and the groundwater level contours for the area. The groundwater is found 55 to 110 feet below the existing ground elevation of the site. The maximum depth of the proposed landfill liner system below existing ground surface is planned to be in the range

of 35 to 40 feet, placing the bottom of the liner at least 17 feet from the historical high groundwater elevation, and well outside the 5 foot proximity requirement

The TDS in groundwater in the southeastern part of Cedar Valley, near the Intermountain Regional Landfill, is expected to be over 1,000 mg/L (Hurlow 2004) The Intermountain Regional Landfill will be constructed with a composite liner and leachate collection system consisting of a geosynthetic clay liner (GCL) and an HDPE geomembrane See Section 3 4 3 below for a detailed description of the landfill's composite liner

The Intermountain Regional Landfill site is not within a sole-source aquifer and is not over groundwater with a 1B classification

3 4 3 Engineering Design

3 4 3 1 Cell Design

The Intermountain Regional Landfill will consist of six cells Cell 1 Phase 1 will consist of an 8-acre geosynthetic-clay-and-HDPE-lined area The soil from the excavation of Cell 1 will be placed in the soil stockpile area north of the cell Excavation side slopes will be constructed on a 4 1 (H V) slope Generally, the bottom slope will be 1 4% west to east and 1 4% north to south

The liner system for Cell 1 will consist of the following components (from bottom to top)

- A non-woven, needle-punched polypropylene geotextile (optional) The excavation will determine the maximum size and gradation of materials that remain on the surface of the excavation The need for an extra layer of cushioning geotextile will be determined to provide puncture resistance for the overlying GCL and geomembrane
- A bentonite-impregnated geotextile, or GCL The GCL will provide a barrier to leachate and landfill gas migration
- A 60-mil HDPE textured flexible membrane liner
- A non-woven needle-punched polypropylene geotextile The upper geotextile will provide puncture resistance for the HDPE liner The thickness of the geotextile will be evaluated based on the soil properties of the material selected for the protective cover soil It is anticipated that a 12- to 16-ounce geotextile will be used

- A 2-foot-thick protective cover layer This sand or non-carbonate gravel soil layer will protect the geotextile, HDPE, and GCL as the first lift of solid waste is placed It will also provide a pathway for leachate above the HDPE to move toward the leachate collection and removal system

During the final design, a Construction Quality Assurance (CQA) Plan will be developed This CQA Plan will describe the responsibilities of the installation contractor for conducting a construction quality-control program during installation The CQA Plan will require that all seams will be tested for continuity In addition, periodic samples will be removed from the rolls and subjected to tensile testing at a third-party laboratory Construction observation personnel will be on-site at all times when HDPE, GCL, and geotextile are installed and when the 2-foot-thick protective layer is placed These personnel will provide a CQA review of the construction and installation of the liner system

3.4.3.2 Leachate Management

Leachate, including stormwater falling in the active landfill cell that comes into contact with solid waste or daily cover, will be transmitted through the 2-foot-thick protective cover soil layer to a leachate collection pipe installed along the southern boundary of Cell 1 (see Sheets 3 and 4 of 13 in Part 4) Cell 1 Phase 1 will include a temporary leachate pond that will be constructed along the eastern edge of Phase 1

With the construction of Cell 1 Phase 2 or 3 (or other cell Phase division), a permanent leachate pond will be constructed at the northeast corner of the site The leachate collection pipe from Cell 1 Phase 1 will be extended to the sump of Cell 1 Phases 2 and 3 The leachate collection pipe will consist of an 8-inch-diameter perforated HDPE pipe encased in a granular fill wrapped with a geotextile The pipe trench will be about 2 feet deep to match the thickness of the protective cover Leachate will be managed by this system during filling and after closure

EPA's Hydrologic Evaluation of Landfill Performance (HELP) model, Version 3.07, was applied to several operational and closure scenarios to evaluate infiltration into Cell 1 and subsequent generation of leachate See Appendix H, Leachate Generation Calculations Soil, waste, and geosynthetic characteristics were modeled with the default soil properties The initial moisture content of the waste was adjusted to reflect the drier waste conditions at other Utah landfills Information from Wasatch Integrated Waste Management District (formerly known as Davis County

1 Solid Waste Management and Energy Recovery Special Service District)
2 indicates waste moisture contents by weight of about 11%. Site specific
3 climatic conditions were included in the model. The HELP model results
4 show that no leachate would be generated.

5 The following scenarios were considered representative of the life cycle
6 for Cell 1:

- 7 • Ten feet of waste and a 6-inch daily cover, simulating initial filling
- 8 • One hundred feet of waste and 12 inches of intermediate cover for
9 20 years, simulating the anticipated life of Cell 1

10 The model produced the same result for each scenario, which indicates
11 that no leachate would be generated. Based on this result, no hydraulic
12 head will occur on the liner.

13 Because the HELP model shows that no leachate would be generated in
14 these scenarios, the temporary leachate pond at the north end of the Cell
15 1 Phase 1 and the permanent leachate pond at the northeast corner of
16 the site was sized to hold the 25-year, 24-hour precipitation event (as
17 required by UAC R-315-7-19) for the largest cell development phase,
18 which is Cell 1.

19 After Cell 1 is fully constructed, the perforated leachate collection pipe will
20 enter a gravel-filled sump in the southeast corner of Cell 1. The pipe
21 (solid wall) will continue up the side slope and terminate at the top of
22 excavation as a clean-out. An 18-inch-diameter HDPE pipe will be
23 installed in the sump and will also continue up the side slope. The bottom
24 of the pipe will be perforated so that leachate can enter. A submersible
25 pump capable of pumping at least 50 gallons per minute will be lowered
26 down the 18-inch pipe to pump leachate out of the cell into another pipe,
27 where it will be conveyed in a dual-lined leachate drain line from Cell 1 to
28 the permanent evaporation pond.

29 The leachate evaporation pond will be double-lined. The pond will consist
30 of the following layers (from bottom to top):

- 31 • An optional 16-ounce non-woven, needle-punched polypropylene
32 geotextile
- 33 • A geosynthetic clay liner (GCL)
- 34 • Liner 1, a 60-mil HDPE geomembrane
- 5 • Liner 2, a 60-mil HDPE geomembrane

- A cushioning geotextile—a non-woven needle-punched polypropylene geotextile
- A layer of soil or other material to provide ballast for the pond liner system

3 4 3 3 Surface Water Controls

The Intermountain Regional Landfill site vicinity generally drains from west to east. As discussed in Section 3 2 3, Surface Water, no defined streams traverse the site. Construction of Cell 1 will not alter the existing stormwater conditions.

Stormwater originating on-site will be managed as non-contact or contact stormwater depending on its source. Non-contact stormwater is water that falls on unimproved parts of the site or on improved parts of the site that have no contact with solid waste (for example, the entrance roads and soil stockpile areas) or on Cell 1 once final cover has been placed. Run-on control structures will divert this water away from the active landfill cell. Run-off control structures will divert water falling on the active landfill cell into the leachate collection system. Ultimately, contact stormwater will be stored and evaporated in the evaporation pond. Neither leachate nor contact stormwater will be discharged from the site in surface waters. If the evaporation pond reaches capacity, water will be pumped from the pond onto waste in the active working area to accelerate evaporation.

Analyses have been conducted for run-on and run-off control systems around Cell 1. These analyses were conducted for a 25-year storm event and the associated time of concentration that produced peak flow. The analyses, presented in Appendix J, Run-on/Runoff Calculations, indicate that a triangular ditch with 4 to 1 side slopes and nominally 1.5 foot deep, provides adequate flow capacity. This ditch geometry will be constructed concurrent with Cell 1 construction.

A perimeter ditch around the west and north property boundaries is required to collect and convey stormwater run-on. Run-on results from stormwater runoff from the property on the west side of the Landfill. This 419-acre area contributes approximately 140 cubic feet per second of stormwater runoff. A ditch with a bottom width of 10 feet, with 4 to 1 (horizontal to vertical) side slopes, and a nominal depth of about 3 feet will be constructed to manage stormwater runoff. Stormwater run-on will be conveyed north and west along the northern portions of the landfill and will be returned to overland flow at the northeast corner of the landfill.

3 4 3 4 Closure and Post-Closure

The final closure of Cell 1 will occur in about 2018. The landfill cap will consist of the standard design final cover as prescribed by UAC R315-303-3. The standard design for final cover consists of a minimum of 2 feet of compacted clay under a 60-mil HDPE synthetic layer. A minimum of 6 inches of topsoil will be placed on the synthetic layer to support vegetation. A seed mix similar to that shown in Table 4 will be used to establish vegetation.

Table 4 Seed Mix for Intermountain Regional Landfill

| Type of Grass | Percent of Mix |
|-------------------------|----------------|
| Sand drop seed | 0.50% |
| Alkali sacaton | 1.50% |
| Blue grama | 3.50% |
| Blue bunch wheat grass | 17.50% |
| Indian nee grass | 17.50% |
| Sandberg blue grass | 3.00% |
| Sheep fescue | 4.00% |
| Slender wheat grass | 16.25% |
| Stream bank wheat grass | 16.25% |
| Western wheat grass | 20.00% |
| | 100.00% |

Proposed final contours for Cell 1 can be seen on Sheet 7 of 13 in Part 4. The side slopes of the landfill will be constructed at a 4:1 (H:V) slope with the top being about 5%.

Post-closure care is expected to consist of the following tasks:

- Quarterly inspections of the cap to determine whether significant erosion or differential settlement has occurred.
- Quarterly inspections of the stormwater/leachate evaporation pond.
- Quarterly monitoring of landfill gases at the extraction wells, if gas generation requires that these are installed.
- Quarterly inspection of groundwater well integrity.
- Semi-annual monitoring and sampling of groundwater wells.

1 These activities will take place on Cell 1 after it has received final cover
2 and will be expanded to all closed areas at the appropriate time. Closure
3 and post-closure is discussed in more detail in Section 2.5, Post-Closure
4 Care Plan, and Section 2.6, Closure Cost Estimate and Financial
5 Assurance, of this application.

6 3.5 References

7 Feltis, R. J. 1967. *Ground-Water Conditions in Cedar Valley, Utah County, Utah*. Technical
8 Report No. 16, U.S. Geological Survey in cooperation with Utah State Engineer.

9 Hurlow, Hugh A. 2004. *The Geology of Cedar Valley, Utah County, Utah, and Its Relation to*
10 *Groundwater Conditions*. Special Study 109.

11 Jordani, Lucy. 2010. Verbal communication between Lucy Jordan, Utah Geological Survey, and
12 Ryan Rigs, HDR Engineering. February.

13 Jordan, J. Lucy, and Walid Sabbah. 2007. *Ground-Water Flow, Water Level Trends, and the*
14 *Connection Between Fairfield Springs and the Basin-Fill Aquifer in Cedar Valley, Utah*
15 *County, North-Central Utah*. Prepared by Utah Geological Survey.

16 [NOAA] National Oceanic and Atmospheric Administration. 2009. *Atlas 14 Precipitation-*
17 *Frequency Atlas of the United States*. National Oceanic and Atmospheric Administration,
18 Volume 1. Available online at http://hdsc.nws.noaa.gov/hdsc/pfds/sa/ut_pfds.html.

19 Utah Division of Water Rights. 2009. Utah Division of Water Rights database. Available online at
20 <http://www.waterrights.utah.gov>. Accessed December 15, 2009.

Part 4: Figures

List of Figures

- Figure 1 USGS Topographic Map and Site Vicinity
- Figure 2 USGS Topographic Map, Site, Water-Related Land uses, and Resources
- Figure 3 Geologic Features Map
- Figure 4 Seismicity Map
- Figure 5 Groundwater Potentiometric Contours
- Figure 6 Water Rights Points-of-Diversion Map
- Figure 7 FEMA FIRM Map

List of Plan Sheets

- Sheet 1 Cover & Index
- Sheet 2 General Notes & Abbreviations
- Sheet 3 Site Plan
- Sheet 4 Excavation Liner Plan Cell 1 Phase 1
- Sheet 5 Cell 1 Phasing Plan
- Sheet 6 Excavation Liner Plan All Cells
- Sheet 7 Final Cover Grading Plan
- Sheet 8 Cross Sections
- Sheet 9 Cross Sections
- Sheet 10 Cross Sections
- Sheet 11 Cross Sections
- Sheet 12 Leachate Pond Plan
- Sheet 13 Details


Part 4: Figures

List of Figures

| | |
|----------|--|
| Figure 1 | USGS Topographic Map and Site Vicinity |
| Figure 2 | USGS Topographic Map, Site, Water-Related Land uses, and Resources |
| Figure 3 | Geologic Features Map |
| Figure 4 | Seismicity Map |
| Figure 5 | Groundwater Potentiometric Contours |
| Figure 6 | Water Rights Points-of-Diversion Map |
| Figure 7 | FEMA FIRM Map |


List of Plan Sheets

| | |
|----------|--------------------------------------|
| Sheet 1 | Cover & Index |
| Sheet 2 | General Notes & Abbreviations |
| Sheet 3 | Site Plan |
| Sheet 4 | Excavation Liner Plan Cell 1 Phase 1 |
| Sheet 5 | Cell 1 Phasing Plan |
| Sheet 6 | Excavation Liner Plan All Cells |
| Sheet 7 | Final Cover Grading Plan |
| Sheet 8 | Cross Sections |
| Sheet 9 | Cross Sections |
| Sheet 10 | Cross Sections |
| Sheet 11 | Cross Sections |
| Sheet 12 | Leachate Pond Plan |
| Sheet 13 | Details |



Data Sources:
 Utah AGRC (<http://gis.utah.gov/download>) layers:
 UDOTMap_MajorRoads; Municipalities; CountyBoundaries;
 UtahMajorLakes; 5-Meter Hillshade; 2009 NAIP 1-Meter Color
 Orthophotography.

- Legend**
- Intermountain Regional Landfill
 - Facility Boundary




USGS 7.5-Minute Topographic Quad:
 Goshen Pass

Intermountain Regional Landfill

Figure One
 USGS Topographic Map
 and Site Vicinity

Permit Application


Data Sources:
Utah AGRC (<http://gis.utah.gov/download>) layer: Municipalities.
Land Use: Utah Division of Water Resources.



Legend

- Land Use
 - Dry Fallow
 - Dry Idle
 - Urban
- Intermountain Regional Landfill
 - Facility Boundary
 - 1000-Foot Buffer


*No resources were found within 1,000 feet of the facility boundary.



Intermountain Regional Landfill

Figure Two
USGS Topographic Map, Site, Water-Related Land Uses, and Resources* within 1000 Feet

Permit Application



Data Sources:
 Utah AGRC (<http://gis.utah.gov/download>) layers:
 EpicentersModern; GeologicFaults; UDOTMap_MajorRoads;
 Municipalities; 2009 NAIP 1 Meter Color Orthophotography.


Legend

- | | | |
|----------------------|----------------------|--|
| Earthquake* | ▲ 1980s, 0.00 - 0.99 | ● Earthquake Outside 15-Mile Radius of Facility Boundary |
| Decade, Magnitude | ■ 1970s, 2.00 - 2.99 | — Geologic Fault |
| ● 1990s, 2.00 - 2.99 | ■ 1970s, 1.00 - 1.99 | ▭ Facility Boundary |
| ● 1990s, 1.00 - 1.99 | ■ 1970s, 0.00 - 0.99 | ▭ Five-Mile Buffer |
| ● 1990s, 0.00 - 0.99 | ◆ 1960s, 2.00 - 2.99 | |
| ▲ 1980s, 2.00 - 2.99 | ◆ 1960s, 1.00 - 1.99 | |
| ▲ 1980s, 1.00 - 1.99 | | |


* Earthquakes displayed are within a 15-mile radius of the facility boundary.

Intermountain Regional Landfill

Figure Three
Geologic Features



Permit Application



Legend


- Facility Boundary
- Five-Mile Buffer

Sources:


Scanned seismicity map of the State of Utah, Map MF-1856.
 UDOTMap_MajorRoads layer from Utah AGRC (<http://gis.utah.gov/download>).

Intermountain Regional Landfill

Figure Four
Seismicity



Permit Application




Explanation

- Well with water-level data
- Normal fault, concealed; bar and ball on downthrown side

Water-level contours

- Perched aquifer; contour interval 50 ft.
- Basin-fill aquifer; contour interval 50 ft.
- Bedrock aquifer; contour interval 100 ft.
- Saturated unconsolidated sediment

Highest priority for contouring was given to 52 water levels measured in March 2005, secondary priority was given to 26 levels measured between October 2004 and July 2005 tertiary consideration was given to 299 levels measured by drillers after well drilling. Data were primarily hand contoured.



Legend


Intermountain Regional Landfill Proposed Location

Intermountain Regional Landfill

Figure Five
Potentiometric Contours

Source:
Potentiometric Contours figure (Figure 3) from *Ground-Water Flow, Water-Level Trends, and the Connection Between Fairfield Spring and the Basin-Fill Aquifer in Cedar Valley, Utah County, North-Central Utah*, J. Lucy Jordan and Walid Sabbah, 2007 UGA Publication 36, G.C. Willis, M.D. Hylland, D. L. Clar, T. C. Chidsey, Jr., editors.

Permit Application




Legend

- Water Right Point-of-Diversion
- Intermountain Regional Landfill Proposed Location
- 2000-Foot Buffer

Data Sources:



WRPOD.shp from State of Utah, Department of Natural Resources, Division of Water Rights, December 2009.
<http://waterrights.utah.gov/gisinfo/wrcover.asp>



Intermountain Regional Landfill

Figure Six
Water Right Points-of-Diversion

Permit Application




INTERMOUNTAIN REGIONAL LANDFILL

2010 PERMIT APPLICATION

AUGUST 13, 2010

INDEX OF DRAWINGS

| | |
|--------------|--|
| CIVIL | |
| 01C-001 | COVER & INDEX |
| 01C-002 | GENERAL NOTES & ABBREVIATIONS |
| 01C-003 | SITE PLAN |
| 01C-004 | EXCAVATION LINER PLAN (CELL 1 PHASE 1) |
| 01C-005 | CELL 1 PHASING PLAN |
| 01C-006 | EXCAVATION LINER PLAN (ALL CELLS) |
| 01C-007 | FINAL COVER GRADING PLAN |
| 01C-008 | CROSS SECTIONS |
| 01C-009 | CROSS SECTIONS |
| 01C-010 | CROSS SECTIONS |
| 01C-011 | CROSS SECTIONS |
| 01C-012 | LEACHATE POND PLAN |
| 01C-013 | DETAILS |



| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | COVER |

| | |
|-----------------|-----------|
| PROJECT NUMBER | |
| PROJECT MANAGER | T. WARNER |
| DATE | 08/13/10 |

| | |
|--------------|------------|
| FILE NAME | 01C001.DWG |
| SCALE | 1"=1000' |
| SHEET NUMBER | 1 OF 13 |


GENERAL NOTES

- 1 COORDINATE SYSTEM IS BASED ON LOCAL SURVEY THE BENCHMARK TO BE USED FOR CONSTRUCTION IS LOCATED AS SHOWN ON DRAWING NO C3 EXISTING CONTOURS ARE BASED ON AERIAL SURVEY FLOWN NOVEMBER 18 2009 BY OLYMPUS AERIALS INC SALT LAKE CITY UTAH CURRENT GROUND ELEVATIONS MAY VARY FROM THOSE SHOWN
- 2 THE CONTRACTOR SHALL VERIFY EXISTING CONTOURS PRIOR TO THE START OF EARTHWORK
- 3 GROUNDWATER AT THE SITE MAY VARY DEPENDING ON STREAM FLOW RAINFALL AND SUBSURFACE CONDITIONS THERE SHALL NOT BE ANY ADDITIONAL PAYMENT OR EXTENSION OF CONTRACT TIME FOR WORKING WITH SATURATED SOILS OR HANDLING GROUNDWATER SEEPAGE
- 4 THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING LANDFILL FEATURES DURING THE CONSTRUCTION PERIOD THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE INCURRED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PROTECT EXISTING LANDFILL FEATURES
- 5 THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES HAVE NOT BEEN ESTABLISHED BY THE OWNER OR HIS REPRESENTATIVES THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING PROPER SAFE WORKING DISTANCE FROM ALL UTILITY EASEMENTS
- 6 EXCAVATION BY "BLASTING" IS NOT PERMITTED ON THIS PROJECT
- 7 FINISHED GROUND ELEVATIONS SHALL MATCH EXISTING GROUND ELEVATIONS EXCEPT AS SHOWN ON THE PLANS EXCESS SOIL FROM EXCAVATION AND GRADING SHALL BE PLACED IN DESIGNATED STOCKPILE LOCATIONS AS APPROVED BY THE OWNER TRANSPORT OF SOIL TO FILL AREAS SHALL BE CONDUCTED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER
- 8 GEOTECHNICAL INVESTIGATION REPORTS FOR THE SITE ARE AVAILABLE FOR REVIEW UPON THE REQUEST OF HDR ENGINEERING THE CONTRACTOR MAY PERFORM ADDITIONAL GEOTECHNICAL INVESTIGATIONS AS HE DEEMS NECESSARY FOR CONSTRUCTION ACTIVITIES HOWEVER THERE SHALL BE NO ADDITIONAL PAYMENT TO THE CONTRACTOR FOR ADDITIONAL GEOTECHNICAL INVESTIGATIONS
- 9 THE CONTRACTOR SHALL CONSTRUCT AND UPON COMPLETION OF THE PROJECT REMOVE TEMPORARY CONSTRUCTION ACCESS ROADS SUCH ROADS SHALL BE LOCATED AS APPROVED BY THE OWNER DRAINAGE PATTERNS AT THE SITE SHALL NOT BE ALTERED BY ROAD CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION AND MAINTENANCE OF TEMPORARY DRAINAGE STRUCTURES INCLUDING CULVERTS AT NO ADDITIONAL COST TO THE OWNER
- 10 THE CONTRACTOR SHALL CREATE SWPPP AND SUBMIT TO ENGINEER AND OWNER FOR APPROVAL THE CONTRACTOR SHALL OBTAIN A UPDES PERMIT FOR LANDFILL CONSTRUCTION REFER TO TECHNICAL SPECIFICATIONS
- 11 THE CONTRACTOR SHALL INSTALL MAINTAIN AND UPON COMPLETION OF THE PROJECT REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS IN ACCORDANCE WITH THE SITE SWPPP AND PURSUANT TO REQUIREMENTS SUCH CONTROLS SHALL BE PLACED AT THE LIMITS OF DISTURBED AREAS AND AT INTERMEDIATE LOCATIONS WHERE CONCENTRATED FLOW IS LIKELY
- 12 THE CONTRACTOR SHALL KEEP THE LANDFILL HAUL ROAD OPERATIONAL AT ALL TIMES THE CONTRACTOR SHALL SUBMIT A SCHEDULE TO THE OWNER FOR REVIEW AND APPROVAL 72 HOURS PRIOR TO CONDUCTING OPERATIONS THAT MAY AFFECT OPERATION OF THE LANDFILL ACCESS ROADS
- 13 TEMPORARY CONSTRUCTION SLOPES SHALL NOT BE GREATER THAN 2H 1V STEEPER SLOPES WILL ONLY BE ALLOWED IF THE CONTRACTOR PROVIDES A GEOTECHNICAL ENGINEERING REPORT SPECIFYING MAXIMUM SLOPES AND THE DURATION FOR WHICH SUCH SLOPES SHALL REMAIN IN PLACE
- 14 THE CONTRACTOR SHALL REMOVE ALL VEGETATION WITHIN THE CONSTRUCTION LIMITS AS REQUIRED TO CONSTRUCT THE PROJECT ALL VEGETATION MAY BE DISPOSED OF ON-SITE AS DIRECTED BY THE OWNER
- 15 THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER ANY ERROR OR DISCREPANCY FOUND ONCE THE CONTRACT DOCUMENT IS CAREFULLY REVIEWED AND ALL ASPECTS OF FIELD WORK HAVE BEEN VERIFIED IN THE EVENT THE CONTRACTOR CONTINUES TO WORK ON AN ITEM WHERE AN ERROR EXISTS IT SHALL BE DEEMED THAT THE CONTRACTOR BID AND INTENDED TO EXECUTE THE MORE STRINGENT OR HIGHER QUALITY REQUIREMENT WITHOUT AN INCREASE IN CONTRACT SUM OR TIME THE CONTRACTOR SHALL ALSO BE RESPONSIBLE TO CORRECT ANY FAILURE OF PARTS TO COORDINATE OR FIT PROPERLY INTO FINAL POSITION AS A RESULT OF CONTRACTOR FAILURE TO RAISE OR RESOLVE A DISCREPANCY
- 16 THE DRAWINGS AND SPECIFICATIONS SHOULD AGREE WITH EACH OTHER AND WORK CALLED FOR BY DRAWINGS AND NOT MENTIONED IN SPECIFICATIONS OR VICE VERSA SHALL BE FURNISHED BY BOTH WHEN DISCREPANCIES EXIST BETWEEN SCALE AND DIMENSIONS THE DIMENSIONED FIGURE SHALL BE USED IF DISCREPANCIES EXIST BETWEEN THE DRAWINGS AND SPECIFICATIONS THE CONTRACTOR SHALL NOT WORK WITHOUT CLARIFICATION FROM ENGINEER AND RESOLUTION BY OWNER THE OWNER'S DECISION ON THE RESOLUTION IS FINAL
- 17 CONTRACTORS AND EACH SUB CONTRACTOR SHALL VERIFY ALL GRADES LINES LEVELS AND DIMENSIONS AS INDICATED ON DRAWINGS AND HE SHALL REPORT ERRORS TO THE ENGINEER THE CONTRACTOR SHALL ESTABLISH BENCHMARKS IN AT LEAST TWO WIDELY SEPARATED PLACES AND AS WORK PROGRESSES THE CONTRACTOR WILL MAINTAIN ADEQUATE HORIZONTAL AND VERTICAL CONTROL

STANDARD ABBREVIATIONS


| | | | |
|--------|--|-------|--------------------------------------|
| & | AND | MIN | MINIMUM |
| APPROX | APPROXIMATELY | MW | MONITOR WELL |
| ASPH | ASPHALT | MSL | MEAN SEA LEVEL |
| ⊙ | AT | N | NORTH |
| AVG | AVERAGE | NIC | NOT IN CONTRACT |
| BOE | BOTTOM OF EXCAVATION | NO | NUMBER |
| BM | BENCHMARK | NTS | NOT TO SCALE |
| BOL | BOTTOM OF LINER | OC | ON CENTER |
| X | BY | OZ | OUNCE |
| BLDG | BUILDING | ⌘ | PERCENT |
| CL | CENTERLINE | PLCP | PERFORATED LEACHATE COLLECTION PIPE |
| CMP | CORRUGATED METAL PIPE | PERF | PERFORATED |
| CO | CLEAN OUT | PGV | PASSIVE GAS VENT |
| CFS | CUBIC FEET PER SECOND | PC | POINT OF CURVATURE |
| CY | CUBIC YARD | PVI | POINT OF VERTICAL INTERSECTION |
| DIA | DIAMETER | PT | POINT OF TANGENCY |
| DET | DETAIL | PZ | PIEZOMETER |
| DWG | DRAWING | Q | FLOW |
| ELEV | ELEVATION | QTY | QUANTITY |
| EXIST | EXISTING | R | RADIUS |
| EXC | EXCAVATION | RCP | REINFORCED CONCRETE PIPE |
| FL | FLOW LINE | REF | REFERENCE |
| FML | FLEXIBLE MEMBRANE LINER | REQ | REQUIRED |
| FT | FEET | RD | ROAD |
| G | GAS PROBE | SCH | SCHEDULE |
| GAL | GALLON | SDL | SAND DRAINAGE LAYER |
| GND | GROUND | SEC | SECTION |
| GCL | GEOCOMPOSITE LINER | SHT | SHEET |
| GCGL | GEOCOMPOSITE DRAINAGE LAYER | S | SOUTH |
| GDL | GRAVEL DRAINAGE LAYER | SDR | STANDARD DIMENSION RATIO |
| GLER | GEOMEMBRANE LINER EVALUATION REPORT | SP | STEEL PIPE |
| GNDL | GEONET DRAINAGE LAYER | SQ | SQUARE |
| GP | GAS PROBE | STA | STATION |
| HDPE | HIGH DENSITY POLYETHYLENE | SLER | SOIL LINER EVALUATION REPORT |
| HORIZ | HORIZONTAL | SLQCP | SOIL LINER QUALITY CONTROL PLAN |
| ID | INSIDE DIAMETER | SS | SIDE SLOPE |
| IN | INCHES | SWPPP | STORMWATER POLLUTION PREVENTION PLAN |
| IE | INVERT ELEVATION | TL | TANGENT LENGTH |
| LCRS | LEACHATE COLLECTION AND REMOVAL SYSTEM | TOC | TOP OF COVER |
| LCS | LEACHATE COLLECTION SYSTEM | TOFC | TOP OF FINAL COVER |
| LCP | LEACHATE COLLECTION PIPE | TOL | TOP OF LINER |
| LCPR | LEACHATE COLLECTION PIPE RISER | TOS | TOE OF SLOPE |
| LF | LINEAR FEET | TS | TOP SLOPE |
| LFG | LANDFILL GAS | TEMP | TEMPORARY |
| LB | POUND | TYP | TYPICAL |
| LG | LONG | VCP | VITRIFIED CLAY PIPE |
| MH | MANHOLE | VERT | VERTICAL |
| MAX | MAXIMUM | VLDPE | VERY LOW DENSITY POLYETHYLENE |
| MIL | 001 INCHES | W | WEST |
| | | W/ | WITH |
| | | YD | YARD |

SYMBOLS



| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | GENERAL NOTES & ABBREVIATIONS |

| | |
|-----------------|--------------|
| PROJECT NUMBER | FILE NAME |
| | 010002 DWG |
| PROJECT MANAGER | SCALE |
| T WARNER | NTS |
| DATE | SHEET NUMBER |
| 08/13/10 | 2 OF 13 |



LEGEND

- 4640-- EXISTING CONTOURS
- CELL FOOTPRINT BOUNDARY (APPROX)
- PROPOSED LEACHATE DRAIN LINE
- PROPOSED INTERIM ACCESS CONTROL FENCE
- (MW) DEEP MONITORING WELL
- DMW-X DEEP MONITORING WELL NUMBER
- TMW-X TEMPORARY MONITORING WELL NUMBER

| BENCHMARKS | | | |
|------------|------------|------------|-----------|
| BM | N | E | ELEVATION |
| 6633 | 7248525 12 | 1477769 21 | 4854 44 |
| 6634 | 7248548 22 | 1480525 47 | 4847 01 |
| 6635 | 7243228 01 | 1480465 01 | 4850 36 |
| 6636 | 7243237 28 | 1477796 04 | 4852 51 |
| 6637 | 7245907 75 | 1477851 32 | 4854 87 |
| 6638 | 7245968 82 | 1480470 15 | 4847 96 |

NOTES
 EXISTING TOPOGRAPHIC DATA IS PROVIDED BY OLYMPUS AERIAL SURVEYS, INC, NOVEMBER 18, 2009



| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | SITE PLAN |


| | |
|-----------------|--------------|
| PROJECT NUMBER | FILE NAME |
| | 01C003 DWG |
| PROJECT MANAGER | SCALE |
| T WARNER | 1"=400' |
| DATE | SHEET NUMBER |
| 08/13/10 | 3 OF 13 |



0 100 200
SCALE IN FEET

LEGEND



- 4640-- EXISTING CONTOURS
- CELL FOOTPRINT BOUNDARY (APPROX)
- PROPOSED LEACHATE DRAIN LINE



| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | EXCAVATION LINER PLAN CELL 1 PHASE 1 |

| | |
|-----------------|----------|
| PROJECT NUMBER | |
| PROJECT MANAGER | T WARNER |
| DATE | 08/13/10 |


| | |
|--------------|------------|
| FILE NAME | 010004 DWG |
| SCALE | 1"=100' |
| SHEET NUMBER | 4 OF 13 |



CELL 1 PHASE 1

CELL 1 PHASE 2


CELL 1 PHASE 3





| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | CELL 1 PHASING PLAN |

| | |
|-----------------|----------|
| PROJECT NUMBER | |
| PROJECT MANAGER | T WARNER |
| DATE | 08/13/10 |

| | |
|--------------|------------|
| FILE NAME | 010005 DWG |
| SCALE | 1"=300' |
| SHEET NUMBER | 5 OF 13 |



FUTURE LEACHATE SUMP FUTURE LEACHATE SUMP FUTURE LEACHATE SUMP




| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | EXCAVATION LINER PLAN ALL CELLS |

| | |
|-----------------|----------|
| PROJECT NUMBER | |
| PROJECT MANAGER | T WARNER |
| DATE | 08/13/10 |

| | |
|--------------|------------|
| FILE NAME | 010006 DWG |
| SCALE | 1"=400' |
| SHEET NUMBER | 6 OF 13 |






REFER TO DETAIL 5
FOR FINAL COVER DESIGN C13



| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | FINAL COVER GRADING PLAN |


| | |
|-----------------|----------|
| PROJECT NUMBER | |
| PROJECT MANAGER | T WARNER |
| DATE | 08/13/10 |

| | |
|--------------|------------|
| FILE NAME | 010007 DWG |
| SCALE | 1"=400' |
| SHEET NUMBER | 7 OF 13 |




| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | CROSS SECTIONS |

| | |
|-----------------|--------------|
| PROJECT NUMBER | FILE NAME |
| PROJECT MANAGER | SCALE |
| DATE | SHEET NUMBER |
| | |




CROSS SECTION EAST-WEST
CELL 3



| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | CROSS SECTIONS |

| | |
|-----------------|------------|
| PROJECT NUMBER | 010009 DWG |
| PROJECT MANAGER | T WARNER |
| DATE | 08/13/10 |
| FILE NAME | 010009 DWG |
| SCALE | 1"=200' |
| SHEET NUMBER | 9 OF 13 |




CROSS SECTION NORTH-SOUTH
ALL CELLS




| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | CROSS SECTIONS |

| | |
|-----------------|----------|
| PROJECT NUMBER | |
| PROJECT MANAGER | T WARNER |
| DATE | 08/13/10 |

| | |
|--------------|------------|
| FILE NAME | 010010 DWG |
| SCALE | 1"=200' |
| SHEET NUMBER | 10 OF 13 |



CROSS SECTION NORTH-SOUTH
ALL CELLS




| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | CROSS SECTIONS |

| | |
|-----------------|--------------|
| PROJECT NUMBER | FILE NAME |
| PROJECT MANAGER | SCALE |
| DATE | SHEET NUMBER |
| | |



0 100 200
SCALE IN FEET



PROPOSED CELL 1 PHASE 1 LEACHATE
COLLECTION PIPE AND TRENCH PER
DETAILS

6,7
C13

-2.00%

PROPOSED INTERIM LEACHATE
POND VOLUME PROVIDED=
66,635 CUBIC FEET/

FUTURE LEACHATE PIPE

FINAL LEACHATE POND
TO BE CONSTRUCTED
AT A LATER DATE
(GRADING APPROXIMATE)

FINAL LEACHATE POND
TO BE CONSTRUCTED AT A LATER TIME
GRADING APPROXIMATE


INTERIM LEACHATE POND CELL 1 PHASE 1




| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | LEACHATE POND PLAN |

| | |
|-----------------|----------|
| PROJECT NUMBER | |
| PROJECT MANAGER | T WARNER |
| DATE | 08/13/10 |


| | |
|--------------|------------|
| FILE NAME | 01C012 DWG |
| SCALE | 1"=100' |
| SHEET NUMBER | 12 OF 13 |



TYPICAL LANDFILL LINER DETAIL 1
NOT TO SCALE




LINER SYSTEM ANCHOR TRENCH 2
NOT TO SCALE




LINER TERMINATION BERM 3
NOT TO SCALE

- NOTES.
- 1 TEMPORARY STORMWATER INTERCEPTOR BERM TO BE PLACED IN FRONT OF WORKING AREA TO DIVERT STORMWATER AWAY FROM ACTIVE FACE. OWNER WILL RELOCATE AS NEEDED
 - 2 SEE SPECIFICATION 02240 FOR PROTECTIVE COVER MATERIAL REQUIREMENTS


| LOCATION | GEOTEXTILE SCHEDULE |
|------------------|--|
| ALL | COMMENTS REMOVE ALL ANGULAR STONES GREATER THAN 0.5 DIAMETER |
| LOWER GEOTEXTILE | USE 16 OZ/SY NON WOVEN IF ROUNDED STONES GREATER THAN 2.5 ARE REMOVED USE 20 OZ/SY NON WOVEN IF ROUNDED STONES GREATER THAN 4 ARE REMOVED NO HORIZONTAL SEAMS ON SIDE SLOPES |
| UPPER GEOTEXTILE | USE 12 OZ/SY NON WOVEN BENEATH PROTECTIVE SOIL COVER |




INTERIM LEACHATE POND 4
NOT TO SCALE



FINAL COVER 5
NOT TO SCALE



8" DIAMETER PERFORATED LEACHATE COLLECTION PIPE 6
NOT TO SCALE



LEACHATE COLLECTION TRENCH 7
NOT TO SCALE

HDR

| | |
|---------------|--|
| PROJECT TITLE | INTERMOUNTAIN REGIONAL LANDFILL 2010 PERMIT APPLICATION |
| SHEET TITLE | DETAILS |

| | |
|-----------------|--------------|
| PROJECT NUMBER | FILE NAME |
| PROJECT MANAGER | SCALE |
| DATE | SHEET NUMBER |
| 08/13/10 | 13 OF 13 |


APPENDIX A

PLAN OF OPERATIONS

Div of Waste Management
and Radiation Control

MAR 02 2021

DSHW-2021-003598



INTERMOUNTAIN REGIONAL LANDFILL

PLAN OF OPERATIONS


(HAL Project No.: 373.02.101)

February 2021

INTERMOUNTAIN REGIONAL LANDFILL

PLAN OF OPERATIONS

(HAL Project No.: 373.02.101)



February 2021

TABLE OF CONTENTS

| | |
|--|-------------|
| TABLE OF CONTENTS | i |
| CHAPTER 1 - INTRODUCTION | 1-1 |
| CHAPTER 2 – EMERGENCY RESPONSE INFORMATION | 2-1 |
| CHAPTER 3 – BACKGROUND INFORMATION..... | 3-1 |
| 3.1 FIXED LANDFILL FEATURES | 3-1 |
| 3.2 LANDFILL EQUIPMENT..... | 3-1 |
| CHAPTER 4 – SCHEDULE OF CONSTRUCTION..... | 4-1 |
| CHAPTER 5 – SOLID WASTE HANDLING | 5-1 |
| 5.1 WASTE DISPOSAL..... | 5-1 |
| 5.2 PLACEMENT OF COVER SOILS..... | 5-1 |
| CHAPTER 6 – INSPECTIONS, MONITORING, AND REPORTING | 6-1 |
| 6.1 INSPECTIONS | 6-1 |
| 6.2 GROUNDWATER MONITORING..... | 6-1 |
| 6.3 LANDFILL GAS MONITORING | 6-3 |
| CHAPTER 7 – CONTINGENCY AND CORRECTIVE ACTION PLANS | 7-1 |
| 7.1 FIRE | 7-1 |
| 7.1.1 FIRE IN A LOADED VEHICLE..... | 7-1 |
| 7.1.2 FIRE ON THE WORKING FACE OR BELOW COVER..... | 7-1 |
| 7.2 EXPLOSION..... | 7-2 |
| 7.3 FAILURE OF RUN-OFF/RUN-ON STRUCTURES | 7-2 |
| 7.3.1 FAILURE OF RUN-OFF STRUCTURES | 7-2 |
| 7.3.2 FAILURE OF RUN-ON STRUCTURES | 7-2 |
| 7.4 RELEASE OF EXPLOSIVE GASES | 7-3 |
| 7.5 GROUNDWATER CONTAMINATION | 7-3 |
| CHAPTER 8 – CONTROL OF NUISANCE CONDITIONS..... | 8-1 |
| 8.1 FUGITIVE DUST | 8-1 |
| 8.2 LITTER..... | 8-1 |
| 8.3 RODENT CONTROL..... | 8-1 |
| 8.4 BIRD CONTROL | 8-2 |
| CHAPTER 9 – ALTERNATIVE WASTE-HANDLING PROCEDURES | 9-1 |
| CHAPTER 10 – MONITORING PROCEDURES..... | 10-1 |
| 10.1 GENERAL | 10-1 |
| 10.2 GROUNDWATER MONITORING WELLS | 10-1 |
| 10.3 GAS MONITORING LOCATIONS | 10-1 |
| CHAPTER 11 – WASTE-SCREENING PROCEDURES..... | 11-1 |
| CHAPTER 12 – TRAINING PROGRAM | 12-1 |

APPENDIX A
Inspection Form

LIST OF TABLES

| | | |
|-----------|------------------------------------|-----|
| Table 2-1 | Emergency Phone Numbers | 2-1 |
| Table 2-2 | Landfill Contact Information | 2-1 |
| Table 2-3 | Landfill Equipment | 3-1 |
| Table 6-1 | Inspections..... | 6-1 |

LIST OF FIGURES

| | | |
|-----------|--|-----|
| Table 6-1 | Utah Requirements for Groundwater Monitoring | 6-2 |
|-----------|--|-----|

CHAPTER 1 - INTRODUCTION

The purpose of this Plan of Operations is to assist the Landfill Operations Manager and operating personnel in conducting day-to-day operations in a manner that is consistent with the various permit requirements and with the design of the Intermountain Regional Landfill. The Plan describes the following: emergency response procedures, permit conditions, designed facilities at the landfill, equipment, personnel requirements for proper operation, procedures for waste handling, requirements for inspections, monitoring, and reporting, contingency plans and corrective action programs, alternative waste handling, maintenance of landfill monitoring equipment, vector control, waste screening to exclude hazardous wastes and a general training program for landfill operators.

CHAPTER 2 – EMERGENCY RESPONSE INFORMATION

Landfill emergencies include injury, dismemberment, or death of personnel, and fire, explosion, or other catastrophic events. Because of its remote location, the landfill maintains its own fire protection equipment for building and equipment, and personnel are trained in the operation of this equipment. Landfill fires at the surface will be controlled by using soil to smother any fires. A water truck will also be available to supplement fire suppression activities. Because of the landfill's remote location, injured personnel will be transported to medical facilities in landfill vehicles if their condition allows movement. The Operations Manager or his designee may request that ambulance and paramedical personnel meet the transporting vehicle en route to the medical facility.

Table 2-1 below lists the phone numbers to access emergency services for other emergencies. This list is posted directly adjacent to each phone on the facility site in a colorless, protective plastic cover.

**TABLE 2-1
EMERGENCY PHONE NUMBERS**

| Emergency Service Provider | Emergency Phone Number | Direct Phone Number |
|-------------------------------------|-------------------------------|----------------------------|
| Fire and Rescue | 911 | |
| Hospital | 911 | |
| Utah Valley Regional Medical Center | | (801) 371 7001 |
| Mountain View Hospital | | (801) 465 7190 |
| Utah County Fire Marshal | | (801) 370 8885 |
| Sheriff | | (801) 375 3601 |
| Office | | (801) 403 7651 |

In the event of any emergency, the personnel in Table 2-2 will also be notified. Landfill personnel will also be provided with 2-way radios for communicating while on site.

**TABLE 2-2
LANDFILL CONTACT INFORMATION**

| Name | Title | Phone |
|----------------|--------------------|----------------|
| Rob Richards | President | (801) 403-7651 |
| Brian Alba | Operations Manager | (801) 865-2624 |
| Mason Lyman | Scale Attendant | (435) 633-5643 |
| Mike Vano | Operator | (801) 735-8677 |
| Gibby McDougal | Operator | (801) 618-6722 |

CHAPTER 3 – BACKGROUND INFORMATION

3.1 FIXED LANDFILL FEATURES

The overall site plan consists of three main cells with each containing its own leachate collection system, sump and leachate withdrawal system. Cells 2 and 3 are both similar in design which drain down the center of the cell to a sump located on the far east end of the cell floor. Cell 1 differs because it included the 20-acre area that has already been developed. The design of Cell 1 was altered in 2016 with a sump located on the north side because the previous design placed the floor trajectory toward the east which would have made the excavation much deeper.

The landfill includes a scale house and administrative office. An all-weather access road exists from the entrance to the area of the first landfill cell. Temporary internal access roads are constructed and rerouted as waste is placed and fill grades change. Other ancillary features include perimeter access control fencing and environmental monitoring equipment.

3.2 LANDFILL EQUIPMENT

Table 3-1 presents the equipment currently in use for landfill operations. Compactors and dozers are used to move and compact waste disposed at the landfill and for placing daily and intermediate cover. Dozers and loaders are used for general site operating activities such as road maintenance, embankment construction, and snow removal. The track excavator will be used to excavate landfill units, maintain runoff and run-on controls, and load the haul truck, which will haul materials within the site. The water truck will be used for dust control and the recycling of leachate, if needed. There are several generators on site to provide power to support facilities.

**TABLE 3-1
LANDFILL EQUIPMENT**

| Type | Model |
|------------------------------|-----------------------|
| Compactor | CAT 836K (4) |
| Dozer | CAT D8T |
| Track Excavator | CAT 349E, Volvo 330B |
| Haul Truck | CAT 740B (2), CAT 735 |
| Motor Grader | CAT 140M |
| Loader | CAT 950H |
| Vibratory Compactor | CAT |
| Allmand Light Plants | (3) |
| Whisper Watt Generator | (2) |
| Water Truck | (2) |
| Portable Landfill Tipper | (2) |
| Service Truck/Mechanic Truck | - |

CHAPTER 4 – SCHEDULE OF CONSTRUCTION

The Intermountain Regional Landfill consists of a single municipal landfill divided into 3 cells that are constructed in phases. The final phases of Cell 1 will be constructed in the coming years with a shift to phased construction of Cell 2 thereafter. Construction of Cell 3 is not expected to occur for some time.

A Gas Collection and Control System (GCCS) is currently in design and is set to be installed and operational by February 28, 2022. Expansion of the GCCS will occur in phases as waste is placed.

CHAPTER 5 – SOLID WASTE HANDLING

5.1 WASTE DISPOSAL

All waste entering the site will be weighed and weights recorded. Customers will be directed to the working face where the driver will be instructed to discharge the load. Landfill operations personnel will push the solid waste down the working face using a compactor. The waste will be placed in lifts with a loose thickness of 2 to 3 feet. After the waste has been placed in loose lifts, the operator will run the compactor over all parts of the lift at least two times parallel with the slope. These general procedures may change depending on site conditions, current lift height, weather, waste type, etc. Equipment operators will also maintain the working face so that it is as small as practical to allow efficient unloading of transfer trucks and placing and compacting of solid wastes.

5.2 PLACEMENT OF COVER SOILS

Cover soils will be placed over solid wastes to minimize the potential for nuisance conditions, fire, and contact between disease vectors and solid wastes. Nuisance conditions include odor generation and air discharges, blowing of plastic and paper wastes, and other conditions that impair the use of adjoining properties.

At the end of each working day, the landfill operations personnel will cover all solid wastes received during that day with daily cover. The daily cover will consist of a minimum of 6 inches of soil excavated from other parts of the landfill site. Daily cover will be placed to minimize the nuisance, fire, and disease vector potential attributable to each day's waste placement.

Whenever part of the landfill cell will be inactive for an extended period, landfill operations personnel will place an intermediate cover over the inactive part. The intermediate cover will reduce the potential for wind- and water-induced erosion of the cover and will reduce the production of leachate and contact stormwater within the landfill cell. The intermediate cover will consist of 6 additional inches of soil on the daily cover.

CHAPTER 6 – INSPECTIONS, MONITORING, AND REPORTING

6.1 INSPECTIONS

The Operations Manager is responsible for conducting and recording routine inspections of landfill facilities. The schedule for conducting routine inspections is provided in Table 6-1. Forms for recording routine inspections are presented in Attachment A. The Operations Manager is responsible for verifying the completeness of the inspection records on a quarterly basis.

**TABLE 6-1
INSPECTIONS**

| Landfill Facility | Inspection | Frequency |
|---|--|---|
| Landfill Cell | Daily and intermediate cover integrity Stormwater and leachate collection (surface ponding) | Daily Daily |
| Leachate Pond (not constructed yet as of 2021) | Perimeter fence integrity Water depth Liner system integrity Water volume | Daily Weekly Weekly Quarterly |
| Other Appurtenances | Entrance/main gate integrity Perimeter fence integrity Monitoring well integrity Equipment maintenance Site road integrity Berm integrity | Daily Weekly Monthly Monthly Quarterly Quarterly |

6.2 GROUNDWATER MONITORING

The Groundwater Monitoring Plan is included in the Permit Application as Appendix G. As specified in the Utah Department of Environmental Quality (UDEQ) regulations (R315-308-2(4)(a)) and Subtitle D (40 Code of Federal Regulations [CFR] 258.53) regulations, background data for the detection monitoring constituents were established on all monitoring wells. Background data was generated by sampling the monitoring wells on a monthly basis after construction. To provide an acceptable level of confidence in the data, a minimum of eight samples were collected and analyzed to establish background concentrations. The groundwater data will be maintained in a database and used as the foundation for determining statistically significant increases during assessment monitoring, described below.


During assessment monitoring, groundwater samples will be collected semiannually. The results will be entered into a database and the data reviewed to determine if a statistically significant increase has occurred. If a statistically significant increase in groundwater contaminants is detected as part of the Detection Monitoring Program, the Intermountain Regional Landfill will initiate the following actions.

- Notify UDEQ in writing within 14 days of obtaining laboratory results. The notification will include identification of the constituents that have shown a statistically significant increase.

- Enter the laboratory results into the operating record for the landfill.
- Immediately resample the groundwater in all wells, or a subset of the wells as specified by the Director, for all constituents listed in R315-308-4. Determine whether a statistically significant change has occurred such that the groundwater protection has been compromised.
- If a statistically significant change has occurred, notify UDEQ within 7 days of receipt of the results of the resampling.

Figure 6-1 below summarizes the requirements imposed on the Intermountain Regional Landfill by UDEQ regulations to define the nature and extent of groundwater contamination and to take corrective action if the source of the groundwater contamination is the landfill.

**FIGURE 6-1
UTAH REQUIREMENTS FOR GROUNDWATER MONITORING**



6.3 LANDFILL GAS MONITORING

Explosive gas monitoring is completed on a quarterly basis. A handheld multi-gas monitor device is used to monitor explosive gases. Monitoring locations include the entire waste mound with particular attention to the working face and the bottom toe as well as enclosed structures such as the scale house, offices and maintenance shop. If concentrations of explosive gas exceed either the 25% of the lower explosive limit standard for facility structures or the lower explosive limit at the property boundary and beyond, IRL will implement mitigation measures so that levels do not exceed allowable limits.

A Gas Collection and Control System (GCCS) is currently in design and is set to be installed and operational by February 28, 2022. Expansion of the GCCS will occur in phases as waste is placed. The operation, inspection and monitoring of the GCCS will comply with the Title V permit and Utah Division of Air Quality requirements.

CHAPTER 7 – CONTINGENCY AND CORRECTIVE ACTION PLANS

The following sections describe the contingency and corrective action plans that will be implemented if fire, explosion, failure of run-off/run-on structures, release of explosive gases, or contamination of groundwater occurs.

7.1 FIRE

No burning of wastes is planned in the active landfill cell area. Limited burning may be planned, permitted, and accomplished when the construction area for a new landfill cell is cleared and when perimeter fences and drainage channels are maintained. No other burning activities are planned at the Intermountain Regional Landfill.

Two other types of fires - fires in loaded vehicles and fires in disposed wastes – must be anticipated and response activities planned. Each of these is discussed below. The preferred method of fighting fires in the Intermountain Regional Landfill will be smothering the fire with soil. Water will contribute to the formation of leachate and should be used only as a last resort if the fire cannot be smothered.

7.1.1 FIRE IN A LOADED VEHICLE

If a transport vehicle enters the landfill site carrying a burning or smoldering load of waste, landfill operations personnel will take the following actions.

- Direct the vehicle to a designated section of the landfill away from the working face. Direct the driver to deposit his load and to clear the area as quickly as possible.
- Immediately cover the burning waste with enough soil to completely smother the fire. Allow the waste to cool for several days, or longer if necessary.
- If necessary, spray equipment and the transfer vehicle with water to cool the equipment while working the fire. This will not be necessary if the equipment is pushing or dumping soil on the burning wastes in front of the advancing equipment.
- If landfill operations personnel cannot control the fire, contact the County Fire Marshal.
- Notify UDEQ immediately and provide written documentation within 14 days of the fire.

7.1.2 FIRE ON THE WORKING FACE OR BELOW COVER

In the event of a working face fire or a fire below cover, landfill operations personnel will take the following actions.

- Evacuate all nonessential personnel from the area of the fire. Nonessential personnel include transfer truck drivers, laborers/spotters, and visitors.
- To the extent possible, isolate the burning material from other wastes. Use compactor blades and dozers to move the burning materials away from other wastes, this might not be possible if the fire is below cover soil.
- Immediately cover the burning waste with enough soil or water to completely smother the fire. Allow the waste to cool for several days, or longer if necessary.

- If necessary, spray equipment and the transfer vehicle with water to cool the equipment while working the fire. This will not be necessary if the equipment is pushing or dumping soil on the burning wastes in front of the advancing equipment.
- If landfill operations personnel cannot control the fire, contact the County Fire Marshal.
- Notify UDEQ immediately and provide written documentation within 14 days of the fire.

7.2 EXPLOSION

If an explosion occurs at the landfill or in any structure associated with the landfill, landfill operations personnel will take the following actions:

- Immediately evacuate the area surrounding the explosion, including any adjacent buildings. Shut down and abandon any equipment near the explosion that is hot and that could provide an ignition source for additional explosions.
- Account for all personnel Contact the County Fire Marshal and the emergency dispatcher (911). Contact the General Manager
- Keep people from entering the explosion area until emergency response personnel clear the area
- Notify UDEQ immediately and provide written documentation within 14 days of the explosion

7.3 FAILURE OF RUN-OFF/RUN-ON STRUCTURES

Failure of run-off structures can allow contaminated water to be released into the environment. Failure of run-on structures can allow stormwater to mingle with waste and become leachate. Neither of these conditions is desirable.

7.3.1 FAILURE OF RUN-OFF STRUCTURES

If a failure of run-off structures is discovered during routine or non-routine inspections, landfill operations personnel will take the following actions.

- As soon as practical, suspend acceptance of wastes at the landfill, if necessary, and inform customers of this suspension
- Use landfill compactor and dozer equipment to construct temporary berms to contain the run-off. Divert the flow of run-off water away from surface water drainage ditches.
- Resume landfilling operations as soon as possible after the run-off is contained. Inspect the temporary berms at least once every 2 hours.
- Assess the impact of the release of run-off as soon as practicable following the event. Assess the need for permanent improvements in temporary berms, or other run-off control structures, as soon as practicable after the run-off is controlled.
- Notify UDEQ immediately and provide written documentation within 14 days of the failure.

7.3.2 FAILURE OF RUN-ON STRUCTURES

Failure of run-on control structures can temporarily overload the leachate collection system but is generally less serious than failure of run-off control structures. If failure of run-on control structures is discovered during routine or non-routine inspections, landfill operations personnel will take the following actions.

- Immediately mobilize landfill compactor or dozer equipment to construct temporary berms, swales, or other structures to temporarily divert surface.
- Water run-on from the active landfill cell. Assess the need to suspend acceptance of waste.
- As soon as practicable, assess the need for permanent run-on control structures
- Notify UDEQ immediately and provide written documentation within 14 days of the failure.

7.4 RELEASE OF EXPLOSIVE GASES

It is unlikely that explosive gas will be released from the Intermountain Region Landfill. However, it is possible that landfill gas concentrations will exceed the regulatory requirements in one or more gas-monitoring locations during the life of the landfill. For the purpose of this contingency plan, a release is defined as the detection of more than 25% of the lower explosive limit (LEL) in a landfill building, or more than 100% LEL at the property boundary. The LEL is 5% by volume of methane in the air. If a release of explosive gases is detected, landfill operations personnel will take the following actions.

- Immediately suspend landfilling operations and determine if landfill personnel or structures are threatened. If so, evacuate personnel immediately and open building doors to allow gases to escape.
- As soon as possible, determine if off-site buildings or other structures are threatened. If so, immediately notify the County Fire Marshal.
- Monitor the release area, and all other landfill gas monitoring locations, until the emergency condition has been eliminated.
- Determine temporary corrective actions as soon as possible, and permanent corrective actions as soon as practicable, after detection of the release.
- Notify UDEQ immediately and provide written documentation within 14 days of the release event.

7.5 GROUNDWATER CONTAMINATION

Contingency and corrective actions plans will be developed after groundwater contamination is detected. Refer to Figure 6-1 for the required workflow.

CHAPTER 8 – CONTROL OF NUISANCE CONDITIONS

8.1 FUGITIVE DUST

Fugitive dust from the working area will be controlled by timely placement of daily, intermediate, or final cover. Haul roads will be maintained by maintaining positive drainage and removing excessive trackout on paved roads within the property boundary and on entrance roads. Sprayed water or a dust palliative will be applied if operators notice that dust is migrating off-site. Disturbed areas not immediately needed for landfill operations will be revegetated if they are causing excessive dust.

8.2 LITTER

The methods to reduce litter in and near the Intermountain Regional Landfill include the following:

- Intermountain Regional Landfill will encourage customers to deliver in covered loads. Potential methods include placing signs along the main road to the landfill, a scaled pricing structure for self-haul customers (uncovered loads will be charged more), and educational campaigns, if needed due to complaints. Commercial vehicles will be required to deliver only covered loads.
- Operators will minimize the working face. This will reduce the waste surface area that is exposed to wind and reduce the potential for winds to transport of the active Cell.
- Operators will placement of daily cover as soon as practical
- Mobile litter control fencing will be placed near the working face to capture as much windblown litter as possible.
- Active cleanup of windblown litter will be conducted within the property boundary as part of the daily operation. Periodically, Intermountain Regional landfill operators will inspect adjacent properties for litter that has migrated offsite.
- Intermountain Regional Landfill will maintain the 6-foot perimeter fencing in good repair and pick-up trash that has collected on the fence.

8.3 RODENT CONTROL

The primary method of rodent control is to eliminate conditions favorable for the reproduction of rodents through properly compacting wastes and placing daily cover. If landfill personnel see signs of rodents, more-frequent application of soils will be considered.

If the primary method of rodent control does not produce satisfactory results, the landfill operators might use poisoning. A poison control program must include the following conditions:

- Poison traps must be set by experienced, professional exterminators.
- Poison traps may be set only within areas of controlled access. This means the trapped area must be within the site's security fencing, and the security gates must be locked for the duration of the poisoning program whenever landfill personnel are not on-site.
- The Occupational Health and Safety Administration (OSHA) requires warning signs of acceptable color and size to be permanently fixed to the outside of the access gate

and fencing, at spacings not to exceed 150 feet, for the duration of the poisoning program. A minimum of one sign per side of the fence is required.

- Landfill personnel must conduct a daily inspection of each poison trap and must notify the professional exterminator if disruptions of any traps are noted.
- The professional exterminator must conduct periodic inspections of the poison traps.
- Written documentation of the poisoning program must be maintained at the maintenance building. The documentation must include the number and exact location(s) of the poison traps, the name of the poison(s) (including both chemical and brand name and a list of ingredients), the quantity of poison contained in each trap, and the medically accepted antidotes or treatments for the poison(s).
- The professional exterminator must submit monthly reports to the Operations Manager documenting the status of the poisoning program. The reports shall include the number and location of traps, the quantities of poison(s) used during the past month, and any changes in the program instituted during the past month.
- Poison supplies shall be stored on-site in a separate, locked, and properly labeled enclosure. Access to the poison shall be restricted to the professional exterminator, the general manager, or his designee.

8.4 BIRD CONTROL

As with rodent control, the primary method of controlling birds is to control the conditions favorable to their existence. The following methods will be used as needed:

- Minimize the size of the working face. This is the most effective method of controlling birds, since it reduces the area available for feeding. More-frequent cover and greater compaction of the waste can also minimize the opportunities for feeding.
- Minimize the accumulation of water in depressions, ponds, or other features near the active working face. The lack of water makes a landfill a less attractive feeding area for birds.
- Use noise or other frightening techniques. These techniques cause a short-term reduction in the number of birds feeding at a landfill.

If the primary methods do not produce satisfactory results, a destructive method of control might need to be implemented. Destructive methods could cause harm or death to some birds, and authorization must be obtained from local officials before implementing a destructive program.

CHAPTER 9 – ALTERNATIVE WASTE-HANDLING PROCEDURES

An all-weather road exists from the site entrance to the active cell. In the semi-arid climate of the Intermountain Regional Landfill site, experience has shown that precipitation has only a minor effect on the operation of the landfill. The owner does not believe that alternate waste-handling plans are necessary for the site to handle wet weather operations.

All reasonable caution and prudence will be exercised to not dispose of wastes during any unreasonable weather conditions. If unforeseen weather conditions occur, the Operations Manager, or his designee, will be informed and will coordinate any changes in operations. The Operations Manager will consider the system-wide requirements in determining what changes, if any, need to be made to operations at the landfill.

CHAPTER 10 – MONITORING PROCEDURES

10.1 GENERAL

The inspection schedule for groundwater monitoring wells and landfill gas monitoring stations is presented in Chapter 6, Inspections, Monitoring, and Reporting. The following section describes the more-detailed inspection and maintenance of these proposed landfill monitoring features.

10.2 GROUNDWATER MONITORING WELLS

All groundwater monitoring wells will be thoroughly inspected during each sampling event. The detailed inspections will note signs of deterioration or failure of the protective steel casing, the concrete pad and bollards, and the polyvinyl chloride (PVC) well casing and screen. If damage is discovered, the nature of the problem will be recorded and reported to the Operations Manager, who will make a decision to repair, replace, or abandon the well. This decision will be documented in the operating record for the landfill, and the required actions will be completed before the next scheduled monitoring event.

The monitoring well locations will be maintained on a routine basis. Weeds will be removed at least every 6 months, about 2 weeks before each scheduled sampling event. During the weed removal, landfill personnel will note any obvious indications that the well has been damaged in order to allow the Operations Manager to assess the situation.

10.3 GAS MONITORING LOCATIONS

Explosive gas monitoring locations generally include strategic areas around the waste mound, including the working face and bottom toe, as well as all structures on the property. The exterior access road around the facility is also monitored.

Gas monitoring locations for the GCCS are not yet established but will be determined once the system is operational. Monitoring locations will also be modified to meet site specific conditions as the landfill and GCCS expands. Regularly scheduled monitoring will occur as well as additional monitoring at installation and start-up of each phase of the GCCS to meet air quality requirements.

CHAPTER 11 – WASTE-SCREENING PROCEDURES

All vehicles entering the site will be stopped at the scale house. Scale attendants will inquire about the contents of the waste entering the site. If a customer is suspected to be carrying unacceptable materials, they will be turned away and directed to an appropriate facility that is permitted to receive the waste materials. After a vehicle leaves the scale, they are directed to the working face. Wastes unloaded at the tipping face will be inspected regularly by landfill operators trained to identify unacceptable materials. All personnel will receive periodic training in detecting wastes that are prohibited for disposal at the landfill. This training will consist of an initial training and annual refresher training. These personnel will conduct routine inspections and random load inspections.

Loads will be selected randomly for a more detailed inspection to detect illegal or inadvertently deposited materials. A location for waste screening will be designated on the active landfill cell. For more detailed random inspections, an unsuspecting collection or transfer vehicle will be directed to a waste screening area near the working face to unload. After being unloaded, waste will be spread with a dozer or compactor, or a 1-to-2-foot thickness, so that the majority of the load can be visually inspected. Information will be recorded on the general contents of the load as well as customer.

The Operations Manager will notify the Director of the Division of Waste Management and Radiation Control with the material type and quantity and the remedial actions taken for unacceptable waste. The Conditional Use Permit (Permit Application Appendix B) specified the following 11 categories of Unacceptable Waste.

- 'Hazardous waste' as defined in 40 CFR part 261, as such part may be amended and expanded from time to time, and in Utah Code Section 19-6-102(9) and the regulations promulgated there under as they may be amended and expanded from time to time,
- Any material that is now or hereafter defined by applicable Federal, State or Local Laws, regulation, or ordinance as radioactive, toxic, hazardous or extremely hazardous waste, excluding household hazardous waste and small quantity generator hazardous waste,
- Vehicle tires in excess of the amount of such tires permitted to be disposed of by applicable Federal, State or Local law, regulation, or ordinance,
- Lead acid batteries,
- Soils contaminated with hazardous, radioactive, or toxic wastes, or hazardous or toxic substances as such terms are defined by applicable Federal or State law or regulations,
- Asbestos, including the asbestiform varieties of serpentine (chrysolite), riebeckite (crocidolite), cummingtonite-grunerite, anthophyllite and actinolite-tremolite,
- Any material which contains asbestos ("ACM"), including asbestos waste from control devices, contaminated clothing, asbestos-waste material, materials used to enclose the work area during asbestos project, or bags or containers that previously contained asbestos,
- Dead animal carcasses in excessive amounts that will attract disease vectors,
- Any soils from coal mine sites, power plants, rail yards, and other industrial development sites and projects which may be removed as part of any voluntary or governmentally mandated environmental remediation plan or program,
- Infectious waste, medical waste, or sharps, and

- Any material whatsoever that the Permit or any Federal, State, or Local law, regulation, or ordinance may prohibit for disposal at the Landfill now or in the future. Any future prohibition shall not operate retroactively, however, as any material previously determined to be Acceptable Waste and disposed of at the Landfill shall not be a breach of updated regulations.


CHAPTER 12 – TRAINING PROGRAM

Landfill personnel will be trained according to the duties required by certain job categories. Training records will be submitted with annual landfill reports. In general personnel will receive one or more of the following:

- 'Hazardous Waste Operations and Emergency Response, pursuant to requirements of the Occupational Safety & Health Administration (OSHA)
- OSHA Safety Training
- First Aid Training
- Solid Waste Association of North America (SWANA) Manager of Landfill Operations (MOLO), which includes waste screening, leachate and gas management, and general information on landfill regulations.

APPENDIX A

Inspection Form



INTERMOUNTAIN REGIONAL LANDFILL

INSPECTION REPORT

Type of Inspection Daily / Weekly / Monthly / Quarterly / Semiannually (circle one)

Performed by _____ Date _____

Overall Condition

| | Satisfactory | | Comments or Corrective Action Needed |
|----------------------------------|--------------|-------|--------------------------------------|
| | Yes | No | |
| Structures & Roads | | | |
| Fences & Gates ¹ | _____ | _____ | _____ |
| Signage ¹ | _____ | _____ | _____ |
| Access Roads ¹ | _____ | _____ | _____ |
| Run-on Control ¹ | _____ | _____ | _____ |
| Dust Control ¹ | _____ | _____ | _____ |
| Landfill Operations | | | |
| Litter Control ¹ | _____ | _____ | _____ |
| Protective Cover ¹ | _____ | _____ | _____ |
| Daily Cover ¹ | _____ | _____ | _____ |
| Intermediate Cover ² | _____ | _____ | _____ |
| Final Cover ⁴ | _____ | _____ | _____ |
| Equipment ¹ | _____ | _____ | _____ |
| Runoff Control ¹ | _____ | _____ | _____ |
| Active Working Face ¹ | _____ | _____ | _____ |
| Vector Control ¹ | _____ | _____ | _____ |
| Leachate System ¹ | _____ | _____ | _____ |
| Weed Control ⁴ | _____ | _____ | _____ |
| Monitoring Wells ⁴ | _____ | _____ | _____ |
| Leachate Pond ² | _____ | _____ | _____ |

* Specify the work needed and the timeframe for completion

Key 1 = daily, 2 = weekly, 3 = monthly, 4 = quarterly, 5 = semiannually

Additional Comments

APPENDIX B

PROPERTY OWNERSHIP AND NOTICE OF INTENT

ENT 34181 2010 PC 1 of 2
Rodney D. Campbell
UTAH COUNTY RECORDER
2010 Apr 27 2 19 PM FEE 12.00 BY SS
RECORDED FOR STRONG AND HANW
ELECTRONICALLY RECORDED

Send Tax Notices To
ROC Fund Landfill Holdings, LLC
1240 East 2100 South, 1st Floor
Salt Lake City, UT 84106

WARRANTY DEED

INTERMOUNTAIN REGIONAL LANDFILL, LLC, a Utah limited liability company, Grantor of Utah County, Utah, hereby CONVEYS AND WARRANTS to ROC FUND LANDFILL HOLDINGS, LLC, a Nevada limited liability company, Grantee, of 1240 East 2100 South, 1st Floor, Salt Lake City, Salt Lake County, Utah 84106 for TEN DOLLARS and other good and valuable consideration, the following described tract of land in Utah County, State of Utah

The West half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian
(59 124 0001)


TOGETHER WITH any and all buildings, improvements, water rights, water shares, mineral rights and interests, and all rights-of-way, easements, privileges and appurtenances


SUBJECT TO

- 1 Trust Deed, dated effective March 12, 2009, recorded May 27, 2009 in the Utah County Recorder's Office, as Entry No 57940 2009, and
- 2 Easements, restrictions, and rights of way of record and general property taxes for the current year which remain unpaid to the date hereof

WITNESS, the hand of said Grantor this 22 day of April, 2010

INTERMOUNTAIN REGIONAL LANDFILL, LLC

By 
David M. Johnston, Manager

By 
Heam Johnston, Manager

August 19, 2010

Corporation of the Presiding Bishopric
50 E North Temple
Salt Lake City, UT 84150

Subject. Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Utah Trust Lands Administration
675 East 500 South
Salt Lake City, UT 84102

**Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed
Intermountain Regional Landfill in Fairfield, Utah**

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Myrna B Carter
13218 South 6200 West
Herriman, UT 84096

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Claude J & Evelyn M Curley
1409 Bryan Avenue
Salt Lake City, UT 84096

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Norbert A & Lorna A Martinez
1142 Randers Lane
Draper, UT 84020

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

John J & Julie Kolar
612 Glorietta Blvd
Lafayette, CA 94549

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Brent O Ault
510 North 1100 East
American Fork, UT 84003

Subject: Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Richard S Fullmer
2150 Willow Brook
Sandy, UT 84092

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Larry D & Sheena L Mitchell
8721 Oakwood Park
Sandy, UT 84094

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Melinda Word
P O Box 301
American Fork, UT 84003

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Don Kaufer
P O Box 301
American Fork, UT 84003

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc



Terry Warner, PE
Engineering Project Manager

Enclosure

August 19, 2010

Howard H & Oliver R Holmes
c/o Bonnie Kaufer
P O Box 301
American Fork, UT 84003

Subject Notice of Intent to Submit a Landfill Permit Application for the Proposed Intermountain Regional Landfill in Fairfield, Utah

Dear Property Owner

The Intermountain Regional Landfill (Landfill) is a proposed landfill near the town of Fairfield, Utah. Once permitted and constructed, the landfill would consist of a single municipal landfill that would be constructed in phases. The landfill site is on the west half of Section 16, Township 7 South, Range 2 West, Salt Lake Base and Meridian (Parcel ID 59 124 0001). Attached is a figure showing the location of the proposed landfill site.

The total area of the facility would be about 330 acres. Once the landfill is full, the top surface of the covered and vegetated landfill would be about 100 feet above the existing ground its highest point. The landfill would accept solid nonhazardous residential and commercial solid wastes, including yard wastes. The landfill would not accept liquid waste, burning materials, radioactive waste, or hazardous waste.

You have received this letter because Utah Solid Waste Permitting rules require that we notify landowners within 1,000 feet of the property boundary of our intent to submit a landfill permit application to the Utah Division of Solid and Hazardous Waste. The permit application is being prepared, and, once it is finalized, the Division will advertise a public comment period during which you can submit comments about the proposed landfill.

If you have any questions about the proposed landfill or the permitting process, please call me at (801) 743-7800.

Sincerely,
HDR Engineering, Inc




Terry Warner, PE
Engineering Project Manager

Enclosure




HDR Engineering Inc


3949 South 700 East
Suite 500
Salt Lake City, UT 84107 2594

Phone (801) 743 7800
Fax (801) 743 7878
www.hdrinc.com



Legend

-  Intermountain Regional Landfill Proposed Location
-  I-15
-  Road



**INTERMOUNTAIN REGIONAL
LANDFILL**

Proposed Location

Permit Application

APPENDIX C

CLASS III CULTURAL RESOURCES SURVEY

APPENDIX C

A Class III Cultural Resources Inventory for the Intermountain Regional Landfill Project, South of Fairfield, Utah County, Utah



Utah State Antiquities Project Number U-10-HK-0093p

Prepared by
HDR Engineering, Inc

HDR Cultural Resources Report 10-13
May 26, 2010

HDR

**A Class III Cultural Resources Inventory for
the Intermountain Regional Landfill Project,
South of Fairfield, Utah County, Utah**

Prepared for

Fairfield Town and ROC Fund Landfill Holdings, LLC

Prepared by

**Mark Brodbeck, M A RPA
Principal Investigator**

**HDR Engineering, Inc
3949 South 700 East, Suite 500
Salt Lake City, UT 84107-2386**

**Under the Authority of
State of Utah Archaeological Survey Permit 170
Utah State Antiquities Project Number U-10-HK-0093p**

Abstract

HDR Engineering (HDR) conducted a Class III pedestrian inventory for cultural resources for the proposed Intermountain Regional Landfill Project south of Fairfield in Utah County, Utah. The proposed project site includes 320 acres of private land in the western half of Section 16 of Township 7 South, Range 2 West, Great Salt Lake Base and Meridian. The project area is currently undeveloped except for a few hundred feet at its western edge, which has been developed as an agricultural field. The project would be privately funded.

The proposed landfill project requires compliance with the Utah Division of Solid and Hazardous Waste's Administrative Code Rule R315, which requires a project proponent to identify historical and archaeological resources that could be affected by a new or expanded landfill facility (R315-310-3[1][k]). Furthermore, because the project requires permitting by the Utah Department of Environmental Quality (UDEQ), it also must comply with Utah Code Annotated 9-8-404, which requires state agencies and developers using state funds to take into account how their expenditures or undertakings will affect prehistoric and historic properties. They must also provide the State Historic Preservation Officer (SHPO) with a written evaluation of the project and an opportunity to comment.

The area of potential effects (APE) for the project is defined as the 320-acre project footprint. There are no standing buildings or structures within 3 miles of the project area, therefore, there will be no indirect effects, such as visual, auditory, or seismic influences, on historic properties beyond the limits of the project footprint.

The Class III survey was conducted on April 12 and 13, 2010. The work was authorized under Utah State Antiquities Project Number U-10-HK-0093p and State of Utah Archaeological Survey Permit 170. Prior to conducting the fieldwork, HDR staff conducted a Class I records check at the Utah Division of State History, accessed the National Register of Historic Places online database, and reviewed historic General Land Office maps. The records check indicated that no previous cultural resource projects have taken place within a 1-mile radius of the APE.

The Class III cultural resources survey was conducted in order to identify and document cultural resources within the APE that may be affected by the proposed project. No archaeological sites or other significant cultural resources were identified in the APE. Based on the results of the Class III investigation, HDR recommends that a finding of "no historic properties affected" is appropriate for the undertaking and that the project proceed as planned. If unanticipated cultural resource materials are encountered during construction, work should cease in the vicinity of the discovery and immediate contact should be made with the Utah Division of Solid and Hazardous Waste to arrange for an assessment by a qualified archaeologist.

Introduction

The Intermountain Regional Landfill is a proposed 320-acre landfill near the town of Fairfield, Utah (see Figures 1 and 2). Once permitted and constructed, the Intermountain Regional Landfill will consist of a single municipal landfill that will be constructed in phases. The major subunits of the landfill are called cells, and each cell will be developed in two or more phases. Other landfill facilities will include a dual-lined stormwater/leachate evaporation pond, a scale house, and administrative offices. The perimeter of the active work area will be fenced using a 6-foot-high fence with an 18-inch angled top.

The landfill project involves permitting approval from the Utah Department of Environmental Quality's (UDEQ) Division of Solid and Hazardous Waste. As such, the project requires compliance with state laws and policies (Administrative Code Rule R315, Utah Code Annotated 9-8-404), which require state agencies and developers using state funds to take into account how their expenditures or undertakings will affect prehistoric and historic properties. Therefore, HDR Engineering (HDR) conducted a Class III cultural resources survey to identify, document, and evaluate any cultural resources that could potentially be affected by the Intermountain Regional Landfill.

Prior to conducting the fieldwork, site, project, and preservation files were reviewed at the Utah Division of State History. HDR conducted the Class III survey on April 12 and 13, 2010. The work was authorized under Utah State Antiquities Project Number U-10-HK-0093p and State of Utah Archaeological Survey Permit 170.

Project Area and Environmental Setting

The project area is located on private land about 3 miles south of the town of Fairfield in Utah County (see Figure 1). The project area includes the west ½ of Section 16 in Township 7 South and Range 2 West (Goshen Pass, UT 7 5' USGS Quadrangle Map) (see Figure 2).

The project is located in the Cedar Valley between the Oquirrh Mountains and the Lake Mountains west of Utah Lake. This area is part of the Uinta Extension of the Basin and Range Province (Stokes 1977). Surface deposits are composed of Pleistocene alluvial and lacustrine deposits associated with Lake Bonneville (Hmtze 1980). The terrain is fairly flat with slight undulations and occasional dune formations. Elevation is about 4,850 feet above mean sea level.

Except for the far western edge of the project area, which has been developed as an agricultural field, the proposed project site is undeveloped and retains its native vegetation (see Photograph 1). Prominent vegetation includes tall sagebrush (*Artemisia tridentate*) and rabbitbrush (*Chrysothamnus* spp.) with a variety of native grasses and occasional cacti (*Opuntia* spp.). A large expanse of wheat fields is to the west.




Figure 1. Project vicinity map.




Figure 2. Project location map.



Photograph 1. Looking east across the project area.

Area of Potential Effects

The area of potential effects (APE) is the geographic area or areas within which an undertaking may directly or indirectly cause changes in the character or use of historic properties, if such properties exist (Title 36, Code of Federal Regulations, Section 800.16(d) [36 CFR § 800.16(d)]). The APE is influenced by the scale and nature of the undertaking and may be different for different kinds of effects caused by the undertaking. The APE for the landfill project is the 320-acre project footprint. There are no standing buildings or structures within 3 miles of the project area; therefore, there will be no indirect effects, such as visual, auditory, or seismic influences, on historic properties beyond the limits of the project footprint.

Regulatory Context

Developing the Intermountain Regional Landfill requires permitting and approval from the Utah Division of Solid and Hazardous Waste. As part of the permitting process, compliance with the Division's Administrative Code Rule R315 is required, which requires a project proponent to identify historical and archaeological resources that could be affected by a new or expanded landfill facility (R315-310-3[1][k]). Furthermore, because the project requires permitting by a state agency, it also must comply with Utah Code Annotated 9-8-404, which requires state agencies, and developers using state funds, to take into account how their expenditures or

undertakings will affect prehistoric and historic properties. They must also provide the State Historic Preservation Officer (SHPO) with a written evaluation of the project and an opportunity to comment.

Cultural Context

Cultural contexts are developed for cultural resource surveys so that the researchers can assess the potential for encountering cultural resources, gain an understanding of the types of resources that might be encountered, and understand the historical significance of such resources. Cultural contexts provide a summary of the prehistoric and historical activities and events that occurred in an area and provide a chronological and thematic framework for interpreting and evaluating identified cultural resources.

The prehistory of the Cedar Valley follows descriptions of the eastern Great Basin provided by Jennings and others (Jennings 1978, Madsen 1982, Aikens and Madsen 1986). The region's prehistory is characterized archaeologically by four broad periods of cultural development: the Archaic Period (10,000 BC–AD 500), the Formative Period (AD 500–1200), the Late Prehistoric Period (AD 1300–1700s), and the Historic Period (late 1700s to mid-1900s). The temporal divisions are based on distinct cultural patterns—projectile point typologies, pottery and basketry styles, the appearance of new technology, architecture, changes in subsistence and settlement strategies—identifiable in the archaeological record. The Historic Period is understood through a combination of archaeological data and written records.

The Archaic Period (10,000 BC–AD 500) is characterized by a generalized mode of subsistence used by regional hunters and gatherers. During this time, people moved across the landscape in small groups, foraging within seasonal rounds. Subsistence was based on a generalized hunting and gathering strategy focused on exploiting the wild flora and fauna resources. One of the primary technologies used by Archaic people that is visible in the archaeological record is the use of large dart points propelled by atlatls.

The Formative Period (AD 500–1200) is defined largely by the development of the Fremont Cultural Tradition. During this period there is a shift in the region toward more sedentary settlement-subsistence systems, the introduction of bow and arrow and ceramic technologies, and the adoption of horticulture as a primary subsistence resource.

Although people developed agriculture and more-permanent settlements during this time, hunting and gathering continued to be important subsistence practices. Morss (1931) first described the Fremont culture as a peripheral variant of the Anasazi, however, subsequent researchers have convincingly argued that the cultural traits of this era in northern Utah warrant distinction as a separate archaeological culture (Cordell 1984). The Fremont tradition fades from the archaeological record around AD 1200. Archaeological evidence suggests that Numic speakers from the Mojave Desert appeared in Utah sometime around AD 1100. Their archaeological remains primarily consist of lithic scatters with low quantities of brownware ceramics, rock art, and occasional wickiups (Barlow 2002). The influx of new people precipitated a shift back to a hunter-gatherer way of life.

The Late Prehistoric Period (AD 1300–1700s) is marked by the abandonment of horticultural practices in the region and the return to hunting and gathering wild foods. Late Prehistoric populations along Utah Lake appear to have occupied a series of long-term camps used for seasonal procurement activities. Many long-term camps have been documented along the mouths of rivers and streams emptying into Utah Lake, as well as spring fishing camps along the Jordan River north of Cedar Valley (Janetski 1990). These camps date between AD 1400 and 1600, just before the arrival of Spanish explorers (Janetski 1991).

The Historic Period (late 1700s to the mid-1900s) generally spans the time from initial contact between Native American populations, European and American explorers, and settlers to the present. The period includes development and change in Native American culture and the restriction of indigenous peoples to reservation lands because of pressure by white settlers. As Euroamericans began exploring and moving into the Great Basin in the 19th century, they found the area inhabited by several groups of linguistically related, Numic-speaking peoples. The southern Great Salt Lake area was occupied by the Gosiute (or Weber Ute) subgroup of the Western Shoshone. The area from the Jordan River south to the eastern and southern Utah Valley was the home of the Umta and Timpanogots Ute tribes.

Following the early explorers, the Mormons began settling the Salt Lake City area in the late 1840s. Other settlements and agricultural development soon followed along the Wasatch Front. Of particular interest to the current project was the establishment of Camp Floyd by the U.S. military about 3 miles north of the project area where the town of Fairfield is situated today. Camp Floyd was a pre-Civil War army post established in 1858 by order of President James Buchanan to suppress an assumed Mormon rebellion. The post had 400 buildings and housed 3,500 soldiers, which at the time was the largest concentration of U.S. troops in the nation (Utah State Parks 2009). The troops were ordered back east in 1861 with the outbreak of the Civil War, and the post was dismantled. Fairfield, which developed next to the army post, continued as an agricultural center and stagecoach stop. Today, three properties in Fairfield are listed on the National Register: the Camp Floyd site, the Stagecoach Inn, and the Fairfield District Schoolhouse.

Records Check

Prior to conducting the Class III survey, HDR's cultural staff conducted a records search at the Utah State Division of History. The records search was conducted on February 4, 2010. The purpose of background research is to document previous survey coverage and gain an understanding of the types of sites that might be encountered during the field investigation. The records check covered a 1-mile radius around the project area. In addition, HDR staff accessed the National Register of Historic Places online database and reviewed historic General Land Office maps for uses of the area during the historical period.

The records check indicated that no previous archaeological projects and no archaeological sites or historic resources have been documented within 1 mile of the project area. The nearest documented cultural resources in the area are about 3 miles to the north in the town of Fairfield.

Prehistoric Resources

Although no archaeological surveys have taken place in the immediate vicinity of the current project, a 760-acre block survey conducted about 6 miles to the northeast provides some perspective on the potential for prehistoric sites in the area. The survey was conducted in 1991 by Archaeological Research Consultants (ARCON) (Norman 1991). The survey covered terrain similar to the flat desert scrub in the project area. ARCON identified four prehistoric sites (42UT825–42UT828). All four sites were lithic scatters representing temporary camps. Artifacts included flakes, projectile point fragments, butchering tools, an awl, and grinding tools (Norman 1991).

Furthermore, the presence of certain favorable natural features suggests the potential for prehistoric use of the valley. In particular, a perennial spring on the west side of Fairfield would have been an attractive place for people in prehistoric times. The spring is labeled Big Spring on the Fort Cedar USGS 7.5' topographic quadrangle.

Historic Resources

The Camp Floyd site is located about 3 miles north of the project area. The camp exists today as an archaeological site and cemetery, no buildings or structures were left in place following its dismantlement in 1861. The only building that remains from the post is the commissary building, which was purchased by a local family in 1861 and relocated across the creek to Fairfield. Today, the commissary building serves as the museum and visitors' center for Camp Floyd State Park.

Survey Methods

HDR staff conducted the Class III survey on April 12 and 13, 2010. The crew included archaeologists Mark Brodbeck, Deil Lundm, and Shawn Fackler. As standard protocol, HDR conducted the inventory in accordance with the *UDOT Guidelines for Archaeological Survey and Testing* (2000). Sites and isolates were defined as follows:

A site is a relatively discrete, definable entity, which includes features and/or a reasonable quantity and aggregation of artifacts. Further, a site displays integrity of location and is potentially interpretable (in terms of past human behavior).

An isolate (or isolated find) is a spatially scattered and/or disassociated manifestation that consists of a single artifact or relatively few artifacts that lack contextual information.

The APE was surveyed in 15-meter parallel pedestrian transects. Field documentation included written notes, photographs, and sketch maps. Location data were collected with a global positioning system (GPS) Trimble Geo XT unit with ArcPad 6. Cultural resources were also plotted in the field on USGS 7.5' topographic quadrangle maps and aerial photographs.

Results

The project area was covered by a fairly homogenous distribution of tall sagebrush and grasses. The vegetation allowed on average for about 75% visual inspection of the ground surface. Numerous ant hills dispersed through the project area were inspected for micro-artifacts and indications of subsurface cultural deposits. Modern shotgun shells and an abundance of articulated rabbit skeletons indicated that the area is currently used for sport hunting.

No archaeological sites or other significant cultural resources were identified during the Class III survey. Two isolated finds were documented. Isolates 1 and 2 consist of church-key-opened cans that date to the 1950s or 1960s.

Management Recommendations

The Class III cultural resources survey was conducted in order to identify and document cultural resources within the APE that may be affected by the proposed project. No archaeological sites or other significant cultural resources were identified in the APE. Based on the results of the Class III investigation, HDR recommends that a finding of "no historic properties affected" is appropriate for the undertaking and that the project proceed as planned. If unanticipated cultural resource materials are encountered during construction, work should cease in the vicinity of the discovery and immediate contact should be made with the Utah Division of Solid and Hazardous Waste to arrange for an assessment by a qualified archaeologist.

References Cited

Aikens, C Melvm, and David B Madsen

1986 Prehistory of the Eastern Area In Great Basin, edited by Warren d'Azevedo, pp 149–160 *Handbook of North American Indians, Vol 11*, W G Sturtevant, general editor Smithsonian Institution, Washington, DC

Barlow, K Renee

2002 Predicting Maize Agriculture among the Fremont An Economic Comparison of Farming and Foraging in the American Southwest *American Antiquity* 67(1) 65–88

Cordell, Linda S

1984 Prehistory of the Southwest Academic Press, Inc , New York, NY

Hmtze, Lehi F

1980 *Geologic Map of Utah* Utah Geological and Mineral Survey, Salt Lake City, UT

Janetski, Joel C

1990 Utah Lake Its Role in the Prehistory of Utah Valley *Utah Historical Quarterly* 58(1) 5–31

1991 *The Ute of Utah Lake* University of Utah Anthropological Papers No 116 Umversity of Utah, Salt Lake City, UT

Jennings, Jesse D

1978 *Prehistory of Utah and the Eastern Great Basin* Anthropological Papers No 98 University of Utah, Salt Lake City, UT

Madsen, David B

1982 Get It Where the Getting's Good A Variable Model of Great Basin Subsistence and Settlement Based on Data from the Eastern Great Basm In *Man and Environment in the Eastern Great Basin*, edited by D B Madsen and J F O'Connell, pp 207–226 SAA Papers No 2, Society for American Archaeology, Washington, DC

Morss, Noel

1931 The Ancient Culture of the Fremont River in Utah Report on the Explorations under the Claflm-Emerson Fimd, 1928–29 *Papers of the Peabody Museum, Vol XII, No 3* Peabody Museum of American Archaeology and Ethnology, Harvard Umversity, Massachusetts, MA

Norman, V Garth

1991 *Cultural Resources Survey of Cedar Valley Phase 1 Ranch Development, Utah County, Utah* Project No U-91-AK-670p Archaeological Research Consultants, American Fork, UT

Stokes, William, L

1977 Subdivisions of the Major Physiographic Provinces in Utah *Utah Geology* 4(1) Utah Geological and Mineral Survey, Salt Lake City, UT

Utah State Parks

2009 Camp Floyd/Stagecoach Inn State Park and Museum Brochure issued by Utah State Parks

APPENDIX D

COST BREAKDOWN FOR CLOSURE/POST-CLOSURE

APPENDIX D
Intermountain Regional Landfill
Closure Cost Estimate
Cell 1 (2010 Dollars)

| | | |
|----------------|-----|-------|
| Cell 1 Phase 1 | 8 0 | Acres |
| Total | 8 0 | Acres |

| | Item | Unit | Unit Cost | Quantity | Cost |
|------|--------------------------------|------|-----------|----------|----------------------|
| 1 00 | Engineering/Management | | | | |
| 1 01 | Topo Survey Initial | HR | \$150 | 25 | \$3,750 |
| 1 02 | Topo Survey Final | HR | \$150 | 20 | \$3,000 |
| 1 03 | Site Reconnaissance | HR | \$150 | 16 | \$2,400 |
| 1 04 | Boundary Survey | HR | \$150 | 16 | \$2,400 |
| 1 05 | Construction Plans/Specs | LUMP | \$45,000 | 1 | \$45,000 |
| 1 06 | Bidding and Award | LUMP | \$5,000 | 1 | \$5,000 |
| 1 07 | Quality Control Testing | LUMP | \$10,000 | 1 | \$10,000 |
| 1 08 | Construction Management/QC | LUMP | \$85,000 | 1 | \$85,000 |
| 1 09 | Closure Report/As-Builts | LUMP | \$25,000 | 1 | \$25,000 |
| 1 10 | Obtain UPDES and other permits | LUMP | \$10,000 | 1 | \$10,000 |
| | | | | | Subtotal |
| | | | | | \$191,550 |
| | | | | 20% | Contingency |
| | | | | | \$38,310 |
| | | | | | Engineering Subtotal |
| | | | | | \$229,860 |

| | | | | | |
|------|--|------|-------------|---------|-----------------------|
| 2 00 | Construction | | | | |
| 2 01 | Grading Top of Intermediate Cover | SY | \$1 25 | 38,720 | \$48,400 |
| 2 02 | Top Liner (60 mil FML) | SF | \$0 55 | 348,480 | \$191,664 |
| 2 03 | Clay Final Cover (1 5') ^[3] | CY | \$13 50 | 19,360 | \$261,360 |
| 2 04 | Topsoil (0 5') ^[4] | CY | \$4 00 | 6,453 | \$25,813 |
| 2 05 | Seed and Seeding | ACRE | \$1,000 00 | 8 | \$8,000 |
| 2 06 | Silt Fence/Erosion Control | LF | \$2 50 | 5,500 | \$13,750 |
| 2 07 | Dust Control and Watering | LS | \$11,000 00 | 1 | \$11,000 |
| 2 08 | Drainage Ditches | LF | \$2 00 | 5,500 | \$11,000 |
| 2 09 | Temporary Drainage Control | LS | \$11,000 00 | 1 | \$11,000 |
| 2 10 | Gas Collection System ^[5] | ACRE | \$15,000 00 | 0 | \$0 |
| | | | | | Subtotal |
| | | | | | \$581,987 |
| | | | | 25% | Contingency |
| | | | | | \$145,497 |
| | | | | | Construction Subtotal |
| | | | | | \$727,484 |

Closure Cost Summary

| | | | | | | |
|--|--|--|--|----|--|--------------------|
| | | | | | Engineering Subtotal | \$229,860 |
| | | | | | Construction Subtotal | \$727,484 |
| | | | | | Subtotal | \$957,344 |
| | | | | 5% | Legal/Regulatory Oversight Contingency | \$47,867 |
| | | | | | Total | \$1,005,211 |

Assumptions/Notes

- 1 Estimate assumes closure of Cell 1 Phase 1 only
- 2 No permanent culverts or drainage piping is required
- 3 Assumes cover is imported from an off-site source TBD
- 4 Assumes topsoil is available onsite
- 5 Active gas collection system not required at this time

APPENDIX D
Intermountain Regional
Landfill
Post-Closure Care Cost Estimate for
Cell 1 (2010 Dollars)

COST ESTIMATE FOR LANDFILL POST-CLOSURE CARE

| | Item | Unit | Unit Cost | Quantity | Cost |
|--------------------------|--|----------|-----------|----------|------------------|
| 1 0 | ENGINEERING | | | | |
| 1 1 | Post Closure Plan | LUMP | \$9,000 | 1 | \$9,000 |
| 1 2 | Site Inspection & Recordkeeping (quarterly) | PER YEAR | \$2,500 | 30 | \$75,000 |
| 1 3 | Correctional Plans & Specs (annual) | PER YEAR | \$1,200 | 30 | \$36,000 |
| 1 4 | Site Monitoring (semi-annually) ⁽¹⁾ | PER YEAR | \$10,000 | 30 | \$300,000 |
| 2 0 | MAINTENANCE COSTS ⁽²⁾ | PER YEAR | \$6,000 | 30 | \$180,000 |
| Subtotal | | | | | \$600,000 |
| Contingency (20%) | | | | | \$120,000 |
| Total | | | | | \$720,000 |

Closure Estimate (previous page) \$1,005,211

Total Closure/Post Closure \$1,725,211

Assumptions/Notes

- 1 Includes groundwater monitoring and statistical analysis but no gas sampling
- 2 Includes repairing eroded final cover material with on site material, compost and seed

APPENDIX E

FAIRFIELD SITE GEOTECHNICAL STUDY BY
EARTHTEC



Earthtec Testing & Engineering, P.C.

133 North 1330 West
Orem, Utah - 84057
Phone (801) 225-5711
Fax (801) 225-3363

1596 W. 2650 S #108
Ogden, Utah - 84401
Phone (801) 399-9516
Fax (801) 399-9842

GEOTECHNICAL STUDY INTERMOUNTAIN REGIONAL LANDFILL FAIRFIELD, UTAH

Prepared By



133 North 1330 West
Orem, Utah 84057
(801) 225-5711

Job No. 062496

Prepared for

Mr David Johnston
P O Box 1503
Orem, Utah 84059

October 13 , 2006

Earthtec

| TABLE OF CONTENTS | | Page No. |
|-------------------|---------------------------------------|----------|
| 1 0 | INTRODUCTION | 1 |
| 2 0 | CONCLUSIONS | 1 |
| 3 0 | PROPOSED DEVELOPMENT | 2 |
| 4 0 | GENERAL SITE DESCRIPTION | 3 |
| 5 0 | SUBSURFACE INVESTIGATION | 3 |
| 5 1 | <u>Soil Exploration</u> | 3 |
| 5 2 | <u>Percolation Testing</u> | 4 |
| 6 0 | LABORATORY TESTING | 5 |
| 7 0 | SUBSURFACE CONDITIONS | 6 |
| 7 1 | <u>Soil Types</u> | 6 |
| 7 2 | <u>Groundwater</u> | 7 |
| 8 0 | SITE GRADING | 7 |
| 8 1 | <u>General Site Grading</u> | 7 |
| 8 2 | <u>Temporary Excavations</u> | 7 |
| 8 3 | <u>Fdl Matenal</u> | 8 |
| 8 4 | <u>Fill Placement and Compaction</u> | 8 |
| 9 0 | SEISMIC CONSIDERATIONS | 9 |
| 9 1 | <u>Faultmg</u> | 9 |
| 9 2 | <u>Liquefaction Potential</u> | 9 |
| 9 3 | <u>IRC Seismic Design Category</u> | 10 |
| 10 0 | FOUNDATIONS | 11 |
| 10 1 | <u>General</u> | 11 |
| 10 2 | <u>Estimated Settlement</u> | 12 |
| 11 0 | FLOOR SLABS | 13 |
| 12 0 | MOISTURE CONTROL AND SURFACE DRAINAGE | 13 |
| 13 0 | GENERAL CONDITIONS | 14 |

FIGURES

| | |
|-----------|--|
| No 1 | VICINITY MAP |
| No 2 | SITE PLAN AND LOCATION OF EXPLORATIONS |
| Nos 3-22 | TEST PIT LOG |
| Nos 23-24 | TEST HOLE LOGS |
| No 25 | LEGEND |
| Nos 26-30 | CONSOLIDATION-SWELL TEST |

TABLES

| | |
|------|-------------------------|
| No 1 | LABORATORY TEST RESULTS |
| No 2 | PAVEMENT SECTION DESIGN |



Earthtec Testing & Engineering, P.C.

133 North 1330 West
Orem, Utah - 84057
Phone (801) 225-5711
Fax (801) 225-3363

1596 W. 2650 S #108
Ogden, Utah - 84401
Phone (801) 399-9516
Fax (801) 399-9842

GEOTECHNICAL STUDY INTERMOUNTAIN REGIONAL LANDFILL FAIRFIELD, UTAH

Prepared By



133 North 1330 West
Orem, Utah 84057
(801) 225-5711

Job No. 062496

Prepared for

Mr David Johnston
P O Box 1503
Orem, Utah 84059

October 13 , 2006

Earthtec

| TABLE OF CONTENTS | | Page No |
|-------------------|---------------------------------------|---------|
| 1 0 | INTRODUCTION | 1 |
| 2 0 | CONCLUSIONS | 1 |
| 3 0 | PROPOSED DEVELOPMENT | 2 |
| 4 0 | GENERAL SITE DESCRIPTION | 3 |
| 5 0 | SUBSURFACE INVESTIGATION | 3 |
| 5 1 | <u>Soil Exploration</u> | 3 |
| 5 2 | <u>Percolation Testmg</u> | 4 |
| 6 0 | LABORATORY TESTING | 5 |
| 7 0 | SUBSURFACE CONDITIONS | 6 |
| 7 1 | <u>Soil Types</u> | 6 |
| 7 2 | <u>Groundwater</u> | 7 |
| 8 0 | SITE GRADING | 7 |
| 8 1 | <u>General Site Gradmg</u> | 7 |
| 8 2 | <u>Temporary Excavations</u> | 7 |
| 8 3 | <u>Fill Material</u> | 8 |
| 8 4 | <u>Fill Placement and Compaction</u> | 8 |
| 9 0 | SEISMIC CONSIDERATIONS | 9 |
| 9 1 | <u>Faultmg</u> | 9 |
| 9 2 | <u>Liquefaction Potential</u> | 9 |
| 9 3 | <u>IRC Seismic Design Category</u> | 10 |
| 10 0 | FOUNDATIONS | 11 |
| 10 1 | <u>General</u> | 11 |
| 10 2 | <u>Estimated Settlement</u> | 12 |
| 11 0 | FLOOR SLABS | 13 |
| 12 0 | MOISTURE CONTROL AND SURFACE DRAINAGE | 13 |
| 13 0 | GENERAL CONDITIONS | 14 |

FIGURES

| | |
|-----------|--|
| No 1 | VICINITY MAP |
| No 2 | SITE PLAN AND LOCATION OF EXPLORATIONS |
| Nos 3-22 | TEST PIT LOG |
| Nos 23-24 | TEST HOLE LOGS |
| No 25 | LEGEND |
| Nos 26-30 | CONSOLIDATION-SWELL TEST |

TABLES

| | |
|------|-------------------------|
| No 1 | LABORATORY TEST RESULTS |
| No 2 | PAVEMENT SECTION DESIGN |

1.0 INTRODUCTION

Earthtec has completed a geotechnical study for an approximately 1 square mile parcel located about 3 miles south of the town of Fairfield, Utah as shown on Figure No 1, *Vicinity Map*. We understand that it is proposed to construct a new solid waste landfill. This report presents our findings and geotechnical engineering recommendations for the proposed development.

The purposes of this study were to 1) evaluate the subsurface soil conditions at the site, 2) assess the engineering characteristics of the subsurface soils, and 3) provide geotechnical recommendations for general site grading and the design and construction of foundations, concrete floor slabs, miscellaneous concrete flatwork, and asphalt pavement sections. The scope of work completed for this study included field reconnaissance, subsurface investigation, field and laboratory soil testing, engineering analysis, and the preparation of this report.

2.0 CONCLUSIONS

The following is a brief summary of our findings and conclusions:

1. Our subsurface exploration included test pits excavated with a rubber tire backhoe, and test holes drilled with a hydraulic drill rig. In the test pits we observed approximately 12 to 24 inches of topsoil followed by Fat Clay (CH), Elastic Silt (MH), and a few layers of Silty Sand (SM), extending to the bottom of the test pits at about 10 to 11 feet below the existing surface. We also encountered topsoil at the surface of the test hole locations followed by Fat Clay (CH) extending to the bottom of the test holes at about 31½ to 41½ feet below the ground surface. Groundwater was not encountered in the test pits nor in the test holes.
2. Percolation tests were performed in Test Pits 2, 3, 5, 9, 16, 18, and 19 at depths of about 4½ to 6½ feet below the existing surface. Measured percolation rates ranged from 1½ to 24 minutes per inch, but slower rates would likely have been measured if the native soils had been saturated.
3. Vegetation should be removed from below areas that will be filled with debris. Where structures are planned, both the vegetation and topsoil should be completely removed from below foundation, floor slab, and exterior concrete.

flatwork areas. Soils in foundation areas disturbed during construction should also be removed or recompacted prior to placement of footings.

4. We estimate that a fill depth of 20 feet (with an estimated unit weight of 50 pcf for debris fill) will induce approximately 4 inches of consolidation settlement in the underlying native soils.
5. The majority of the subsurface clay soils were found to have high plasticity characteristics. Each of the consolidation test samples indicated swell potential of about 1 to 1½%. If allowed to become saturated after construction, these soils can swell under foundations and floor slabs causing distress and cracking. The drainage recommendations presented in Section 13.0 could be carefully followed if structures are planned.
6. Conventional strip and spread footings may be used to support proposed structures within this development. Foundations should be constructed entirely on undisturbed, uniform, native soils, or entirely on a minimum 36 inches of structural fill placed on undisturbed native soils. Footings constructed on the native soils should be designed for a minimum bearing capacity of 4,000 pcf. We also recommend a crawl space beneath floor slabs to minimize the potential for swelling soils to impact floor slabs. More details regarding foundation design can be found in Section 10.0 of this report.

These findings and conclusions should not be relied upon without reading and consulting this entire report for a more detailed description of the geotechnical evaluation and recommendations contained herein.

3.0 PROPOSED DEVELOPMENT

We understand that the site will be used as a landfill and understand that the landfill will handle mixed solid waste. We also anticipate that some associated structures will be constructed. We estimate that foundation loads for structures will not exceed 4 kips per linear foot for bearing walls, 30 kips for columns, and 150 pounds per square foot for floor slabs. If structural loads will be greater, our office should be notified so that we may review our recommendations and, if necessary, make modifications.

4.0 GENERAL SITE DESCRIPTION

At the time we conducted our subsurface explorations, the site for the proposed landfill was an approximately 1 square mile parcel vegetated with sage brush and weeds. No existing structures were observed. The ground surface appeared to be relatively flat. The site was bounded on the east, west, and south by fields, and on the north by a dirt road.

5.0 SUBSURFACE INVESTIGATION

5.1 Soil Exploration

Subsurface soil conditions at the site were investigated under the direction of a qualified member of our geotechnical staff. On September 7 and 8, 2006 a rubber tire backhoe was used to excavate 20 test pits extending to approximate depths of 10 to 11 feet below the existing surface. On September 27, 2006 we returned to the site with an all-terrain hydraulic drill rig and drilled 2 test holes to depths of about 31½ to 41½ feet below the existing surface. The approximate locations of the test pits and the test holes are shown on Figure No. 2 at the end of this report.

The soils exposed in the test pits, and the samples collected in the test holes, were classified by visual examination following the guidelines of the Unified Soil Classification System (USCS). In the test pits, disturbed bag samples and relatively undisturbed block samples of the subsurface soils were collected at various intervals. In the test holes disturbed samples were collected with a 1½ inch inside diameter spt spoon sampler. The spt spoon sampler was driven 18 inches into undisturbed soil with a 140 pound hammer free-falling through a distance of 30 inches. The blows required to drive the sampler through the final 12 inches of penetration is called the blow count, which is recorded on the attached test hole logs at the respective sample depths. When 50 blows were achieved for any 6-inch interval, sampling was stopped and the blows for each 6-inch interval (or less) are indicated on the logs. Relatively undisturbed samples were collected with thin walled "Shelby" tubes hydraulically pushed into the soil below the augers by the drill.

The collected samples were transported to our Orem, Utah laboratory where they will be retained for 30 days following the date of this report and then discarded, unless a written request for additional holding time is received prior to the 30 day limit

5.2 Percolation Testing

To provide information regarding the permeability of the native soils we conducted percolation tests in several of the test pits as part of our subsurface explorations. The percolation tests were performed by digging a small hole into undisturbed soil with a shovel at the depth indicated, filling the hole with water, and measuring the rate of water loss with time. The tests were conducted several times and the final measured percolation rate is presented in the following table

Table No. 2: Percolation Test Results

| TEST PIT NO | DEPTH (ft.) | SOIL TYPE | PERCOLATION RATE (min/inch) |
|-------------|-------------|-----------|-----------------------------|
| TP-2 | 6½ | SM | 1½ |
| TP 3 | 6 | CH | 3 |
| TP-5 | 6 | CH | 20 |
| TP-9 | 5 | CH | 6 |
| TP-16 | 6 | CH | 17 |
| TP 18 | 5 | CH | 9 |
| TP 19 | 4½ | CH | 24 |

These tests give a representation of how percolation rates may change across the site. The soils encountered in the test pits had high plasticity characteristics which would indicate these soils have the ability to absorb a significant amount of water. The percolation rates generally were still slowing when the final percolation test was conducted, and actual percolation rates would likely be much slower if the soils were saturated.

6.0 LABORATORY TESTING

From the samples collected in the test pits and test holes, representative samples were selected for laboratory testing to assess pertinent engineering properties and to aid in refining field classifications, if needed. Laboratory testing consisted of natural moisture content and dry density tests, one-dimensional consolidation tests, Atterberg limits determinations, and mechanical gradation analyses. The following table summarizes the results of the laboratory testing. Test results are also shown on the enclosed test pit and test hole logs at the respective sample depths, and on Figure Nos 26 through 30, *Consolidation-Swell Test*

Table No 1 • Laboratory Test Results

| TEST PIT/ HOLE NO | DEPTH (ft) | NATURAL MOISTURE (%) | NATURAL DRY DENSITY (pcf) | ATTERBERG LIMITS | | GRAIN SIZE DISTRIBUTION (%) | | | SOIL TYPE |
|-------------------------|---------------|----------------------------|------------------------------------|------------------|---------------------|--------------------------------|------|-----------------------|--------------|
| | | | | LIQUID LIMIT | PLASTICITY INDEX | GRAVEL #4 | SAND | SILT/ CLAY #200 | |
| TP-2 | 9 | 4 | -- | -- | -- | 0 | 75 | 25 | SM |
| TP-4 | 2½ | 19 | -- | 50 | 17 | -- | -- | -- | MH |
| TP-6 | 8 | 22 | -- | 63 | 41 | -- | -- | - | CH |
| TP-7 | 9 | 23 | 90 | 70 | 37 | -- | -- | -- | CH |
| TP-9 | 7 | 23 | -- | 73 | 50 | -- | -- | -- | CH |
| TP-10 | 8½ | 26 | 91 | 70 | 50 | -- | -- | -- | CH |
| TP-12 | 4 | 11 | -- | -- | -- | 0 | 37 | 63 | ML |
| TP-14 | 6 | 20 | 93 | 71 | 47 | -- | -- | -- | CH |
| TP-15 | 7½ | 19 | 93 | 61 | 37 | -- | -- | -- | CH |
| TP-16 | 8½ | 20 | -- | 70 | 46 | -- | -- | -- | CH |
| TP-18 | 9 | 22 | -- | 71 | 47 | -- | -- | -- | CH |
| TP-19 | 4 | 16 | -- | 53 | 28 | -- | -- | -- | CH |
| TP-20 | 3 | 16 | -- | 58 | 35 | -- | -- | -- | CH |
| TH-1 | 15 | 21 | 97 | 77 | 51 | -- | -- | -- | CH |
| TH-1 | 25 | 19 | -- | 52 | 26 | -- | -- | -- | CH |

Table No. 1 Laboratory Test Results continued

| TEST PIT NO | DEPTH (ft) | NATURAL MOISTURE (%) | NATURAL DRY DENSITY (pcf) | ATTERBERG LIMITS | | GRAIN SIZE DISTRIBUTION (%) | | | SOIL TYPE |
|-------------|------------|----------------------|---------------------------|------------------|------------------|-----------------------------|------|----------------|-----------|
| | | | | LIQUID LIMIT | PLASTICITY INDEX | GRAVEL #4 | SAND | SILT/CLAY #200 | |
| TH-2 | 20 | 13 | --- | 55 | 36 | --- | -- | -- | CH |
| TH-2 | 30 | 15 | --- | 55 | 33 | --- | -- | --- | CH |

7.0 SUBSURFACE CONDITIONS

7.1 Soil Types

At the locations of the test pits we encountered about 12 to 24 inches of topsoil at the surface. Subsurface soils were predominately fine-grained and consisted of Fat Clay (CH), Elastic Silt (MH), and a few layers of Silty Sand (SM) to Sandy Silt (ML), extending to the maximum depths explored in the test pits of approximately 10 to 11 feet below the existing ground surface.

At the locations of the test holes we also encountered topsoil at the surface which we estimated to extend about 18 inches in depth, followed by layers of Fat Clay (CH) extending to the bottom of the test holes at about 31½ to 41½ feet below the existing surface. The subsurface soils encountered in the test holes below those observed in the test pits were found to be very stiff to hard and the hydraulic drilling had considerable difficulty penetrating to the exploration depths.

Graphical representations and detailed descriptions of the soils encountered in the test pits and test holes are shown on Figure Nos 3 through 22, *Test Pit Log*, and Figure Nos 23 and 24, *Test Hole Log*, at the end of this report. The stratification lines shown on the logs represent the approximate boundary between soil units, the actual transition may be gradual. Due to potential natural variations inherent in soil deposits, care should be taken in interpolating between and extrapolating beyond exploration points. A key to the symbols and terms on the logs is presented on Figure No 25, *Legend*.

7.2 Groundwater

Groundwater was not encountered within the depths explored. Groundwater levels will fluctuate in response to the season, precipitation and snow melt, irrigation, and other on and off-site influences. Precisely quantifying these fluctuations would require long term monitoring.

8.0 SITE GRADING

8.1 General Site Grading

Vegetation should be removed from below the landfill areas. Unsuitable soils and vegetation should be removed from below foundation, floor slab, exterior concrete flatwork, and pavement areas to minimize the potential for distress and settlement. Unsuitable soils consist of: topsoil, organic soils, undocumented fill, soft, loose, or disturbed native soils, and any other inapt materials. Topsoil was encountered on the surface of the site which extended to depths of about 12 to 24 inches below the existing surface. The topsoil, including any soil containing roots larger than about 1/4 inch in diameter, and any other unsuitable soils, should be completely removed beneath building, flatwork, and pavement areas.

Fill placed over large areas, even if only a few feet in depth, can cause consolidation in the underlying native soils and settlement of the overlying fill. We assume that fairly deep fills will be placed on the site. For settlement estimates (See Section 10.2) we have assumed that the material placed and compacted in the landfill will have a density of about 50 pounds per cubic foot.

8.2 Temporary Excavations

For temporary excavations less than 5 feet in depth into the native soils or into structural fill, slopes should not be made steeper than 0.5:1.0 (horizontal:vertical). Temporary excavations extending up to 10 feet in depth should not be made steeper than 1:1. If unstable conditions or groundwater seepage are encountered, flatter slopes, shoring, or bracing may be required.

8.3 Fill Material

The native soils are not suitable for use as structural fill due to their generally high plasticity characteristics and difficulty controlling the moisture content needed to achieve the required compaction. These soils are also subject to swelling and shrinkage with changes in moisture content.

Structural fill should consist of imported material meeting the following requirements:

| | |
|--|------------|
| Maximum particle size | 4 inches |
| Percent retained on the 3/4 inch sieve (coarse gravel) | 30 maximum |
| Percent passing the No. 200 sieve (fines) | 15 maximum |
| Liquid Limit of fines | 35 maximum |
| Plasticity Index of fines | 15 maximum |

In some situations, particles larger than 4 inches and/or more than 30 percent coarse gravel may be acceptable, however, compaction and compaction testing may be more difficult. As a result, more strict quality control measures than normally used may be required. Such measures may include using thinner lifts, and increased or full time observation of fill placement.

Utility trench fill below structures, concrete flatwork, and asphalt paving should consist of structural fill as defined above.

8.4 Fill Placement and Compaction

The thickness of each lift should be appropriate for the compaction equipment that is used. We recommend a maximum lift thickness of 4 inches for hand operated equipment, 6 inches for most "trench compactors", and 8 inches for larger rollers, unless it can be demonstrated by in-place density tests that the required compaction can be obtained throughout a thicker lift. The full thickness of each lift of structural fill placed should be compacted to at least the following percentages of the maximum dry density, as determined by ASTM D-1557:

| | |
|---|-----|
| In landscape areas not supporting structural loads | 90% |
| Less than 5 feet of fill below foundations, flatwork and pavements | 95% |
| Five or more feet of fill below foundations, flatwork and pavements | 98% |

Generally, placing and compacting fill at a moisture content within 2% of the optimum moisture content, as determined by ASTM D-1557, will facilitate compaction. Typically, the further the moisture content is from optimum the more difficult it will be to achieve the required compaction.

Fill should be tested frequently during placement and early testing (initial lift) is recommended to demonstrate that placement methods and compaction efforts are achieving the required compaction. It is the contractor's responsibility to ensure that fill materials and compaction efforts are consistent so that tested areas are representative of the entire fill.

9.0 SEISMIC CONSIDERATIONS

9.1 Faulting

Based on published data no active faults are known to traverse the site and no surficial evidence of faulting was observed during our field investigation. The nearest mapped¹ fault trace considered to be active is one of a group of faults located beneath Utah Lake and is located approximately 12 miles east of the site.

9.2 Liquefaction Potential

The site appears to be located in an area mapped by the Utah Geological Survey² as having very low liquefaction potential. Liquefaction is a phenomenon where a soil loses intergranular strength due to an increase in soil pore water pressures during a dynamic event such as an earthquake. The potential for liquefaction is based on several factors, including 1) the grain size

¹Hecker, S., 1993, Quaternary Faults and Folds, Utah, Utah Geologic Survey, Bulletin 127

²Liquefaction Potential Map, Utah Geological Survey, Public Information Series 25, 1994

distribution of the soil, 2) the plasticity of the fine fraction of the soil (material passing the No. 200 sieve), 3) relative density of the soil, 4) earthquake strength (magnitude) and duration, and 5) overburden pressures. In addition, the soils must be saturated for liquefaction to occur. As a part of this investigation, the potential for liquefaction to occur in the soils we observed was assessed.

Loose, saturated sands are most susceptible to liquefaction, but soft, sensitive silt soils also have the potential to experience failure and movement during a seismic event. Sand soils encountered in the test pits were unsaturated, and the remainder of the soils were predominately composed of Fat Clay (CH), typically considered non-liquefiable. These conditions, in our opinion, support the very low liquefaction potential designation.

9.3 IRC Seismic Design Category

The Site Class definitions in the International Building Code (IBC) are based upon the soil properties in the upper 100 feet of the soil profile. These properties are determined from SPT blow counts and undrained shear strength measurements. The code states that "Where site specific data are not available to a depth of 100 feet, appropriate soil properties may be estimated by the registered design professional preparing the soils report." We estimate the soils encountered in the test pits and test holes have properties consistent with those defined by Site Class D.

The site is located at approximately 40° 21' latitude and -112° 07' longitude. Using Site Class D, the design spectral response acceleration parameters are 0.55 g for S_{DS} and 0.31 g for S_{D1} , for short and one second periods, respectively. The intermediate values from the IBC used to obtain the design parameters are contained in Table Nos. 2 and 3 below.

Table No. 2: Design Acceleration for Short Period

| S_s | F_a | S_{MS} | S_{DS} |
|--------|-------|--------------------|-----------------------|
| | | $S_{MS} = F_a S_s$ | $S_{DS} = 2/3 S_{MS}$ |
| 0.65 g | 1.28 | 0.83 g | 0.55 g |

S_s = The mapped spectral accelerations for short periods from Figure 1615(5)
 F_a = Site coefficient from Table 1615.1.2(1)
 S_{MS} = The maximum considered earthquake spectral response accelerations for short periods
 S_{DS} = Five-percent damped design spectral response acceleration at short periods

Table No. 3: Design Acceleration for 1 Second Period

| S_1 | F_v | S_{M1} | S_{D1} |
|--------|-------|--------------------|-----------------------|
| | | $S_{M1} = F_v S_1$ | $S_{D1} = 2/3 S_{M1}$ |
| 0.24 g | 1.92 | 0.46 g | 0.31 g |

S_1 = The mapped spectral accelerations for 1-second period from Figure 1615(6)
 F_v = Site coefficient from Table 1615.1.2(2)
 S_{M1} = The maximum considered earthquake spectral response accelerations for 1 second period
 S_{D1} = Five-percent damped design spectral response acceleration at 1 second period

10.0 FOUNDATIONS

10.1 General

The foundation recommendations presented in this report are based on the soil conditions observed in the test pits, the results of laboratory testing of samples of the native soils, the site grading recommendations presented in this report, and the foundation loading conditions presented in Section 3.0, *Proposed Construction*, of this report. If loading conditions are significantly different, we should be notified in order to re-evaluate our design parameters and estimates, and to provide additional recommendations if necessary.

Conventional strip and spread footings may be used to support proposed structures. Foundations should not be installed on topsoil, disturbed native soils, undocumented fill, debris, combination soils (structural fill/native soil combinations), frozen soil, or in ponded water. If foundation soils become disturbed during construction they should be removed or recompacted until firm.

The native soils have a potential to swell when wetted. Foundations constructed directly on undisturbed, uniform native soils should be designed for a minimum bearing pressure of 4,000 psf to help counter potential swell pressures which could develop if the native soils are allowed to become saturated. As an alternative, native soils directly below footings could be over excavated a minimum of 36 inches and replaced with compacted structural fill and footings designed for a maximum bearing capacity of 4,000 psf. The recommendations given in Section 13.0 below should also be carefully followed to minimize the potential for foundation soils to become saturated.

A representative from Earthtec should observe the soil conditions in foundation excavations if soil conditions differing from those described in this report are encountered. Other general footing design parameters are as follows:

| | |
|---|------------|
| Minimum embedment for frost protection | 30 inches |
| Minimum strip footing width | 20 inches |
| Minimum spot footing width | 30 inches |
| Bearing pressure increase for transient loading | 33 percent |

Structural fill used below foundations should extend laterally a minimum of 12 inches for every 12 vertical inches of structural fill placed. For example, if 36 inches of structural fill are required to bring the excavation to footing grade, the structural fill should extend laterally a minimum of 36 inches beyond the edge of the footings.

10.2 Estimated Settlement

For structures, if the proposed foundations are properly designed and constructed using the parameters provided above, total settlement for non-earthquake conditions is estimated not to exceed one inch. Differential settlement is anticipated to be one-half of the total settlement over a 25-foot length of foundation. Additional movements could occur during an earthquake due to ground shaking, or if foundation soils become saturated.

We estimate that consolidation settlement of about 4 inches will occur under the weight of 20 feet of debris fill. Deeper fill depths could cause additional settlement.

11.0 FLOOR SLABS

The swell potential of the native soils could have the most detrimental impact to floor slabs if allowed to become saturated after construction. To minimize this potential we recommend that crawl-spaces be constructed between the floor slabs and the native soils. Suspended concrete floor slabs would require proper design by a structural engineer.

For exterior concrete flat work, to facilitate construction, act as a capillary break, and aid in distributing loads we recommend that exterior flatwork be underlaid by four inches of free-draining granular material such as "pea" gravel or three-quarters to one-inch minus clean gravel supported on native soils or structural fill.

Special precautions should be taken during placement and curing of all concrete slabs and flatwork. Excessive slump (high water-cement ratios) of the concrete and/or improper finishing and curing procedures used during hot or cold weather conditions may lead to excessive shrinkage, cracking, spalling, or curling of slabs. We recommend all concrete placement and curing operations be performed in accordance with American Concrete Institute (ACI) codes and practices.

12.0 MOISTURE CONTROL AND SURFACE DRAINAGE

The native subsurface soils were found to have high plasticity characteristics and a potential to swell when wetted. To minimize the potential for subsurface soils to become wetted below and adjacent to any structures constructed at this site we recommend that the following precautions be taken:

- 1 Adequate compaction of foundation backfill should be provided i.e. a minimum of 90% of ASTM D-1557. Water consolidation methods should not be used.
- 2 The ground surface should be graded to drain away from structures in all directions. We recommend a minimum fall of 8 inches in the first 10 feet. More slope may be needed in areas where settlement due to debris fill will occur.
- 3 Roof runoff should be collected in rain gutters with down spouts designed to discharge well outside of the backfill limits, or at least 10 feet from foundations, whichever is greater.
- 4 Sprinklers should be aimed away from foundation walls and sprinkler heads, lines, and valves should be kept at least 5 feet from foundations. Sprinkler systems should be well maintained, checked for leaks frequently, and repaired promptly. Over watering should be avoided and consideration should be given to minimizing lawn areas.
- 5 Any additional precautions which may become evident during construction.

13.0 GENERAL CONDITIONS

The exploratory data presented in this report was collected to provide geotechnical design recommendations for this project. The test pits and test holes may not be indicative of subsurface conditions outside the study area or between points explored and thus have a limited value in depicting subsurface conditions for contractor bidding. Variations from the conditions portrayed in the test pits and test holes may occur and may be sufficient to require modifications in the design. If during construction, conditions are different than presented in this report, please advise us so that the appropriate modifications can be made.

The geotechnical study as presented in this report was conducted within the limits prescribed by our client, with the usual thoroughness and competence of the engineering profession in the area. No other warranty or representation, either expressed or implied, is intended in our proposals, contracts or reports.

**Geotechnical Study
Intermountain Regional Landfill
Fairfield, Utah**

Page 15

We appreciate the opportunity of providing our services on this project. If we can answer questions or be of further service, please call

Respectfully,

EARTHTEC TESTING AND ENGINEERING, P.C

Jeffrey J Egbert, P E
Project Geotechnical Engineer


William G Turner, P E
Senior Geotechnical Engineer

Earthtec

Professional Engineering Services - Geotechnical Engineering - Drilling Services - Construction Materials Inspection / Testing - Non-Destructive Examination - Failure Analysis
ICBO - ACI - AWS

VICINITY MAP

INTERMOUNTAIN REGIONAL LANDFILL




PROJECT NO 062496



FIGURE NO. 1

SITE PLAN & LOCATION OF EXPLORATIONS

INTERMOUNTAIN REGIONAL LANDFILL



TEST PIT LOG

NO.: TP- 1

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USGS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cent (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, light brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY, some sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | CH | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | X | | | | | | | | | |
| 7 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | | |
| 8 | | SM | | X | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | FAT CLAY with sand, very stiff, moist, gray | | | | | | | | | | |
| 11 | | CH | | X | | | | | | | | | |
| 12 | | | Bottom at approximately 11 feet | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO.: 062496



FIGURE NO 3

LOG OF TESTPIT 062496 GPJ EARTHTEC.GDT 4/12/07

TEST PIT LOG

NO.: TP- 2

PROJECT Intermountam Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO . 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇ .

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, minor pinholes, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | CH | | X | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | X | | | | | | | | |
| 6 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | | |
| 7 | | SM | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | X | 4 | | | 0 | 75 | 25 | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolodation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO . 062496



FIGURE NO 4

TEST PIT LOG

NO.: TP- 3

PROJECT Intermountain Regional Landfill
CLIENT. David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT. RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE: 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, very stiff, slightly moist, gray-brown | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | CH | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | X | | | | | | | | | |
| 7 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | | |
| 8 | | SM | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | X | | | | | | | | | |
| | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 5

LOG OF TESTPIT 062496 GPJ EARTHTEC.GDT 4/12/07

TEST PIT LOG

NO.: TP- 4

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY. P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | |
| 3 | | | ELASTIC SILT with sand, minor pinholes, very stiff, slightly moist, gray | X | 19 | | 50 | 17 | | | | |
| 4 | | MH | | | | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | |
| 7 | | | | X | | | | | | | | |
| 8 | | | SILTY SAND, medium dense, moist, brown | | | | | | | | | |
| 9 | | SM | | | | | | | | | | |
| 10 | | | | X | | | | | | | | |
| 11 | | | Bottom at approximately 10 feet. | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO. 062496



FIGURE NO 6

LOG OF TESTPIT_062496.GPJ EARTHTEC.GDT 4/12/07

TEST PIT LOG

NO.: TP- 5

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇ .

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | Perc |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | X | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GFJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 7

TEST PIT LOG

NO.: TP- 6

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION: NM
LOGGED BY: P E

AT COMPLETION ▽ .

| Depth (Ft.) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|-------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, pockets of white sand, very stiff, slightly moist, gray | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | |
| 5 | | | | X | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | |
| 9 | | | | X | 22 | | 63 | 41 | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO · 8

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP- 7

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | FAY CLAY with sand, very stiff, slightly moist to moist, gray | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | |
| 5 | | | | X | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | | | | | 23 | 90 | 70 | 37 | | | | C |
| 11 | | | Bottom at approximately 10 feet | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 9

TEST PIT LOG

NO.: TP- 8

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 10

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP- 9

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION. Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇ .

PROJECT NO 062496
DATE. 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | |
| 3 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 4 | | | | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | X | 23 | | 73 | 50 | | | | | |
| 11 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 11

TEST PIT LOG

NO.: TP-10

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|---|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | 26 | 91 | 70 | 50 | | | | C |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes. No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO • 062496



FIGURE NO 12

LOG OF TESTPIT 062496.GPJ EARTHTEC QBT 4/12/07


TEST PIT LOG

NO.: TP-11

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION. Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE. 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | | |
|------------|--|------|--|---------|---------------------------------|----------------|----|----|------------|----------|-----------|-------------|--|--|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | | |
| 1 | | | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | | | |
| 3 |  | CH | FAT CLAY with sand, some layers of white sand, very stiff, slightly moist to moist, gray | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | |
| 9 | | | | | Minor pinholes at 8.5 feet | | | | | | | | | | |
| 10 | | | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 13

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP-12

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO. 062496
DATE. 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | Sandy SILT, stiff, slightly moist, brown | | | | | | | | | | |
| 3 | | ML | | | | | | | | | | | |
| 4 | | | | X | 11 | | | | 0 | 37 | 63 | | |
| 5 | | | FAT CLAY with sand, very stiff, slightly moist to moist, gray-brown | | | | | | | | | | |
| 6 | | | | X | | | | | | | | | |
| 7 | | CH | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | X | | | | | | | | | |
| 10 | | | | | | | | | | | | | |
| 11 | | | Bottom at approximately 10 feet | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes. No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 14

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP-13

PROJECT Intennountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO · 062496
DATE · 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft.) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|-------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, minor pinholes, very shff, slightly moist, white | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | X | | | | | | | | |
| 5 | | | Moist, gray-brown at 4 feet, | X | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | X | | | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 15

TEST PIT LOG

NO.: TP-14

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY: P E

AT COMPLETION ▽

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|---------|---------------------------------|----------------|----|----|------------|----------|-----------|-------------|--|---|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | ▽▽ | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 1 | ▽▽ | | FAT CLAY with sand, minor pinholes, very stiff, slightly moist, white | | | | | | | | | | | |
| 2 | ▨ | CH | Moist, gray at 4 feet | | | | | | | | | | | |
| 3 | ▨ | | | | | | | | | | | | | |
| 4 | ▨ | | | | | X | | | | | | | | |
| 5 | ▨ | | | | | | | | | | | | | |
| 6 | ▨ | | | | | █ | 20 | 93 | 71 | 47 | | | | C |
| 7 | ▨ | | | | | | | | | | | | | |
| 8 | ▨ | | | | | | | | | | | | | |
| 9 | ▨ | | | | | X | | | | | | | | |
| 10 | ▨ | | | | | | | | | | | | | |
| 11 | | | | | Bottom at approximately 10 feet | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |

Notes: No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO. 16

TEST PIT LOG

NO.: TP-15

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER; INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|---------|-----------------------|----------------|----|----|------------|----------|-----------|-------------|--|---|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 1 | | | | | | | | | | | | | | |
| 2 | | CH | FAT CLAY with sand, minor pinholes, very stiff, slightly moist, light brown | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | |
| 5 | | | | | Moist, gray at 5 feet | X | | | | | | | | |
| 6 | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | |
| 8 | | | | | | █ | 19 | 93 | 61 | 37 | | | | C |
| 9 | | | | | | | | | | | | | | |
| 10 | | | Bottom at approximately 10 feet | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key
 CBR = California Bearing Ratio
 C = Consolidation
 R = Resistivity
 DS = Direct Shear
 SS = Soluble Sulfates
 UC = Unconfined Compressive Strength

PROJECT NO 062496



FIGURE NO 17

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

TEST PIT LOG

NO.: TP-16

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇.

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | | | | | | | | | | | |
| 2 | | | FAT CLAY with sand, very stiff, slightly moist, light brown | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | Moist, gray at 4 feet | X | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | | Perc |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | X | 20 | | 70 | 46 | | | | | |
| 10 | | | Bottom at approximately 10 feet. | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 OF J EARTHTEC 09/07 4/12/07

PROJECT NO : 062496



FIGURE NO 18

TEST PIT LOG

NO.: TP-17

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇.

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | |
| 1 | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | |
| 3 | | | FAT CLAY with layers of white sand, very stiff, slightly moist to moist, gray-brown | | | | | | | | | |
| 4 | | | | X | | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | | CH | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | X | | | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | |
| | | | Bottom at approximately 10 feet | | | | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO. 062496



FIGURE NO. 19

TEST PIT LOG

NO.: TP-18

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------|------|--|---------------------------------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | |
| 1 | | | FAT CLAY with sand, minor pinholes, very stiff, slightly moist, light brown Moist, gray at 5 feet | | | | | | | | | | |
| 2 | | CH | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | | | X | 22 | | 71 | 47 | | | |
| | | | | Bottom at approximately 10 feet | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC 09/07 4/12/07

PROJECT NO 062496



FIGURE NO 20

TEST PIT LOG

NO.: TP-19

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | TEST RESULTS | | | | | | | | | | | |
|------------|-------------|------|---|--------------|----------------|---------------------------------|----|----|------------|----------|-----------|-------------|--|--|------|
| | | | | Samples | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | | |
| 1 | | | FAT CLAY with sand, very stiff, slightly moist, light brown | | | | | | | | | | | | |
| 2 | | CH | Moist, gray at 3 feet | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | | |
| 4 | | | | | | | X | 16 | | 53 | 28 | | | | Perc |
| 5 | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | |
| 10 | | | | | | | X | | | | | | | | |
| 11 | | | | | | Bottom at approximately 10 feet | | | | | | | | | |
| 12 | | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 G.F.J. EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO. 21

TEST PIT LOG

NO.: TP-20

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR: Halls
EQUIPMENT RTB
DEPTH TO WATER, INITIAL ∇

PROJECT NO 062496
DATE 09/07/06 - 09/08/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ∇

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|--|
| | | | | | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 1 | | | FAT CLAY with sand, very stiff, slightly moist, light brown Moist, gray at 5 feet CH | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | |
| 4 | | | | | X | 16 | | 58 | 35 | | | | | |
| 5 | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | | |
| 8 | | | | | X | | | | | | | | | |
| 9 | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | |
| 11 | | | Bottom at approximately 10 feet | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTPIT 062496 GPJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 22

TEST HOLE LOG

NO.: TH-1

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basm
EQUIPMENT Mobile A T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE: 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E
AT COMPLETION ▼

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | |
|------------|-------------|------|---|---------|----------------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|
| | | | | | Blows per feet | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | |
| 3 | | CH | FAT CLAY with sand, stiff to hard, slightly moist to moist, brown | | | | | | | | | | | |
| 6 | | | | 25 | | | | | | | | | | |
| 9 | | | | 26 | | | | | | | | | | |
| 12 | | | | 35 | | | | | | | | | | |
| 15 | | | | 15 | | | | | | | | | | |
| 18 | | | | | 21 | 97 | 77 | 51 | | | | | C | |
| 21 | | | | | 40 | | | | | | | | | |
| 24 | | | | | | | | | | | | | | |

Notes. No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO: 062496



FIGURE NO 23a

LOG OF TESTHOLE 062496.GPJ EARTHTEC.GDT 4/12/07

TEST HOLE LOG

NO.. TH-1

PROJECT Intermountam Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basm
EQUIPMENT Mobile A.T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▽ :

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|-------------------|------|---|------------|---------------------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Blows per foot | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 27 | [Hatched Pattern] | CH | FAT CLAY with sand, stiff to hard, slightly moist to moist, brown | [Triangle] | 20 | 19 | | 52 | 26 | | | | |
| 30 | | | | | | | | | | | | | |
| | | | Bottom at approximately 31 feet 5 5 inches | | 17 35 50/5 5" | | | | | | | | |
| 33 | | | | | | | | | | | | | |
| 36 | | | | | | | | | | | | | |
| 39 | | | | | | | | | | | | | |
| 42 | | | | | | | | | | | | | |
| 45 | | | | | | | | | | | | | |
| 48 | | | | | | | | | | | | | |

Notes: No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolhdation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO . 062496



FIGURE NO. 23b

LOG OF TESTHOLE 062496 GPJ EARTHTEC GDT 4/12/07

TEST HOLE LOG

NO.: TH-2

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basin
EQUIPMENT Mobile A T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▽ :

| Depth (Ft) | Graphic Log | USCS | Description | Samples | TEST RESULTS | | | | | | | | | | |
|------------|-------------|------|--|---------|----------------|----------------|----------------|----|----|------------|----------|-----------|-------------|--|--|
| | | | | | Blows per foot | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests | | |
| 0 | | | TOPSOIL Silt with sand, dry, brown | | | | | | | | | | | | |
| 3 | | CH | FAT CLAY with sand, hard to very stiff, slightly moist to moist, brown | | | | | | | | | | | | |
| 6 | | | | 47 | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | | |
| 12 | | | | 24 | | | | | | | | | | | |
| 15 | | | | 45 | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | | | |
| 21 | | | | 38 | 13 | | 55 | 36 | | | | | | | |
| 24 | | | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

LOG OF TESTHOLE 062496 G/FJ EARTHTEC GDT 4/12/07

PROJECT NO 062496



FIGURE NO 24a


TEST HOLE LOG

NO.: TH-2

PROJECT Intermountain Regional Landfill
CLIENT David Johnston
LOCATION Refer to Figure 2
OPERATOR Great Basn
EQUIPMENT Mobile A T
DEPTH TO WATER, INITIAL ▽

PROJECT NO 062496
DATE: 09/27/06 - 09/27/06
ELEVATION NM
LOGGED BY P E

AT COMPLETION ▽

| Depth (Ft) | Graphic Log | USGS | Description | Samples | TEST RESULTS | | | | | | | | |
|------------|--|------|--|---------|---------------------|----------------|----------------|----|----|------------|----------|-----------|-------------|
| | | | | | Blows per foot | Water Cont (%) | Dry Dens (pcf) | LL | PI | Gravel (%) | Sand (%) | Fines (%) | Other Tests |
| 27 |  | CH | FAT CLAY with sand, hard to very stiff, slightly moist to moist, brown | | | | | | | | | | |
| 30 | | | | | | | | | | | | | |
| 33 | | | | | 60 | 15 | 55 | 33 | | | | | |
| 36 | | | | | | | | | | | | | |
| 39 | | | | | | | | | | | | | |
| 42 | | | Bottom at approximately 41 feet 5 5 inches | | 13 34 50/5 5" | | | | | | | | |
| 45 | | | | | | | | | | | | | |
| 48 | | | | | | | | | | | | | |

Notes No groundwater encountered

Tests Key

- CBR = California Bearing Ratio
- C = Consolidation
- R = Resistivity
- DS = Direct Shear
- SS = Soluble Sulfates
- UC = Unconfined Compressive Strength

PROJECT NO · 062496



FIGURE NO 24b

LOG OF TESTHOLE 062496 GPJ EARTHTEC GDT 4/12/07
















LEGEND

PROJECT Intermountain Regional Landfill
CLIENT David Johnston






DATE 09/07/06
LOGGED BY P E

UNIFIED SOIL CLASSIFICATION SYSTEM



USCS
MAJOR SOIL DIVISIONS **SYMBOL** **TYPICAL SOIL DESCRIPTIONS**

| | | | | | |
|--|---|---|---|---|---|
| COARSE GRAINED SOILS (More than 50% retaining on No 200 Sieve) | GRAVELS (More than 50% of coarse fraction retained on No 4 Sieve) | CLEAN GRAVELS (Less than 5% fines) |  | GW | Well Graded Gravel, May Contain Sand, Very Little Fines |
| | | GRAVELS WITH FINES (More than 12% fines) |  | GP | Poorly Graded Gravel, May Contain Sand, Very Little Fines |
| | | SANDS (50% or more of coarse fraction passes No 4 Sieve) | CLEAN SANDS (Less than 5% fines) |  | GM |
| | SANDS (50% or more of coarse fraction passes No 4 Sieve) | SANDS WITH FINES (More than 12% fines) |  | GC | Clayey Gravel, May Contain Sand |
| | | |  | SW | Well Graded Sand, May Contain Gravel, Very Little Fines |
| | | |  | SP | Poorly Graded Sand, May Contain Gravel, Very Little Fines |
| FINE GRAINED SOILS (More than 50% passing No 200 Sieve) | SILTS AND CLAYS (Liquid Limit less than 50) |  | SM | Silty Sand, May Contain Gravel | |
| | |  | SC | Clayey Sand, May Contain Gravel | |
| | |  | CL | Lean Clay, Inorganic, May Contain Gravel and/or Sand | |
| | SILTS AND CLAYS (Liquid Limit Greater than 50) |  | ML | Silt, Inorganic, May Contain Gravel and/or Sand | |
| | |  | OL | Organic Silt or Clay, May Contain Gravel and/or Sand | |
| | |  | CH | Fat Clay, Inorganic, May Contain Gravel and/or Sand | |
| HIGHLY ORGANIC SOILS |  | MH | Elastic Silt, Inorganic, May Contain Gravel and/or Sand | | |
| |  | OH | Organic Clay or Silt, May Contain Gravel and/or Sand | | |
| | |  | PT | Peat, Primarily Organic Matter | |

SAMPLER DESCRIPTIONS

-  SPLIT SPOON SAMPLER
(1 3/8 inch inside diameter)
-  MODIFIED CALIFORNIA SAMPLER
(2 inch outside diameter)
-  SHELBY TUBE
(3 inch outside diameter)
-  BLOCK SAMPLE
-  BAG/BULK SAMPLE

WATER SYMBOLS

-  Water level encountered during field exploration
-  Water level encountered at completion of field exploration


- NOTES:**
- 1 The logs are subject to the limitations, conclusions, and recommendations in this report
 - 2 Results of tests conducted on samples recovered are reported on the logs and any applicable graphs
 - 3 Strata lines on the logs represent approximate boundaries only Actual transitions may be gradual
 - 4 In general, USCS symbols shown on the logs are based on visual methods only actual designations (based on laboratory tests) may vary

PROJECT NO 062496



FIGURE NO · 25

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intennountain Regional Landfill |
| Location | TP-7 |
| Sample Depth | 9 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 90 |
| Natural Moisture, % | 23 |
| Liquid Limit | 70 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 1.5 |

PROJECT NO 062496



FIGURE NO 26

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-10 |
| Sample Depth | 8½ |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 91 |
| Natural Moisture, % | 26 |
| Liquid Limit | 70 |
| Plasticity Index | 50 |
| Water Added at | 1 ksf |
| Percent Swell | 1.1 |

PROJECT NO 062496



FIGURE NO 27

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-14 |
| Sample Depth | 6 |
| Description | Block |
| Soil Type | FTA CLAY (CH) |
| Dry Density, pcf | 93 |
| Natural Moisture, % | 20 |
| Liquid Limit | 71 |
| Plasticity Index | 47 |
| Water Added at | 1 ksf |
| Percent Swell | 0.9 |

PROJECT NO 062496



FIGURE NO 28

CONSOLIDATION - SWELL TEST




| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-15 |
| Sample Depth | 7½ |
| Description | Block |
| Soil Type | FTA CLAY (CH) |
| Dry Density, pcf | 93 |
| Natural Moisture, % | 19 |
| Liquid Limit | 61 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 0.9 |

PROJECT NO 062496



FIGURE NO 29

CONSOLIDATION - SWELL TEST



| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TH-1 |
| Sample Depth | 15 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 97 |
| Natural Moisture, % | 21 |
| Liquid Limit | 77 |
| Plasticity Index | 51 |
| Water Added at | 1 ksf |
| Percent Swell | 0.7 |

PROJECT NO 062496



FIGURE NO 30

APPENDIX F

SLOPE STABILITY AND SETTLEMENT ANALYSIS

APPENDIX F

SLOPE STABILITY AND SETTLEMENT ANALYSIS

INTERMOUNTAIN REGIONAL LANDFILL
FAIRFIELD, UTAH

CLASS I LANDFILL PERMIT APPLICATION

ISSUED AUGUST 2010
PREPARED BY
HDR ENGINEERING, INC

TABLE OF CONTENTS

| | | |
|-------------|--|---|
| SECTION 1 0 | INTRODUCTION | 1 |
| | 1 1 PURPOSE | 1 |
| | 1 2 SCOPE | 1 |
| SECTION 2 0 | SITE CONDITIONS | 2 |
| | 2 1 LOCATION | 2 |
| | 2 2 SOILS | 2 |
| | 2 3 SEISMICITY | 2 |
| | 2 4 ADOPTED DESIGN VALUES | 2 |
| SECTION 3 0 | STATIC AND PSEUDO-STATIC STABILITY ANALYSES AND DEFORMATION ANALYSES | 4 |
| | 3 1 METHOD OF ANALYSIS | 4 |
| | 3 2 CASES CONSIDERED | 4 |
| | 3 2 1 MAXIMUM CUT SLOPE (EXCAVATION) | 4 |
| | 3 2 2 MAXIMUM FILL SLOPE (WASTE) | 4 |
| | 3 2 3 WASTE FILL OVER LINER AND LEACHATE COLLECTION SYSTEM (SLIDING BLOCK) | 4 |
| | 3 3 METHODOLOGY | 4 |
| SECTION 4 0 | SETTLEMENT AND LINER STRAIN | 6 |
| | 4 1 SETTLEMENT | 6 |
| | 4 2 LINER STRAIN | 6 |
| SECTION 5 0 | FINDINGS AND CONCLUSIONS | 7 |
| | 5 1 FINDINGS | 7 |
| | 5 2 CONCLUSIONS | 7 |
| SECTION 6 0 | REFERENCES | 8 |

ATTACHMENTS

| | |
|-----------------|---|
| ATTACHMENT 1 | MAXIMUM HORIZONTAL ACCELERATION & DESIGN EARTHQUAKE |
| ATTACHMENT 1A | USGS MAPPING, REFERENCE B |
| ATTACHMENT 1B | SOIL CONSISTENCY, REFERENCE D |
| ATTACHMENT 2 | SLOPE STABILITY CASES AND RUNS |
| ATTACHMENT 2A | PLAN VIEWS, CROSS SECTIONS, AND DETAILS |
| ATTACHMENT 2B | DISPLACEMENT CHART, REFERENCE A |
| ATTACHMENT 2C | SLOPE STABILITY RUNS & RESULTS |
| ATTACHMENT 2C-1 | SLOPE STABILITY RUNS & RESULTS – CUT SLOPE |
| ATTACHMENT 2C-2 | SLOPE STABILITY RUNS & RESULTS – FILL SLOPE |
| ATTACHMENT 2C-3 | SLOPE STABILITY RUNS & RESULTS – WASTE MASS SLIDING BLOCK |
| ATTACHMENT 3 | SETTLEMENT CALCULATIONS |
| ATTACHMENT 3A | SETTLEMENT AND CONSOLIDATION CALCULATIONS |

SECTION 1.0 INTRODUCTION

1.1 PURPOSE

This technical memorandum presents the results of slope stability and settlement analyses as part of the 2010 Permit Application for the Intermountain Regional Landfill (the Site) in Fairfield, Utah. The purpose of this work is to

- Evaluate the stability of the maximum cut and fill slopes
- Evaluate the settlement along the leachate collection and recovery system (LCRS) piping alignments

The Site is located in a seismic impact zone as defined by the State of Utah Administrative Code (UAC) R315-301-2. This report provides analyses demonstrating that "all containment structures, including liners, leachate collection systems, and surface water control systems, are designed to resist the maximum horizontal acceleration in lithified earth material for the site." In addition, this report provides analyses demonstrating that the LCRS piping alignment maintains positive drainage toward the sumps.

These analyses have been conducted in accordance with the State of Utah Administrative Code and U.S. Environmental Protection Agency (EPA) guidance presented in Resource Conservation and Recovery Act (RCRA) Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities (EPA 1995).

1.2 SCOPE

The scope of this report includes a literature review of regional and local seismicity, demonstration analyses of the seismic performance and settlement of the site features, and findings and conclusions. This report is divided into the following sections:

- Section 2.0, Site Conditions, presents soils, geology, and site-specific seismicity data for the Site.
- Section 3.0, Static and Pseudo-Static Stability Analyses and Deformation Analyses, presents stability analyses for maximum cut and maximum fill slopes.
- Section 4.0, Settlement and Liner Strain, presents estimates of settlement along the LCRS piping alignment.
- Section 5.0, Findings and Conclusions, discusses the impact of the estimated deformations and settlement on the function of the landfill features.

SECTION 2.0 SITE CONDITIONS

2.1 LOCATION

The Site is located in Township 7 South, Range 2 West, west half of Section 16 (Salt Lake Base and Meridian) in Utah County. The Site is located southeast of the intersection of county roads 800 South and 18150 West. The approximate latitude and longitude of the site are 40 21 degrees and -112 07 degrees, respectively. This location is in Cedar Valley between the Thorpe Hills on the west and the Lake Mountains on the east.

2.2 SOILS

Information on the site soils has been obtained from regional references and on-site soil borings. The locations of the on-site borings are shown on the Site Plan & Location of Explorations, Figure 2 of Reference 1.

The surficial soils consist of mostly lacustrine fine-grained deposits (Qlf, see Reference 2). Twenty test pit excavations and two test holes were advanced during the Geotechnical Study (Reference 1) to depths ranging from 10 feet to 41 feet below grade. The soil borings indicate that the soils consist mostly of very stiff to hard fat clay (CH) with a few layers of dense silty sand (SM) and very stiff elastic silt (MH). Standard penetration blow counts range from 15 to refusal in the fat clay.

2.3 SEISMICITY

The probabilistic bedrock maximum (peak) horizontal acceleration for a return period of 2% in 50 years (10% in 250 years) at the Site is 0.25g, as determined from the U.S. Geological Survey (USGS), National Seismic Hazard Mapping Project Probabilistic Seismic Hazards Assessment, Custom Mapping and Analysis Tools, Interactive Deaggregation Tool (2008) (<http://eqint.cr.usgs.gov/deaggint/2008/>).

Using the Interactive Deaggregation Tool and adjusting the shear wave velocity based on the site-specific soil characteristics, the maximum (peak) horizontal acceleration for the Site was determined to be 0.28g. This value was used to evaluate the cut slope and the waste mass stability. See Attachment 1.

The peak maximum credible earthquake was also determined probabilistically using the same source and methodology. A magnitude 7.0 was used for slope stability evaluation. See Attachment 1.

The design accelerations (above the bedrock at bottom of waste) for Short Period, S_{DS} , and for 1-Second Period, S_{D1} , were determined to be 0.55g and 0.31g, respectively. These were determined by Earthtec in accordance with International Building Code (IBC) using a Site Class D classification. See Reference 1. These values are appropriate to evaluate structural components that are not part of this analysis.

2.4 ADOPTED DESIGN VALUES

The regional soil stratigraphy and site-specific boring logs were reviewed to establish a design profile for use in stability and settlement analyses. Soil shear strengths were based on the laboratory soil testing program and correlations with the Standard Penetration Test results, Attachment 1, Reference D. Waste shear strengths were based on EPA data (EPA 1995).

The adopted stratigraphy and corresponding physical properties for stability are summarized in Table 2.1 below from Attachment 2.

Table 2 1
Adopted Soil Properties (Attachment 2)

| Feature | Depth (ft) | Total Unit Weight (PCF) | Saturated Unit Weight (PCF) | Cohesion (PSF)* | Phi (degrees) | Material |
|-----------------------|------------|-------------------------|-----------------------------|----------------------------------|-------------------------------|----------|
| Upper very stiff clay | 0-10 | 113.5 | 121.0 | 3000 short term, 50 long term | 0 short term, 29 long term | CH |
| Less stiff clay | 10-20 | 121.0 | 125.5 | 1500 short term, 50 long term | 0 short term, 29 long term | CH |
| Stiff clay | 20-30 | 121.0 | 125.5 | 2000 short term, 50 long term | 0 short term, 29 long term | CH |
| Lower very stiff clay | 30+ | 121.0 | 125.5 | 3000 short term, 50 long term | 0 short term, 50 long term | CH |
| Waste | Vanes | 50.0 | 60.0 | 150 | 22 | Waste* |
| LCRS | | 100.0 | 110.0 | 0 | 32 | Sand |
| Cap | | 110.0 | 120.0 | 1000 | 0 | Clay |

*EPA Reference 4

The adopted seismic properties for stability, as discussed in the previous section, are summarized in Table 2 2 from Attachment 2

Table 2 2
Maximum Horizontal Acceleration and Design Earthquake (Attachment 2)

| Location | Maximum Horizontal Acceleration | Design Earthquake Intensity |
|-----------------------------|---------------------------------|-----------------------------|
| Bottom of waste (cut slope) | 0.28g | 7.0 |
| Waste mass (fill slope) | 0.28g | 7.0 |

SECTION 3.0 STATIC AND PSEUDO-STATIC STABILITY ANALYSES AND DEFORMATION ANALYSES

3.1 METHOD OF ANALYSIS

The stability analyses were performed using the computer program PCSTABL7 (Purdue University 2002) and STEDwin Smart Editor (Van Aller 2007). The STABL program is an analytical tool developed by Purdue University that uses limit equilibrium techniques to search for and identify the critical failure surface and provides estimates of the factor of safety against instability. Failure surfaces can be circular, block, or random in shape depending on the geometry of the slope, loading condition, and subsurface details. STEDwin is a user interface for STABL that allows on-screen data entry and modifications and generates graphics.

3.2 CASES CONSIDERED

Stability analyses were conducted to determine the factor of safety against slope failures under static and pseudo-static loading conditions. The following landfill features, which are shown on Figure 2-1, were considered:

3.2.1 Maximum Cut Slope (Excavation)

The proposed excavation will be 1V 4H (25%) slopes to a maximum depth of nominally 45 feet at the east portion of the cells. To be conservative, a maximum depth of 50 feet was evaluated.

3.2.2 Maximum Fill Slope (Waste)

The proposed waste fill slopes are about 2.5% north and south and about 5% east and west from the crest at El 4950+ to a variable slope break, ranging between from El 4898 to 4905. The side slopes are 1V 4H (25%) from the slope break to original grade. Maximum waste fill heights in Cell 4 are 130 feet above the cell bottom and 100 feet above original grade. These slopes are consistent with UAC R315-303-4(4).

3.2.3 Waste Fill over Liner and Leachate Collection System (Sliding Block)

The proposed liner system will consist of a lower cushion nonwoven geotextile (or a sand cushion) placed on the subgrade. A geosynthetic clay liner (GCL) will be placed over the lower cushion with a 60-mil textured high-density polyethylene (HDPE) geomembrane overlying the GCL. The leachate collection/protective cover layer will consist of 2 feet of protective soil cover (granular leachate collection material) placed over an upper cushion geotextile placed over the HDPE geomembrane.

It is anticipated that the Cell 4 waste fills could reach a maximum of 130 feet above the liner/leachate collection system in the adjacent Cell 5 area. For analysis, a waste/intermediate soil cover slope of 1V 3H (33%) was evaluated.

3.3 METHODOLOGY

Both static and pseudo-static conditions were evaluated. The generalized factor of safety against a slope failure is defined as $FS = s/t$, where s is the available shear strength of the slope and t is the shear strength required for unity ($FS = 1.0$).

The Simplified Bishop circular arc method was used to evaluate the global stability of the excavated and filled slopes. The computer program PCSTABL7 (Purdue University 2002) was used to conduct these analyses. This program searches for the potential failure surface that produces the lowest factor of safety. The location of this failure surface is a function of the site geometry (slope angle and height), material stratigraphy and physical properties, and loadings (weight of soil and/or waste above the failure surface).

The sliding block (wedge) method was used to evaluate the sliding stability along the bottom liner and the LCRS system. The computer program PCSTABL7 (Purdue University 2002) was also used to conduct these analyses. The failure surface is defined by the bottom of the cell. For a given slope geometry, the interface friction angle, δ , between adjacent materials normally controls slope stability, with the lowest interface friction angle controlling overall slope stability. Adopted friction values for the geosynthetic interfaces are presented in Table 3.1.

A minimum static safety factor of 1.3 was adopted (EPA 1995). The pseudo-static seismic coefficient (a_y) was iterated for both the circular arc and sliding block analyses to determine the yield acceleration (a_y) corresponding to a factor of safety of 1.0. This yield acceleration is used to estimate the excavation, closure cap, and leachate collection system deformations cell (Section 5).

Table 3.1
Adopted Interface Friction Angles

| Lower | Upper | Interface Friction Angle (degrees) |
|---|---|------------------------------------|
| Soil subgrade | Lower cushion nonwoven geotextile or sand cushion | 25 |
| Lower cushion nonwoven geotextile or sand cushion | Geosynthetic clay liner (GCL) | 25 |
| Geosynthetic clay liner (GCL) | 60-mil textured HDPE geomembrane | 18 |
| 60-mil textured HDPE geomembrane | Upper cushion nonwoven geotextile | 18 |
| Upper cushion nonwoven geotextile | 2-ft leachate collection/protective soil cover | 18 |

The results of the static and pseudo-static stability analyses for the excavations and waste fills are presented in Attachment 2 and summarized below in Table 3.2. The results indicate that the static factor of safety is adequate for the existing and proposed cut and fill slope geometry. The yield accelerations at a safety factor of 1.0 are near the adopted peak bedrock acceleration, suggesting minimal permanent deformation (EPA 1995).

Table 3.2
Global Stability Results

| Feature | Static Factor of Safety | Yield Acceleration | Displacement, U (cm) |
|--|----------------------------------|--------------------|----------------------|
| Maximum excavation slope, 1V 4H (short-term controls) | 2.95 | 0.10g | 14.0 |
| Maximum fill slope, 1V 4H | 2.19 | 0.28g | 0.05 |
| Waste fill over liner and leachate collection system (sliding block) | 1.46 (18° interface friction) | 0.13g | 8.0 |

SECTION 4 0 SETTLEMENT AND LINER STRAIN

4 1 SETTLEMENT

For this analysis, settlement was calculated along the Cell 3 leachate collection pipe alignment for the worst-case scenario. Points along the alignment were evaluated to determine if the slope toward the sump would be positive after final waste has been placed. The results are shown in Table 4 1.

Table 4 1
Differential Settlement Results

| Point | Location | Thickness of Waste (ft) | Settlement (ft) | Final Slope between Points (%) |
|-------|---|-------------------------|-----------------|--------------------------------|
| 1 | Interior west toe of slope | 42 | 1 6 | NA |
| 2 | 120 ft east of west toe of slope | 72 | 1 8 | 1 69 |
| 3 | 560 ft east of west toe of slope | 100 | 2 0 | 1 54 |
| 4 | 1110 ft east of west toe of slope | 134 | 2 2 | 1 53 |
| 5 | 1660 ft east of west toe of slope | 73 | 1 8 | 1 44 |
| 6 | 2160 ft east of west toe of slope (east sump) | 46 | 1 6 | 1 45 |

4 2 LINER STRAIN

The strain in the liner between the points above was also determined based on the initial and final (after settlement) slope information. The calculated strains were much less than the 17% allowable. See Attachment 3.

SECTION 5.0 FINDINGS AND CONCLUSIONS

5.1 FINDINGS

The Intermountain Regional Landfill site is located in a seismic impact zone. Probabilistic methods indicate a peak bedrock acceleration of 0.25g. Factoring the on-site soils and waste properties, the maximum bottom of waste and waste mass accelerations were both determined to be 0.28g.

The cut and fill slopes have adequate static factor of safety and indicate minimal permanent deformations ($U < 30$ cm) in response to the design seismic event. The upper limit of 30 cm (1 ft) was established as the maximum tolerable deformation of the geosynthetic components (EPA 1995).

Settlement along the leachate collection line (worst case) was evaluated in Attachment 3 and was determined to range from 1.6 ft to 2.2 ft. Differential settlement calculations indicate that positive slopes toward the sumps will be maintained and liner strains ($< 1\%$) will be less than allowable (17%).

5.2 CONCLUSIONS

The analyses show that the proposed Intermountain Regional Landfill components are designed to resist the "maximum horizontal acceleration" at the site.

SECTION 6 0 REFERENCES

Earthtec 2009 Geotechnical Study Intermountain Regional Landfill, Fairfield, Utah October 13

[EPA] U S Environmental Protection Agency 1995 RCRA Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities EPA/600/R-95/051 Prepared by G N Richardson and E Kavazanjan

Purdue University 2002 PCSTABL7 Slope Stability Computer Program

Van Aller, H W 2007 STEDwin Smart Editor for PCSTABL

**ATTACHMENT 1: MAXIMUM HORIZONTAL
ACCELERATION & DESIGN EARTHQUAKE**

| | | | | | |
|---------|---------------------------------|-------------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PJP</i> | Date | 4.6.10 |
| Task | Slope Stability MHA & Design EQ | Page 1 of 2 | | | |
| Job # | Dept 00143 | No | 125184 | | |

1.1 Task

- A Determine the maximum (peak) horizontal acceleration (MHA) for the site
 - a At bedrock
 - b At bottom of waste
 - c At top of waste
- B Determine the design earthquake for the site

1.2 References

- A EPA, Richardson, G N and Kavazanjian, E (1995), RCRA Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities, EPA/600/R-95/051
- B USGS, National Seismic Hazard Mapping Project Probabilistic Seismic Hazards Assessment , Custom Mapping and Analysis Tools, Interactive Deaggregation Tool [http //eqint cr usgs gov/deaggint/2008/index php](http://eqint.cr.usgs.gov/deaggint/2008/index.php)
- C Earthtec Testing & Engineering, P C (2006) Geotechnical Study Intermountain Regional Landfill
- D Das, B , (1990) Principles of Foundation Engineering, 2nd Ed

1.3 Summary

- A Site location 40 21 degrees latitude, -112 07 degrees longitude Ref C
- B Determine the shear wave velocity
 - a Below the waste
 - b Depth & N, Standard Penetration values

| TH-1, Ref C, Figure No's 23a & 23b | | | | |
|------------------------------------|-------------|--|--------------|-----------------------------|
| Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* | Shear Wave Velocity** (m/s) |
| 2.5-4.0 | 25 | 3.0 | Very Stiff | 650 |
| 5.0-6.5 | 26 | 3.0 | Very Stiff | 650 |
| 7.5-9.0 | 35 | 4.0+ | Hard | 700 |
| 10.0-11.5 | 15 | 1.5 | Stiff | 550 |
| 20.0-21.5 | 40 | 4.0+ | Hard | 700 |
| 25.0-26.5 | 20 | 2.0 | Stiff | 550 |
| 30.0-31.5 | 80+ | 4.0+ | Hard | 700 |

| | | | | | |
|---------|---------------------------------|----------|-------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PJP</i> | Date | 11-26-10 |
| Task | Slope Stability MHA & Design EQ | | Page 2 of 2 | | |
| Job # | Dept 00143 | No | 125184 | | |

| TH-2, Ref C, Figure No's 24a & 24b | | | | |
|------------------------------------|-------------|--|--------------|-----------------------------|
| Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* | Shear Wave Velocity** (m/s) |
| 5 0-6 5 | 47 | 4 0+ | Hard | 700 |
| 10 0-11 5 | 24 | 3 0 | Very Stiff | 650 |
| 15 0-16 5 | 45 | 4 0+ | Hard | 700 |
| 20 0-21 5 | 38 | 4 0+ | Hard | 700 |
| 30 0-31 5 | 60 | 4 0+ | Hard | 700 |
| 40 0-41 5 | 80+ | 4 0+ | Hard | 700 |

Notes

* Reference D, pg 87

** Reference A, Section 4

1.4 Results

A Maximum (peak) Horizontal Acceleration (MHA)

- a At bedrock = 0.2467g (Vs=760 m/s) Reference B, see attached
- b At the bottom of the waste = 0.2747g (Vs=500 m/s) Reference B, see attached Note that Reference A indicates to use the bedrock acceleration based on the site specific shear wave velocities (stiff soils, page 45 of Ref A) Therefore this value is conservative
- c From Reference C (Earthtec) These accelerations to be used for evaluation of structures on the site and not the slopes or waste mass The evaluation of structures was not part of this analysis
 - i $S_{DS} = 0.55g$, Short Period Acceleration (bottom of waste)
 - ii $S_{DI} = 0.31g$, 1-Second Acceleration (bottom of waste)
- d For slope stability evaluation (worst case, maximum accelerations)
 - i Bottom of Waste (cut slope) = 0.28g
 - ii The average acceleration of the failure mass (waste fill slope) = 0.28g See Reference A, pages 46 and 47

B Maximum (peak) horizontal acceleration (MHA)

- a Magnitude of the design earthquake for the site 7.0 Reference B, see Attachment 1A

ATTACHMENT 1A: USGS MAPPING, REFERENCE B

PSH Deaggregation on NEHRP BC rock
Intermountain R 112.070° W, 40.210 N.

Peak Horiz. Ground Accel. ≥ 0.2467 g


Ann. Exceedance Rate .409E-03. Mean Return Time 2475 years

Mean (R,M, ϵ_0) 20.4 km, 6.54, 0.87

Modal (R,M, ϵ_0) = 24.8 km, 6.99, 1.07 (from peak R,M bin)

Modal (R,M, ϵ^*) = 24.8 km, 6.99, 1 to 2 sigma (from peak R,M, ϵ bin)

Binning: DeltaR 10. km, deltaM=0.2, Delta ϵ =1.0



PSH Deaggregation on NEHRP C soil
 Intermountain R 112.070° W, 40.210 N.

Peak Horiz. Ground Accel. ≥ 0.2747 g


Ann. Exceedance Rate $.410E-03$. Mean Return Time 2475 years

Mean (R,M, ϵ_0) 19.7 km, 6.57, 0.90

Modal (R,M, ϵ_0) = 24.9 km, 6.99, 1.05 (from peak R,M bin)

Modal (R,M, ϵ^*) = 24.9 km, 6.99, 1 to 2 sigma (from peak R,M, ϵ bin)

Binning: DeltaR 10. km, deltaM=0.2, Delta ϵ =1.0



Prob. SA, PGA

<median(R,M)

>median

$\epsilon_0 < -2$

$0 < \epsilon_0 < 0.5$

$-2 < \epsilon_0 < -1$

$0.5 < \epsilon_0 < 1$

$-1 < \epsilon_0 < -0.5$

$1 < \epsilon_0 < 2$

$-0.5 < \epsilon_0 < 0$

$2 < \epsilon_0 < 3$

200910 UPDATE

**ATTACHMENT 1B: SOIL CONSISTENCY,
REFERENCE D**

From Ref D

where A_R = area ratio
 D_o = outside diameter of the sampling tube
 D_i = inside diameter of the sampling tube

When the area ratio is 10% or less, the sample is generally considered to be undisturbed For a standard split-spoon sampler

$$A_R(\%) = \frac{(50.8)^2 - (34.93)^2}{(34.93)^2} (100) = 111.5\%$$

Hence, these samples are highly disturbed Split-spoon samples are generally taken at intervals of about 1.53 m (5 ft)

When the material encountered on the field is sand (particularly fine sand below the water table), sample recovery by a split-spoon sampler may be difficult In that case, a device such as a spring core catcher may have to be placed inside the split spoon (Figure 2.7b)

Besides obtaining soil samples, standard penetration tests provide several useful correlations For example, the consistency of clayey soils can often be estimated from the standard penetration number (N) This is shown in Table 2.3

Table 2.3 Consistency of Clays and Approximate Correlation to the Standard Penetration Number N

| Standard penetration number, N | Consistency | Unconfined compression strength, q_u (kN/m ²) | q_u TSF |
|----------------------------------|--------------|---|-----------|
| 0-2 | Very soft | 0-25 | 0-0.26 |
| 2-5 | Soft | 25-50 | 0.26-0.52 |
| 5-10 | Medium stiff | 50-100 | 0.52-1.04 |
| 10-20 | Stiff | 100-200 | 1.04-2.09 |
| 20-30 | Very stiff | 200-400 | 2.09-4.17 |
| >30 | Hard | >400 | >4.17 |

1 kN/m² = 0.01044 tons/ft²
 pg 719


In granular soils, the N -value is affected by the effective overburden pressure, a'_v . For that reason, the N -value obtained from field exploration at different effective overburden pressures should be changed to correspond to a standard value of a'_v . This means that

$$N_{cor} = C_N N_F \quad (2.4)$$

N_{cor} = corrected N -value to a standard value of a'_v [95.6 kN/m² (1 ton/ft²)]

C_N = correction factor

N_F = N -value obtained from the field



ing
 ie

er is driven into
 d The standard
 low, the hammer
 ows required for
 e recorded The
 dded to give the
 referred to as the
 986, Designation
 and the couple
 be is then plac

y expressed by

**ATTACHMENT 2: SLOPE STABILITY CASES AND
RUNS**

| | | | | | |
|---------|---------------------------------|----------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PHF</i> | Date | 4-26-12 |
| Task | Slope Stability Cases | Page | 1 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |

2.1 Task

- A Determine the Static Factor of Safety (FS) and Seismic Yield Acceleration (a_y) for
 - a Case 1 Maximum Cut Slope
 - b Case 2 Maximum Fill Slope
 - c Case 3 Maximum Operational Waste Fill Slope (sliding block)
- B Determine the maximum displacement and verify less than 30 CM

2.2 References

- A EPA, Richardson, G N and Kavazanjian, E (1995), RCRA Subtitle D (258) Seismic Design Guidance for Municipal Solid Waste Landfill Facilities, EPA/600/R-95/051
- B Salgado, R , Purdue University (2002) PCSTABL7 Slope Stability Computer Program, Joint Highway Research Program FHWA, and Van Aller, H W (2007) STEDwin Smart Editor for PCSTABL
- C Earthtec Testing & Engineering, P C (2006) Geotechnical Study Intermountain Regional Landfill
- D Das, B , (1990) Principles of Foundation Engineering, 2nd Ed
- E HDR (2010) Determination of the MHA and Design EQ Calculations

2.3 Soil Profile and Matenal Properties (Reference C and E)

- A Unit weight/classification

| <u>Sample, Depth (FT)</u> | <u>Dry Density (PCF)</u> | <u>Water Content (%)</u> | <u>Total Unit Weight (PCF)</u> | <u>Classification</u> |
|---------------------------|--------------------------|--------------------------|--------------------------------|-----------------------|
| TP-14, 6' | 93 | 20 | 111.7 | CH |
| TP-15, 7.5' | 93 | 19 | 110.7 | CH |
| TP-10, 8.5' | 91 | 26 | 114.7 | CH |
| TP-7, 9' | 90 | 23 | 110.7 | CH |
| TH-1, 15'-17' | 97 | 21 | 117.4 | CH |

Unit weight relationship

$$Y_d = \frac{(G_s \cdot Y_w)}{(1+e)}, \quad e = \frac{(G_s \cdot Y_w)}{Y_d} - 1, \quad Y_{sat} = \frac{(G_s + e) \cdot (Y_w)}{(1+e)}, \quad \text{Reference D}$$

Where

Y_d = Dry Density

e = void ratio

Y_{sat} = saturated unit weight

G_s = 2.70 (assumed)

| | | | | | |
|---------|---------------------------------|-------------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>RHP</i> | Date | 4 26 10 |
| Task | Slope Stability Cases | Page 2 of 6 | | | |
| Job # | Dept 00143 | No | 125184 | | |

$\gamma_w = 62.4 \text{ PCF}$

- i) Depth 0-10' $\gamma_d = 93 \text{ PCF}$, $w = 22.0$, $\gamma_{total} = 113.5$, $e = 0.8$, $\gamma_{sat} = 121.0 \text{ PCF}$
- ii) Depth 10+ For $\gamma_d = 100 \text{ PCF}$, $w = 21.0$, $\gamma_{total} = 121.0$, $e = 0.68$, $\gamma_{sat} = 125.5 \text{ PCF}$

B Strength

| TH-1, Ref C, Figure No's 23a & 23b | | | |
|------------------------------------|-------------|--|-----------------|
| Sample Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* |
| 2.5-4.0 | 25 | 3.0 | Very Stiff (CH) |
| 5.0-6.5 | 26 | 3.0 | Very Stiff (CH) |
| 7.5-9.0 | 35 | 4.0+ | Hard (CH) |
| 10.0-11.5 | 15 | 1.5 | Stiff (CH) |
| 20.0-21.5 | 40 | 4.0+ | Hard (CH) |
| 25.0-26.5 | 20 | 2.0 | Stiff (CH) |
| 30.0-31.5 | 80+ | 4.0+ | Hard (CH) |

| TH-2, Ref C, Figure No's 24a & 24b | | | |
|------------------------------------|-------------|--|-----------------|
| Depth (FT) | N, Blows/FT | Unconfined Compressive Strength Correlation (TSF)* | Consistency* |
| 5.0-6.5 | 47 | 4.0+ | Hard (CH) |
| 10.0-11.5 | 24 | 3.0 | Very Stiff (CH) |
| 15.0-16.5 | 45 | 4.0+ | Hard (CH) |
| 20.0-21.5 | 38 | 4.0+ | Hard (CH) |
| 30.0-31.5 | 60 | 4.0+ | Hard (CH) |
| 40.0-41.5 | 80+ | 4.0+ | Hard (CH) |

Notes

* Reference D, pg 87

| | | | | | |
|---------|---------------------------------|-------------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | PHD | Date | 4/26/10 |
| Task | Slope Stability Cases | Page 3 of 6 | | | |
| Job # | Dept 00143 | No | 125184 | | |

C Design values

| Feature | Depth (FT) | Total Unit Weight (PCF) | Saturated Unit Weight (PCF) | Cohesion (PSF)* | Phi (Degrees) | Material |
|-----------------------|------------|-------------------------|-----------------------------|----------------------------------|-------------------------------|----------|
| Upper Very Stiff Clay | 0-10 | 113.5 | 121.0 | 3000 Short Term, 50 Long Term | 0 Short Term, 29 Long Term | CH |
| Less Stiff Clay | 10-20 | 121.0 | 125.5 | 1500 Short Term, 50 Long Term | 0 Short Term, 29 Long Term | CH |
| Stiff Clay | 20-30 | 121.0 | 125.5 | 2000 Short Term, 50 Long Term | 0 Short Term, 29 Long Term | CH |
| Lower Very Stiff Clay | 30+ | 121.0 | 125.5 | 3000 Short Term, 50 Long Term | 0 Short Term, 50 Long Term | CH |
| Waste | Vanes | 50.0 | 60.0 | 150 | 22 | Waste** |
| LCRS | | 100.0 | 110.0 | 0 | 32 | Sand |
| Cap | | 110.0 | 120.0 | 1000 | 0 | Clay |


* Reference D, pg 87

**EPA, Reference 4

| | | | | | |
|---------|---------------------------------|----------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | PHH | Date | 4/26/10 |
| Task | Slope Stability Cases | Page | 4 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |


2.4 Cross Sections

A West-East Cross Section (see attached)



| | | | | | |
|---------|---------------------------------|----------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | <i>PHF</i> | Date | 4 16 10 |
| Task | Slope Stability Gases | Page | 5 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |

B North-South Cross Sections (see attached)



| | | | | | |
|---------|---------------------------------|----------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Slope Stability | Checked | PHP | Date | 4 26 10 |
| Task | Slope Stability Gases | Page | 6 of 6 | | |
| Job # | Dept 00143 | No | 125184 | | |

- C Case 1 - Maximum Cut Slope
 - i) East end of East-West cross-section (Cell 1, Phase 3) Depth of cut=45 FT
Use 50 FT for analysis
 - ii) Slope = 4H 1V
 - iii) See Attachment 2C-1 for stability output
- D Case 2 - Maximum Fill Slope (Waste)
 - i) East end of the East-West cross section (Cell 1, Phase 3) Height above existing grade = 80 FT Use 100 FT for analysis
 - ii) Slope = 4H 1V
 - iii) See Attachment 2C-2 for stability output
- E Case 3 – Maximum Operational Fill Slope (Cell 4/Cell 5)
 - i) Maximum waste height = 130 FT above cell floor
 - ii) Waste slope = 3H 1V
 - iii) See Attachment 2C-3 for stability output

2.5 Results

| Feature | Static Factor of Safety | Yield Acceleration | Displacement, U (CM) |
|--|----------------------------------|--------------------|----------------------|
| Maximum Excavation Slope, 1V 4H (Short Term controls) | 2.95 | 0.10g | 14.0 |
| Maximum Fill Slope, 1V 4H | 2.19 | 0.28g | 0.05 |
| Waste Fill Over Liner and Leachate Collection System (Sliding Block) | 1.46 (18° Interface Friction) | 0.13g | 8.0 |

**ATTACHMENT 2A: PLAN VIEWS, CROSS SECTIONS,
AND DETAILS**

C:\P\working\11\1601\16405\01\003.dwg Plot: 3/1/2010 1:44:13 PM ghafer


1/6
 0 200
 SCALE IN FEET

NOTES:
 EXISTING TOPOGRAPHIC DATA IS FROM
 AERIAL SURVEYS INC. NOVEMBER 18,

| BENCHMARKS | | | |
|------------|------------|------------|---|
| BM | N | E | I |
| 8633 | 7248525.12 | 1477789.21 | |
| 8634 | 7248548.22 | 1480525.47 | |
| 8635 | 7243226.01 | 1480483.01 | |
| 8636 | 7243237.28 | 1477790.04 | |
| 8637 | 7245607.75 | 1477851.32 | |
| 8638 | 7245688.82 | 1480470.15 | |

LEGEND

- - - - - EXISTING CONTOURS
- — — — CELL FOOTPRINT BOUNDARY
- — — — PROPOSED 1 DRAWN LINE
- - - - - LITTER CONTROL FENCE LOC.



| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |
| | | |



| | | |
|----------------|-----------|-----------|
| PROJECT | MM4001 | T. WARNER |
| CHECKED BY | S. WDMACK | |
| DESIGNED BY | C. HODARY | |
| DRAWN BY | C. HODARY | |
| PROJECT NUMBER | | |

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |

INTERMOUNTAIN
 REGIONAL
 LANDFILL

| SITE PLAN | |
|-----------|---------------------|
| 0 1 2 | FILENAME: D1003.DWG |
| | SCALE: 1"=200' |

2/6



| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |
| | | |


| | |
|-----------------|------------|
| PROJECT MANAGER | T. WINKER |
| CHECKED BY | S. WOMBACK |
| DESIGNED BY | C. MCCARTY |
| DRAWN BY | C. MCCARTY |
| PROJECT NUMBER | |

INTERMOUNTAIN REGIONAL LANDFILL

FINAL COVER PLAN

| | | |
|----------|------------|---------|
| 0 | 1 | 2' |
| FILENAME | 010005.DWG | SHEET |
| SCALE | 1"=200' | 5 OF 13 |

3/6



CROSS SECTION EAST-WEST
ALL CELLS



| | |
|-----------------|------------|
| PROJECT MANAGER | T. WINKER |
| DESIGNED BY | S. WORMACK |
| DRAWN BY | C. MCCARTY |
| PROJECT NUMBER | |
| DATE | |
| DESCRIPTION | |


INTERMOUNTAIN
REGIONAL
LANDFILL

CROSS SECTION

0 1 2
SCALE 1"=100'

FILENAME 010007.DWG SHEET 7 OF 12

4/6




| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| | |
|-----------------|------------|
| PROJECT MANAGER | T. WARNER |
| CHECKED BY | S. WISNACK |
| DESIGNED BY | C. MCCARTY |
| DRAWN BY | C. MCCARTY |
| PROJECT NUMBER | |

INTERMOUNTAIN
REGIONAL
LANDFILL

| | | | | | | |
|---------------|--|--|----------|------------|-------|---------|
| CROSS SECTION | | | FILENAME | 010000 CRG | SHEET | 8 OF 13 |
| | | | SCALE | 1"=100' | | |

5/6



CROSS SECTION NORTH-SOUTH
ALL CELLS




| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |
| | | |

| | |
|----------------|-------------|
| PROJECT NUMBER | T 10000 |
| CHECKED BY | S. WIMACK |
| DESIGNED BY | C. MCCARTHY |
| DRAWN BY | C. MCCARTHY |
| | |
| PROJECT NUMBER | |


INTERMOUNTAIN
REGIONAL
LANDFILL

| | | | | |
|------------------|--|--|------------------------|------------------|
| CROSS SECTION | | | FILENAME 01000E.DWG | SHEET 9 OF 13 |
| SCALE 1"=100' | | | | |

6/6




TYPICAL LANDFILL LINER DETAIL
NOT TO SCALE



LINER SYSTEM ANCHOR TRENCH
NOT TO SCALE

NOTE
1. AREA BETWEEN TOP 2 OF EXCAVATION AND BACK OF ANCHOR TRENCH TO BE GRADED SMOOTH AND EVEN PRIOR TO PLACING UPPER GEOTEXTILE. REMOVE ANGULAR STONES.



LINER AT SLOPE TRANSITION
NOT TO SCALE

NOTE: THICKNESS MEASURED PERPENDICULAR TO EXCAVATION SURFACE.

- NOTES:
1. TEMPORARY STORMWATER INTERCEPTOR BERM TO BE PLACED IN FRONT OF WORKING AREA TO DIVERT STORMWATER AWAY FROM ACTIVE FACE. OWNER WILL RELOCATE AS NEEDED.
 2. STAGE 2 GEOMEMBRANE TO BE WELDED TO STAGE 1 FUTURE GEOSYNTHETIC COMPONENTS TO BE OVERLAPPED AND SECURED.
 3. PIPE 1 GEOTEXTILE IS REINFORCED AND REQUIRED ON SEE SLOPES ONLY ABOVE HOPE LINER. TYPE 2 GEOTEXTILE IS NON-REINFORCED (NON-WOVEN) AND IS TO BE USED ABOVE HOPE LINER ON SLOPES AND BETWEEN SUBGRADE AND CCL. A SAND CUSHION MAY BE USED IN LIEU OF THE LOWER TYPE 2 GEOTEXTILE WITH PRIOR APPROVAL OF ENGINEER AND OWNER.
 4. SEE SPECIFICATION 02240 FOR PROTECTIVE COVER MATERIAL REQUIREMENTS.
 5. SEE SPECIFICATION 02776 FOR REQUIRED MINIMUM INTERFACE FRICTION VALUES.

| GEOTEXTILE SCHEDULE | | |
|------------------------------------|------|---|
| LOCATION | TYPE | COMMENTS |
| ALL | ALL | REMOVE ALL ANGULAR STONES GREATER THAN 0.5 INCHES |
| LOWER GEOTEXTILE | 2 | USE 16 OZ/SY NON-WOVEN IF ROUNDED STONES GREATER THAN 2 INCHES ARE REMOVED. USE 20 OZ/SY NON-WOVEN IF ONLY ROUNDED STONES GREATER THAN 4 INCHES ARE REMOVED. NO HORIZONTAL SEAMS ON SIDESLOPES. |
| UPPER GEOTEXTILE ON SIDESLOPES | 1 | REINFORCED GEOTEXTILE. NO HORIZONTAL SEAMS ON SIDESLOPES. |
| UPPER GEOTEXTILE ON BOTTOM (FLOOR) | 2 | USE 12 OZ/SY NON-WOVEN BENEATH DUNE SAND (PROTECTIVE SOIL COVER). |

C:\PW\working\PHX\014085\01\0009.dwg Plot: 3/1/2010 2:07:11 PM gahar:

| ISSUE | DATE | DESCRIPTION |
|-------|------|-------------|
| | | |
| | | |
| | | |

| | |
|-----------------|------------|
| PROJECT MANAGER | T. WARNER |
| CHECKED BY | S. WOMACK |
| DESIGNED BY | C. MCCARTY |
| DRAWN BY | C. MCCARTY |
| PROJECT NUMBER | |

INTERMOUNTAIN REGIONAL LANDFILL

LINER DETAILS

| | | |
|--|------------------------------------|----------------|
| | FILENAME: 010009.DWG SCALE: NTS | SHEET: 9 OF 12 |
|--|------------------------------------|----------------|

**ATTACHMENT 2B: DISPLACEMENT CHART,
REFERENCE A**

Ref. A





Figure 6 6 Makdisi and Seed Permanent Displacement Chart (Makdisi and Seed, 1978)

**ATTACHMENT 2C: SLOPE STABILITY RUNS &
RESULTS**

**ATTACHMENT 2C-1: SLOPE STABILITY RUNS &
RESULTS – CUT SLOPE**


Cut slope (Max)
H=50'



H 1"=50'
 V 1"=20'

| Horizontal Acceleration | Short Term FS | Long Term FS |
|-------------------------|---------------|--------------|
| static | 2.95 | 2.49 |
| 0.1g | 1.00 ← | 1.75 |
| 0.2g | 0.57 | 1.33 |

↑ Controls



| | | | | | |
|---------|-----------------|----------|-----|------|---------|
| Project | IRL | Computed | GMS | Date | 4/20/10 |
| Subject | slope stability | Checked | PHR | Date | 4-26-10 |
| Task | Cut slope | Page | 2 | of | 130 |
| Job # | 125184 | Dist | 143 | No | |

Maximum Cut slope results / Displacement

$$a_{max} = 0.28g \text{ (Reference E)}$$

$$a_y = 0.1g \text{ (Previous page)}$$


$$\frac{a_y}{a_{max}} = \frac{0.1g}{0.28g} = 0.36 \text{ @ } M=70$$

Attachment 2B (Reference A)

$$U_{max} = 14 \text{ cm} < 30 \text{ cm (max allow)} \quad \underline{\underline{OK}}$$

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\lrf1\pl2 Run By Greg Shafer HDR 4/20/2010 02:22PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Piez Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|--------------|
| a | 2.85 | | | | | | No |
| b | 2.85 | | | | | | No |
| c | 2.86 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | W1 |
| d | 2.86 | LSC | 2 | 121.0 | 125.5 | 1500.0 | W1 |
| e | 2.87 | SC | 3 | 121.0 | 125.5 | 2000.0 | W1 |
| f | 2.87 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | W1 |
| g | 2.87 | | | | | | |
| h | 2.88 | | | | | | |
| i | 2.89 | | | | | | |
| j | 2.89 | | | | | | |

PCSTABL7 FSmin=2.85
 Safety Factors Are Calculated By The Modified Bishop Method

STED



3/150

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 02 22PM
Run By Greg Shafer, HDR
Input Data Filename C 1 in
Output Filename C 1 OUT
Unit ENGLISH
Plotted Output Filename C 1 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below End |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param (psf) | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 280 00 ft
and X = 770 00 ft
Each Surface Terminates Between X = 950 00 ft
and X =2000 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 341 25 | 615 01 |
| 2 | 348 38 | 508 00 |
| 3 | 355 61 | 601 09 |
| 4 | 362 94 | 594 29 |
| 5 | 370 37 | 587 59 |
| 6 | 377 89 | 580 99 |
| 7 | 385 50 | 574 51 |
| 8 | 393 20 | 568 13 |
| 9 | 400 99 | 561 87 |
| 10 | 408 88 | 555 71 |
| 11 | 416 85 | 549 67 |
| 12 | 424 90 | 543 74 |
| 13 | 433 04 | 537 93 |

| | | |
|----|---------|--------|
| 14 | 441 26 | 532 24 |
| 15 | 449 56 | 526 66 |
| 16 | 457 93 | 521 20 |
| 17 | 466 39 | 515 86 |
| 18 | 474 92 | 510 64 |
| 19 | 483 52 | 505 54 |
| 20 | 492 20 | 500 57 |
| 21 | 500 94 | 495 72 |
| 22 | 509 75 | 490 99 |
| 23 | 518 63 | 486 39 |
| 24 | 527 58 | 481 92 |
| 25 | 536 58 | 477 57 |
| 26 | 545 65 | 473 36 |
| 27 | 554 78 | 469 27 |
| 28 | 563 96 | 465 31 |
| 29 | 573 20 | 461 49 |
| 30 | 582 49 | 457 79 |
| 31 | 591 84 | 454 23 |
| 32 | 601 23 | 450 80 |
| 33 | 610 68 | 447 51 |
| 34 | 620 16 | 444 35 |
| 35 | 629 69 | 441 33 |
| 36 | 639 27 | 438 44 |
| 37 | 648 88 | 435 69 |
| 38 | 658 53 | 433 07 |
| 39 | 668 22 | 430 60 |
| 40 | 677 95 | 428 26 |
| 41 | 687 70 | 426 06 |
| 42 | 697 49 | 424 00 |
| 43 | 707 30 | 422 07 |
| 44 | 717 14 | 420 29 |
| 45 | 727 00 | 418 65 |
| 46 | 736 89 | 417 15 |
| 47 | 746 80 | 415 79 |
| 48 | 756 72 | 414 57 |
| 49 | 766 66 | 413 49 |
| 50 | 776 62 | 412 56 |
| 51 | 786 59 | 411 76 |
| 52 | 796 57 | 411 11 |
| 53 | 806 55 | 410 60 |
| 54 | 816 55 | 410 23 |
| 55 | 826 55 | 410 00 |
| 56 | 836 55 | 409 92 |
| 57 | 846 54 | 409 98 |
| 58 | 856 54 | 410 18 |
| 59 | 866 54 | 410 52 |
| 60 | 876 53 | 411 00 |
| 61 | 886 51 | 411 63 |
| 62 | 896 48 | 412 40 |
| 63 | 906 43 | 413 31 |
| 64 | 916 38 | 414 36 |
| 65 | 926 31 | 415 56 |
| 66 | 936 22 | 416 89 |
| 67 | 946 11 | 418 37 |
| 68 | 955 98 | 419 98 |
| 69 | 965 82 | 421 74 |
| 70 | 975 64 | 423 64 |
| 71 | 985 43 | 425 67 |
| 72 | 995 19 | 427 85 |
| 73 | 1004 92 | 430 16 |
| 74 | 1014 61 | 432 51 |
| 75 | 1024 27 | 435 20 |
| 76 | 1033 89 | 437 93 |
| 77 | 1043 48 | 440 79 |
| 78 | 1053 02 | 443 79 |
| 79 | 1062 51 | 446 92 |
| 80 | 1071 96 | 450 19 |
| 81 | 1081 37 | 453 60 |

6/130

| | | | | |
|-----|------|----|-----|----|
| 82 | 1090 | 72 | 457 | 13 |
| 83 | 1100 | 02 | 460 | 80 |
| 84 | 1109 | 27 | 464 | 61 |
| 85 | 1118 | 46 | 468 | 54 |
| 86 | 1127 | 60 | 472 | 60 |
| 87 | 1136 | 68 | 476 | 80 |
| 88 | 1145 | 70 | 481 | 12 |
| 89 | 1154 | 65 | 485 | 57 |
| 90 | 1163 | 54 | 490 | 14 |
| 91 | 1172 | 37 | 494 | 85 |
| 92 | 1181 | 13 | 499 | 67 |
| 93 | 1189 | 82 | 504 | 63 |
| 94 | 1198 | 43 | 509 | 70 |
| 95 | 1206 | 98 | 514 | 90 |
| 96 | 1215 | 44 | 520 | 22 |
| 97 | 1223 | 84 | 525 | 65 |
| 98 | 1232 | 15 | 531 | 21 |
| 99 | 1240 | 38 | 536 | 89 |
| 100 | 1248 | 54 | 542 | 68 |
| 101 | 1255 | 61 | 548 | 58 |
| 102 | 1264 | 59 | 554 | 60 |
| 103 | 1272 | 49 | 560 | 74 |
| 104 | 1280 | 30 | 566 | 98 |
| 105 | 1288 | 02 | 573 | 34 |
| 106 | 1295 | 55 | 579 | 80 |
| 107 | 1303 | 18 | 586 | 38 |
| 108 | 1310 | 62 | 593 | 06 |
| 109 | 1317 | 97 | 599 | 84 |
| 110 | 1325 | 22 | 606 | 73 |
| 111 | 1332 | 37 | 613 | 72 |
| 112 | 1339 | 42 | 620 | 81 |
| 113 | 1346 | 37 | 628 | 01 |
| 114 | 1353 | 21 | 635 | 30 |
| 115 | 1359 | 95 | 642 | 68 |
| 116 | 1366 | 59 | 650 | 16 |
| 117 | 1373 | 12 | 657 | 74 |
| 118 | 1379 | 54 | 665 | 41 |
| 119 | 1383 | 27 | 670 | 00 |

Circle Center At X = 837 5 , Y = 1112 7 and Radius, 702 8
 *** 2 850 ***

Individual data on the 126 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Sot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 7 1 | 3062 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 7 2 | 9269 | 7 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 7 3 | 15552 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 7 4 | 21902 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 7 5 | 28311 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 7 6 | 34769 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 7 7 | 41268 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 7 8 | 47800 | 7 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 7 9 | 54356 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 8 0 | 60927 | 7 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 8 1 | 67506 | 3 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 12 | 8 1 | 74083 | 2 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 8 2 | 80650 | 6 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 8 3 | 87200 | 2 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 8 4 | 93723 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 8 5 | 100212 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 8 5 | 106658 | 9 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 8 6 | 113055 | 3 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 8 7 | 119393 | 6 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 8 7 | 125666 | 0 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 8 8 | 131865 | 4 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 22 | 8 9 | 137983 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 23 | 8 9 | 144013 | 1 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

| | | | | | | | | | |
|----|------|----------|-----|-----|-----|-----|-----|-----|-----|
| 24 | 9 0 | 149947 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 25 | 9 1 | 155779 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 26 | 9 1 | 161502 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 27 | 9 2 | 167109 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 28 | 9 2 | 172592 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 29 | 9 3 | 177946 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 30 | 9 3 | 183165 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 31 | 9 4 | 188242 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 32 | 9 4 | 193171 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 33 | 9 5 | 197947 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 34 | 9 5 | 202565 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 35 | 9 6 | 207019 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 36 | 9 6 | 211304 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 37 | 9 7 | 215413 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 38 | 9 7 | 219345 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 39 | 9 7 | 223092 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 40 | 9 8 | 226652 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 41 | 9 8 | 230021 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 42 | 9 8 | 233194 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 43 | 9 8 | 236168 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 44 | 9 9 | 238940 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 45 | 9 9 | 241505 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 46 | 9 9 | 243863 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 47 | 3 2 | 79195 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 48 | 6 7 | 157083 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 49 | 9 9 | 235711 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 50 | 10 0 | 240000 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 51 | 10 0 | 244094 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 52 | 10 0 | 247990 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 53 | 10 0 | 251684 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 54 | 10 0 | 255174 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 55 | 10 0 | 258454 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 56 | 3 5 | 90014 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 57 | 5 5 | 182803 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 58 | 10 0 | 281635 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 59 | 10 0 | 284263 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 60 | 10 0 | 286660 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 61 | 3 5 | 99879 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 62 | 6 5 | 189432 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 63 | 10 0 | 291499 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 64 | 10 0 | 293189 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 65 | 10 0 | 294641 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 66 | 3 6 | 105898 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 67 | 6 4 | 190434 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 68 | 9 9 | 297575 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 69 | 9 9 | 298309 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 70 | 9 9 | 298803 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 71 | 3 9 | 117829 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 72 | 6 0 | 180724 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 73 | 9 8 | 296033 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 74 | 9 8 | 293082 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 75 | 9 8 | 289918 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 76 | 9 8 | 286544 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 77 | 9 7 | 282965 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 78 | 9 7 | 279183 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 79 | 9 7 | 275204 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 80 | 9 6 | 271033 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 81 | 9 6 | 266671 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 82 | 9 5 | 262129 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 83 | 9 5 | 257404 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 84 | 9 5 | 252509 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 85 | 9 4 | 247444 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 86 | 9 4 | 242215 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 87 | 9 3 | 236831 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 88 | 9 2 | 231299 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 89 | 9 2 | 225619 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 90 | 9 1 | 219803 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 91 | 9 1 | 213856 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

8/130

| | | | | | | | | | | |
|-----|-----|----------|-----|-----|-----|-----|-----|-----|-----|-----|
| 92 | 9 0 | 207784 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 93 | 9 0 | 201592 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 94 | 8 9 | 195291 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 95 | 8 8 | 188889 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 96 | 8 8 | 182387 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 97 | 8 7 | 175797 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 98 | 8 6 | 169128 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 99 | 8 5 | 162383 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 100 | 8 5 | 155573 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 101 | 8 4 | 148706 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 102 | 8 3 | 141792 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 103 | 8 2 | 134833 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 104 | 8 2 | 127843 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 105 | 8 1 | 120826 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 106 | 8 0 | 113794 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 107 | 7 9 | 106755 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 108 | 7 8 | 99714 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 109 | 7 7 | 92685 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 110 | 7 6 | 85671 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 111 | 7 5 | 78686 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 112 | 7 4 | 71734 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 113 | 7 3 | 54826 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 114 | 7 2 | 57972 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 115 | 7 2 | 51178 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 116 | 7 0 | 44453 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 117 | 6 9 | 37808 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 118 | 6 8 | 31250 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 119 | 4 3 | 16484 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 120 | 2 4 | 8304 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 121 | 6 5 | 18091 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 122 | 0 1 | 339 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 123 | 6 5 | 12186 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 124 | 1 9 | 2407 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 125 | 4 5 | 3748 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 126 | 3 7 | 973 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By139 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 280 00 | 514 26 |
| 2 | 287 20 | 607 32 |
| 3 | 294 49 | 600 47 |
| 4 | 301 86 | 593 71 |
| 5 | 309 30 | 587 03 |
| 6 | 316 83 | 580 45 |
| 7 | 324 43 | 573 95 |
| 8 | 332 11 | 567 55 |
| 9 | 339 87 | 561 24 |
| 10 | 347 70 | 555 02 |
| 11 | 355 60 | 548 89 |
| 12 | 363 58 | 542 86 |
| 13 | 371 62 | 536 92 |
| 14 | 379 74 | 531 08 |
| 15 | 387 93 | 525 34 |
| 16 | 396 18 | 519 70 |
| 17 | 404 50 | 514 15 |
| 18 | 412 89 | 508 70 |
| 19 | 421 34 | 503 36 |
| 20 | 429 86 | 498 11 |
| 21 | 438 43 | 492 97 |
| 22 | 447 07 | 487 93 |
| 23 | 455 76 | 482 99 |
| 24 | 464 52 | 478 16 |
| 25 | 473 33 | 473 43 |
| 26 | 482 19 | 468 80 |
| 27 | 491 12 | 464 28 |
| 28 | 500 09 | 459 87 |
| 29 | 509 12 | 455 57 |
| 30 | 518 19 | 451 37 |

9/130

| | | |
|----|---------|--------|
| 31 | 527 32 | 447 28 |
| 32 | 536 49 | 443 30 |
| 33 | 545 71 | 439 44 |
| 34 | 554 98 | 435 68 |
| 35 | 564 29 | 432 03 |
| 36 | 573 65 | 428 49 |
| 37 | 583 04 | 425 06 |
| 38 | 592 47 | 421 75 |
| 39 | 601 95 | 418 55 |
| 40 | 611 46 | 415 46 |
| 41 | 621 01 | 412 48 |
| 42 | 630 59 | 409 62 |
| 43 | 640 20 | 406 88 |
| 44 | 649 85 | 404 25 |
| 45 | 659 53 | 401 73 |
| 46 | 669 24 | 399 33 |
| 47 | 678 97 | 397 04 |
| 48 | 688 73 | 394 87 |
| 49 | 698 52 | 392 82 |
| 50 | 708 33 | 390 88 |
| 51 | 718 17 | 389 06 |
| 52 | 728 02 | 387 36 |
| 53 | 737 89 | 385 78 |
| 54 | 747 78 | 384 31 |
| 55 | 757 69 | 382 96 |
| 56 | 767 62 | 381 73 |
| 57 | 777 56 | 380 62 |
| 58 | 787 51 | 379 62 |
| 59 | 797 47 | 378 75 |
| 60 | 807 44 | 377 99 |
| 61 | 817 42 | 377 35 |
| 62 | 827 40 | 376 83 |
| 63 | 837 40 | 376 43 |
| 64 | 847 39 | 376 15 |
| 65 | 857 39 | 375 99 |
| 66 | 867 39 | 375 95 |
| 67 | 877 39 | 376 02 |
| 68 | 887 39 | 376 22 |
| 69 | 897 38 | 376 53 |
| 70 | 907 37 | 376 97 |
| 71 | 917 36 | 377 52 |
| 72 | 927 34 | 378 19 |
| 73 | 937 31 | 378 98 |
| 74 | 947 26 | 379 89 |
| 75 | 957 21 | 380 91 |
| 76 | 967 15 | 382 06 |
| 77 | 977 07 | 383 32 |
| 78 | 986 97 | 384 71 |
| 79 | 996 85 | 386 21 |
| 80 | 1006 73 | 387 82 |
| 81 | 1016 57 | 389 56 |
| 82 | 1026 40 | 391 41 |
| 83 | 1036 20 | 393 38 |
| 84 | 1045 98 | 395 46 |
| 85 | 1055 74 | 397 66 |
| 86 | 1065 47 | 399 98 |
| 87 | 1075 17 | 402 42 |
| 88 | 1084 84 | 404 96 |
| 89 | 1094 48 | 407 63 |
| 90 | 1104 08 | 410 41 |
| 91 | 1113 65 | 413 30 |
| 92 | 1123 19 | 416 31 |
| 93 | 1132 69 | 419 43 |
| 94 | 1142 16 | 422 66 |
| 95 | 1151 58 | 426 00 |
| 96 | 1160 96 | 429 46 |
| 97 | 1170 30 | 433 03 |
| 98 | 1179 60 | 436 71 |

10/
130

| | | |
|-----|---------|--------|
| 99 | 1188 86 | 440 50 |
| 100 | 1198 06 | 444 40 |
| 101 | 1207 23 | 448 41 |
| 102 | 1216 34 | 452 53 |
| 103 | 1225 40 | 456 75 |
| 104 | 1234 41 | 461 09 |
| 105 | 1243 37 | 465 53 |
| 106 | 1252 28 | 470 08 |
| 107 | 1251 13 | 474 73 |
| 108 | 1269 93 | 479 49 |
| 109 | 1278 66 | 484 35 |
| 110 | 1287 34 | 489 32 |
| 111 | 1295 96 | 494 39 |
| 112 | 1304 52 | 499 56 |
| 113 | 1313 02 | 504 83 |
| 114 | 1321 45 | 510 21 |
| 115 | 1329 82 | 515 68 |
| 116 | 1338 12 | 521 25 |
| 117 | 1346 36 | 526 93 |
| 118 | 1354 53 | 532 70 |
| 119 | 1362 62 | 538 56 |
| 120 | 1370 65 | 544 53 |
| 121 | 1378 61 | 550 58 |
| 122 | 1386 49 | 556 74 |
| 123 | 1394 30 | 562 98 |
| 124 | 1402 04 | 569 32 |
| 125 | 1409 70 | 575 75 |
| 126 | 1417 28 | 582 27 |
| 127 | 1424 78 | 588 88 |
| 128 | 1432 20 | 595 58 |
| 129 | 1439 55 | 602 37 |
| 130 | 1446 81 | 609 24 |
| 131 | 1453 99 | 616 20 |
| 132 | 1461 09 | 623 25 |
| 133 | 1468 10 | 630 38 |
| 134 | 1475 03 | 537 59 |
| 135 | 1481 87 | 644 88 |
| 136 | 1488 62 | 652 26 |
| 137 | 1495 29 | 659 71 |
| 138 | 1501 86 | 667 25 |
| 139 | 1504 21 | 670 00 |

Circle Center At X = 866 0 , Y = 1215 6 and Radius, 839 6
*** 2 851 ***

Failure Surface Specified By127 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 361 67 | 615 26 |
| 2 | 368 76 | 608 20 |
| 3 | 375 94 | 601 25 |
| 4 | 383 21 | 594 38 |
| 5 | 390 58 | 587 62 |
| 6 | 398 04 | 580 96 |
| 7 | 405 58 | 574 40 |
| 8 | 413 21 | 567 93 |
| 9 | 420 93 | 561 58 |
| 10 | 428 73 | 555 32 |
| 11 | 436 62 | 549 17 |
| 12 | 444 59 | 543 13 |
| 13 | 452 63 | 537 19 |
| 14 | 460 76 | 531 36 |
| 15 | 468 96 | 525 64 |
| 16 | 477 24 | 520 03 |
| 17 | 485 60 | 514 54 |
| 18 | 494 02 | 509 15 |
| 19 | 502 52 | 503 88 |
| 20 | 511 09 | 498 72 |
| 21 | 519 72 | 493 68 |
| 22 | 528 43 | 488 76 |

11/130

| | | |
|----|---------|--------|
| 23 | 537 19 | 483 95 |
| 24 | 546 03 | 479 26 |
| 25 | 554 92 | 474 68 |
| 26 | 563 87 | 470 23 |
| 27 | 572 89 | 465 90 |
| 28 | 581 96 | 461 69 |
| 29 | 591 08 | 457 60 |
| 30 | 600 26 | 453 63 |
| 31 | 609 49 | 449 79 |
| 32 | 618 77 | 446 07 |
| 33 | 628 11 | 442 47 |
| 34 | 637 48 | 439 00 |
| 35 | 646 91 | 435 66 |
| 36 | 656 38 | 432 44 |
| 37 | 665 89 | 429 35 |
| 38 | 675 44 | 426 39 |
| 39 | 685 03 | 423 55 |
| 40 | 694 65 | 420 84 |
| 41 | 704 32 | 418 27 |
| 42 | 714 01 | 415 82 |
| 43 | 723 74 | 413 50 |
| 44 | 733 50 | 411 32 |
| 45 | 743 28 | 409 25 |
| 46 | 753 10 | 407 34 |
| 47 | 762 94 | 405 54 |
| 48 | 772 80 | 403 88 |
| 49 | 782 68 | 402 35 |
| 50 | 792 58 | 400 96 |
| 51 | 802 50 | 399 69 |
| 52 | 812 44 | 398 56 |
| 53 | 822 39 | 397 56 |
| 54 | 832 35 | 396 70 |
| 55 | 842 32 | 395 97 |
| 56 | 852 30 | 395 37 |
| 57 | 862 29 | 394 91 |
| 58 | 872 29 | 394 58 |
| 59 | 882 29 | 394 38 |
| 60 | 892 29 | 394 32 |
| 61 | 902 29 | 394 39 |
| 62 | 912 28 | 394 60 |
| 63 | 922 28 | 394 93 |
| 64 | 932 27 | 395 41 |
| 65 | 942 25 | 396 01 |
| 66 | 952 22 | 396 76 |
| 67 | 962 18 | 397 63 |
| 68 | 972 13 | 398 64 |
| 69 | 982 07 | 399 78 |
| 70 | 991 99 | 401 05 |
| 71 | 1001 89 | 402 46 |
| 72 | 1011 77 | 404 00 |
| 73 | 1021 63 | 405 67 |
| 74 | 1031 46 | 407 47 |
| 75 | 1041 27 | 409 40 |
| 76 | 1051 06 | 411 47 |
| 77 | 1060 81 | 413 67 |
| 78 | 1070 54 | 415 99 |
| 79 | 1080 23 | 418 45 |
| 80 | 1089 89 | 421 03 |
| 81 | 1099 52 | 423 75 |
| 82 | 1109 10 | 426 59 |
| 83 | 1118 65 | 429 57 |
| 84 | 1128 16 | 432 67 |
| 85 | 1137 62 | 435 89 |
| 86 | 1147 05 | 439 25 |
| 87 | 1156 42 | 442 73 |
| 88 | 1165 75 | 446 33 |
| 89 | 1175 03 | 450 06 |
| 90 | 1184 26 | 453 91 |

12/130

| | | |
|-----|---------|--------|
| 91 | 1193 43 | 457 89 |
| 92 | 1202 55 | 461 99 |
| 93 | 1211 62 | 466 21 |
| 94 | 1220 63 | 470 55 |
| 95 | 1229 58 | 475 01 |
| 96 | 1238 47 | 479 59 |
| 97 | 1247 29 | 484 29 |
| 98 | 1256 06 | 489 11 |
| 99 | 1264 75 | 494 04 |
| 100 | 1273 38 | 499 09 |
| 101 | 1281 95 | 504 26 |
| 102 | 1290 44 | 509 54 |
| 103 | 1298 86 | 514 93 |
| 104 | 1307 21 | 520 43 |
| 105 | 1315 48 | 526 05 |
| 106 | 1323 68 | 531 78 |
| 107 | 1331 80 | 537 61 |
| 108 | 1339 84 | 543 56 |
| 109 | 1347 80 | 549 61 |
| 110 | 1355 68 | 555 77 |
| 111 | 1363 48 | 562 03 |
| 112 | 1371 19 | 568 39 |
| 113 | 1378 82 | 574 86 |
| 114 | 1386 36 | 581 43 |
| 115 | 1393 81 | 588 10 |
| 116 | 1401 17 | 594 87 |
| 117 | 1408 43 | 601 74 |
| 118 | 1415 61 | 608 71 |
| 119 | 1422 69 | 615 77 |
| 120 | 1429 58 | 622 92 |
| 121 | 1436 57 | 630 17 |
| 122 | 1443 36 | 637 51 |
| 123 | 1450 06 | 644 94 |
| 124 | 1456 65 | 652 45 |
| 125 | 1463 14 | 650 06 |
| 126 | 1469 53 | 667 75 |
| 127 | 1471 35 | 570 00 |

Circle Center At X = 891 9 , Y = 1141 1 and Radius, 746 8
*** 2 858 ***

Failure Surface Specified By123 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 382 08 | 615 51 |
| 2 | 389 16 | 608 44 |
| 3 | 396 33 | 601 46 |
| 4 | 403 59 | 594 59 |
| 5 | 410 95 | 587 82 |
| 6 | 418 40 | 581 16 |
| 7 | 425 95 | 574 59 |
| 8 | 433 58 | 568 13 |
| 9 | 441 31 | 561 78 |
| 10 | 449 12 | 555 54 |
| 11 | 457 01 | 549 40 |
| 12 | 464 99 | 543 37 |
| 13 | 473 06 | 537 46 |
| 14 | 481 20 | 531 66 |
| 15 | 489 42 | 525 97 |
| 16 | 497 73 | 520 39 |
| 17 | 506 10 | 514 93 |
| 18 | 514 56 | 509 59 |
| 19 | 523 08 | 504 37 |
| 20 | 531 68 | 499 26 |
| 21 | 540 35 | 494 27 |
| 22 | 549 08 | 489 40 |
| 23 | 557 89 | 484 66 |
| 24 | 566 75 | 480 04 |
| 25 | 575 58 | 475 54 |
| 26 | 584 68 | 471 16 |

| | | |
|----|---------|--------|
| 27 | 593 73 | 466 91 |
| 28 | 602 84 | 462 79 |
| 29 | 612 00 | 458 79 |
| 30 | 621 22 | 454 92 |
| 31 | 630 50 | 451 17 |
| 32 | 639 82 | 447 56 |
| 33 | 649 19 | 444 08 |
| 34 | 658 62 | 440 72 |
| 35 | 668 08 | 437 50 |
| 36 | 677 59 | 434 40 |
| 37 | 687 14 | 431 44 |
| 38 | 696 74 | 428 62 |
| 39 | 705 37 | 425 92 |
| 40 | 716 03 | 423 36 |
| 41 | 725 73 | 420 93 |
| 42 | 735 47 | 418 64 |
| 43 | 745 23 | 415 48 |
| 44 | 755 02 | 414 46 |
| 45 | 764 84 | 412 58 |
| 46 | 774 69 | 410 83 |
| 47 | 784 56 | 409 21 |
| 48 | 794 45 | 407 74 |
| 49 | 804 36 | 405 40 |
| 50 | 814 29 | 405 19 |
| 51 | 824 23 | 404 13 |
| 52 | 834 19 | 403 20 |
| 53 | 844 16 | 402 41 |
| 54 | 854 14 | 401 76 |
| 55 | 864 12 | 401 25 |
| 56 | 874 11 | 400 88 |
| 57 | 884 11 | 400 64 |
| 58 | 894 11 | 400 54 |
| 59 | 904 11 | 400 59 |
| 60 | 914 11 | 400 77 |
| 61 | 924 10 | 401 08 |
| 62 | 934 09 | 401 54 |
| 63 | 944 08 | 402 13 |
| 64 | 954 05 | 402 87 |
| 65 | 964 01 | 403 74 |
| 66 | 973 96 | 404 75 |
| 67 | 983 89 | 405 89 |
| 68 | 993 81 | 407 18 |
| 69 | 1003 71 | 408 60 |
| 70 | 1013 59 | 410 16 |
| 71 | 1023 44 | 411 85 |
| 72 | 1033 27 | 413 58 |
| 73 | 1043 08 | 415 55 |
| 74 | 1052 86 | 417 75 |
| 75 | 1062 60 | 419 99 |
| 76 | 1072 32 | 422 37 |
| 77 | 1082 00 | 424 87 |
| 78 | 1091 64 | 427 51 |
| 79 | 1101 25 | 430 29 |
| 80 | 1110 82 | 433 19 |
| 81 | 1120 34 | 436 23 |
| 82 | 1129 83 | 439 40 |
| 83 | 1139 27 | 442 71 |
| 84 | 1148 66 | 446 14 |
| 85 | 1158 00 | 449 70 |
| 86 | 1167 30 | 453 39 |
| 87 | 1176 54 | 457 21 |
| 88 | 1185 73 | 461 16 |
| 89 | 1194 86 | 465 23 |
| 90 | 1203 94 | 459 43 |
| 91 | 1212 95 | 473 76 |
| 92 | 1221 91 | 478 21 |
| 93 | 1230 80 | 482 78 |
| 94 | 1239 63 | 487 47 |

A/130

| | | |
|-----|---------|--------|
| 95 | 1248 39 | 492 29 |
| 96 | 1257 09 | 497 23 |
| 97 | 1265 71 | 502 29 |
| 98 | 1274 27 | 507 47 |
| 99 | 1282 75 | 512 76 |
| 100 | 1291 16 | 518 17 |
| 101 | 1299 49 | 523 70 |
| 102 | 1307 75 | 529 35 |
| 103 | 1315 93 | 535 10 |
| 104 | 1324 02 | 540 97 |
| 105 | 1332 04 | 546 95 |
| 106 | 1339 97 | 553 05 |
| 107 | 1347 81 | 559 25 |
| 108 | 1355 57 | 555 56 |
| 109 | 1363 24 | 571 97 |
| 110 | 1370 82 | 578 49 |
| 111 | 1378 31 | 585 12 |
| 112 | 1385 71 | 591 85 |
| 113 | 1393 01 | 598 68 |
| 114 | 1400 22 | 605 61 |
| 115 | 1407 33 | 612 64 |
| 116 | 1414 35 | 619 77 |
| 117 | 1421 26 | 626 99 |
| 118 | 1428 07 | 634 31 |
| 119 | 1434 79 | 641 73 |
| 120 | 1441 39 | 549 23 |
| 121 | 1447 90 | 656 83 |
| 122 | 1454 30 | 664 51 |
| 123 | 1458 74 | 670 00 |

Circle Center At X = 896 1 , Y = 1122 6 and Radius, 722 1
 *** 2 864 ***

Failure Surface Specified By 121 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 280 00 | 614 26 |
| 2 | 287 10 | 607 21 |
| 3 | 294 29 | 600 27 |
| 4 | 301 58 | 593 43 |
| 5 | 308 97 | 586 59 |
| 6 | 316 45 | 580 05 |
| 7 | 324 03 | 573 52 |
| 8 | 331 69 | 567 10 |
| 9 | 339 45 | 560 79 |
| 10 | 347 29 | 554 58 |
| 11 | 355 22 | 548 49 |
| 12 | 353 23 | 542 51 |
| 13 | 371 33 | 536 64 |
| 14 | 379 51 | 530 89 |
| 15 | 387 77 | 525 25 |
| 16 | 396 11 | 519 73 |
| 17 | 404 52 | 514 32 |
| 18 | 413 01 | 509 04 |
| 19 | 421 57 | 503 87 |
| 20 | 430 21 | 498 83 |
| 21 | 438 91 | 493 91 |
| 22 | 447 69 | 489 11 |
| 23 | 456 52 | 484 43 |
| 24 | 465 43 | 479 88 |
| 25 | 474 40 | 475 45 |
| 26 | 483 43 | 471 16 |
| 27 | 492 51 | 466 98 |
| 28 | 501 66 | 452 94 |
| 29 | 510 86 | 459 03 |
| 30 | 520 12 | 455 24 |
| 31 | 529 43 | 451 59 |
| 32 | 538 79 | 448 07 |
| 33 | 548 19 | 444 67 |
| 34 | 557 65 | 441 42 |

| | | |
|-----|---------|--------|
| 35 | 567 15 | 438 29 |
| 36 | 576 69 | 435 30 |
| 37 | 586 27 | 432 44 |
| 38 | 595 89 | 429 72 |
| 39 | 605 55 | 427 13 |
| 40 | 615 25 | 424 68 |
| 41 | 624 98 | 422 37 |
| 42 | 634 74 | 420 19 |
| 43 | 644 53 | 418 15 |
| 44 | 654 35 | 416 25 |
| 45 | 664 19 | 414 49 |
| 46 | 674 06 | 412 86 |
| 47 | 683 94 | 411 38 |
| 48 | 693 85 | 410 03 |
| 49 | 703 78 | 408 82 |
| 50 | 713 72 | 407 76 |
| 51 | 723 68 | 406 83 |
| 52 | 733 65 | 406 04 |
| 53 | 743 63 | 405 39 |
| 54 | 753 62 | 404 89 |
| 55 | 763 61 | 404 52 |
| 56 | 773 61 | 404 29 |
| 57 | 783 61 | 404 21 |
| 58 | 793 61 | 404 26 |
| 59 | 803 60 | 404 46 |
| 60 | 813 60 | 404 79 |
| 61 | 823 59 | 405 27 |
| 62 | 833 57 | 405 89 |
| 63 | 843 54 | 406 64 |
| 64 | 853 50 | 407 54 |
| 65 | 863 44 | 408 58 |
| 66 | 873 38 | 409 75 |
| 67 | 883 29 | 411 07 |
| 68 | 893 18 | 412 52 |
| 69 | 903 05 | 414 12 |
| 70 | 912 90 | 415 85 |
| 71 | 922 73 | 417 72 |
| 72 | 932 52 | 419 73 |
| 73 | 942 29 | 421 88 |
| 74 | 952 02 | 424 16 |
| 75 | 961 73 | 425 58 |
| 76 | 971 40 | 429 14 |
| 77 | 981 03 | 431 83 |
| 78 | 990 62 | 434 66 |
| 79 | 1000 17 | 437 62 |
| 80 | 1009 68 | 440 72 |
| 81 | 1019 14 | 443 94 |
| 82 | 1028 56 | 447 31 |
| 83 | 1037 93 | 450 80 |
| 84 | 1047 25 | 454 43 |
| 85 | 1056 52 | 458 18 |
| 86 | 1065 73 | 462 07 |
| 87 | 1074 89 | 465 08 |
| 88 | 1083 99 | 470 23 |
| 89 | 1093 03 | 474 50 |
| 90 | 1102 01 | 478 89 |
| 91 | 1110 93 | 483 42 |
| 92 | 1119 79 | 488 07 |
| 93 | 1128 58 | 492 84 |
| 94 | 1137 29 | 497 73 |
| 95 | 1145 95 | 502 75 |
| 96 | 1154 52 | 507 89 |
| 97 | 1163 03 | 513 15 |
| 98 | 1171 46 | 518 53 |
| 99 | 1179 82 | 524 02 |
| 100 | 1188 09 | 529 63 |
| 101 | 1196 29 | 535 36 |
| 102 | 1204 40 | 541 20 |

16/130

| | | |
|-----|---------|--------|
| 103 | 1212 44 | 547 16 |
| 104 | 1220 38 | 553 23 |
| 105 | 1228 25 | 559 41 |
| 106 | 1236 02 | 565 70 |
| 107 | 1243 71 | 572 10 |
| 108 | 1251 30 | 578 60 |
| 109 | 1258 80 | 585 22 |
| 110 | 1266 21 | 591 93 |
| 111 | 1273 52 | 598 75 |
| 112 | 1280 74 | 605 68 |
| 113 | 1287 85 | 612 70 |
| 114 | 1294 88 | 619 82 |
| 115 | 1301 80 | 527 04 |
| 116 | 1308 61 | 634 36 |
| 117 | 1315 33 | 641 77 |
| 118 | 1321 93 | 549 28 |
| 119 | 1328 44 | 656 87 |
| 120 | 1334 83 | 664 56 |
| 121 | 1339 22 | 670 00 |

Circle Center At X = 784 7 , Y = 1115 6 and Radius, 711 4
*** 2 865 ***

Failure Surface Specified By 117 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 402 50 | 615 76 |
| 2 | 409 58 | 608 69 |
| 3 | 416 75 | 601 73 |
| 4 | 424 03 | 594 87 |
| 5 | 431 41 | 588 12 |
| 6 | 438 89 | 581 48 |
| 7 | 446 46 | 574 95 |
| 8 | 454 13 | 568 53 |
| 9 | 461 89 | 562 22 |
| 10 | 459 74 | 556 03 |
| 11 | 477 68 | 549 95 |
| 12 | 485 71 | 543 99 |
| 13 | 493 83 | 538 15 |
| 14 | 502 03 | 532 43 |
| 15 | 510 31 | 526 82 |
| 16 | 518 68 | 521 34 |
| 17 | 527 12 | 515 99 |
| 18 | 535 64 | 510 75 |
| 19 | 544 24 | 505 55 |
| 20 | 552 91 | 500 66 |
| 21 | 561 65 | 495 81 |
| 22 | 570 46 | 491 08 |
| 23 | 579 35 | 486 49 |
| 24 | 588 29 | 482 02 |
| 25 | 597 30 | 477 69 |
| 26 | 606 38 | 473 48 |
| 27 | 615 51 | 469 41 |
| 28 | 624 71 | 455 48 |
| 29 | 533 96 | 461 68 |
| 30 | 643 26 | 458 01 |
| 31 | 652 52 | 454 49 |
| 32 | 662 02 | 451 10 |
| 33 | 671 48 | 447 84 |
| 34 | 580 98 | 444 73 |
| 35 | 690 53 | 441 75 |
| 35 | 700 12 | 438 92 |
| 37 | 709 75 | 436 22 |
| 38 | 719 42 | 433 67 |
| 39 | 729 12 | 431 26 |
| 40 | 738 86 | 428 99 |
| 41 | 748 63 | 426 85 |
| 42 | 758 44 | 424 88 |
| 43 | 768 27 | 423 04 |
| 44 | 778 12 | 421 35 |

| | | |
|-----|---------|--------|
| 45 | 788 00 | 419 79 |
| 46 | 797 90 | 418 39 |
| 47 | 807 82 | 417 13 |
| 48 | 817 76 | 416 01 |
| 49 | 827 71 | 415 04 |
| 50 | 837 68 | 414 21 |
| 51 | 847 65 | 413 53 |
| 52 | 857 64 | 413 00 |
| 53 | 867 63 | 412 61 |
| 54 | 877 63 | 412 37 |
| 55 | 887 63 | 412 28 |
| 56 | 897 63 | 412 33 |
| 57 | 907 63 | 412 53 |
| 58 | 917 62 | 412 87 |
| 59 | 927 61 | 413 36 |
| 60 | 937 59 | 414 00 |
| 61 | 947 56 | 414 78 |
| 62 | 957 51 | 415 71 |
| 63 | 967 46 | 416 78 |
| 64 | 977 38 | 418 00 |
| 65 | 987 29 | 419 36 |
| 66 | 997 17 | 420 87 |
| 67 | 1007 04 | 422 53 |
| 68 | 1016 87 | 424 32 |
| 69 | 1026 68 | 426 26 |
| 70 | 1036 46 | 428 35 |
| 71 | 1045 21 | 430 57 |
| 72 | 1055 93 | 432 94 |
| 73 | 1055 61 | 435 46 |
| 74 | 1075 25 | 438 11 |
| 75 | 1084 85 | 440 90 |
| 76 | 1094 41 | 443 84 |
| 77 | 1103 93 | 446 91 |
| 78 | 1113 40 | 450 12 |
| 79 | 1122 82 | 453 47 |
| 80 | 1132 19 | 456 96 |
| 81 | 1141 51 | 460 58 |
| 82 | 1150 78 | 454 34 |
| 83 | 1159 99 | 468 24 |
| 84 | 1169 14 | 472 27 |
| 85 | 1178 23 | 476 43 |
| 86 | 1187 26 | 480 73 |
| 87 | 1196 23 | 485 15 |
| 88 | 1205 13 | 489 71 |
| 89 | 1213 96 | 494 40 |
| 90 | 1222 73 | 499 22 |
| 91 | 1231 42 | 504 16 |
| 92 | 1240 04 | 509 23 |
| 93 | 1248 58 | 514 43 |
| 94 | 1257 05 | 519 75 |
| 95 | 1265 44 | 525 19 |
| 96 | 1273 74 | 530 76 |
| 97 | 1281 97 | 536 45 |
| 98 | 1290 11 | 542 25 |
| 99 | 1298 17 | 548 18 |
| 100 | 1306 13 | 554 22 |
| 101 | 1314 01 | 560 38 |
| 102 | 1321 80 | 566 65 |
| 103 | 1329 49 | 573 04 |
| 104 | 1337 10 | 579 54 |
| 105 | 1344 60 | 586 15 |
| 106 | 1352 01 | 592 87 |
| 107 | 1359 32 | 599 59 |
| 108 | 1366 52 | 606 62 |
| 109 | 1373 63 | 513 66 |
| 110 | 1380 63 | 520 80 |
| 111 | 1387 53 | 628 04 |
| 112 | 1394 32 | 635 38 |

18/130

| | | |
|-----|---------|--------|
| 113 | 1401 00 | 642 82 |
| 114 | 1407 57 | 650 35 |
| 115 | 1414 03 | 657 99 |
| 116 | 1420 38 | 665 72 |
| 117 | 1423 80 | 670 00 |

Circle Center At X = 889 1 , Y = 1095 8 and Radius, 683 6
 *** 2 867 ***

Failure Surface Specified By127 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 300 42 | 614 51 |
| 2 | 307 68 | 607 64 |
| 3 | 315 03 | 600 86 |
| 4 | 322 47 | 594 17 |
| 5 | 330 00 | 587 59 |
| 6 | 337 61 | 581 10 |
| 7 | 345 30 | 574 71 |
| 8 | 353 07 | 568 42 |
| 9 | 350 93 | 562 23 |
| 10 | 368 86 | 556 15 |
| 11 | 376 88 | 550 17 |
| 12 | 384 97 | 544 29 |
| 13 | 393 13 | 538 51 |
| 14 | 401 37 | 532 84 |
| 15 | 409 58 | 527 28 |
| 16 | 418 06 | 521 83 |
| 17 | 426 52 | 516 49 |
| 18 | 435 04 | 511 25 |
| 19 | 443 63 | 506 13 |
| 20 | 452 28 | 501 12 |
| 21 | 461 00 | 496 22 |
| 22 | 469 78 | 491 43 |
| 23 | 478 62 | 486 76 |
| 24 | 487 52 | 482 20 |
| 25 | 496 48 | 477 76 |
| 26 | 505 49 | 473 43 |
| 27 | 514 56 | 469 22 |
| 28 | 523 69 | 465 13 |
| 29 | 532 86 | 461 16 |
| 30 | 542 09 | 457 30 |
| 31 | 551 37 | 453 57 |
| 32 | 560 69 | 449 95 |
| 33 | 570 06 | 445 45 |
| 34 | 579 48 | 443 09 |
| 35 | 588 93 | 439 84 |
| 36 | 598 43 | 436 71 |
| 37 | 607 97 | 433 71 |
| 38 | 617 55 | 430 83 |
| 39 | 627 16 | 428 07 |
| 40 | 636 81 | 425 44 |
| 41 | 645 49 | 422 93 |
| 42 | 656 20 | 420 55 |
| 43 | 665 94 | 418 29 |
| 44 | 675 71 | 416 16 |
| 45 | 685 51 | 414 16 |
| 46 | 695 33 | 412 28 |
| 47 | 705 18 | 410 53 |
| 48 | 715 04 | 408 91 |
| 49 | 724 93 | 407 42 |
| 50 | 734 84 | 406 05 |
| 51 | 744 76 | 404 81 |
| 52 | 754 70 | 403 70 |
| 53 | 764 65 | 402 72 |
| 54 | 774 51 | 401 87 |
| 55 | 784 59 | 401 15 |
| 56 | 794 57 | 400 55 |
| 57 | 804 56 | 400 09 |
| 58 | 814 55 | 399 75 |

19/130

| | | |
|-----|---------|--------|
| 59 | 824 55 | 399 54 |
| 50 | 834 55 | 399 47 |
| 51 | 844 55 | 399 52 |
| 62 | 854 55 | 399 70 |
| 63 | 864 55 | 400 01 |
| 64 | 874 54 | 400 45 |
| 65 | 884 52 | 401 02 |
| 66 | 894 50 | 401 72 |
| 67 | 904 46 | 402 54 |
| 68 | 914 42 | 403 50 |
| 69 | 924 36 | 404 58 |
| 70 | 934 28 | 405 79 |
| 71 | 944 19 | 407 14 |
| 72 | 954 08 | 408 60 |
| 73 | 963 96 | 410 20 |
| 74 | 973 81 | 411 93 |
| 75 | 983 63 | 413 78 |
| 76 | 993 44 | 415 76 |
| 77 | 1003 21 | 417 86 |
| 78 | 1012 96 | 420 09 |
| 79 | 1022 68 | 422 45 |
| 80 | 1032 36 | 424 93 |
| 81 | 1042 02 | 427 54 |
| 82 | 1051 64 | 430 27 |
| 83 | 1051 22 | 433 13 |
| 84 | 1070 77 | 436 11 |
| 85 | 1080 27 | 439 21 |
| 86 | 1089 74 | 442 44 |
| 87 | 1099 16 | 445 78 |
| 88 | 1108 54 | 449 25 |
| 89 | 1117 87 | 452 84 |
| 90 | 1127 16 | 456 56 |
| 91 | 1136 40 | 460 39 |
| 92 | 1145 58 | 454 34 |
| 93 | 1154 72 | 468 40 |
| 94 | 1153 80 | 472 59 |
| 95 | 1172 83 | 476 89 |
| 95 | 1181 80 | 481 31 |
| 97 | 1190 71 | 485 85 |
| 98 | 1199 56 | 490 50 |
| 99 | 1208 35 | 495 26 |
| 100 | 1217 08 | 500 14 |
| 101 | 1225 75 | 505 13 |
| 102 | 1234 35 | 510 23 |
| 103 | 1242 89 | 515 44 |
| 104 | 1251 35 | 520 77 |
| 105 | 1259 75 | 526 20 |
| 106 | 1268 07 | 531 74 |
| 107 | 1276 33 | 537 38 |
| 108 | 1284 51 | 543 14 |
| 109 | 1292 61 | 548 99 |
| 110 | 1300 64 | 554 96 |
| 111 | 1308 59 | 561 02 |
| 112 | 1316 46 | 567 19 |
| 113 | 1324 25 | 573 46 |
| 114 | 1331 96 | 579 83 |
| 115 | 1339 59 | 586 30 |
| 116 | 1347 13 | 592 86 |
| 117 | 1354 58 | 599 53 |
| 118 | 1361 95 | 606 29 |
| 119 | 1369 24 | 613 14 |
| 120 | 1376 43 | 620 09 |
| 121 | 1383 53 | 627 13 |
| 122 | 1390 54 | 634 25 |
| 123 | 1397 46 | 641 48 |
| 124 | 1404 28 | 648 79 |
| 125 | 1411 01 | 656 19 |
| 126 | 1417 64 | 563 68 |

20/130

127 1423 10 670 00
Circle Center At X = 835 5 , Y = 1172 8 and Radius, 773 3
*** 2 873 ***

Failure Surface Specified By 126 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 382 08 | 615 51 |
| 2 | 389 15 | 608 44 |
| 3 | 396 32 | 601 46 |
| 4 | 403 58 | 594 58 |
| 5 | 410 93 | 587 80 |
| 6 | 418 38 | 581 13 |
| 7 | 425 91 | 574 55 |
| 8 | 433 53 | 568 07 |
| 9 | 441 24 | 561 70 |
| 10 | 449 03 | 555 44 |
| 11 | 456 91 | 549 28 |
| 12 | 464 87 | 543 22 |
| 13 | 472 91 | 537 28 |
| 14 | 481 03 | 531 44 |
| 15 | 489 23 | 525 71 |
| 16 | 497 50 | 520 10 |
| 17 | 505 85 | 514 60 |
| 18 | 514 27 | 509 21 |
| 19 | 522 77 | 503 93 |
| 20 | 531 34 | 498 77 |
| 21 | 539 97 | 493 73 |
| 22 | 548 67 | 488 81 |
| 23 | 557 44 | 484 00 |
| 24 | 565 28 | 479 31 |
| 25 | 575 17 | 474 74 |
| 26 | 584 13 | 470 29 |
| 27 | 593 14 | 465 97 |
| 28 | 602 22 | 461 76 |
| 29 | 611 35 | 457 68 |
| 30 | 620 53 | 453 72 |
| 31 | 629 76 | 449 89 |
| 32 | 639 05 | 446 18 |
| 33 | 648 39 | 442 50 |
| 34 | 657 77 | 439 14 |
| 35 | 667 20 | 435 82 |
| 36 | 676 68 | 432 52 |
| 37 | 686 19 | 429 54 |
| 38 | 695 75 | 426 50 |
| 39 | 705 35 | 423 79 |
| 40 | 714 98 | 421 10 |
| 41 | 724 65 | 418 55 |
| 42 | 734 35 | 416 13 |
| 43 | 744 08 | 413 83 |
| 44 | 753 85 | 411 68 |
| 45 | 763 64 | 409 65 |
| 46 | 773 46 | 407 75 |
| 47 | 783 30 | 405 99 |
| 48 | 793 17 | 404 36 |
| 49 | 803 06 | 402 87 |
| 50 | 812 96 | 401 51 |
| 51 | 822 89 | 400 28 |
| 52 | 832 83 | 399 19 |
| 53 | 842 78 | 398 23 |
| 54 | 852 75 | 397 40 |
| 55 | 862 72 | 396 72 |
| 56 | 872 71 | 395 16 |
| 57 | 882 70 | 395 74 |
| 58 | 892 70 | 395 46 |
| 59 | 902 69 | 395 31 |
| 60 | 912 69 | 395 30 |
| 61 | 922 69 | 395 42 |
| 62 | 932 69 | 395 67 |

21/130

| | | |
|-----|---------|--------|
| 63 | 942 68 | 396 07 |
| 64 | 952 67 | 396 59 |
| 65 | 962 65 | 397 25 |
| 55 | 972 62 | 398 05 |
| 67 | 982 57 | 398 98 |
| 68 | 992 52 | 400 05 |
| 69 | 1002 44 | 401 25 |
| 70 | 1012 35 | 402 58 |
| 71 | 1022 25 | 404 05 |
| 72 | 1032 12 | 405 65 |
| 73 | 1041 96 | 407 39 |
| 74 | 1051 79 | 409 25 |
| 75 | 1061 59 | 411 25 |
| 76 | 1071 36 | 413 39 |
| 77 | 1081 10 | 415 65 |
| 78 | 1090 81 | 418 05 |
| 79 | 1100 48 | 420 57 |
| 80 | 1110 12 | 423 23 |
| 81 | 1119 72 | 426 02 |
| 82 | 1129 29 | 428 94 |
| 83 | 1138 81 | 431 98 |
| 84 | 1148 30 | 435 15 |
| 85 | 1157 74 | 438 45 |
| 86 | 1167 13 | 441 89 |
| 87 | 1176 48 | 445 45 |
| 88 | 1185 77 | 449 13 |
| 89 | 1195 02 | 452 94 |
| 90 | 1204 21 | 456 87 |
| 91 | 1213 35 | 450 92 |
| 92 | 1222 44 | 465 10 |
| 93 | 1231 47 | 469 41 |
| 94 | 1240 43 | 473 83 |
| 95 | 1249 34 | 478 37 |
| 96 | 1258 19 | 483 04 |
| 97 | 1266 97 | 487 82 |
| 98 | 1275 69 | 492 72 |
| 99 | 1284 34 | 497 74 |
| 100 | 1292 92 | 502 88 |
| 101 | 1301 43 | 508 13 |
| 102 | 1309 86 | 513 50 |
| 103 | 1318 23 | 518 97 |
| 104 | 1326 52 | 524 57 |
| 105 | 1334 73 | 530 27 |
| 106 | 1342 87 | 536 08 |
| 107 | 1350 93 | 542 01 |
| 108 | 1358 90 | 548 04 |
| 109 | 1366 80 | 554 18 |
| 110 | 1374 61 | 560 42 |
| 111 | 1382 33 | 565 77 |
| 112 | 1389 97 | 573 23 |
| 113 | 1397 52 | 579 78 |
| 114 | 1404 98 | 586 44 |
| 115 | 1412 35 | 593 20 |
| 116 | 1419 53 | 600 06 |
| 117 | 1426 82 | 607 01 |
| 118 | 1433 91 | 614 06 |
| 119 | 1440 90 | 621 21 |
| 120 | 1447 80 | 628 45 |
| 121 | 1454 60 | 635 79 |
| 122 | 1461 30 | 643 21 |
| 123 | 1467 89 | 650 72 |
| 124 | 1474 39 | 658 33 |
| 125 | 1480 78 | 665 02 |
| 126 | 1484 00 | 670 00 |

Circle Center At X = 908 7 , Y = 1135 0 and Radius, 739 8

*** 2 875 ***

Failure Surface Specified By 90 Coordinate Points

| Point | X-Surf | Y-Surf |
|-------|--------|--------|
|-------|--------|--------|

22/130

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 504 58 | 617 00 |
| 2 | 511 67 | 609 95 |
| 3 | 518 90 | 603 04 |
| 4 | 526 26 | 596 26 |
| 5 | 533 74 | 589 64 |
| 6 | 541 36 | 583 16 |
| 7 | 549 10 | 576 82 |
| 8 | 556 96 | 570 64 |
| 9 | 564 94 | 564 62 |
| 10 | 573 04 | 558 74 |
| 11 | 581 24 | 553 03 |
| 12 | 589 55 | 547 48 |
| 13 | 597 98 | 542 09 |
| 14 | 606 51 | 536 87 |
| 15 | 615 14 | 531 81 |
| 16 | 623 86 | 526 92 |
| 17 | 632 68 | 522 20 |
| 18 | 641 58 | 517 65 |
| 19 | 650 57 | 513 28 |
| 20 | 659 65 | 509 08 |
| 21 | 668 81 | 505 05 |
| 22 | 678 04 | 501 21 |
| 23 | 687 34 | 497 55 |
| 24 | 596 72 | 494 07 |
| 25 | 706 16 | 490 77 |
| 26 | 715 66 | 487 65 |
| 27 | 725 22 | 484 72 |
| 28 | 734 84 | 481 98 |
| 29 | 744 50 | 479 42 |
| 30 | 754 22 | 477 05 |
| 31 | 763 98 | 474 87 |
| 32 | 773 78 | 472 88 |
| 33 | 783 62 | 471 09 |
| 34 | 793 49 | 469 48 |
| 35 | 803 39 | 468 06 |
| 36 | 813 31 | 466 84 |
| 37 | 823 26 | 465 81 |
| 38 | 833 22 | 464 97 |
| 39 | 843 20 | 464 33 |
| 40 | 853 19 | 463 88 |
| 41 | 863 19 | 463 62 |
| 42 | 873 19 | 463 56 |
| 43 | 883 19 | 463 69 |
| 44 | 893 18 | 454 02 |
| 45 | 903 17 | 464 54 |
| 46 | 913 14 | 465 26 |
| 47 | 923 10 | 466 15 |
| 48 | 933 04 | 467 27 |
| 49 | 942 96 | 468 56 |
| 50 | 952 85 | 470 05 |
| 51 | 952 70 | 471 72 |
| 52 | 972 53 | 473 59 |
| 53 | 982 31 | 475 65 |
| 54 | 992 06 | 477 90 |
| 55 | 1001 75 | 480 34 |
| 56 | 1011 40 | 482 97 |
| 57 | 1021 00 | 485 78 |
| 58 | 1030 54 | 488 78 |
| 59 | 1040 02 | 491 96 |
| 60 | 1049 44 | 495 33 |
| 61 | 1058 79 | 498 88 |
| 62 | 1068 06 | 502 60 |
| 63 | 1077 27 | 505 51 |
| 64 | 1086 40 | 510 60 |
| 65 | 1095 44 | 514 86 |
| 66 | 1104 40 | 519 30 |
| 67 | 1113 28 | 523 91 |

| | | |
|----|---------|--------|
| 68 | 1122 06 | 528 70 |
| 69 | 1130 74 | 533 65 |
| 70 | 1139 33 | 538 77 |
| 71 | 1147 82 | 544 05 |
| 72 | 1156 21 | 549 50 |
| 73 | 1164 49 | 555 12 |
| 74 | 1172 65 | 560 89 |
| 75 | 1180 71 | 566 81 |
| 76 | 1188 64 | 572 90 |
| 77 | 1196 46 | 579 14 |
| 78 | 1204 15 | 585 52 |
| 79 | 1211 72 | 592 06 |
| 80 | 1219 16 | 598 74 |
| 81 | 1226 47 | 605 56 |
| 82 | 1233 65 | 612 53 |
| 83 | 1240 69 | 619 63 |
| 84 | 1247 59 | 626 87 |
| 85 | 1254 34 | 634 24 |
| 86 | 1260 96 | 641 74 |
| 87 | 1267 42 | 649 37 |
| 88 | 1273 74 | 657 12 |
| 89 | 1279 91 | 664 99 |
| 90 | 1283 57 | 670 00 |

Circle Center At X = 871 3 , Y = 978 6 and Radius, 515 0
 *** 2 890 ***

Failure Surface Specified By100 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 402 50 | 615 76 |
| 2 | 409 55 | 608 76 |
| 3 | 416 92 | 501 90 |
| 4 | 424 31 | 595 15 |
| 5 | 431 81 | 588 54 |
| 6 | 439 42 | 582 06 |
| 7 | 447 14 | 575 71 |
| 8 | 454 97 | 569 49 |
| 9 | 462 91 | 563 40 |
| 10 | 470 95 | 557 46 |
| 11 | 479 09 | 551 65 |
| 12 | 487 33 | 545 98 |
| 13 | 495 66 | 540 46 |
| 14 | 504 09 | 535 07 |
| 15 | 512 61 | 529 84 |
| 16 | 521 22 | 524 75 |
| 17 | 529 92 | 519 81 |
| 18 | 538 69 | 515 02 |
| 19 | 547 55 | 510 38 |
| 20 | 556 49 | 505 89 |
| 21 | 565 50 | 501 56 |
| 22 | 574 59 | 497 38 |
| 23 | 583 74 | 493 36 |
| 24 | 592 97 | 489 50 |
| 25 | 602 26 | 485 79 |
| 26 | 611 61 | 482 25 |
| 27 | 621 02 | 478 87 |
| 28 | 630 48 | 475 64 |
| 29 | 640 00 | 472 59 |
| 30 | 649 58 | 469 69 |
| 31 | 659 20 | 466 96 |
| 32 | 668 86 | 454 40 |
| 33 | 678 57 | 462 00 |
| 34 | 688 32 | 459 77 |
| 35 | 698 10 | 457 70 |
| 36 | 707 92 | 455 81 |
| 37 | 717 77 | 454 08 |
| 38 | 727 65 | 452 52 |
| 39 | 737 55 | 451 13 |
| 40 | 747 48 | 449 91 |


24/130

| | | |
|-----|---------|--------|
| 41 | 757 42 | 448 87 |
| 42 | 767 38 | 447 99 |
| 43 | 777 36 | 447 28 |
| 44 | 787 34 | 446 75 |
| 45 | 797 34 | 446 39 |
| 46 | 807 34 | 446 19 |
| 47 | 817 34 | 446 17 |
| 48 | 827 33 | 446 33 |
| 49 | 837 33 | 446 65 |
| 50 | 847 32 | 447 14 |
| 51 | 857 29 | 447 81 |
| 52 | 867 26 | 448 65 |
| 53 | 877 21 | 449 65 |
| 54 | 887 14 | 450 83 |
| 55 | 897 05 | 452 18 |
| 56 | 906 93 | 453 70 |
| 57 | 916 79 | 455 39 |
| 58 | 926 61 | 457 24 |
| 59 | 936 41 | 459 27 |
| 60 | 946 16 | 461 46 |
| 61 | 955 88 | 463 82 |
| 62 | 965 56 | 466 35 |
| 63 | 975 19 | 469 04 |
| 64 | 984 77 | 471 90 |
| 65 | 994 30 | 474 92 |
| 66 | 1003 78 | 478 10 |
| 67 | 1013 21 | 481 45 |
| 68 | 1022 57 | 484 95 |
| 69 | 1031 88 | 488 62 |
| 70 | 1041 11 | 492 45 |
| 71 | 1050 29 | 495 43 |
| 72 | 1059 39 | 500 57 |
| 73 | 1068 42 | 504 87 |
| 74 | 1077 37 | 509 32 |
| 75 | 1086 25 | 513 92 |
| 76 | 1095 05 | 518 68 |
| 77 | 1103 75 | 523 58 |
| 78 | 1112 39 | 528 64 |
| 79 | 1120 93 | 533 84 |
| 80 | 1129 38 | 539 19 |
| 81 | 1137 74 | 544 68 |
| 82 | 1146 00 | 550 31 |
| 83 | 1154 16 | 556 09 |
| 84 | 1162 23 | 562 00 |
| 85 | 1170 19 | 568 06 |
| 86 | 1178 04 | 574 24 |
| 87 | 1185 79 | 580 56 |
| 88 | 1193 43 | 587 02 |
| 89 | 1200 96 | 593 60 |
| 90 | 1208 37 | 600 31 |
| 91 | 1215 67 | 607 15 |
| 92 | 1222 85 | 614 11 |
| 93 | 1229 90 | 621 20 |
| 94 | 1236 84 | 628 40 |
| 95 | 1243 65 | 635 73 |
| 96 | 1250 33 | 643 16 |
| 97 | 1256 89 | 650 72 |
| 98 | 1263 31 | 658 38 |
| 99 | 1269 61 | 666 15 |
| 100 | 1272 61 | 670 00 |

Circle Center At X = 813 5 , Y = 1028 9 and Radius, 582 8
*** 2 893 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\12 pl2 Run By Greg Shafer, HDR 4/20/2010 02:04PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Piez. Surface | Load Horiz Eqk | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|---------------|----------------|--------|
| a | 1 00 | | | | | | No | 0 | 100 g< |
| b | 1 02 | | | | | | No | | |
| c | 1 03 | UVSC | 1 | 113 5 | 121 0 | 3000 0 | W1 | | |
| d | 1 04 | LSC | 2 | 121 0 | 125 5 | 1500 0 | W1 | | |
| e | 1 05 | SC | 3 | 121 0 | 125 5 | 2000 0 | W1 | | |
| f | 1 05 | LVSC | 4 | 121 0 | 125 5 | 3000 0 | W1 | | |
| g | 1 06 | | | | | | | | |
| h | 1 07 | | | | | | | | |
| i | 1 07 | | | | | | | | |
| j | 1 08 | | | | | | | | |

✓ RHP 4-26-10

STED



PCSTABL7 FSmin=1.00
Safety Factors Are Calculated By The Modified Bishop Method

25/30

** PCSTABL7 **
 by
 Purdue University
 --Slope Stability Analysis--
 Simplified Janbu, Simplified Bishop
 or Spencer s Method of Slices

Run Date 4/20/2010
 Time of Run 02 04PM
 Run By Greg Shafer, HDR
 Input Data Filename C 2 in
 Output Filename C 2 OUT
 Unit ENGLISH
 Plotted Output Filename C 2 PLT
 PROBLEM DESCRIPTION Intermountain Regional Landfill
 Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
 Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
 6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 550 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
 Of 0 100 Has Been Assigned

A Vertical Earthquake Loading Coefficient
 Of 0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random
 Technique For Generating Circular Surfaces, Has Been Specified
 625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced
 Along The Ground Surface Between X = 500 00 ft

and X = 770 00 ft

Each Surface Terminates Between X = 950 00 ft
 and X = 2250 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation
 At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
 First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 188 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 511 25 | 617 08 |
| 2 | 518 40 | 610 09 |
| 3 | 525 61 | 603 16 |
| 4 | 532 88 | 596 30 |
| 5 | 540 21 | 589 49 |
| 6 | 547 60 | 582 75 |
| 7 | 555 04 | 576 08 |
| 8 | 562 55 | 569 47 |

| | | |
|----|---------|--------|
| 9 | 570 11 | 562 93 |
| 10 | 577 73 | 556 45 |
| 11 | 585 40 | 550 04 |
| 12 | 593 13 | 543 69 |
| 13 | 600 92 | 537 41 |
| 14 | 608 75 | 531 20 |
| 15 | 616 65 | 525 06 |
| 16 | 624 59 | 518 99 |
| 17 | 632 59 | 512 99 |
| 18 | 640 64 | 507 05 |
| 19 | 648 74 | 501 19 |
| 20 | 656 89 | 495 40 |
| 21 | 665 09 | 489 68 |
| 22 | 673 34 | 484 03 |
| 23 | 681 64 | 478 45 |
| 24 | 689 99 | 472 94 |
| 25 | 598 39 | 467 51 |
| 26 | 706 83 | 462 15 |
| 27 | 715 32 | 456 86 |
| 28 | 723 85 | 451 65 |
| 29 | 732 43 | 446 51 |
| 30 | 741 05 | 441 45 |
| 31 | 749 72 | 436 46 |
| 32 | 758 43 | 431 55 |
| 33 | 767 18 | 426 71 |
| 34 | 775 98 | 421 95 |
| 35 | 784 81 | 417 27 |
| 36 | 793 69 | 412 66 |
| 37 | 802 60 | 408 13 |
| 38 | 811 55 | 403 68 |
| 39 | 820 55 | 399 30 |
| 40 | 829 58 | 395 00 |
| 41 | 838 64 | 390 79 |
| 42 | 847 75 | 386 65 |
| 43 | 856 89 | 382 59 |
| 44 | 866 06 | 378 61 |
| 45 | 875 27 | 374 71 |
| 46 | 884 51 | 370 89 |
| 47 | 893 79 | 367 15 |
| 48 | 903 09 | 363 49 |
| 49 | 912 43 | 359 91 |
| 50 | 921 80 | 356 42 |
| 51 | 931 20 | 353 00 |
| 52 | 940 63 | 349 67 |
| 53 | 950 08 | 346 42 |
| 54 | 959 57 | 343 25 |
| 55 | 959 08 | 340 17 |
| 56 | 978 62 | 337 16 |
| 57 | 988 18 | 334 24 |
| 58 | 997 77 | 331 40 |
| 59 | 1007 38 | 328 65 |
| 60 | 1017 02 | 325 98 |
| 61 | 1026 68 | 323 39 |
| 62 | 1036 36 | 320 89 |
| 63 | 1046 07 | 318 47 |
| 64 | 1055 79 | 316 14 |
| 65 | 1065 53 | 313 89 |
| 66 | 1075 30 | 311 73 |
| 67 | 1085 08 | 309 65 |
| 68 | 1094 88 | 307 65 |
| 69 | 1104 69 | 305 74 |
| 70 | 1114 53 | 303 92 |
| 71 | 1124 37 | 302 18 |
| 72 | 1134 24 | 300 53 |
| 73 | 1144 11 | 298 96 |
| 74 | 1154 00 | 297 48 |
| 75 | 1163 90 | 296 09 |
| 76 | 1173 82 | 294 78 |

28/130

| | | |
|-----|---------|--------|
| 77 | 1183 74 | 293 55 |
| 78 | 1193 68 | 292 42 |
| 79 | 1203 62 | 291 37 |
| 80 | 1213 58 | 290 40 |
| 81 | 1223 54 | 289 53 |
| 82 | 1233 51 | 288 74 |
| 83 | 1243 48 | 288 03 |
| 84 | 1253 46 | 287 42 |
| 85 | 1263 45 | 286 88 |
| 86 | 1273 44 | 286 44 |
| 87 | 1283 43 | 286 08 |
| 88 | 1293 43 | 285 81 |
| 89 | 1303 43 | 285 63 |
| 90 | 1313 43 | 285 53 |
| 91 | 1323 43 | 285 52 |
| 92 | 1333 43 | 285 60 |
| 93 | 1343 43 | 285 77 |
| 94 | 1353 42 | 286 02 |
| 95 | 1363 42 | 285 36 |
| 96 | 1373 41 | 286 78 |
| 97 | 1383 39 | 287 29 |
| 98 | 1393 38 | 287 89 |
| 99 | 1403 35 | 288 58 |
| 100 | 1413 32 | 289 35 |
| 101 | 1423 29 | 290 21 |
| 102 | 1433 24 | 291 15 |
| 103 | 1443 19 | 292 18 |
| 104 | 1453 13 | 293 30 |
| 105 | 1453 05 | 294 50 |
| 106 | 1472 97 | 295 79 |
| 107 | 1482 87 | 297 17 |
| 108 | 1492 77 | 298 63 |
| 109 | 1502 65 | 300 18 |
| 110 | 1512 51 | 301 81 |
| 111 | 1522 36 | 303 53 |
| 112 | 1532 20 | 305 34 |
| 113 | 1542 02 | 307 23 |
| 114 | 1551 82 | 309 21 |
| 115 | 1561 61 | 311 27 |
| 116 | 1571 37 | 313 41 |
| 117 | 1581 12 | 315 64 |
| 118 | 1590 85 | 317 96 |
| 119 | 1600 56 | 320 36 |
| 120 | 1610 24 | 322 84 |
| 121 | 1619 91 | 325 41 |
| 122 | 1629 55 | 328 06 |
| 123 | 1639 17 | 330 80 |
| 124 | 1648 76 | 333 62 |
| 125 | 1658 33 | 335 52 |
| 126 | 1557 88 | 339 50 |
| 127 | 1677 40 | 342 57 |
| 128 | 1686 89 | 345 72 |
| 129 | 1596 35 | 348 96 |
| 130 | 1705 78 | 352 27 |
| 131 | 1715 19 | 355 67 |
| 132 | 1724 56 | 359 15 |
| 133 | 1733 91 | 362 71 |
| 134 | 1743 22 | 366 35 |
| 135 | 1752 50 | 370 07 |
| 136 | 1761 75 | 373 87 |
| 137 | 1770 97 | 377 75 |
| 138 | 1780 15 | 381 72 |
| 139 | 1789 30 | 385 76 |
| 140 | 1798 41 | 389 88 |
| 141 | 1807 48 | 394 08 |
| 142 | 1816 52 | 398 36 |
| 143 | 1825 52 | 402 72 |
| 144 | 1834 48 | 407 15 |

29/30

| | | | | |
|-----|------|----|-----|----|
| 145 | 1843 | 41 | 411 | 67 |
| 146 | 1852 | 29 | 416 | 26 |
| 147 | 1861 | 14 | 420 | 92 |
| 148 | 1869 | 94 | 425 | 67 |
| 149 | 1878 | 70 | 430 | 49 |
| 150 | 1887 | 42 | 435 | 38 |
| 151 | 1896 | 10 | 440 | 36 |
| 152 | 1904 | 73 | 445 | 40 |
| 153 | 1913 | 32 | 450 | 53 |
| 154 | 1921 | 86 | 455 | 72 |
| 155 | 1930 | 36 | 460 | 99 |
| 156 | 1938 | 81 | 466 | 34 |
| 157 | 1947 | 22 | 471 | 75 |
| 158 | 1955 | 58 | 477 | 24 |
| 159 | 1963 | 89 | 482 | 81 |
| 160 | 1972 | 15 | 488 | 44 |
| 161 | 1980 | 36 | 494 | 15 |
| 162 | 1988 | 52 | 499 | 92 |
| 163 | 1996 | 63 | 505 | 77 |
| 164 | 2004 | 69 | 511 | 59 |
| 165 | 2012 | 70 | 517 | 68 |
| 166 | 2020 | 66 | 523 | 74 |
| 167 | 2028 | 56 | 529 | 86 |
| 168 | 2036 | 41 | 536 | 06 |
| 169 | 2044 | 21 | 542 | 32 |
| 170 | 2051 | 95 | 548 | 65 |
| 171 | 2059 | 64 | 555 | 05 |
| 172 | 2067 | 27 | 561 | 51 |
| 173 | 2074 | 84 | 568 | 04 |
| 174 | 2082 | 36 | 574 | 64 |
| 175 | 2089 | 82 | 581 | 30 |
| 176 | 2097 | 22 | 588 | 02 |
| 177 | 2104 | 56 | 594 | 81 |
| 178 | 2111 | 84 | 601 | 65 |
| 179 | 2119 | 07 | 608 | 58 |
| 180 | 2125 | 23 | 615 | 56 |
| 181 | 2133 | 33 | 622 | 60 |
| 182 | 2140 | 37 | 629 | 70 |
| 183 | 2147 | 35 | 636 | 86 |
| 184 | 2154 | 27 | 644 | 08 |
| 185 | 2151 | 12 | 651 | 37 |
| 186 | 2167 | 91 | 658 | 71 |
| 187 | 2174 | 63 | 666 | 11 |
| 188 | 2178 | 11 | 670 | 00 |

Circle Center At X = 1319 5 , Y = 1436 4 and Radius, 1150 9
 *** 0 997 ***

Individual data on the 195 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 7 1 | 3062 0 | 0 0 | 0 0 | 0 0 | 0 0 | 306 2 | 0 0 | 0 0 |
| 2 | 7 2 | 9236 9 | 0 0 | 0 0 | 0 0 | 0 0 | 923 7 | 0 0 | 0 0 |
| 3 | 7 3 | 15459 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1545 9 | 0 0 | 0 0 |
| 4 | 7 3 | 21725 9 | 0 0 | 0 0 | 0 0 | 0 0 | 2172 6 | 0 0 | 0 0 |
| 5 | 7 4 | 28033 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2803 4 | 0 0 | 0 0 |
| 6 | 7 4 | 34379 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3438 0 | 0 0 | 0 0 |
| 7 | 7 5 | 40759 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4076 0 | 0 0 | 0 0 |
| 8 | 7 6 | 47171 9 | 0 0 | 0 0 | 0 0 | 0 0 | 4717 2 | 0 0 | 0 0 |
| 9 | 7 6 | 53612 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5351 2 | 0 0 | 0 0 |
| 10 | 7 7 | 60077 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6007 7 | 0 0 | 0 0 |
| 11 | 7 7 | 66564 4 | 0 0 | 0 0 | 0 0 | 0 0 | 6656 4 | 0 0 | 0 0 |
| 12 | 7 8 | 73069 9 | 0 0 | 0 0 | 0 0 | 0 0 | 7307 0 | 0 0 | 0 0 |
| 13 | 7 8 | 79591 4 | 0 0 | 0 0 | 0 0 | 0 0 | 7959 1 | 0 0 | 0 0 |
| 14 | 7 9 | 86125 1 | 0 0 | 0 0 | 0 0 | 0 0 | 8612 5 | 0 0 | 0 0 |
| 15 | 7 9 | 92668 5 | 0 0 | 0 0 | 0 0 | 0 0 | 9266 8 | 0 0 | 0 0 |
| 16 | 8 0 | 99217 1 | 0 0 | 0 0 | 0 0 | 0 0 | 9921 7 | 0 0 | 0 0 |
| 17 | 8 0 | 105769 2 | 0 0 | 0 0 | 0 0 | 0 0 | 10576 9 | 0 0 | 0 0 |

| | | | | | | | | | |
|----|------|----------|-----|-----|-----|-----|---------|-----|-----|
| 18 | 8 1 | 112320 3 | 0 0 | 0 0 | 0 0 | 0 0 | 11232 0 | 0 0 | 0 0 |
| 19 | 8 2 | 118868 8 | 0 0 | 0 0 | 0 0 | 0 0 | 11886 9 | 0 0 | 0 0 |
| 20 | 8 2 | 125411 0 | 0 0 | 0 0 | 0 0 | 0 0 | 12541 1 | 0 0 | 0 0 |
| 21 | 8 3 | 131942 9 | 0 0 | 0 0 | 0 0 | 0 0 | 13194 3 | 0 0 | 0 0 |
| 22 | 8 3 | 138462 3 | 0 0 | 0 0 | 0 0 | 0 0 | 13846 2 | 0 0 | 0 0 |
| 23 | 8 3 | 144966 4 | 0 0 | 0 0 | 0 0 | 0 0 | 14496 5 | 0 0 | 0 0 |
| 24 | 8 4 | 151452 1 | 0 0 | 0 0 | 0 0 | 0 0 | 15145 2 | 0 0 | 0 0 |
| 25 | 8 4 | 157915 5 | 0 0 | 0 0 | 0 0 | 0 0 | 15791 5 | 0 0 | 0 0 |
| 26 | 8 5 | 164354 6 | 0 0 | 0 0 | 0 0 | 0 0 | 16435 5 | 0 0 | 0 0 |
| 27 | 8 5 | 170765 5 | 0 0 | 0 0 | 0 0 | 0 0 | 17076 6 | 0 0 | 0 0 |
| 28 | 8 6 | 177146 4 | 0 0 | 0 0 | 0 0 | 0 0 | 17714 6 | 0 0 | 0 0 |
| 29 | 8 5 | 183493 3 | 0 0 | 0 0 | 0 0 | 0 0 | 18349 3 | 0 0 | 0 0 |
| 30 | 8 7 | 189803 4 | 0 0 | 0 0 | 0 0 | 0 0 | 18980 3 | 0 0 | 0 0 |
| 31 | 0 3 | 6244 7 | 0 0 | 0 0 | 0 0 | 0 0 | 624 5 | 0 0 | 0 0 |
| 32 | 8 4 | 179022 8 | 0 0 | 0 0 | 0 0 | 0 0 | 17902 3 | 0 0 | 0 0 |
| 33 | 8 8 | 192789 5 | 0 0 | 0 0 | 0 0 | 0 0 | 19279 0 | 0 0 | 0 0 |
| 34 | 8 8 | 200586 8 | 0 0 | 0 0 | 0 0 | 0 0 | 20068 7 | 0 0 | 0 0 |
| 35 | 8 8 | 208568 1 | 0 0 | 0 0 | 0 0 | 0 0 | 20856 8 | 0 0 | 0 0 |
| 36 | 8 9 | 215432 1 | 0 0 | 0 0 | 0 0 | 0 0 | 21643 2 | 0 0 | 0 0 |
| 37 | 8 9 | 224272 5 | 0 0 | 0 0 | 0 0 | 0 0 | 22427 3 | 0 0 | 0 0 |
| 38 | 9 0 | 232088 1 | 0 0 | 0 0 | 0 0 | 0 0 | 23208 8 | 0 0 | 0 0 |
| 39 | 9 0 | 239877 3 | 0 0 | 0 0 | 0 0 | 0 0 | 23987 7 | 0 0 | 0 0 |
| 40 | 9 0 | 247634 2 | 0 0 | 0 0 | 0 0 | 0 0 | 24763 4 | 0 0 | 0 0 |
| 41 | 0 4 | 11750 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1175 0 | 0 0 | 0 0 |
| 42 | 8 6 | 259534 3 | 0 0 | 0 0 | 0 0 | 0 0 | 25963 4 | 0 0 | 0 0 |
| 43 | 9 1 | 280200 2 | 0 0 | 0 0 | 0 0 | 0 0 | 28020 0 | 0 0 | 0 0 |
| 44 | 9 1 | 288193 5 | 0 0 | 0 0 | 0 0 | 0 0 | 28819 3 | 0 0 | 0 0 |
| 45 | 9 2 | 296139 8 | 0 0 | 0 0 | 0 0 | 0 0 | 29614 0 | 0 0 | 0 0 |
| 46 | 3 9 | 129228 5 | 0 0 | 0 0 | 0 0 | 0 0 | 12922 9 | 0 0 | 0 0 |
| 47 | 5 3 | 175202 9 | 0 0 | 0 0 | 0 0 | 0 0 | 17520 3 | 0 0 | 0 0 |
| 48 | 9 2 | 312573 1 | 0 0 | 0 0 | 0 0 | 0 0 | 31257 3 | 0 0 | 0 0 |
| 49 | 9 3 | 320361 6 | 0 0 | 0 0 | 0 0 | 0 0 | 32036 2 | 0 0 | 0 0 |
| 50 | 9 3 | 328089 4 | 0 0 | 0 0 | 0 0 | 0 0 | 32808 9 | 0 0 | 0 0 |
| 51 | 6 9 | 247739 7 | 0 0 | 0 0 | 0 0 | 0 0 | 24774 0 | 0 0 | 0 0 |
| 52 | 2 4 | 88198 4 | 0 0 | 0 0 | 0 0 | 0 0 | 8819 8 | 0 0 | 0 0 |
| 53 | 9 4 | 344060 7 | 0 0 | 0 0 | 0 0 | 0 0 | 34405 1 | 0 0 | 0 0 |
| 54 | 9 4 | 351595 0 | 0 0 | 0 0 | 0 0 | 0 0 | 35159 6 | 0 0 | 0 0 |
| 55 | 9 4 | 359059 3 | 0 0 | 0 0 | 0 0 | 0 0 | 35905 9 | 0 0 | 0 0 |
| 56 | 9 4 | 363192 0 | 0 0 | 0 0 | 0 0 | 0 0 | 36319 2 | 0 0 | 0 0 |
| 57 | 0 1 | 3258 0 | 0 0 | 0 0 | 0 0 | 0 0 | 325 8 | 0 0 | 0 0 |
| 58 | 9 5 | 372462 4 | 0 0 | 0 0 | 0 0 | 0 0 | 37246 2 | 0 0 | 0 0 |
| 59 | 9 5 | 377130 8 | 0 0 | 0 0 | 0 0 | 0 0 | 37713 1 | 0 0 | 0 0 |
| 60 | 9 5 | 381692 7 | 0 0 | 0 0 | 0 0 | 0 0 | 38169 3 | 0 0 | 0 0 |
| 61 | 9 6 | 386151 1 | 0 0 | 0 0 | 0 0 | 0 0 | 38615 1 | 0 0 | 0 0 |
| 62 | 9 6 | 390501 5 | 0 0 | 0 0 | 0 0 | 0 0 | 39050 2 | 0 0 | 0 0 |
| 63 | 9 6 | 394740 1 | 0 0 | 0 0 | 0 0 | 0 0 | 39474 0 | 0 0 | 0 0 |
| 64 | 9 6 | 398872 3 | 0 0 | 0 0 | 0 0 | 0 0 | 39887 2 | 0 0 | 0 0 |
| 65 | 9 7 | 402886 5 | 0 0 | 0 0 | 0 0 | 0 0 | 40288 7 | 0 0 | 0 0 |
| 66 | 9 7 | 406791 2 | 0 0 | 0 0 | 0 0 | 0 0 | 40679 1 | 0 0 | 0 0 |
| 67 | 9 7 | 410577 2 | 0 0 | 0 0 | 0 0 | 0 0 | 41057 7 | 0 0 | 0 0 |
| 68 | 9 7 | 414245 5 | 0 0 | 0 0 | 0 0 | 0 0 | 41424 5 | 0 0 | 0 0 |
| 69 | 9 7 | 417794 6 | 0 0 | 0 0 | 0 0 | 0 0 | 41779 5 | 0 0 | 0 0 |
| 70 | 9 8 | 421223 2 | 0 0 | 0 0 | 0 0 | 0 0 | 42122 3 | 0 0 | 0 0 |
| 71 | 9 8 | 424529 8 | 0 0 | 0 0 | 0 0 | 0 0 | 42453 0 | 0 0 | 0 0 |
| 72 | 9 8 | 427713 1 | 0 0 | 0 0 | 0 0 | 0 0 | 42771 3 | 0 0 | 0 0 |
| 73 | 9 8 | 430771 9 | 0 0 | 0 0 | 0 0 | 0 0 | 43077 2 | 0 0 | 0 0 |
| 74 | 9 8 | 433704 9 | 0 0 | 0 0 | 0 0 | 0 0 | 43370 5 | 0 0 | 0 0 |
| 75 | 9 8 | 436511 0 | 0 0 | 0 0 | 0 0 | 0 0 | 43651 1 | 0 0 | 0 0 |
| 76 | 9 9 | 439189 1 | 0 0 | 0 0 | 0 0 | 0 0 | 43918 9 | 0 0 | 0 0 |
| 77 | 9 9 | 441732 5 | 0 0 | 0 0 | 0 0 | 0 0 | 44173 3 | 0 0 | 0 0 |
| 78 | 9 9 | 444151 3 | 0 0 | 0 0 | 0 0 | 0 0 | 44415 1 | 0 0 | 0 0 |
| 79 | 9 9 | 446433 5 | 0 0 | 0 0 | 0 0 | 0 0 | 44643 4 | 0 0 | 0 0 |
| 80 | 9 9 | 448583 7 | 0 0 | 0 0 | 0 0 | 0 0 | 44858 4 | 0 0 | 0 0 |
| 81 | 9 9 | 450601 0 | 0 0 | 0 0 | 0 0 | 0 0 | 45060 1 | 0 0 | 0 0 |
| 82 | 9 9 | 452484 6 | 0 0 | 0 0 | 0 0 | 0 0 | 45248 5 | 0 0 | 0 0 |
| 83 | 9 9 | 454233 8 | 0 0 | 0 0 | 0 0 | 0 0 | 45423 4 | 0 0 | 0 0 |
| 84 | 10 0 | 455848 0 | 0 0 | 0 0 | 0 0 | 0 0 | 45584 8 | 0 0 | 0 0 |
| 85 | 10 0 | 457320 8 | 0 0 | 0 0 | 0 0 | 0 0 | 45732 1 | 0 0 | 0 0 |

34/170

| | | | | | | | | | |
|-----|------|----------|-----|-----|-----|-----|---------|-----|-----|
| 86 | 10 0 | 458662 9 | 0 0 | 0 0 | 0 0 | 0 0 | 45866 3 | 0 0 | 0 0 |
| 87 | 10 0 | 459862 6 | 0 0 | 0 0 | 0 0 | 0 0 | 45986 3 | 0 0 | 0 0 |
| 88 | 10 0 | 460924 8 | 0 0 | 0 0 | 0 0 | 0 0 | 46092 5 | 0 0 | 0 0 |
| 89 | 10 0 | 461849 4 | 0 0 | 0 0 | 0 0 | 0 0 | 46184 9 | 0 0 | 0 0 |
| 90 | 10 0 | 462630 1 | 0 0 | 0 0 | 0 0 | 0 0 | 46263 0 | 0 0 | 0 0 |
| 91 | 10 0 | 463278 2 | 0 0 | 0 0 | 0 0 | 0 0 | 46327 8 | 0 0 | 0 0 |
| 92 | 10 0 | 463781 9 | 0 0 | 0 0 | 0 0 | 0 0 | 46378 2 | 0 0 | 0 0 |
| 93 | 10 0 | 454146 8 | 0 0 | 0 0 | 0 0 | 0 0 | 46414 7 | 0 0 | 0 0 |
| 94 | 10 0 | 464372 6 | 0 0 | 0 0 | 0 0 | 0 0 | 46437 3 | 0 0 | 0 0 |
| 95 | 10 0 | 464459 2 | 0 0 | 0 0 | 0 0 | 0 0 | 46445 9 | 0 0 | 0 0 |
| 96 | 10 0 | 464406 8 | 0 0 | 0 0 | 0 0 | 0 0 | 46440 7 | 0 0 | 0 0 |
| 97 | 10 0 | 464209 5 | 0 0 | 0 0 | 0 0 | 0 0 | 46421 0 | 0 0 | 0 0 |
| 98 | 10 0 | 463873 2 | 0 0 | 0 0 | 0 0 | 0 0 | 46387 3 | 0 0 | 0 0 |
| 99 | 10 0 | 463398 0 | 0 0 | 0 0 | 0 0 | 0 0 | 46339 8 | 0 0 | 0 0 |
| 100 | 10 0 | 462784 0 | 0 0 | 0 0 | 0 0 | 0 0 | 46278 4 | 0 0 | 0 0 |
| 101 | 10 0 | 462031 7 | 0 0 | 0 0 | 0 0 | 0 0 | 46203 2 | 0 0 | 0 0 |
| 102 | 10 0 | 461135 4 | 0 0 | 0 0 | 0 0 | 0 0 | 46113 5 | 0 0 | 0 0 |
| 103 | 10 0 | 460107 0 | 0 0 | 0 0 | 0 0 | 0 0 | 46010 7 | 0 0 | 0 0 |
| 104 | 10 0 | 458935 4 | 0 0 | 0 0 | 0 0 | 0 0 | 45893 5 | 0 0 | 0 0 |
| 105 | 10 0 | 457627 0 | 0 0 | 0 0 | 0 0 | 0 0 | 45762 7 | 0 0 | 0 0 |
| 105 | 10 0 | 456176 5 | 0 0 | 0 0 | 0 0 | 0 0 | 45617 6 | 0 0 | 0 0 |
| 107 | 9 9 | 454595 7 | 0 0 | 0 0 | 0 0 | 0 0 | 45459 6 | 0 0 | 0 0 |
| 108 | 9 9 | 452879 6 | 0 0 | 0 0 | 0 0 | 0 0 | 45288 0 | 0 0 | 0 0 |
| 109 | 9 9 | 451023 5 | 0 0 | 0 0 | 0 0 | 0 0 | 45102 4 | 0 0 | 0 0 |
| 110 | 9 9 | 449033 5 | 0 0 | 0 0 | 0 0 | 0 0 | 44903 4 | 0 0 | 0 0 |
| 111 | 9 9 | 446910 4 | 0 0 | 0 0 | 0 0 | 0 0 | 44691 0 | 0 0 | 0 0 |
| 112 | 9 9 | 444655 2 | 0 0 | 0 0 | 0 0 | 0 0 | 44465 5 | 0 0 | 0 0 |
| 113 | 9 9 | 442268 7 | 0 0 | 0 0 | 0 0 | 0 0 | 44226 9 | 0 0 | 0 0 |
| 114 | 9 9 | 439751 8 | 0 0 | 0 0 | 0 0 | 0 0 | 43975 2 | 0 0 | 0 0 |
| 115 | 9 9 | 437105 5 | 0 0 | 0 0 | 0 0 | 0 0 | 43710 6 | 0 0 | 0 0 |
| 115 | 9 8 | 434325 6 | 0 0 | 0 0 | 0 0 | 0 0 | 43432 6 | 0 0 | 0 0 |
| 117 | 9 8 | 431423 8 | 0 0 | 0 0 | 0 0 | 0 0 | 43142 4 | 0 0 | 0 0 |
| 118 | 9 8 | 428390 7 | 0 0 | 0 0 | 0 0 | 0 0 | 42839 1 | 0 0 | 0 0 |
| 119 | 9 8 | 425232 7 | 0 0 | 0 0 | 0 0 | 0 0 | 42523 3 | 0 0 | 0 0 |
| 120 | 9 8 | 421956 5 | 0 0 | 0 0 | 0 0 | 0 0 | 42195 6 | 0 0 | 0 0 |
| 121 | 9 7 | 418552 7 | 0 0 | 0 0 | 0 0 | 0 0 | 41855 3 | 0 0 | 0 0 |
| 122 | 9 7 | 415028 1 | 0 0 | 0 0 | 0 0 | 0 0 | 41502 8 | 0 0 | 0 0 |
| 123 | 9 7 | 411384 0 | 0 0 | 0 0 | 0 0 | 0 0 | 41138 4 | 0 0 | 0 0 |
| 124 | 9 7 | 407627 1 | 0 0 | 0 0 | 0 0 | 0 0 | 40762 7 | 0 0 | 0 0 |
| 125 | 9 7 | 403748 5 | 0 0 | 0 0 | 0 0 | 0 0 | 40374 9 | 0 0 | 0 0 |
| 126 | 9 5 | 399755 0 | 0 0 | 0 0 | 0 0 | 0 0 | 39975 5 | 0 0 | 0 0 |
| 127 | 9 6 | 395648 2 | 0 0 | 0 0 | 0 0 | 0 0 | 39564 8 | 0 0 | 0 0 |
| 128 | 9 6 | 391434 7 | 0 0 | 0 0 | 0 0 | 0 0 | 39143 5 | 0 0 | 0 0 |
| 129 | 9 6 | 387106 3 | 0 0 | 0 0 | 0 0 | 0 0 | 38710 6 | 0 0 | 0 0 |
| 130 | 9 5 | 382659 9 | 0 0 | 0 0 | 0 0 | 0 0 | 38267 0 | 0 0 | 0 0 |
| 131 | 9 5 | 378131 8 | 0 0 | 0 0 | 0 0 | 0 0 | 37813 2 | 0 0 | 0 0 |
| 132 | 9 5 | 373489 3 | 0 0 | 0 0 | 0 0 | 0 0 | 37348 9 | 0 0 | 0 0 |
| 133 | 9 5 | 368739 2 | 0 0 | 0 0 | 0 0 | 0 0 | 36873 9 | 0 0 | 0 0 |
| 134 | 9 4 | 363893 4 | 0 0 | 0 0 | 0 0 | 0 0 | 36389 3 | 0 0 | 0 0 |
| 135 | 9 4 | 358953 4 | 0 0 | 0 0 | 0 0 | 0 0 | 35895 3 | 0 0 | 0 0 |
| 136 | 9 4 | 353912 1 | 0 0 | 0 0 | 0 0 | 0 0 | 35391 2 | 0 0 | 0 0 |
| 137 | 9 3 | 348776 2 | 0 0 | 0 0 | 0 0 | 0 0 | 34877 5 | 0 0 | 0 0 |
| 138 | 9 3 | 343552 3 | 0 0 | 0 0 | 0 0 | 0 0 | 34355 2 | 0 0 | 0 0 |
| 139 | 9 3 | 338238 2 | 0 0 | 0 0 | 0 0 | 0 0 | 33823 8 | 0 0 | 0 0 |
| 140 | 9 2 | 332835 9 | 0 0 | 0 0 | 0 0 | 0 0 | 33283 6 | 0 0 | 0 0 |
| 141 | 9 2 | 327352 1 | 0 0 | 0 0 | 0 0 | 0 0 | 32735 2 | 0 0 | 0 0 |
| 142 | 9 2 | 321784 6 | 0 0 | 0 0 | 0 0 | 0 0 | 32178 5 | 0 0 | 0 0 |
| 143 | 9 1 | 316136 0 | 0 0 | 0 0 | 0 0 | 0 0 | 31613 6 | 0 0 | 0 0 |
| 144 | 9 1 | 310408 4 | 0 0 | 0 0 | 0 0 | 0 0 | 31040 8 | 0 0 | 0 0 |
| 145 | 9 1 | 304608 4 | 0 0 | 0 0 | 0 0 | 0 0 | 30460 8 | 0 0 | 0 0 |
| 146 | 9 0 | 298734 4 | 0 0 | 0 0 | 0 0 | 0 0 | 29873 4 | 0 0 | 0 0 |
| 147 | 9 0 | 292792 9 | 0 0 | 0 0 | 0 0 | 0 0 | 29279 3 | 0 0 | 0 0 |
| 148 | 9 0 | 286782 2 | 0 0 | 0 0 | 0 0 | 0 0 | 28678 2 | 0 0 | 0 0 |
| 149 | 8 9 | 280709 0 | 0 0 | 0 0 | 0 0 | 0 0 | 28070 9 | 0 0 | 0 0 |
| 150 | 8 9 | 274571 7 | 0 0 | 0 0 | 0 0 | 0 0 | 27457 2 | 0 0 | 0 0 |
| 151 | 8 8 | 268373 1 | 0 0 | 0 0 | 0 0 | 0 0 | 26837 3 | 0 0 | 0 0 |
| 152 | 8 8 | 252119 8 | 0 0 | 0 0 | 0 0 | 0 0 | 25212 0 | 0 0 | 0 0 |
| 153 | 8 8 | 255814 0 | 0 0 | 0 0 | 0 0 | 0 0 | 25581 4 | 0 0 | 0 0 |

| | | | | | | | | | |
|-----|-----|----------|-----|-----|-----|-----|---------|-----|-----|
| 154 | 8 7 | 249455 0 | 0 0 | 0 0 | 0 0 | 0 0 | 24945 5 | 0 0 | 0 0 |
| 155 | 8 7 | 243049 1 | 0 0 | 0 0 | 0 0 | 0 0 | 24304 9 | 0 0 | 0 0 |
| 156 | 8 6 | 236595 4 | 0 0 | 0 0 | 0 0 | 0 0 | 23659 5 | 0 0 | 0 0 |
| 157 | 8 6 | 230100 3 | 0 0 | 0 0 | 0 0 | 0 0 | 23010 0 | 0 0 | 0 0 |
| 158 | 8 5 | 223566 5 | 0 0 | 0 0 | 0 0 | 0 0 | 22356 7 | 0 0 | 0 0 |
| 159 | 8 5 | 216996 6 | 0 0 | 0 0 | 0 0 | 0 0 | 21699 7 | 0 0 | 0 0 |
| 160 | 8 5 | 210390 5 | 0 0 | 0 0 | 0 0 | 0 0 | 21039 1 | 0 0 | 0 0 |
| 161 | 8 4 | 203754 2 | 0 0 | 0 0 | 0 0 | 0 0 | 20375 4 | 0 0 | 0 0 |
| 162 | 8 4 | 197090 6 | 0 0 | 0 0 | 0 0 | 0 0 | 19709 1 | 0 0 | 0 0 |
| 163 | 8 3 | 190399 5 | 0 0 | 0 0 | 0 0 | 0 0 | 19040 0 | 0 0 | 0 0 |
| 164 | 8 3 | 183689 9 | 0 0 | 0 0 | 0 0 | 0 0 | 18359 0 | 0 0 | 0 0 |
| 165 | 8 2 | 176958 9 | 0 0 | 0 0 | 0 0 | 0 0 | 17695 9 | 0 0 | 0 0 |
| 166 | 8 2 | 170215 0 | 0 0 | 0 0 | 0 0 | 0 0 | 17021 5 | 0 0 | 0 0 |
| 167 | 8 1 | 163455 9 | 0 0 | 0 0 | 0 0 | 0 0 | 16345 6 | 0 0 | 0 0 |
| 168 | 8 1 | 156687 2 | 0 0 | 0 0 | 0 0 | 0 0 | 15668 7 | 0 0 | 0 0 |
| 169 | 8 0 | 149912 0 | 0 0 | 0 0 | 0 0 | 0 0 | 14991 2 | 0 0 | 0 0 |
| 170 | 8 0 | 143135 8 | 0 0 | 0 0 | 0 0 | 0 0 | 14313 6 | 0 0 | 0 0 |
| 171 | 7 9 | 136355 8 | 0 0 | 0 0 | 0 0 | 0 0 | 13635 7 | 0 0 | 0 0 |
| 172 | 7 9 | 129582 7 | 0 0 | 0 0 | 0 0 | 0 0 | 12958 3 | 0 0 | 0 0 |
| 173 | 7 8 | 122812 3 | 0 0 | 0 0 | 0 0 | 0 0 | 12281 2 | 0 0 | 0 0 |
| 174 | 7 7 | 115054 9 | 0 0 | 0 0 | 0 0 | 0 0 | 11605 5 | 0 0 | 0 0 |
| 175 | 7 7 | 109305 6 | 0 0 | 0 0 | 0 0 | 0 0 | 10930 6 | 0 0 | 0 0 |
| 176 | 7 6 | 102573 6 | 0 0 | 0 0 | 0 0 | 0 0 | 10257 4 | 0 0 | 0 0 |
| 177 | 7 6 | 95861 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9586 2 | 0 0 | 0 0 |
| 178 | 7 5 | 89169 9 | 0 0 | 0 0 | 0 0 | 0 0 | 8917 0 | 0 0 | 0 0 |
| 179 | 7 5 | 82507 2 | 0 0 | 0 0 | 0 0 | 0 0 | 8250 7 | 0 0 | 0 0 |
| 180 | 7 4 | 75868 4 | 0 0 | 0 0 | 0 0 | 0 0 | 7586 8 | 0 0 | 0 0 |
| 181 | 7 3 | 69264 7 | 0 0 | 0 0 | 0 0 | 0 0 | 6926 5 | 0 0 | 0 0 |
| 182 | 7 3 | 62694 3 | 0 0 | 0 0 | 0 0 | 0 0 | 6269 4 | 0 0 | 0 0 |
| 183 | 7 2 | 56162 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5616 3 | 0 0 | 0 0 |
| 184 | 7 2 | 49672 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4967 3 | 0 0 | 0 0 |
| 185 | 7 1 | 43228 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4322 8 | 0 0 | 0 0 |
| 186 | 7 0 | 36830 1 | 0 0 | 0 0 | 0 0 | 0 0 | 3683 0 | 0 0 | 0 0 |
| 187 | 7 0 | 30483 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3048 3 | 0 0 | 0 0 |
| 188 | 3 0 | 11256 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1125 7 | 0 0 | 0 0 |
| 189 | 3 9 | 12934 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1293 5 | 0 0 | 0 0 |
| 190 | 5 6 | 15048 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1504 8 | 0 0 | 0 0 |
| 191 | 1 3 | 2908 6 | 0 0 | 0 0 | 0 0 | 0 0 | 290 9 | 0 0 | 0 0 |
| 192 | 6 8 | 11783 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1178 3 | 0 0 | 0 0 |
| 193 | 1 2 | 1424 3 | 0 0 | 0 0 | 0 0 | 0 0 | 142 4 | 0 0 | 0 0 |
| 194 | 5 6 | 4376 3 | 0 0 | 0 0 | 0 0 | 0 0 | 437 6 | 0 0 | 0 0 |
| 195 | 3 5 | 767 5 | 0 0 | 0 0 | 0 0 | 0 0 | 76 7 | 0 0 | 0 0 |

Failure Surface Specified By 184 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 545 00 | 617 50 |
| 2 | 552 09 | 610 44 |
| 3 | 559 23 | 603 45 |
| 4 | 566 45 | 596 52 |
| 5 | 573 72 | 589 66 |
| 6 | 581 05 | 582 86 |
| 7 | 588 45 | 576 13 |
| 8 | 595 90 | 569 46 |
| 9 | 503 42 | 562 87 |
| 10 | 610 99 | 556 34 |
| 11 | 618 63 | 549 88 |
| 12 | 625 32 | 543 48 |
| 13 | 634 07 | 537 16 |
| 14 | 641 87 | 530 91 |
| 15 | 649 73 | 524 73 |
| 16 | 657 65 | 518 62 |
| 17 | 665 62 | 512 58 |
| 18 | 673 64 | 506 61 |
| 19 | 581 72 | 500 72 |
| 20 | 689 85 | 494 89 |
| 21 | 698 03 | 489 15 |
| 22 | 706 27 | 483 47 |
| 23 | 714 55 | 477 87 |

| | | |
|----|---------|--------|
| 24 | 722 88 | 472 34 |
| 25 | 731 27 | 466 89 |
| 26 | 739 70 | 461 52 |
| 27 | 748 18 | 456 22 |
| 28 | 756 71 | 451 00 |
| 29 | 765 29 | 445 85 |
| 30 | 773 91 | 440 78 |
| 31 | 782 57 | 435 79 |
| 32 | 791 28 | 430 88 |
| 33 | 800 04 | 426 05 |
| 34 | 808 83 | 421 29 |
| 35 | 817 67 | 416 62 |
| 36 | 826 56 | 412 02 |
| 37 | 835 48 | 407 51 |
| 38 | 844 44 | 403 07 |
| 39 | 853 44 | 398 72 |
| 40 | 862 48 | 394 45 |
| 41 | 871 56 | 390 25 |
| 42 | 880 68 | 386 15 |
| 43 | 889 83 | 382 12 |
| 44 | 899 02 | 378 17 |
| 45 | 908 25 | 374 31 |
| 46 | 917 50 | 370 53 |
| 47 | 925 80 | 365 84 |
| 48 | 936 12 | 363 22 |
| 49 | 945 48 | 359 70 |
| 50 | 954 87 | 356 25 |
| 51 | 964 29 | 352 89 |
| 52 | 973 74 | 349 62 |
| 53 | 983 21 | 346 43 |
| 54 | 992 72 | 343 33 |
| 55 | 1002 25 | 340 31 |
| 56 | 1011 81 | 337 38 |
| 57 | 1021 40 | 334 53 |
| 58 | 1031 01 | 331 77 |
| 59 | 1040 65 | 329 10 |
| 60 | 1050 31 | 326 52 |
| 61 | 1059 99 | 324 02 |
| 62 | 1069 70 | 321 61 |
| 63 | 1079 42 | 319 28 |
| 64 | 1089 17 | 317 04 |
| 65 | 1098 94 | 314 90 |
| 66 | 1108 72 | 312 83 |
| 67 | 1118 52 | 310 86 |
| 68 | 1128 34 | 308 98 |
| 69 | 1138 18 | 307 18 |
| 70 | 1148 04 | 305 47 |
| 71 | 1157 90 | 303 85 |
| 72 | 1167 79 | 302 32 |
| 73 | 1177 68 | 300 88 |
| 74 | 1187 59 | 299 53 |
| 75 | 1197 51 | 298 27 |
| 76 | 1207 44 | 297 10 |
| 77 | 1217 38 | 296 01 |
| 78 | 1227 33 | 295 02 |
| 79 | 1237 29 | 294 11 |
| 80 | 1247 26 | 293 30 |
| 81 | 1257 23 | 292 57 |
| 82 | 1267 21 | 291 94 |
| 83 | 1277 20 | 291 39 |
| 84 | 1287 19 | 290 93 |
| 85 | 1297 18 | 290 57 |
| 86 | 1307 17 | 290 29 |
| 87 | 1317 17 | 290 10 |
| 88 | 1327 17 | 290 01 |
| 89 | 1337 17 | 290 00 |
| 90 | 1347 17 | 290 08 |
| 91 | 1357 17 | 290 26 |

| | | |
|-----|---------|--------|
| 92 | 1367 17 | 290 52 |
| 93 | 1377 16 | 290 87 |
| 94 | 1387 15 | 291 32 |
| 95 | 1397 14 | 291 85 |
| 96 | 1407 12 | 292 47 |
| 97 | 1417 09 | 293 19 |
| 98 | 1427 06 | 293 99 |
| 99 | 1437 02 | 294 88 |
| 100 | 1446 97 | 295 86 |
| 101 | 1456 91 | 296 93 |
| 102 | 1466 85 | 298 09 |
| 103 | 1476 77 | 299 34 |
| 104 | 1485 68 | 300 68 |
| 105 | 1496 58 | 302 11 |
| 106 | 1506 46 | 303 63 |
| 107 | 1516 33 | 305 23 |
| 108 | 1526 19 | 306 93 |
| 109 | 1536 03 | 308 71 |
| 110 | 1545 85 | 310 58 |
| 111 | 1555 65 | 312 54 |
| 112 | 1565 44 | 314 59 |
| 113 | 1575 21 | 316 73 |
| 114 | 1584 96 | 318 95 |
| 115 | 1594 69 | 321 26 |
| 116 | 1604 40 | 323 66 |
| 117 | 1614 08 | 326 15 |
| 118 | 1623 75 | 328 72 |
| 119 | 1633 39 | 331 38 |
| 120 | 1643 00 | 334 13 |
| 121 | 1652 59 | 336 96 |
| 122 | 1662 16 | 339 88 |
| 123 | 1671 70 | 342 88 |
| 124 | 1681 21 | 345 98 |
| 125 | 1690 69 | 349 15 |
| 126 | 1700 14 | 352 41 |
| 127 | 1709 56 | 355 76 |
| 128 | 1718 96 | 359 19 |
| 129 | 1728 32 | 362 71 |
| 130 | 1737 65 | 366 31 |
| 131 | 1746 95 | 369 99 |
| 132 | 1756 21 | 373 76 |
| 133 | 1765 44 | 377 61 |
| 134 | 1774 63 | 381 54 |
| 135 | 1783 79 | 385 55 |
| 136 | 1792 91 | 389 65 |
| 137 | 1802 00 | 393 83 |
| 138 | 1811 04 | 398 09 |
| 139 | 1820 05 | 402 43 |
| 140 | 1829 02 | 406 86 |
| 141 | 1837 95 | 411 36 |
| 142 | 1846 84 | 415 95 |
| 143 | 1855 68 | 420 61 |
| 144 | 1864 49 | 425 35 |
| 145 | 1873 25 | 430 17 |
| 146 | 1881 96 | 435 07 |
| 147 | 1890 64 | 440 05 |
| 148 | 1899 25 | 445 11 |
| 149 | 1907 85 | 450 24 |
| 150 | 1916 38 | 455 46 |
| 151 | 1924 87 | 460 74 |
| 152 | 1933 31 | 466 11 |
| 153 | 1941 70 | 471 55 |
| 154 | 1950 04 | 477 06 |
| 155 | 1958 33 | 482 65 |
| 156 | 1966 57 | 488 31 |
| 157 | 1974 76 | 494 05 |
| 158 | 1982 90 | 499 86 |
| 159 | 1990 99 | 505 75 |

| | | |
|-----|---------|--------|
| 160 | 1999 02 | 511 71 |
| 161 | 2007 00 | 517 73 |
| 162 | 2014 92 | 523 83 |
| 163 | 2022 79 | 530 01 |
| 164 | 2030 60 | 536 25 |
| 165 | 2038 36 | 542 56 |
| 166 | 2046 06 | 548 94 |
| 167 | 2053 70 | 555 39 |
| 168 | 2061 28 | 561 91 |
| 169 | 2068 81 | 568 50 |
| 170 | 2076 27 | 575 15 |
| 171 | 2083 68 | 581 87 |
| 172 | 2091 02 | 588 66 |
| 173 | 2098 30 | 595 52 |
| 174 | 2105 52 | 602 43 |
| 175 | 2112 68 | 609 42 |
| 176 | 2119 77 | 616 47 |
| 177 | 2126 80 | 623 58 |
| 178 | 2133 77 | 630 75 |
| 179 | 2140 67 | 637 99 |
| 180 | 2147 51 | 645 28 |
| 181 | 2154 28 | 652 64 |
| 182 | 2160 98 | 660 06 |
| 183 | 2167 62 | 567 54 |
| 184 | 2169 76 | 670 00 |

Circle Center At X = 1332 9 , Y = 1401 5 and Radius, 1111 5

*** 1 021 ***

Failure Surface Specified By 187 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 545 00 | 617 50 |
| 2 | 552 32 | 610 69 |
| 3 | 559 70 | 603 94 |
| 4 | 567 14 | 597 25 |
| 5 | 574 63 | 590 63 |
| 6 | 582 18 | 584 07 |
| 7 | 589 78 | 577 58 |
| 8 | 597 44 | 571 15 |
| 9 | 605 16 | 564 78 |
| 10 | 612 92 | 558 48 |
| 11 | 620 74 | 552 25 |
| 12 | 628 61 | 546 08 |
| 13 | 636 54 | 539 98 |
| 14 | 644 51 | 533 95 |
| 15 | 652 54 | 527 98 |
| 15 | 660 61 | 522 08 |
| 17 | 658 74 | 516 25 |
| 18 | 676 91 | 510 49 |
| 19 | 685 14 | 504 80 |
| 20 | 693 41 | 499 18 |
| 21 | 701 72 | 493 63 |
| 22 | 710 09 | 488 15 |
| 23 | 718 50 | 482 74 |
| 24 | 726 96 | 477 41 |
| 25 | 735 46 | 472 14 |
| 26 | 744 00 | 466 95 |
| 27 | 752 59 | 461 82 |
| 28 | 761 22 | 456 78 |
| 29 | 769 90 | 451 80 |
| 30 | 778 62 | 446 90 |
| 31 | 787 37 | 442 07 |
| 32 | 796 17 | 437 32 |
| 33 | 805 01 | 432 64 |
| 34 | 813 89 | 428 04 |
| 35 | 822 80 | 423 51 |
| 36 | 831 76 | 419 05 |
| 37 | 840 75 | 414 68 |
| 38 | 849 78 | 410 38 |

| | | |
|-----|---------|--------|
| 39 | 858 84 | 406 15 |
| 40 | 867 94 | 402 00 |
| 41 | 877 07 | 397 93 |
| 42 | 886 24 | 393 94 |
| 43 | 895 44 | 390 03 |
| 44 | 904 68 | 386 19 |
| 45 | 913 94 | 382 43 |
| 46 | 923 24 | 378 75 |
| 47 | 932 57 | 375 15 |
| 48 | 941 93 | 371 63 |
| 49 | 951 32 | 368 18 |
| 50 | 960 74 | 364 82 |
| 51 | 970 18 | 361 54 |
| 52 | 979 55 | 358 33 |
| 53 | 989 15 | 355 21 |
| 54 | 998 68 | 352 17 |
| 55 | 1008 23 | 349 20 |
| 56 | 1017 81 | 346 32 |
| 57 | 1027 41 | 343 52 |
| 58 | 1037 03 | 340 80 |
| 59 | 1046 68 | 338 17 |
| 60 | 1056 34 | 335 61 |
| 61 | 1065 03 | 333 14 |
| 62 | 1075 74 | 330 74 |
| 63 | 1085 47 | 328 44 |
| 64 | 1095 22 | 326 21 |
| 65 | 1104 99 | 324 06 |
| 66 | 1114 77 | 322 00 |
| 67 | 1124 58 | 320 02 |
| 68 | 1134 40 | 318 13 |
| 69 | 1144 23 | 316 32 |
| 70 | 1154 08 | 314 59 |
| 71 | 1163 94 | 312 94 |
| 72 | 1173 82 | 311 38 |
| 73 | 1183 71 | 309 90 |
| 74 | 1193 61 | 308 50 |
| 75 | 1203 53 | 307 19 |
| 76 | 1213 45 | 305 97 |
| 77 | 1223 38 | 304 82 |
| 78 | 1233 33 | 303 76 |
| 79 | 1243 28 | 302 79 |
| 80 | 1253 24 | 301 90 |
| 81 | 1253 21 | 301 09 |
| 82 | 1273 18 | 300 37 |
| 83 | 1283 16 | 299 73 |
| 84 | 1293 15 | 299 18 |
| 85 | 1303 14 | 298 71 |
| 86 | 1313 13 | 298 33 |
| 87 | 1323 12 | 298 03 |
| 88 | 1333 12 | 297 81 |
| 89 | 1343 12 | 297 68 |
| 90 | 1353 12 | 297 63 |
| 91 | 1363 12 | 297 67 |
| 92 | 1373 12 | 297 80 |
| 93 | 1383 12 | 298 01 |
| 94 | 1393 11 | 298 30 |
| 95 | 1403 11 | 298 68 |
| 96 | 1413 10 | 299 14 |
| 97 | 1423 08 | 299 68 |
| 98 | 1433 06 | 300 31 |
| 99 | 1443 04 | 301 03 |
| 100 | 1453 00 | 301 83 |
| 101 | 1462 96 | 302 71 |
| 102 | 1472 92 | 303 68 |
| 103 | 1482 86 | 304 73 |
| 104 | 1492 80 | 305 87 |
| 105 | 1502 72 | 307 09 |
| 106 | 1512 64 | 308 39 |

| | | |
|-----|---------|--------|
| 107 | 1522 54 | 309 78 |
| 108 | 1532 43 | 311 25 |
| 109 | 1542 31 | 312 81 |
| 110 | 1652 17 | 314 45 |
| 111 | 1552 02 | 316 17 |
| 112 | 1571 86 | 317 98 |
| 113 | 1581 68 | 319 87 |
| 114 | 1591 48 | 321 84 |
| 115 | 1601 27 | 323 89 |
| 116 | 1611 04 | 326 03 |
| 117 | 1620 79 | 328 25 |
| 118 | 1630 52 | 330 55 |
| 119 | 1640 23 | 332 94 |
| 120 | 1649 92 | 335 41 |
| 121 | 1559 59 | 337 96 |
| 122 | 1669 24 | 340 59 |
| 123 | 1678 87 | 343 30 |
| 124 | 1688 47 | 346 09 |
| 125 | 1698 05 | 348 97 |
| 126 | 1707 60 | 351 92 |
| 127 | 1717 13 | 354 96 |
| 128 | 1726 63 | 358 08 |
| 129 | 1736 10 | 361 27 |
| 130 | 1745 55 | 364 55 |
| 131 | 1754 97 | 367 91 |
| 132 | 1764 36 | 371 34 |
| 133 | 1773 72 | 374 86 |
| 134 | 1783 05 | 378 46 |
| 135 | 1792 35 | 382 13 |
| 136 | 1801 62 | 385 88 |
| 137 | 1810 86 | 389 71 |
| 138 | 1820 07 | 393 62 |
| 139 | 1829 24 | 397 61 |
| 140 | 1838 37 | 401 67 |
| 141 | 1847 48 | 405 81 |
| 142 | 1856 54 | 410 03 |
| 143 | 1865 57 | 414 33 |
| 144 | 1874 57 | 418 70 |
| 145 | 1883 52 | 423 14 |
| 146 | 1892 44 | 427 67 |
| 147 | 1901 32 | 432 26 |
| 148 | 1910 17 | 436 94 |
| 149 | 1918 97 | 441 68 |
| 150 | 1927 73 | 446 51 |
| 151 | 1936 45 | 451 40 |
| 152 | 1945 12 | 456 37 |
| 153 | 1953 76 | 461 41 |
| 154 | 1962 35 | 466 53 |
| 155 | 1970 90 | 471 72 |
| 156 | 1979 41 | 476 98 |
| 157 | 1987 87 | 482 31 |
| 158 | 1996 28 | 487 71 |
| 159 | 2004 65 | 493 19 |
| 160 | 2012 97 | 498 73 |
| 161 | 2021 25 | 504 35 |
| 162 | 2029 47 | 510 03 |
| 163 | 2037 65 | 515 79 |
| 164 | 2045 78 | 521 61 |
| 165 | 2053 86 | 527 50 |
| 166 | 2061 89 | 533 45 |
| 167 | 2069 87 | 539 49 |
| 168 | 2077 80 | 545 58 |
| 169 | 2085 67 | 551 75 |
| 170 | 2093 50 | 557 97 |
| 171 | 2101 27 | 564 27 |
| 172 | 2108 98 | 570 63 |
| 173 | 2116 65 | 577 05 |
| 174 | 2124 26 | 583 54 |

| | | |
|-----|---------|--------|
| 175 | 2131 81 | 590 10 |
| 176 | 2139 31 | 596 71 |
| 177 | 2145 75 | 503 39 |
| 178 | 2154 13 | 610 14 |
| 179 | 2161 46 | 616 94 |
| 180 | 2168 73 | 623 81 |
| 181 | 2175 94 | 630 74 |
| 182 | 2183 09 | 637 73 |
| 183 | 2190 18 | 544 78 |
| 184 | 2197 22 | 651 89 |
| 185 | 2204 19 | 659 06 |
| 185 | 2211 10 | 665 28 |
| 187 | 2214 59 | 670 00 |

Circle Center At X = 1353 5 Y = 1479 4 and Radius, 1181 8
 *** 1 026 ***

Failure Surface Specified By 184 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 578 75 | 617 91 |
| 2 | 585 86 | 510 87 |
| 3 | 593 03 | 603 91 |
| 4 | 600 26 | 597 00 |
| 5 | 607 56 | 590 16 |
| 6 | 614 91 | 583 39 |
| 7 | 622 33 | 576 68 |
| 8 | 629 81 | 570 04 |
| 9 | 637 34 | 563 46 |
| 10 | 644 93 | 556 95 |
| 11 | 652 59 | 550 52 |
| 12 | 660 29 | 544 15 |
| 13 | 668 06 | 537 85 |
| 14 | 675 88 | 531 62 |
| 15 | 683 76 | 525 46 |
| 16 | 691 69 | 519 37 |
| 17 | 699 68 | 513 35 |
| 18 | 707 72 | 507 40 |
| 19 | 715 81 | 501 53 |
| 20 | 723 96 | 495 73 |
| 21 | 732 15 | 490 00 |
| 22 | 740 40 | 484 34 |
| 23 | 748 70 | 478 76 |
| 24 | 757 05 | 473 26 |
| 25 | 765 44 | 467 83 |
| 26 | 773 89 | 462 47 |
| 27 | 782 38 | 457 19 |
| 28 | 790 92 | 451 99 |
| 29 | 799 51 | 446 86 |
| 30 | 808 14 | 441 81 |
| 31 | 816 82 | 436 84 |
| 32 | 825 54 | 431 95 |
| 33 | 834 30 | 427 13 |
| 34 | 843 11 | 422 39 |
| 35 | 851 96 | 417 74 |
| 36 | 860 85 | 413 16 |
| 37 | 869 78 | 408 66 |
| 38 | 878 75 | 404 24 |
| 39 | 887 76 | 399 90 |
| 40 | 896 81 | 395 64 |
| 41 | 905 89 | 391 47 |
| 42 | 915 02 | 387 37 |
| 43 | 924 18 | 383 36 |
| 44 | 933 37 | 379 43 |
| 45 | 942 60 | 375 58 |
| 46 | 951 87 | 371 82 |
| 47 | 961 16 | 368 14 |
| 48 | 970 49 | 364 54 |
| 49 | 979 85 | 361 02 |
| 50 | 989 25 | 357 59 |

| | | |
|-----|---------|--------|
| 51 | 998 67 | 354 25 |
| 52 | 1008 12 | 350 98 |
| 53 | 1017 61 | 347 81 |
| 54 | 1027 12 | 344 72 |
| 55 | 1036 55 | 341 71 |
| 55 | 1045 22 | 338 79 |
| 57 | 1055 81 | 335 95 |
| 58 | 1065 42 | 333 20 |
| 59 | 1075 06 | 330 54 |
| 60 | 1084 72 | 327 96 |
| 61 | 1094 41 | 325 47 |
| 62 | 1104 11 | 323 07 |
| 63 | 1113 84 | 320 75 |
| 64 | 1123 59 | 318 52 |
| 55 | 1133 36 | 316 38 |
| 66 | 1143 15 | 314 33 |
| 67 | 1152 95 | 312 36 |
| 68 | 1162 77 | 310 48 |
| 69 | 1172 61 | 308 69 |
| 70 | 1182 47 | 306 99 |
| 71 | 1192 33 | 305 38 |
| 72 | 1202 22 | 303 85 |
| 73 | 1212 11 | 302 42 |
| 74 | 1222 02 | 301 07 |
| 75 | 1231 94 | 299 81 |
| 76 | 1241 87 | 298 64 |
| 77 | 1251 82 | 297 56 |
| 78 | 1261 77 | 296 57 |
| 79 | 1271 72 | 295 66 |
| 80 | 1281 69 | 294 85 |
| 81 | 1291 67 | 294 12 |
| 82 | 1301 65 | 293 49 |
| 83 | 1311 63 | 292 94 |
| 84 | 1321 62 | 292 49 |
| 85 | 1331 61 | 292 12 |
| 86 | 1341 61 | 291 84 |
| 87 | 1351 61 | 291 65 |
| 88 | 1361 61 | 291 56 |
| 89 | 1371 61 | 291 55 |
| 90 | 1381 61 | 291 63 |
| 91 | 1391 51 | 291 80 |
| 92 | 1401 50 | 292 06 |
| 93 | 1411 60 | 292 41 |
| 94 | 1421 59 | 292 85 |
| 95 | 1431 57 | 293 38 |
| 96 | 1441 55 | 293 99 |
| 97 | 1451 53 | 294 70 |
| 98 | 1461 50 | 295 50 |
| 99 | 1471 46 | 296 38 |
| 100 | 1481 41 | 297 36 |
| 101 | 1491 35 | 298 42 |
| 102 | 1501 29 | 299 58 |
| 103 | 1511 21 | 300 82 |
| 104 | 1521 12 | 302 15 |
| 105 | 1531 02 | 303 57 |
| 106 | 1540 90 | 305 08 |
| 107 | 1550 78 | 306 67 |
| 108 | 1560 63 | 308 36 |
| 109 | 1570 47 | 310 13 |
| 110 | 1580 30 | 311 99 |
| 111 | 1590 11 | 313 94 |
| 112 | 1599 90 | 315 98 |
| 113 | 1509 67 | 318 11 |
| 114 | 1519 42 | 320 32 |
| 115 | 1629 15 | 322 62 |
| 116 | 1638 86 | 325 00 |
| 117 | 1648 55 | 327 48 |
| 118 | 1558 22 | 330 04 |

| | | |
|-----|---------|--------|
| 119 | 1667 86 | 332 68 |
| 120 | 1677 48 | 335 42 |
| 121 | 1687 08 | 338 24 |
| 122 | 1696 65 | 341 14 |
| 123 | 1706 19 | 344 13 |
| 124 | 1715 70 | 347 21 |
| 125 | 1725 19 | 350 37 |
| 126 | 1734 65 | 353 61 |
| 127 | 1744 08 | 356 94 |
| 128 | 1753 48 | 360 36 |
| 129 | 1752 85 | 363 86 |
| 130 | 1772 18 | 367 44 |
| 131 | 1781 49 | 371 10 |
| 132 | 1790 76 | 374 85 |
| 133 | 1799 99 | 378 68 |
| 134 | 1809 20 | 382 60 |
| 135 | 1818 36 | 386 60 |
| 136 | 1827 49 | 390 67 |
| 137 | 1836 59 | 394 83 |
| 138 | 1845 64 | 399 08 |
| 139 | 1854 66 | 403 40 |
| 140 | 1863 64 | 407 80 |
| 141 | 1872 58 | 412 29 |
| 142 | 1881 48 | 416 85 |
| 143 | 1890 33 | 421 49 |
| 144 | 1899 15 | 426 21 |
| 145 | 1907 92 | 431 01 |
| 146 | 1916 65 | 435 89 |
| 147 | 1925 33 | 440 85 |
| 148 | 1933 97 | 445 88 |
| 149 | 1942 57 | 451 00 |
| 150 | 1951 12 | 456 18 |
| 151 | 1959 62 | 461 45 |
| 152 | 1968 07 | 466 79 |
| 153 | 1976 48 | 472 21 |
| 154 | 1984 84 | 477 70 |
| 155 | 1993 14 | 483 26 |
| 156 | 2001 40 | 488 90 |
| 157 | 2009 61 | 494 62 |
| 158 | 2017 76 | 500 41 |
| 159 | 2025 87 | 506 27 |
| 160 | 2033 92 | 512 20 |
| 161 | 2041 91 | 518 20 |
| 162 | 2049 86 | 524 28 |
| 163 | 2057 75 | 530 42 |
| 164 | 2055 58 | 536 64 |
| 165 | 2073 35 | 542 93 |
| 166 | 2081 07 | 549 28 |
| 167 | 2088 74 | 555 71 |
| 168 | 2096 34 | 562 20 |
| 169 | 2103 89 | 568 76 |
| 170 | 2111 38 | 575 39 |
| 171 | 2118 80 | 582 09 |
| 172 | 2126 17 | 588 85 |
| 173 | 2133 46 | 595 68 |
| 174 | 2140 72 | 602 57 |
| 175 | 2147 91 | 609 53 |
| 176 | 2155 03 | 616 55 |
| 177 | 2162 08 | 623 63 |
| 178 | 2169 08 | 630 78 |
| 179 | 2176 01 | 637 99 |
| 180 | 2182 87 | 645 26 |
| 181 | 2189 67 | 652 60 |
| 132 | 2196 40 | 659 99 |
| 183 | 2203 07 | 667 44 |
| 184 | 2205 31 | 670 00 |

Circle Center At X = 1367 6 , Y = 1408 0 and Radius, 1116 4
 *** 1 040 ***

Failure Surface Specified By 170 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 500 00 | 616 95 |
| 2 | 507 07 | 609 88 |
| 3 | 514 21 | 602 87 |
| 4 | 521 42 | 595 94 |
| 5 | 528 70 | 589 08 |
| 6 | 536 04 | 582 30 |
| 7 | 543 45 | 575 58 |
| 8 | 550 93 | 568 94 |
| 9 | 558 47 | 562 37 |
| 10 | 566 07 | 555 88 |
| 11 | 573 74 | 549 46 |
| 12 | 581 47 | 543 12 |
| 13 | 589 26 | 535 85 |
| 14 | 597 12 | 530 66 |
| 15 | 605 03 | 524 55 |
| 16 | 613 01 | 518 51 |
| 17 | 621 04 | 512 56 |
| 18 | 629 13 | 506 68 |
| 19 | 637 28 | 500 89 |
| 20 | 645 49 | 495 17 |
| 21 | 653 75 | 489 54 |
| 22 | 662 06 | 483 98 |
| 23 | 670 43 | 478 51 |
| 24 | 678 86 | 473 12 |
| 25 | 687 33 | 467 82 |
| 26 | 695 86 | 452 59 |
| 27 | 704 44 | 457 46 |
| 28 | 713 07 | 452 40 |
| 29 | 721 75 | 447 43 |
| 30 | 730 48 | 442 55 |
| 31 | 739 25 | 437 75 |
| 32 | 748 07 | 433 04 |
| 33 | 756 94 | 428 42 |
| 34 | 765 85 | 423 88 |
| 35 | 774 81 | 419 44 |
| 35 | 783 81 | 415 07 |
| 37 | 792 85 | 410 80 |
| 38 | 801 93 | 406 62 |
| 39 | 811 05 | 402 53 |
| 40 | 820 22 | 398 53 |
| 41 | 829 42 | 394 61 |
| 42 | 838 66 | 390 79 |
| 43 | 847 94 | 387 06 |
| 44 | 857 25 | 383 42 |
| 45 | 866 60 | 379 87 |
| 46 | 875 99 | 376 42 |
| 47 | 885 40 | 373 05 |
| 48 | 894 85 | 369 78 |
| 49 | 904 34 | 366 60 |
| 50 | 913 85 | 363 52 |
| 51 | 923 39 | 360 53 |
| 52 | 932 96 | 357 63 |
| 53 | 942 56 | 354 83 |
| 54 | 952 19 | 352 12 |
| 55 | 961 84 | 349 51 |
| 56 | 971 52 | 346 99 |
| 57 | 981 22 | 344 57 |
| 58 | 990 95 | 342 24 |
| 59 | 1000 69 | 340 01 |
| 60 | 1010 45 | 337 87 |
| 61 | 1020 25 | 335 83 |
| 62 | 1030 06 | 333 89 |
| 63 | 1039 89 | 332 04 |
| 64 | 1049 74 | 330 29 |
| 65 | 1059 60 | 328 64 |

| | | |
|-----|---------|--------|
| 66 | 1059 48 | 327 08 |
| 67 | 1079 37 | 325 62 |
| 68 | 1089 28 | 324 26 |
| 59 | 1099 20 | 323 00 |
| 70 | 1109 13 | 321 83 |
| 71 | 1119 07 | 320 76 |
| 72 | 1129 02 | 319 79 |
| 73 | 1138 99 | 318 92 |
| 74 | 1148 96 | 318 14 |
| 75 | 1158 93 | 317 46 |
| 76 | 1168 92 | 316 89 |
| 77 | 1178 90 | 316 40 |
| 78 | 1188 90 | 315 02 |
| 79 | 1198 89 | 315 74 |
| 80 | 1208 89 | 315 55 |
| 81 | 1218 89 | 315 46 |
| 82 | 1228 89 | 315 47 |
| 83 | 1238 89 | 315 58 |
| 84 | 1248 89 | 315 79 |
| 85 | 1258 88 | 316 09 |
| 86 | 1268 87 | 316 50 |
| 87 | 1278 86 | 317 00 |
| 88 | 1288 84 | 317 60 |
| 89 | 1298 82 | 318 30 |
| 90 | 1308 79 | 319 09 |
| 91 | 1318 75 | 319 98 |
| 92 | 1328 70 | 320 98 |
| 93 | 1338 64 | 322 07 |
| 94 | 1348 57 | 323 25 |
| 95 | 1358 49 | 324 54 |
| 96 | 1368 39 | 325 92 |
| 97 | 1378 28 | 327 40 |
| 98 | 1388 15 | 328 97 |
| 99 | 1398 01 | 330 65 |
| 100 | 1407 86 | 332 42 |
| 101 | 1417 68 | 334 29 |
| 102 | 1427 49 | 336 25 |
| 103 | 1437 27 | 338 31 |
| 104 | 1447 04 | 340 46 |
| 105 | 1456 78 | 342 72 |
| 106 | 1466 50 | 345 06 |
| 107 | 1476 20 | 347 51 |
| 108 | 1485 87 | 350 04 |
| 109 | 1495 52 | 352 68 |
| 110 | 1505 14 | 355 40 |
| 111 | 1514 73 | 358 23 |
| 112 | 1524 30 | 361 14 |
| 113 | 1533 83 | 364 15 |
| 114 | 1543 34 | 367 26 |
| 115 | 1552 81 | 370 45 |
| 116 | 1562 26 | 373 74 |
| 117 | 1571 67 | 377 13 |
| 118 | 1581 04 | 380 60 |
| 119 | 1590 39 | 384 17 |
| 120 | 1599 69 | 387 83 |
| 121 | 1608 96 | 391 58 |
| 122 | 1618 20 | 395 42 |
| 123 | 1627 39 | 399 35 |
| 124 | 1636 55 | 403 37 |
| 125 | 1645 66 | 407 48 |
| 126 | 1654 74 | 411 68 |
| 127 | 1663 77 | 415 97 |
| 128 | 1672 76 | 420 35 |
| 129 | 1681 71 | 424 82 |
| 130 | 1690 61 | 429 37 |
| 131 | 1699 47 | 434 01 |
| 132 | 1708 28 | 438 74 |
| 133 | 1717 04 | 443 56 |

| | | |
|-----|---------|--------|
| 134 | 1725 76 | 448 46 |
| 135 | 1734 43 | 453 44 |
| 136 | 1743 05 | 458 51 |
| 137 | 1751 62 | 463 67 |
| 138 | 1760 13 | 468 91 |
| 139 | 1768 60 | 474 23 |
| 140 | 1777 01 | 479 64 |
| 141 | 1785 37 | 485 13 |
| 142 | 1793 68 | 490 70 |
| 143 | 1801 93 | 496 35 |
| 144 | 1810 12 | 502 08 |
| 145 | 1818 26 | 507 90 |
| 146 | 1826 34 | 513 79 |
| 147 | 1834 36 | 519 76 |
| 148 | 1842 32 | 525 81 |
| 149 | 1850 22 | 531 94 |
| 150 | 1858 06 | 538 14 |
| 151 | 1865 84 | 544 43 |
| 152 | 1873 56 | 550 79 |
| 153 | 1881 22 | 557 22 |
| 154 | 1888 81 | 563 73 |
| 155 | 1896 33 | 570 31 |
| 156 | 1903 80 | 576 97 |
| 157 | 1911 19 | 583 70 |
| 158 | 1918 52 | 590 50 |
| 159 | 1925 79 | 597 38 |
| 160 | 1932 98 | 604 32 |
| 161 | 1940 11 | 611 34 |
| 162 | 1947 16 | 618 42 |
| 163 | 1954 15 | 625 58 |
| 164 | 1951 07 | 632 80 |
| 165 | 1967 91 | 640 09 |
| 166 | 1974 68 | 647 45 |
| 167 | 1981 38 | 654 87 |
| 168 | 1988 01 | 662 35 |
| 169 | 1994 56 | 669 91 |
| 170 | 1994 64 | 670 00 |

Circle Center At X = 1222 9 , Y = 1332 8 and Radius, 1017 3
 *** 1 046 ***

Failure Surface Specified By 178 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 533 75 | 517 36 |
| 2 | 541 11 | 610 59 |
| 3 | 548 54 | 603 89 |
| 4 | 556 02 | 597 26 |
| 5 | 563 56 | 590 69 |
| 6 | 571 16 | 584 19 |
| 7 | 578 81 | 577 75 |
| 8 | 586 52 | 571 38 |
| 9 | 594 29 | 565 09 |
| 10 | 602 11 | 558 86 |
| 11 | 609 99 | 552 70 |
| 12 | 617 92 | 546 61 |
| 13 | 625 91 | 540 59 |
| 14 | 633 94 | 534 64 |
| 15 | 642 03 | 528 76 |
| 16 | 650 18 | 522 95 |
| 17 | 558 37 | 517 22 |
| 18 | 666 61 | 511 56 |
| 19 | 674 90 | 505 97 |
| 20 | 683 24 | 500 45 |
| 21 | 691 63 | 495 01 |
| 22 | 700 07 | 489 64 |
| 23 | 708 56 | 484 36 |
| 24 | 717 09 | 479 13 |
| 25 | 725 67 | 473 99 |
| 26 | 734 29 | 468 93 |

| | | |
|----|---------|--------|
| 27 | 742 95 | 463 94 |
| 28 | 751 66 | 459 02 |
| 29 | 760 42 | 454 19 |
| 30 | 769 21 | 449 43 |
| 31 | 778 05 | 444 75 |
| 32 | 786 93 | 440 15 |
| 33 | 795 85 | 435 63 |
| 34 | 804 80 | 431 18 |
| 35 | 813 80 | 426 82 |
| 36 | 822 84 | 422 53 |
| 37 | 831 91 | 418 32 |
| 38 | 841 02 | 414 20 |
| 39 | 850 16 | 410 15 |
| 40 | 859 34 | 406 19 |
| 41 | 858 56 | 402 31 |
| 42 | 877 81 | 398 51 |
| 43 | 887 09 | 394 79 |
| 44 | 896 41 | 391 15 |
| 45 | 905 75 | 387 60 |
| 46 | 915 13 | 384 12 |
| 47 | 924 54 | 380 74 |
| 48 | 933 98 | 377 43 |
| 49 | 943 45 | 374 21 |
| 50 | 952 94 | 371 07 |
| 51 | 962 46 | 358 01 |
| 52 | 972 01 | 365 04 |
| 53 | 981 58 | 362 16 |
| 54 | 991 18 | 359 36 |
| 55 | 1000 81 | 356 64 |
| 56 | 1010 46 | 354 01 |
| 57 | 1020 13 | 351 46 |
| 58 | 1029 82 | 349 00 |
| 59 | 1039 63 | 346 63 |
| 60 | 1049 27 | 344 34 |
| 61 | 1059 02 | 342 14 |
| 62 | 1058 80 | 340 02 |
| 63 | 1078 59 | 337 99 |
| 64 | 1088 40 | 336 05 |
| 65 | 1098 22 | 334 19 |
| 66 | 1108 06 | 332 42 |
| 67 | 1117 92 | 330 74 |
| 68 | 1127 79 | 329 14 |
| 69 | 1137 68 | 327 53 |
| 70 | 1147 58 | 326 21 |
| 71 | 1157 49 | 324 87 |
| 72 | 1167 41 | 323 63 |
| 73 | 1177 34 | 322 47 |
| 74 | 1187 29 | 321 40 |
| 75 | 1197 24 | 320 42 |
| 76 | 1207 20 | 319 52 |
| 77 | 1217 16 | 318 71 |
| 78 | 1227 14 | 317 99 |
| 79 | 1237 12 | 317 36 |
| 80 | 1247 10 | 316 82 |
| 81 | 1257 09 | 316 37 |
| 82 | 1267 09 | 316 00 |
| 83 | 1277 08 | 315 72 |
| 84 | 1287 08 | 315 53 |
| 85 | 1297 08 | 315 43 |
| 86 | 1307 08 | 315 42 |
| 87 | 1317 08 | 315 49 |
| 88 | 1327 08 | 315 65 |
| 89 | 1337 08 | 315 91 |
| 90 | 1347 07 | 316 25 |
| 91 | 1357 06 | 316 67 |
| 92 | 1367 05 | 317 19 |
| 93 | 1377 03 | 317 80 |
| 94 | 1387 00 | 318 49 |

| | | |
|-----|---------|--------|
| 95 | 1396 97 | 319 27 |
| 96 | 1406 94 | 320 14 |
| 97 | 1416 89 | 321 09 |
| 98 | 1426 84 | 322 14 |
| 99 | 1436 77 | 323 27 |
| 100 | 1446 70 | 324 49 |
| 101 | 1456 61 | 325 80 |
| 102 | 1466 51 | 327 19 |
| 103 | 1476 40 | 328 68 |
| 104 | 1486 28 | 330 25 |
| 105 | 1496 14 | 331 90 |
| 106 | 1505 99 | 333 65 |
| 107 | 1515 82 | 335 48 |
| 108 | 1525 63 | 337 40 |
| 109 | 1535 43 | 339 40 |
| 110 | 1545 21 | 341 49 |
| 111 | 1554 97 | 343 67 |
| 112 | 1564 71 | 345 93 |
| 113 | 1574 43 | 348 28 |
| 114 | 1584 13 | 350 72 |
| 115 | 1593 81 | 353 24 |
| 115 | 1603 46 | 355 84 |
| 117 | 1613 09 | 358 53 |
| 118 | 1622 70 | 361 31 |
| 119 | 1632 28 | 364 17 |
| 120 | 1641 84 | 367 11 |
| 121 | 1651 37 | 370 14 |
| 122 | 1660 87 | 373 26 |
| 123 | 1670 35 | 376 45 |
| 124 | 1679 79 | 379 73 |
| 125 | 1689 21 | 383 10 |
| 126 | 1698 60 | 386 55 |
| 127 | 1707 95 | 390 08 |
| 128 | 1717 28 | 393 69 |
| 129 | 1726 57 | 397 38 |
| 130 | 1735 83 | 401 16 |
| 131 | 1745 05 | 405 02 |
| 132 | 1754 25 | 408 96 |
| 133 | 1763 40 | 412 98 |
| 134 | 1772 52 | 417 08 |
| 135 | 1781 61 | 421 26 |
| 136 | 1790 65 | 425 52 |
| 137 | 1799 66 | 429 86 |
| 138 | 1808 63 | 434 28 |
| 139 | 1817 56 | 438 78 |
| 140 | 1826 45 | 443 36 |
| 141 | 1836 30 | 448 02 |
| 142 | 1844 11 | 452 75 |
| 143 | 1852 88 | 457 56 |
| 144 | 1861 60 | 452 45 |
| 145 | 1870 28 | 467 42 |
| 146 | 1878 91 | 472 46 |
| 147 | 1887 51 | 477 58 |
| 148 | 1896 05 | 482 78 |
| 149 | 1904 55 | 488 05 |
| 150 | 1913 00 | 493 39 |
| 151 | 1921 41 | 498 81 |
| 152 | 1929 75 | 504 30 |
| 153 | 1938 07 | 509 87 |
| 154 | 1946 33 | 515 51 |
| 155 | 1954 53 | 521 22 |
| 156 | 1962 69 | 527 01 |
| 157 | 1970 80 | 532 86 |
| 158 | 1978 85 | 538 79 |
| 159 | 1986 85 | 544 79 |
| 160 | 1994 80 | 550 86 |
| 161 | 2002 69 | 557 00 |
| 162 | 2010 53 | 563 21 |

46/130

| | | |
|-----|---------|--------|
| 153 | 2018 32 | 569 49 |
| 164 | 2026 04 | 575 83 |
| 165 | 2033 72 | 582 25 |
| 166 | 2041 33 | 588 73 |
| 167 | 2048 89 | 595 28 |
| 168 | 2056 39 | 601 89 |
| 169 | 2063 83 | 608 57 |
| 170 | 2071 21 | 615 32 |
| 171 | 2078 53 | 622 13 |
| 172 | 2085 79 | 529 01 |
| 173 | 2092 99 | 535 95 |
| 174 | 2100 13 | 542 95 |
| 175 | 2107 21 | 650 02 |
| 176 | 2114 22 | 557 14 |
| 177 | 2121 17 | 664 33 |
| 178 | 2126 55 | 670 00 |

Circle Center At X = 1303 6 , Y = 1447 7 and Radius, 1132 3
 *** 1 052 ***

Failure Surface Specified By 185 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 601 25 | 618 18 |
| 2 | 608 54 | 611 34 |
| 3 | 615 89 | 604 56 |
| 4 | 623 30 | 597 85 |
| 5 | 630 77 | 591 20 |
| 6 | 638 30 | 584 61 |
| 7 | 645 88 | 578 09 |
| 8 | 653 51 | 571 63 |
| 9 | 661 20 | 565 24 |
| 10 | 668 95 | 558 92 |
| 11 | 676 75 | 552 66 |
| 12 | 684 61 | 546 47 |
| 13 | 592 51 | 540 35 |
| 14 | 700 47 | 534 29 |
| 15 | 708 48 | 528 31 |
| 16 | 716 55 | 522 39 |
| 17 | 724 65 | 516 55 |
| 18 | 732 82 | 510 77 |
| 19 | 741 04 | 505 07 |
| 20 | 749 30 | 499 43 |
| 21 | 757 61 | 493 87 |
| 22 | 765 97 | 488 38 |
| 23 | 774 37 | 482 96 |
| 24 | 782 82 | 477 61 |
| 25 | 791 32 | 472 34 |
| 26 | 799 86 | 467 14 |
| 27 | 808 44 | 462 01 |
| 28 | 817 07 | 456 96 |
| 29 | 825 75 | 451 98 |
| 30 | 834 46 | 447 08 |
| 31 | 843 22 | 442 25 |
| 32 | 852 02 | 437 50 |
| 33 | 860 86 | 432 82 |
| 34 | 869 74 | 428 22 |
| 35 | 878 66 | 423 70 |
| 36 | 887 61 | 419 25 |
| 37 | 896 61 | 414 88 |
| 38 | 905 64 | 410 59 |
| 39 | 914 71 | 406 38 |
| 40 | 923 81 | 402 24 |
| 41 | 932 95 | 398 19 |
| 42 | 942 13 | 394 21 |
| 43 | 951 34 | 390 31 |
| 44 | 960 58 | 386 49 |
| 45 | 969 85 | 382 75 |
| 46 | 979 16 | 379 09 |
| 47 | 988 50 | 375 51 |

| | | |
|-----|---------|--------|
| 48 | 997 86 | 372 01 |
| 49 | 1007 26 | 368 59 |
| 50 | 1016 69 | 365 26 |
| 51 | 1026 14 | 362 00 |
| 52 | 1035 63 | 358 83 |
| 53 | 1045 14 | 355 73 |
| 54 | 1054 67 | 352 72 |
| 55 | 1064 23 | 349 79 |
| 56 | 1073 82 | 346 95 |
| 57 | 1083 43 | 344 18 |
| 58 | 1093 07 | 341 50 |
| 59 | 1102 72 | 338 91 |
| 60 | 1112 40 | 336 39 |
| 51 | 1122 10 | 333 96 |
| 62 | 1131 82 | 331 61 |
| 63 | 1141 56 | 329 35 |
| 64 | 1151 32 | 327 17 |
| 65 | 1161 10 | 325 03 |
| 66 | 1170 90 | 323 06 |
| 67 | 1180 71 | 321 14 |
| 68 | 1190 54 | 319 30 |
| 69 | 1200 38 | 317 54 |
| 70 | 1210 24 | 315 87 |
| 71 | 1220 11 | 314 28 |
| 72 | 1230 00 | 312 78 |
| 73 | 1239 90 | 311 36 |
| 74 | 1249 81 | 310 03 |
| 75 | 1259 73 | 308 78 |
| 76 | 1269 66 | 307 62 |
| 77 | 1279 61 | 306 54 |
| 78 | 1289 56 | 305 55 |
| 79 | 1299 52 | 304 65 |
| 80 | 1309 48 | 303 83 |
| 81 | 1319 46 | 303 10 |
| 82 | 1329 43 | 302 45 |
| 83 | 1339 42 | 301 89 |
| 84 | 1349 41 | 301 41 |
| 85 | 1359 40 | 301 02 |
| 86 | 1369 40 | 300 72 |
| 87 | 1379 39 | 300 50 |
| 88 | 1389 39 | 300 37 |
| 89 | 1399 39 | 300 33 |
| 90 | 1409 39 | 300 37 |
| 91 | 1419 39 | 300 50 |
| 92 | 1429 39 | 300 71 |
| 93 | 1439 38 | 301 01 |
| 94 | 1449 38 | 301 40 |
| 95 | 1459 37 | 301 87 |
| 96 | 1469 35 | 302 43 |
| 97 | 1479 33 | 303 07 |
| 98 | 1489 30 | 303 80 |
| 99 | 1499 27 | 304 61 |
| 100 | 1509 23 | 305 52 |
| 101 | 1519 18 | 306 50 |
| 102 | 1529 12 | 307 58 |
| 103 | 1539 06 | 308 73 |
| 104 | 1548 98 | 309 98 |
| 105 | 1558 89 | 311 31 |
| 106 | 1568 79 | 312 72 |
| 107 | 1578 68 | 314 22 |
| 108 | 1588 55 | 315 80 |
| 109 | 1598 41 | 317 47 |
| 110 | 1608 25 | 319 23 |
| 111 | 1618 08 | 321 07 |
| 112 | 1627 90 | 322 99 |
| 113 | 1637 69 | 325 00 |
| 114 | 1647 47 | 327 09 |
| 115 | 1657 23 | 329 27 |

| | | | | |
|-----|------|----|-----|----|
| 116 | 1666 | 97 | 331 | 53 |
| 117 | 1576 | 69 | 333 | 87 |
| 118 | 1686 | 40 | 336 | 30 |
| 119 | 1696 | 07 | 338 | 81 |
| 120 | 1705 | 73 | 341 | 40 |
| 121 | 1715 | 37 | 344 | 08 |
| 122 | 1724 | 98 | 346 | 84 |
| 123 | 1734 | 57 | 349 | 68 |
| 124 | 1744 | 13 | 352 | 61 |
| 125 | 1753 | 67 | 355 | 62 |
| 125 | 1763 | 18 | 358 | 71 |
| 127 | 1772 | 66 | 361 | 88 |
| 128 | 1782 | 12 | 365 | 13 |
| 129 | 1791 | 54 | 368 | 46 |
| 130 | 1800 | 94 | 371 | 88 |
| 131 | 1810 | 31 | 375 | 38 |
| 132 | 1819 | 65 | 378 | 95 |
| 133 | 1828 | 96 | 382 | 61 |
| 134 | 1838 | 23 | 386 | 35 |
| 135 | 1847 | 48 | 390 | 15 |
| 136 | 1856 | 69 | 394 | 06 |
| 137 | 1865 | 86 | 398 | 03 |
| 138 | 1875 | 00 | 402 | 09 |
| 139 | 1884 | 11 | 406 | 22 |
| 140 | 1893 | 18 | 410 | 43 |
| 141 | 1902 | 21 | 414 | 72 |
| 142 | 1911 | 21 | 419 | 08 |
| 143 | 1920 | 17 | 423 | 53 |
| 144 | 1929 | 09 | 428 | 05 |
| 145 | 1937 | 97 | 432 | 65 |
| 146 | 1946 | 81 | 437 | 32 |
| 147 | 1955 | 61 | 442 | 07 |
| 148 | 1964 | 37 | 446 | 89 |
| 149 | 1973 | 09 | 451 | 79 |
| 150 | 1981 | 76 | 456 | 77 |
| 151 | 1990 | 39 | 461 | 82 |
| 152 | 1998 | 98 | 466 | 94 |
| 153 | 2007 | 52 | 472 | 14 |
| 154 | 2016 | 02 | 477 | 41 |
| 155 | 2024 | 47 | 482 | 75 |
| 156 | 2032 | 88 | 488 | 17 |
| 157 | 2041 | 24 | 493 | 66 |
| 158 | 2049 | 55 | 499 | 22 |
| 159 | 2057 | 82 | 504 | 85 |
| 160 | 2066 | 03 | 510 | 55 |
| 161 | 2074 | 20 | 516 | 33 |
| 162 | 2082 | 31 | 522 | 17 |
| 163 | 2090 | 38 | 528 | 08 |
| 164 | 2098 | 39 | 534 | 06 |
| 165 | 2106 | 35 | 540 | 12 |
| 166 | 2114 | 26 | 546 | 23 |
| 167 | 2122 | 12 | 552 | 42 |
| 168 | 2129 | 92 | 558 | 68 |
| 169 | 2137 | 67 | 565 | 00 |
| 170 | 2145 | 36 | 571 | 38 |
| 171 | 2153 | 00 | 577 | 84 |
| 172 | 2160 | 58 | 584 | 36 |
| 173 | 2168 | 11 | 590 | 94 |
| 174 | 2175 | 58 | 597 | 59 |
| 175 | 2182 | 99 | 604 | 30 |
| 176 | 2190 | 34 | 611 | 08 |
| 177 | 2197 | 64 | 617 | 92 |
| 178 | 2204 | 87 | 624 | 82 |
| 179 | 2212 | 05 | 631 | 79 |
| 180 | 2219 | 17 | 638 | 81 |
| 181 | 2226 | 22 | 645 | 90 |
| 182 | 2233 | 22 | 653 | 05 |
| 183 | 2240 | 15 | 650 | 25 |

184 2247 02 667 52
 185 2249 32 670 00
 Circle Center At X = 1399 6 , Y = 1461 8 and Radius, 1161 5
 *** 1 060 ***

Failure Surface Specified By180 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 533 75 | 617 36 |
| 2 | 541 38 | 610 90 |
| 3 | 549 07 | 504 50 |
| 4 | 556 80 | 598 16 |
| 5 | 564 59 | 591 89 |
| 6 | 572 43 | 585 68 |
| 7 | 580 32 | 579 54 |
| 8 | 588 26 | 573 46 |
| 9 | 596 25 | 567 45 |
| 10 | 604 30 | 561 51 |
| 11 | 612 39 | 555 63 |
| 12 | 620 52 | 549 82 |
| 13 | 628 71 | 544 07 |
| 14 | 636 94 | 538 40 |
| 15 | 645 22 | 532 79 |
| 16 | 653 55 | 527 25 |
| 17 | 661 92 | 521 78 |
| 18 | 670 34 | 516 38 |
| 19 | 678 80 | 511 05 |
| 20 | 587 30 | 505 79 |
| 21 | 695 85 | 500 60 |
| 22 | 704 44 | 495 48 |
| 23 | 713 07 | 490 43 |
| 24 | 721 75 | 485 45 |
| 25 | 730 46 | 480 55 |
| 26 | 739 22 | 475 72 |
| 27 | 748 01 | 470 96 |
| 28 | 756 84 | 466 27 |
| 29 | 765 72 | 461 55 |
| 30 | 774 62 | 457 11 |
| 31 | 783 57 | 452 65 |
| 32 | 792 56 | 448 25 |
| 33 | 801 57 | 443 94 |
| 34 | 810 63 | 439 59 |
| 35 | 819 72 | 435 52 |
| 36 | 828 84 | 431 43 |
| 37 | 838 00 | 427 41 |
| 38 | 847 19 | 423 47 |
| 39 | 856 41 | 419 60 |
| 40 | 865 67 | 415 81 |
| 41 | 874 95 | 412 10 |
| 42 | 884 27 | 408 47 |
| 43 | 893 61 | 404 91 |
| 44 | 902 99 | 401 42 |
| 45 | 912 39 | 398 02 |
| 46 | 921 82 | 394 69 |
| 47 | 931 28 | 391 45 |
| 48 | 940 76 | 388 28 |
| 49 | 950 27 | 385 18 |
| 50 | 959 81 | 382 17 |
| 51 | 969 37 | 379 24 |
| 52 | 978 95 | 376 38 |
| 53 | 988 56 | 373 61 |
| 54 | 998 19 | 370 91 |
| 55 | 1007 84 | 368 30 |
| 56 | 1017 51 | 365 76 |
| 57 | 1027 21 | 363 30 |
| 58 | 1036 92 | 360 93 |
| 59 | 1046 65 | 358 63 |
| 60 | 1056 40 | 356 41 |
| 51 | 1056 17 | 354 28 |

| | | | | |
|-----|------|----|-----|----|
| 62 | 1075 | 96 | 352 | 23 |
| 63 | 1085 | 75 | 350 | 25 |
| 64 | 1095 | 58 | 348 | 35 |
| 65 | 1105 | 42 | 345 | 55 |
| 66 | 1115 | 27 | 344 | 82 |
| 67 | 1125 | 13 | 343 | 17 |
| 68 | 1135 | 01 | 341 | 61 |
| 69 | 1144 | 90 | 340 | 12 |
| 70 | 1154 | 80 | 338 | 72 |
| 71 | 1164 | 71 | 337 | 40 |
| 72 | 1174 | 63 | 336 | 16 |
| 73 | 1184 | 67 | 335 | 00 |
| 74 | 1194 | 51 | 333 | 93 |
| 75 | 1204 | 46 | 332 | 94 |
| 76 | 1214 | 42 | 332 | 03 |
| 77 | 1224 | 38 | 331 | 20 |
| 78 | 1234 | 36 | 330 | 45 |
| 79 | 1244 | 33 | 329 | 79 |
| 80 | 1254 | 32 | 329 | 21 |
| 81 | 1264 | 30 | 328 | 71 |
| 82 | 1274 | 30 | 328 | 29 |
| 83 | 1284 | 29 | 327 | 96 |
| 84 | 1294 | 29 | 327 | 71 |
| 85 | 1304 | 29 | 327 | 54 |
| 86 | 1314 | 28 | 327 | 46 |
| 87 | 1324 | 28 | 327 | 46 |
| 88 | 1334 | 28 | 327 | 54 |
| 89 | 1344 | 28 | 327 | 70 |
| 90 | 1354 | 28 | 327 | 94 |
| 91 | 1364 | 27 | 328 | 27 |
| 92 | 1374 | 27 | 328 | 68 |
| 93 | 1384 | 25 | 329 | 18 |
| 94 | 1394 | 24 | 329 | 75 |
| 95 | 1404 | 22 | 330 | 41 |
| 96 | 1414 | 19 | 331 | 15 |
| 97 | 1424 | 15 | 331 | 97 |
| 98 | 1434 | 11 | 332 | 88 |
| 99 | 1444 | 06 | 333 | 87 |
| 100 | 1454 | 01 | 334 | 94 |
| 101 | 1463 | 94 | 336 | 09 |
| 102 | 1473 | 86 | 337 | 32 |
| 103 | 1483 | 78 | 338 | 64 |
| 104 | 1493 | 68 | 340 | 04 |
| 105 | 1503 | 57 | 341 | 52 |
| 106 | 1513 | 45 | 343 | 08 |
| 107 | 1523 | 31 | 344 | 72 |
| 108 | 1533 | 16 | 346 | 44 |
| 109 | 1543 | 00 | 348 | 25 |
| 110 | 1552 | 82 | 350 | 14 |
| 111 | 1562 | 62 | 352 | 10 |
| 112 | 1572 | 41 | 354 | 15 |
| 113 | 1582 | 18 | 356 | 28 |
| 114 | 1591 | 93 | 358 | 49 |
| 115 | 1601 | 67 | 360 | 78 |
| 116 | 1611 | 38 | 353 | 16 |
| 117 | 1621 | 08 | 365 | 61 |
| 118 | 1630 | 75 | 368 | 14 |
| 119 | 1640 | 40 | 370 | 75 |
| 120 | 1650 | 03 | 373 | 44 |
| 121 | 1659 | 64 | 376 | 21 |
| 122 | 1669 | 23 | 379 | 06 |
| 123 | 1678 | 79 | 381 | 99 |
| 124 | 1688 | 33 | 385 | 00 |
| 125 | 1697 | 84 | 388 | 09 |
| 126 | 1707 | 32 | 391 | 25 |
| 127 | 1716 | 78 | 394 | 50 |
| 128 | 1726 | 21 | 397 | 82 |
| 129 | 1735 | 62 | 401 | 22 |

5/130

| | | |
|-----|---------|--------|
| 130 | 1745 00 | 404 69 |
| 131 | 1754 34 | 408 25 |
| 132 | 1763 65 | 411 88 |
| 133 | 1772 95 | 415 59 |
| 134 | 1782 20 | 419 37 |
| 135 | 1791 43 | 423 23 |
| 136 | 1800 62 | 427 17 |
| 137 | 1809 78 | 431 19 |
| 138 | 1818 90 | 435 27 |
| 139 | 1828 00 | 439 44 |
| 140 | 1837 05 | 443 68 |
| 141 | 1846 07 | 447 99 |
| 142 | 1855 06 | 452 38 |
| 143 | 1864 01 | 455 84 |
| 144 | 1872 92 | 461 38 |
| 145 | 1881 80 | 465 99 |
| 146 | 1890 63 | 470 67 |
| 147 | 1899 43 | 475 43 |
| 148 | 1908 18 | 480 25 |
| 149 | 1916 90 | 485 16 |
| 150 | 1925 58 | 490 13 |
| 151 | 1934 21 | 495 17 |
| 152 | 1942 81 | 500 29 |
| 153 | 1951 35 | 505 47 |
| 154 | 1959 86 | 510 73 |
| 155 | 1968 33 | 516 05 |
| 156 | 1976 75 | 521 45 |
| 157 | 1985 12 | 526 92 |
| 158 | 1993 45 | 532 45 |
| 159 | 2001 73 | 538 06 |
| 160 | 2009 97 | 543 73 |
| 161 | 2018 16 | 549 47 |
| 162 | 2025 30 | 555 27 |
| 163 | 2034 39 | 561 15 |
| 164 | 2042 43 | 567 09 |
| 165 | 2050 43 | 573 10 |
| 166 | 2058 37 | 579 17 |
| 167 | 2066 27 | 585 31 |
| 168 | 2074 11 | 591 51 |
| 169 | 2081 90 | 597 78 |
| 170 | 2089 64 | 604 11 |
| 171 | 2097 33 | 610 51 |
| 172 | 2104 96 | 616 97 |
| 173 | 2112 54 | 623 49 |
| 174 | 2120 07 | 630 07 |
| 175 | 2127 54 | 636 72 |
| 176 | 2134 96 | 643 43 |
| 177 | 2142 32 | 650 20 |
| 178 | 2149 62 | 657 03 |
| 179 | 2156 87 | 663 92 |
| 180 | 2163 17 | 670 00 |

Circle Center At X = 1319 6 , Y = 1537 4 and Radius, 1210 0
*** 1 068 ***

Failure Surface Specified By 181 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 623 75 | 618 46 |
| 2 | 630 82 | 511 39 |
| 3 | 637 96 | 604 39 |
| 4 | 546 16 | 597 45 |
| 5 | 652 43 | 590 58 |
| 6 | 659 76 | 583 77 |
| 7 | 667 15 | 577 03 |
| 8 | 674 60 | 570 36 |
| 9 | 682 11 | 563 76 |
| 10 | 689 68 | 557 23 |
| 11 | 697 31 | 550 77 |
| 12 | 705 00 | 544 38 |

| | | |
|----|---------|--------|
| 13 | 712 75 | 538 05 |
| 14 | 720 55 | 531 80 |
| 15 | 728 42 | 526 63 |
| 16 | 735 34 | 519 52 |
| 17 | 744 31 | 513 49 |
| 18 | 752 34 | 507 53 |
| 19 | 760 43 | 501 64 |
| 20 | 768 56 | 495 83 |
| 21 | 776 75 | 490 09 |
| 22 | 785 00 | 484 43 |
| 23 | 793 29 | 478 84 |
| 24 | 801 64 | 473 33 |
| 25 | 810 03 | 467 90 |
| 26 | 818 48 | 462 54 |
| 27 | 826 97 | 457 26 |
| 28 | 835 51 | 452 06 |
| 29 | 844 10 | 446 94 |
| 30 | 852 73 | 441 90 |
| 31 | 861 41 | 436 93 |
| 32 | 870 14 | 432 05 |
| 33 | 878 91 | 427 24 |
| 34 | 887 72 | 422 52 |
| 35 | 896 58 | 417 88 |
| 36 | 905 48 | 413 31 |
| 37 | 914 42 | 408 83 |
| 38 | 923 40 | 404 44 |
| 39 | 932 42 | 400 12 |
| 40 | 941 48 | 395 89 |
| 41 | 950 58 | 391 74 |
| 42 | 959 72 | 387 67 |
| 43 | 968 89 | 383 69 |
| 44 | 978 10 | 379 79 |
| 45 | 987 34 | 375 98 |
| 46 | 996 62 | 372 25 |
| 47 | 1005 93 | 368 61 |
| 48 | 1015 28 | 365 05 |
| 49 | 1024 66 | 361 58 |
| 50 | 1034 07 | 358 19 |
| 51 | 1043 51 | 354 89 |
| 52 | 1052 98 | 351 68 |
| 53 | 1062 48 | 348 55 |
| 54 | 1072 00 | 345 51 |
| 55 | 1081 56 | 342 56 |
| 56 | 1091 14 | 339 70 |
| 57 | 1100 74 | 336 92 |
| 58 | 1110 38 | 334 23 |
| 59 | 1120 03 | 331 63 |
| 60 | 1129 71 | 329 12 |
| 61 | 1139 41 | 326 70 |
| 62 | 1149 14 | 324 36 |
| 63 | 1158 88 | 322 12 |
| 64 | 1158 65 | 319 96 |
| 65 | 1178 43 | 317 90 |
| 66 | 1188 24 | 315 92 |
| 67 | 1198 06 | 314 04 |
| 68 | 1207 89 | 312 24 |
| 69 | 1217 75 | 310 63 |
| 70 | 1227 62 | 308 92 |
| 71 | 1237 50 | 307 39 |
| 72 | 1247 39 | 305 96 |
| 73 | 1257 30 | 304 61 |
| 74 | 1267 23 | 303 36 |
| 75 | 1277 16 | 302 20 |
| 76 | 1287 10 | 301 13 |
| 77 | 1297 05 | 300 15 |
| 78 | 1307 01 | 299 26 |
| 79 | 1316 98 | 298 46 |
| 80 | 1325 96 | 297 75 |

| | | |
|-----|---------|--------|
| 81 | 1336 94 | 297 14 |
| 82 | 1345 92 | 296 62 |
| 83 | 1356 91 | 296 18 |
| 84 | 1366 91 | 295 84 |
| 85 | 1376 90 | 295 59 |
| 86 | 1386 90 | 295 44 |
| 87 | 1396 90 | 295 37 |
| 88 | 1406 90 | 295 40 |
| 89 | 1416 90 | 295 51 |
| 90 | 1426 90 | 295 72 |
| 91 | 1436 90 | 296 02 |
| 92 | 1446 89 | 296 42 |
| 93 | 1456 88 | 295 90 |
| 94 | 1466 86 | 297 47 |
| 95 | 1476 84 | 298 14 |
| 96 | 1486 81 | 298 90 |
| 97 | 1496 77 | 299 75 |
| 98 | 1506 73 | 300 69 |
| 99 | 1516 68 | 301 72 |
| 100 | 1526 61 | 302 84 |
| 101 | 1636 54 | 304 05 |
| 102 | 1546 45 | 305 36 |
| 103 | 1556 35 | 306 75 |
| 104 | 1566 24 | 308 24 |
| 105 | 1576 12 | 309 82 |
| 106 | 1585 98 | 311 48 |
| 107 | 1595 82 | 313 24 |
| 108 | 1605 65 | 315 09 |
| 109 | 1615 46 | 317 02 |
| 110 | 1625 25 | 319 05 |
| 111 | 1635 03 | 321 16 |
| 112 | 1644 78 | 323 37 |
| 113 | 1654 52 | 325 67 |
| 114 | 1664 23 | 328 05 |
| 115 | 1673 92 | 330 52 |
| 116 | 1683 58 | 333 08 |
| 117 | 1693 23 | 335 73 |
| 118 | 1702 84 | 338 47 |
| 119 | 1712 44 | 341 30 |
| 120 | 1722 00 | 344 21 |
| 121 | 1731 54 | 347 21 |
| 122 | 1741 05 | 350 30 |
| 123 | 1750 53 | 353 48 |
| 124 | 1759 99 | 356 74 |
| 125 | 1769 41 | 360 09 |
| 126 | 1778 80 | 363 52 |
| 127 | 1788 16 | 367 04 |
| 128 | 1797 49 | 370 65 |
| 129 | 1806 78 | 374 34 |
| 130 | 1816 04 | 378 11 |
| 131 | 1825 27 | 381 98 |
| 132 | 1834 46 | 385 92 |
| 133 | 1843 61 | 389 95 |
| 134 | 1852 72 | 394 06 |
| 135 | 1861 80 | 398 26 |
| 136 | 1870 84 | 402 54 |
| 137 | 1879 84 | 406 90 |
| 138 | 1888 79 | 411 34 |
| 139 | 1897 71 | 415 87 |
| 140 | 1906 59 | 420 48 |
| 141 | 1915 42 | 425 17 |
| 142 | 1924 21 | 429 94 |
| 143 | 1932 95 | 434 79 |
| 144 | 1941 66 | 439 71 |
| 145 | 1950 31 | 444 72 |
| 146 | 1958 92 | 449 81 |
| 147 | 1967 48 | 454 98 |
| 148 | 1976 00 | 460 22 |

| | | |
|-----|---------|--------|
| 149 | 1984 46 | 465 55 |
| 150 | 1992 88 | 470 95 |
| 151 | 2001 25 | 476 42 |
| 152 | 2009 56 | 481 97 |
| 153 | 2017 83 | 487 60 |
| 154 | 2025 04 | 493 31 |
| 155 | 2034 20 | 499 09 |
| 155 | 2042 31 | 504 94 |
| 157 | 2050 35 | 510 87 |
| 158 | 2058 36 | 516 87 |
| 159 | 2066 30 | 522 95 |
| 150 | 2074 19 | 629 09 |
| 161 | 2082 02 | 535 31 |
| 162 | 2089 80 | 541 50 |
| 163 | 2097 51 | 547 96 |
| 164 | 2105 17 | 554 39 |
| 165 | 2112 77 | 560 90 |
| 166 | 2120 31 | 567 47 |
| 167 | 2127 78 | 574 11 |
| 168 | 2135 20 | 580 81 |
| 169 | 2142 66 | 587 59 |
| 170 | 2149 85 | 594 43 |
| 171 | 2157 08 | 601 34 |
| 172 | 2164 24 | 608 32 |
| 173 | 2171 34 | 615 36 |
| 174 | 2178 38 | 622 46 |
| 175 | 2185 35 | 629 63 |
| 176 | 2192 26 | 536 86 |
| 177 | 2199 10 | 644 16 |
| 178 | 2205 87 | 651 52 |
| 179 | 2212 57 | 658 94 |
| 180 | 2219 21 | 666 42 |
| 181 | 2222 33 | 670 00 |

Circle Center At X = 1399 1 , Y = 1387 2 and Radius, 1091 9
 *** 1 074 ***

Failure Surface Specified By 167 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 533 76 | 617 36 |
| 2 | 540 98 | 610 45 |
| 3 | 548 27 | 603 61 |
| 4 | 655 63 | 596 84 |
| 5 | 563 06 | 590 14 |
| 6 | 570 55 | 583 51 |
| 7 | 578 10 | 576 96 |
| 8 | 685 71 | 570 48 |
| 9 | 593 39 | 564 07 |
| 10 | 601 13 | 557 74 |
| 11 | 608 94 | 551 48 |
| 12 | 616 80 | 545 30 |
| 13 | 624 72 | 539 20 |
| 14 | 632 70 | 533 17 |
| 15 | 640 74 | 527 23 |
| 16 | 648 83 | 521 36 |
| 17 | 655 98 | 515 55 |
| 18 | 665 19 | 509 85 |
| 19 | 673 45 | 504 22 |
| 20 | 681 77 | 498 67 |
| 21 | 690 14 | 493 19 |
| 22 | 698 56 | 487 80 |
| 23 | 707 04 | 482 49 |
| 24 | 715 56 | 477 27 |
| 25 | 724 14 | 472 12 |
| 26 | 732 77 | 467 06 |
| 27 | 741 44 | 462 09 |
| 28 | 750 16 | 457 20 |
| 29 | 758 93 | 452 39 |
| 30 | 767 75 | 447 67 |

| | | |
|----|---------|--------|
| 31 | 776 61 | 443 03 |
| 32 | 785 51 | 438 48 |
| 33 | 794 46 | 434 02 |
| 34 | 803 45 | 429 54 |
| 36 | 812 48 | 425 36 |
| 36 | 821 56 | 421 15 |
| 37 | 830 67 | 417 04 |
| 38 | 839 83 | 413 01 |
| 39 | 849 02 | 409 07 |
| 40 | 858 25 | 405 23 |
| 41 | 867 52 | 401 47 |
| 42 | 876 82 | 397 80 |
| 43 | 886 16 | 394 23 |
| 44 | 895 53 | 390 74 |
| 45 | 904 94 | 387 34 |
| 45 | 914 38 | 384 04 |
| 47 | 923 85 | 380 83 |
| 48 | 933 35 | 377 71 |
| 49 | 942 88 | 374 68 |
| 50 | 952 44 | 371 74 |
| 51 | 962 02 | 368 90 |
| 52 | 971 64 | 366 15 |
| 53 | 981 28 | 363 49 |
| 54 | 990 94 | 350 93 |
| 55 | 1000 63 | 358 46 |
| 56 | 1010 35 | 356 08 |
| 57 | 1020 08 | 353 80 |
| 58 | 1029 84 | 351 61 |
| 59 | 1039 62 | 349 62 |
| 60 | 1049 42 | 347 52 |
| 61 | 1059 24 | 345 62 |
| 62 | 1069 07 | 343 82 |
| 63 | 1078 92 | 342 10 |
| 64 | 1088 79 | 340 49 |
| 65 | 1098 68 | 338 97 |
| 66 | 1108 57 | 337 54 |
| 67 | 1118 49 | 336 21 |
| 68 | 1128 41 | 334 98 |
| 69 | 1138 34 | 333 84 |
| 70 | 1148 29 | 332 80 |
| 71 | 1158 25 | 331 86 |
| 72 | 1168 21 | 331 01 |
| 73 | 1178 18 | 330 25 |
| 74 | 1188 16 | 329 61 |
| 75 | 1198 15 | 329 05 |
| 76 | 1208 13 | 328 69 |
| 77 | 1218 13 | 328 23 |
| 78 | 1228 12 | 327 96 |
| 79 | 1238 12 | 327 79 |
| 80 | 1248 12 | 327 72 |
| 81 | 1258 12 | 327 74 |
| 82 | 1258 12 | 327 86 |
| 83 | 1278 12 | 328 08 |
| 84 | 1288 11 | 328 39 |
| 85 | 1298 11 | 328 81 |
| 86 | 1308 09 | 329 31 |
| 87 | 1318 07 | 329 92 |
| 88 | 1328 05 | 330 62 |
| 89 | 1338 02 | 331 42 |
| 90 | 1347 98 | 332 31 |
| 91 | 1357 93 | 333 30 |
| 92 | 1367 87 | 334 39 |
| 93 | 1377 80 | 335 58 |
| 94 | 1387 72 | 336 86 |
| 95 | 1397 62 | 338 23 |
| 96 | 1407 51 | 339 70 |
| 97 | 1417 39 | 341 27 |
| 98 | 1427 26 | 342 93 |

56/30


| | | |
|-----|---------|--------|
| 99 | 1437 09 | 344 69 |
| 100 | 1446 92 | 346 65 |
| 101 | 1456 73 | 348 50 |
| 102 | 1466 52 | 350 64 |
| 103 | 1476 29 | 352 68 |
| 104 | 1486 03 | 354 91 |
| 105 | 1495 76 | 357 24 |
| 106 | 1505 46 | 359 66 |
| 107 | 1515 14 | 362 18 |
| 108 | 1524 79 | 364 79 |
| 109 | 1534 42 | 367 49 |
| 110 | 1544 02 | 370 29 |
| 111 | 1553 60 | 373 18 |
| 112 | 1563 14 | 376 15 |
| 113 | 1572 66 | 379 23 |
| 114 | 1582 14 | 382 40 |
| 115 | 1591 60 | 386 66 |
| 116 | 1601 02 | 389 00 |
| 117 | 1610 41 | 392 44 |
| 118 | 1619 77 | 395 98 |
| 119 | 1629 09 | 399 60 |
| 120 | 1638 37 | 403 31 |
| 121 | 1647 62 | 407 11 |
| 122 | 1656 83 | 411 00 |
| 123 | 1665 01 | 414 98 |
| 124 | 1675 14 | 419 05 |
| 125 | 1684 24 | 423 21 |
| 125 | 1693 29 | 427 45 |
| 127 | 1702 30 | 431 79 |
| 128 | 1711 27 | 436 21 |
| 129 | 1720 20 | 440 71 |
| 130 | 1729 08 | 445 30 |
| 131 | 1737 92 | 449 98 |
| 132 | 1746 71 | 454 75 |
| 133 | 1755 46 | 459 60 |
| 134 | 1764 16 | 464 53 |
| 135 | 1772 81 | 469 55 |
| 136 | 1781 41 | 474 55 |
| 137 | 1789 96 | 479 83 |
| 138 | 1798 46 | 485 10 |
| 139 | 1806 91 | 490 45 |
| 140 | 1815 31 | 495 88 |
| 141 | 1823 65 | 501 39 |
| 142 | 1831 94 | 506 98 |
| 143 | 1840 18 | 512 65 |
| 144 | 1848 36 | 518 41 |
| 145 | 1856 48 | 524 24 |
| 146 | 1864 55 | 530 15 |
| 147 | 1872 56 | 536 13 |
| 148 | 1880 51 | 542 20 |
| 149 | 1888 40 | 548 34 |
| 150 | 1896 23 | 554 56 |
| 151 | 1904 01 | 550 85 |
| 152 | 1911 72 | 567 22 |
| 153 | 1919 36 | 573 66 |
| 154 | 1926 95 | 580 18 |
| 155 | 1934 47 | 586 77 |
| 156 | 1941 93 | 593 43 |
| 157 | 1949 32 | 600 16 |
| 158 | 1956 65 | 606 97 |
| 159 | 1963 91 | 613 84 |
| 160 | 1971 10 | 620 79 |
| 161 | 1978 23 | 627 80 |
| 162 | 1985 29 | 634 89 |
| 163 | 1992 28 | 642 04 |
| 164 | 1999 20 | 649 26 |
| 165 | 2006 05 | 656 55 |
| 166 | 2012 83 | 663 90 |

57/30

167 2018 34 670 00
Circle Center At X = 1250 7 , Y = 1359 8 and Radius, 1032 0
*** 1 080 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\irf\3 pl2 Run By: Greg Shafer, HDR 4/20/2010 02:12PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Piez Surface | Load | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|--------------|----------|----------|
| a | 0.57 | | | | | | | Horz Eqk | 0.200 g< |
| b | 0.58 | | | | | | | | |
| c | 0.58 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | W1 | | |
| d | 0.59 | LSC | 2 | 121.0 | 125.5 | 1500.0 | W1 | | |
| e | 0.59 | SC | 3 | 121.0 | 125.5 | 2000.0 | W1 | | |
| f | 0.59 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | W1 | | |
| g | 0.60 | | | | | | | | |
| h | 0.60 | | | | | | | | |
| i | 0.61 | | | | | | | | |
| j | 0.61 | | | | | | | | |

PCSTABL7 FSmin=0.57

Safety Factors Are Calculated By The Modified Bishop Method

STED



4/28/10

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 02 12PM
Run By Greg Shafer, HDR
Input Data Filename C 3 in
Output Filename C 3 OUT
Unit ENGLISH
Plotted Output Filename C 3 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 550 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param (psf) | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of0 200 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 480 00 ft
and X = 770 00 ft
Each Surface Termlnates Between X = 950 00 ft
and X =2220 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial
Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By183 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 504 17 | 617 00 |
| 2 | 511 29 | 609 98 |
| 3 | 518 48 | 603 03 |
| 4 | 525 73 | 596 14 |
| 5 | 533 04 | 589 32 |
| 6 | 540 41 | 582 56 |
| 7 | 547 84 | 575 87 |
| 8 | 555 33 | 569 24 |

| | | |
|----|---------|--------|
| 9 | 562 88 | 562 69 |
| 10 | 570 49 | 556 20 |
| 11 | 578 16 | 549 78 |
| 12 | 585 88 | 543 43 |
| 13 | 593 57 | 537 15 |
| 14 | 601 50 | 630 93 |
| 15 | 609 39 | 524 79 |
| 16 | 617 34 | 518 72 |
| 17 | 625 34 | 512 72 |
| 18 | 533 40 | 505 80 |
| 19 | 641 50 | 500 94 |
| 20 | 649 66 | 495 16 |
| 21 | 657 87 | 489 45 |
| 22 | 666 13 | 483 82 |
| 23 | 674 45 | 478 26 |
| 24 | 682 81 | 472 77 |
| 25 | 691 22 | 467 36 |
| 26 | 699 68 | 462 03 |
| 27 | 708 18 | 455 77 |
| 28 | 716 73 | 451 59 |
| 29 | 725 33 | 446 48 |
| 30 | 733 98 | 441 45 |
| 31 | 742 67 | 435 50 |
| 32 | 751 40 | 431 63 |
| 33 | 760 17 | 426 84 |
| 34 | 768 99 | 422 12 |
| 35 | 777 85 | 417 49 |
| 36 | 786 75 | 412 93 |
| 37 | 796 70 | 408 45 |
| 38 | 804 68 | 404 06 |
| 39 | 813 70 | 399 74 |
| 40 | 822 76 | 395 51 |
| 41 | 831 86 | 391 35 |
| 42 | 840 99 | 387 28 |
| 43 | 860 16 | 383 29 |
| 44 | 859 37 | 379 39 |
| 45 | 868 60 | 375 56 |
| 46 | 877 88 | 371 82 |
| 47 | 887 19 | 368 16 |
| 48 | 896 53 | 364 59 |
| 49 | 905 90 | 361 10 |
| 50 | 915 30 | 367 69 |
| 51 | 924 73 | 354 37 |
| 52 | 934 19 | 351 13 |
| 53 | 943 68 | 347 98 |
| 54 | 953 20 | 344 91 |
| 55 | 952 74 | 341 93 |
| 55 | 972 32 | 339 04 |
| 57 | 981 91 | 336 23 |
| 58 | 991 53 | 333 50 |
| 59 | 1001 18 | 330 86 |
| 60 | 1010 85 | 328 31 |
| 61 | 1020 54 | 325 85 |
| 62 | 1030 25 | 323 47 |
| 63 | 1039 99 | 321 18 |
| 64 | 1049 74 | 318 98 |
| 65 | 1059 52 | 316 86 |
| 66 | 1069 31 | 314 83 |
| 67 | 1079 12 | 312 89 |
| 68 | 1088 95 | 311 04 |
| 69 | 1098 79 | 309 28 |
| 70 | 1108 65 | 307 50 |
| 71 | 1118 52 | 306 01 |
| 72 | 1128 41 | 304 52 |
| 73 | 1138 31 | 303 11 |
| 74 | 1148 22 | 301 78 |
| 75 | 1158 14 | 300 55 |
| 75 | 1168 08 | 299 41 |

| | | |
|-----|---------|--------|
| 77 | 1178 02 | 298 35 |
| 78 | 1187 98 | 297 39 |
| 79 | 1197 94 | 296 51 |
| 80 | 1207 91 | 295 73 |
| 81 | 1217 88 | 295 03 |
| 82 | 1227 86 | 294 42 |
| 83 | 1237 85 | 293 90 |
| 84 | 1247 84 | 293 48 |
| 85 | 1257 84 | 293 14 |
| 86 | 1267 83 | 292 89 |
| 87 | 1277 83 | 292 73 |
| 88 | 1287 83 | 292 56 |
| 89 | 1297 83 | 292 68 |
| 90 | 1307 83 | 292 79 |
| 91 | 1317 83 | 292 98 |
| 92 | 1327 83 | 293 27 |
| 93 | 1337 82 | 293 65 |
| 94 | 1347 81 | 294 12 |
| 95 | 1357 79 | 294 57 |
| 96 | 1367 77 | 295 32 |
| 97 | 1377 74 | 296 06 |
| 98 | 1387 71 | 296 88 |
| 99 | 1397 57 | 297 79 |
| 100 | 1407 62 | 298 80 |
| 101 | 1417 56 | 299 89 |
| 102 | 1427 49 | 301 07 |
| 103 | 1437 41 | 302 34 |
| 104 | 1447 31 | 303 70 |
| 105 | 1457 21 | 305 15 |
| 106 | 1467 09 | 306 69 |
| 107 | 1476 96 | 308 31 |
| 108 | 1486 81 | 310 03 |
| 109 | 1496 64 | 311 83 |
| 110 | 1506 46 | 313 72 |
| 111 | 1516 27 | 315 70 |
| 112 | 1526 05 | 317 76 |
| 113 | 1535 82 | 319 92 |
| 114 | 1545 56 | 322 16 |
| 115 | 1555 29 | 324 48 |
| 116 | 1564 99 | 325 90 |
| 117 | 1574 67 | 329 40 |
| 118 | 1584 33 | 331 99 |
| 119 | 1593 97 | 334 66 |
| 120 | 1603 58 | 337 43 |
| 121 | 1613 17 | 340 27 |
| 122 | 1622 73 | 343 21 |
| 123 | 1632 26 | 346 23 |
| 124 | 1541 77 | 349 33 |
| 125 | 1651 24 | 352 52 |
| 126 | 1660 69 | 355 79 |
| 127 | 1670 11 | 359 15 |
| 128 | 1679 50 | 362 59 |
| 129 | 1688 86 | 356 12 |
| 130 | 1698 18 | 369 73 |
| 131 | 1707 48 | 373 42 |
| 132 | 1716 73 | 377 20 |
| 133 | 1725 96 | 381 06 |
| 134 | 1735 15 | 385 00 |
| 135 | 1744 30 | 389 03 |
| 136 | 1753 42 | 393 13 |
| 137 | 1762 50 | 397 32 |
| 138 | 1771 55 | 401 59 |
| 139 | 1780 55 | 405 94 |
| 140 | 1789 52 | 410 37 |
| 141 | 1798 44 | 414 88 |
| 142 | 1807 32 | 419 47 |
| 143 | 1816 17 | 424 14 |
| 144 | 1824 97 | 428 89 |

60/130

| | | |
|-----|---------|--------|
| 77 | 1178 02 | 298 35 |
| 78 | 1187 98 | 297 39 |
| 79 | 1197 94 | 296 51 |
| 80 | 1207 91 | 295 73 |
| 81 | 1217 88 | 295 03 |
| 82 | 1227 86 | 294 42 |
| 83 | 1237 85 | 293 90 |
| 84 | 1247 84 | 293 48 |
| 85 | 1257 84 | 293 14 |
| 86 | 1257 83 | 292 89 |
| 87 | 1277 83 | 292 73 |
| 88 | 1287 83 | 292 56 |
| 89 | 1297 83 | 292 68 |
| 90 | 1307 83 | 292 79 |
| 91 | 1317 83 | 292 98 |
| 92 | 1327 83 | 293 27 |
| 93 | 1337 82 | 293 65 |
| 94 | 1347 81 | 294 12 |
| 95 | 1367 79 | 294 67 |
| 96 | 1367 77 | 295 32 |
| 97 | 1377 74 | 296 06 |
| 98 | 1387 71 | 296 88 |
| 99 | 1397 67 | 297 79 |
| 100 | 1407 62 | 298 80 |
| 101 | 1417 56 | 299 89 |
| 102 | 1427 49 | 301 07 |
| 103 | 1437 41 | 302 34 |
| 104 | 1447 31 | 303 70 |
| 105 | 1457 21 | 305 15 |
| 106 | 1467 09 | 306 69 |
| 107 | 1476 96 | 308 31 |
| 108 | 1486 81 | 310 03 |
| 109 | 1496 64 | 311 83 |
| 110 | 1506 46 | 313 72 |
| 111 | 1516 27 | 315 70 |
| 112 | 1526 05 | 317 76 |
| 113 | 1535 82 | 319 92 |
| 114 | 1545 56 | 322 16 |
| 115 | 1565 29 | 324 48 |
| 116 | 1564 99 | 326 90 |
| 117 | 1574 67 | 329 40 |
| 118 | 1584 33 | 331 99 |
| 119 | 1593 97 | 334 66 |
| 120 | 1603 58 | 337 43 |
| 121 | 1613 17 | 340 27 |
| 122 | 1622 73 | 343 21 |
| 123 | 1632 26 | 346 23 |
| 124 | 1641 77 | 349 33 |
| 125 | 1651 24 | 352 52 |
| 126 | 1660 59 | 355 79 |
| 127 | 1670 11 | 359 15 |
| 128 | 1679 50 | 362 59 |
| 129 | 1688 86 | 366 12 |
| 130 | 1698 18 | 359 73 |
| 131 | 1707 48 | 373 42 |
| 132 | 1716 73 | 377 20 |
| 133 | 1725 96 | 381 06 |
| 134 | 1735 15 | 385 00 |
| 135 | 1744 30 | 389 03 |
| 136 | 1753 42 | 393 13 |
| 137 | 1762 50 | 397 32 |
| 138 | 1771 55 | 401 59 |
| 139 | 1780 55 | 405 94 |
| 140 | 1789 52 | 410 37 |
| 141 | 1798 44 | 414 88 |
| 142 | 1807 32 | 419 47 |
| 143 | 1816 17 | 424 14 |
| 144 | 1824 97 | 428 89 |

| | | | | |
|-----|------|----|-----|----|
| 145 | 1833 | 72 | 433 | 72 |
| 146 | 1842 | 44 | 438 | 63 |
| 147 | 1861 | 11 | 443 | 61 |
| 148 | 1859 | 73 | 448 | 57 |
| 149 | 1868 | 31 | 453 | 81 |
| 150 | 1876 | 84 | 459 | 03 |
| 151 | 1885 | 33 | 464 | 32 |
| 152 | 1893 | 77 | 469 | 68 |
| 153 | 1902 | 16 | 475 | 13 |
| 154 | 1910 | 50 | 480 | 66 |
| 155 | 1918 | 79 | 486 | 24 |
| 156 | 1927 | 03 | 491 | 90 |
| 157 | 1935 | 21 | 497 | 64 |
| 158 | 1943 | 35 | 503 | 46 |
| 159 | 1951 | 43 | 509 | 34 |
| 160 | 1959 | 47 | 615 | 30 |
| 161 | 1967 | 44 | 521 | 33 |
| 162 | 1975 | 37 | 527 | 43 |
| 163 | 1983 | 24 | 533 | 50 |
| 164 | 1991 | 05 | 539 | 84 |
| 165 | 1998 | 80 | 546 | 16 |
| 166 | 2006 | 50 | 552 | 54 |
| 167 | 2014 | 15 | 558 | 99 |
| 168 | 2021 | 73 | 565 | 51 |
| 169 | 2029 | 25 | 572 | 09 |
| 170 | 2036 | 72 | 578 | 74 |
| 171 | 2044 | 13 | 585 | 46 |
| 172 | 2051 | 47 | 592 | 25 |
| 173 | 2058 | 75 | 599 | 10 |
| 174 | 2065 | 98 | 606 | 02 |
| 175 | 2073 | 14 | 613 | 00 |
| 176 | 2080 | 24 | 620 | 04 |
| 177 | 2087 | 27 | 627 | 15 |
| 178 | 2094 | 24 | 634 | 32 |
| 179 | 2101 | 15 | 641 | 55 |
| 180 | 2107 | 99 | 648 | 85 |
| 181 | 2114 | 76 | 656 | 20 |
| 182 | 2121 | 47 | 663 | 62 |
| 183 | 2127 | 14 | 670 | 00 |

Circle Center At X = 1290 7 , Y = 1408 4 and Radius, 1115 8
 *** 0 574 ***

Individual data on the 190 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 7 1 | 3062 2 | 0 0 | 0 0 | 0 0 | 0 0 | 612 4 | 0 0 | 0 0 |
| 2 | 7 2 | 9239 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1847 9 | 0 0 | 0 0 |
| 3 | 7 2 | 15457 2 | 0 0 | 0 0 | 0 0 | 0 0 | 3093 4 | 0 0 | 0 0 |
| 4 | 7 3 | 21741 4 | 0 0 | 0 0 | 0 0 | 0 0 | 4348 3 | 0 0 | 0 0 |
| 5 | 7 4 | 28058 9 | 0 0 | 0 0 | 0 0 | 0 0 | 5611 8 | 0 0 | 0 0 |
| 6 | 7 4 | 34416 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6883 2 | 0 0 | 0 0 |
| 7 | 7 6 | 40810 0 | 0 0 | 0 0 | 0 0 | 0 0 | 8162 0 | 0 0 | 0 0 |
| 8 | 7 5 | 47236 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9447 4 | 0 0 | 0 0 |
| 9 | 7 6 | 53592 7 | 0 0 | 0 0 | 0 0 | 0 0 | 10738 5 | 0 0 | 0 0 |
| 10 | 7 7 | 60175 4 | 0 0 | 0 0 | 0 0 | 0 0 | 12035 1 | 0 0 | 0 0 |
| 11 | 7 7 | 66580 7 | 0 0 | 0 0 | 0 0 | 0 0 | 13336 1 | 0 0 | 0 0 |
| 12 | 7 8 | 73205 1 | 0 0 | 0 0 | 0 0 | 0 0 | 14641 0 | 0 0 | 0 0 |
| 13 | 7 8 | 79746 2 | 0 0 | 0 0 | 0 0 | 0 0 | 15949 2 | 0 0 | 0 0 |
| 14 | 7 9 | 86299 5 | 0 0 | 0 0 | 0 0 | 0 0 | 17259 9 | 0 0 | 0 0 |
| 15 | 7 9 | 92861 6 | 0 0 | 0 0 | 0 0 | 0 0 | 18572 3 | 0 0 | 0 0 |
| 16 | 8 0 | 99429 9 | 0 0 | 0 0 | 0 0 | 0 0 | 19886 0 | 0 0 | 0 0 |
| 17 | 8 1 | 106001 1 | 0 0 | 0 0 | 0 0 | 0 0 | 21200 2 | 0 0 | 0 0 |
| 18 | 8 1 | 112571 3 | 0 0 | 0 0 | 0 0 | 0 0 | 22514 3 | 0 0 | 0 0 |
| 19 | 8 2 | 119137 1 | 0 0 | 0 0 | 0 0 | 0 0 | 23827 4 | 0 0 | 0 0 |
| 20 | 8 2 | 125696 2 | 0 0 | 0 0 | 0 0 | 0 0 | 25139 2 | 0 0 | 0 0 |
| 21 | 8 3 | 132243 4 | 0 0 | 0 0 | 0 0 | 0 0 | 26448 7 | 0 0 | 0 0 |
| 22 | 8 3 | 138777 6 | 0 0 | 0 0 | 0 0 | 0 0 | 27755 5 | 0 0 | 0 0 |

| | | | | | | | | | |
|----|------|----------|-----|-----|-----|-----|---------|-----|-----|
| 23 | 8 4 | 145294 5 | 0 0 | 0 0 | 0 0 | 0 0 | 29058 9 | 0 0 | 0 0 |
| 24 | 8 4 | 151791 1 | 0 0 | 0 0 | 0 0 | 0 0 | 30358 2 | 0 0 | 0 0 |
| 25 | 8 6 | 158264 1 | 0 0 | 0 0 | 0 0 | 0 0 | 31652 8 | 0 0 | 0 0 |
| 26 | 8 5 | 164710 5 | 0 0 | 0 0 | 0 0 | 0 0 | 32942 1 | 0 0 | 0 0 |
| 27 | 8 6 | 171127 2 | 0 0 | 0 0 | 0 0 | 0 0 | 34225 4 | 0 0 | 0 0 |
| 28 | 8 5 | 177510 0 | 0 0 | 0 0 | 0 0 | 0 0 | 35502 0 | 0 0 | 0 0 |
| 29 | 8 6 | 183856 9 | 0 0 | 0 0 | 0 0 | 0 0 | 35771 4 | 0 0 | 0 0 |
| 30 | 8 7 | 190154 0 | 0 0 | 0 0 | 0 0 | 0 0 | 38032 8 | 0 0 | 0 0 |
| 31 | 7 3 | 164631 9 | 0 0 | 0 0 | 0 0 | 0 0 | 32926 4 | 0 0 | 0 0 |
| 32 | 1 4 | 29854 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5970 8 | 0 0 | 0 0 |
| 33 | 8 8 | 191469 2 | 0 0 | 0 0 | 0 0 | 0 0 | 38291 8 | 0 0 | 0 0 |
| 34 | 8 8 | 199348 8 | 0 0 | 0 0 | 0 0 | 0 0 | 39869 8 | 0 0 | 0 0 |
| 35 | 8 9 | 207221 0 | 0 0 | 0 0 | 0 0 | 0 0 | 41444 2 | 0 0 | 0 0 |
| 36 | 8 9 | 215071 4 | 0 0 | 0 0 | 0 0 | 0 0 | 43014 3 | 0 0 | 0 0 |
| 37 | 8 9 | 222896 7 | 0 0 | 0 0 | 0 0 | 0 0 | 44579 3 | 0 0 | 0 0 |
| 38 | 9 0 | 230693 5 | 0 0 | 0 0 | 0 0 | 0 0 | 46138 7 | 0 0 | 0 0 |
| 39 | 9 0 | 238460 5 | 0 0 | 0 0 | 0 0 | 0 0 | 47592 1 | 0 0 | 0 0 |
| 40 | 9 1 | 246193 0 | 0 0 | 0 0 | 0 0 | 0 0 | 49238 6 | 0 0 | 0 0 |
| 41 | 7 2 | 201544 0 | 0 0 | 0 0 | 0 0 | 0 0 | 40308 8 | 0 0 | 0 0 |
| 42 | 1 9 | 55799 6 | 0 0 | 0 0 | 0 0 | 0 0 | 11159 9 | 0 0 | 0 0 |
| 43 | 9 1 | 278712 8 | 0 0 | 0 0 | 0 0 | 0 0 | 55742 6 | 0 0 | 0 0 |
| 44 | 9 2 | 286668 3 | 0 0 | 0 0 | 0 0 | 0 0 | 57333 7 | 0 0 | 0 0 |
| 45 | 9 2 | 294572 3 | 0 0 | 0 0 | 0 0 | 0 0 | 58914 5 | 0 0 | 0 0 |
| 46 | 9 2 | 302419 3 | 0 0 | 0 0 | 0 0 | 0 0 | 60483 9 | 0 0 | 0 0 |
| 47 | 1 4 | 46241 5 | 0 0 | 0 0 | 0 0 | 0 0 | 9248 3 | 0 0 | 0 0 |
| 48 | 7 9 | 264560 1 | 0 0 | 0 0 | 0 0 | 0 0 | 52912 0 | 0 0 | 0 0 |
| 49 | 9 3 | 318537 0 | 0 0 | 0 0 | 0 0 | 0 0 | 63727 4 | 0 0 | 0 0 |
| 50 | 9 3 | 326303 8 | 0 0 | 0 0 | 0 0 | 0 0 | 65260 8 | 0 0 | 0 0 |
| 51 | 9 4 | 333903 5 | 0 0 | 0 0 | 0 0 | 0 0 | 66780 7 | 0 0 | 0 0 |
| 52 | 4 1 | 148249 9 | 0 0 | 0 0 | 0 0 | 0 0 | 29650 0 | 0 0 | 0 0 |
| 53 | 5 3 | 193678 7 | 0 0 | 0 0 | 0 0 | 0 0 | 38715 7 | 0 0 | 0 0 |
| 54 | 9 4 | 349693 4 | 0 0 | 0 0 | 0 0 | 0 0 | 69918 7 | 0 0 | 0 0 |
| 55 | 9 5 | 356974 8 | 0 0 | 0 0 | 0 0 | 0 0 | 71395 0 | 0 0 | 0 0 |
| 56 | 9 5 | 364275 1 | 0 0 | 0 0 | 0 0 | 0 0 | 72855 0 | 0 0 | 0 0 |
| 57 | 6 3 | 245928 8 | 0 0 | 0 0 | 0 0 | 0 0 | 49185 8 | 0 0 | 0 0 |
| 58 | 3 2 | 125420 0 | 0 0 | 0 0 | 0 0 | 0 0 | 25084 0 | 0 0 | 0 0 |
| 59 | 9 5 | 376467 4 | 0 0 | 0 0 | 0 0 | 0 0 | 75293 5 | 0 0 | 0 0 |
| 60 | 9 6 | 380908 7 | 0 0 | 0 0 | 0 0 | 0 0 | 76181 7 | 0 0 | 0 0 |
| 61 | 9 6 | 385239 6 | 0 0 | 0 0 | 0 0 | 0 0 | 77047 9 | 0 0 | 0 0 |
| 62 | 9 6 | 389458 5 | 0 0 | 0 0 | 0 0 | 0 0 | 77891 7 | 0 0 | 0 0 |
| 63 | 9 6 | 393558 5 | 0 0 | 0 0 | 0 0 | 0 0 | 78711 7 | 0 0 | 0 0 |
| 64 | 9 7 | 397642 8 | 0 0 | 0 0 | 0 0 | 0 0 | 79508 6 | 0 0 | 0 0 |
| 65 | 9 7 | 401409 7 | 0 0 | 0 0 | 0 0 | 0 0 | 80281 9 | 0 0 | 0 0 |
| 65 | 9 7 | 405155 1 | 0 0 | 0 0 | 0 0 | 0 0 | 81031 0 | 0 0 | 0 0 |
| 67 | 9 7 | 408772 2 | 0 0 | 0 0 | 0 0 | 0 0 | 81754 4 | 0 0 | 0 0 |
| 68 | 9 8 | 412269 8 | 0 0 | 0 0 | 0 0 | 0 0 | 82454 0 | 0 0 | 0 0 |
| 69 | 9 8 | 415643 7 | 0 0 | 0 0 | 0 0 | 0 0 | 83128 7 | 0 0 | 0 0 |
| 70 | 9 8 | 418887 4 | 0 0 | 0 0 | 0 0 | 0 0 | 83777 5 | 0 0 | 0 0 |
| 71 | 9 8 | 422004 8 | 0 0 | 0 0 | 0 0 | 0 0 | 84401 0 | 0 0 | 0 0 |
| 72 | 9 8 | 424989 3 | 0 0 | 0 0 | 0 0 | 0 0 | 84997 9 | 0 0 | 0 0 |
| 73 | 9 8 | 427844 7 | 0 0 | 0 0 | 0 0 | 0 0 | 85568 9 | 0 0 | 0 0 |
| 74 | 9 9 | 430564 7 | 0 0 | 0 0 | 0 0 | 0 0 | 86112 9 | 0 0 | 0 0 |
| 75 | 9 9 | 433153 4 | 0 0 | 0 0 | 0 0 | 0 0 | 86630 7 | 0 0 | 0 0 |
| 76 | 9 9 | 435604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 87120 9 | 0 0 | 0 0 |
| 77 | 9 9 | 437922 0 | 0 0 | 0 0 | 0 0 | 0 0 | 87584 4 | 0 0 | 0 0 |
| 78 | 9 9 | 440099 8 | 0 0 | 0 0 | 0 0 | 0 0 | 88020 0 | 0 0 | 0 0 |
| 79 | 9 9 | 442142 3 | 0 0 | 0 0 | 0 0 | 0 0 | 88428 5 | 0 0 | 0 0 |
| 80 | 9 9 | 444043 3 | 0 0 | 0 0 | 0 0 | 0 0 | 88808 7 | 0 0 | 0 0 |
| 81 | 9 9 | 445807 3 | 0 0 | 0 0 | 0 0 | 0 0 | 89161 5 | 0 0 | 0 0 |
| 82 | 10 0 | 447428 2 | 0 0 | 0 0 | 0 0 | 0 0 | 89485 5 | 0 0 | 0 0 |
| 83 | 10 0 | 448905 2 | 0 0 | 0 0 | 0 0 | 0 0 | 89781 1 | 0 0 | 0 0 |
| 84 | 10 0 | 450243 4 | 0 0 | 0 0 | 0 0 | 0 0 | 90048 7 | 0 0 | 0 0 |
| 86 | 10 0 | 451441 9 | 0 0 | 0 0 | 0 0 | 0 0 | 90288 4 | 0 0 | 0 0 |
| 86 | 10 0 | 452495 1 | 0 0 | 0 0 | 0 0 | 0 0 | 90499 0 | 0 0 | 0 0 |
| 87 | 10 0 | 453402 2 | 0 0 | 0 0 | 0 0 | 0 0 | 90680 4 | 0 0 | 0 0 |
| 88 | 10 0 | 454168 5 | 0 0 | 0 0 | 0 0 | 0 0 | 90833 7 | 0 0 | 0 0 |
| 89 | 10 0 | 454788 1 | 0 0 | 0 0 | 0 0 | 0 0 | 90957 6 | 0 0 | 0 0 |
| 90 | 10 0 | 455250 8 | 0 0 | 0 0 | 0 0 | 0 0 | 91052 2 | 0 0 | 0 0 |

67/130

| | | | | | | | | | |
|-----|-----|----------|-----|-----|-----|-----|---------|-----|-----|
| 159 | 8 3 | 186517 1 | 0 0 | 0 0 | 0 0 | 0 0 | 37303 4 | 0 0 | 0 0 |
| 160 | 8 2 | 179770 3 | 0 0 | 0 0 | 0 0 | 0 0 | 35954 1 | 0 0 | 0 0 |
| 161 | 8 2 | 173003 6 | 0 0 | 0 0 | 0 0 | 0 0 | 34600 7 | 0 0 | 0 0 |
| 162 | 8 1 | 166222 9 | 0 0 | 0 0 | 0 0 | 0 0 | 33244 6 | 0 0 | 0 0 |
| 163 | 8 1 | 159431 1 | 0 0 | 0 0 | 0 0 | 0 0 | 31886 2 | 0 0 | 0 0 |
| 164 | 8 0 | 152629 1 | 0 0 | 0 0 | 0 0 | 0 0 | 30525 8 | 0 0 | 0 0 |
| 165 | 8 0 | 145822 6 | 0 0 | 0 0 | 0 0 | 0 0 | 29164 6 | 0 0 | 0 0 |
| 166 | 7 9 | 139012 5 | 0 0 | 0 0 | 0 0 | 0 0 | 27802 5 | 0 0 | 0 0 |
| 167 | 7 9 | 132206 6 | 0 0 | 0 0 | 0 0 | 0 0 | 26441 3 | 0 0 | 0 0 |
| 168 | 7 8 | 125403 7 | 0 0 | 0 0 | 0 0 | 0 0 | 25080 7 | 0 0 | 0 0 |
| 169 | 7 8 | 118609 4 | 0 0 | 0 0 | 0 0 | 0 0 | 23721 9 | 0 0 | 0 0 |
| 170 | 7 7 | 111827 0 | 0 0 | 0 0 | 0 0 | 0 0 | 22365 4 | 0 0 | 0 0 |
| 171 | 7 6 | 105059 7 | 0 0 | 0 0 | 0 0 | 0 0 | 21011 9 | 0 0 | 0 0 |
| 172 | 7 6 | 98311 1 | 0 0 | 0 0 | 0 0 | 0 0 | 19662 2 | 0 0 | 0 0 |
| 173 | 7 5 | 91584 2 | 0 0 | 0 0 | 0 0 | 0 0 | 18316 8 | 0 0 | 0 0 |
| 174 | 7 5 | 84882 5 | 0 0 | 0 0 | 0 0 | 0 0 | 16976 5 | 0 0 | 0 0 |
| 175 | 7 4 | 78209 5 | 0 0 | 0 0 | 0 0 | 0 0 | 15641 9 | 0 0 | 0 0 |
| 176 | 7 3 | 71558 4 | 0 0 | 0 0 | 0 0 | 0 0 | 14313 7 | 0 0 | 0 0 |
| 177 | 7 3 | 64964 9 | 0 0 | 0 0 | 0 0 | 0 0 | 12993 0 | 0 0 | 0 0 |
| 178 | 7 2 | 58398 2 | 0 0 | 0 0 | 0 0 | 0 0 | 11679 6 | 0 0 | 0 0 |
| 179 | 7 2 | 51874 8 | 0 0 | 0 0 | 0 0 | 0 0 | 10375 0 | 0 0 | 0 0 |
| 180 | 7 1 | 45396 1 | 0 0 | 0 0 | 0 0 | 0 0 | 9079 2 | 0 0 | 0 0 |
| 181 | 7 0 | 38968 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7793 8 | 0 0 | 0 0 |
| 182 | 7 0 | 32592 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6518 4 | 0 0 | 0 0 |
| 183 | 5 4 | 21141 6 | 0 0 | 0 0 | 0 0 | 0 0 | 4228 3 | 0 0 | 0 0 |
| 184 | 1 5 | 5131 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1026 3 | 0 0 | 0 0 |
| 185 | 6 8 | 20013 2 | 0 0 | 0 0 | 0 0 | 0 0 | 4002 6 | 0 0 | 0 0 |
| 186 | 1 1 | 2563 3 | 0 0 | 0 0 | 0 0 | 0 0 | 512 7 | 0 0 | 0 0 |
| 187 | 5 7 | 11253 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2250 8 | 0 0 | 0 0 |
| 188 | 3 4 | 4687 9 | 0 0 | 0 0 | 0 0 | 0 0 | 937 6 | 0 0 | 0 0 |
| 189 | 3 3 | 3043 1 | 0 0 | 0 0 | 0 0 | 0 0 | 608 6 | 0 0 | 0 0 |
| 190 | 5 7 | 2053 1 | 0 0 | 0 0 | 0 0 | 0 0 | 410 6 | 0 0 | 0 0 |

Failure Surface Specified By192 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 480 00 | 616 70 |
| 2 | 487 72 | 510 34 |
| 3 | 496 49 | 604 04 |
| 4 | 503 30 | 597 80 |
| 5 | 511 16 | 591 62 |
| 6 | 519 07 | 585 50 |
| 7 | 527 02 | 579 44 |
| 8 | 535 02 | 573 44 |
| 9 | 543 07 | 567 51 |
| 10 | 561 16 | 561 63 |
| 11 | 559 30 | 555 81 |
| 12 | 567 48 | 550 06 |
| 13 | 575 70 | 544 37 |
| 14 | 583 97 | 638 74 |
| 15 | 692 27 | 533 18 |
| 16 | 600 62 | 627 68 |
| 17 | 609 02 | 622 24 |
| 18 | 617 45 | 516 87 |
| 19 | 625 92 | 511 55 |
| 20 | 634 44 | 506 31 |
| 21 | 642 99 | 501 13 |
| 22 | 651 59 | 496 02 |
| 23 | 660 22 | 490 97 |
| 24 | 658 89 | 485 99 |
| 25 | 677 60 | 481 07 |
| 26 | 686 34 | 476 22 |
| 27 | 695 12 | 471 43 |
| 28 | 703 94 | 466 72 |
| 29 | 712 79 | 462 07 |
| 30 | 721 68 | 457 48 |
| 31 | 730 60 | 452 97 |
| 32 | 739 56 | 448 52 |
| 33 | 748 55 | 444 15 |

6/6/30

| | | |
|-----|---------|--------|
| 34 | 757 58 | 439 84 |
| 35 | 766 63 | 435 60 |
| 36 | 775 72 | 431 42 |
| 37 | 784 84 | 427 32 |
| 38 | 793 99 | 423 29 |
| 39 | 803 17 | 419 32 |
| 40 | 812 38 | 415 43 |
| 41 | 821 62 | 411 61 |
| 42 | 830 89 | 407 86 |
| 43 | 840 19 | 404 17 |
| 44 | 849 51 | 400 55 |
| 45 | 858 87 | 397 02 |
| 46 | 858 25 | 393 55 |
| 47 | 877 65 | 390 16 |
| 48 | 887 08 | 386 83 |
| 49 | 896 54 | 383 58 |
| 50 | 906 02 | 380 40 |
| 51 | 915 52 | 377 29 |
| 52 | 925 06 | 374 25 |
| 53 | 934 60 | 371 28 |
| 54 | 944 17 | 368 39 |
| 55 | 953 77 | 365 57 |
| 56 | 963 38 | 362 83 |
| 57 | 973 02 | 350 16 |
| 58 | 982 68 | 357 56 |
| 59 | 992 35 | 355 03 |
| 60 | 1002 05 | 352 58 |
| 61 | 1011 76 | 350 20 |
| 62 | 1021 49 | 347 90 |
| 63 | 1031 24 | 345 67 |
| 64 | 1041 00 | 343 51 |
| 65 | 1050 78 | 341 43 |
| 66 | 1060 58 | 339 42 |
| 67 | 1070 39 | 337 49 |
| 68 | 1080 22 | 335 63 |
| 69 | 1090 06 | 333 85 |
| 70 | 1099 91 | 332 14 |
| 71 | 1109 78 | 330 51 |
| 72 | 1119 66 | 328 95 |
| 73 | 1129 55 | 327 47 |
| 74 | 1139 45 | 326 06 |
| 75 | 1149 36 | 324 73 |
| 76 | 1159 28 | 323 48 |
| 77 | 1169 21 | 322 30 |
| 78 | 1179 16 | 321 19 |
| 79 | 1189 09 | 320 16 |
| 80 | 1199 05 | 319 21 |
| 81 | 1209 01 | 318 33 |
| 82 | 1218 98 | 317 53 |
| 83 | 1228 95 | 316 80 |
| 84 | 1238 93 | 316 15 |
| 85 | 1248 91 | 315 58 |
| 86 | 1258 90 | 315 08 |
| 87 | 1268 89 | 314 66 |
| 88 | 1278 89 | 314 31 |
| 89 | 1288 88 | 314 04 |
| 90 | 1298 88 | 313 85 |
| 91 | 1308 88 | 313 73 |
| 92 | 1318 88 | 313 69 |
| 93 | 1328 88 | 313 72 |
| 94 | 1338 88 | 313 83 |
| 95 | 1348 88 | 314 02 |
| 96 | 1358 87 | 314 28 |
| 97 | 1368 87 | 314 62 |
| 98 | 1378 86 | 316 03 |
| 99 | 1388 85 | 315 52 |
| 100 | 1398 83 | 315 09 |
| 101 | 1408 81 | 316 73 |

| | | |
|-----|---------|--------|
| 102 | 1418 78 | 317 45 |
| 103 | 1428 75 | 318 24 |
| 104 | 1438 71 | 319 11 |
| 105 | 1448 67 | 320 06 |
| 106 | 1458 62 | 321 08 |
| 107 | 1458 56 | 322 18 |
| 108 | 1478 49 | 323 35 |
| 109 | 1488 41 | 324 60 |
| 110 | 1498 32 | 325 92 |
| 111 | 1508 22 | 327 32 |
| 112 | 1518 11 | 328 80 |
| 113 | 1527 99 | 330 35 |
| 114 | 1537 86 | 331 97 |
| 115 | 1547 72 | 333 67 |
| 116 | 1557 56 | 335 45 |
| 117 | 1567 38 | 337 30 |
| 118 | 1577 20 | 339 22 |
| 119 | 1586 99 | 341 22 |
| 120 | 1596 78 | 343 29 |
| 121 | 1606 54 | 345 44 |
| 122 | 1616 29 | 347 66 |
| 123 | 1626 03 | 349 96 |
| 124 | 1635 74 | 352 33 |
| 125 | 1645 44 | 354 77 |
| 126 | 1655 12 | 357 29 |
| 127 | 1654 77 | 359 88 |
| 128 | 1674 41 | 362 55 |
| 129 | 1684 03 | 365 29 |
| 130 | 1693 63 | 368 10 |
| 131 | 1703 20 | 370 98 |
| 132 | 1712 76 | 373 94 |
| 133 | 1722 29 | 376 97 |
| 134 | 1731 79 | 380 07 |
| 135 | 1741 28 | 383 24 |
| 135 | 1750 73 | 386 49 |
| 137 | 1760 17 | 389 81 |
| 138 | 1769 57 | 393 20 |
| 139 | 1778 96 | 396 66 |
| 140 | 1788 31 | 400 19 |
| 141 | 1797 54 | 403 80 |
| 142 | 1806 94 | 407 47 |
| 143 | 1816 21 | 411 22 |
| 144 | 1825 46 | 415 03 |
| 145 | 1834 67 | 418 92 |
| 146 | 1843 86 | 422 88 |
| 147 | 1853 01 | 426 90 |
| 148 | 1862 13 | 431 00 |
| 149 | 1871 22 | 435 16 |
| 150 | 1880 28 | 439 39 |
| 151 | 1889 31 | 443 70 |
| 152 | 1898 30 | 448 07 |
| 153 | 1907 26 | 452 51 |
| 154 | 1916 19 | 457 02 |
| 155 | 1925 08 | 461 59 |
| 156 | 1933 94 | 466 23 |
| 167 | 1942 76 | 470 94 |
| 158 | 1951 56 | 475 72 |
| 169 | 1960 29 | 480 56 |
| 160 | 1969 01 | 485 47 |
| 161 | 1977 68 | 490 45 |
| 162 | 1986 32 | 496 49 |
| 163 | 1994 91 | 500 60 |
| 164 | 2003 47 | 505 77 |
| 165 | 2011 99 | 511 01 |
| 166 | 2020 47 | 516 31 |
| 167 | 2028 90 | 521 68 |
| 168 | 2037 30 | 527 11 |
| 159 | 2045 66 | 532 61 |

68/130

| | | |
|-----|---------|--------|
| 170 | 2053 97 | 538 17 |
| 171 | 2062 24 | 543 79 |
| 172 | 2070 47 | 549 47 |
| 173 | 2078 65 | 555 22 |
| 174 | 2086 79 | 561 03 |
| 175 | 2094 89 | 566 90 |
| 176 | 2102 94 | 672 83 |
| 177 | 2110 94 | 578 82 |
| 178 | 2118 90 | 584 88 |
| 179 | 2126 82 | 590 99 |
| 180 | 2134 68 | 597 16 |
| 181 | 2142 50 | 603 40 |
| 182 | 2160 27 | 609 59 |
| 183 | 2158 00 | 616 04 |
| 184 | 2165 67 | 622 45 |
| 185 | 2173 30 | 628 92 |
| 186 | 2180 87 | 635 45 |
| 187 | 2188 40 | 542 03 |
| 188 | 2195 88 | 648 67 |
| 189 | 2203 30 | 655 37 |
| 190 | 2210 68 | 662 13 |
| 191 | 2218 00 | 668 94 |
| 192 | 2219 12 | 670 00 |

Circle Center At X = 1319 4 , Y = 1627 8 and Radius, 1314 1
*** 0 576 ***

Failure Surface Specified By183 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 516 25 | 617 14 |
| 2 | 523 44 | 610 20 |
| 3 | 530 69 | 603 31 |
| 4 | 538 00 | 596 49 |
| 5 | 546 38 | 589 73 |
| 6 | 552 81 | 583 04 |
| 7 | 560 30 | 675 42 |
| 8 | 567 85 | 569 86 |
| 9 | 575 46 | 563 37 |
| 10 | 583 12 | 566 94 |
| 11 | 590 84 | 550 59 |
| 12 | 598 62 | 544 30 |
| 13 | 606 45 | 538 08 |
| 14 | 614 34 | 531 93 |
| 15 | 622 28 | 525 86 |
| 16 | 630 27 | 519 85 |
| 17 | 638 32 | 513 91 |
| 18 | 646 42 | 508 05 |
| 19 | 654 57 | 502 25 |
| 20 | 662 77 | 496 53 |
| 21 | 671 02 | 490 88 |
| 22 | 679 32 | 485 31 |
| 23 | 687 67 | 479 81 |
| 24 | 696 07 | 474 38 |
| 25 | 704 52 | 469 03 |
| 26 | 713 01 | 463 75 |
| 27 | 721 66 | 458 55 |
| 28 | 730 14 | 453 42 |
| 29 | 738 77 | 448 37 |
| 30 | 747 46 | 443 40 |
| 31 | 756 17 | 438 50 |
| 32 | 764 93 | 433 68 |
| 33 | 773 73 | 428 94 |
| 34 | 782 58 | 424 28 |
| 35 | 791 47 | 419 69 |
| 36 | 800 39 | 415 18 |
| 37 | 809 36 | 410 75 |
| 38 | 818 35 | 406 41 |
| 39 | 827 41 | 402 14 |
| 40 | 836 49 | 397 96 |

| | | | | |
|-----|------|----|-----|----|
| 41 | 845 | 51 | 393 | 85 |
| 42 | 854 | 76 | 389 | 82 |
| 43 | 863 | 96 | 385 | 88 |
| 44 | 873 | 17 | 382 | 01 |
| 45 | 882 | 43 | 378 | 23 |
| 46 | 891 | 72 | 374 | 53 |
| 47 | 901 | 04 | 370 | 91 |
| 48 | 910 | 40 | 367 | 38 |
| 49 | 919 | 78 | 363 | 93 |
| 50 | 929 | 20 | 350 | 56 |
| 51 | 938 | 64 | 357 | 28 |
| 52 | 948 | 12 | 354 | 07 |
| 53 | 967 | 62 | 350 | 95 |
| 54 | 967 | 15 | 347 | 92 |
| 55 | 976 | 70 | 344 | 97 |
| 55 | 986 | 29 | 342 | 11 |
| 57 | 995 | 89 | 339 | 33 |
| 58 | 1005 | 52 | 336 | 64 |
| 59 | 1015 | 18 | 334 | 03 |
| 60 | 1024 | 85 | 331 | 51 |
| 61 | 1034 | 55 | 329 | 07 |
| 62 | 1044 | 27 | 326 | 72 |
| 63 | 1064 | 01 | 324 | 45 |
| 64 | 1063 | 77 | 322 | 27 |
| 65 | 1073 | 55 | 320 | 18 |
| 66 | 1083 | 34 | 318 | 17 |
| 67 | 1093 | 16 | 316 | 25 |
| 68 | 1102 | 99 | 314 | 42 |
| 69 | 1112 | 84 | 312 | 68 |
| 70 | 1122 | 70 | 311 | 02 |
| 71 | 1132 | 57 | 309 | 45 |
| 72 | 1142 | 46 | 307 | 97 |
| 73 | 1152 | 36 | 306 | 57 |
| 74 | 1162 | 28 | 305 | 26 |
| 75 | 1172 | 20 | 304 | 04 |
| 76 | 1182 | 14 | 302 | 91 |
| 77 | 1192 | 09 | 301 | 86 |
| 78 | 1202 | 04 | 300 | 91 |
| 79 | 1212 | 00 | 300 | 04 |
| 80 | 1221 | 97 | 299 | 26 |
| 81 | 1231 | 95 | 298 | 57 |
| 82 | 1241 | 93 | 297 | 97 |
| 83 | 1251 | 92 | 297 | 45 |
| 84 | 1261 | 91 | 297 | 02 |
| 85 | 1271 | 90 | 296 | 69 |
| 86 | 1281 | 90 | 296 | 44 |
| 87 | 1291 | 90 | 296 | 28 |
| 88 | 1301 | 90 | 296 | 20 |
| 89 | 1311 | 90 | 296 | 22 |
| 90 | 1321 | 90 | 295 | 32 |
| 91 | 1331 | 89 | 296 | 52 |
| 92 | 1341 | 89 | 296 | 80 |
| 93 | 1351 | 88 | 297 | 17 |
| 94 | 1361 | 87 | 297 | 62 |
| 95 | 1371 | 86 | 298 | 17 |
| 96 | 1381 | 84 | 298 | 81 |
| 97 | 1391 | 81 | 299 | 53 |
| 98 | 1401 | 78 | 300 | 34 |
| 99 | 1411 | 74 | 301 | 24 |
| 100 | 1421 | 69 | 302 | 23 |
| 101 | 1431 | 63 | 303 | 30 |
| 102 | 1441 | 56 | 304 | 47 |
| 103 | 1451 | 48 | 305 | 72 |
| 104 | 1461 | 39 | 307 | 06 |
| 105 | 1471 | 29 | 308 | 48 |
| 106 | 1481 | 18 | 310 | 00 |
| 107 | 1491 | 05 | 311 | 60 |
| 108 | 1600 | 90 | 313 | 29 |

70/120

| | | |
|-----|---------|--------|
| 109 | 1510 74 | 315 07 |
| 110 | 1520 57 | 316 93 |
| 111 | 1530 38 | 318 88 |
| 112 | 1540 17 | 320 92 |
| 113 | 1549 94 | 323 04 |
| 114 | 1559 69 | 325 25 |
| 115 | 1569 43 | 327 55 |
| 116 | 1579 14 | 329 93 |
| 117 | 1588 83 | 332 40 |
| 118 | 1598 50 | 334 95 |
| 119 | 1608 14 | 337 59 |
| 120 | 1517 76 | 340 31 |
| 121 | 1527 36 | 343 12 |
| 122 | 1635 93 | 346 02 |
| 123 | 1646 48 | 349 00 |
| 124 | 1656 00 | 352 06 |
| 125 | 1655 49 | 355 21 |
| 126 | 1674 95 | 358 44 |
| 127 | 1684 39 | 361 75 |
| 128 | 1693 79 | 365 15 |
| 129 | 1703 17 | 368 63 |
| 130 | 1712 51 | 372 20 |
| 131 | 1721 82 | 375 84 |
| 132 | 1731 10 | 379 57 |
| 133 | 1740 35 | 383 38 |
| 134 | 1749 56 | 387 28 |
| 135 | 1758 73 | 391 25 |
| 136 | 1767 88 | 395 30 |
| 137 | 1776 98 | 399 44 |
| 138 | 1785 05 | 403 66 |
| 139 | 1795 08 | 407 95 |
| 140 | 1804 07 | 412 33 |
| 141 | 1813 02 | 416 78 |
| 142 | 1821 94 | 421 32 |
| 143 | 1830 81 | 425 93 |
| 144 | 1839 54 | 430 62 |
| 145 | 1848 43 | 435 39 |
| 146 | 1857 18 | 440 24 |
| 147 | 1865 88 | 445 16 |
| 148 | 1874 54 | 450 17 |
| 149 | 1883 16 | 455 24 |
| 150 | 1891 72 | 450 40 |
| 151 | 1900 25 | 465 63 |
| 152 | 1908 72 | 470 93 |
| 153 | 1917 15 | 476 31 |
| 154 | 1925 54 | 481 75 |
| 155 | 1933 87 | 487 29 |
| 155 | 1942 15 | 492 89 |
| 157 | 1950 39 | 498 57 |
| 158 | 1958 57 | 504 31 |
| 159 | 1966 70 | 510 13 |
| 160 | 1974 78 | 516 02 |
| 161 | 1982 81 | 521 99 |
| 152 | 1990 79 | 528 02 |
| 163 | 1998 71 | 634 12 |
| 164 | 2006 58 | 540 30 |
| 165 | 2014 39 | 546 54 |
| 166 | 2022 16 | 552 85 |
| 167 | 2029 85 | 559 23 |
| 168 | 2037 49 | 565 68 |
| 169 | 2045 08 | 572 19 |
| 170 | 2052 60 | 578 77 |
| 171 | 2050 07 | 585 42 |
| 172 | 2057 49 | 592 14 |
| 173 | 2074 84 | 598 92 |
| 174 | 2082 13 | 605 76 |
| 175 | 2089 36 | 612 67 |
| 175 | 2096 53 | 619 64 |

71/130

177 2103 63 626 68
 178 2110 68 633 77
 179 2117 66 640 93
 180 2124 57 648 16
 181 2131 43 555 44
 182 2138 22 662 78
 183 2144 77 670 00
 Circle Center At X = 1305 1 , Y = 1426 1 and Radius, 1130 0
 *** 0 577 ***

Failure Surface Specified By187 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 504 17 | 617 00 |
| 2 | 511 82 | 610 57 |
| 3 | 519 53 | 604 20 |
| 4 | 527 29 | 597 89 |
| 5 | 535 10 | 591 64 |
| 6 | 542 95 | 685 45 |
| 7 | 550 86 | 579 33 |
| 8 | 558 82 | 573 27 |
| 9 | 566 82 | 567 27 |
| 10 | 574 87 | 561 34 |
| 11 | 582 96 | 566 47 |
| 12 | 591 10 | 549 66 |
| 13 | 599 29 | 643 92 |
| 14 | 607 52 | 538 24 |
| 15 | 615 80 | 532 63 |
| 16 | 624 12 | 527 08 |
| 17 | 632 49 | 521 60 |
| 18 | 640 90 | 516 19 |
| 19 | 649 35 | 510 84 |
| 20 | 657 84 | 505 56 |
| 21 | 665 37 | 500 35 |
| 22 | 674 95 | 495 21 |
| 23 | 683 56 | 490 13 |
| 24 | 592 22 | 485 12 |
| 25 | 700 91 | 480 18 |
| 26 | 709 65 | 475 31 |
| 27 | 718 42 | 470 51 |
| 28 | 727 23 | 465 78 |
| 29 | 736 07 | 461 11 |
| 30 | 744 96 | 456 52 |
| 31 | 753 88 | 452 00 |
| 32 | 762 83 | 447 55 |
| 33 | 771 82 | 443 17 |
| 34 | 780 84 | 438 86 |
| 35 | 789 90 | 434 62 |
| 35 | 798 99 | 430 45 |
| 37 | 808 12 | 426 36 |
| 38 | 817 27 | 422 34 |
| 39 | 826 46 | 418 39 |
| 40 | 835 68 | 414 51 |
| 41 | 844 93 | 410 71 |
| 42 | 854 20 | 406 98 |
| 43 | 863 51 | 403 32 |
| 44 | 872 85 | 399 74 |
| 45 | 882 21 | 396 23 |
| 46 | 891 60 | 392 79 |
| 47 | 901 02 | 389 43 |
| 48 | 910 47 | 386 16 |
| 49 | 919 94 | 382 94 |
| 50 | 929 43 | 379 80 |
| 51 | 938 95 | 376 74 |
| 62 | 948 50 | 373 75 |
| 53 | 958 06 | 370 84 |
| 64 | 967 65 | 368 01 |
| 55 | 977 26 | 365 25 |
| 56 | 985 90 | 362 57 |

| | | |
|-----|---------|--------|
| 67 | 996 55 | 359 96 |
| 58 | 1006 23 | 357 43 |
| 69 | 1015 92 | 354 98 |
| 60 | 1025 64 | 352 60 |
| 61 | 1035 37 | 360 30 |
| 62 | 1045 12 | 348 08 |
| 63 | 1054 88 | 345 94 |
| 64 | 1064 67 | 343 87 |
| 65 | 1074 47 | 341 88 |
| 56 | 1084 28 | 339 97 |
| 67 | 1094 11 | 338 13 |
| 68 | 1103 96 | 336 37 |
| 69 | 1113 82 | 334 59 |
| 70 | 1123 69 | 333 09 |
| 71 | 1133 57 | 331 57 |
| 72 | 1143 47 | 330 12 |
| 73 | 1153 37 | 328 76 |
| 74 | 1153 29 | 327 47 |
| 75 | 1173 21 | 326 26 |
| 76 | 1183 15 | 325 12 |
| 77 | 1193 09 | 324 07 |
| 78 | 1203 05 | 323 10 |
| 79 | 1213 01 | 322 20 |
| 80 | 1222 97 | 321 39 |
| 81 | 1232 95 | 320 65 |
| 82 | 1242 92 | 319 99 |
| 83 | 1252 91 | 319 41 |
| 84 | 1262 90 | 318 91 |
| 85 | 1272 89 | 318 48 |
| 86 | 1282 88 | 318 14 |
| 87 | 1292 88 | 317 88 |
| 88 | 1302 88 | 317 69 |
| 89 | 1312 87 | 317 59 |
| 90 | 1322 87 | 317 56 |
| 91 | 1332 87 | 317 61 |
| 92 | 1342 87 | 317 74 |
| 93 | 1352 87 | 317 95 |
| 94 | 1362 87 | 318 24 |
| 95 | 1372 86 | 318 61 |
| 96 | 1382 86 | 319 06 |
| 97 | 1392 84 | 319 58 |
| 98 | 1402 82 | 320 19 |
| 99 | 1412 79 | 320 87 |
| 100 | 1422 77 | 321 64 |
| 101 | 1432 73 | 322 48 |
| 102 | 1442 69 | 323 40 |
| 103 | 1452 64 | 324 40 |
| 104 | 1462 58 | 325 47 |
| 105 | 1472 51 | 326 63 |
| 106 | 1482 44 | 327 87 |
| 107 | 1492 35 | 329 18 |
| 108 | 1602 25 | 330 57 |
| 109 | 1612 14 | 332 04 |
| 110 | 1522 02 | 333 59 |
| 111 | 1531 89 | 336 22 |
| 112 | 1541 74 | 336 92 |
| 113 | 1551 58 | 338 70 |
| 114 | 1561 41 | 340 55 |
| 115 | 1671 22 | 342 50 |
| 116 | 1581 01 | 344 52 |
| 117 | 1590 79 | 346 61 |
| 118 | 1600 56 | 348 78 |
| 119 | 1610 30 | 351 02 |
| 120 | 1620 02 | 353 35 |
| 121 | 1629 73 | 355 75 |
| 122 | 1639 42 | 368 23 |
| 123 | 1649 09 | 360 78 |
| 124 | 1658 74 | 363 41 |

| | | | | |
|-----|------|----|-----|----|
| 125 | 1568 | 36 | 366 | 12 |
| 126 | 1677 | 97 | 368 | 90 |
| 127 | 1687 | 55 | 371 | 76 |
| 128 | 1697 | 11 | 374 | 69 |
| 129 | 1706 | 65 | 377 | 70 |
| 130 | 1716 | 16 | 380 | 79 |
| 131 | 1725 | 65 | 383 | 95 |
| 132 | 1735 | 11 | 387 | 18 |
| 133 | 1744 | 55 | 390 | 49 |
| 134 | 1753 | 96 | 393 | 87 |
| 135 | 1763 | 34 | 397 | 33 |
| 136 | 1772 | 69 | 400 | 87 |
| 137 | 1782 | 02 | 404 | 47 |
| 138 | 1791 | 32 | 408 | 15 |
| 139 | 1800 | 59 | 411 | 91 |
| 140 | 1809 | 83 | 415 | 73 |
| 141 | 1819 | 04 | 419 | 63 |
| 142 | 1828 | 21 | 423 | 60 |
| 143 | 1837 | 36 | 427 | 65 |
| 144 | 1846 | 47 | 431 | 76 |
| 145 | 1855 | 55 | 435 | 95 |
| 146 | 1854 | 60 | 440 | 21 |
| 147 | 1873 | 61 | 444 | 55 |
| 148 | 1882 | 59 | 448 | 95 |
| 149 | 1891 | 53 | 463 | 42 |
| 150 | 1900 | 44 | 457 | 97 |
| 151 | 1909 | 31 | 452 | 68 |
| 152 | 1918 | 15 | 467 | 27 |
| 153 | 1926 | 95 | 472 | 02 |
| 154 | 1935 | 71 | 476 | 85 |
| 155 | 1944 | 43 | 481 | 74 |
| 156 | 1953 | 11 | 486 | 70 |
| 157 | 1961 | 75 | 491 | 73 |
| 158 | 1970 | 35 | 496 | 83 |
| 159 | 1978 | 92 | 502 | 00 |
| 150 | 1987 | 44 | 507 | 23 |
| 161 | 1995 | 92 | 512 | 53 |
| 162 | 2004 | 35 | 517 | 90 |
| 163 | 2012 | 75 | 523 | 33 |
| 164 | 2021 | 10 | 528 | 83 |
| 165 | 2029 | 41 | 534 | 40 |
| 166 | 2037 | 67 | 540 | 03 |
| 157 | 2045 | 89 | 545 | 73 |
| 168 | 2054 | 06 | 551 | 49 |
| 159 | 2062 | 19 | 557 | 32 |
| 170 | 2070 | 27 | 563 | 21 |
| 171 | 2078 | 30 | 569 | 16 |
| 172 | 2086 | 29 | 575 | 18 |
| 173 | 2094 | 23 | 581 | 25 |
| 174 | 2102 | 12 | 587 | 41 |
| 175 | 2109 | 96 | 593 | 61 |
| 176 | 2117 | 75 | 599 | 88 |
| 177 | 2125 | 50 | 606 | 21 |
| 178 | 2133 | 19 | 612 | 60 |
| 179 | 2140 | 83 | 619 | 05 |
| 180 | 2148 | 42 | 626 | 56 |
| 181 | 2155 | 96 | 632 | 13 |
| 182 | 2163 | 45 | 638 | 76 |
| 183 | 2170 | 88 | 646 | 45 |
| 184 | 2178 | 26 | 652 | 19 |
| 185 | 2185 | 59 | 659 | 00 |
| 186 | 2192 | 86 | 655 | 86 |
| 187 | 2197 | 18 | 670 | 00 |

Circle Center At X = 1321 3 , Y = 1582 2 and Radius, 1264 6
 *** 0 586 ***

Failure Surface Specified By 186 Coordinate Points
 Point X-Surf Y-Surf
 No (ft) (ft)

| | | |
|----|---------|--------|
| 1 | 540 42 | 617 44 |
| 2 | 547 95 | 610 85 |
| 3 | 555 54 | 604 35 |
| 4 | 563 18 | 597 89 |
| 5 | 570 87 | 591 50 |
| 6 | 578 61 | 585 18 |
| 7 | 586 41 | 578 91 |
| 8 | 694 26 | 572 71 |
| 9 | 602 15 | 566 58 |
| 10 | 610 09 | 560 50 |
| 11 | 618 09 | 554 50 |
| 12 | 626 13 | 548 55 |
| 13 | 534 22 | 542 68 |
| 14 | 642 35 | 536 87 |
| 15 | 650 55 | 531 13 |
| 16 | 558 78 | 525 45 |
| 17 | 667 06 | 519 84 |
| 18 | 676 39 | 514 30 |
| 19 | 683 76 | 508 83 |
| 20 | 692 17 | 503 43 |
| 21 | 700 63 | 498 09 |
| 22 | 709 13 | 492 83 |
| 23 | 717 67 | 487 63 |
| 24 | 726 26 | 482 50 |
| 25 | 734 89 | 477 45 |
| 26 | 743 55 | 472 46 |
| 27 | 752 26 | 467 55 |
| 28 | 761 01 | 462 70 |
| 29 | 769 80 | 457 93 |
| 30 | 778 63 | 453 23 |
| 31 | 787 49 | 448 60 |
| 32 | 796 39 | 444 05 |
| 33 | 805 33 | 439 66 |
| 34 | 814 31 | 435 15 |
| 35 | 823 32 | 430 82 |
| 36 | 832 36 | 426 55 |
| 37 | 841 44 | 422 36 |
| 38 | 850 56 | 418 25 |
| 39 | 859 71 | 414 21 |
| 40 | 868 89 | 410 24 |
| 41 | 878 10 | 405 35 |
| 42 | 887 34 | 402 54 |
| 43 | 895 62 | 398 80 |
| 44 | 905 92 | 395 14 |
| 45 | 915 26 | 391 55 |
| 46 | 924 52 | 388 04 |
| 47 | 934 01 | 384 50 |
| 48 | 943 43 | 381 24 |
| 49 | 952 88 | 377 96 |
| 50 | 962 35 | 374 76 |
| 51 | 971 85 | 371 63 |
| 52 | 981 37 | 368 58 |
| 53 | 990 92 | 365 61 |
| 54 | 1000 49 | 362 72 |
| 55 | 1010 09 | 359 90 |
| 56 | 1019 70 | 357 16 |
| 57 | 1029 34 | 354 51 |
| 58 | 1039 01 | 351 93 |
| 59 | 1048 59 | 349 43 |
| 60 | 1058 39 | 347 00 |
| 61 | 1068 11 | 344 66 |
| 62 | 1077 85 | 342 40 |
| 63 | 1087 61 | 340 21 |
| 64 | 1097 39 | 338 11 |
| 66 | 1107 18 | 336 09 |
| 66 | 1116 99 | 334 14 |
| 67 | 1126 82 | 332 28 |
| 68 | 1136 66 | 330 50 |

| | | |
|-----|---------|--------|
| 69 | 1145 51 | 328 79 |
| 70 | 1156 38 | 327 17 |
| 71 | 1166 26 | 325 63 |
| 72 | 1176 15 | 324 17 |
| 73 | 1186 05 | 322 78 |
| 74 | 1195 97 | 321 48 |
| 75 | 1205 89 | 320 26 |
| 76 | 1215 83 | 319 13 |
| 77 | 1225 77 | 318 07 |
| 78 | 1235 73 | 317 09 |
| 79 | 1245 69 | 316 20 |
| 80 | 1255 65 | 315 39 |
| 81 | 1265 63 | 314 65 |
| 82 | 1275 60 | 314 00 |
| 83 | 1285 59 | 313 43 |
| 84 | 1295 58 | 312 95 |
| 85 | 1305 57 | 312 54 |
| 86 | 1315 56 | 312 21 |
| 87 | 1325 56 | 311 97 |
| 88 | 1335 56 | 311 81 |
| 89 | 1345 56 | 311 73 |
| 90 | 1355 56 | 311 73 |
| 91 | 1365 56 | 311 81 |
| 92 | 1375 56 | 311 98 |
| 93 | 1385 55 | 312 22 |
| 94 | 1395 55 | 312 55 |
| 95 | 1405 54 | 312 96 |
| 96 | 1415 53 | 313 45 |
| 97 | 1425 51 | 314 02 |
| 98 | 1435 49 | 314 68 |
| 99 | 1445 46 | 315 41 |
| 100 | 1455 43 | 316 23 |
| 101 | 1465 39 | 317 13 |
| 102 | 1475 34 | 318 11 |
| 103 | 1485 28 | 319 17 |
| 104 | 1495 22 | 320 31 |
| 105 | 1505 14 | 321 53 |
| 106 | 1515 06 | 322 83 |
| 107 | 1524 96 | 324 22 |
| 108 | 1534 85 | 325 68 |
| 109 | 1544 73 | 327 22 |
| 110 | 1554 60 | 328 85 |
| 111 | 1564 45 | 330 55 |
| 112 | 1574 29 | 332 34 |
| 113 | 1584 12 | 334 21 |
| 114 | 1593 93 | 336 16 |
| 115 | 1603 72 | 338 18 |
| 116 | 1613 50 | 340 29 |
| 117 | 1623 25 | 342 48 |
| 118 | 1632 99 | 344 74 |
| 119 | 1642 71 | 347 09 |
| 120 | 1652 42 | 349 51 |
| 121 | 1662 10 | 352 02 |
| 122 | 1671 76 | 354 60 |
| 123 | 1681 40 | 357 26 |
| 124 | 1691 01 | 360 00 |
| 125 | 1700 61 | 362 82 |
| 126 | 1710 18 | 365 71 |
| 127 | 1719 73 | 368 69 |
| 128 | 1729 25 | 371 74 |
| 129 | 1738 75 | 374 87 |
| 130 | 1748 22 | 378 08 |
| 131 | 1757 67 | 381 36 |
| 132 | 1767 08 | 384 72 |
| 133 | 1776 47 | 388 16 |
| 134 | 1785 84 | 391 67 |
| 135 | 1795 17 | 395 26 |
| 136 | 1804 47 | 398 93 |

76/130

| | | |
|-----|---------|--------|
| 137 | 1813 75 | 402 57 |
| 138 | 1822 99 | 406 49 |
| 139 | 1832 20 | 410 38 |
| 140 | 1841 38 | 414 35 |
| 141 | 1850 53 | 418 39 |
| 142 | 1859 64 | 422 51 |
| 143 | 1868 72 | 425 70 |
| 144 | 1877 76 | 430 97 |
| 145 | 1886 77 | 435 31 |
| 145 | 1895 75 | 439 72 |
| 147 | 1904 68 | 444 20 |
| 148 | 1913 58 | 448 76 |
| 149 | 1922 45 | 463 39 |
| 150 | 1931 27 | 468 10 |
| 151 | 1940 06 | 462 87 |
| 152 | 1948 81 | 467 72 |
| 153 | 1957 51 | 472 64 |
| 154 | 1966 18 | 477 62 |
| 155 | 1974 81 | 482 68 |
| 156 | 1983 39 | 487 81 |
| 157 | 1991 93 | 493 01 |
| 158 | 2000 43 | 498 28 |
| 159 | 2008 89 | 503 62 |
| 160 | 2017 30 | 609 02 |
| 161 | 2025 67 | 514 50 |
| 152 | 2033 99 | 520 04 |
| 153 | 2042 27 | 525 65 |
| 164 | 2050 50 | 531 33 |
| 165 | 2058 69 | 537 07 |
| 155 | 2066 83 | 542 89 |
| 167 | 2074 92 | 548 76 |
| 168 | 2082 96 | 554 71 |
| 169 | 2090 95 | 550 72 |
| 170 | 2098 90 | 556 79 |
| 171 | 2106 79 | 572 93 |
| 172 | 2114 63 | 579 13 |
| 173 | 2122 43 | 585 40 |
| 174 | 2130 17 | 591 73 |
| 175 | 2137 86 | 598 12 |
| 176 | 2145 50 | 604 58 |
| 177 | 2153 08 | 611 09 |
| 178 | 2160 51 | 617 67 |
| 179 | 2168 09 | 624 31 |
| 180 | 2175 51 | 631 01 |
| 181 | 2182 88 | 637 77 |
| 182 | 2190 19 | 644 60 |
| 183 | 2197 45 | 551 48 |
| 184 | 2204 65 | 658 42 |
| 185 | 2211 79 | 665 41 |
| 185 | 2216 39 | 670 00 |

Circle Center At X = 1350 4 , Y = 1537 5 and Radius, 1225 8
*** 0 587 ***

Failure Surface Specified By 175 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 480 00 | 616 70 |
| 2 | 487 13 | 609 69 |
| 3 | 494 33 | 602 76 |
| 4 | 501 60 | 595 88 |
| 5 | 508 93 | 589 08 |
| 6 | 616 32 | 582 35 |
| 7 | 523 78 | 575 68 |
| 8 | 531 30 | 669 09 |
| 9 | 538 88 | 562 57 |
| 10 | 546 52 | 555 12 |
| 11 | 564 22 | 549 74 |
| 12 | 551 98 | 543 44 |
| 13 | 569 81 | 537 20 |

| | | |
|----|---------|--------|
| 14 | 577 68 | 531 05 |
| 15 | 585 62 | 524 96 |
| 16 | 593 62 | 518 95 |
| 17 | 601 67 | 513 02 |
| 18 | 609 77 | 507 17 |
| 19 | 617 93 | 501 39 |
| 20 | 626 15 | 495 69 |
| 21 | 634 42 | 490 06 |
| 22 | 642 74 | 484 52 |
| 23 | 651 11 | 479 05 |
| 24 | 659 54 | 473 66 |
| 25 | 668 01 | 468 35 |
| 26 | 676 54 | 463 13 |
| 27 | 685 11 | 457 98 |
| 28 | 693 73 | 452 91 |
| 29 | 702 40 | 447 93 |
| 30 | 711 11 | 443 02 |
| 31 | 719 88 | 438 20 |
| 32 | 728 68 | 433 46 |
| 33 | 737 53 | 428 81 |
| 34 | 746 43 | 424 24 |
| 35 | 755 36 | 419 75 |
| 35 | 764 34 | 415 35 |
| 37 | 773 36 | 411 03 |
| 38 | 782 42 | 406 80 |
| 39 | 791 52 | 402 65 |
| 40 | 800 56 | 398 59 |
| 41 | 809 84 | 394 62 |
| 42 | 819 05 | 390 73 |
| 43 | 828 30 | 386 93 |
| 44 | 837 58 | 383 21 |
| 45 | 846 90 | 379 59 |
| 46 | 856 26 | 376 05 |
| 47 | 865 64 | 372 60 |
| 48 | 875 06 | 369 24 |
| 49 | 884 51 | 365 97 |
| 50 | 893 99 | 362 78 |
| 51 | 903 50 | 359 69 |
| 52 | 913 04 | 356 69 |
| 53 | 922 60 | 363 78 |
| 54 | 932 20 | 350 95 |
| 55 | 941 82 | 348 22 |
| 56 | 951 46 | 345 58 |
| 57 | 951 13 | 343 03 |
| 58 | 970 82 | 340 57 |
| 59 | 980 54 | 338 20 |
| 60 | 990 28 | 335 93 |
| 61 | 1000 04 | 333 74 |
| 62 | 1009 81 | 331 65 |
| 63 | 1019 61 | 329 65 |
| 64 | 1029 43 | 327 74 |
| 65 | 1039 26 | 325 93 |
| 66 | 1049 11 | 324 21 |
| 67 | 1058 98 | 322 58 |
| 68 | 1068 86 | 321 04 |
| 69 | 1078 76 | 319 60 |
| 70 | 1088 57 | 318 25 |
| 71 | 1098 59 | 316 99 |
| 72 | 1108 52 | 315 83 |
| 73 | 1118 46 | 314 76 |
| 74 | 1128 41 | 313 79 |
| 75 | 1138 38 | 312 91 |
| 76 | 1148 34 | 312 12 |
| 77 | 1158 32 | 311 43 |
| 78 | 1168 30 | 310 83 |
| 79 | 1178 29 | 310 32 |
| 80 | 1188 28 | 309 91 |
| 81 | 1198 28 | 309 60 |

78/130

| | | | | |
|-----|------|----|-----|----|
| 82 | 1208 | 27 | 309 | 38 |
| 83 | 1218 | 27 | 309 | 25 |
| 84 | 1228 | 27 | 309 | 22 |
| 85 | 1238 | 27 | 309 | 28 |
| 86 | 1248 | 27 | 309 | 43 |
| 87 | 1258 | 27 | 309 | 68 |
| 88 | 1268 | 26 | 310 | 02 |
| 89 | 1278 | 25 | 310 | 46 |
| 90 | 1288 | 24 | 310 | 99 |
| 91 | 1298 | 22 | 311 | 62 |
| 92 | 1308 | 19 | 312 | 34 |
| 93 | 1318 | 16 | 313 | 16 |
| 94 | 1328 | 12 | 314 | 06 |
| 95 | 1338 | 07 | 315 | 07 |
| 96 | 1348 | 01 | 316 | 16 |
| 97 | 1357 | 94 | 317 | 35 |
| 98 | 1367 | 85 | 318 | 63 |
| 99 | 1377 | 76 | 320 | 01 |
| 100 | 1387 | 56 | 321 | 48 |
| 101 | 1397 | 63 | 323 | 04 |
| 102 | 1407 | 39 | 324 | 70 |
| 103 | 1417 | 24 | 326 | 45 |
| 104 | 1427 | 06 | 328 | 29 |
| 105 | 1436 | 88 | 330 | 22 |
| 106 | 1446 | 67 | 332 | 25 |
| 107 | 1456 | 44 | 334 | 37 |
| 108 | 1466 | 19 | 336 | 58 |
| 109 | 1475 | 92 | 338 | 88 |
| 110 | 1485 | 63 | 341 | 28 |
| 111 | 1495 | 32 | 343 | 76 |
| 112 | 1504 | 98 | 346 | 34 |
| 113 | 1514 | 62 | 349 | 01 |
| 114 | 1524 | 23 | 351 | 77 |
| 115 | 1533 | 82 | 354 | 62 |
| 116 | 1543 | 37 | 357 | 56 |
| 117 | 1552 | 90 | 360 | 59 |
| 118 | 1562 | 41 | 363 | 71 |
| 119 | 1571 | 88 | 366 | 92 |
| 120 | 1581 | 32 | 370 | 21 |
| 121 | 1590 | 73 | 373 | 60 |
| 122 | 1600 | 10 | 377 | 08 |
| 123 | 1609 | 45 | 380 | 64 |
| 124 | 1618 | 76 | 384 | 29 |
| 125 | 1628 | 03 | 388 | 03 |
| 126 | 1637 | 27 | 391 | 86 |
| 127 | 1646 | 47 | 396 | 77 |
| 128 | 1655 | 64 | 399 | 77 |
| 129 | 1664 | 76 | 403 | 86 |
| 130 | 1673 | 85 | 408 | 03 |
| 131 | 1682 | 90 | 412 | 28 |
| 132 | 1691 | 91 | 416 | 63 |
| 133 | 1700 | 88 | 421 | 05 |
| 134 | 1709 | 80 | 425 | 57 |
| 135 | 1718 | 68 | 430 | 16 |
| 136 | 1727 | 52 | 434 | 84 |
| 137 | 1735 | 31 | 439 | 60 |
| 138 | 1745 | 06 | 444 | 45 |
| 139 | 1753 | 76 | 449 | 38 |
| 140 | 1762 | 42 | 454 | 38 |
| 141 | 1771 | 03 | 459 | 47 |
| 142 | 1779 | 58 | 464 | 65 |
| 143 | 1788 | 09 | 469 | 90 |
| 144 | 1796 | 55 | 475 | 23 |
| 145 | 1804 | 95 | 480 | 64 |
| 146 | 1813 | 32 | 486 | 13 |
| 147 | 1821 | 63 | 491 | 70 |
| 148 | 1829 | 88 | 497 | 35 |
| 149 | 1838 | 08 | 503 | 07 |

79/130

| | | |
|-----|---------|--------|
| 150 | 1845 22 | 508 87 |
| 151 | 1864 31 | 514 75 |
| 152 | 1862 35 | 520 71 |
| 153 | 1870 33 | 526 74 |
| 154 | 1878 25 | 532 84 |
| 155 | 1886 11 | 539 02 |
| 156 | 1893 91 | 545 27 |
| 157 | 1901 66 | 551 60 |
| 168 | 1909 34 | 558 00 |
| 159 | 1916 97 | 564 47 |
| 160 | 1924 53 | 571 01 |
| 161 | 1932 03 | 577 62 |
| 162 | 1939 47 | 584 31 |
| 153 | 1945 84 | 691 06 |
| 164 | 1954 15 | 597 89 |
| 165 | 1961 40 | 604 78 |
| 166 | 1968 58 | 611 74 |
| 167 | 1975 69 | 618 76 |
| 168 | 1982 74 | 625 86 |
| 169 | 1989 72 | 633 02 |
| 170 | 1996 64 | 640 24 |
| 171 | 2003 48 | 647 53 |
| 172 | 2010 26 | 654 89 |
| 173 | 2016 96 | 662 31 |
| 174 | 2023 60 | 669 79 |
| 175 | 2023 78 | 670 00 |

Circle Center At X = 1226 8 , Y = 1369 9 and Radius, 1060 7
 *** 0 593 ***

Failure Surface Specified By 180 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 625 00 | 618 47 |
| 2 | 632 07 | 611 40 |
| 3 | 639 21 | 604 40 |
| 4 | 646 41 | 597 46 |
| 5 | 653 68 | 590 59 |
| 6 | 651 00 | 583 78 |
| 7 | 668 39 | 577 05 |
| 8 | 675 85 | 570 38 |
| 9 | 683 36 | 563 78 |
| 10 | 690 93 | 557 25 |
| 11 | 698 57 | 550 79 |
| 12 | 706 26 | 544 40 |
| 13 | 714 01 | 538 08 |
| 14 | 721 82 | 531 83 |
| 15 | 729 68 | 525 56 |
| 16 | 737 60 | 519 66 |
| 17 | 745 58 | 513 53 |
| 18 | 753 62 | 507 57 |
| 19 | 761 70 | 501 59 |
| 20 | 769 84 | 495 88 |
| 21 | 778 04 | 490 15 |
| 22 | 786 29 | 484 49 |
| 23 | 794 58 | 478 91 |
| 24 | 802 93 | 473 41 |
| 25 | 811 33 | 467 98 |
| 26 | 819 78 | 462 63 |
| 27 | 828 28 | 457 35 |
| 28 | 836 83 | 452 17 |
| 29 | 845 42 | 447 05 |
| 30 | 864 05 | 442 02 |
| 31 | 862 75 | 437 07 |
| 32 | 871 48 | 432 19 |
| 33 | 880 25 | 427 40 |
| 34 | 889 07 | 422 69 |
| 35 | 897 94 | 418 06 |
| 36 | 906 84 | 413 61 |
| 37 | 915 79 | 409 04 |

| | | |
|-----|---------|--------|
| 38 | 924 77 | 404 65 |
| 39 | 933 80 | 400 35 |
| 40 | 942 87 | 396 13 |
| 41 | 951 97 | 391 99 |
| 42 | 961 11 | 387 94 |
| 43 | 970 29 | 383 97 |
| 44 | 979 51 | 380 09 |
| 45 | 988 75 | 376 29 |
| 46 | 998 05 | 372 68 |
| 47 | 1007 36 | 368 95 |
| 48 | 1016 72 | 365 41 |
| 49 | 1026 10 | 361 95 |
| 50 | 1035 52 | 358 59 |
| 51 | 1044 96 | 355 31 |
| 52 | 1054 44 | 352 11 |
| 53 | 1063 94 | 349 01 |
| 54 | 1073 48 | 345 99 |
| 55 | 1083 04 | 343 05 |
| 55 | 1092 62 | 340 21 |
| 57 | 1102 24 | 337 45 |
| 58 | 1111 87 | 334 79 |
| 59 | 1121 54 | 332 21 |
| 50 | 1131 22 | 329 72 |
| 61 | 1140 93 | 327 32 |
| 62 | 1150 66 | 325 01 |
| 63 | 1160 41 | 322 79 |
| 54 | 1170 18 | 320 66 |
| 65 | 1179 97 | 318 62 |
| 66 | 1189 78 | 316 67 |
| 57 | 1199 60 | 314 80 |
| 68 | 1209 44 | 313 03 |
| 69 | 1219 30 | 311 35 |
| 70 | 1229 18 | 309 77 |
| 71 | 1239 05 | 308 27 |
| 72 | 1248 96 | 306 86 |
| 73 | 1258 88 | 305 55 |
| 74 | 1268 80 | 304 32 |
| 75 | 1278 74 | 303 19 |
| 76 | 1288 68 | 302 15 |
| 77 | 1298 64 | 301 20 |
| 78 | 1308 60 | 300 34 |
| 79 | 1318 57 | 299 57 |
| 80 | 1328 55 | 298 90 |
| 81 | 1338 53 | 298 31 |
| 82 | 1348 52 | 297 82 |
| 83 | 1358 51 | 297 42 |
| 84 | 1368 51 | 297 11 |
| 85 | 1378 50 | 296 90 |
| 86 | 1388 50 | 296 77 |
| 87 | 1398 60 | 296 74 |
| 88 | 1408 50 | 296 80 |
| 89 | 1418 50 | 296 96 |
| 90 | 1428 50 | 297 20 |
| 91 | 1438 49 | 297 54 |
| 92 | 1448 48 | 297 95 |
| 93 | 1458 47 | 298 49 |
| 94 | 1468 46 | 299 10 |
| 95 | 1478 43 | 299 80 |
| 96 | 1488 39 | 300 60 |
| 97 | 1498 36 | 301 48 |
| 98 | 1508 31 | 302 46 |
| 99 | 1518 25 | 303 53 |
| 100 | 1528 18 | 304 70 |
| 101 | 1638 10 | 305 95 |
| 102 | 1548 01 | 307 29 |
| 103 | 1557 91 | 308 73 |
| 104 | 1567 79 | 310 25 |
| 105 | 1577 66 | 311 87 |

81/130

| | | |
|-----|---------|--------|
| 106 | 1587 51 | 313 68 |
| 107 | 1597 35 | 315 38 |
| 108 | 1607 17 | 317 27 |
| 109 | 1615 97 | 319 25 |
| 110 | 1525 76 | 321 32 |
| 111 | 1636 52 | 323 48 |
| 112 | 1545 26 | 325 73 |
| 113 | 1655 99 | 328 06 |
| 114 | 1665 69 | 330 49 |
| 115 | 1675 36 | 333 01 |
| 116 | 1685 02 | 335 62 |
| 117 | 1694 65 | 338 31 |
| 118 | 1704 25 | 341 09 |
| 119 | 1713 83 | 343 96 |
| 120 | 1723 38 | 346 92 |
| 121 | 1732 91 | 349 97 |
| 122 | 1742 41 | 353 11 |
| 123 | 1751 87 | 356 33 |
| 124 | 1751 31 | 359 64 |
| 125 | 1770 71 | 363 03 |
| 126 | 1780 09 | 366 52 |
| 127 | 1789 43 | 370 08 |
| 128 | 1798 74 | 373 74 |
| 129 | 1808 01 | 377 48 |
| 130 | 1817 25 | 381 30 |
| 131 | 1826 46 | 385 21 |
| 132 | 1835 62 | 389 21 |
| 133 | 1844 76 | 393 28 |
| 134 | 1853 85 | 397 45 |
| 135 | 1862 90 | 401 69 |
| 136 | 1871 92 | 406 02 |
| 137 | 1880 89 | 410 43 |
| 138 | 1889 82 | 414 92 |
| 139 | 1898 72 | 419 50 |
| 140 | 1907 57 | 424 16 |
| 141 | 1916 37 | 428 90 |
| 142 | 1925 13 | 433 72 |
| 143 | 1933 85 | 438 61 |
| 144 | 1942 52 | 443 59 |
| 145 | 1951 15 | 448 65 |
| 146 | 1959 73 | 453 79 |
| 147 | 1968 26 | 459 01 |
| 148 | 1976 74 | 464 31 |
| 149 | 1985 18 | 469 68 |
| 150 | 1993 56 | 475 13 |
| 151 | 2001 89 | 480 66 |
| 152 | 2010 18 | 486 26 |
| 153 | 2018 41 | 491 94 |
| 154 | 2026 58 | 497 70 |
| 155 | 2034 71 | 503 53 |
| 156 | 2042 78 | 509 43 |
| 157 | 2050 79 | 515 41 |
| 158 | 2058 75 | 521 46 |
| 159 | 2066 66 | 527 59 |
| 160 | 2074 51 | 533 79 |
| 161 | 2082 30 | 540 06 |
| 162 | 2090 03 | 546 40 |
| 163 | 2097 70 | 552 81 |
| 164 | 2105 32 | 559 29 |
| 166 | 2112 87 | 565 84 |
| 166 | 2120 36 | 572 47 |
| 167 | 2127 80 | 579 16 |
| 168 | 2135 17 | 595 91 |
| 169 | 2142 48 | 592 74 |
| 170 | 2149 72 | 599 53 |
| 171 | 2156 90 | 606 59 |
| 172 | 2164 02 | 613 62 |
| 173 | 2171 07 | 620 71 |

82/130

| | | |
|-----|---------|--------|
| 174 | 2178 06 | 627 85 |
| 175 | 2184 98 | 635 08 |
| 176 | 2191 83 | 542 36 |
| 177 | 2198 62 | 649 70 |
| 178 | 2205 34 | 657 11 |
| 179 | 2211 99 | 664 68 |
| 180 | 2216 73 | 670 00 |

Circle Center At X = 1396 9 , Y = 1383 6 and Radius, 1086 9

*** 0 598 ***

Failure Surface Specified By172 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 628 33 | 617 29 |
| 2 | 535 45 | 610 26 |
| 3 | 542 63 | 603 30 |
| 4 | 649 87 | 596 41 |
| 5 | 567 19 | 589 59 |
| 6 | 564 56 | 582 84 |
| 7 | 572 01 | 576 16 |
| 8 | 579 51 | 569 55 |
| 9 | 587 08 | 663 02 |
| 10 | 594 71 | 556 56 |
| 11 | 602 41 | 550 17 |
| 12 | 610 16 | 543 85 |
| 13 | 617 97 | 537 61 |
| 14 | 625 85 | 531 45 |
| 16 | 633 78 | 525 36 |
| 16 | 641 77 | 519 35 |
| 17 | 649 82 | 613 41 |
| 18 | 657 92 | 507 55 |
| 19 | 656 08 | 501 77 |
| 20 | 674 30 | 496 07 |
| 21 | 682 57 | 490 45 |
| 22 | 690 89 | 484 91 |
| 23 | 699 27 | 479 44 |
| 24 | 707 70 | 474 06 |
| 26 | 716 18 | 468 76 |
| 25 | 724 70 | 453 54 |
| 27 | 733 28 | 458 40 |
| 28 | 741 91 | 463 35 |
| 29 | 750 59 | 448 38 |
| 30 | 759 31 | 443 49 |
| 31 | 768 08 | 438 68 |
| 32 | 776 90 | 433 96 |
| 33 | 785 76 | 429 33 |
| 34 | 794 57 | 424 78 |
| 35 | 803 51 | 420 31 |
| 36 | 812 60 | 415 94 |
| 37 | 821 64 | 411 64 |
| 38 | 830 71 | 407 44 |
| 39 | 839 82 | 403 32 |
| 40 | 848 97 | 399 29 |
| 41 | 868 16 | 396 35 |
| 42 | 867 39 | 391 50 |
| 43 | 876 66 | 387 73 |
| 44 | 886 96 | 384 06 |
| 45 | 895 29 | 380 47 |
| 46 | 904 66 | 376 97 |
| 47 | 914 06 | 373 57 |
| 48 | 923 50 | 370 25 |
| 49 | 932 95 | 367 02 |
| 50 | 942 46 | 363 89 |
| 51 | 961 98 | 350 85 |
| 52 | 961 64 | 367 89 |
| 53 | 971 12 | 355 03 |
| 54 | 980 73 | 352 27 |
| 55 | 990 36 | 349 69 |
| 66 | 1000 03 | 347 01 |

| | | |
|-----|---------|--------|
| 67 | 1009 71 | 344 52 |
| 58 | 1019 42 | 342 12 |
| 59 | 1029 15 | 339 82 |
| 60 | 1038 90 | 337 61 |
| 61 | 1048 68 | 335 49 |
| 62 | 1058 47 | 333 47 |
| 63 | 1068 28 | 331 54 |
| 64 | 1078 11 | 329 70 |
| 65 | 1087 96 | 327 96 |
| 66 | 1097 82 | 326 32 |
| 67 | 1107 70 | 324 77 |
| 68 | 1117 60 | 323 31 |
| 69 | 1127 50 | 321 95 |
| 70 | 1137 42 | 320 68 |
| 71 | 1147 35 | 319 51 |
| 72 | 1157 29 | 318 44 |
| 73 | 1167 25 | 317 46 |
| 74 | 1177 21 | 316 57 |
| 75 | 1187 18 | 315 78 |
| 76 | 1197 15 | 315 09 |
| 77 | 1207 13 | 314 49 |
| 78 | 1217 12 | 313 99 |
| 79 | 1227 11 | 313 59 |
| 80 | 1237 11 | 313 28 |
| 81 | 1247 11 | 313 06 |
| 82 | 1257 11 | 312 95 |
| 83 | 1267 11 | 312 92 |
| 84 | 1277 11 | 313 00 |
| 85 | 1287 10 | 313 17 |
| 86 | 1297 10 | 313 43 |
| 87 | 1307 09 | 313 80 |
| 88 | 1317 08 | 314 25 |
| 89 | 1327 07 | 314 81 |
| 90 | 1337 05 | 315 46 |
| 91 | 1347 02 | 316 20 |
| 92 | 1356 98 | 317 04 |
| 93 | 1366 94 | 317 98 |
| 94 | 1376 89 | 319 01 |
| 95 | 1386 82 | 320 14 |
| 96 | 1396 75 | 321 36 |
| 97 | 1406 66 | 322 68 |
| 98 | 1416 56 | 324 09 |
| 99 | 1426 45 | 325 60 |
| 100 | 1436 32 | 327 20 |
| 101 | 1445 17 | 328 90 |
| 102 | 1456 01 | 330 69 |
| 103 | 1466 83 | 332 57 |
| 104 | 1475 63 | 334 55 |
| 105 | 1485 42 | 336 63 |
| 106 | 1495 18 | 338 80 |
| 107 | 1504 92 | 341 06 |
| 108 | 1514 64 | 343 41 |
| 109 | 1524 33 | 345 86 |
| 110 | 1534 01 | 348 40 |
| 111 | 1543 65 | 351 03 |
| 112 | 1553 27 | 353 76 |
| 113 | 1562 87 | 356 58 |
| 114 | 1572 44 | 359 49 |
| 115 | 1581 97 | 362 49 |
| 116 | 1591 48 | 365 58 |
| 117 | 1600 96 | 368 77 |
| 118 | 1610 41 | 372 04 |
| 119 | 1619 83 | 375 41 |
| 120 | 1629 21 | 378 86 |
| 121 | 1638 56 | 382 41 |
| 122 | 1647 88 | 386 04 |
| 123 | 1657 16 | 389 77 |
| 124 | 1656 40 | 393 58 |

| | | |
|-----|---------|--------|
| 125 | 1575 61 | 397 48 |
| 126 | 1684 78 | 401 47 |
| 127 | 1593 91 | 405 55 |
| 128 | 1703 00 | 409 71 |
| 129 | 1712 05 | 413 97 |
| 130 | 1721 06 | 418 30 |
| 131 | 1730 03 | 422 73 |
| 132 | 1738 96 | 427 24 |
| 133 | 1747 84 | 431 84 |
| 134 | 1756 67 | 436 52 |
| 135 | 1765 47 | 441 28 |
| 136 | 1774 21 | 446 13 |
| 137 | 1782 91 | 451 07 |
| 138 | 1791 56 | 456 08 |
| 139 | 1800 16 | 461 18 |
| 140 | 1808 71 | 466 37 |
| 141 | 1817 22 | 471 63 |
| 142 | 1825 67 | 476 97 |
| 143 | 1834 07 | 482 40 |
| 144 | 1842 42 | 487 91 |
| 145 | 1850 71 | 493 49 |
| 145 | 1858 95 | 499 16 |
| 147 | 1867 14 | 504 90 |
| 148 | 1875 27 | 510 73 |
| 149 | 1883 34 | 516 63 |
| 150 | 1891 36 | 522 60 |
| 151 | 1899 32 | 528 66 |
| 152 | 1907 22 | 534 79 |
| 153 | 1915 06 | 540 99 |
| 154 | 1922 84 | 547 27 |
| 155 | 1930 56 | 553 63 |
| 156 | 1938 22 | 660 06 |
| 157 | 1945 82 | 556 56 |
| 158 | 1953 35 | 573 14 |
| 159 | 1960 82 | 579 78 |
| 160 | 1968 23 | 586 50 |
| 161 | 1975 57 | 593 29 |
| 162 | 1982 85 | 500 15 |
| 163 | 1990 06 | 607 08 |
| 154 | 1997 20 | 614 07 |
| 165 | 2004 28 | 621 14 |
| 166 | 2011 29 | 628 27 |
| 167 | 2018 23 | 636 47 |
| 168 | 2025 10 | 642 74 |
| 169 | 2031 90 | 650 07 |
| 170 | 2038 63 | 657 47 |
| 171 | 2045 29 | 664 93 |
| 172 | 2049 73 | 570 00 |

Circle Center At X = 1264 4 , Y = 1355 1 and Radius, 1042 2
 *** 0 604 ***

Failure Surface Specified By 177 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 625 00 | 618 47 |
| 2 | 632 12 | 611 46 |
| 3 | 639 31 | 604 50 |
| 4 | 646 57 | 597 62 |
| 5 | 653 88 | 590 80 |
| 6 | 661 26 | 584 05 |
| 7 | 668 70 | 577 37 |
| 8 | 676 21 | 570 76 |
| 9 | 683 77 | 554 22 |
| 10 | 691 39 | 567 75 |
| 11 | 699 08 | 551 36 |
| 12 | 706 82 | 545 02 |
| 13 | 714 62 | 538 77 |
| 14 | 722 48 | 532 58 |
| 15 | 730 40 | 626 47 |

| | | |
|----|---------|--------|
| 16 | 738 37 | 520 44 |
| 17 | 746 40 | 514 47 |
| 18 | 764 48 | 508 59 |
| 19 | 752 62 | 502 77 |
| 20 | 770 81 | 497 04 |
| 21 | 779 05 | 491 38 |
| 22 | 787 35 | 485 79 |
| 23 | 795 70 | 480 29 |
| 24 | 804 09 | 474 86 |
| 25 | 812 54 | 469 50 |
| 26 | 821 04 | 464 23 |
| 27 | 829 58 | 459 04 |
| 28 | 838 18 | 453 92 |
| 29 | 846 82 | 448 89 |
| 30 | 855 50 | 443 93 |
| 31 | 864 24 | 439 06 |
| 32 | 873 01 | 434 27 |
| 33 | 881 83 | 429 56 |
| 34 | 890 70 | 424 93 |
| 36 | 899 60 | 420 38 |
| 36 | 908 66 | 415 92 |
| 37 | 917 54 | 411 54 |
| 38 | 926 57 | 407 24 |
| 39 | 935 64 | 403 03 |
| 40 | 944 75 | 398 90 |
| 41 | 953 89 | 394 85 |
| 42 | 963 08 | 390 90 |
| 43 | 972 30 | 387 02 |
| 44 | 981 55 | 383 23 |
| 45 | 990 84 | 379 53 |
| 46 | 1000 15 | 375 91 |
| 47 | 1009 52 | 372 38 |
| 48 | 1018 91 | 368 94 |
| 49 | 1028 33 | 365 59 |
| 50 | 1037 78 | 362 32 |
| 51 | 1047 26 | 359 14 |
| 52 | 1056 77 | 366 05 |
| 53 | 1066 31 | 353 04 |
| 54 | 1075 87 | 350 13 |
| 55 | 1085 47 | 347 30 |
| 56 | 1095 08 | 344 55 |
| 57 | 1104 73 | 341 91 |
| 58 | 1114 39 | 339 35 |
| 59 | 1124 08 | 336 88 |
| 60 | 1133 80 | 334 51 |
| 61 | 1143 53 | 332 22 |
| 62 | 1153 29 | 330 02 |
| 63 | 1163 06 | 327 91 |
| 64 | 1172 86 | 325 89 |
| 65 | 1182 67 | 323 97 |
| 66 | 1192 50 | 322 13 |
| 67 | 1202 35 | 320 39 |
| 68 | 1212 21 | 318 73 |
| 69 | 1222 09 | 317 17 |
| 70 | 1231 98 | 315 70 |
| 71 | 1241 88 | 314 32 |
| 72 | 1251 80 | 313 04 |
| 73 | 1261 73 | 311 84 |
| 74 | 1271 67 | 310 74 |
| 75 | 1281 61 | 309 73 |
| 76 | 1291 57 | 308 81 |
| 77 | 1301 54 | 307 99 |
| 78 | 1311 51 | 307 25 |
| 79 | 1321 49 | 306 61 |
| 80 | 1331 48 | 306 06 |
| 81 | 1341 47 | 305 61 |
| 82 | 1351 45 | 305 25 |
| 83 | 1361 46 | 304 98 |

| | | |
|-----|---------|--------|
| 84 | 1371 45 | 304 80 |
| 85 | 1381 45 | 304 71 |
| 86 | 1391 45 | 304 72 |
| 87 | 1401 45 | 304 82 |
| 88 | 1411 45 | 306 01 |
| 89 | 1421 45 | 305 30 |
| 90 | 1431 44 | 305 68 |
| 91 | 1441 43 | 306 15 |
| 92 | 1451 41 | 306 71 |
| 93 | 1461 39 | 307 37 |
| 94 | 1471 36 | 308 12 |
| 95 | 1481 33 | 308 95 |
| 96 | 1491 28 | 309 89 |
| 97 | 1501 23 | 310 92 |
| 98 | 1511 17 | 312 04 |
| 99 | 1521 10 | 313 25 |
| 100 | 1531 01 | 314 55 |
| 101 | 1640 91 | 315 94 |
| 102 | 1550 80 | 317 43 |
| 103 | 1560 68 | 319 01 |
| 104 | 1570 54 | 320 67 |
| 105 | 1580 38 | 322 43 |
| 106 | 1590 21 | 324 28 |
| 107 | 1600 02 | 326 23 |
| 108 | 1609 81 | 328 26 |
| 109 | 1619 58 | 330 38 |
| 110 | 1629 33 | 332 60 |
| 111 | 1639 06 | 334 90 |
| 112 | 1648 77 | 337 30 |
| 113 | 1658 46 | 339 78 |
| 114 | 1668 12 | 342 35 |
| 115 | 1677 76 | 345 02 |
| 116 | 1687 37 | 347 77 |
| 117 | 1696 96 | 350 61 |
| 118 | 1706 52 | 353 54 |
| 119 | 1716 06 | 356 56 |
| 120 | 1725 56 | 359 67 |
| 121 | 1735 04 | 362 87 |
| 122 | 1744 48 | 366 15 |
| 123 | 1753 90 | 369 52 |
| 124 | 1763 28 | 372 98 |
| 125 | 1772 63 | 376 52 |
| 126 | 1781 95 | 380 15 |
| 127 | 1791 23 | 383 87 |
| 128 | 1800 48 | 387 67 |
| 129 | 1809 69 | 391 56 |
| 130 | 1818 87 | 395 53 |
| 131 | 1828 01 | 399 59 |
| 132 | 1837 11 | 403 74 |
| 133 | 1846 17 | 407 96 |
| 134 | 1855 20 | 412 27 |
| 135 | 1864 18 | 416 67 |
| 136 | 1873 12 | 421 15 |
| 137 | 1882 02 | 425 71 |
| 138 | 1890 88 | 430 35 |
| 139 | 1899 69 | 435 07 |
| 140 | 1908 46 | 439 88 |
| 141 | 1917 18 | 444 77 |
| 142 | 1925 85 | 449 74 |
| 143 | 1934 50 | 454 78 |
| 144 | 1943 08 | 459 91 |
| 145 | 1951 62 | 465 12 |
| 146 | 1960 11 | 470 40 |
| 147 | 1968 55 | 475 77 |
| 148 | 1976 93 | 481 21 |
| 149 | 1985 27 | 486 73 |
| 150 | 1993 56 | 492 33 |
| 151 | 2001 79 | 498 00 |

87/30

| | | |
|-----|---------|--------|
| 152 | 2009 98 | 503 75 |
| 153 | 2018 10 | 509 58 |
| 154 | 2026 18 | 515 48 |
| 155 | 2034 20 | 521 45 |
| 156 | 2042 16 | 527 50 |
| 157 | 2050 07 | 533 63 |
| 158 | 2057 91 | 539 82 |
| 159 | 2065 71 | 546 09 |
| 160 | 2073 44 | 552 43 |
| 161 | 2081 11 | 558 84 |
| 162 | 2088 73 | 566 32 |
| 153 | 2096 28 | 671 88 |
| 164 | 2103 77 | 578 50 |
| 165 | 2111 21 | 585 19 |
| 166 | 2118 57 | 691 95 |
| 167 | 2125 88 | 598 78 |
| 168 | 2133 12 | 605 68 |
| 159 | 2140 30 | 612 64 |
| 170 | 2147 41 | 619 67 |
| 171 | 2154 46 | 626 76 |
| 172 | 2161 44 | 633 92 |
| 173 | 2168 35 | 641 15 |
| 174 | 2175 20 | 648 43 |
| 175 | 2181 98 | 665 78 |
| 176 | 2188 70 | 663 20 |
| 177 | 2194 74 | 670 00 |

Circle Center At X = 1385 6 , Y = 1383 5 and Radius, 1078 8
 *** 0 506 ***

Failure Surface Specified By 178 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 625 00 | 618 47 |
| 2 | 632 19 | 611 52 |
| 3 | 639 44 | 604 64 |
| 4 | 646 76 | 597 82 |
| 5 | 654 14 | 591 07 |
| 6 | 661 57 | 584 39 |
| 7 | 669 07 | 577 77 |
| 8 | 676 63 | 571 22 |
| 9 | 684 25 | 564 75 |
| 10 | 691 93 | 558 34 |
| 11 | 699 67 | 562 00 |
| 12 | 707 45 | 545 74 |
| 13 | 715 31 | 539 64 |
| 14 | 723 22 | 533 42 |
| 15 | 731 18 | 527 37 |
| 15 | 739 20 | 521 39 |
| 17 | 747 27 | 515 49 |
| 18 | 755 39 | 509 66 |
| 19 | 763 57 | 503 90 |
| 20 | 771 80 | 498 22 |
| 21 | 780 08 | 492 62 |
| 22 | 788 41 | 487 09 |
| 23 | 796 80 | 481 64 |
| 24 | 805 23 | 476 26 |
| 25 | 813 71 | 470 96 |
| 26 | 822 24 | 465 74 |
| 27 | 830 81 | 450 60 |
| 28 | 839 44 | 465 53 |
| 29 | 848 10 | 450 55 |
| 30 | 856 82 | 445 54 |
| 31 | 865 58 | 440 81 |
| 32 | 874 38 | 436 07 |
| 33 | 883 22 | 431 40 |
| 34 | 892 11 | 426 82 |
| 35 | 901 04 | 422 31 |
| 36 | 910 01 | 417 89 |
| 37 | 919 02 | 413 55 |

| | | |
|-----|---------|--------|
| 38 | 928 06 | 409 29 |
| 39 | 937 15 | 405 12 |
| 40 | 946 28 | 401 03 |
| 41 | 955 44 | 397 02 |
| 42 | 964 64 | 393 10 |
| 43 | 973 87 | 389 26 |
| 44 | 983 14 | 385 50 |
| 45 | 992 44 | 381 83 |
| 46 | 1001 77 | 378 24 |
| 47 | 1011 14 | 374 74 |
| 48 | 1020 54 | 371 33 |
| 49 | 1029 97 | 368 00 |
| 50 | 1039 43 | 364 76 |
| 51 | 1048 92 | 361 60 |
| 52 | 1058 44 | 358 53 |
| 53 | 1067 98 | 355 55 |
| 54 | 1077 55 | 352 66 |
| 55 | 1087 15 | 349 85 |
| 56 | 1096 77 | 347 13 |
| 57 | 1106 42 | 344 50 |
| 58 | 1116 09 | 341 95 |
| 59 | 1125 79 | 339 50 |
| 60 | 1136 50 | 337 13 |
| 61 | 1145 24 | 334 86 |
| 62 | 1155 00 | 332 67 |
| 63 | 1164 77 | 330 57 |
| 64 | 1174 67 | 328 56 |
| 65 | 1184 38 | 326 64 |
| 66 | 1194 22 | 324 81 |
| 67 | 1204 05 | 323 07 |
| 68 | 1213 93 | 321 42 |
| 69 | 1223 80 | 319 85 |
| 70 | 1233 69 | 318 38 |
| 71 | 1243 60 | 317 00 |
| 72 | 1253 51 | 315 71 |
| 73 | 1263 44 | 314 52 |
| 74 | 1273 38 | 313 41 |
| 75 | 1283 33 | 312 39 |
| 76 | 1293 29 | 311 46 |
| 77 | 1303 25 | 310 63 |
| 78 | 1313 22 | 309 88 |
| 79 | 1323 20 | 309 23 |
| 80 | 1333 19 | 308 67 |
| 81 | 1343 17 | 308 19 |
| 82 | 1353 17 | 307 81 |
| 83 | 1363 16 | 307 63 |
| 84 | 1373 16 | 307 33 |
| 85 | 1383 16 | 307 22 |
| 85 | 1393 16 | 307 21 |
| 87 | 1403 16 | 307 28 |
| 88 | 1413 16 | 307 46 |
| 89 | 1423 16 | 307 71 |
| 90 | 1433 15 | 308 06 |
| 91 | 1443 14 | 308 50 |
| 92 | 1453 13 | 309 03 |
| 93 | 1463 11 | 309 66 |
| 94 | 1473 08 | 310 37 |
| 96 | 1483 05 | 311 18 |
| 96 | 1493 01 | 312 08 |
| 97 | 1502 96 | 313 06 |
| 98 | 1512 90 | 314 14 |
| 99 | 1522 83 | 315 31 |
| 100 | 1532 75 | 316 57 |
| 101 | 1542 66 | 317 92 |
| 102 | 1552 56 | 319 36 |
| 103 | 1562 44 | 320 89 |
| 104 | 1572 31 | 322 52 |
| 105 | 1682 16 | 324 23 |

89/130

| | | |
|-----|---------|--------|
| 106 | 1592 00 | 326 03 |
| 107 | 1601 81 | 327 92 |
| 108 | 1611 62 | 329 90 |
| 109 | 1621 40 | 331 97 |
| 110 | 1631 16 | 334 13 |
| 111 | 1640 91 | 336 38 |
| 112 | 1650 63 | 338 71 |
| 113 | 1660 33 | 341 14 |
| 114 | 1670 01 | 343 65 |
| 115 | 1679 67 | 346 26 |
| 116 | 1689 30 | 348 95 |
| 117 | 1698 90 | 351 73 |
| 118 | 1708 48 | 354 59 |
| 119 | 1718 04 | 357 55 |
| 120 | 1727 56 | 360 59 |
| 121 | 1737 06 | 363 71 |
| 122 | 1746 53 | 366 93 |
| 123 | 1755 97 | 370 23 |
| 124 | 1765 38 | 373 61 |
| 126 | 1774 76 | 377 09 |
| 126 | 1784 11 | 380 64 |
| 127 | 1793 42 | 384 29 |
| 128 | 1802 70 | 388 02 |
| 129 | 1811 94 | 391 83 |
| 130 | 1821 15 | 395 72 |
| 131 | 1830 33 | 399 70 |
| 132 | 1839 46 | 403 77 |
| 133 | 1848 55 | 407 92 |
| 134 | 1857 62 | 412 15 |
| 135 | 1866 65 | 416 46 |
| 136 | 1875 63 | 420 85 |
| 137 | 1884 57 | 425 33 |
| 138 | 1893 47 | 429 89 |
| 139 | 1902 33 | 434 53 |
| 140 | 1911 14 | 439 25 |
| 141 | 1919 92 | 444 05 |
| 142 | 1928 65 | 448 93 |
| 143 | 1937 33 | 453 89 |
| 144 | 1945 97 | 458 93 |
| 145 | 1954 56 | 464 05 |
| 146 | 1963 10 | 469 24 |
| 147 | 1971 60 | 474 51 |
| 148 | 1980 05 | 479 87 |
| 149 | 1988 45 | 485 29 |
| 150 | 1996 79 | 490 80 |
| 151 | 2005 09 | 496 38 |
| 152 | 2013 34 | 502 03 |
| 153 | 2021 53 | 507 76 |
| 154 | 2029 68 | 513 57 |
| 155 | 2037 77 | 519 45 |
| 156 | 2045 80 | 525 40 |
| 157 | 2053 78 | 531 43 |
| 158 | 2061 71 | 537 53 |
| 159 | 2069 57 | 543 70 |
| 160 | 2077 39 | 549 94 |
| 161 | 2085 14 | 556 25 |
| 162 | 2092 84 | 562 64 |
| 163 | 2100 48 | 569 09 |
| 164 | 2108 06 | 675 62 |
| 165 | 2115 57 | 582 21 |
| 166 | 2123 03 | 588 87 |
| 167 | 2130 43 | 595 60 |
| 168 | 2137 77 | 602 40 |
| 169 | 2145 04 | 609 26 |
| 170 | 2162 25 | 616 19 |
| 171 | 2159 40 | 623 18 |
| 172 | 2155 48 | 630 24 |
| 173 | 2173 50 | 637 35 |


90/130

| | | |
|-----|---------|--------|
| 174 | 2180 45 | 644 55 |
| 175 | 2187 34 | 651 80 |
| 176 | 2194 16 | 659 12 |
| 177 | 2200 91 | 666 49 |
| 178 | 2204 07 | 670 00 |

Circle Center At X = 1389 8 , Y = 1402 4 and Radius, 1095 2
*** 0 607 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\ir\4 pl2 Run By: Greg Shafer, HDR 4/20/2010 02:56PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|
| a | 2.49 | | | | | | | |
| b | 2.53 | | | | | | | |
| c | 2.54 | UVSC | 1 | 113.5 | 121.0 | 50.0 | 29.0 | W1 |
| d | 2.59 | LSC | 2 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| e | 2.60 | SC | 3 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| f | 2.61 | LVSC | 4 | 121.0 | 125.5 | 50.0 | 29.0 | W1 |
| g | 2.63 | | | | | | | |
| h | 2.68 | | | | | | | |
| i | 2.74 | | | | | | | |
| i | 2.75 | | | | | | | |

✓ PMP 4-26.0

STED



PCSTABL7 FS_{min}=2.49
Safety Factors Are Calculated By The Modified Bishop Method

9/1/10

**** PCSTABL7 ****

by
 Purdue University
 --Slope Stability Analysis--
 Simplified Janbu, Simplified Bishop
 or Spencer s Method of Slices
 Run Date 4/20/2010
 Time of Run 02 56PM
 Run By Greg Shafer, HDR
 Input Data Filename C 4 in
 Output Filename C 4 OUT
 Unit ENGLISH
 Plotted Output Filename C 4 PLT
 PROBLEM DESCRIPTION Intermountain Regional Landfill
 Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
 Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
 6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 760 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |

93/130

| | | | | | |
|---|--------|--------|---------|--------|---|
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 6 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 6 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified
525 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced Along The Ground Surface Between X = 280 00 ft and X = 800 00 ft

Each Surface Terminates Between X = 850 00 ft and X = 2000 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 67 | 621 67 |
| 2 | 766 61 | 620 61 |
| 3 | 776 59 | 619 96 |
| 4 | 786 59 | 619 70 |
| 5 | 796 59 | 619 85 |
| 6 | 806 57 | 620 40 |
| 7 | 816 53 | 621 34 |
| 8 | 826 44 | 622 68 |
| 9 | 836 28 | 624 42 |
| 10 | 846 05 | 626 66 |
| 11 | 855 73 | 629 08 |
| 12 | 865 30 | 631 98 |
| 13 | 874 74 | 635 27 |
| 14 | 884 05 | 638 94 |
| 15 | 893 20 | 642 97 |
| 16 | 902 18 | 547 36 |
| 17 | 910 98 | 652 12 |
| 18 | 919 58 | 657 22 |
| 19 | 927 97 | 662 66 |
| 20 | 931 98 | 555 50 |

Circle Center At X = 788 0 , Y = 869 0 and Radius, 249 3
*** 2 493 ***

Individual data on the 25 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | Surcharge Load (lbs) |
| 1 | 9 9 | 1997 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 10 0 | 6792 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 10 0 | 9152 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 10 0 | 12052 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 10 0 | 14474 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 10 0 | 16405 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 9 9 | 17835 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 3 6 | 6697 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 6 3 | 12824 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 9 8 | 20250 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 9 7 | 20002 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

94/130

| | | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|-----|-----|-----|-----|
| 12 | 9 6 | 19247 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 4 7 | 9117 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 4 7 | 9244 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 9 3 | 17000 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 2 4 | 4124 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 6 7 | 10729 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 9 0 | 12309 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 4 9 | 5571 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 2 9 | 2960 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 1 0 | 977 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 22 | 8 5 | 6838 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 23 | 4 3 | 2149 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 24 | 4 1 | 1233 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 25 | 4 0 | 417 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 521 67 |
| 2 | 766 43 | 619 52 |
| 3 | 775 29 | 517 82 |
| 4 | 785 21 | 616 59 |
| 5 | 796 18 | 615 82 |
| 6 | 806 18 | 615 51 |
| 7 | 815 18 | 616 66 |
| 8 | 826 16 | 615 28 |
| 9 | 836 10 | 617 37 |
| 10 | 845 98 | 618 91 |
| 11 | 855 78 | 620 91 |
| 12 | 865 47 | 623 36 |
| 13 | 875 04 | 626 26 |
| 14 | 884 47 | 629 61 |
| 15 | 893 73 | 633 38 |
| 16 | 902 80 | 637 58 |
| 17 | 911 67 | 642 20 |
| 18 | 920 31 | 647 23 |
| 19 | 928 72 | 652 65 |
| 20 | 936 86 | 658 46 |
| 21 | 944 72 | 664 64 |
| 22 | 950 93 | 670 00 |

Circle Center At X = 807 8 Y = 830 6 and Radius, 215 1
*** 2 533 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 67 | 621 67 |
| 2 | 766 67 | 621 53 |
| 3 | 776 66 | 621 75 |
| 4 | 786 65 | 522 32 |
| 5 | 796 60 | 523 24 |
| 6 | 806 62 | 624 52 |
| 7 | 816 39 | 626 14 |
| 8 | 826 19 | 628 12 |
| 9 | 835 92 | 630 44 |
| 10 | 846 56 | 633 11 |
| 11 | 855 10 | 636 11 |
| 12 | 864 52 | 639 45 |
| 13 | 873 82 | 543 12 |
| 14 | 882 99 | 547 12 |
| 15 | 892 01 | 651 44 |
| 16 | 900 87 | 656 08 |
| 17 | 906 00 | 659 00 |

Circle Center At X = 765 5 , Y = 903 8 and Radius, 282 3
*** 2 536 ***

Failure Surface Specified By 15 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 621 67 |
| 2 | 765 67 | 621 88 |

75/130

| | | |
|----|--------|--------|
| 3 | 776 65 | 622 43 |
| 4 | 786 61 | 623 33 |
| 5 | 796 53 | 624 57 |
| 6 | 806 41 | 626 14 |
| 7 | 816 22 | 628 06 |
| 8 | 825 97 | 630 30 |
| 9 | 836 63 | 632 88 |
| 10 | 845 20 | 635 79 |
| 11 | 854 56 | 639 02 |
| 12 | 854 01 | 642 58 |
| 13 | 873 23 | 646 46 |
| 14 | 882 31 | 650 64 |
| 16 | 891 24 | 655 13 |
| 16 | 891 83 | 655 46 |

Circle Center At X = 755 5 , Y = 913 7 and Radius, 292 0
*** 2 591 ***

Failure Surface Specified By 14 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 778 33 | 527 08 |
| 2 | 788 33 | 626 88 |
| 3 | 798 33 | 627 15 |
| 4 | 808 30 | 627 90 |
| 5 | 818 23 | 629 11 |
| 6 | 828 09 | 630 78 |
| 7 | 837 85 | 632 92 |
| 8 | 847 51 | 635 52 |
| 9 | 857 04 | 638 57 |
| 10 | 866 41 | 642 06 |
| 11 | 875 60 | 645 99 |
| 12 | 884 60 | 650 35 |
| 13 | 893 38 | 655 13 |
| 14 | 895 39 | 656 35 |

Circle Center At X = 787 6 , Y = 838 6 and Radius, 211 8
*** 2 604 ***

Failure Surface Specified By 13 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 67 | 621 67 |
| 2 | 766 56 | 620 20 |
| 3 | 776 53 | 619 44 |
| 4 | 786 53 | 619 41 |
| 5 | 796 51 | 620 10 |
| 6 | 806 41 | 621 50 |
| 7 | 816 18 | 623 61 |
| 8 | 825 78 | 626 42 |
| 9 | 835 15 | 629 92 |
| 10 | 844 24 | 634 08 |
| 11 | 853 01 | 638 88 |
| 12 | 861 41 | 644 31 |
| 13 | 868 47 | 649 62 |

Circle Center At X = 782 0 , Y = 758 1 and Radius, 138 8
*** 2 609 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 800 00 | 532 50 |
| 2 | 809 68 | 630 00 |
| 3 | 819 51 | 628 15 |
| 4 | 829 44 | 626 96 |
| 5 | 839 43 | 626 42 |
| 6 | 849 42 | 626 55 |
| 7 | 859 39 | 627 33 |
| 8 | 869 29 | 628 77 |
| 9 | 879 07 | 630 87 |
| 10 | 888 69 | 633 60 |
| 11 | 898 10 | 636 97 |
| 12 | 907 28 | 640 95 |

9/6/30

| | | |
|----|--------|--------|
| 13 | 916 17 | 645 53 |
| 14 | 924 73 | 650 69 |
| 16 | 932 94 | 556 40 |
| 16 | 940 75 | 662 64 |
| 17 | 948 14 | 569 39 |
| 18 | 948 32 | 569 58 |

Circle Center At X = 842 6 , Y = 777 5 and Radius, 151 1
 *** 2 631 ***

Failure Surface Specified By 12 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 800 00 | 632 50 |
| 2 | 809 84 | 630 69 |
| 3 | 819 80 | 629 82 |
| 4 | 829 80 | 629 89 |
| 5 | 839 75 | 630 90 |
| 6 | 849 55 | 532 86 |
| 7 | 859 14 | 535 71 |
| 8 | 868 40 | 639 46 |
| 9 | 877 28 | 644 07 |
| 10 | 885 68 | 649 50 |
| 11 | 893 52 | 655 70 |
| 12 | 893 78 | 655 95 |

Circle Center At X = 824 1 , Y = 735 5 and Radius, 105 8
 *** 2 678 ***

Failure Surface Specified By 25 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 735 00 | 619 82 |
| 2 | 744 09 | 615 66 |
| 3 | 753 41 | 612 03 |
| 4 | 762 92 | 608 94 |
| 5 | 772 60 | 606 40 |
| 6 | 782 40 | 604 43 |
| 7 | 792 30 | 603 02 |
| 8 | 802 26 | 602 19 |
| 9 | 812 26 | 601 93 |
| 10 | 822 26 | 602 24 |
| 11 | 832 22 | 603 13 |
| 12 | 842 11 | 604 60 |
| 13 | 861 90 | 606 63 |
| 14 | 861 56 | 609 22 |
| 15 | 871 05 | 612 36 |
| 16 | 880 35 | 616 04 |
| 17 | 889 42 | 520 25 |
| 18 | 898 23 | 624 98 |
| 19 | 906 76 | 530 21 |
| 20 | 914 97 | 636 92 |
| 21 | 922 84 | 642 09 |
| 22 | 930 34 | 648 70 |
| 23 | 937 44 | 655 74 |
| 24 | 944 13 | 663 17 |
| 25 | 949 50 | 659 88 |

Circle Center At X = 811 8 , Y = 775 6 and Radius, 173 6
 *** 2 736 ***

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 713 33 | 619 55 |
| 2 | 722 97 | 616 87 |
| 3 | 732 72 | 614 66 |
| 4 | 742 57 | 612 95 |
| 5 | 752 50 | 611 72 |
| 6 | 762 47 | 610 99 |
| 7 | 772 47 | 610 76 |
| 8 | 782 46 | 611 02 |
| 9 | 792 44 | 611 78 |
| 10 | 802 36 | 613 04 |


97/130

| | | |
|----|--------|--------|
| 11 | 812 20 | 614 79 |
| 12 | 821 95 | 617 02 |
| 13 | 831 67 | 619 73 |
| 14 | 841 05 | 622 92 |
| 15 | 850 35 | 626 58 |
| 16 | 859 47 | 630 69 |
| 17 | 868 37 | 635 26 |
| 18 | 877 03 | 640 26 |
| 19 | 885 44 | 645 68 |
| 20 | 893 56 | 651 51 |
| 21 | 901 38 | 657 74 |
| 22 | 901 54 | 657 89 |

Circle Center At X = 772 2 , Y = 811 9 and Radius, 201 2
*** 2 749 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\l15 pl2 Run By Greg Shafer, HDR 4/20/2010 03:00PM



STED



PCSTABL7 FSmin=1.75
Safety Factors Are Calculated By The Modified Bishop Method

98/30

99/130

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 00PM
Run By Greg Shafer, HDR
Input Data Filename C 5 in
Output Filename C 5 OUT
Unit ENGLISH
Plotted Output Filename C 5 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
5 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 650 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 6 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of 0 100 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 500 00 ft
and X = 800 00 ft
Each Surface Terminates Between X = 850 00 ft
and X =1500 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial
Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 619 69 |
| 2 | 734 94 | 518 63 |
| 3 | 744 91 | 617 82 |
| 4 | 754 90 | 617 27 |
| 5 | 764 89 | 616 97 |
| 6 | 774 89 | 616 94 |
| 7 | 784 89 | 617 16 |
| 8 | 794 88 | 617 64 |

100/130

| | | |
|----|--------|--------|
| 9 | 804 85 | 618 37 |
| 10 | 814 80 | 619 37 |
| 11 | 824 72 | 620 62 |
| 12 | 834 61 | 622 12 |
| 13 | 844 45 | 623 88 |
| 14 | 854 25 | 625 89 |
| 15 | 863 99 | 628 16 |
| 16 | 873 67 | 630 67 |
| 17 | 883 28 | 633 44 |
| 18 | 892 81 | 636 45 |
| 19 | 902 27 | 639 70 |
| 20 | 911 54 | 643 20 |
| 21 | 920 91 | 646 94 |
| 22 | 930 09 | 650 92 |
| 23 | 939 16 | 655 13 |
| 24 | 948 11 | 659 58 |
| 25 | 956 95 | 564 26 |
| 26 | 965 67 | 669 15 |
| 27 | 957 10 | 670 00 |

Circle Center At X = 771 3 , Y = 1004 7 and Radius, 387 8
 *** 1 754 ***

Individual data on the 34 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 9 | 714 3 | 0 0 | 0 0 | 0 0 | 0 0 | 71 4 | 0 0 | 0 0 |
| 2 | 10 0 | 1993 6 | 0 0 | 0 0 | 0 0 | 0 0 | 199 4 | 0 0 | 0 0 |
| 3 | 5 1 | 1410 4 | 0 0 | 0 0 | 0 0 | 0 0 | 141 0 | 0 0 | 0 0 |
| 4 | 4 9 | 1783 2 | 0 0 | 0 0 | 0 0 | 0 0 | 178 3 | 0 0 | 0 0 |
| 5 | 10 0 | 6073 3 | 0 0 | 0 0 | 0 0 | 0 0 | 607 3 | 0 0 | 0 0 |
| 6 | 10 0 | 9100 5 | 0 0 | 0 0 | 0 0 | 0 0 | 910 1 | 0 0 | 0 0 |
| 7 | 10 0 | 11830 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1183 0 | 0 0 | 0 0 |
| 8 | 10 0 | 14254 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1425 4 | 0 0 | 0 0 |
| 9 | 10 0 | 16368 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1636 8 | 0 0 | 0 0 |
| 10 | 10 0 | 18167 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1816 7 | 0 0 | 0 0 |
| 11 | 9 9 | 19649 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1964 9 | 0 0 | 0 0 |
| 12 | 5 3 | 10975 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1097 6 | 0 0 | 0 0 |
| 13 | 4 6 | 10465 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1046 6 | 0 0 | 0 0 |
| 14 | 9 8 | 22909 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2290 9 | 0 0 | 0 0 |
| 15 | 9 8 | 23289 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2329 0 | 0 0 | 0 0 |
| 16 | 9 7 | 23337 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2333 8 | 0 0 | 0 0 |
| 17 | 6 0 | 14357 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1435 7 | 0 0 | 0 0 |
| 18 | 3 7 | 8975 2 | 0 0 | 0 0 | 0 0 | 0 0 | 897 5 | 0 0 | 0 0 |
| 19 | 9 6 | 23176 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2317 7 | 0 0 | 0 0 |
| 20 | 9 5 | 22256 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2225 6 | 0 0 | 0 0 |
| 21 | 9 5 | 21029 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2103 0 | 0 0 | 0 0 |
| 22 | 0 8 | 1704 4 | 0 0 | 0 0 | 0 0 | 0 0 | 170 4 | 0 0 | 0 0 |
| 23 | 6 9 | 14505 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1450 5 | 0 0 | 0 0 |
| 24 | 1 6 | 3423 1 | 0 0 | 0 0 | 0 0 | 0 0 | 342 3 | 0 0 | 0 0 |
| 26 | 9 3 | 18403 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1840 3 | 0 0 | 0 0 |
| 26 | 7 1 | 12733 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1273 3 | 0 0 | 0 0 |
| 27 | 2 1 | 3591 4 | 0 0 | 0 0 | 0 0 | 0 0 | 359 1 | 0 0 | 0 0 |
| 28 | 9 1 | 13990 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1399 1 | 0 0 | 0 0 |
| 29 | 9 0 | 11418 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1141 8 | 0 0 | 0 0 |
| 30 | 0 8 | 898 2 | 0 0 | 0 0 | 0 0 | 0 0 | 89 8 | 0 0 | 0 0 |
| 31 | 1 1 | 1178 0 | 0 0 | 0 0 | 0 0 | 0 0 | 117 8 | 0 0 | 0 0 |
| 32 | 7 0 | 5989 5 | 0 0 | 0 0 | 0 0 | 0 0 | 598 9 | 0 0 | 0 0 |
| 33 | 8 7 | 3265 2 | 0 0 | 0 0 | 0 0 | 0 0 | 326 5 | 0 0 | 0 0 |
| 34 | 1 4 | 68 7 | 0 0 | 0 0 | 0 0 | 0 0 | 6 9 | 0 0 | 0 0 |

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 42 | 521 87 |
| 3 | 782 39 | 621 08 |
| 4 | 792 38 | 620 74 |
| 5 | 802 38 | 520 85 |

101/130

| | | |
|----|--------|--------|
| 6 | 812 37 | 621 43 |
| 7 | 822 31 | 622 45 |
| 8 | 832 20 | 623 94 |
| 9 | 842 02 | 625 87 |
| 10 | 851 73 | 628 24 |
| 11 | 861 32 | 631 06 |
| 12 | 870 78 | 634 31 |
| 13 | 880 08 | 637 99 |
| 14 | 889 20 | 642 10 |
| 15 | 898 12 | 646 61 |
| 16 | 906 83 | 551 53 |
| 17 | 915 30 | 656 84 |
| 18 | 923 53 | 662 53 |
| 19 | 925 20 | 663 80 |

Circle Center At X = 794 8 , Y = 839 7 and Radius, 219 0
*** 1 762 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 769 73 | 517 68 |
| 3 | 769 58 | 615 95 |
| 4 | 779 51 | 614 82 |
| 5 | 789 50 | 614 28 |
| 6 | 799 50 | 614 35 |
| 7 | 809 48 | 615 01 |
| 8 | 819 40 | 616 27 |
| 9 | 829 22 | 618 13 |
| 10 | 838 92 | 620 57 |
| 11 | 848 45 | 623 59 |
| 12 | 857 79 | 627 17 |
| 13 | 866 89 | 631 31 |
| 14 | 875 73 | 635 99 |
| 15 | 884 27 | 641 19 |
| 16 | 892 48 | 646 90 |
| 17 | 900 34 | 653 08 |
| 18 | 907 38 | 659 34 |

Circle Center At X = 793 4 , Y = 780 7 and Radius, 166 5
*** 1 810 ***

Failure Surface Specified By 24 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 92 | 621 23 |
| 3 | 769 83 | 622 57 |
| 4 | 779 73 | 623 99 |
| 5 | 789 62 | 625 52 |
| 6 | 799 48 | 627 14 |
| 7 | 809 33 | 628 86 |
| 8 | 819 17 | 630 58 |
| 9 | 828 98 | 632 59 |
| 10 | 838 78 | 634 60 |
| 11 | 848 56 | 636 70 |
| 12 | 858 31 | 638 90 |
| 13 | 868 04 | 641 20 |
| 14 | 877 75 | 643 59 |
| 15 | 887 44 | 645 08 |
| 16 | 897 10 | 648 66 |
| 17 | 906 74 | 651 34 |
| 18 | 916 34 | 654 11 |
| 19 | 925 92 | 656 97 |
| 20 | 935 48 | 659 93 |
| 21 | 945 00 | 662 98 |
| 22 | 954 49 | 666 13 |
| 23 | 963 95 | 669 37 |
| 24 | 965 75 | 670 00 |

Circle Center At X = 629 3 , Y = 1631 4 and Radius, 1018 5
*** 1 818 ***

102/170

Failure Surface Specified By 16 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 42 | 618 58 |
| 3 | 767 39 | 617 84 |
| 4 | 767 39 | 617 63 |
| 6 | 777 39 | 617 95 |
| 6 | 787 35 | 618 81 |
| 7 | 797 25 | 620 19 |
| 8 | 807 07 | 622 10 |
| 9 | 815 77 | 624 52 |
| 10 | 826 33 | 627 45 |
| 11 | 835 72 | 630 89 |
| 12 | 844 92 | 634 82 |
| 13 | 853 89 | 639 24 |
| 14 | 862 62 | 644 12 |
| 15 | 871 07 | 649 46 |
| 16 | 872 83 | 650 71 |

Circle Center At X = 766 3 , Y = 805 6 and Radius, 188 0
*** 1 823 ***

Failure Surface Specified By 13 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 45 | 628 36 |
| 3 | 807 44 | 628 03 |
| 4 | 817 44 | 628 38 |
| 5 | 827 38 | 629 41 |
| 6 | 837 24 | 631 12 |
| 7 | 846 95 | 533 51 |
| 8 | 856 47 | 636 55 |
| 9 | 865 77 | 640 23 |
| 10 | 874 79 | 644 54 |
| 11 | 883 50 | 649 46 |
| 12 | 891 86 | 654 96 |
| 13 | 892 83 | 655 71 |

Circle Center At X = 807 3 , Y = 774 2 and Radius, 146 1
*** 1 833 ***

Failure Surface Specified By 25 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 50 | 622 98 |
| 3 | 782 50 | 623 02 |
| 4 | 792 50 | 623 25 |
| 5 | 802 49 | 623 67 |
| 6 | 812 47 | 624 28 |
| 7 | 822 44 | 525 07 |
| 8 | 832 39 | 626 06 |
| 9 | 842 32 | 627 22 |
| 10 | 852 23 | 628 58 |
| 11 | 862 11 | 630 12 |
| 12 | 871 95 | 631 85 |
| 13 | 881 77 | 633 75 |
| 14 | 891 55 | 636 85 |
| 16 | 901 29 | 638 13 |
| 16 | 910 98 | 540 59 |
| 17 | 920 63 | 643 24 |
| 18 | 930 22 | 646 06 |
| 19 | 939 76 | 649 07 |
| 20 | 949 24 | 552 25 |
| 21 | 958 66 | 655 61 |
| 22 | 968 01 | 659 15 |
| 23 | 977 30 | 662 86 |
| 24 | 986 51 | 566 74 |
| 25 | 993 84 | 670 00 |

Circle Center At X = 775 2 , Y = 1154 9 and Radius, 532 0

*** 1 850 ***
 Failure Surface Specified By 14 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 775 00 | 626 26 |
| 2 | 784 73 | 623 95 |
| 3 | 794 62 | 622 44 |
| 4 | 804 59 | 621 74 |
| 5 | 814 59 | 621 85 |
| 5 | 824 55 | 522 77 |
| 7 | 834 40 | 624 49 |
| 8 | 844 08 | 627 00 |
| 9 | 853 52 | 630 29 |
| 10 | 862 67 | 634 33 |
| 11 | 871 46 | 639 10 |
| 12 | 879 83 | 544 57 |
| 13 | 887 74 | 650 70 |
| 14 | 893 37 | 655 84 |

Circle Center At X = 808 2 , Y = 744 8 and Radius, 123 1

*** 1 851 ***
 Failure Surface Specified By 32 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 675 00 | 619 08 |
| 2 | 684 96 | 618 20 |
| 3 | 594 94 | 617 49 |
| 4 | 704 92 | 616 96 |
| 5 | 714 92 | 616 60 |
| 6 | 724 91 | 616 42 |
| 7 | 734 91 | 616 42 |
| 8 | 744 91 | 616 60 |
| 9 | 754 91 | 616 96 |
| 10 | 764 89 | 617 48 |
| 11 | 774 87 | 618 18 |
| 12 | 784 83 | 619 07 |
| 13 | 794 77 | 620 12 |
| 14 | 804 70 | 621 36 |
| 15 | 814 60 | 622 77 |
| 16 | 824 47 | 624 35 |
| 17 | 834 31 | 626 11 |
| 18 | 844 13 | 628 04 |
| 19 | 853 90 | 630 15 |
| 20 | 863 64 | 632 42 |
| 21 | 873 33 | 634 87 |
| 22 | 882 98 | 637 50 |
| 23 | 892 59 | 640 29 |
| 24 | 902 14 | 643 25 |
| 25 | 911 64 | 646 38 |
| 26 | 921 08 | 649 67 |
| 27 | 930 46 | 653 14 |
| 28 | 939 78 | 656 77 |
| 29 | 949 03 | 660 56 |
| 30 | 958 21 | 664 52 |
| 31 | 967 33 | 668 63 |
| 32 | 970 21 | 670 00 |

Circle Center At X = 730 0 , Y = 1181 4 and Radius, 565 0

*** 1 856 ***
 Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 523 13 |
| 2 | 771 98 | 619 93 |
| 3 | 781 62 | 617 30 |
| 4 | 791 41 | 615 22 |
| 5 | 801 29 | 613 72 |
| 6 | 811 25 | 612 80 |
| 7 | 821 24 | 612 46 |
| 8 | 831 24 | 612 69 |


102/130

| | | |
|----|--------|--------|
| 9 | 841 21 | 513 51 |
| 10 | 851 11 | 614 91 |
| 11 | 860 91 | 616 88 |
| 12 | 870 59 | 619 41 |
| 13 | 880 10 | 522 50 |
| 14 | 889 41 | 626 14 |
| 15 | 898 50 | 630 32 |
| 16 | 907 33 | 535 01 |
| 17 | 915 87 | 540 21 |
| 18 | 924 09 | 645 90 |
| 19 | 931 98 | 652 06 |
| 20 | 939 48 | 658 66 |
| 21 | 946 60 | 665 69 |
| 22 | 950 48 | 670 00 |

Circle Center At X = 822 1 , Y = 784 3 and Radius, 171 9
*** 1 858 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\l16 pl2 Run By Greg Shafer, HDR 4/20/2010 03 03PM



PCSTABL7 FSmin=1.33

Safety Factors Are Calculated By The Modified Bishop Method

STED



04/20/10

** PCSTABL7 **
 by
 Purdue University
 --Slope Stability Analysis--
 Simplified Janbu, Simplified Bishop
 or Spencer s Method of Slices

Run Date 4/20/2010
 Time of Run 03 03PM
 Run By Greg Shafer, HDR
 Input Data Filename C 6 in
 Output Filename C 6 OUT
 Unit ENGLISH
 Plotted Output Filename C 5 PLT
 PROBLEM DESCRIPTION Intermountain Regional Landfill
 Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below End |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 60 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 570 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 660 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient

Of 0 200 Has Been Assigned

A Vertical Earthquake Loading Coefficient

Of 0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random

Technique For Generating Circular Surfaces, Has Been Specified

626 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced

Along The Ground Surface Between X = 500 00 ft

and X = 800 00 ft

Each Surface Terminates Between X = 850 00 ft

and X =1500 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation

At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 23 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 40 | 618 45 |
| 3 | 757 35 | 617 41 |
| 4 | 767 33 | 616 75 |
| 5 | 777 32 | 616 45 |
| 6 | 787 32 | 616 52 |
| 7 | 797 31 | 616 96 |
| 8 | 807 28 | 617 77 |

| | | |
|----|--------|--------|
| 9 | 817 21 | 618 95 |
| 10 | 827 09 | 620 49 |
| 11 | 836 91 | 622 40 |
| 12 | 846 65 | 624 67 |
| 13 | 856 29 | 527 30 |
| 14 | 865 84 | 630 28 |
| 15 | 875 27 | 633 61 |
| 16 | 884 57 | 637 28 |
| 17 | 893 73 | 641 30 |
| 18 | 902 73 | 645 66 |
| 19 | 911 56 | 650 34 |
| 20 | 920 22 | 655 34 |
| 21 | 928 59 | 660 67 |
| 22 | 936 95 | 666 30 |
| 23 | 937 86 | 666 96 |

Circle Center At X = 780 4 , Y = 887 2 and Radius, 270 8

*** 1 331 ***

Individual data on the 29 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 9 | 911 2 | 0 0 | 0 0 | 0 0 | 0 0 | 182 2 | 0 0 | 0 0 |
| 2 | 2 6 | 525 6 | 0 0 | 0 0 | 0 0 | 0 0 | 105 1 | 0 0 | 0 0 |
| 3 | 7 3 | 2605 1 | 0 0 | 0 0 | 0 0 | 0 0 | 521 0 | 0 0 | 0 0 |
| 4 | 10 0 | 6799 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1359 9 | 0 0 | 0 0 |
| 6 | 10 0 | 10190 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2038 1 | 0 0 | 0 0 |
| 6 | 10 0 | 13158 9 | 0 0 | 0 0 | 0 0 | 0 0 | 2631 8 | 0 0 | 0 0 |
| 7 | 10 0 | 15688 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3137 7 | 0 0 | 0 0 |
| 8 | 10 0 | 17766 5 | 0 0 | 0 0 | 0 0 | 0 0 | 3553 3 | 0 0 | 0 0 |
| 9 | 9 9 | 19384 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3876 9 | 0 0 | 0 0 |
| 10 | 9 9 | 20537 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4107 6 | 0 0 | 0 0 |
| 11 | 2 9 | 6229 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1246 0 | 0 0 | 0 0 |
| 12 | 6 9 | 15942 9 | 0 0 | 0 0 | 0 0 | 0 0 | 3188 6 | 0 0 | 0 0 |
| 13 | 9 7 | 22656 9 | 0 0 | 0 0 | 0 0 | 0 0 | 4531 4 | 0 0 | 0 0 |
| 14 | 9 6 | 22243 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4448 7 | 0 0 | 0 0 |
| 15 | 9 5 | 21366 5 | 0 0 | 0 0 | 0 0 | 0 0 | 4273 3 | 0 0 | 0 0 |
| 16 | 4 2 | 9000 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1800 2 | 0 0 | 0 0 |
| 17 | 5 3 | 11437 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2287 5 | 0 0 | 0 0 |
| 18 | 9 3 | 18993 9 | 0 0 | 0 0 | 0 0 | 0 0 | 3798 8 | 0 0 | 0 0 |
| 19 | 6 2 | 11607 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2321 5 | 0 0 | 0 0 |
| 20 | 3 0 | 5231 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1046 2 | 0 0 | 0 0 |
| 21 | 9 0 | 14314 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2862 9 | 0 0 | 0 0 |
| 22 | 7 3 | 9630 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1926 1 | 0 0 | 0 0 |
| 23 | 0 9 | 1160 9 | 0 0 | 0 0 | 0 0 | 0 0 | 232 2 | 0 0 | 0 0 |
| 24 | 0 6 | 781 3 | 0 0 | 0 0 | 0 0 | 0 0 | 156 3 | 0 0 | 0 0 |
| 25 | 8 7 | 8946 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1789 4 | 0 0 | 0 0 |
| 26 | 7 4 | 5013 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1002 8 | 0 0 | 0 0 |
| 27 | 1 1 | 505 5 | 0 0 | 0 0 | 0 0 | 0 0 | 101 1 | 0 0 | 0 0 |
| 28 | 8 3 | 2086 2 | 0 0 | 0 0 | 0 0 | 0 0 | 417 2 | 0 0 | 0 0 |
| 29 | 0 9 | 22 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4 5 | 0 0 | 0 0 |

Failure Surface Specified By 21 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 520 00 |
| 2 | 759 99 | 620 33 |
| 3 | 769 98 | 620 89 |
| 4 | 779 95 | 621 67 |
| 5 | 789 90 | 622 59 |
| 6 | 799 82 | 623 92 |
| 7 | 809 71 | 625 38 |
| 8 | 819 57 | 627 06 |
| 9 | 829 39 | 628 97 |
| 10 | 839 16 | 631 10 |
| 11 | 848 88 | 533 45 |
| 12 | 858 54 | 635 02 |
| 13 | 868 15 | 638 81 |
| 14 | 877 68 | 541 81 |

| | | |
|----|--------|--------|
| 15 | 887 15 | 645 03 |
| 16 | 896 54 | 648 47 |
| 17 | 905 85 | 552 11 |
| 18 | 915 08 | 655 97 |
| 19 | 924 22 | 660 03 |
| 20 | 933 26 | 664 30 |
| 21 | 939 31 | 667 33 |

Circle Center At X = 740 4 , Y = 1061 1 and Radius, 441 2
 *** 1 333 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 775 00 | 626 25 |
| 2 | 784 95 | 625 29 |
| 3 | 794 94 | 624 75 |
| 4 | 804 94 | 624 61 |
| 5 | 814 94 | 624 89 |
| 6 | 824 91 | 625 57 |
| 7 | 834 85 | 626 67 |
| 8 | 844 74 | 628 17 |
| 9 | 854 55 | 630 08 |
| 10 | 864 28 | 632 38 |
| 11 | 873 91 | 635 09 |
| 12 | 883 42 | 638 19 |
| 13 | 892 79 | 641 68 |
| 14 | 902 01 | 645 54 |
| 15 | 911 07 | 649 79 |
| 15 | 919 94 | 654 40 |
| 17 | 928 62 | 559 37 |
| 18 | 937 08 | 664 70 |
| 19 | 941 82 | 667 96 |

Circle Center At X = 803 2 , Y = 858 1 and Radius, 243 5
 *** 1 337 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 99 | 619 63 |
| 3 | 769 99 | 619 62 |
| 4 | 779 99 | 519 99 |
| 5 | 789 96 | 620 72 |
| 6 | 799 90 | 621 82 |
| 7 | 809 79 | 623 29 |
| 8 | 819 62 | 625 13 |
| 9 | 829 38 | 627 32 |
| 10 | 839 04 | 629 88 |
| 11 | 848 61 | 632 79 |
| 12 | 858 06 | 636 06 |
| 13 | 867 39 | 639 66 |
| 14 | 876 58 | 643 61 |
| 16 | 885 61 | 647 90 |
| 16 | 894 48 | 652 52 |
| 17 | 903 17 | 657 47 |
| 18 | 906 41 | 658 85 |

Circle Center At X = 765 1 , Y = 889 7 and Radius, 270 1
 *** 1 342 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 88 | 618 44 |
| 3 | 769 82 | 617 35 |
| 4 | 779 80 | 616 74 |
| 6 | 789 80 | 616 61 |
| 6 | 799 79 | 616 95 |
| 7 | 809 75 | 517 78 |
| 8 | 819 67 | 619 08 |
| 9 | 829 52 | 620 85 |

109/130

| | | |
|----|--------|--------|
| 10 | 839 26 | 623 09 |
| 11 | 848 89 | 625.79 |
| 12 | 858 38 | 628 95 |
| 13 | 867 70 | 632 56 |
| 14 | 876 85 | 636 61 |
| 15 | 885 79 | 641 10 |
| 16 | 894 50 | 646 00 |
| 17 | 902 97 | 651 32 |
| 18 | 911 18 | 657 03 |
| 19 | 917 45 | 661 86 |

Circle Center At X = 787 6 , Y = 825 8 and Radius, 209 2
*** 1 348 ***

Failure Surface Specified By 26 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 619 19 |
| 3 | 769 95 | 618 63 |
| 4 | 779 95 | 618 32 |
| 5 | 789 95 | 618 26 |
| 5 | 799 94 | 618 45 |
| 7 | 809 93 | 618 90 |
| 8 | 819 91 | 619 60 |
| 9 | 829 86 | 620 56 |
| 10 | 839 79 | 621 75 |
| 11 | 849 69 | 623 20 |
| 12 | 859 54 | 624 91 |
| 13 | 869 35 | 626 86 |
| 14 | 879 10 | 629 05 |
| 15 | 888 80 | 631 49 |
| 16 | 898 43 | 634 18 |
| 17 | 908 00 | 637 11 |
| 18 | 917 48 | 640 27 |
| 19 | 926 88 | 643 68 |
| 20 | 936 20 | 647 32 |
| 21 | 945 41 | 651 20 |
| 22 | 954 53 | 655 31 |
| 23 | 963 64 | 659 64 |
| 24 | 972 44 | 664 21 |
| 25 | 981 22 | 668 99 |
| 26 | 982 97 | 670 00 |

Circle Center At X = 787 2 , Y = 1014 3 and Radius, 396 1
*** 1 348 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 50 | 623 22 |
| 3 | 782 49 | 623 63 |
| 4 | 792 47 | 624 36 |
| 5 | 802 41 | 625 40 |
| 6 | 812 32 | 626 75 |
| 7 | 822 18 | 628 42 |
| 8 | 831 98 | 630 40 |
| 9 | 841 72 | 632 69 |
| 10 | 851 37 | 635 28 |
| 11 | 850 94 | 638 18 |
| 12 | 870 42 | 641 38 |
| 13 | 879 79 | 644 88 |
| 14 | 889 04 | 648 67 |
| 15 | 898 17 | 652 76 |
| 16 | 907 16 | 657 13 |
| 17 | 915 00 | 661 25 |

Circle Center At X = 764 5 , Y = 939 2 and Radius, 316 1
*** 1 356 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
|----------|-------------|-------------|

110/130

| | | |
|----|--------|--------|
| 1 | 800 00 | 632 50 |
| 2 | 809 99 | 532 02 |
| 3 | 819 99 | 631 87 |
| 4 | 829 99 | 632 03 |
| 5 | 839 97 | 632 51 |
| 6 | 849 94 | 633 32 |
| 7 | 859 88 | 634 44 |
| 8 | 869 78 | 635 88 |
| 9 | 879 62 | 637 63 |
| 10 | 889 40 | 639 70 |
| 11 | 899 12 | 642 09 |
| 12 | 908 75 | 644 78 |
| 13 | 918 29 | 647 78 |
| 14 | 927 73 | 651 08 |
| 15 | 937 05 | 654 68 |
| 16 | 945 26 | 658 58 |
| 17 | 955 34 | 662 77 |
| 18 | 964 28 | 667 26 |
| 19 | 959 35 | 670 00 |

Circle Center At X = 819 9 , Y = 944 2 and Radius, 312 3
*** 1 361 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 38 | 621 60 |
| 3 | 782 34 | 620 62 |
| 4 | 792 33 | 620 19 |
| 5 | 802 33 | 620 30 |
| 6 | 812 30 | 620 96 |
| 7 | 822 23 | 622 17 |
| 8 | 832 08 | 623 92 |
| 9 | 841 81 | 626 20 |
| 10 | 861 41 | 629 02 |
| 11 | 860 84 | 632 35 |
| 12 | 870 07 | 636 20 |
| 13 | 879 07 | 640 55 |
| 14 | 887 83 | 645 38 |
| 15 | 895 30 | 660 68 |
| 16 | 904 48 | 656 44 |
| 17 | 908 51 | 559 63 |

Circle Center At X = 795 2 , Y = 802 8 and Radius, 182 6
*** 1 361 ***


Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 800 00 | 632 50 |
| 2 | 809 98 | 633 11 |
| 3 | 819 95 | 633 91 |
| 4 | 829 90 | 634 90 |
| 5 | 839 83 | 636 09 |
| 6 | 849 73 | 637 47 |
| 7 | 859 61 | 639 05 |
| 8 | 859 45 | 640 81 |
| 9 | 879 26 | 642 77 |
| 10 | 889 03 | 644 92 |
| 11 | 898 75 | 647 25 |
| 12 | 908 42 | 649 78 |
| 13 | 918 05 | 652 49 |
| 14 | 927 62 | 656 39 |
| 16 | 937 13 | 658 47 |
| 16 | 946 58 | 661 74 |
| 17 | 955 97 | 665 19 |
| 18 | 965 29 | 668 83 |
| 19 | 968 13 | 670 00 |

Circle Center At X = 773 7 , Y = 1146 1 and Radius, 514 3
*** 1 381 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\17 pl2 Run By Greg Shafer HDR 4/20/2010 03:06PM



STED



PCSTABL7 FSmin=1.06
Safety Factors Are Calculated By The Modified Bishop Method

11/1/10

112/30

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 06PM
Run By Greg Shafer, HDR
Input Data Filename C 7 in
Output Filename C 7 OUT
Unit ENGLISH
Plotted Output Filename C 7 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

| 3 Top Boundaries | | 5 Total Boundaries | | | |
|------------------|-------------|--------------------|--------------|--------------|---------------------|
| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
| 1 | 60 00 | 611 45 | 760 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 540 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

| 4 Type(s) of Soil | | | | | | | | | |
|-------------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|--|--|
| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No | | |
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |
| 3 | 121 0 | 125 6 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 | | |

A Horizontal Earthquake Loading Coefficient
Of0 300 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 500 00 ft
and X = 800 00 ft
Each Surface Terminates Between X = 850 00 ft
and X =1500 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial
Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 23 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 49 | 622 60 |
| 3 | 782 48 | 622 34 |
| 4 | 792 48 | 622 36 |
| 5 | 802 48 | 622 63 |
| 6 | 812 46 | 623 18 |
| 7 | 822 43 | 623 99 |
| 8 | 832 37 | 625 08 |

113/130

| | | |
|----|--------|--------|
| 9 | 842 28 | 626 42 |
| 10 | 852 15 | 628 04 |
| 11 | 861 97 | 529 92 |
| 12 | 871 74 | 632 06 |
| 13 | 881 45 | 634 46 |
| 14 | 891 09 | 637 12 |
| 15 | 900 65 | 640 04 |
| 16 | 910 13 | 643 21 |
| 17 | 919 63 | 646 64 |
| 18 | 928 83 | 650 32 |
| 19 | 938 02 | 654 25 |
| 20 | 947 11 | 658 42 |
| 21 | 956 08 | 662 84 |
| 22 | 964 93 | 667 49 |
| 23 | 969 41 | 670 00 |

Circle Center At X = 787 1 , Y = 995 0 and Radius, 372 6

*** 1 060 ***

Individual data on the 29 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 10 0 | 1712 8 | 0 0 | 0 0 | 0 0 | 0 0 | 513 8 | 0 0 | 0 0 |
| 2 | 10 0 | 4993 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1498 0 | 0 0 | 0 0 |
| 3 | 10 0 | 7972 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2391 6 | 0 0 | 0 0 |
| 4 | 10 0 | 10640 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3192 2 | 0 0 | 0 0 |
| 5 | 10 0 | 12991 2 | 0 0 | 0 0 | 0 0 | 0 0 | 3897 4 | 0 0 | 0 0 |
| 6 | 10 0 | 15018 3 | 0 0 | 0 0 | 0 0 | 0 0 | 4505 5 | 0 0 | 0 0 |
| 7 | 7 6 | 12584 2 | 0 0 | 0 0 | 0 0 | 0 0 | 3775 2 | 0 0 | 0 0 |
| 8 | 2 4 | 4401 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1320 4 | 0 0 | 0 0 |
| 9 | 9 9 | 19145 8 | 0 0 | 0 0 | 0 0 | 0 0 | 5743 7 | 0 0 | 0 0 |
| 10 | 9 9 | 20069 7 | 0 0 | 0 0 | 0 0 | 0 0 | 6020 9 | 0 0 | 0 0 |
| 11 | 9 8 | 20643 4 | 0 0 | 0 0 | 0 0 | 0 0 | 6193 0 | 0 0 | 0 0 |
| 12 | 8 0 | 17138 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5141 6 | 0 0 | 0 0 |
| 13 | 1 7 | 3861 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1158 5 | 0 0 | 0 0 |
| 14 | 9 7 | 21482 0 | 0 0 | 0 0 | 0 0 | 0 0 | 6444 6 | 0 0 | 0 0 |
| 15 | 9 6 | 21024 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6307 3 | 0 0 | 0 0 |
| 16 | 9 4 | 19969 9 | 0 0 | 0 0 | 0 0 | 0 0 | 6991 0 | 0 0 | 0 0 |
| 17 | 0 1 | 267 3 | 0 0 | 0 0 | 0 0 | 0 0 | 80 2 | 0 0 | 0 0 |
| 18 | 9 3 | 18868 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5660 4 | 0 0 | 0 0 |
| 19 | 0 1 | 272 1 | 0 0 | 0 0 | 0 0 | 0 0 | 81 6 | 0 0 | 0 0 |
| 20 | 9 4 | 18418 9 | 0 0 | 0 0 | 0 0 | 0 0 | 5525 7 | 0 0 | 0 0 |
| 21 | 8 5 | 15305 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4591 7 | 0 0 | 0 0 |
| 22 | 0 8 | 1393 7 | 0 0 | 0 0 | 0 0 | 0 0 | 418 1 | 0 0 | 0 0 |
| 23 | 9 2 | 14697 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4409 1 | 0 0 | 0 0 |
| 24 | 9 1 | 12427 3 | 0 0 | 0 0 | 0 0 | 0 0 | 3728 2 | 0 0 | 0 0 |
| 25 | 2 9 | 3464 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1039 3 | 0 0 | 0 0 |
| 26 | 0 3 | 363 4 | 0 0 | 0 0 | 0 0 | 0 0 | 109 0 | 0 0 | 0 0 |
| 27 | 5 8 | 5515 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1684 7 | 0 0 | 0 0 |
| 28 | 8 9 | 4857 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1457 4 | 0 0 | 0 0 |
| 29 | 4 5 | 637 1 | 0 0 | 0 0 | 0 0 | 0 0 | 191 1 | 0 0 | 0 0 |

Failure Surface Specified By 28 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 712 50 | 519 54 |
| 2 | 722 44 | 618 46 |
| 3 | 732 41 | 617 61 |
| 4 | 742 39 | 617 01 |
| 5 | 752 38 | 616 66 |
| 6 | 762 38 | 616 53 |
| 7 | 772 38 | 616 65 |
| 8 | 782 37 | 617 02 |
| 9 | 792 35 | 617 63 |
| 10 | 802 32 | 618 48 |
| 11 | 812 26 | 519 57 |
| 12 | 822 17 | 620 90 |
| 13 | 832 04 | 622 47 |
| 14 | 841 88 | 624 28 |

114/130

| | | |
|----|--------|--------|
| 15 | 851 67 | 626 33 |
| 16 | 861 40 | 628 61 |
| 17 | 871 08 | 631 13 |
| 18 | 880 69 | 633 89 |
| 19 | 890 24 | 535 87 |
| 20 | 899 71 | 640 09 |
| 21 | 909 09 | 643 53 |
| 22 | 918 40 | 647 20 |
| 23 | 927 61 | 651 10 |
| 24 | 936 72 | 655 22 |
| 25 | 945 73 | 659 55 |
| 26 | 954 63 | 554 11 |
| 27 | 963 42 | 668 88 |
| 28 | 965 38 | 670 00 |

Circle Center At X = 762 3 , Y = 1028 9 and Radius, 412 4
*** 1 068 ***

Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 619 69 |
| 2 | 734 91 | 618 33 |
| 3 | 744 85 | 617 24 |
| 4 | 754 81 | 516 42 |
| 5 | 764 80 | 615 87 |
| 6 | 774 79 | 615 59 |
| 7 | 784 79 | 616 58 |
| 8 | 794 79 | 615 85 |
| 9 | 804 78 | 616 39 |
| 10 | 814 74 | 617 19 |
| 11 | 824 69 | 618 28 |
| 12 | 834 59 | 619 63 |
| 13 | 844 46 | 621 25 |
| 14 | 854 28 | 623 13 |
| 15 | 864 05 | 525 29 |
| 16 | 873 75 | 627 71 |
| 17 | 883 38 | 630 39 |
| 18 | 892 94 | 633 33 |
| 19 | 902 41 | 636 54 |
| 20 | 911 80 | 640 00 |
| 21 | 921 08 | 543 71 |
| 22 | 930 26 | 647 68 |
| 23 | 939 33 | 651 89 |
| 24 | 948 28 | 656 35 |
| 25 | 957 11 | 661 05 |
| 26 | 955 80 | 665 99 |
| 27 | 972 44 | 670 00 |

Circle Center At X = 780 0 , Y = 982 9 and Radius, 367 4
*** 1 070 ***

Failure Surface Specified By 17 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 760 00 | 520 00 |
| 2 | 759 95 | 619 01 |
| 3 | 769 94 | 618 50 |
| 4 | 779 94 | 518 47 |
| 5 | 789 93 | 618 90 |
| 6 | 799 89 | 619 82 |
| 7 | 809 79 | 621 20 |
| 8 | 819 62 | 623 06 |
| 9 | 829 34 | 625 38 |
| 10 | 838 95 | 528 16 |
| 11 | 848 41 | 631 40 |
| 12 | 857 71 | 635 08 |
| 13 | 866 82 | 639 19 |
| 14 | 876 73 | 643 74 |
| 15 | 884 41 | 548 71 |
| 16 | 892 84 | 664 08 |
| 17 | 896 42 | 555 60 |

115/30

Circle Center At X = 775 7 , Y = 828 7 and Radius, 210 2
*** 1 083 ***

Failure Surface Specified By 21 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 620 76 |
| 3 | 769 93 | 621 70 |
| 4 | 779 86 | 622 82 |
| 5 | 789 78 | 624 13 |
| 6 | 799 67 | 625 61 |
| 7 | 809 53 | 627 28 |
| 8 | 819 36 | 629 12 |
| 9 | 829 15 | 631 15 |
| 10 | 838 90 | 633 35 |
| 11 | 848 61 | 635 74 |
| 12 | 858 28 | 638 30 |
| 13 | 867 90 | 641 03 |
| 14 | 877 47 | 643 94 |
| 15 | 886 98 | 647 03 |
| 16 | 896 43 | 650 29 |
| 17 | 905 83 | 653 72 |
| 18 | 915 15 | 657 32 |
| 19 | 924 42 | 661 10 |
| 20 | 933 61 | 665 04 |
| 21 | 937 91 | 666 98 |

Circle Center At X = 713 5 , Y = 1166 5 and Radius, 546 7
*** 1 088 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 81 | 618 06 |
| 3 | 769 70 | 616 60 |
| 4 | 779 66 | 615 64 |
| 5 | 789 65 | 515 18 |
| 6 | 799 65 | 615 22 |
| 7 | 809 63 | 615 75 |
| 8 | 819 58 | 516 78 |
| 9 | 829 45 | 518 31 |
| 10 | 839 26 | 620 32 |
| 11 | 848 94 | 622 82 |
| 12 | 858 49 | 625 80 |
| 13 | 857 87 | 629 25 |
| 14 | 877 08 | 633 15 |
| 15 | 886 07 | 637 63 |
| 16 | 894 84 | 642 33 |
| 17 | 903 36 | 647 57 |
| 18 | 911 60 | 663 23 |
| 19 | 919 56 | 659 29 |
| 20 | 924 78 | 653 70 |

Circle Center At X = 793 9 , Y = 815 7 and Radius, 200 6
*** 1 090 ***

Failure Surface Specified By 15 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 760 00 | 619 82 |
| 3 | 770 00 | 620 04 |
| 4 | 779 98 | 620 67 |
| 6 | 789 92 | 621 69 |
| 6 | 799 82 | 623 11 |
| 7 | 809 66 | 624 92 |
| 8 | 819 41 | 527 13 |
| 9 | 829 07 | 529 72 |
| 10 | 838 61 | 632 70 |
| 11 | 848 03 | 636 05 |
| 12 | 857 31 | 639 79 |

11/6/130

13 866 43 643 89
 14 875 38 648 36
 15 884 14 653 17
 16 885 17 653 79
 Circle Center At X = 759 5 , Y = 869 4 and Radius, 249 5
 *** 1 095 ***

Failure Surface Specified By 15 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 752 50 | 623 13 |
| 2 | 772 44 | 621 99 |
| 3 | 782 42 | 621 43 |
| 4 | 792 42 | 621 44 |
| 5 | 802 40 | 622 03 |
| 5 | 812 33 | 623 20 |
| 7 | 822 18 | 624 93 |
| 8 | 831 92 | 627 23 |
| 9 | 841 50 | 630 08 |
| 10 | 850 90 | 633 48 |
| 11 | 860 10 | 637 42 |
| 12 | 869 05 | 641 88 |
| 13 | 877 72 | 646 85 |
| 14 | 886 10 | 652 31 |
| 15 | 889 63 | 654 91 |

Circle Center At X = 787 2 , Y = 795 0 and Radius, 173 6
 *** 1 099 ***

Failure Surface Specified By 25 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 48 | 622 51 |
| 3 | 782 47 | 622 12 |
| 4 | 792 47 | 621 96 |
| 5 | 802 47 | 622 02 |
| 5 | 812 47 | 622 30 |
| 7 | 822 46 | 622 81 |
| 8 | 832 43 | 623 54 |
| 9 | 842 38 | 624 49 |
| 10 | 852 31 | 625 57 |
| 11 | 862 22 | 527 06 |
| 12 | 872 08 | 628 68 |
| 13 | 881 91 | 630 52 |
| 14 | 891 70 | 532 58 |
| 15 | 901 44 | 634 86 |
| 16 | 911 12 | 637 35 |
| 17 | 920 75 | 640 06 |
| 18 | 930 31 | 642 99 |
| 19 | 939 80 | 646 12 |
| 20 | 949 23 | 649 47 |
| 21 | 958 57 | 653 03 |
| 22 | 967 83 | 656 80 |
| 23 | 977 01 | 660 78 |
| 24 | 986 10 | 654 96 |
| 25 | 995 08 | 669 34 |
| 26 | 996 37 | 670 00 |

Circle Center At X = 794 8 , Y = 1068 6 and Radius, 446 7
 *** 1 099 ***

Failure Surface Specified By 14 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 750 00 | 619 92 |
| 3 | 769 99 | 620 29 |
| 4 | 779 96 | 621 10 |
| 5 | 789 88 | 622 36 |
| 6 | 799 74 | 624 06 |
| 7 | 809 51 | 625 19 |
| 8 | 819 17 | 628 76 |

| | | |
|----|--------|--------|
| 9 | 828 71 | 531 76 |
| 10 | 838 11 | 635 18 |
| 11 | 847 34 | 639 01 |
| 12 | 856 40 | 543 25 |
| 13 | 865 25 | 647 90 |
| 14 | 868 00 | 649 50 |

Circle Center At X = 756 8 , Y = 843 5 and Radius, 223 6
*** 1 116 ***

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 08PM
Run By Greg Shafer, HDR
Input Data Filename C 8 in
Output Filename C 8 OUT
Unit ENGLISH
Plotted Output Filename C 8 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 640 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 126 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient Of0 400 Has Been Assigned
A Vertical Earthquake Loading Coefficient Of0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced Along The Ground Surface Between X = 500 00 ft and X = 800 00 ft
Each Surface Terminates Between X = 850 00 ft and X =1500 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 24 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 619 26 |
| 3 | 769 96 | 618 81 |
| 4 | 779 95 | 618 64 |
| 5 | 789 96 | 618 77 |
| 6 | 799 95 | 619 17 |
| 7 | 809 93 | 619 87 |

| | | |
|----|--------|--------|
| 8 | 819 88 | 620 85 |
| 9 | 829 80 | 622 11 |
| 10 | 839 68 | 623 66 |
| 11 | 849 51 | 625 49 |
| 12 | 859 28 | 627 60 |
| 13 | 868 99 | 630 00 |
| 14 | 878 63 | 632 66 |
| 15 | 888 19 | 635 61 |
| 16 | 897 65 | 638 83 |
| 17 | 907 03 | 642 31 |
| 18 | 916 30 | 546 07 |
| 19 | 925 45 | 650 09 |
| 20 | 934 49 | 654 37 |
| 21 | 943 40 | 658 90 |
| 22 | 952 18 | 563 69 |
| 23 | 960 82 | 668 73 |
| 24 | 962 85 | 670 00 |

Circle Center At X = 780 8 , Y = 967 1 and Radius, 348 5
 *** 0 870 ***

Individual data on the 30 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 10 0 | 1828 9 | 0 0 | 0 0 | 0 0 | 0 0 | 731 6 | 0 0 | 0 0 |
| 2 | 10 0 | 5336 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2134 5 | 0 0 | 0 0 |
| 3 | 10 0 | 8527 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3410 8 | 0 0 | 0 0 |
| 4 | 10 0 | 11389 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4555 9 | 0 0 | 0 0 |
| 5 | 10 0 | 13915 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5566 0 | 0 0 | 0 0 |
| 6 | 10 0 | 16095 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6438 1 | 0 0 | 0 0 |
| 7 | 10 0 | 17924 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7169 9 | 0 0 | 0 0 |
| 8 | 9 9 | 19399 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7759 9 | 0 0 | 0 0 |
| 9 | 0 2 | 405 0 | 0 0 | 0 0 | 0 0 | 0 0 | 162 0 | 0 0 | 0 0 |
| 10 | 9 7 | 21354 9 | 0 0 | 0 0 | 0 0 | 0 0 | 8542 0 | 0 0 | 0 0 |
| 11 | 9 8 | 22418 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8967 4 | 0 0 | 0 0 |
| 12 | 9 8 | 22676 4 | 0 0 | 0 0 | 0 0 | 0 0 | 9070 6 | 0 0 | 0 0 |
| 13 | 9 7 | 22564 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9025 9 | 0 0 | 0 0 |
| 14 | 1 0 | 2327 4 | 0 0 | 0 0 | 0 0 | 0 0 | 931 0 | 0 0 | 0 0 |
| 15 | 8 6 | 20410 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8164 2 | 0 0 | 0 0 |
| 16 | 9 6 | 21979 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8791 9 | 0 0 | 0 0 |
| 17 | 9 5 | 20802 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8321 0 | 0 0 | 0 0 |
| 18 | 3 2 | 6656 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2562 5 | 0 0 | 0 0 |
| 19 | 6 2 | 12638 8 | 0 0 | 0 0 | 0 0 | 0 0 | 5055 5 | 0 0 | 0 0 |
| 20 | 3 0 | 5793 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2317 5 | 0 0 | 0 0 |
| 21 | 6 3 | 12150 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4860 0 | 0 0 | 0 0 |
| 22 | 9 0 | 15710 1 | 0 0 | 0 0 | 0 0 | 0 0 | 6284 0 | 0 0 | 0 0 |
| 23 | 0 2 | 325 5 | 0 0 | 0 0 | 0 0 | 0 0 | 130 2 | 0 0 | 0 0 |
| 24 | 9 0 | 13522 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5449 1 | 0 0 | 0 0 |
| 25 | 8 9 | 10948 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4379 2 | 0 0 | 0 0 |
| 25 | 2 0 | 2094 2 | 0 0 | 0 0 | 0 0 | 0 0 | 837 7 | 0 0 | 0 0 |
| 27 | 4 6 | 4256 6 | 0 0 | 0 0 | 0 0 | 0 0 | 1702 6 | 0 0 | 0 0 |
| 23 | 2 2 | 1708 7 | 0 0 | 0 0 | 0 0 | 0 0 | 683 5 | 0 0 | 0 0 |
| 29 | 8 6 | 3710 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1484 3 | 0 0 | 0 0 |
| 30 | 2 0 | 145 9 | 0 0 | 0 0 | 0 0 | 0 0 | 58 4 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 760 00 | 620 00 |
| 2 | 759 97 | 619 22 |
| 3 | 769 96 | 618 82 |
| 4 | 779 95 | 618 79 |
| 5 | 789 95 | 619 13 |
| 6 | 799 93 | 619 84 |
| 7 | 809 87 | 620 92 |
| 8 | 819 77 | 622 37 |
| 9 | 829 60 | 624 19 |
| 10 | 839 36 | 626 38 |
| 11 | 849 03 | 628 92 |

120/130

| | | |
|----|--------|--------|
| 12 | 858 50 | 631 82 |
| 13 | 868 05 | 635 08 |
| 14 | 877 38 | 638 69 |
| 15 | 886 57 | 642 64 |
| 16 | 895 60 | 645 93 |
| 17 | 904 47 | 651 55 |
| 18 | 913 16 | 556 50 |
| 19 | 921 65 | 661 77 |
| 20 | 924 36 | 663 59 |

Circle Center At X = 775 8 , Y = 887 1 and Radius, 268 4
*** 0 882 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 43 | 621 95 |
| 3 | 782 40 | 621 21 |
| 4 | 792 40 | 620 91 |
| 5 | 802 40 | 621 04 |
| 6 | 812 38 | 621 61 |
| 7 | 822 33 | 622 62 |
| 8 | 832 23 | 624 06 |
| 9 | 842 05 | 625 93 |
| 10 | 851 78 | 628 22 |
| 11 | 861 41 | 630 94 |
| 12 | 870 90 | 634 08 |
| 13 | 880 25 | 637 63 |
| 14 | 889 44 | 641 58 |
| 15 | 898 44 | 645 93 |
| 16 | 907 25 | 650 67 |
| 17 | 915 84 | 655 79 |
| 18 | 924 20 | 661 28 |
| 19 | 929 01 | 664 75 |

Circle Center At X = 794 3 , Y = 849 9 and Radius 229 0
*** 0 890 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 49 | 629 79 |
| 3 | 807 47 | 630 44 |
| 4 | 817 43 | 631 33 |
| 5 | 827 37 | 632 46 |
| 6 | 837 27 | 533 82 |
| 7 | 847 14 | 635 42 |
| 8 | 856 97 | 637 26 |
| 9 | 866 76 | 539 34 |
| 10 | 876 49 | 641 64 |
| 11 | 886 16 | 644 18 |
| 12 | 895 77 | 646 95 |
| 13 | 905 31 | 649 95 |
| 14 | 914 77 | 653 18 |
| 15 | 924 16 | 655 63 |
| 16 | 933 45 | 660 31 |
| 17 | 942 67 | 664 21 |
| 18 | 951 78 | 668 33 |
| 19 | 955 26 | 670 00 |

Circle Center At X = 775 3 , Y = 1046 7 and Radius, 417 5
*** 0 894 ***

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 35 | 621 39 |
| 3 | 782 26 | 620 08 |
| 4 | 792 22 | 619 18 |
| 5 | 802 21 | 618 70 |
| 5 | 812 21 | 618 65 |

121/130

| | | |
|----|--------|--------|
| 7 | 822 20 | 619 01 |
| 8 | 832 17 | 619 80 |
| 9 | 842 10 | 621 01 |
| 10 | 851 97 | 622 63 |
| 11 | 861 76 | 624 67 |
| 12 | 871 45 | 627 12 |
| 13 | 881 04 | 629 97 |
| 14 | 890 49 | 633 23 |
| 15 | 899 80 | 636 88 |
| 16 | 908 95 | 640 92 |
| 17 | 917 92 | 645 34 |
| 18 | 926 69 | 650 14 |
| 19 | 935 26 | 555 30 |
| 20 | 943 60 | 660 82 |
| 21 | 951 70 | 666 68 |
| 22 | 955 89 | 570 00 |

Circle Center At X = 808 5 , Y = 855 6 and Radius, 237 0
 *** 0 894 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 523 13 |
| 2 | 772 38 | 621 57 |
| 3 | 782 32 | 620 52 |
| 4 | 792 31 | 619 99 |
| 5 | 802 31 | 619 97 |
| 6 | 812 30 | 620 46 |
| 7 | 822 25 | 621 47 |
| 8 | 832 13 | 622 98 |
| 9 | 841 93 | 625 00 |
| 10 | 851 60 | 627 52 |
| 11 | 861 14 | 630 54 |
| 12 | 870 50 | 634 04 |
| 13 | 879 68 | 538 01 |
| 14 | 888 64 | 642 45 |
| 15 | 897 36 | 647 35 |
| 16 | 905 81 | 652 69 |
| 17 | 913 99 | 558 45 |
| 18 | 918 73 | 662 18 |

Circle Center At X = 797 7 , Y = 814 2 and Radius, 194 3
 *** 0 902 ***

Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 30 | 617 87 |
| 3 | 757 17 | 616 23 |
| 4 | 767 08 | 614 91 |
| 5 | 777 03 | 613 91 |
| 6 | 787 01 | 613 26 |
| 7 | 797 00 | 612 91 |
| 8 | 807 00 | 612 91 |
| 9 | 817 00 | 613 23 |
| 10 | 826 98 | 613 89 |
| 11 | 836 93 | 614 87 |
| 12 | 846 84 | 616 19 |
| 13 | 856 71 | 617 83 |
| 14 | 856 51 | 619 79 |
| 15 | 876 25 | 622 08 |
| 16 | 885 90 | 624 68 |
| 17 | 895 46 | 627 61 |
| 18 | 904 92 | 630 84 |
| 19 | 914 27 | 634 39 |
| 20 | 923 50 | 638 25 |
| 21 | 932 60 | 642 40 |
| 22 | 941 55 | 645 86 |
| 23 | 950 35 | 651 61 |
| 24 | 958 99 | 656 55 |

122/130

25 967 46 651 96
 26 975 74 657 56
 27 979 11 570 00
 Circle Center At X = 802 1 , Y = 915 8 and Radius, 302 9
 *** 0 903 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 34 | 521 34 |
| 3 | 782 25 | 520 10 |
| 4 | 792 24 | 619 39 |
| 5 | 802 24 | 619 24 |
| 6 | 812 23 | 619 62 |
| 7 | 822 19 | 620 56 |
| 8 | 832 08 | 622 03 |
| 9 | 841 87 | 624 04 |
| 10 | 851 54 | 626 58 |
| 11 | 861 06 | 629 64 |
| 12 | 870 40 | 633 22 |
| 13 | 879 53 | 637 30 |
| 14 | 888 42 | 641 87 |
| 15 | 897 06 | 646 92 |
| 16 | 905 40 | 652 44 |
| 17 | 913 43 | 658 40 |
| 18 | 917 67 | 661 92 |

Circle Center At X = 800 1 , Y = 802 3 and Radius, 183 1
 *** 0 909 ***

Failure Surface Specified By 31 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 519 69 |
| 2 | 734 88 | 618 14 |
| 3 | 744 79 | 616 83 |
| 4 | 754 73 | 615 75 |
| 5 | 764 70 | 614 90 |
| 6 | 774 68 | 614 30 |
| 7 | 784 67 | 613 93 |
| 8 | 794 67 | 613 79 |
| 9 | 804 67 | 613 90 |
| 10 | 814 67 | 614 24 |
| 11 | 824 65 | 614 82 |
| 12 | 834 52 | 615 53 |
| 13 | 844 56 | 616 68 |
| 14 | 854 48 | 617 97 |
| 15 | 864 36 | 619 49 |
| 16 | 874 21 | 621 24 |
| 17 | 884 01 | 523 23 |
| 18 | 893 76 | 625 46 |
| 19 | 903 45 | 627 90 |
| 20 | 913 09 | 630 58 |
| 21 | 922 65 | 633 49 |
| 22 | 932 15 | 636 63 |
| 23 | 941 57 | 639 98 |
| 24 | 950 91 | 643 56 |
| 25 | 960 16 | 647 37 |
| 26 | 969 31 | 651 39 |
| 27 | 978 37 | 655 62 |
| 28 | 987 33 | 650 07 |
| 29 | 996 17 | 664 73 |
| 30 | 1004 91 | 669 60 |
| 31 | 1005 59 | 670 00 |

Circle Center At X = 795 3 , Y = 1035 4 and Radius, 421 6
 *** 0 917 ***

Failure Surface Specified By 21 Coordinate Points


| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |

| | | |
|----|--------|--------|
| 2 | 772 45 | 624 11 |
| 3 | 782 39 | 626 25 |
| 4 | 792 30 | 626 56 |
| 5 | 802 19 | 628 02 |
| 6 | 812 06 | 629 65 |
| 7 | 821 90 | 631 43 |
| 8 | 831 71 | 633 37 |
| 9 | 841 49 | 635 46 |
| 10 | 851 23 | 637 72 |
| 11 | 860 94 | 640 13 |
| 12 | 870 60 | 642 70 |
| 13 | 880 22 | 645 42 |
| 14 | 889 80 | 648 30 |
| 15 | 899 33 | 651 33 |
| 16 | 908 81 | 654 51 |
| 17 | 918 24 | 657 85 |
| 18 | 927 61 | 661 34 |
| 19 | 936 92 | 664 97 |
| 20 | 946 18 | 668 75 |
| 21 | 947 76 | 669 44 |

Circle Center At X = 706 4 , Y = 1241 5 and Radius, 621 0
*** 0 918 ***

Intermountain Regional Landfill Cut slope 1

c:\program files\stedwin\irl\8 pl2 Run By Greg Shafer, HDR 4/20/2010 03:08PM




| # | FS | Soil Desc | Soil Type No | Total Unit WL (pcf) | Saturated Unit WL (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface No | Load | Value |
|---|------|-----------|--------------|---------------------|-------------------------|--------------------------|----------------------|-----------------|------|-------|
| a | 0.87 | | | | | | | | | |
| b | 0.88 | | | | | | | | | |
| c | 0.89 | UVSC | 1 | 113.5 | 121.0 | 50.0 | 29.0 | W1 | | |
| d | 0.89 | LSC | 2 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| e | 0.89 | SC | 3 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| f | 0.90 | LVSC | 4 | 121.0 | 125.5 | 50.0 | 29.0 | W1 | | |
| g | 0.90 | | | | | | | | | |
| h | 0.91 | | | | | | | | | |
| i | 0.92 | | | | | | | | | |
| j | 0.92 | | | | | | | | | |

PCSTABL7 FSmm=0.87

Safety Factors Are Calculated By The Modified Bishop Method

STED



124/130

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 08PM
Run By Greg Shafer, HDR
Input Data Filename C 8 in
Output Filename C 8 OUT
Unit ENGLISH
Plotted Output Filename C 8 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Cut slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
6 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 611 45 | 750 00 | 620 00 | 4 |
| 2 | 750 00 | 620 00 | 950 00 | 670 00 | 1 |
| 3 | 950 00 | 670 00 | 3000 00 | 670 00 | 1 |
| 4 | 910 00 | 660 00 | 3000 00 | 660 00 | 2 |
| 5 | 870 00 | 650 00 | 3000 00 | 650 00 | 3 |
| 6 | 830 00 | 540 00 | 3000 00 | 640 00 | 4 |

ISOTROPIC SOIL PARAMETERS

4 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 60 0 | 29 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 50 0 | 29 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient

Of0 400 Has Been Assigned

A Vertical Earthquake Loading Coefficient

Of0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified

525 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced

Along The Ground Surface Between X = 500 00 ft

and X = 800 00 ft

Each Surface Terminates Between X = 850 00 ft

and X =1500 00 ft

Unless Further Limitations Were Imposed The Minimum Elevation

At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 24 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 769 97 | 619 26 |
| 3 | 769 95 | 618 81 |
| 4 | 779 95 | 618 54 |
| 5 | 789 96 | 518 77 |
| 6 | 799 95 | 619 17 |
| 7 | 809 93 | 519 87 |

126/130

| | | |
|----|--------|--------|
| 8 | 819 88 | 620 85 |
| 9 | 829 80 | 622 11 |
| 10 | 839 68 | 623 66 |
| 11 | 849 51 | 625 49 |
| 12 | 859 28 | 627 60 |
| 13 | 868 99 | 630 00 |
| 14 | 878 63 | 632 66 |
| 15 | 888 19 | 635 61 |
| 16 | 897 66 | 638 83 |
| 17 | 907 03 | 642 31 |
| 18 | 916 30 | 546 07 |
| 19 | 925 45 | 650 09 |
| 20 | 934 49 | 654 37 |
| 21 | 943 40 | 658 90 |
| 22 | 952 18 | 663 69 |
| 23 | 960 82 | 668 73 |
| 24 | 962 85 | 670 00 |

Circle Center At X = 780 8 , Y = 967 1 and Radius, 348 5
 *** 0 870 ***

Individual data on the 30 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force Surcharge | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|----------------------------|-----------|------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | Load (lbs) |
| 1 | 10 0 | 1828 9 | 0 0 | 0 0 | 0 0 | 0 0 | 731 6 | 0 0 | 0 0 |
| 2 | 10 0 | 5336 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2134 5 | 0 0 | 0 0 |
| 3 | 10 0 | 8527 0 | 0 0 | 0 0 | 0 0 | 0 0 | 3410 8 | 0 0 | 0 0 |
| 4 | 10 0 | 11389 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4555 9 | 0 0 | 0 0 |
| 5 | 10 0 | 13915 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5566 0 | 0 0 | 0 0 |
| 6 | 10 0 | 16095 2 | 0 0 | 0 0 | 0 0 | 0 0 | 6438 1 | 0 0 | 0 0 |
| 7 | 10 0 | 17924 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7169 9 | 0 0 | 0 0 |
| 8 | 9 9 | 19399 8 | 0 0 | 0 0 | 0 0 | 0 0 | 7759 9 | 0 0 | 0 0 |
| 9 | 0 2 | 405 0 | 0 0 | 0 0 | 0 0 | 0 0 | 162 0 | 0 0 | 0 0 |
| 10 | 9 7 | 21354 9 | 0 0 | 0 0 | 0 0 | 0 0 | 8542 0 | 0 0 | 0 0 |
| 11 | 9 8 | 22418 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8967 4 | 0 0 | 0 0 |
| 12 | 9 8 | 22676 4 | 0 0 | 0 0 | 0 0 | 0 0 | 9070 6 | 0 0 | 0 0 |
| 13 | 9 7 | 22554 8 | 0 0 | 0 0 | 0 0 | 0 0 | 9025 9 | 0 0 | 0 0 |
| 14 | 1 0 | 2327 4 | 0 0 | 0 0 | 0 0 | 0 0 | 931 0 | 0 0 | 0 0 |
| 15 | 8 6 | 20410 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8164 2 | 0 0 | 0 0 |
| 15 | 9 6 | 21979 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8791 9 | 0 0 | 0 0 |
| 17 | 9 5 | 20802 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8321 0 | 0 0 | 0 0 |
| 18 | 3 2 | 6656 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2662 5 | 0 0 | 0 0 |
| 19 | 6 2 | 12638 8 | 0 0 | 0 0 | 0 0 | 0 0 | 5055 5 | 0 0 | 0 0 |
| 20 | 3 0 | 5793 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2317 5 | 0 0 | 0 0 |
| 21 | 6 3 | 12150 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4860 0 | 0 0 | 0 0 |
| 22 | 9 0 | 15710 1 | 0 0 | 0 0 | 0 0 | 0 0 | 6284 0 | 0 0 | 0 0 |
| 23 | 0 2 | 325 5 | 0 0 | 0 0 | 0 0 | 0 0 | 130 2 | 0 0 | 0 0 |
| 24 | 9 0 | 13622 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5449 1 | 0 0 | 0 0 |
| 25 | 8 9 | 10948 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4379 2 | 0 0 | 0 0 |
| 26 | 2 0 | 2094 2 | 0 0 | 0 0 | 0 0 | 0 0 | 837 7 | 0 0 | 0 0 |
| 27 | 4 6 | 4255 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1702 6 | 0 0 | 0 0 |
| 28 | 2 2 | 1708 7 | 0 0 | 0 0 | 0 0 | 0 0 | 683 5 | 0 0 | 0 0 |
| 29 | 8 6 | 3710 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1484 3 | 0 0 | 0 0 |
| 30 | 2 0 | 145 9 | 0 0 | 0 0 | 0 0 | 0 0 | 58 4 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 00 | 620 00 |
| 2 | 759 97 | 619 22 |
| 3 | 769 96 | 618 82 |
| 4 | 779 96 | 618 79 |
| 5 | 789 96 | 619 13 |
| 6 | 799 93 | 619 84 |
| 7 | 809 87 | 620 92 |
| 8 | 819 77 | 622 37 |
| 9 | 829 60 | 624 19 |
| 10 | 839 36 | 626 38 |
| 11 | 849 03 | 628 92 |

| | | |
|----|--------|--------|
| 12 | 858 60 | 631 82 |
| 13 | 868 05 | 635 08 |
| 14 | 877 38 | 638 69 |
| 15 | 886 57 | 642 64 |
| 16 | 895 60 | 646 93 |
| 17 | 904 47 | 651 55 |
| 18 | 913 16 | 656 50 |
| 19 | 921 65 | 661 77 |
| 20 | 924 36 | 663 59 |

Circle Center At X = 775 8 , Y = 887 1 and Radius, 268 4
*** 0 882 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 43 | 621 95 |
| 3 | 782 40 | 621 21 |
| 4 | 792 40 | 520 91 |
| 5 | 802 40 | 621 04 |
| 6 | 812 38 | 521 51 |
| 7 | 822 33 | 622 62 |
| 8 | 832 23 | 624 06 |
| 9 | 842 05 | 625 93 |
| 10 | 851 78 | 628 22 |
| 11 | 861 41 | 630 94 |
| 12 | 870 90 | 634 08 |
| 13 | 880 25 | 637 63 |
| 14 | 889 44 | 641 58 |
| 15 | 898 44 | 645 93 |
| 16 | 907 25 | 650 57 |
| 17 | 915 84 | 655 79 |
| 18 | 924 20 | 661 28 |
| 19 | 929 01 | 654 75 |

Circle Center At X = 794 3 , Y = 849 9 and Radius, 229 0
*** 0 890 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 49 | 629 79 |
| 3 | 807 47 | 630 44 |
| 4 | 817 43 | 631 33 |
| 5 | 827 37 | 632 45 |
| 5 | 837 27 | 633 82 |
| 7 | 847 14 | 635 42 |
| 8 | 856 97 | 637 25 |
| 9 | 866 76 | 639 34 |
| 10 | 876 49 | 641 64 |
| 11 | 885 16 | 644 18 |
| 12 | 895 77 | 646 95 |
| 13 | 905 31 | 649 95 |
| 14 | 914 77 | 653 18 |
| 15 | 924 16 | 656 63 |
| 16 | 933 46 | 660 31 |
| 17 | 942 67 | 664 21 |
| 18 | 951 78 | 668 33 |
| 19 | 955 26 | 670 00 |

Circle Center At X = 775 3 , Y = 1046 7 and Radius, 417 5
*** 0 894 ***

Failure Surface Specified By 22 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 35 | 621 39 |
| 3 | 782 26 | 620 08 |
| 4 | 792 22 | 619 18 |
| 5 | 802 21 | 618 70 |
| 5 | 812 21 | 618 65 |

| | | |
|----|--------|--------|
| 7 | 822 20 | 619 01 |
| 8 | 832 17 | 619 80 |
| 9 | 842 10 | 621 01 |
| 10 | 851 97 | 622 63 |
| 11 | 861 76 | 624 67 |
| 12 | 871 45 | 627 12 |
| 13 | 881 04 | 629 97 |
| 14 | 890 49 | 633 23 |
| 15 | 899 80 | 636 88 |
| 16 | 908 95 | 640 92 |
| 17 | 917 92 | 645 34 |
| 18 | 925 69 | 650 14 |
| 19 | 936 26 | 655 30 |
| 20 | 943 60 | 660 82 |
| 21 | 951 70 | 666 68 |
| 22 | 955 89 | 670 00 |

Circle Center At X = 808 5 , Y = 855 6 and Radius, 237 0
 *** 0 894 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 38 | 621 57 |
| 3 | 782 32 | 620 52 |
| 4 | 792 31 | 619 99 |
| 5 | 802 31 | 519 97 |
| 6 | 812 30 | 620 46 |
| 7 | 822 25 | 621 47 |
| 8 | 832 13 | 622 98 |
| 9 | 841 93 | 625 00 |
| 10 | 851 60 | 627 52 |
| 11 | 861 14 | 630 54 |
| 12 | 870 50 | 634 04 |
| 13 | 879 58 | 638 01 |
| 14 | 888 64 | 642 45 |
| 15 | 897 36 | 647 35 |
| 16 | 905 81 | 652 69 |
| 17 | 913 99 | 658 45 |
| 18 | 918 73 | 662 18 |

Circle Center At X = 797 7 , Y = 814 2 and Radius, 194 3
 *** 0 902 ***

Failure Surface Specified By 27 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 737 50 | 619 85 |
| 2 | 747 30 | 617 87 |
| 3 | 757 17 | 616 23 |
| 4 | 767 08 | 614 91 |
| 5 | 777 03 | 613 91 |
| 6 | 787 01 | 613 25 |
| 7 | 797 00 | 612 91 |
| 8 | 807 00 | 612 91 |
| 9 | 817 00 | 613 23 |
| 10 | 826 98 | 613 89 |
| 11 | 836 93 | 614 87 |
| 12 | 846 84 | 615 19 |
| 13 | 856 71 | 517 83 |
| 14 | 866 51 | 619 79 |
| 15 | 876 25 | 622 08 |
| 16 | 885 90 | 624 68 |
| 17 | 895 46 | 627 61 |
| 18 | 904 92 | 630 84 |
| 19 | 914 27 | 634 39 |
| 20 | 923 60 | 538 25 |
| 21 | 932 60 | 642 40 |
| 22 | 941 55 | 646 86 |
| 23 | 960 35 | 651 61 |
| 24 | 958 99 | 556 65 |

| | | |
|----|--------|--------|
| 25 | 957 46 | 661 96 |
| 26 | 975 74 | 657 56 |
| 27 | 979 11 | 670 00 |

Circle Center At X = 802 1 , Y = 915 8 and Radius, 302 9
 *** 0 903 ***

Failure Surface Specified By 18 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 50 | 623 13 |
| 2 | 772 34 | 621 34 |
| 3 | 782 26 | 520 10 |
| 4 | 792 24 | 619 39 |
| 5 | 802 24 | 619 24 |
| 6 | 812 23 | 619 62 |
| 7 | 822 19 | 620 56 |
| 8 | 832 08 | 622 03 |
| 9 | 841 87 | 624 04 |
| 10 | 851 54 | 626 58 |
| 11 | 861 06 | 629 64 |
| 12 | 870 40 | 633 22 |
| 13 | 879 53 | 637 30 |
| 14 | 888 42 | 641 87 |
| 15 | 897 05 | 645 92 |
| 16 | 905 40 | 652 44 |
| 17 | 913 43 | 658 40 |
| 18 | 917 67 | 661 92 |

Circle Center At X = 800 1 , Y = 802 3 and Radius, 183 1
 *** 0 909 ***

Failure Surface Specified By 31 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 725 00 | 619 69 |
| 2 | 734 88 | 618 14 |
| 3 | 744 79 | 616 83 |
| 4 | 754 73 | 615 75 |
| 5 | 764 70 | 614 90 |
| 6 | 774 68 | 614 30 |
| 7 | 784 67 | 613 93 |
| 8 | 794 57 | 613 79 |
| 9 | 804 67 | 613 90 |
| 10 | 814 67 | 614 24 |
| 11 | 824 65 | 614 82 |
| 12 | 834 62 | 615 63 |
| 13 | 844 56 | 616 68 |
| 14 | 854 48 | 617 97 |
| 15 | 864 36 | 619 49 |
| 15 | 874 21 | 621 24 |
| 17 | 884 01 | 623 23 |
| 18 | 893 76 | 625 45 |
| 19 | 903 45 | 627 90 |
| 20 | 913 09 | 630 58 |
| 21 | 922 65 | 633 49 |
| 22 | 932 15 | 636 63 |
| 23 | 941 57 | 639 98 |
| 24 | 950 91 | 643 56 |
| 25 | 960 16 | 647 37 |
| 26 | 969 31 | 651 39 |
| 27 | 978 37 | 665 62 |
| 28 | 987 33 | 660 07 |
| 29 | 996 17 | 664 73 |
| 30 | 1004 91 | 659 60 |
| 31 | 1005 59 | 670 00 |

Circle Center At X = 795 3 , Y = 1035 4 and Radius, 421 6
 *** 0 917 ***

Failure Surface Specified By 21 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 762 60 | 623 13 |

130/130

| | | |
|----|--------|--------|
| 2 | 772 45 | 624 11 |
| 3 | 782 39 | 625 25 |
| 4 | 792 30 | 626 56 |
| 5 | 802 19 | 628 02 |
| 6 | 812 06 | 629 65 |
| 7 | 821 90 | 531 43 |
| 8 | 831 71 | 533 37 |
| 9 | 841 49 | 635 46 |
| 10 | 851 23 | 637 72 |
| 11 | 860 94 | 640 13 |
| 12 | 870 60 | 642 70 |
| 13 | 880 22 | 645 42 |
| 14 | 889 80 | 548 30 |
| 15 | 899 33 | 651 33 |
| 16 | 908 81 | 654 51 |
| 17 | 918 24 | 657 85 |
| 18 | 927 61 | 661 34 |
| 19 | 936 92 | 664 97 |
| 20 | 946 18 | 668 76 |
| 21 | 947 76 | 669 44 |


Circle Center At X = 706 4 , Y = 1241 5 and Radius, 621 0
*** 0 918 ***

**ATTACHMENT 2C-3: SLOPE STABILITY RUNS &
RESULTS – WASTE MASS SLIDING BLOCK**

| | | | | | |
|---------|------------------|----------|------|------|--------------------|
| Project | IRL | Computed | LRMS | Date | 3/20/10 4/20/10 |
| Subject | slope stability | Checked | POP | Date | 4-9-10 |
| Task | Sliding Block | Page | 1 | of | 22 |
| Job # | 125124 Dept. 143 | No | | | |


Liner stability - Sliding Block

Worst case @ Cell 3 / Cell 4 - 130 FT from top of Waste to cell floors



| Interface | Flow angles | ✓ S |
|--|-------------|--------|
| 2' Protective Cover / Upper Geotextile | 25° | |
| Upper Geo / Textured HDPE | 25° | |
| Textured HDPE / GCL | * 18° | |
| GCL / Lower Geotextile | * 18° | |
| Lower Geotextile / Subgrade | 25° | |


* Anticipated critical Interface to be verified.



- 2' Protective Soil / LCRS
- Upper Geotextile (Nonwoven on cell floor, Re. forced woven on sideslope)
- Texture 60 mil HDPE Geomembrane
- Geosynthetic Clay Liner (GCL)
- Lower Geotextile (Nonwoven)
- Subgrade

| | | | | | |
|---------|-----------------|----------|-----|------|---------|
| Project | IRL | Computed | Gms | Date | 3/20/10 |
| Subject | Slope Stability | Checked | PDP | Date | 4-9-10 |
| Task | Sliding Block | Page | 2 | of | 22 |
| Job # | 125184 | Dept. | 143 | No | |

Results



| acceleration, g | FS |
|----------------------|----------------------|
| 0 (stat.) | 14 |
| x \rightarrow 0.1g | 10.7 \leftarrow 10 |
| 0.2g | 0.83 |

@ FS = 10

$$\frac{1.07 - 0.83}{0.1 - 0.2} = \frac{1.07 - 1.0}{0.1 - x} \Rightarrow \frac{0.24}{-0.1} = \frac{0.07}{0.1 - x}$$

$$0.22(0.1 - x) = (-0.1)(0.07) \Rightarrow 0.022 - 0.22x = -0.007$$

$$-0.22x = -0.029 \quad x = 0.13$$

| | | | | | |
|---------|-----------------|----------|---------|------|---------|
| Project | IRL | Computed | 6/11/05 | Date | 3/20/10 |
| Subject | Slope Stability | Checked | | Date | |
| Task | Sliding Block | Page | 3 | of | 22 |
| Job # | 125/84 Dept 143 | No | | | |

Linear stability, Max Waste - Sliding Block / Displacement

$$a_{max} = 0.28 \text{ (Reference E)}$$

$$a_y = 0.13 \text{ (Previous page)}$$

$$\frac{a_y}{a_{max}} = \frac{0.13}{0.28} = 0.46 \quad @ M=7.0$$


See Attachment 2B (Reference A)

$$@ M=7.0 \quad U_{max} = 80 \text{ cm} < 30 \text{ cm (allow)} \quad \underline{\underline{OK}}$$

(Blank)

Intermountain Regional Landfill Sliding Block

c:\program files\stedwin\rt21 pl2 Run By Greg Shafer, HDR 4/20/2010 04 10PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez. Surface |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|---------------|
| a | 1.44 | | | | | | | |
| b | 1.45 | | No | | | | | No |
| c | 1.46 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 |
| d | 1.46 | Waste | 2 | 50.0 | 60.0 | 150.0 | 22.0 | W1 |
| e | 1.47 | Liner | 3 | 50.0 | 50.0 | 0.0 | 18.0 | W1 |
| f | 1.47 | | | | | | | |
| g | 1.47 | | | | | | | |
| h | 1.47 | | | | | | | |
| i | 1.47 | | | | | | | |
| j | 1.48 | | | | | | | |

STED



PCSTABL7 FSmin=1.44
Safety Factors Are Calculated By The Modified Janbu Method

5/22

6/22

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 04 10PM
Run By Greg Shafer, HDR
Input Data Filename C 21 in
Output Filename C 21 OUT
Unit ENGLISH
Plotted Output Filename C 21 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Sliding Block

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

5 Top Boundaries
12 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 550 00 | 750 00 | 558 75 | 1 |
| 2 | 750 00 | 558 75 | 1140 00 | 688 75 | 2 |
| 3 | 1140 00 | 688 75 | 1440 00 | 688 75 | 2 |
| 4 | 1440 00 | 688 75 | 1760 00 | 608 75 | 2 |
| 5 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |
| 6 | 750 00 | 558 75 | 750 30 | 558 85 | 3 |
| 7 | 750 30 | 558 85 | 1560 00 | 558 85 | 3 |
| 8 | 1560 00 | 558 85 | 1759 90 | 608 75 | 3 |
| 9 | 1759 90 | 608 75 | 1760 00 | 608 75 | 3 |
| 10 | 750 00 | 558 75 | 1560 00 | 558 75 | 1 |
| 11 | 1560 00 | 558 75 | 1760 00 | 608 75 | 1 |
| 12 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |

ISOTROPIC SOIL PARAMETERS

3 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |
| 3 | 50 0 | 50 0 | 0 0 | 18 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random Technique For Generating Sliding Block Surfaces, Has Been Specified

1000 Trial Surfaces Have Been Generated

6 Boxes Specified For Generation Of Central Block Base Length Of Line Segments For Active And Passive Portions Of Sliding Block Is 10 0

| Box No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Height (ft) |
|--------|-------------|-------------|--------------|--------------|-------------|
| 1 | 751 00 | 558 84 | 751 00 | 558 84 | 0 00 |
| 2 | 800 00 | 558 84 | 800 00 | 558 84 | 0 00 |
| 3 | 850 00 | 558 84 | 850 00 | 558 84 | 0 00 |
| 4 | 900 00 | 558 84 | 900 00 | 558 84 | 0 00 |
| 5 | 950 00 | 558 84 | 950 00 | 558 84 | 0 00 |
| 6 | 960 00 | 558 84 | 960 00 | 558 84 | 0 00 |

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Janbu Method * *
Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |

7/22

| | | |
|----|---------|--------|
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 00 | 565 99 |
| 9 | 972 39 | 574 41 |
| 10 | 979 45 | 581 49 |
| 11 | 986 45 | 588 63 |
| 12 | 993 17 | 596 04 |
| 13 | 1000 13 | 603 22 |
| 14 | 1007 18 | 610 31 |
| 15 | 1013 23 | 618 27 |
| 16 | 1019 88 | 625 74 |
| 17 | 1026 86 | 632 90 |
| 18 | 1032 31 | 641 28 |
| 19 | 1039 31 | 648 42 |
| 20 | 1041 75 | 656 00 |

*** 1 444 ***

Individual data on the 21 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 0 2 | 1 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 0 0 | 0 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 49 0 | 20604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 50 0 | 62274 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 50 0 | 103941 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 50 0 | 145608 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 10 0 | 34121 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 0 0 | 34 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 7 0 | 23575 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 5 4 | 16663 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 7 1 | 19811 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 12 | 7 0 | 17977 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 6 7 | 15558 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 7 0 | 14385 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 7 1 | 12879 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 6 1 | 9449 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 6 6 | 8500 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 7 0 | 7178 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 5 5 | 4050 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 7 0 | 3208 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 2 4 | 411 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 09 | 566 78 |
| 9 | 972 91 | 574 08 |
| 10 | 978 87 | 582 11 |
| 11 | 985 69 | 589 43 |
| 12 | 991 48 | 597 58 |
| 13 | 998 08 | 605 09 |
| 14 | 1004 94 | 612 37 |
| 15 | 1012 01 | 619 44 |
| 16 | 1019 08 | 626 51 |
| 17 | 1026 15 | 633 59 |
| 18 | 1033 20 | 640 68 |
| 19 | 1038 93 | 648 87 |
| 20 | 1044 53 | 656 93 |

*** 1 449 ***

Failure Surface Specified By 20 Coordinate Points

8/22

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 96 | 566 02 |
| 9 | 972 37 | 574 43 |
| 10 | 977 89 | 582 77 |
| 11 | 984 95 | 589 85 |
| 12 | 992 02 | 596 92 |
| 13 | 998 89 | 604 19 |
| 14 | 1005 95 | 611 27 |
| 15 | 1012 08 | 619 17 |
| 16 | 1018 78 | 626 59 |
| 17 | 1024 95 | 634 47 |
| 18 | 1030 69 | 642 65 |
| 19 | 1036 37 | 650 88 |
| 20 | 1036 89 | 654 38 |

*** 1 458 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 98 | 566 00 |
| 9 | 972 83 | 574 11 |
| 10 | 979 85 | 581 24 |
| 11 | 985 80 | 589 27 |
| 12 | 992 85 | 596 36 |
| 13 | 999 92 | 603 43 |
| 14 | 1005 88 | 611 47 |
| 15 | 1012 34 | 619 10 |
| 16 | 1016 21 | 628 32 |
| 17 | 1022 75 | 635 89 |
| 18 | 1029 67 | 643 11 |
| 19 | 1034 59 | 651 81 |
| 20 | 1034 59 | 653 61 |

*** 1 464 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 99 | 565 99 |
| 9 | 974 05 | 573 08 |
| 10 | 979 99 | 581 12 |
| 11 | 986 46 | 588 74 |
| 12 | 992 33 | 596 84 |
| 13 | 997 72 | 605 26 |
| 14 | 1004 76 | 612 36 |
| 15 | 1011 22 | 620 00 |
| 16 | 1018 02 | 627 33 |
| 17 | 1024 85 | 634 63 |
| 18 | 1031 80 | 641 83 |

9/22

| | | |
|---|-------------|-------------|
| 19 | 1038 73 | 649 03 |
| 20 | 1038 81 | 655 02 |
| *** | 1 465 | *** |
| Failure Surface Specified By 19 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 17 | 566 71 |
| 9 | 973 11 | 573 91 |
| 10 | 980 18 | 580 99 |
| 11 | 987 03 | 588 27 |
| 12 | 994 10 | 595 34 |
| 13 | 1000 41 | 603 10 |
| 14 | 1007 31 | 610 33 |
| 15 | 1011 73 | 619 31 |
| 16 | 1015 48 | 628 58 |
| 17 | 1022 13 | 636 04 |
| 18 | 1028 64 | 643 63 |
| 19 | 1030 87 | 652 38 |
| *** | 1 469 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 66 | 558 97 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 70 | 566 26 |
| 9 | 973 14 | 573 91 |
| 10 | 979 70 | 581 46 |
| 11 | 986 77 | 588 53 |
| 12 | 992 71 | 596 58 |
| 13 | 999 27 | 604 12 |
| 14 | 1004 68 | 612 54 |
| 15 | 1008 95 | 621 58 |
| 16 | 1015 71 | 628 95 |
| 17 | 1020 46 | 637 75 |
| 18 | 1027 53 | 644 82 |
| 19 | 1034 58 | 651 91 |
| 20 | 1035 07 | 653 77 |
| *** | 1 469 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 82 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 84 | 566 14 |
| 9 | 973 87 | 573 25 |
| 10 | 980 90 | 580 36 |
| 11 | 987 03 | 588 26 |
| 12 | 992 93 | 596 33 |
| 13 | 999 90 | 603 50 |
| 14 | 1004 94 | 612 14 |
| 15 | 1011 74 | 619 48 |

10/22

| | | |
|----|---------|--------|
| 16 | 1018 69 | 626 66 |
| 17 | 1024 54 | 634 77 |
| 18 | 1026 24 | 644 63 |
| 19 | 1032 55 | 652 38 |
| 20 | 1033 11 | 653 12 |

*** 1 471 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 49 | 558 91 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 72 | 566 25 |
| 9 | 973 01 | 574 02 |
| 10 | 980 01 | 581 16 |
| 11 | 987 06 | 588 25 |
| 12 | 993 57 | 595 84 |
| 13 | 997 83 | 604 89 |
| 14 | 1002 99 | 613 46 |
| 15 | 1009 75 | 620 83 |
| 16 | 1016 68 | 628 03 |
| 17 | 1022 52 | 636 15 |
| 18 | 1029 27 | 643 53 |
| 19 | 1031 89 | 652 71 |

*** 1 472 ***


Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 58 | 558 94 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 965 21 | 567 38 |
| 9 | 971 78 | 574 91 |
| 10 | 977 37 | 583 21 |
| 11 | 983 95 | 590 74 |
| 12 | 990 76 | 598 06 |
| 13 | 997 83 | 605 13 |
| 14 | 1004 42 | 612 65 |
| 15 | 1010 81 | 620 34 |
| 16 | 1016 86 | 628 30 |
| 17 | 1022 82 | 636 33 |
| 18 | 1027 05 | 645 40 |
| 19 | 1034 11 | 652 47 |
| 20 | 1034 17 | 653 47 |

*** 1 476 ***

Intermountain Regional Landfill Sliding Block

c:\program files\stedwin\lrf122 pl2 Run By Greg Shafer HDR 4/20/2010 04:14PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez. Surface | Load Horiz | Value Eqk |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|---------------|------------|-----------|
| a | 1.07 | | | | | | | | 0 | 100 g< |
| b | 1.07 | | No | | | | | No | | |
| c | 1.07 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 | | |
| d | 1.08 | Waste | 2 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| e | 1.08 | Liner | 3 | 50.0 | 50.0 | 0.0 | 18.0 | W1 | | |
| f | 1.08 | | | | | | | | | |
| g | 1.08 | | | | | | | | | |
| h | 1.08 | | | | | | | | | |
| i | 1.08 | | | | | | | | | |
| j | 1.09 | | | | | | | | | |

PCSTABL7 FSmin=1.07

Safety Factors Are Calculated By The Modified Janbu Method

STED



11/22

12/22

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 04 14PM
Run By Greg Shafer, HDR
Input Data Filename C 22 in
Output Filename C 22 OUT
Unit ENGLISH
Plotted Output Filename C 22 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Sliding Block

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

5 Top Boundaries
12 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 550 00 | 750 00 | 558 75 | 1 |
| 2 | 750 00 | 558 75 | 1140 00 | 688 75 | 2 |
| 3 | 1140 00 | 688 75 | 1440 00 | 688 75 | 2 |
| 4 | 1440 00 | 688 75 | 1760 00 | 608 75 | 2 |
| 5 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |
| 6 | 750 00 | 558 75 | 750 30 | 558 85 | 3 |
| 7 | 750 30 | 558 85 | 1560 00 | 558 85 | 3 |
| 8 | 1560 00 | 558 85 | 1759 90 | 608 75 | 3 |
| 9 | 1759 90 | 608 75 | 1760 00 | 608 75 | 3 |
| 10 | 750 00 | 558 75 | 1560 00 | 558 75 | 1 |
| 11 | 1560 00 | 558 75 | 1760 00 | 608 75 | 1 |
| 12 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |

ISOTROPIC SOIL PARAMETERS

3 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |
| 3 | 50 0 | 50 0 | 0 0 | 18 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of 0 100 Has Been Assigned

A Vertical Earthquake Loading Coefficient
Of 0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Sliding Block Surfaces, Has Been
Specified

1000 Trial Surfaces Have Been Generated

6 Boxes Specified For Generation Of Central Block Base

Length Of Line Segments For Active And Passive Portions Of
Sliding Block Is 10 0

| Box No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Height (ft) |
|--------|-------------|-------------|--------------|--------------|-------------|
| 1 | 751 00 | 558 84 | 751 00 | 558 84 | 0 00 |
| 2 | 800 00 | 558 84 | 800 00 | 558 84 | 0 00 |
| 3 | 850 00 | 558 84 | 850 00 | 558 84 | 0 00 |
| 4 | 900 00 | 558 84 | 900 00 | 558 84 | 0 00 |
| 5 | 950 00 | 558 84 | 950 00 | 558 84 | 0 00 |
| 6 | 960 00 | 558 84 | 960 00 | 558 84 | 0 00 |

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Janbu Method * *

Failure Surface Specified By 20 Coordinate Points

Point X-Surf Y-Surf

13/22

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 750 44 | 558 90 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 07 | 565 91 |
| 9 | 972 96 | 573 99 |
| 10 | 979 03 | 581 94 |
| 11 | 985 98 | 589 13 |
| 12 | 992 75 | 596 49 |
| 13 | 999 58 | 603 80 |
| 14 | 1005 98 | 611 48 |
| 15 | 1012 13 | 619 37 |
| 16 | 1017 76 | 627 63 |
| 17 | 1024 20 | 635 28 |
| 18 | 1031 24 | 642 38 |
| 19 | 1037 61 | 650 09 |
| 20 | 1039 59 | 655 28 |

*** 1 067 ***

Individual data on the 21 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 0 5 | 2 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 2 | 0 0 | 0 0 |
| 2 | 0 1 | 1 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 1 | 0 0 | 0 0 |
| 3 | 49 0 | 20604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2060 4 | 0 0 | 0 0 |
| 4 | 50 0 | 62274 9 | 0 0 | 0 0 | 0 0 | 0 0 | 6227 5 | 0 0 | 0 0 |
| 5 | 50 0 | 103941 6 | 0 0 | 0 0 | 0 0 | 0 0 | 10394 2 | 0 0 | 0 0 |
| 6 | 50 0 | 145608 2 | 0 0 | 0 0 | 0 0 | 0 0 | 14560 8 | 0 0 | 0 0 |
| 7 | 10 0 | 34121 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3412 2 | 0 0 | 0 0 |
| 8 | 0 0 | 34 6 | 0 0 | 0 0 | 0 0 | 0 0 | 3 5 | 0 0 | 0 0 |
| 9 | 7 1 | 23844 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2384 5 | 0 0 | 0 0 |
| 10 | 5 9 | 18298 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1829 9 | 0 0 | 0 0 |
| 11 | 6 1 | 17020 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1702 0 | 0 0 | 0 0 |
| 12 | 7 0 | 17640 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1764 1 | 0 0 | 0 0 |
| 13 | 6 8 | 15483 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1548 4 | 0 0 | 0 0 |
| 14 | 6 8 | 13874 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1387 5 | 0 0 | 0 0 |
| 15 | 6 4 | 11318 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1131 9 | 0 0 | 0 0 |
| 16 | 6 1 | 9124 3 | 0 0 | 0 0 | 0 0 | 0 0 | 912 4 | 0 0 | 0 0 |
| 17 | 5 6 | 6637 1 | 0 0 | 0 0 | 0 0 | 0 0 | 663 7 | 0 0 | 0 0 |
| 18 | 6 4 | 5678 5 | 0 0 | 0 0 | 0 0 | 0 0 | 567 8 | 0 0 | 0 0 |
| 19 | 7 0 | 4393 2 | 0 0 | 0 0 | 0 0 | 0 0 | 439 3 | 0 0 | 0 0 |
| 20 | 6 4 | 2331 1 | 0 0 | 0 0 | 0 0 | 0 0 | 233 1 | 0 0 | 0 0 |
| 21 | 2 0 | 224 2 | 0 0 | 0 0 | 0 0 | 0 0 | 22 4 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 02 | 565 96 |
| 9 | 973 57 | 573 52 |
| 10 | 979 85 | 581 30 |
| 11 | 986 80 | 588 49 |
| 12 | 992 13 | 596 95 |
| 13 | 998 36 | 604 78 |
| 14 | 1004 16 | 612 92 |
| 15 | 1011 21 | 620 01 |
| 16 | 1017 54 | 627 75 |
| 17 | 1024 59 | 634 85 |

14/22

| | | |
|----|---------|--------|
| 18 | 1031 59 | 641 99 |
| 19 | 1037 22 | 650 25 |
| 20 | 1038 88 | 655 04 |

*** 1 070 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 74 | 559 00 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 03 | 565 95 |
| 9 | 974 09 | 573 03 |
| 10 | 981 04 | 580 23 |
| 11 | 987 13 | 588 16 |
| 12 | 993 04 | 596 23 |
| 13 | 1000 11 | 603 30 |
| 14 | 1006 29 | 611 16 |
| 15 | 1011 81 | 619 49 |
| 16 | 1018 14 | 627 24 |
| 17 | 1025 16 | 634 36 |
| 18 | 1032 23 | 641 43 |
| 19 | 1034 13 | 651 25 |
| 20 | 1037 42 | 654 56 |

*** 1 071 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 04 | 565 95 |
| 9 | 974 09 | 573 03 |
| 10 | 980 44 | 580 76 |
| 11 | 987 42 | 587 92 |
| 12 | 992 15 | 596 73 |
| 13 | 999 19 | 603 83 |
| 14 | 1005 67 | 611 45 |
| 15 | 1012 16 | 619 05 |
| 16 | 1017 96 | 627 20 |
| 17 | 1024 95 | 634 35 |
| 18 | 1028 08 | 643 85 |
| 19 | 1034 26 | 651 71 |
| 20 | 1034 46 | 653 57 |

*** 1 075 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 74 | 559 00 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 91 | 566 07 |
| 9 | 973 88 | 573 24 |
| 10 | 980 94 | 580 32 |
| 11 | 987 13 | 588 17 |
| 12 | 994 17 | 595 28 |
| 13 | 999 01 | 604 03 |

15/22

| | | |
|----|---------|--------|
| 14 | 1006 02 | 611 16 |
| 15 | 1012 22 | 619 00 |
| 16 | 1017 65 | 627 40 |
| 17 | 1021 36 | 636 69 |
| 18 | 1025 70 | 645 70 |
| 19 | 1032 66 | 652 88 |
| 20 | 1032 74 | 653 00 |

*** 1 077 ***
Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 71 | 558 99 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 77 | 566 20 |
| 9 | 973 81 | 573 30 |
| 10 | 980 05 | 581 11 |
| 11 | 986 97 | 588 33 |
| 12 | 994 04 | 595 41 |
| 13 | 998 15 | 604 52 |
| 14 | 1005 13 | 611 69 |
| 15 | 1010 93 | 619 83 |
| 16 | 1015 61 | 628 67 |
| 17 | 1021 50 | 636 75 |
| 18 | 1026 92 | 645 15 |
| 19 | 1030 58 | 652 28 |

*** 1 079 ***
Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 82 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 06 | 565 92 |
| 9 | 972 30 | 574 44 |
| 10 | 978 94 | 581 92 |
| 11 | 984 16 | 590 44 |
| 12 | 990 56 | 598 13 |
| 13 | 997 56 | 605 27 |
| 14 | 1004 43 | 612 54 |
| 15 | 1011 27 | 619 83 |
| 16 | 1018 27 | 626 98 |
| 17 | 1023 57 | 635 46 |
| 18 | 1028 88 | 643 93 |
| 19 | 1035 95 | 651 01 |
| 20 | 1039 21 | 655 15 |

*** 1 079 ***
Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 60 | 558 95 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 83 | 566 14 |
| 9 | 973 63 | 573 48 |
| 10 | 980 29 | 580 93 |

10/22

| | | |
|----|---------|--------|
| 11 | 986 44 | 588 82 |
| 12 | 993 27 | 596 13 |
| 13 | 1000 10 | 603 43 |
| 14 | 1004 83 | 612 24 |
| 15 | 1011 89 | 619 32 |
| 16 | 1015 00 | 628 83 |
| 17 | 1022 01 | 635 96 |
| 18 | 1027 79 | 644 12 |
| 19 | 1030 10 | 652 12 |

*** 1 082 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 61 | 558 95 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 49 | 566 45 |
| 9 | 972 06 | 574 75 |
| 10 | 978 99 | 581 96 |
| 11 | 985 95 | 589 15 |
| 12 | 992 90 | 596 33 |
| 13 | 999 57 | 603 78 |
| 14 | 1003 98 | 612 76 |
| 15 | 1010 23 | 620 57 |
| 16 | 1017 26 | 627 68 |
| 17 | 1023 65 | 635 37 |
| 18 | 1030 72 | 642 45 |
| 19 | 1032 14 | 652 34 |
| 20 | 1032 64 | 652 96 |

*** 1 084 ***


Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 37 | 558 87 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 01 | 565 98 |
| 9 | 973 01 | 573 97 |
| 10 | 977 24 | 583 04 |
| 11 | 984 24 | 590 17 |
| 12 | 990 47 | 598 00 |
| 13 | 997 46 | 605 14 |
| 14 | 1004 10 | 612 62 |
| 15 | 1011 17 | 619 70 |
| 16 | 1017 47 | 627 46 |
| 17 | 1022 70 | 635 98 |
| 18 | 1028 48 | 644 15 |
| 19 | 1035 55 | 651 22 |
| 20 | 1039 41 | 655 22 |

*** 1 085 ***

Intermountain Regional Landfill Sliding Block

c:\program files\stedwin\lrf\23 pl2 Run By Greg Shafer, HDR 4/20/2010 04:18PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface | Load | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|-------|-------|
| a | 0.83 | | | | | | | | Honz | Eqk |
| b | 0.83 | | | | | | | | 0.200 | g< |
| c | 0.84 | UVSC | 1 | 113.6 | 121.0 | 3000.0 | 0.0 | W1 | | |
| d | 0.84 | Waste | 2 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| e | 0.84 | Liner | 3 | 50.0 | 50.0 | 0.0 | 18.0 | W1 | | |
| f | 0.84 | | | | | | | | | |
| g | 0.84 | | | | | | | | | |
| h | 0.84 | | | | | | | | | |
| i | 0.84 | | | | | | | | | |
| j | 0.84 | | | | | | | | | |

PCSTABL7 FSmin=0.83

Safety Factors Are Calculated By The Modified Janbu Method

STED



17/22

18/22

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 04 18PM
Run By Greg Shafer, HDR
Input Data Filename C 23 in
Output Filename C 23 OUT
Unit ENGLISH
Plotted Output Filename C 23 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Sliding Block

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

5 Top Boundaries
12 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 550 00 | 750 00 | 558 75 | 1 |
| 2 | 750 00 | 558 75 | 1140 00 | 688 75 | 2 |
| 3 | 1140 00 | 688 75 | 1440 00 | 688 75 | 2 |
| 4 | 1440 00 | 688 75 | 1760 00 | 608 75 | 2 |
| 5 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |
| 6 | 750 00 | 558 75 | 750 30 | 558 85 | 3 |
| 7 | 750 30 | 558 85 | 1560 00 | 558 85 | 3 |
| 8 | 1560 00 | 558 85 | 1759 90 | 608 75 | 3 |
| 9 | 1759 90 | 608 75 | 1760 00 | 608 75 | 3 |
| 10 | 750 00 | 558 75 | 1560 00 | 558 75 | 1 |
| 11 | 1560 00 | 558 75 | 1760 00 | 608 75 | 1 |
| 12 | 1760 00 | 608 75 | 2050 00 | 608 75 | 1 |

ISOTROPIC SOIL PARAMETERS

3 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |
| 3 | 50 0 | 50 0 | 0 0 | 18 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient Of 0 200 Has Been Assigned
A Vertical Earthquake Loading Coefficient Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random Technique For Generating Sliding Block Surfaces, Has Been Specified

1000 Trial Surfaces Have Been Generated
6 Boxes Specified For Generation Of Central Block Base
Length Of Line Segments For Active And Passive Portions Of Sliding Block Is 10 0

| Box No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Height (ft) |
|--------|-------------|-------------|--------------|--------------|-------------|
| 1 | 751 00 | 558 84 | 751 00 | 558 84 | 0 00 |
| 2 | 800 00 | 558 84 | 800 00 | 558 84 | 0 00 |
| 3 | 850 00 | 558 84 | 850 00 | 558 84 | 0 00 |
| 4 | 900 00 | 558 84 | 900 00 | 558 84 | 0 00 |
| 5 | 950 00 | 558 84 | 950 00 | 558 84 | 0 00 |
| 6 | 960 00 | 558 84 | 960 00 | 558 84 | 0 00 |

Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Janbu Method * *
Failure Surface Specified By 20 Coordinate Points
Point X-Surf Y-Surf

19/22

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 750 81 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 967 00 | 565 99 |
| 9 | 972 39 | 574 41 |
| 10 | 979 45 | 581 49 |
| 11 | 986 45 | 588 63 |
| 12 | 993 17 | 596 04 |
| 13 | 1000 13 | 603 22 |
| 14 | 1007 18 | 610 31 |
| 15 | 1013 23 | 618 27 |
| 16 | 1019 88 | 625 74 |
| 17 | 1026 86 | 632 90 |
| 18 | 1032 31 | 641 28 |
| 19 | 1039 31 | 648 42 |
| 20 | 1041 75 | 656 00 |

*** 0 830 ***

Individual data on the 21 slices

| Slice No | Width (ft) | Weight (lbs) | Water | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake | | |
|----------|------------|--------------|-----------------|-----------------|-------------------|------------------|-----------------|-----------------|----------------------|
| | | | Force Top (lbs) | Force Bot (lbs) | | | Force Hor (lbs) | Force Ver (lbs) | Surcharge Load (lbs) |
| 1 | 0 2 | 1 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 2 | 0 0 | 0 0 |
| 2 | 0 0 | 0 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 49 0 | 20604 4 | 0 0 | 0 0 | 0 0 | 0 0 | 4120 9 | 0 0 | 0 0 |
| 4 | 50 0 | 62274 9 | 0 0 | 0 0 | 0 0 | 0 0 | 12455 0 | 0 0 | 0 0 |
| 5 | 50 0 | 103941 6 | 0 0 | 0 0 | 0 0 | 0 0 | 20788 3 | 0 0 | 0 0 |
| 6 | 50 0 | 145608 2 | 0 0 | 0 0 | 0 0 | 0 0 | 29121 6 | 0 0 | 0 0 |
| 7 | 10 0 | 34121 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6824 3 | 0 0 | 0 0 |
| 8 | 0 0 | 34 1 | 0 0 | 0 0 | 0 0 | 0 0 | 6 8 | 0 0 | 0 0 |
| 9 | 7 0 | 23575 6 | 0 0 | 0 0 | 0 0 | 0 0 | 4715 1 | 0 0 | 0 0 |
| 10 | 5 4 | 16663 3 | 0 0 | 0 0 | 0 0 | 0 0 | 3332 7 | 0 0 | 0 0 |
| 11 | 7 1 | 19811 5 | 0 0 | 0 0 | 0 0 | 0 0 | 3962 3 | 0 0 | 0 0 |
| 12 | 7 0 | 17977 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3595 5 | 0 0 | 0 0 |
| 13 | 6 7 | 15558 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3111 7 | 0 0 | 0 0 |
| 14 | 7 0 | 14385 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2877 1 | 0 0 | 0 0 |
| 15 | 7 1 | 12879 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2575 9 | 0 0 | 0 0 |
| 16 | 6 1 | 9449 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1889 9 | 0 0 | 0 0 |
| 17 | 6 6 | 8500 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1700 0 | 0 0 | 0 0 |
| 18 | 7 0 | 7178 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1435 7 | 0 0 | 0 0 |
| 19 | 5 5 | 4050 2 | 0 0 | 0 0 | 0 0 | 0 0 | 810 0 | 0 0 | 0 0 |
| 20 | 7 0 | 3208 7 | 0 0 | 0 0 | 0 0 | 0 0 | 641 7 | 0 0 | 0 0 |
| 21 | 2 4 | 411 4 | 0 0 | 0 0 | 0 0 | 0 0 | 82 3 | 0 0 | 0 0 |

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 09 | 566 78 |
| 9 | 972 91 | 574 08 |
| 10 | 978 87 | 582 11 |
| 11 | 985 69 | 589 43 |
| 12 | 991 48 | 597 58 |
| 13 | 998 08 | 605 09 |
| 14 | 1004 94 | 612 37 |
| 15 | 1012 01 | 619 44 |
| 16 | 1019 08 | 626 51 |
| 17 | 1026 15 | 633 59 |

20/22

| | | |
|---|-------------|-------------|
| 18 | 1033 20 | 640 68 |
| 19 | 1038 93 | 648 87 |
| 20 | 1044 53 | 656 93 |
| *** | 0 833 | *** |
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 96 | 566 02 |
| 9 | 972 37 | 574 43 |
| 10 | 977 89 | 582 77 |
| 11 | 984 95 | 589 85 |
| 12 | 992 02 | 596 92 |
| 13 | 998 89 | 604 19 |
| 14 | 1005 95 | 611 27 |
| 15 | 1012 08 | 619 17 |
| 16 | 1018 78 | 626 59 |
| 17 | 1024 95 | 634 47 |
| 18 | 1030 69 | 642 65 |
| 19 | 1036 37 | 650 88 |
| 20 | 1036 89 | 654 38 |
| *** | 0 836 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 99 | 565 99 |
| 9 | 974 05 | 573 08 |
| 10 | 979 99 | 581 12 |
| 11 | 986 46 | 588 74 |
| 12 | 992 33 | 596 84 |
| 13 | 997 72 | 605 26 |
| 14 | 1004 76 | 612 36 |
| 15 | 1011 22 | 620 00 |
| 16 | 1018 02 | 627 33 |
| 17 | 1024 85 | 634 63 |
| 18 | 1031 80 | 641 83 |
| 19 | 1038 73 | 649 03 |
| 20 | 1038 81 | 655 02 |
| *** | 0 837 | *** |

| | | |
|---|-------------|-------------|
| Failure Surface Specified By 20 Coordinate Points | | |
| Point No | X-Surf (ft) | Y-Surf (ft) |
| 1 | 750 80 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 98 | 566 00 |
| 9 | 972 83 | 574 11 |
| 10 | 979 85 | 581 24 |
| 11 | 985 80 | 589 27 |
| 12 | 992 85 | 596 36 |
| 13 | 999 92 | 603 43 |

2/22

| | | |
|----|---------|--------|
| 14 | 1005 88 | 611 47 |
| 15 | 1012 34 | 619 10 |
| 16 | 1016 21 | 628 32 |
| 17 | 1022 75 | 635 89 |
| 18 | 1029 67 | 643 11 |
| 19 | 1034 59 | 651 81 |
| 20 | 1034 59 | 653 61 |

*** 0 838 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 17 | 566 71 |
| 9 | 973 11 | 573 91 |
| 10 | 980 18 | 580 99 |
| 11 | 987 03 | 588 27 |
| 12 | 994 10 | 595 34 |
| 13 | 1000 41 | 603 10 |
| 14 | 1007 31 | 610 33 |
| 15 | 1011 73 | 619 31 |
| 16 | 1015 48 | 628 58 |
| 17 | 1022 13 | 636 04 |
| 18 | 1028 64 | 643 63 |
| 19 | 1030 87 | 652 38 |

*** 0 840 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 82 | 559 02 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 84 | 566 14 |
| 9 | 973 87 | 573 25 |
| 10 | 980 90 | 580 36 |
| 11 | 987 03 | 588 26 |
| 12 | 992 93 | 596 33 |
| 13 | 999 90 | 603 50 |
| 14 | 1004 94 | 612 14 |
| 15 | 1011 74 | 619 48 |
| 16 | 1018 69 | 626 66 |
| 17 | 1024 54 | 634 77 |
| 18 | 1026 24 | 644 63 |
| 19 | 1032 55 | 652 38 |
| 20 | 1033 11 | 653 12 |

*** 0 840 ***

Failure Surface Specified By 20 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 66 | 558 97 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 70 | 566 26 |
| 9 | 973 14 | 573 91 |
| 10 | 979 70 | 581 46 |

| | | |
|----|---------|--------|
| 11 | 986 77 | 588 53 |
| 12 | 992 71 | 596 58 |
| 13 | 999 27 | 604 12 |
| 14 | 1004 68 | 612 54 |
| 15 | 1008 95 | 621 58 |
| 16 | 1015 71 | 628 95 |
| 17 | 1020 46 | 637 75 |
| 18 | 1027 53 | 644 82 |
| 19 | 1034 58 | 651 91 |
| 20 | 1035 07 | 653 77 |

*** 0 842 ***

Failure Surface Specified By 19 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 49 | 558 91 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 966 72 | 566 25 |
| 9 | 973 01 | 574 02 |
| 10 | 980 01 | 581 16 |
| 11 | 987 06 | 588 25 |
| 12 | 993 57 | 595 84 |
| 13 | 997 83 | 604 89 |
| 14 | 1002 99 | 613 46 |
| 15 | 1009 75 | 620 83 |
| 16 | 1016 68 | 628 03 |
| 17 | 1022 52 | 635 15 |
| 18 | 1029 27 | 643 53 |
| 19 | 1031 89 | 652 71 |


*** 0 842 ***

Failure Surface Specified By 19 Coordinate Points


| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 750 79 | 559 01 |
| 2 | 751 00 | 558 84 |
| 3 | 800 00 | 558 84 |
| 4 | 850 00 | 558 84 |
| 5 | 900 00 | 558 84 |
| 6 | 950 00 | 558 84 |
| 7 | 960 00 | 558 84 |
| 8 | 965 59 | 566 36 |
| 9 | 973 16 | 573 90 |
| 10 | 979 21 | 581 86 |
| 11 | 986 24 | 588 98 |
| 12 | 991 11 | 597 71 |
| 13 | 997 67 | 605 26 |
| 14 | 1003 09 | 613 66 |
| 15 | 1010 12 | 620 78 |
| 16 | 1016 97 | 628 06 |
| 17 | 1022 16 | 636 61 |
| 18 | 1026 22 | 645 75 |
| 19 | 1026 69 | 650 98 |

*** 0 844 ***

**ATTACHMENT 2C-2: SLOPE STABILITY RUNS &
RESULTS – FILL SLOPE**



| Horizontal Accel. | α | F.S. |
|-------------------|----------|------|
| Static | | 2.18 |
| | 0.1 | 1.75 |
| | 0.2 | 1.33 |
| | 0.3 | 0.94 |



1" = 200' H
1" = 50' V

$$\frac{-0.033}{0.39} = 0.2 - x$$

$$\boxed{x = 0.28}$$

$$\rightarrow \frac{1.33 - 0.94}{0.2 - 0.3} = \frac{1.33 - 1.0}{0.2 - x} \rightarrow \frac{0.39}{-0.1} = \frac{0.33}{0.2 - x}$$

| | | | | | |
|---------|-----------------|----------|-----|------|------------------|
| Project | IRL | Computed | GMS | Date | 3/2010 4/2010 |
| Subject | Slope Stability | Checked | | Date | |
| Task | Waste mass | Page | 2 | of | 46 |
| Job # | 125184 | Dept | 143 | No | |

Maximum Fill Slope Results / Displacement

$$a_{max} = 0.28 \text{ (Reference E)}$$

$$a_y = 0.28 \text{ (Previous page)}$$


$$\frac{a_y}{a_{max}} = \frac{0.28}{0.28} = 1.0 \quad @ \quad M=70$$

See Attachment 273 (Reference A)

$$U_{max} = 0.05 \text{ cm} < 30 \text{ cm (allowable)} \quad \underline{\underline{OK}}$$

Intermountain Regional Landfill Fill Slope 1


c:\program files\stedwin\l11 pi2 Run By Greg Shafer HDR 4/20/2010 03 35PM



PCSTABL7 FSmin=2.18

Safety Factors Are Calculated By The Modified Bishop Method

STED



3/46

4/26

** PCSTABL7 **

by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 35PM
Run By Greg Shafer, HDR
Input Data Filename C 11 in
Output Filename C 11 OUT
Unit ENGLISH
Plotted Output Filename C 11 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Critical Failure Surface Searching Method, Using A Random
Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 600 00 ft
and X = 850 00 ft

Each Surface Terminates Between X =1100 00 ft
and X =1250 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *
Failure Surface Specified By 47 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 92 | 619 02 |
| 3 | 775 65 | 616 69 |
| 4 | 785 42 | 614 58 |
| 5 | 795 24 | 612 67 |
| 6 | 805 10 | 610 99 |
| 7 | 814 99 | 609 52 |
| 8 | 824 91 | 608 26 |
| 9 | 834 85 | 607 22 |
| 10 | 844 82 | 606 40 |

5/40

| | | |
|----|---------|--------|
| 11 | 854 80 | 605 80 |
| 12 | 864 79 | 605 42 |
| 13 | 874 79 | 605 25 |
| 14 | 884 79 | 605 30 |
| 15 | 894 79 | 605 58 |
| 16 | 904 78 | 606 07 |
| 17 | 914 75 | 606 77 |
| 18 | 924 71 | 607 70 |
| 19 | 934 64 | 608 84 |
| 20 | 944 55 | 610 20 |
| 21 | 954 43 | 611 78 |
| 22 | 964 26 | 613 57 |
| 23 | 974 06 | 615 57 |
| 24 | 983 81 | 617 79 |
| 25 | 993 51 | 620 23 |
| 26 | 1003 16 | 622 87 |
| 27 | 1012 74 | 625 72 |
| 28 | 1022 26 | 628 78 |
| 29 | 1031 71 | 632 05 |
| 30 | 1041 09 | 635 53 |
| 31 | 1050 39 | 639 21 |
| 32 | 1059 60 | 643 09 |
| 33 | 1068 73 | 647 17 |
| 34 | 1077 77 | 651 45 |
| 35 | 1086 71 | 655 93 |
| 36 | 1095 55 | 660 60 |
| 37 | 1104 29 | 665 46 |
| 38 | 1112 92 | 670 51 |
| 39 | 1121 44 | 675 75 |
| 40 | 1129 84 | 681 18 |
| 41 | 1138 12 | 586 78 |
| 42 | 1146 27 | 692 57 |
| 43 | 1154 30 | 698 53 |
| 44 | 1162 20 | 704 67 |
| 45 | 1169 96 | 710 98 |
| 46 | 1177 58 | 717 46 |
| 47 | 1182 47 | 721 80 |

Circle Center At X = 877 4 , Y = 1062 9 and Radius, 457 7

*** 2 184 ***

Individual data on the 47 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 7 | 1199 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 2 | 9 7 | 3568 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 3 | 9 8 | 5863 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 4 | 9 8 | 8078 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 5 | 9 9 | 10206 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 6 | 9 9 | 12244 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 7 | 9 9 | 14185 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 8 | 9 9 | 16026 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 9 | 10 0 | 17762 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 10 | 10 0 | 19389 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 11 | 10 0 | 20904 4 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 12 | 10 0 | 22303 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 13 | 10 0 | 23584 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 14 | 10 0 | 24744 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 15 | 10 0 | 25781 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 16 | 10 0 | 26693 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 17 | 10 0 | 27479 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 18 | 9 9 | 28138 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 19 | 9 9 | 28670 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 20 | 9 9 | 29073 3 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 21 | 9 8 | 29349 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 22 | 9 8 | 29497 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 23 | 9 8 | 29520 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 24 | 9 7 | 29417 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

6/46

| | | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|-----|-----|-----|-----|
| 25 | 9 6 | 29191 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 26 | 9 6 | 28845 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 27 | 9 5 | 28379 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 28 | 9 5 | 27797 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 29 | 9 4 | 27103 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 30 | 9 3 | 26300 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 31 | 9 2 | 25391 1 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 32 | 9 1 | 24381 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 33 | 9 0 | 23273 8 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 34 | 8 9 | 22074 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 35 | 8 8 | 20789 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 36 | 8 7 | 19421 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 37 | 8 6 | 17978 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 38 | 8 5 | 16465 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 39 | 8 4 | 14888 6 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 40 | 8 3 | 13254 5 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 41 | 8 2 | 11570 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 42 | 3 7 | 4764 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 43 | 4 3 | 4986 9 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 44 | 7 9 | 7443 7 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 45 | 7 8 | 5070 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 46 | 7 6 | 2706 2 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |
| 47 | 4 9 | 499 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 | 0 0 |

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 83 | 624 51 |
| 3 | 796 61 | 622 47 |
| 4 | 806 44 | 620 63 |
| 5 | 816 31 | 619 01 |
| 6 | 826 21 | 617 61 |
| 7 | 836 14 | 616 42 |
| 8 | 846 10 | 615 45 |
| 9 | 856 07 | 614 69 |
| 10 | 866 05 | 614 15 |
| 11 | 876 05 | 613 83 |
| 12 | 886 05 | 613 72 |
| 13 | 896 05 | 613 84 |
| 14 | 906 04 | 614 16 |
| 15 | 916 03 | 614 71 |
| 16 | 926 00 | 615 47 |
| 17 | 935 95 | 616 45 |
| 18 | 945 88 | 617 65 |
| 19 | 955 78 | 619 06 |
| 20 | 965 64 | 620 69 |
| 21 | 975 47 | 622 53 |
| 22 | 985 26 | 624 58 |
| 23 | 995 00 | 626 84 |
| 24 | 1004 69 | 629 32 |
| 25 | 1014 32 | 632 01 |
| 26 | 1023 89 | 634 90 |
| 27 | 1033 40 | 638 00 |
| 28 | 1042 84 | 641 31 |
| 29 | 1052 20 | 644 82 |
| 30 | 1061 48 | 648 54 |
| 31 | 1070 69 | 652 45 |
| 32 | 1079 80 | 656 57 |
| 33 | 1088 82 | 660 88 |
| 34 | 1097 75 | 665 39 |
| 35 | 1106 58 | 670 09 |
| 36 | 1115 30 | 674 98 |
| 37 | 1123 91 | 680 05 |
| 38 | 1132 41 | 685 32 |
| 39 | 1140 80 | 690 77 |
| 40 | 1149 07 | 696 40 |
| 41 | 1157 21 | 702 20 |
| 42 | 1165 22 | 708 19 |

7/26

43 1173 10 714 34
 44 1180 85 720 67
 45 1182 16 721 79
 Circle Center At X = 885 9 , Y = 1073 9 and Radius, 460 2
 *** 2 200 ***

Failure Surface Specified By 46 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 16 | 621 03 |
| 3 | 785 74 | 618 15 |
| 4 | 795 38 | 615 50 |
| 5 | 805 09 | 613 11 |
| 6 | 814 86 | 610 96 |
| 7 | 824 68 | 609 07 |
| 8 | 834 54 | 607 42 |
| 9 | 844 44 | 606 03 |
| 10 | 854 38 | 604 89 |
| 11 | 864 34 | 604 01 |
| 12 | 874 32 | 603 38 |
| 13 | 884 31 | 603 01 |
| 14 | 894 31 | 602 89 |
| 15 | 904 31 | 603 03 |
| 16 | 914 30 | 603 43 |
| 17 | 924 28 | 604 08 |
| 18 | 934 24 | 604 98 |
| 19 | 944 17 | 606 14 |
| 20 | 954 07 | 607 56 |
| 21 | 963 93 | 609 22 |
| 22 | 973 75 | 611 14 |
| 23 | 983 51 | 613 31 |
| 24 | 993 21 | 615 73 |
| 25 | 1002 85 | 618 39 |
| 26 | 1012 42 | 621 31 |
| 27 | 1021 91 | 624 46 |
| 28 | 1031 31 | 627 86 |
| 29 | 1040 63 | 631 49 |
| 30 | 1049 85 | 635 36 |
| 31 | 1058 97 | 639 47 |
| 32 | 1067 98 | 643 81 |
| 33 | 1076 87 | 648 38 |
| 34 | 1085 65 | 653 17 |
| 35 | 1094 30 | 658 19 |
| 36 | 1102 82 | 663 43 |
| 37 | 1111 20 | 668 88 |
| 38 | 1119 44 | 674 55 |
| 39 | 1127 53 | 680 42 |
| 40 | 1135 47 | 686 50 |
| 41 | 1143 25 | 692 78 |
| 42 | 1150 87 | 699 26 |
| 43 | 1158 32 | 705 93 |
| 44 | 1165 60 | 712 79 |
| 45 | 1172 70 | 719 83 |
| 46 | 1174 14 | 721 34 |

Circle Center At X = 893 9 , Y = 993 7 and Radius, 390 8
 *** 2 214 ***

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 70 | 618 30 |
| 3 | 775 24 | 615 30 |
| 4 | 784 86 | 612 56 |
| 5 | 794 55 | 610 09 |
| 6 | 804 30 | 607 87 |
| 7 | 814 11 | 605 92 |
| 8 | 823 97 | 604 24 |
| 9 | 833 87 | 602 83 |

8/46

| | | |
|----|---------|--------|
| 10 | 843 80 | 601 69 |
| 11 | 853 76 | 600 81 |
| 12 | 863 75 | 600 21 |
| 13 | 873 74 | 599 88 |
| 14 | 883 74 | 599 82 |
| 15 | 893 74 | 600 04 |
| 16 | 903 73 | 600 52 |
| 17 | 913 70 | 601 28 |
| 18 | 923 64 | 602 30 |
| 19 | 933 56 | 603 60 |
| 20 | 943 44 | 605 16 |
| 21 | 953 27 | 607 00 |
| 22 | 963 04 | 609 10 |
| 23 | 972 76 | 611 46 |
| 24 | 982 41 | 614 09 |
| 25 | 991 98 | 616 98 |
| 26 | 1001 47 | 620 13 |
| 27 | 1010 88 | 623 53 |
| 28 | 1020 18 | 627 19 |
| 29 | 1029 39 | 631 10 |
| 30 | 1038 48 | 635 26 |
| 31 | 1047 46 | 639 66 |
| 32 | 1056 32 | 644 31 |
| 33 | 1065 04 | 649 19 |
| 34 | 1073 63 | 654 31 |
| 35 | 1082 08 | 659 67 |
| 36 | 1090 38 | 665 25 |
| 37 | 1098 52 | 671 05 |
| 38 | 1106 50 | 677 07 |
| 39 | 1114 32 | 683 31 |
| 40 | 1121 96 | 689 75 |
| 41 | 1129 43 | 696 41 |
| 42 | 1136 71 | 703 26 |
| 43 | 1143 81 | 710 31 |
| 44 | 1150 71 | 717 55 |
| 45 | 1153 08 | 720 17 |

Circle Center At X = 880 9 , Y = 967 8 and Radius, 368 0

*** 2 219 ***

Failure Surface Specified By 42 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 57 | 622 80 |
| 3 | 786 51 | 621 63 |
| 4 | 796 46 | 620 65 |
| 5 | 806 43 | 619 86 |
| 6 | 816 41 | 619 27 |
| 7 | 826 40 | 618 86 |
| 8 | 836 40 | 618 65 |
| 9 | 846 40 | 618 63 |
| 10 | 856 40 | 618 80 |
| 11 | 866 39 | 619 16 |
| 12 | 876 37 | 619 71 |
| 13 | 886 35 | 620 46 |
| 14 | 896 30 | 621 40 |
| 15 | 906 24 | 622 53 |
| 16 | 916 15 | 623 85 |
| 17 | 926 04 | 625 36 |
| 18 | 935 89 | 627 06 |
| 19 | 945 71 | 628 94 |
| 20 | 955 49 | 631 02 |
| 21 | 965 23 | 633 29 |
| 22 | 974 93 | 635 74 |
| 23 | 984 57 | 638 37 |
| 24 | 994 17 | 641 20 |
| 25 | 1003 71 | 644 20 |
| 26 | 1013 18 | 647 39 |
| 27 | 1022 60 | 650 76 |

9/26

| | | |
|----|---------|--------|
| 28 | 1031 95 | 654 31 |
| 29 | 1041 23 | 658 04 |
| 30 | 1050 43 | 661 94 |
| 31 | 1059 56 | 666 03 |
| 32 | 1068 61 | 670 28 |
| 33 | 1077 57 | 674 71 |
| 34 | 1086 45 | 679 32 |
| 35 | 1095 24 | 684 09 |
| 36 | 1103 94 | 689 03 |
| 37 | 1112 53 | 694 13 |
| 38 | 1121 03 | 699 40 |
| 39 | 1129 43 | 704 83 |
| 40 | 1137 72 | 710 43 |
| 41 | 1145 90 | 716 18 |
| 42 | 1151 22 | 720 07 |

Circle Center At X = 842 5 , Y = 1139 0 and Radius, 520 3

*** 2 227 ***

Failure Surface Specified By 40 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 33 | 621 61 |
| 3 | 786 07 | 619 30 |
| 4 | 795 85 | 617 26 |
| 5 | 805 69 | 615 48 |
| 6 | 815 58 | 613 96 |
| 7 | 825 50 | 612 70 |
| 8 | 835 45 | 611 71 |
| 9 | 845 42 | 610 99 |
| 10 | 855 41 | 610 53 |
| 11 | 865 41 | 610 33 |
| 12 | 875 41 | 610 40 |
| 13 | 885 41 | 610 74 |
| 14 | 895 39 | 611 35 |
| 15 | 905 35 | 612 22 |
| 16 | 915 28 | 613 35 |
| 17 | 925 19 | 614 75 |
| 18 | 935 05 | 616 41 |
| 19 | 944 86 | 618 33 |
| 20 | 954 62 | 620 52 |
| 21 | 964 32 | 622 96 |
| 22 | 973 94 | 625 66 |
| 23 | 983 50 | 628 62 |
| 24 | 992 97 | 631 82 |
| 25 | 1002 35 | 635 28 |
| 26 | 1011 64 | 638 99 |
| 27 | 1020 82 | 642 94 |
| 28 | 1029 90 | 647 14 |
| 29 | 1038 86 | 651 58 |
| 30 | 1047 70 | 656 25 |
| 31 | 1056 42 | 661 16 |
| 32 | 1065 00 | 666 30 |
| 33 | 1073 44 | 671 66 |
| 34 | 1081 73 | 677 25 |
| 35 | 1089 87 | 683 05 |
| 36 | 1097 86 | 689 07 |
| 37 | 1105 68 | 695 30 |
| 38 | 1113 33 | 701 74 |
| 39 | 1120 81 | 708 38 |
| 40 | 1127 11 | 714 28 |

Circle Center At X = 867 7 , Y = 986 0 and Radius, 375 6

*** 2 233 ***

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 06 | 626 45 |
| 3 | 806 69 | 623 75 |

10/
16

| | | |
|----|---------|--------|
| 4 | 816 39 | 621 30 |
| 5 | 826 14 | 619 09 |
| 6 | 835 95 | 517 13 |
| 7 | 845 80 | 615 41 |
| 8 | 855 69 | 613 93 |
| 9 | 865 61 | 612 70 |
| 10 | 875 56 | 611 72 |
| 11 | 885 54 | 610 99 |
| 12 | 895 52 | 610 50 |
| 13 | 905 52 | 610 26 |
| 14 | 915 52 | 610 28 |
| 15 | 925 52 | 610 54 |
| 16 | 935 51 | 611 05 |
| 17 | 945 48 | 611 80 |
| 18 | 955 43 | 612 81 |
| 19 | 965 35 | 614 06 |
| 20 | 975 23 | 615 56 |
| 21 | 985 08 | 617 30 |
| 22 | 994 88 | 619 29 |
| 23 | 1004 63 | 621 52 |
| 24 | 1014 32 | 624 00 |
| 25 | 1023 94 | 626 71 |
| 26 | 1033 50 | 629 67 |
| 27 | 1042 97 | 632 85 |
| 28 | 1052 37 | 636 28 |
| 29 | 1061 68 | 639 94 |
| 30 | 1070 89 | 643 82 |
| 31 | 1080 00 | 647 94 |
| 32 | 1089 01 | 652 28 |
| 33 | 1097 91 | 656 84 |
| 34 | 1106 69 | 661 63 |
| 35 | 1115 35 | 666 63 |
| 36 | 1123 89 | 671 84 |
| 37 | 1132 29 | 677 27 |
| 38 | 1140 55 | 682 90 |
| 39 | 1148 67 | 688 74 |
| 40 | 1156 64 | 694 77 |
| 41 | 1164 46 | 701 00 |
| 42 | 1172 12 | 707 43 |
| 43 | 1179 62 | 714 04 |
| 44 | 1186 96 | 720 84 |
| 45 | 1188 28 | 722 13 |

Circle Center At X = 910 0 , Y = 1012 2 and Radius, 401 9
*** 2 233 ***

Failure Surface Specified By 40 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 47 | 622 17 |
| 3 | 786 31 | 620 41 |
| 4 | 796 19 | 618 89 |
| 5 | 806 11 | 617 61 |
| 6 | 816 06 | 616 56 |
| 7 | 826 02 | 615 76 |
| 8 | 836 01 | 615 19 |
| 9 | 846 00 | 614 87 |
| 10 | 856 00 | 614 78 |
| 11 | 866 00 | 614 94 |
| 12 | 875 99 | 615 33 |
| 13 | 885 97 | 615 97 |
| 14 | 895 93 | 616 85 |
| 15 | 905 87 | 617 97 |
| 16 | 915 78 | 619 32 |
| 17 | 925 65 | 620 92 |
| 18 | 935 48 | 622 75 |
| 19 | 945 27 | 624 81 |
| 20 | 955 00 | 627 11 |
| 21 | 964 67 | 629 65 |

11/26

| | | |
|----|---------|--------|
| 22 | 974 28 | 632 42 |
| 23 | 983 82 | 635 41 |
| 24 | 993 29 | 638 64 |
| 25 | 1002 67 | 642 09 |
| 26 | 1011 97 | 645 77 |
| 27 | 1021 18 | 649 67 |
| 28 | 1030 29 | 653 79 |
| 29 | 1039 30 | 658 13 |
| 30 | 1048 20 | 662 69 |
| 31 | 1055 99 | 667 45 |
| 32 | 1065 67 | 672 43 |
| 33 | 1074 22 | 677 62 |
| 34 | 1082 64 | 683 00 |
| 35 | 1090 93 | 688 59 |
| 36 | 1099 09 | 694 38 |
| 37 | 1107 10 | 700 37 |
| 38 | 1114 97 | 706 54 |
| 39 | 1122 68 | 712 90 |
| 40 | 1123 12 | 713 28 |

Circle Center At X = 854 5 , Y = 1030 3 and Radius, 415 5
*** 2 240 ***

Failure Surface Specified By 40 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 48 | 629 06 |
| 3 | 817 12 | 626 41 |
| 4 | 826 84 | 624 04 |
| 5 | 836 62 | 621 94 |
| 6 | 846 45 | 620 12 |
| 7 | 856 33 | 618 58 |
| 8 | 866 25 | 617 32 |
| 9 | 876 20 | 616 35 |
| 10 | 886 18 | 615 65 |
| 11 | 896 17 | 615 24 |
| 12 | 906 17 | 615 11 |
| 13 | 916 17 | 615 27 |
| 14 | 926 16 | 615 71 |
| 15 | 936 13 | 616 43 |
| 16 | 946 08 | 617 43 |
| 17 | 956 00 | 618 72 |
| 18 | 965 88 | 620 29 |
| 19 | 975 70 | 622 13 |
| 20 | 985 48 | 624 26 |
| 21 | 995 18 | 626 66 |
| 22 | 1004 82 | 629 33 |
| 23 | 1014 37 | 632 28 |
| 24 | 1023 84 | 635 50 |
| 25 | 1033 22 | 638 98 |
| 26 | 1042 49 | 642 73 |
| 27 | 1051 65 | 646 74 |
| 28 | 1060 69 | 651 00 |
| 29 | 1069 61 | 655 53 |
| 30 | 1078 40 | 660 30 |
| 31 | 1087 05 | 665 32 |
| 32 | 1095 55 | 670 59 |
| 33 | 1103 90 | 676 09 |
| 34 | 1112 09 | 681 83 |
| 35 | 1120 11 | 687 79 |
| 36 | 1127 97 | 693 98 |
| 37 | 1135 64 | 700 40 |
| 38 | 1143 13 | 707 02 |
| 39 | 1150 43 | 713 86 |
| 40 | 1157 01 | 720 39 |

Circle Center At X = 905 7 , Y = 967 7 and Radius, 352 6
*** 2 241 ***

Failure Surface Specified By 41 Coordinate Points

| Point | X-Surf | Y-Surf |
|-------|--------|--------|
|-------|--------|--------|


12/10

| No | (ft) | (ft) |
|----|---------|--------|
| 1 | 777 08 | 626 77 |
| 2 | 787 00 | 625 49 |
| 3 | 796 94 | 624 40 |
| 4 | 806 90 | 623 50 |
| 5 | 816 88 | 622 80 |
| 6 | 826 86 | 622 29 |
| 7 | 836 86 | 621 97 |
| 8 | 846 86 | 621 84 |
| 9 | 856 86 | 621 90 |
| 10 | 866 85 | 622 16 |
| 11 | 876 84 | 622 61 |
| 12 | 886 82 | 623 26 |
| 13 | 896 79 | 624 09 |
| 14 | 906 74 | 625 12 |
| 15 | 916 66 | 626 34 |
| 16 | 926 56 | 627 75 |
| 17 | 936 43 | 629 35 |
| 18 | 946 27 | 631 14 |
| 19 | 956 07 | 633 12 |
| 20 | 965 83 | 635 29 |
| 21 | 975 55 | 637 64 |
| 22 | 985 22 | 640 18 |
| 23 | 994 85 | 642 91 |
| 24 | 1004 41 | 645 83 |
| 25 | 1013 92 | 648 92 |
| 26 | 1023 37 | 652 21 |
| 27 | 1032 75 | 655 67 |
| 28 | 1042 06 | 659 31 |
| 29 | 1051 30 | 663 13 |
| 30 | 1060 47 | 667 13 |
| 31 | 1069 56 | 671 30 |
| 32 | 1078 56 | 675 65 |
| 33 | 1087 48 | 680 17 |
| 34 | 1096 31 | 684 87 |
| 35 | 1105 05 | 689 73 |
| 36 | 1113 69 | 694 76 |
| 37 | 1122 24 | 699 95 |
| 38 | 1130 68 | 705 31 |
| 39 | 1139 02 | 710 83 |
| 40 | 1147 25 | 716 51 |
| 41 | 1152 28 | 720 13 |

Circle Center At X = 848 5 , Y = 1140 6 and Radius, 518 8
*** 2 244 ***

Intermountain Regional Landfill Fill Slope 1

c:\program files\stedwin\lrl\12 pl2 Run By Greg Shafer, HDR 4/20/2010 03:39PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt. (pcf) | Saturated Unit Wt. (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface | Load | Value |
|---|------|-----------|-----------|----------------------|--------------------------|--------------------------|----------------------|--------------|----------|----------|
| a | 1.53 | | | | | | | | | |
| b | 1.54 | | | | | | | | | |
| c | 1.54 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 | Honz Eqk | 0.100 g< |
| d | 1.55 | LSC | 2 | 121.0 | 125.5 | 1500.0 | 0.0 | W1 | | |
| e | 1.55 | SC | 3 | 121.0 | 125.5 | 2000.0 | 0.0 | W1 | | |
| f | 1.55 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | 0.0 | W1 | | |
| g | 1.55 | Waste | 5 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| h | 1.55 | | | | | | | | | |
| i | 1.55 | | | | | | | | | |
| 1 | 1.55 | | | | | | | | | |

PCSTABL7 FSmin=1.53

Safety Factors Are Calculated By The Modified Bishop Method

STED



13/A6

**** PCSTABL7 ****

by
 Purdue University
 --Slope Stability Analysis--
 Simplified Janbu, Simplified Bishop
 or Spencer s Method of Slices

Run Date 4/20/2010
 Time of Run 03 39PM
 Run By Greg Shafer, HDR
 Input Data Filename C 12 in
 Output Filename C 12 OUT
 Unit ENGLISH
 Plotted Output Filename C 12 PLT
 PROBLEM DESCRIPTION Intermountain Regional Landfill
 Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
 Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
 8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient

Of 0 100 Has Been Assigned

A Vertical Earthquake Loading Coefficient

Of 0 000 Has Been Assigned

Cavitation Pressure = 0 0 (psf)

A Critical Failure Surface Searching Method, Using A Random
 Technique For Generating Circular Surfaces, Has Been Specified
 625 Trial Surfaces Have Been Generated

25 Surfaces Initiate From Each Of 25 Points Equally Spaced

Along The Ground Surface Between X = 600 00 ft
 and X = 850 00 ft

Each Surface Terminates Between X =1100 00 ft
 and X =1250 00 ft

Unless Further Limitations Were Imposed, The Minimum Elevation

At Which A Surface Extends Is Y = 0 00 ft

10 00 ft Line Segments Define Each Trial Failure Surface

Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
 First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 11 | 619 87 |
| 3 | 775 99 | 618 37 |
| 4 | 785 91 | 617 06 |
| 5 | 795 84 | 615 93 |

15/A6

| | | |
|----|---------|--------|
| 6 | 805 80 | 615 00 |
| 7 | 815 77 | 614 27 |
| 8 | 825 76 | 613 72 |
| 9 | 835 75 | 613 36 |
| 10 | 845 75 | 613 20 |
| 11 | 855 75 | 613 23 |
| 12 | 865 75 | 613 45 |
| 13 | 875 74 | 613 87 |
| 14 | 885 72 | 614 47 |
| 15 | 895 69 | 615 27 |
| 16 | 905 64 | 616 26 |
| 17 | 915 57 | 617 44 |
| 18 | 925 48 | 618 81 |
| 19 | 935 35 | 620 37 |
| 20 | 945 20 | 622 12 |
| 21 | 955 01 | 624 06 |
| 22 | 964 78 | 626 18 |
| 23 | 974 51 | 628 50 |
| 24 | 984 19 | 631 00 |
| 25 | 993 82 | 633 68 |
| 26 | 1003 40 | 636 56 |
| 27 | 1012 92 | 639 61 |
| 28 | 1022 39 | 642 85 |
| 29 | 1031 78 | 646 26 |
| 30 | 1041 11 | 649 86 |
| 31 | 1050 37 | 653 64 |
| 32 | 1059 56 | 557 59 |
| 33 | 1068 67 | 661 72 |
| 34 | 1077 69 | 666 03 |
| 35 | 1086 63 | 670 50 |
| 36 | 1095 49 | 675 15 |
| 37 | 1104 25 | 679 97 |
| 38 | 1112 92 | 684 95 |
| 39 | 1121 49 | 690 10 |
| 40 | 1129 96 | 695 42 |
| 41 | 1138 33 | 700 89 |
| 42 | 1146 59 | 706 53 |
| 43 | 1154 74 | 712 32 |
| 44 | 1162 78 | 718 27 |
| 45 | 1166 19 | 720 90 |

Circle Center At X = 849 2 , Y = 1133 5 and Radius, 520 4
 *** 1 528 ***

Individual data on the 45 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force Surcharge | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|----------------------------|-----------|------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | Load (lbs) |
| 1 | 9 9 | 1024 0 | 0 0 | 0 0 | 0 0 | 0 0 | 102 4 | 0 0 | 0 0 |
| 2 | 9 9 | 3036 7 | 0 0 | 0 0 | 0 0 | 0 0 | 303 7 | 0 0 | 0 0 |
| 3 | 9 9 | 4969 3 | 0 0 | 0 0 | 0 0 | 0 0 | 496 9 | 0 0 | 0 0 |
| 4 | 9 9 | 6818 5 | 0 0 | 0 0 | 0 0 | 0 0 | 681 8 | 0 0 | 0 0 |
| 5 | 10 0 | 8580 7 | 0 0 | 0 0 | 0 0 | 0 0 | 858 1 | 0 0 | 0 0 |
| 6 | 10 0 | 10252 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1025 3 | 0 0 | 0 0 |
| 7 | 10 0 | 11831 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1183 2 | 0 0 | 0 0 |
| 8 | 10 0 | 13315 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1331 5 | 0 0 | 0 0 |
| 9 | 10 0 | 14700 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1470 1 | 0 0 | 0 0 |
| 10 | 10 0 | 15985 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1598 6 | 0 0 | 0 0 |
| 11 | 10 0 | 17169 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1716 9 | 0 0 | 0 0 |
| 12 | 10 0 | 18248 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1824 8 | 0 0 | 0 0 |
| 13 | 10 0 | 19221 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1922 2 | 0 0 | 0 0 |
| 14 | 10 0 | 20089 4 | 0 0 | 0 0 | 0 0 | 0 0 | 2008 9 | 0 0 | 0 0 |
| 15 | 10 0 | 20849 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2084 9 | 0 0 | 0 0 |
| 16 | 9 9 | 21501 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2150 1 | 0 0 | 0 0 |
| 17 | 9 9 | 22044 9 | 0 0 | 0 0 | 0 0 | 0 0 | 2204 5 | 0 0 | 0 0 |
| 18 | 9 9 | 22479 7 | 0 0 | 0 0 | 0 0 | 0 0 | 2248 0 | 0 0 | 0 0 |
| 19 | 9 8 | 22806 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2280 6 | 0 0 | 0 0 |
| 20 | 9 8 | 23024 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2302 5 | 0 0 | 0 0 |
| 21 | 9 8 | 23135 6 | 0 0 | 0 0 | 0 0 | 0 0 | 2313 6 | 0 0 | 0 0 |

16/16

| | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|--------|-----|-----|
| 22 | 9 7 | 23140 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2314 0 | 0 0 | 0 0 |
| 23 | 9 7 | 23039 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2303 9 | 0 0 | 0 0 |
| 24 | 9 6 | 22834 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2283 4 | 0 0 | 0 0 |
| 25 | 9 6 | 22526 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2252 7 | 0 0 | 0 0 |
| 26 | 9 5 | 22119 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2211 9 | 0 0 | 0 0 |
| 27 | 9 5 | 21613 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2161 3 | 0 0 | 0 0 |
| 28 | 9 4 | 21011 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2101 1 | 0 0 | 0 0 |
| 29 | 9 3 | 20315 7 | 0 0 | 0 0 | 0 0 | 0 0 | 2031 6 | 0 0 | 0 0 |
| 30 | 9 3 | 19530 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1953 0 | 0 0 | 0 0 |
| 31 | 9 2 | 18656 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1865 7 | 0 0 | 0 0 |
| 32 | 9 1 | 17699 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1770 0 | 0 0 | 0 0 |
| 33 | 9 0 | 16662 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1666 2 | 0 0 | 0 0 |
| 34 | 8 9 | 15547 4 | 0 0 | 0 0 | 0 0 | 0 0 | 1554 7 | 0 0 | 0 0 |
| 35 | 8 9 | 14360 1 | 0 0 | 0 0 | 0 0 | 0 0 | 1436 0 | 0 0 | 0 0 |
| 36 | 8 8 | 13103 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1310 4 | 0 0 | 0 0 |
| 37 | 8 7 | 11783 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1178 3 | 0 0 | 0 0 |
| 38 | 8 6 | 10402 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1040 3 | 0 0 | 0 0 |
| 39 | 8 5 | 8966 9 | 0 0 | 0 0 | 0 0 | 0 0 | 896 7 | 0 0 | 0 0 |
| 40 | 8 4 | 7480 7 | 0 0 | 0 0 | 0 0 | 0 0 | 748 1 | 0 0 | 0 0 |
| 41 | 8 3 | 5949 0 | 0 0 | 0 0 | 0 0 | 0 0 | 594 9 | 0 0 | 0 0 |
| 42 | 3 4 | 2016 2 | 0 0 | 0 0 | 0 0 | 0 0 | 201 6 | 0 0 | 0 0 |
| 43 | 4 7 | 2251 5 | 0 0 | 0 0 | 0 0 | 0 0 | 225 1 | 0 0 | 0 0 |
| 44 | 8 0 | 2085 4 | 0 0 | 0 0 | 0 0 | 0 0 | 208 5 | 0 0 | 0 0 |
| 45 | 3 4 | 207 8 | 0 0 | 0 0 | 0 0 | 0 0 | 20 8 | 0 0 | 0 0 |

Failure Surface Specified By 49 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 81 | 618 62 |
| 3 | 775 43 | 615 89 |
| 4 | 785 11 | 613 38 |
| 5 | 794 84 | 611 09 |
| 6 | 804 62 | 609 02 |
| 7 | 814 45 | 607 17 |
| 8 | 824 32 | 605 55 |
| 9 | 834 22 | 604 15 |
| 10 | 844 15 | 602 97 |
| 11 | 854 11 | 602 02 |
| 12 | 864 08 | 601 30 |
| 13 | 874 07 | 600 80 |
| 14 | 884 06 | 600 53 |
| 15 | 894 06 | 600 48 |
| 16 | 904 06 | 600 66 |
| 17 | 914 05 | 601 07 |
| 18 | 924 03 | 601 70 |
| 19 | 934 00 | 602 56 |
| 20 | 943 94 | 603 65 |
| 21 | 953 85 | 604 96 |
| 22 | 963 73 | 606 49 |
| 23 | 973 58 | 608 25 |
| 24 | 983 38 | 610 23 |
| 25 | 993 13 | 612 43 |
| 26 | 1002 84 | 614 86 |
| 27 | 1012 48 | 617 50 |
| 28 | 1022 06 | 620 36 |
| 29 | 1031 58 | 623 43 |
| 30 | 1041 02 | 626 72 |
| 31 | 1050 39 | 630 23 |
| 32 | 1059 67 | 633 94 |
| 33 | 1068 87 | 637 87 |
| 34 | 1077 98 | 642 00 |
| 35 | 1085 99 | 546 34 |
| 36 | 1095 90 | 650 88 |
| 37 | 1104 70 | 655 62 |
| 38 | 1113 40 | 660 55 |
| 39 | 1121 98 | 665 69 |
| 40 | 1130 44 | 671 02 |
| 41 | 1138 78 | 676 54 |

17/86

| | | |
|----|---------|--------|
| 42 | 1146 99 | 682 24 |
| 43 | 1155 08 | 688 13 |
| 44 | 1163 02 | 694 20 |
| 45 | 1170 83 | 700 45 |
| 46 | 1178 49 | 706 88 |
| 47 | 1186 00 | 713 48 |
| 48 | 1193 37 | 720 24 |
| 49 | 1195 76 | 722 54 |

Circle Center At X = 891 1 Y = 1041 9 and Radius, 441 4
 *** 1 540 ***

Failure Surface Specified By 52 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 07 | 619 66 |
| 3 | 775 91 | 617 91 |
| 4 | 785 79 | 616 33 |
| 5 | 795 69 | 614 91 |
| 6 | 805 61 | 613 65 |
| 7 | 815 55 | 612 55 |
| 8 | 825 50 | 611 62 |
| 9 | 835 47 | 610 85 |
| 10 | 845 45 | 610 24 |
| 11 | 855 44 | 609 79 |
| 12 | 865 44 | 609 51 |
| 13 | 875 44 | 609 39 |
| 14 | 885 44 | 609 44 |
| 15 | 895 44 | 609 65 |
| 16 | 905 43 | 610 02 |
| 17 | 915 42 | 610 55 |
| 18 | 925 39 | 611 25 |
| 19 | 935 36 | 612 11 |
| 20 | 945 30 | 613 13 |
| 21 | 955 23 | 614 32 |
| 22 | 965 14 | 615 67 |
| 23 | 975 03 | 617 18 |
| 24 | 984 89 | 618 85 |
| 25 | 994 72 | 620 68 |
| 26 | 1004 52 | 622 67 |
| 27 | 1014 28 | 624 83 |
| 28 | 1024 01 | 627 14 |
| 29 | 1033 70 | 629 61 |
| 30 | 1043 35 | 632 23 |
| 31 | 1052 95 | 635 02 |
| 32 | 1062 51 | 637 96 |
| 33 | 1072 02 | 641 06 |
| 34 | 1081 48 | 644 31 |
| 35 | 1090 88 | 647 72 |
| 36 | 1100 22 | 651 28 |
| 37 | 1109 51 | 654 99 |
| 38 | 1118 73 | 658 86 |
| 39 | 1127 89 | 662 87 |
| 40 | 1136 98 | 667 03 |
| 41 | 1146 01 | 671 34 |
| 42 | 1154 96 | 675 80 |
| 43 | 1163 83 | 680 40 |
| 44 | 1172 64 | 685 15 |
| 45 | 1181 36 | 690 04 |
| 46 | 1190 00 | 695 08 |
| 47 | 1198 56 | 700 25 |
| 48 | 1207 03 | 705 56 |
| 49 | 1215 41 | 711 01 |
| 50 | 1223 71 | 716 60 |
| 51 | 1231 91 | 722 32 |
| 52 | 1235 25 | 724 74 |

Circle Center At X = 877 7 , Y = 1221 2 and Radius, 611 8
 *** 1 541 ***

Failure Surface Specified By 44 Coordinate Points

18/46

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 59 | 622 95 |
| 3 | 786 54 | 621 89 |
| 4 | 796 50 | 621 01 |
| 5 | 806 47 | 520 30 |
| 6 | 816 46 | 619 76 |
| 7 | 826 45 | 619 39 |
| 8 | 836 45 | 619 20 |
| 9 | 845 45 | 619 17 |
| 10 | 856 45 | 619 31 |
| 11 | 866 44 | 619 63 |
| 12 | 876 43 | 620 12 |
| 13 | 886 41 | 620 77 |
| 14 | 896 38 | 621 60 |
| 15 | 906 33 | 622 60 |
| 16 | 916 26 | 623 77 |
| 17 | 926 17 | 625 11 |
| 18 | 936 05 | 626 61 |
| 19 | 945 91 | 628 29 |
| 20 | 955 74 | 630 13 |
| 21 | 965 54 | 632 15 |
| 22 | 975 30 | 634 33 |
| 23 | 985 02 | 636 67 |
| 24 | 994 70 | 639 19 |
| 25 | 1004 33 | 641 86 |
| 26 | 1013 92 | 644 71 |
| 27 | 1023 46 | 647 71 |
| 28 | 1032 94 | 650 88 |
| 29 | 1042 37 | 654 21 |
| 30 | 1051 74 | 657 70 |
| 31 | 1061 05 | 661 35 |
| 32 | 1070 30 | 665 16 |
| 33 | 1079 47 | 669 13 |
| 34 | 1088 59 | 673 25 |
| 35 | 1097 62 | 677 53 |
| 36 | 1106 59 | 681 96 |
| 37 | 1115 47 | 686 55 |
| 38 | 1124 28 | 691 29 |
| 39 | 1133 01 | 696 17 |
| 40 | 1141 64 | 701 21 |
| 41 | 1150 20 | 706 39 |
| 42 | 1158 66 | 711 72 |
| 43 | 1167 03 | 717 19 |
| 44 | 1173 05 | 721 28 |

Circle Center At X = 843 0 , Y = 1203 5 and Radius, 584 4
 *** 1 545 ***

Failure Surface Specified By 48 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 91 | 624 91 |
| 3 | 796 77 | 623 23 |
| 4 | 806 65 | 621 72 |
| 5 | 816 56 | 620 39 |
| 6 | 826 50 | 619 24 |
| 7 | 836 45 | 618 27 |
| 8 | 846 42 | 617 47 |
| 9 | 856 40 | 616 85 |
| 10 | 866 39 | 616 41 |
| 11 | 876 39 | 616 14 |
| 12 | 886 39 | 616 06 |
| 13 | 896 39 | 616 15 |
| 14 | 906 38 | 616 42 |
| 15 | 916 37 | 616 87 |
| 16 | 926 35 | 617 50 |
| 17 | 936 32 | 618 31 |

19/10

| | | |
|----|---------|--------|
| 18 | 946 27 | 619 29 |
| 19 | 956 20 | 620 45 |
| 20 | 966 11 | 621 79 |
| 21 | 976 00 | 623 31 |
| 22 | 985 85 | 625 00 |
| 23 | 995 68 | 626 86 |
| 24 | 1005 47 | 628 91 |
| 25 | 1016 22 | 631 12 |
| 26 | 1024 93 | 633 51 |
| 27 | 1034 59 | 636 07 |
| 28 | 1044 21 | 638 81 |
| 29 | 1053 78 | 641 71 |
| 30 | 1063 30 | 644 79 |
| 31 | 1072 76 | 648 04 |
| 32 | 1082 16 | 651 45 |
| 33 | 1091 49 | 655 03 |
| 34 | 1100 76 | 658 78 |
| 35 | 1109 97 | 662 69 |
| 36 | 1119 10 | 666 76 |
| 37 | 1128 16 | 671 00 |
| 38 | 1137 14 | 675 40 |
| 39 | 1146 04 | 679 95 |
| 40 | 1154 86 | 684 67 |
| 41 | 1163 59 | 689 54 |
| 42 | 1172 24 | 694 57 |
| 43 | 1180 79 | 699 75 |
| 44 | 1189 25 | 705 08 |
| 45 | 1197 61 | 710 56 |
| 46 | 1205 88 | 716 20 |
| 47 | 1214 04 | 721 97 |
| 48 | 1216 37 | 723 69 |

Circle Center At X = 886 1 , Y = 1176 5 and Radius, 560 4
*** 1 545 ***

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 22 | 621 21 |
| 3 | 785 85 | 618 51 |
| 4 | 795 54 | 616 04 |
| 5 | 805 29 | 613 83 |
| 6 | 815 10 | 611 86 |
| 7 | 824 95 | 610 14 |
| 8 | 834 84 | 608 68 |
| 9 | 844 77 | 607 46 |
| 10 | 854 72 | 606 50 |
| 11 | 864 69 | 605 80 |
| 12 | 874 68 | 605 34 |
| 13 | 884 68 | 605 14 |
| 14 | 894 68 | 605 20 |
| 15 | 904 68 | 605 51 |
| 16 | 914 66 | 606 07 |
| 17 | 924 63 | 606 89 |
| 18 | 934 57 | 607 96 |
| 19 | 944 48 | 609 28 |
| 20 | 954 36 | 610 86 |
| 21 | 964 19 | 612 68 |
| 22 | 973 97 | 614 76 |
| 23 | 983 70 | 617 08 |
| 24 | 993 36 | 619 65 |
| 25 | 1002 96 | 622 46 |
| 26 | 1012 48 | 625 52 |
| 27 | 1021 92 | 628 82 |
| 28 | 1031 27 | 632 35 |
| 29 | 1040 53 | 636 13 |
| 30 | 1049 70 | 640 14 |
| 31 | 1058 75 | 644 38 |
| 32 | 1067 70 | 648 85 |

20/46

| | | |
|----|---------|--------|
| 33 | 1076 53 | 653 54 |
| 34 | 1086 23 | 658 46 |
| 35 | 1093 81 | 663 60 |
| 36 | 1102 25 | 668 95 |
| 37 | 1110 57 | 674 52 |
| 38 | 1118 73 | 680 30 |
| 39 | 1126 74 | 686 28 |
| 40 | 1134 60 | 692 46 |
| 41 | 1142 30 | 698 84 |
| 42 | 1149 83 | 705 42 |
| 43 | 1157 20 | 712 19 |
| 44 | 1164 39 | 719 14 |
| 45 | 1166 12 | 720 90 |

Circle Center At X = 887 5 , Y = 998 3 and Radius, 393 2
 *** 1 546 ***

Failure Surface Specified By 52 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 93 | 619 04 |
| 3 | 775 65 | 616 69 |
| 4 | 785 41 | 614 54 |
| 5 | 795 22 | 612 56 |
| 6 | 805 06 | 610 78 |
| 7 | 814 93 | 609 18 |
| 8 | 824 83 | 607 77 |
| 9 | 834 75 | 606 55 |
| 10 | 844 70 | 605 51 |
| 11 | 854 66 | 604 67 |
| 12 | 864 64 | 604 01 |
| 13 | 874 63 | 603 54 |
| 14 | 884 63 | 603 27 |
| 15 | 894 63 | 603 18 |
| 16 | 904 63 | 603 28 |
| 17 | 914 62 | 603 57 |
| 18 | 924 61 | 604 06 |
| 19 | 934 59 | 604 73 |
| 20 | 944 55 | 605 59 |
| 21 | 954 49 | 606 64 |
| 22 | 964 42 | 607 88 |
| 23 | 974 32 | 609 30 |
| 24 | 984 18 | 610 91 |
| 25 | 994 02 | 612 71 |
| 26 | 1003 82 | 614 70 |
| 27 | 1013 58 | 616 87 |
| 28 | 1023 30 | 619 23 |
| 29 | 1032 97 | 621 77 |
| 30 | 1042 59 | 624 50 |
| 31 | 1052 16 | 627 40 |
| 32 | 1061 67 | 630 49 |
| 33 | 1071 13 | 633 76 |
| 34 | 1080 51 | 637 20 |
| 35 | 1089 83 | 640 83 |
| 36 | 1099 08 | 644 63 |
| 37 | 1108 26 | 648 60 |
| 38 | 1117 36 | 652 75 |
| 39 | 1126 38 | 657 07 |
| 40 | 1135 31 | 661 56 |
| 41 | 1144 16 | 666 22 |
| 42 | 1152 92 | 671 05 |
| 43 | 1161 58 | 676 04 |
| 44 | 1170 15 | 681 19 |
| 45 | 1178 62 | 686 51 |
| 46 | 1186 99 | 691 99 |
| 47 | 1195 25 | 697 62 |
| 48 | 1203 40 | 703 41 |
| 49 | 1211 45 | 709 35 |
| 50 | 1219 37 | 715 45 |

2/26

51 1227 18 721 69
 52 1230 53 724 47
 Circle Center At X = 894 2 , Y = 1130 0 and Radius, 526 9
 *** 1 546 ***

Failure Surface Specified By 51 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 47 | 622 18 |
| 3 | 786 30 | 620 35 |
| 4 | 796 16 | 618 69 |
| 5 | 806 05 | 617 20 |
| 6 | 815 96 | 615 88 |
| 7 | 825 89 | 614 72 |
| 3 | 835 84 | 613 73 |
| 9 | 845 81 | 612 90 |
| 10 | 855 79 | 612 25 |
| 11 | 865 78 | 611 75 |
| 12 | 875 77 | 611 44 |
| 13 | 885 77 | 611 29 |
| 14 | 895 77 | 611 30 |
| 15 | 905 77 | 611 49 |
| 16 | 915 76 | 611 84 |
| 17 | 925 75 | 612 36 |
| 18 | 935 73 | 613 05 |
| 19 | 945 69 | 613 91 |
| 20 | 955 64 | 614 93 |
| 21 | 965 56 | 616 12 |
| 22 | 975 47 | 617 48 |
| 23 | 985 36 | 619 00 |
| 24 | 995 21 | 620 69 |
| 25 | 1005 04 | 622 55 |
| 26 | 1014 83 | 624 57 |
| 27 | 1024 59 | 626 76 |
| 28 | 1034 31 | 629 11 |
| 29 | 1043 99 | 631 62 |
| 30 | 1053 62 | 634 30 |
| 31 | 1063 21 | 637 13 |
| 32 | 1072 75 | 640 13 |
| 33 | 1082 24 | 643 29 |
| 34 | 1091 67 | 646 61 |
| 35 | 1101 05 | 650 08 |
| 36 | 1110 37 | 653 72 |
| 37 | 1119 62 | 657 51 |
| 38 | 1128 81 | 661 45 |
| 39 | 1137 93 | 665 55 |
| 40 | 1146 98 | 669 80 |
| 41 | 1155 96 | 674 20 |
| 42 | 1164 87 | 678 76 |
| 43 | 1173 69 | 683 46 |
| 44 | 1182 44 | 688 31 |
| 45 | 1191 10 | 693 31 |
| 46 | 1199 67 | 698 45 |
| 47 | 1208 16 | 703 73 |
| 48 | 1216 56 | 709 15 |
| 49 | 1224 87 | 714 73 |
| 50 | 1233 08 | 720 44 |
| 51 | 1239 36 | 724 96 |

Circle Center At X = 889 8 , Y = 1205 6 and Radius, 594 3
 *** 1 553 ***

Failure Surface Specified By 42 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 02 | 619 41 |
| 3 | 775 83 | 617 48 |
| 4 | 785 68 | 615 78 |
| 5 | 795 58 | 614 32 |

22/46

| | | |
|----|---------|--------|
| 6 | 805 50 | 613 09 |
| 7 | 815 45 | 612 10 |
| 8 | 825 42 | 611 34 |
| 9 | 835 41 | 610 81 |
| 10 | 845 40 | 610 53 |
| 11 | 855 40 | 610 47 |
| 12 | 865 40 | 610 65 |
| 13 | 875 39 | 611 07 |
| 14 | 885 37 | 611 72 |
| 15 | 895 33 | 612 61 |
| 16 | 905 27 | 613 73 |
| 17 | 915 18 | 615 09 |
| 18 | 925 05 | 616 68 |
| 19 | 934 88 | 618 50 |
| 20 | 944 67 | 620 55 |
| 21 | 954 41 | 622 84 |
| 22 | 964 08 | 625 35 |
| 23 | 973 70 | 628 09 |
| 24 | 983 25 | 631 05 |
| 25 | 992 73 | 634 24 |
| 26 | 1002 13 | 637 65 |
| 27 | 1011 45 | 641 28 |
| 28 | 1020 68 | 645 13 |
| 29 | 1029 81 | 649 20 |
| 30 | 1038 85 | 653 48 |
| 31 | 1047 78 | 657 97 |
| 32 | 1056 61 | 662 68 |
| 33 | 1065 32 | 667 58 |
| 34 | 1073 92 | 672 70 |
| 35 | 1082 39 | 678 01 |
| 36 | 1090 73 | 683 52 |
| 37 | 1098 94 | 689 23 |
| 38 | 1107 02 | 695 13 |
| 39 | 1114 95 | 701 21 |
| 40 | 1122 74 | 707 49 |
| 41 | 1130 38 | 713 94 |
| 42 | 1132 19 | 715 55 |

Circle Center At X = 852 7 , Y = 1034 7 and Radius, 424 3
 *** 1 553 ***

Failure Surface Specified By 49 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 91 | 624 89 |
| 3 | 796 76 | 623 18 |
| 4 | 806 64 | 621 64 |
| 5 | 816 54 | 620 26 |
| 6 | 826 47 | 619 06 |
| 7 | 836 42 | 618 03 |
| 8 | 846 38 | 617 17 |
| 9 | 856 36 | 616 49 |
| 10 | 866 34 | 615 97 |
| 11 | 876 34 | 615 63 |
| 12 | 886 34 | 615 45 |
| 13 | 896 34 | 615 45 |
| 14 | 906 34 | 615 63 |
| 15 | 916 33 | 615 97 |
| 16 | 926 32 | 616 49 |
| 17 | 936 29 | 617 17 |
| 18 | 946 26 | 618 03 |
| 19 | 956 20 | 619 06 |
| 20 | 966 13 | 620 26 |
| 21 | 976 04 | 621 64 |
| 22 | 985 92 | 623 18 |
| 23 | 995 77 | 624 89 |
| 24 | 1005 59 | 626 77 |
| 25 | 1015 38 | 628 82 |
| 26 | 1025 13 | 631 04 |


23/46

| | | |
|----|---------|--------|
| 27 | 1034 84 | 633 42 |
| 28 | 1044 51 | 635 97 |
| 29 | 1054 13 | 638 69 |
| 30 | 1063 71 | 641 58 |
| 31 | 1073 23 | 644 62 |
| 32 | 1082 70 | 647 83 |
| 33 | 1092 12 | 651 21 |
| 34 | 1101 47 | 654 74 |
| 35 | 1110 76 | 658 44 |
| 36 | 1119 99 | 662 29 |
| 37 | 1129 15 | 666 30 |
| 38 | 1138 24 | 670 47 |
| 39 | 1147 26 | 674 80 |
| 40 | 1156 20 | 679 28 |
| 41 | 1165 06 | 683 91 |
| 42 | 1173 84 | 688 69 |
| 43 | 1182 54 | 693 63 |
| 44 | 1191 15 | 698 71 |
| 45 | 1199 67 | 703 94 |
| 46 | 1208 10 | 709 32 |
| 47 | 1216 44 | 714 84 |
| 48 | 1224 68 | 720 51 |
| 49 | 1230 22 | 724 46 |

Circle Center At X = 891 3 , Y = 1196 7 and Radius, 581 3
*** 1 554 ***

Intermountain Regional Landfill Fill Slope 1

c:\program files\stedwin\irf\13 pl2 Run By Greg Shafer HDR 4/20/2010 03:44PM



| # | FS | Soil Desc | Soil Type | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Piez Surface | Load Horz Eqk | Value |
|---|------|-----------|-----------|---------------------|-------------------------|--------------------------|----------------------|--------------|---------------|----------|
| a | 1.17 | | | | | | | | | 0.200 g< |
| b | 1.17 | | | | | | | | | |
| c | 1.19 | UVSC | 1 | 113.5 | 121.0 | 3000.0 | 0.0 | W1 | | |
| d | 1.19 | LSC | 2 | 121.0 | 125.5 | 1500.0 | 0.0 | W1 | | |
| e | 1.19 | SC | 3 | 121.0 | 125.5 | 2000.0 | 0.0 | W1 | | |
| f | 1.19 | LVSC | 4 | 121.0 | 125.5 | 3000.0 | 0.0 | W1 | | |
| g | 1.19 | Waste | 5 | 50.0 | 60.0 | 150.0 | 22.0 | W1 | | |
| h | 1.19 | | | | | | | | | |
| i | 1.20 | | | | | | | | | |
| j | 1.20 | | | | | | | | | |

PCSTABL7 FSmin=1.17

Safety Factors Are Calculated By The Modified Bishop Method

STED



Handwritten signature/initials

25/46

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu, Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 44PM
Run By Greg Shafer, HDR
Input Data Filename C 13 in
Output Filename C 13 OUT
Unit ENGLISH
Plotted Output Filename C 13 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient Of 0 200 Has Been Assigned
A Vertical Earthquake Loading Coefficient Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method, Using A Random Technique For Generating Circular Surfaces, Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced Along The Ground Surface Between X = 600 00 ft and X = 850 00 ft
Each Surface Terminates Between X =1100 00 ft and X =1300 00 ft
Unless Further Limitations Were Imposed, The Minimum Elevation At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial Failure Surfaces Examined They Are Ordered - Most Critical First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 98 | 619 23 |
| 3 | 775 75 | 617 12 |
| 4 | 785 57 | 615 23 |
| 5 | 795 43 | 613 55 |

26/26

| | | | | |
|----|------|----|-----|----|
| 6 | 805 | 32 | 612 | 10 |
| 7 | 815 | 24 | 610 | 86 |
| 8 | 825 | 19 | 609 | 85 |
| 9 | 835 | 16 | 609 | 06 |
| 10 | 845 | 15 | 608 | 49 |
| 11 | 855 | 14 | 608 | 15 |
| 12 | 865 | 14 | 608 | 03 |
| 13 | 875 | 14 | 608 | 13 |
| 14 | 885 | 13 | 608 | 45 |
| 15 | 895 | 12 | 609 | 00 |
| 16 | 905 | 09 | 609 | 77 |
| 17 | 915 | 04 | 610 | 76 |
| 18 | 924 | 97 | 611 | 97 |
| 19 | 934 | 86 | 613 | 41 |
| 20 | 944 | 73 | 615 | 06 |
| 21 | 954 | 55 | 616 | 93 |
| 22 | 964 | 33 | 619 | 03 |
| 23 | 974 | 06 | 621 | 34 |
| 24 | 983 | 73 | 623 | 86 |
| 25 | 993 | 35 | 626 | 60 |
| 26 | 1002 | 90 | 629 | 56 |
| 27 | 1012 | 39 | 632 | 72 |
| 28 | 1021 | 80 | 636 | 10 |
| 29 | 1031 | 13 | 639 | 69 |
| 30 | 1040 | 39 | 643 | 48 |
| 31 | 1049 | 55 | 647 | 48 |
| 32 | 1058 | 63 | 651 | 69 |
| 33 | 1067 | 60 | 656 | 09 |
| 34 | 1076 | 48 | 660 | 69 |
| 35 | 1085 | 25 | 665 | 49 |
| 36 | 1093 | 92 | 670 | 49 |
| 37 | 1102 | 47 | 675 | 67 |
| 38 | 1110 | 90 | 681 | 05 |
| 39 | 1119 | 21 | 686 | 61 |
| 40 | 1127 | 40 | 692 | 36 |
| 41 | 1135 | 45 | 698 | 28 |
| 42 | 1143 | 37 | 704 | 39 |
| 43 | 1151 | 15 | 710 | 67 |
| 44 | 1158 | 79 | 717 | 12 |
| 45 | 1162 | 86 | 720 | 71 |

Circle Center At X = 865 6 , Y = 1056 5 and Radius, 448 5
 *** 1 168 ***

Individual data on the 45 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force Surchage Load | | |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|--------------------------------|-----------|-------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | (lbs) |
| 1 | 9 7 | 1157 5 | 0 0 | 0 0 | 0 0 | 0 0 | 231 5 | 0 0 | 0 0 |
| 2 | 9 8 | 3440 2 | 0 0 | 0 0 | 0 0 | 0 0 | 688 0 | 0 0 | 0 0 |
| 3 | 9 8 | 5641 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1128 4 | 0 0 | 0 0 |
| 4 | 9 9 | 7756 8 | 0 0 | 0 0 | 0 0 | 0 0 | 1551 4 | 0 0 | 0 0 |
| 5 | 9 9 | 9779 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1955 9 | 0 0 | 0 0 |
| 6 | 9 9 | 11705 3 | 0 0 | 0 0 | 0 0 | 0 0 | 2341 1 | 0 0 | 0 0 |
| 7 | 9 9 | 13529 0 | 0 0 | 0 0 | 0 0 | 0 0 | 2705 8 | 0 0 | 0 0 |
| 8 | 10 0 | 15246 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3049 3 | 0 0 | 0 0 |
| 9 | 10 0 | 16853 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3370 7 | 0 0 | 0 0 |
| 10 | 10 0 | 18346 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3669 3 | 0 0 | 0 0 |
| 11 | 10 0 | 19722 1 | 0 0 | 0 0 | 0 0 | 0 0 | 3944 4 | 0 0 | 0 0 |
| 12 | 10 0 | 20977 6 | 0 0 | 0 0 | 0 0 | 0 0 | 4195 5 | 0 0 | 0 0 |
| 13 | 10 0 | 22110 4 | 0 0 | 0 0 | 0 0 | 0 0 | 4422 1 | 0 0 | 0 0 |
| 14 | 10 0 | 23118 5 | 0 0 | 0 0 | 0 0 | 0 0 | 4623 7 | 0 0 | 0 0 |
| 15 | 10 0 | 24000 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4800 0 | 0 0 | 0 0 |
| 16 | 10 0 | 24753 8 | 0 0 | 0 0 | 0 0 | 0 0 | 4950 8 | 0 0 | 0 0 |
| 17 | 9 9 | 25378 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5075 7 | 0 0 | 0 0 |
| 18 | 9 9 | 25874 6 | 0 0 | 0 0 | 0 0 | 0 0 | 5174 9 | 0 0 | 0 0 |
| 19 | 9 9 | 26241 2 | 0 0 | 0 0 | 0 0 | 0 0 | 5248 2 | 0 0 | 0 0 |
| 20 | 9 8 | 26478 6 | 0 0 | 0 0 | 0 0 | 0 0 | 5295 7 | 0 0 | 0 0 |
| 21 | 9 8 | 26588 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5317 6 | 0 0 | 0 0 |

27/1/16

| | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|--------|-----|-----|
| 22 | 9 7 | 26570 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5314 0 | 0 0 | 0 0 |
| 23 | 9 7 | 26426 8 | 0 0 | 0 0 | 0 0 | 0 0 | 5285 4 | 0 0 | 0 0 |
| 24 | 9 6 | 26159 7 | 0 0 | 0 0 | 0 0 | 0 0 | 5231 9 | 0 0 | 0 0 |
| 25 | 9 6 | 25771 1 | 0 0 | 0 0 | 0 0 | 0 0 | 5154 2 | 0 0 | 0 0 |
| 26 | 9 5 | 25264 0 | 0 0 | 0 0 | 0 0 | 0 0 | 5052 8 | 0 0 | 0 0 |
| 27 | 9 4 | 24641 3 | 0 0 | 0 0 | 0 0 | 0 0 | 4928 3 | 0 0 | 0 0 |
| 28 | 9 3 | 23906 6 | 0 0 | 0 0 | 0 0 | 0 0 | 4781 3 | 0 0 | 0 0 |
| 29 | 9 3 | 23063 3 | 0 0 | 0 0 | 0 0 | 0 0 | 4612 7 | 0 0 | 0 0 |
| 30 | 9 2 | 22116 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4423 2 | 0 0 | 0 0 |
| 31 | 9 1 | 21069 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4213 8 | 0 0 | 0 0 |
| 32 | 9 0 | 19927 5 | 0 0 | 0 0 | 0 0 | 0 0 | 3985 5 | 0 0 | 0 0 |
| 33 | 8 9 | 18696 5 | 0 0 | 0 0 | 0 0 | 0 0 | 3739 3 | 0 0 | 0 0 |
| 34 | 8 8 | 17381 3 | 0 0 | 0 0 | 0 0 | 0 0 | 3476 3 | 0 0 | 0 0 |
| 35 | 8 7 | 15987 7 | 0 0 | 0 0 | 0 0 | 0 0 | 3197 5 | 0 0 | 0 0 |
| 35 | 8 6 | 14522 2 | 0 0 | 0 0 | 0 0 | 0 0 | 2904 4 | 0 0 | 0 0 |
| 37 | 8 4 | 12990 7 | 0 0 | 0 0 | 0 0 | 0 0 | 2598 1 | 0 0 | 0 0 |
| 38 | 8 3 | 11400 1 | 0 0 | 0 0 | 0 0 | 0 0 | 2280 0 | 0 0 | 0 0 |
| 39 | 8 2 | 9757 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1951 4 | 0 0 | 0 0 |
| 40 | 8 1 | 8069 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1613 8 | 0 0 | 0 0 |
| 41 | 7 9 | 6343 0 | 0 0 | 0 0 | 0 0 | 0 0 | 1268 6 | 0 0 | 0 0 |
| 42 | 6 6 | 4014 0 | 0 0 | 0 0 | 0 0 | 0 0 | 802 8 | 0 0 | 0 0 |
| 43 | 1 2 | 566 2 | 0 0 | 0 0 | 0 0 | 0 0 | 113 2 | 0 0 | 0 0 |
| 44 | 7 6 | 2438 1 | 0 0 | 0 0 | 0 0 | 0 0 | 487 6 | 0 0 | 0 0 |
| 45 | 4 1 | 342 7 | 0 0 | 0 0 | 0 0 | 0 0 | 68 5 | 0 0 | 0 0 |

Failure Surface Specified By 47 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 84 | 624 58 |
| 3 | 796 64 | 622 59 |
| 4 | 806 48 | 620 79 |
| 5 | 816 35 | 619 19 |
| 6 | 826 25 | 617 79 |
| 7 | 836 18 | 616 59 |
| 8 | 846 13 | 615 58 |
| 9 | 856 10 | 614 78 |
| 10 | 866 08 | 614 17 |
| 11 | 876 07 | 613 76 |
| 12 | 886 07 | 613 55 |
| 13 | 896 07 | 613 55 |
| 14 | 906 06 | 613 74 |
| 15 | 916 06 | 614 13 |
| 16 | 926 04 | 614 72 |
| 17 | 936 01 | 615 51 |
| 18 | 945 96 | 616 50 |
| 19 | 955 89 | 617 69 |
| 20 | 965 79 | 619 07 |
| 21 | 975 67 | 620 66 |
| 22 | 985 51 | 622 44 |
| 23 | 995 31 | 624 41 |
| 24 | 1005 07 | 626 58 |
| 25 | 1014 79 | 628 95 |
| 26 | 1024 45 | 631 51 |
| 27 | 1034 07 | 634 26 |
| 28 | 1043 62 | 637 21 |
| 29 | 1053 12 | 640 34 |
| 30 | 1062 55 | 643 67 |
| 31 | 1071 91 | 647 18 |
| 32 | 1081 20 | 650 88 |
| 33 | 1090 42 | 654 76 |
| 34 | 1099 56 | 658 83 |
| 35 | 1108 61 | 663 07 |
| 36 | 1117 57 | 667 50 |
| 37 | 1126 45 | 672 11 |
| 38 | 1135 23 | 676 89 |
| 39 | 1143 92 | 681 85 |
| 40 | 1152 50 | 686 98 |
| 41 | 1160 98 | 692 28 |

28/46

| | | |
|----|---------|--------|
| 42 | 1169 35 | 697 75 |
| 43 | 1177 62 | 703 38 |
| 44 | 1185 75 | 709 18 |
| 45 | 1193 79 | 715 14 |
| 46 | 1201 70 | 721 26 |
| 47 | 1203 85 | 722 99 |

Circle Center At X = 891 5 , Y = 1114 1 and Radius, 500 5
 *** 1 170 ***

Failure Surface Specified By 52 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 79 | 624 37 |
| 3 | 796 54 | 622 15 |
| 4 | 806 33 | 620 10 |
| 5 | 816 15 | 618 23 |
| 6 | 826 01 | 616 53 |
| 7 | 835 89 | 615 01 |
| 8 | 845 80 | 613 68 |
| 9 | 855 73 | 612 52 |
| 10 | 865 69 | 611 54 |
| 11 | 875 65 | 610 74 |
| 12 | 885 64 | 610 12 |
| 13 | 895 63 | 609 67 |
| 14 | 905 62 | 609 41 |
| 15 | 915 62 | 609 33 |
| 16 | 925 62 | 609 43 |
| 17 | 935 62 | 609 71 |
| 18 | 945 61 | 610 17 |
| 19 | 955 59 | 610 81 |
| 20 | 965 55 | 611 63 |
| 21 | 975 50 | 612 63 |
| 22 | 985 43 | 613 81 |
| 23 | 995 34 | 615 17 |
| 24 | 1005 22 | 616 70 |
| 25 | 1015 07 | 618 41 |
| 26 | 1024 89 | 620 30 |
| 27 | 1034 68 | 622 37 |
| 28 | 1044 42 | 624 61 |
| 29 | 1054 13 | 627 03 |
| 30 | 1063 78 | 629 62 |
| 31 | 1073 39 | 632 39 |
| 32 | 1082 95 | 635 33 |
| 33 | 1092 46 | 638 44 |
| 34 | 1101 90 | 641 72 |
| 35 | 1111 29 | 645 17 |
| 36 | 1120 61 | 648 79 |
| 37 | 1129 86 | 652 58 |
| 38 | 1139 05 | 656 54 |
| 39 | 1148 16 | 660 65 |
| 40 | 1157 20 | 664 94 |
| 41 | 1166 16 | 669 38 |
| 42 | 1175 03 | 673 99 |
| 43 | 1183 83 | 678 75 |
| 44 | 1192 53 | 683 67 |
| 45 | 1201 15 | 688 75 |
| 46 | 1209 67 | 693 98 |
| 47 | 1218 09 | 699 37 |
| 48 | 1226 42 | 704 90 |
| 49 | 1234 65 | 710 59 |
| 50 | 1242 77 | 716 42 |
| 51 | 1250 79 | 722 40 |
| 52 | 1255 24 | 725 85 |

Circle Center At X = 915 1 , Y = 1164 1 and Radius, 554 8
 *** 1 189 ***

Failure Surface Specified By 57 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
|----------|-------------|-------------|

29/46

| | | |
|----|---------|--------|
| 1 | 756 25 | 621 56 |
| 2 | 766 18 | 620 42 |
| 3 | 776 13 | 619 38 |
| 4 | 786 09 | 618 45 |
| 5 | 796 06 | 617 65 |
| 6 | 806 03 | 616 96 |
| 7 | 816 01 | 616 38 |
| 8 | 826 00 | 615 91 |
| 9 | 836 00 | 615 55 |
| 10 | 845 99 | 615 31 |
| 11 | 855 99 | 615 19 |
| 12 | 865 99 | 615 18 |
| 13 | 875 99 | 615 28 |
| 14 | 885 99 | 615 49 |
| 15 | 895 99 | 615 82 |
| 16 | 905 98 | 616 26 |
| 17 | 915 96 | 616 82 |
| 18 | 925 94 | 617 49 |
| 19 | 935 91 | 618 27 |
| 20 | 945 87 | 619 16 |
| 21 | 955 82 | 620 17 |
| 22 | 965 75 | 621 29 |
| 23 | 975 68 | 622 53 |
| 24 | 985 59 | 623 88 |
| 25 | 995 48 | 625 34 |
| 26 | 1005 35 | 626 91 |
| 27 | 1015 21 | 628 59 |
| 28 | 1025 05 | 630 39 |
| 29 | 1034 86 | 632 30 |
| 30 | 1044 66 | 634 32 |
| 31 | 1054 43 | 636 45 |
| 32 | 1064 17 | 638 69 |
| 33 | 1073 89 | 641 04 |
| 34 | 1083 58 | 643 51 |
| 35 | 1093 25 | 646 08 |
| 36 | 1102 88 | 648 76 |
| 37 | 1112 48 | 651 56 |
| 38 | 1122 05 | 654 46 |
| 39 | 1131 59 | 657 47 |
| 40 | 1141 09 | 660 59 |
| 41 | 1150 56 | 663 81 |
| 42 | 1159 99 | 667 14 |
| 43 | 1169 37 | 670 58 |
| 44 | 1178 72 | 674 13 |
| 45 | 1188 03 | 677 78 |
| 46 | 1197 30 | 681 54 |
| 47 | 1206 52 | 685 41 |
| 48 | 1215 70 | 689 38 |
| 49 | 1224 84 | 693 45 |
| 50 | 1233 92 | 697 62 |
| 51 | 1242 96 | 701 90 |
| 52 | 1251 95 | 706 28 |
| 53 | 1260 89 | 710 77 |
| 54 | 1269 77 | 715 35 |
| 55 | 1278 61 | 720 04 |
| 56 | 1287 39 | 724 82 |
| 57 | 1292 96 | 727 94 |

Circle Center At X = 862 1 Y = 1494 6 and Radius 879 5
*** 1 191 ***

Failure Surface Specified By 46 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 83 | 630 69 |
| 3 | 817 77 | 629 55 |
| 4 | 827 72 | 628 57 |
| 5 | 837 69 | 627 74 |
| 6 | 847 66 | 627 08 |

30/10

| | | |
|----|---------|--------|
| 7 | 857 65 | 626 57 |
| 8 | 867 65 | 625 22 |
| 9 | 877 64 | 626 03 |
| 10 | 887 64 | 626 00 |
| 11 | 897 64 | 626 12 |
| 12 | 907 64 | 626 41 |
| 13 | 917 63 | 626 85 |
| 14 | 927 51 | 627 44 |
| 15 | 937 58 | 628 20 |
| 16 | 947 54 | 629 11 |
| 17 | 957 48 | 630 19 |
| 18 | 967 41 | 631 41 |
| 19 | 977 31 | 632 80 |
| 20 | 987 19 | 634 34 |
| 21 | 997 05 | 636 04 |
| 22 | 1006 87 | 637 89 |
| 23 | 1016 67 | 639 90 |
| 24 | 1026 43 | 642 06 |
| 25 | 1036 16 | 644 38 |
| 26 | 1045 85 | 646 84 |
| 27 | 1055 50 | 649 47 |
| 28 | 1065 11 | 652 24 |
| 29 | 1074 67 | 655 17 |
| 30 | 1084 19 | 658 25 |
| 31 | 1093 65 | 661 47 |
| 32 | 1103 06 | 664 85 |
| 33 | 1112 42 | 668 37 |
| 34 | 1121 72 | 672 05 |
| 35 | 1130 97 | 675 86 |
| 36 | 1140 15 | 679 83 |
| 37 | 1149 26 | 683 94 |
| 38 | 1158 31 | 688 19 |
| 39 | 1167 30 | 692 58 |
| 40 | 1176 21 | 697 12 |
| 41 | 1185 05 | 701 80 |
| 42 | 1193 81 | 706 61 |
| 43 | 1202 50 | 711 57 |
| 44 | 1211 11 | 716 66 |
| 45 | 1219 63 | 721 88 |
| 46 | 1223 06 | 724 06 |

Circle Center At X = 884 8 Y = 1258 5 and Radius, 632 5

*** 1 191 ***

Failure Surface Specified By 43 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 24 | 621 28 |
| 3 | 785 89 | 618 64 |
| 4 | 795 60 | 616 27 |
| 5 | 805 38 | 614 15 |
| 6 | 815 20 | 612 30 |
| 7 | 825 08 | 610 71 |
| 8 | 834 99 | 609 39 |
| 9 | 844 93 | 608 33 |
| 10 | 854 90 | 607 53 |
| 11 | 864 89 | 607 00 |
| 12 | 874 88 | 606 74 |
| 13 | 884 88 | 606 75 |
| 14 | 894 88 | 607 03 |
| 15 | 904 86 | 607 57 |
| 16 | 914 83 | 608 37 |
| 17 | 924 77 | 609 45 |
| 18 | 934 68 | 610 79 |
| 19 | 944 55 | 612 39 |
| 20 | 954 38 | 614 26 |
| 21 | 964 15 | 616 38 |
| 22 | 973 86 | 618 77 |
| 23 | 983 50 | 621 42 |

31/260

| | | |
|----|---------|--------|
| 24 | 993 07 | 624 32 |
| 25 | 1002 56 | 627 48 |
| 26 | 1011 96 | 630 89 |
| 27 | 1021 27 | 634 55 |
| 28 | 1030 47 | 638 46 |
| 29 | 1039 57 | 642 61 |
| 30 | 1048 55 | 647 01 |
| 31 | 1057 41 | 651 64 |
| 32 | 1066 15 | 656 51 |
| 33 | 1074 75 | 661 60 |
| 34 | 1083 21 | 666 93 |
| 35 | 1091 53 | 672 48 |
| 36 | 1099 70 | 678 25 |
| 37 | 1107 71 | 684 24 |
| 38 | 1115 55 | 690 44 |
| 39 | 1123 23 | 696 85 |
| 40 | 1130 74 | 703 46 |
| 41 | 1138 06 | 710 27 |
| 42 | 1145 20 | 717 27 |
| 43 | 1147 16 | 719 29 |

Circle Center At X = 879 6 Y = 981 0 and Radius 374 3
*** 1 192 ***

Failure Surface Specified By 41 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 787 50 | 629 38 |
| 2 | 797 31 | 627 45 |
| 3 | 807 17 | 625 76 |
| 4 | 817 06 | 624 29 |
| 5 | 826 98 | 623 04 |
| 6 | 836 93 | 622 02 |
| 7 | 846 90 | 621 23 |
| 8 | 856 88 | 620 67 |
| 9 | 866 88 | 620 34 |
| 10 | 876 88 | 620 23 |
| 11 | 886 88 | 620 36 |
| 12 | 896 87 | 620 71 |
| 13 | 906 85 | 621 29 |
| 14 | 916 82 | 622 10 |
| 15 | 926 77 | 623 14 |
| 16 | 936 69 | 624 40 |
| 17 | 946 58 | 625 89 |
| 18 | 956 43 | 627 61 |
| 19 | 966 24 | 629 55 |
| 20 | 976 00 | 631 71 |
| 21 | 985 71 | 634 10 |
| 22 | 995 37 | 636 70 |
| 23 | 1004 96 | 639 53 |
| 24 | 1014 48 | 642 58 |
| 25 | 1023 93 | 645 84 |
| 26 | 1033 31 | 649 32 |
| 27 | 1042 60 | 653 01 |
| 28 | 1051 81 | 656 91 |
| 29 | 1060 93 | 661 03 |
| 30 | 1069 94 | 665 35 |
| 31 | 1078 86 | 669 87 |
| 32 | 1087 67 | 674 60 |
| 33 | 1096 38 | 679 53 |
| 34 | 1104 96 | 684 65 |
| 35 | 1113 43 | 689 97 |
| 36 | 1121 77 | 695 49 |
| 37 | 1129 99 | 701 19 |
| 38 | 1138 07 | 707 08 |
| 39 | 1146 02 | 713 15 |
| 40 | 1153 82 | 719 40 |
| 41 | 1154 86 | 720 27 |

Circle Center At X = 876 5 Y = 1057 7 and Radius 437 5
*** 1 193 ***

32/A6

Failure Surface Specified By 54 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 62 | 623 23 |
| 3 | 786 59 | 622 40 |
| 4 | 796 56 | 621 69 |
| 5 | 806 55 | 621 09 |
| 6 | 816 53 | 620 61 |
| 7 | 826 53 | 620 24 |
| 8 | 836 52 | 619 99 |
| 9 | 846 52 | 619 85 |
| 10 | 856 52 | 619 83 |
| 11 | 866 52 | 619 92 |
| 12 | 876 52 | 620 13 |
| 13 | 886 52 | 620 45 |
| 14 | 896 51 | 620 89 |
| 15 | 906 49 | 621 44 |
| 16 | 916 47 | 622 11 |
| 17 | 926 44 | 622 89 |
| 18 | 936 40 | 623 78 |
| 19 | 946 35 | 624 79 |
| 20 | 956 28 | 625 91 |
| 21 | 966 21 | 627 15 |
| 22 | 976 12 | 628 50 |
| 23 | 986 01 | 629 97 |
| 24 | 995 88 | 631 55 |
| 25 | 1005 74 | 633 24 |
| 26 | 1015 57 | 635 04 |
| 27 | 1025 39 | 636 96 |
| 28 | 1035 18 | 638 99 |
| 29 | 1044 95 | 641 13 |
| 30 | 1054 69 | 643 39 |
| 31 | 1064 41 | 645 75 |
| 32 | 1074 09 | 648 23 |
| 33 | 1083 75 | 650 82 |
| 34 | 1093 38 | 653 52 |
| 35 | 1102 98 | 656 33 |
| 36 | 1112 54 | 659 25 |
| 37 | 1122 07 | 662 28 |
| 38 | 1131 57 | 665 41 |
| 39 | 1141 03 | 668 66 |
| 40 | 1150 45 | 672 02 |
| 41 | 1159 83 | 675 48 |
| 42 | 1169 17 | 679 05 |
| 43 | 1178 47 | 682 73 |
| 44 | 1187 72 | 686 52 |
| 45 | 1196 94 | 690 41 |
| 46 | 1206 10 | 694 40 |
| 47 | 1215 22 | 698 50 |
| 48 | 1224 30 | 702 71 |
| 49 | 1233 32 | 707 02 |
| 50 | 1242 29 | 711 43 |
| 51 | 1251 21 | 715 95 |
| 52 | 1260 08 | 720 57 |
| 53 | 1268 90 | 725 29 |
| 54 | 1271 57 | 726 75 |

Circle Center At X = 853 5 , Y = 1490 5 and Radius 870 7
*** 1 193 ***

Failure Surface Specified By 58 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 20 | 620 53 |
| 3 | 776 15 | 619 61 |
| 4 | 786 12 | 618 79 |
| 5 | 796 10 | 618 08 |
| 6 | 806 08 | 617 48 |

33/46

| | | |
|----|---------|--------|
| 7 | 816 07 | 616 99 |
| 8 | 826 06 | 616 60 |
| 9 | 836 05 | 616 32 |
| 10 | 846 05 | 616 15 |
| 11 | 856 05 | 616 09 |
| 12 | 866 05 | 616 14 |
| 13 | 876 05 | 616 30 |
| 14 | 886 05 | 616 56 |
| 15 | 896 04 | 616 93 |
| 16 | 906 03 | 617 41 |
| 17 | 916 01 | 618 00 |
| 18 | 925 99 | 618 69 |
| 19 | 935 96 | 619 49 |
| 20 | 945 91 | 620 40 |
| 21 | 955 86 | 621 42 |
| 22 | 965 80 | 622 55 |
| 23 | 975 72 | 623 78 |
| 24 | 985 63 | 625 12 |
| 25 | 995 53 | 526 57 |
| 26 | 1005 41 | 628 12 |
| 27 | 1015 27 | 629 78 |
| 28 | 1025 11 | 631 55 |
| 29 | 1034 93 | 633 42 |
| 30 | 1044 74 | 635 40 |
| 31 | 1054 52 | 637 48 |
| 32 | 1064 27 | 639 67 |
| 33 | 1074 01 | 641 97 |
| 34 | 1083 71 | 644 37 |
| 35 | 1093 39 | 646 88 |
| 36 | 1103 05 | 649 49 |
| 37 | 1112 67 | 652 20 |
| 38 | 1122 27 | 655 02 |
| 39 | 1131 83 | 657 94 |
| 40 | 1141 36 | 660 97 |
| 41 | 1150 86 | 664 09 |
| 42 | 1160 32 | 667 32 |
| 43 | 1169 75 | 670 66 |
| 44 | 1179 14 | 674 09 |
| 45 | 1188 50 | 677 63 |
| 46 | 1197 81 | 681 26 |
| 47 | 1207 09 | 685 00 |
| 48 | 1216 32 | 688 84 |
| 49 | 1225 52 | 692 77 |
| 50 | 1234 67 | 696 81 |
| 51 | 1243 77 | 700 94 |
| 52 | 1252 83 | 705 17 |
| 53 | 1261 85 | 709 50 |
| 54 | 1270 81 | 713 93 |
| 55 | 1279 73 | 718 45 |
| 56 | 1288 60 | 723 07 |
| 57 | 1297 42 | 727 79 |
| 58 | 1298 23 | 728 23 |

Circle Center At X = 856 7 Y = 1541 3 and Radius 925 2
 *** 1 196 ***

Failure Surface Specified By 51 Coordinate Points


| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 61 | 623 73 |
| 3 | 796 20 | 620 90 |
| 4 | 805 85 | 618 28 |
| 5 | 815 55 | 615 86 |
| 6 | 825 31 | 613 65 |
| 7 | 835 10 | 611 64 |
| 8 | 844 94 | 609 85 |
| 9 | 854 82 | 608 27 |
| 10 | 864 72 | 606 90 |
| 11 | 874 66 | 605 74 |

| | | |
|----|---------|--------|
| 12 | 884 61 | 604 80 |
| 13 | 894 58 | 604 07 |
| 14 | 904 57 | 603 55 |
| 15 | 914 57 | 603 25 |
| 16 | 924 57 | 603 16 |
| 17 | 934 56 | 603 28 |
| 18 | 944 56 | 603 62 |
| 19 | 954 54 | 604 17 |
| 20 | 964 51 | 604 94 |
| 21 | 974 47 | 605 91 |
| 22 | 984 40 | 607 11 |
| 23 | 994 30 | 608 51 |
| 24 | 1004 17 | 610 12 |
| 25 | 1014 00 | 611 95 |
| 26 | 1023 79 | 613 98 |
| 27 | 1033 53 | 616 23 |
| 28 | 1043 23 | 618 68 |
| 29 | 1052 87 | 621 34 |
| 30 | 1062 45 | 624 20 |
| 31 | 1071 97 | 627 27 |
| 32 | 1081 42 | 630 54 |
| 33 | 1090 79 | 634 02 |
| 34 | 1100 09 | 637 69 |
| 35 | 1109 31 | 641 56 |
| 36 | 1118 45 | 645 63 |
| 37 | 1127 50 | 649 89 |
| 38 | 1136 45 | 654 35 |
| 39 | 1145 30 | 658 99 |
| 40 | 1154 06 | 663 83 |
| 41 | 1162 71 | 668 84 |
| 42 | 1171 25 | 674 05 |
| 43 | 1179 67 | 679 43 |
| 44 | 1187 98 | 685 00 |
| 45 | 1196 17 | 690 74 |
| 46 | 1204 23 | 696 65 |
| 47 | 1212 17 | 702 74 |
| 48 | 1219 97 | 708 99 |
| 49 | 1227 64 | 715 41 |
| 50 | 1235 17 | 721 99 |
| 51 | 1238 36 | 724 91 |

Circle Center At X = 923 8 Y = 1070 6 and Radius 467 4
 *** 1 197 ***

Intermountain Regional Landfill Fill Slope 1

c:\program files\stedwin\rl\14 pl2 Run By Greg Shafer HDR 4/20/2010 03 48PM



STED



PCSTABL7 FSmin=0.94
Safety Factors Are Calculated By The Modified Bishop Method

35/A10

36/40

** PCSTABL7 **
by
Purdue University
--Slope Stability Analysis--
Simplified Janbu Simplified Bishop
or Spencer s Method of Slices

Run Date 4/20/2010
Time of Run 03 48PM
Run By Greg Shafer HDR
Input Data Filename C 14 in
Output Filename C 14 OUT
Unit ENGLISH
Plotted Output Filename C 14 PLT
PROBLEM DESCRIPTION Intermountain Regional Landfill
Fill Slope 1

BOUNDARY COORDINATES

Note User origin value specified
Add 0 00 to X-values and 0 00 to Y-values listed

3 Top Boundaries
8 Total Boundaries

| Boundary No | X-Left (ft) | Y-Left (ft) | X-Right (ft) | Y-Right (ft) | Soil Type Below Bnd |
|-------------|-------------|-------------|--------------|--------------|---------------------|
| 1 | 50 00 | 620 00 | 750 00 | 620 00 | 1 |
| 2 | 750 00 | 620 00 | 1150 00 | 720 00 | 5 |
| 3 | 1150 00 | 720 00 | 2050 00 | 770 00 | 5 |
| 4 | 750 00 | 620 00 | 950 00 | 570 00 | 1 |
| 5 | 950 00 | 570 00 | 2050 00 | 586 50 | 4 |
| 6 | 50 00 | 610 00 | 790 00 | 610 00 | 2 |
| 7 | 50 00 | 600 00 | 830 00 | 600 00 | 3 |
| 8 | 50 00 | 590 00 | 870 00 | 590 00 | 4 |

ISOTROPIC SOIL PARAMETERS

5 Type(s) of Soil

| Soil Type No | Total Unit Wt (pcf) | Saturated Unit Wt (pcf) | Cohesion Intercept (psf) | Friction Angle (deg) | Pore Pressure Param | Pressure Constant (psf) | Piez Surface No |
|--------------|---------------------|-------------------------|--------------------------|----------------------|---------------------|-------------------------|-----------------|
| 1 | 113 5 | 121 0 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 2 | 121 0 | 125 5 | 1500 0 | 0 0 | 0 00 | 0 0 | 1 |
| 3 | 121 0 | 125 5 | 2000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 4 | 121 0 | 125 5 | 3000 0 | 0 0 | 0 00 | 0 0 | 1 |
| 5 | 50 0 | 60 0 | 150 0 | 22 0 | 0 00 | 0 0 | 1 |

A Horizontal Earthquake Loading Coefficient
Of 0 300 Has Been Assigned
A Vertical Earthquake Loading Coefficient
Of 0 000 Has Been Assigned
Cavitation Pressure = 0 0 (psf)
A Critical Failure Surface Searching Method Using A Random
Technique For Generating Circular Surfaces Has Been Specified
625 Trial Surfaces Have Been Generated
25 Surfaces Initiate From Each Of 25 Points Equally Spaced
Along The Ground Surface Between X = 600 00 ft
and X = 850 00 ft
Each Surface Terminates Between X =1100 00 ft
and X =1300 00 ft

Unless Further Limitations Were Imposed The Minimum Elevation
At Which A Surface Extends Is Y = 0 00 ft
10 00 ft Line Segments Define Each Trial Failure Surface
Following Are Displayed The Ten Most Critical Of The Trial

Failure Surfaces Examined They Are Ordered - Most Critical
First

* * Safety Factors Are Calculated By The Modified Bishop Method * *

Failure Surface Specified By 47 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 84 | 624 58 |
| 3 | 796 64 | 622 59 |
| 4 | 806 48 | 620 79 |
| 5 | 816 35 | 619 19 |

| | | |
|----|---------|--------|
| 6 | 826 25 | 617 79 |
| 7 | 836 18 | 616 59 |
| 8 | 846 13 | 615 58 |
| 9 | 856 10 | 614 78 |
| 10 | 866 08 | 614 17 |
| 11 | 876 07 | 613 76 |
| 12 | 886 07 | 613 55 |
| 13 | 896 07 | 613 55 |
| 14 | 906 06 | 613 74 |
| 15 | 916 06 | 614 13 |
| 16 | 926 04 | 614 72 |
| 17 | 936 01 | 615 51 |
| 18 | 945 96 | 616 50 |
| 19 | 955 89 | 617 69 |
| 20 | 965 79 | 619 07 |
| 21 | 975 67 | 620 66 |
| 22 | 985 51 | 622 44 |
| 23 | 995 31 | 624 41 |
| 24 | 1005 07 | 626 58 |
| 25 | 1014 79 | 628 95 |
| 26 | 1024 45 | 631 51 |
| 27 | 1034 07 | 634 26 |
| 28 | 1043 62 | 637 21 |
| 29 | 1053 12 | 640 34 |
| 30 | 1062 55 | 643 67 |
| 31 | 1071 91 | 647 18 |
| 32 | 1081 20 | 650 88 |
| 33 | 1090 42 | 654 76 |
| 34 | 1099 56 | 658 83 |
| 35 | 1108 61 | 663 07 |
| 36 | 1117 57 | 667 50 |
| 37 | 1126 45 | 672 11 |
| 38 | 1135 23 | 676 89 |
| 39 | 1143 92 | 681 85 |
| 40 | 1152 50 | 686 98 |
| 41 | 1160 98 | 692 28 |
| 42 | 1169 35 | 697 75 |
| 43 | 1177 62 | 703 38 |
| 44 | 1185 76 | 709 18 |
| 45 | 1193 79 | 715 14 |
| 46 | 1201 70 | 721 26 |
| 47 | 1203 85 | 722 99 |

Circle Center At X = 891 5 Y = 1114 1 and Radius 500 5
 *** 0 938 ***

Individual data on the 47 slices

| Slice No | Width (ft) | Weight (lbs) | Water Force | | Force Tnorm (lbs) | Force Ttan (lbs) | Earthquake Force | | Surcharge Load (lbs) |
|----------|------------|--------------|-------------|-----------|-------------------|------------------|------------------|-----------|----------------------|
| | | | Top (lbs) | Bot (lbs) | | | Hor (lbs) | Ver (lbs) | |
| 1 | 9 8 | 1128 8 | 0 0 | 0 0 | 0 0 | 0 0 | 338 6 | 0 0 | 0 0 |
| 2 | 9 8 | 3355 7 | 0 0 | 0 0 | 0 0 | 0 0 | 1006 7 | 0 0 | 0 0 |
| 3 | 9 8 | 5507 9 | 0 0 | 0 0 | 0 0 | 0 0 | 1652 4 | 0 0 | 0 0 |
| 4 | 9 9 | 7580 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2274 3 | 0 0 | 0 0 |
| 5 | 9 9 | 9570 5 | 0 0 | 0 0 | 0 0 | 0 0 | 2871 1 | 0 0 | 0 0 |
| 6 | 9 9 | 11472 7 | 0 0 | 0 0 | 0 0 | 0 0 | 3441 8 | 0 0 | 0 0 |
| 7 | 9 9 | 13283 8 | 0 0 | 0 0 | 0 0 | 0 0 | 3985 1 | 0 0 | 0 0 |
| 8 | 10 0 | 15000 1 | 0 0 | 0 0 | 0 0 | 0 0 | 4500 0 | 0 0 | 0 0 |
| 9 | 10 0 | 16618 7 | 0 0 | 0 0 | 0 0 | 0 0 | 4985 6 | 0 0 | 0 0 |
| 10 | 10 0 | 18136 4 | 0 0 | 0 0 | 0 0 | 0 0 | 5440 9 | 0 0 | 0 0 |
| 11 | 10 0 | 19550 5 | 0 0 | 0 0 | 0 0 | 0 0 | 5865 2 | 0 0 | 0 0 |
| 12 | 10 0 | 20858 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6257 6 | 0 0 | 0 0 |
| 13 | 10 0 | 22058 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6617 6 | 0 0 | 0 0 |
| 14 | 10 0 | 23148 6 | 0 0 | 0 0 | 0 0 | 0 0 | 6944 6 | 0 0 | 0 0 |
| 15 | 10 0 | 24127 0 | 0 0 | 0 0 | 0 0 | 0 0 | 7238 1 | 0 0 | 0 0 |
| 16 | 10 0 | 24992 5 | 0 0 | 0 0 | 0 0 | 0 0 | 7497 8 | 0 0 | 0 0 |
| 17 | 10 0 | 25744 0 | 0 0 | 0 0 | 0 0 | 0 0 | 7723 2 | 0 0 | 0 0 |
| 18 | 9 9 | 26381 2 | 0 0 | 0 0 | 0 0 | 0 0 | 7914 3 | 0 0 | 0 0 |
| 19 | 9 9 | 26903 2 | 0 0 | 0 0 | 0 0 | 0 0 | 8071 0 | 0 0 | 0 0 |

38/46

| | | | | | | | | | |
|----|-----|---------|-----|-----|-----|-----|--------|-----|-----|
| 20 | 9 9 | 27310 2 | 0 0 | 0 0 | 0 0 | 0 0 | 8193 1 | 0 0 | 0 0 |
| 21 | 9 8 | 27602 0 | 0 0 | 0 0 | 0 0 | 0 0 | 8280 6 | 0 0 | 0 0 |
| 22 | 9 8 | 27779 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8333 8 | 0 0 | 0 0 |
| 23 | 9 8 | 27843 1 | 0 0 | 0 0 | 0 0 | 0 0 | 8352 9 | 0 0 | 0 0 |
| 24 | 9 7 | 27794 0 | 0 0 | 0 0 | 0 0 | 0 0 | 8338 2 | 0 0 | 0 0 |
| 25 | 9 7 | 27633 6 | 0 0 | 0 0 | 0 0 | 0 0 | 8290 1 | 0 0 | 0 0 |
| 26 | 9 6 | 27363 5 | 0 0 | 0 0 | 0 0 | 0 0 | 8209 1 | 0 0 | 0 0 |
| 27 | 9 6 | 26985 1 | 0 0 | 0 0 | 0 0 | 0 0 | 8095 5 | 0 0 | 0 0 |
| 28 | 9 5 | 26501 3 | 0 0 | 0 0 | 0 0 | 0 0 | 7950 4 | 0 0 | 0 0 |
| 29 | 9 4 | 25913 9 | 0 0 | 0 0 | 0 0 | 0 0 | 7774 2 | 0 0 | 0 0 |
| 30 | 9 4 | 25226 3 | 0 0 | 0 0 | 0 0 | 0 0 | 7567 9 | 0 0 | 0 0 |
| 31 | 9 3 | 24440 9 | 0 0 | 0 0 | 0 0 | 0 0 | 7332 3 | 0 0 | 0 0 |
| 32 | 9 2 | 23561 2 | 0 0 | 0 0 | 0 0 | 0 0 | 7068 4 | 0 0 | 0 0 |
| 33 | 9 1 | 22590 3 | 0 0 | 0 0 | 0 0 | 0 0 | 6777 1 | 0 0 | 0 0 |
| 34 | 9 1 | 21532 5 | 0 0 | 0 0 | 0 0 | 0 0 | 6459 8 | 0 0 | 0 0 |
| 35 | 9 0 | 20391 5 | 0 0 | 0 0 | 0 0 | 0 0 | 6117 4 | 0 0 | 0 0 |
| 36 | 8 9 | 19171 2 | 0 0 | 0 0 | 0 0 | 0 0 | 5751 4 | 0 0 | 0 0 |
| 37 | 8 8 | 17876 6 | 0 0 | 0 0 | 0 0 | 0 0 | 5363 0 | 0 0 | 0 0 |
| 38 | 8 7 | 16512 0 | 0 0 | 0 0 | 0 0 | 0 0 | 4953 6 | 0 0 | 0 0 |
| 39 | 6 1 | 10818 3 | 0 0 | 0 0 | 0 0 | 0 0 | 3245 5 | 0 0 | 0 0 |
| 40 | 2 5 | 4233 5 | 0 0 | 0 0 | 0 0 | 0 0 | 1270 0 | 0 0 | 0 0 |
| 41 | 8 5 | 13036 7 | 0 0 | 0 0 | 0 0 | 0 0 | 3911 0 | 0 0 | 0 0 |
| 42 | 8 4 | 10813 4 | 0 0 | 0 0 | 0 0 | 0 0 | 3244 0 | 0 0 | 0 0 |
| 43 | 8 3 | 8567 8 | 0 0 | 0 0 | 0 0 | 0 0 | 2570 3 | 0 0 | 0 0 |
| 44 | 8 1 | 6306 2 | 0 0 | 0 0 | 0 0 | 0 0 | 1891 9 | 0 0 | 0 0 |
| 45 | 8 0 | 4035 3 | 0 0 | 0 0 | 0 0 | 0 0 | 1210 6 | 0 0 | 0 0 |
| 46 | 7 9 | 1761 3 | 0 0 | 0 0 | 0 0 | 0 0 | 528 4 | 0 0 | 0 0 |
| 47 | 2 2 | 86 7 | 0 0 | 0 0 | 0 0 | 0 0 | 26 0 | 0 0 | 0 0 |

Failure Surface Specified By 45 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 765 98 | 619 23 |
| 3 | 775 75 | 617 12 |
| 4 | 785 57 | 615 23 |
| 5 | 795 43 | 613 55 |
| 6 | 805 32 | 612 10 |
| 7 | 815 24 | 610 86 |
| 8 | 825 19 | 609 85 |
| 9 | 835 16 | 609 06 |
| 10 | 845 15 | 608 49 |
| 11 | 855 14 | 608 15 |
| 12 | 865 14 | 608 03 |
| 13 | 875 14 | 608 13 |
| 14 | 885 13 | 608 45 |
| 15 | 895 12 | 609 00 |
| 16 | 905 09 | 609 77 |
| 17 | 915 04 | 610 76 |
| 18 | 924 97 | 611 97 |
| 19 | 934 86 | 613 41 |
| 20 | 944 73 | 615 06 |
| 21 | 954 55 | 616 93 |
| 22 | 964 33 | 619 03 |
| 23 | 974 06 | 621 34 |
| 24 | 983 73 | 623 86 |
| 25 | 993 35 | 626 60 |
| 26 | 1002 90 | 629 56 |
| 27 | 1012 39 | 632 72 |
| 28 | 1021 80 | 636 10 |
| 29 | 1031 13 | 639 69 |
| 30 | 1040 39 | 643 48 |
| 31 | 1049 55 | 647 48 |
| 32 | 1058 63 | 651 69 |
| 33 | 1067 60 | 656 09 |
| 34 | 1076 48 | 660 69 |
| 35 | 1085 25 | 665 49 |
| 36 | 1093 92 | 670 49 |
| 37 | 1102 47 | 675 67 |

| | | | | |
|----|------|----|-----|----|
| 38 | 1110 | 90 | 681 | 05 |
| 39 | 1119 | 21 | 686 | 61 |
| 40 | 1127 | 40 | 692 | 36 |
| 41 | 1135 | 45 | 698 | 28 |
| 42 | 1143 | 37 | 704 | 39 |
| 43 | 1151 | 15 | 710 | 67 |
| 44 | 1158 | 79 | 717 | 12 |
| 45 | 1162 | 86 | 720 | 71 |

Circle Center At X = 865 6 Y = 1056 5 and Radius 448 5
 *** 0 939 ***

Failure Surface Specified By 57 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 18 | 620 42 |
| 3 | 776 13 | 619 38 |
| 4 | 786 09 | 618 46 |
| 5 | 796 06 | 617 65 |
| 6 | 806 03 | 616 96 |
| 7 | 816 01 | 616 38 |
| 8 | 826 00 | 615 91 |
| 9 | 836 00 | 615 55 |
| 10 | 845 99 | 615 31 |
| 11 | 855 99 | 615 19 |
| 12 | 865 99 | 615 18 |
| 13 | 875 99 | 615 28 |
| 14 | 885 99 | 615 49 |
| 15 | 895 99 | 615 82 |
| 16 | 905 98 | 616 26 |
| 17 | 915 96 | 616 82 |
| 18 | 925 94 | 617 49 |
| 19 | 935 91 | 618 27 |
| 20 | 945 87 | 619 16 |
| 21 | 955 82 | 620 17 |
| 22 | 965 75 | 621 29 |
| 23 | 975 68 | 622 53 |
| 24 | 985 59 | 623 88 |
| 25 | 995 48 | 625 34 |
| 26 | 1005 35 | 626 91 |
| 27 | 1015 21 | 628 59 |
| 28 | 1025 05 | 630 39 |
| 29 | 1034 86 | 632 30 |
| 30 | 1044 66 | 634 32 |
| 31 | 1054 43 | 636 45 |
| 32 | 1064 17 | 638 69 |
| 33 | 1073 89 | 641 04 |
| 34 | 1083 58 | 643 51 |
| 35 | 1093 25 | 646 08 |
| 36 | 1102 88 | 648 76 |
| 37 | 1112 48 | 651 56 |
| 38 | 1122 05 | 654 46 |
| 39 | 1131 59 | 657 47 |
| 40 | 1141 09 | 660 59 |
| 41 | 1150 56 | 663 81 |
| 42 | 1159 99 | 667 14 |
| 43 | 1169 37 | 670 58 |
| 44 | 1178 72 | 674 13 |
| 45 | 1188 03 | 677 78 |
| 46 | 1197 30 | 681 54 |
| 47 | 1206 52 | 685 41 |
| 48 | 1215 70 | 689 38 |
| 49 | 1224 84 | 693 45 |
| 50 | 1233 92 | 697 62 |
| 51 | 1242 96 | 701 90 |
| 52 | 1251 95 | 706 28 |
| 53 | 1260 89 | 710 77 |
| 54 | 1269 77 | 715 35 |
| 55 | 1278 61 | 720 04 |

40/46

56 1287 39 724 82
 57 1292 96 727 94
 Circle Center At X = 862 1 Y = 1494 6 and Radius 879 5
 *** 0 943 ***

Failure Surface Specified By 58 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 20 | 620 53 |
| 3 | 776 15 | 619 61 |
| 4 | 786 12 | 618 79 |
| 5 | 796 10 | 618 08 |
| 6 | 806 08 | 617 48 |
| 7 | 816 07 | 616 99 |
| 8 | 826 06 | 616 60 |
| 9 | 836 05 | 616 32 |
| 10 | 846 05 | 616 15 |
| 11 | 856 05 | 616 09 |
| 12 | 866 05 | 616 14 |
| 13 | 876 05 | 616 30 |
| 14 | 886 05 | 616 56 |
| 15 | 896 04 | 616 93 |
| 16 | 906 03 | 617 41 |
| 17 | 916 01 | 618 00 |
| 18 | 925 99 | 618 69 |
| 19 | 935 96 | 619 49 |
| 20 | 945 91 | 620 40 |
| 21 | 955 86 | 621 42 |
| 22 | 965 80 | 622 55 |
| 23 | 975 72 | 623 78 |
| 24 | 985 63 | 625 12 |
| 25 | 995 53 | 626 57 |
| 26 | 1005 41 | 628 12 |
| 27 | 1015 27 | 629 78 |
| 23 | 1025 11 | 631 55 |
| 29 | 1034 93 | 633 42 |
| 30 | 1044 74 | 635 40 |
| 31 | 1054 52 | 637 48 |
| 32 | 1064 27 | 639 67 |
| 33 | 1074 01 | 641 97 |
| 34 | 1083 71 | 644 37 |
| 35 | 1093 39 | 646 88 |
| 36 | 1103 05 | 649 49 |
| 37 | 1112 67 | 652 20 |
| 38 | 1122 27 | 655 02 |
| 39 | 1131 83 | 657 94 |
| 40 | 1141 36 | 660 97 |
| 41 | 1150 86 | 664 09 |
| 42 | 1160 32 | 667 32 |
| 43 | 1169 75 | 670 66 |
| 44 | 1179 14 | 674 09 |
| 45 | 1188 50 | 677 63 |
| 46 | 1197 81 | 681 26 |
| 47 | 1207 09 | 685 00 |
| 48 | 1216 32 | 688 84 |
| 49 | 1225 52 | 692 77 |
| 50 | 1234 67 | 696 81 |
| 51 | 1243 77 | 700 94 |
| 52 | 1252 83 | 705 17 |
| 53 | 1261 85 | 709 50 |
| 54 | 1270 81 | 713 93 |
| 55 | 1279 73 | 718 45 |
| 56 | 1288 60 | 723 07 |
| 57 | 1297 42 | 727 79 |
| 58 | 1298 23 | 728 23 |

Circle Center At X = 856 7 Y = 1541 3 and Radius 925 2
 *** 0 946 ***

Failure Surface Specified By 52 Coordinate Points

21/26

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 777 08 | 626 77 |
| 2 | 786 79 | 624 37 |
| 3 | 796 54 | 622 15 |
| 4 | 806 33 | 620 10 |
| 5 | 816 15 | 618 23 |
| 6 | 826 01 | 616 53 |
| 7 | 835 89 | 615 01 |
| 8 | 845 80 | 613 68 |
| 9 | 855 73 | 612 52 |
| 10 | 865 69 | 611 54 |
| 11 | 875 65 | 610 74 |
| 12 | 885 64 | 610 12 |
| 13 | 895 63 | 609 67 |
| 14 | 905 62 | 609 41 |
| 15 | 915 62 | 609 33 |
| 16 | 925 62 | 609 43 |
| 17 | 935 62 | 609 71 |
| 18 | 945 61 | 610 17 |
| 19 | 955 59 | 610 81 |
| 20 | 965 55 | 611 63 |
| 21 | 975 50 | 612 63 |
| 22 | 985 43 | 613 81 |
| 23 | 995 34 | 615 17 |
| 24 | 1005 22 | 616 70 |
| 25 | 1015 07 | 618 41 |
| 26 | 1024 89 | 620 30 |
| 27 | 1034 68 | 622 37 |
| 28 | 1044 42 | 624 61 |
| 29 | 1054 13 | 627 03 |
| 30 | 1063 78 | 629 62 |
| 31 | 1073 39 | 632 39 |
| 32 | 1082 95 | 635 33 |
| 33 | 1092 46 | 638 44 |
| 34 | 1101 90 | 641 72 |
| 35 | 1111 29 | 645 17 |
| 36 | 1120 61 | 648 79 |
| 37 | 1129 86 | 652 58 |
| 38 | 1139 05 | 656 54 |
| 39 | 1148 16 | 660 65 |
| 40 | 1157 20 | 664 94 |
| 41 | 1166 16 | 669 38 |
| 42 | 1175 03 | 673 99 |
| 43 | 1183 83 | 678 75 |
| 44 | 1192 53 | 683 67 |
| 45 | 1201 15 | 688 75 |
| 46 | 1209 67 | 693 98 |
| 47 | 1218 09 | 699 37 |
| 48 | 1226 42 | 704 90 |
| 49 | 1234 65 | 710 59 |
| 50 | 1242 77 | 716 42 |
| 51 | 1250 79 | 722 40 |
| 52 | 1255 24 | 725 85 |

Circle Center At X = 915 1 Y = 1164 1 and Radius 554 8
 *** 0 947 ***

Failure Surface Specified By 54 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 766 67 | 624 17 |
| 2 | 776 62 | 623 23 |
| 3 | 786 59 | 622 40 |
| 4 | 796 56 | 621 69 |
| 5 | 806 55 | 621 09 |
| 6 | 816 53 | 620 61 |
| 7 | 826 53 | 620 24 |
| 8 | 836 52 | 619 99 |
| 9 | 846 52 | 619 85 |

42/No

| | | |
|----|---------|--------|
| 10 | 856 52 | 619 83 |
| 11 | 866 52 | 619 92 |
| 12 | 876 52 | 620 13 |
| 13 | 886 52 | 620 45 |
| 14 | 896 51 | 620 89 |
| 15 | 906 49 | 621 44 |
| 16 | 916 47 | 622 11 |
| 17 | 926 44 | 622 89 |
| 18 | 936 40 | 623 78 |
| 19 | 946 35 | 624 79 |
| 20 | 956 28 | 625 91 |
| 21 | 966 21 | 627 15 |
| 22 | 976 12 | 628 50 |
| 23 | 986 01 | 629 97 |
| 24 | 995 88 | 631 55 |
| 25 | 1005 74 | 633 24 |
| 26 | 1015 57 | 635 04 |
| 27 | 1025 39 | 636 96 |
| 28 | 1035 18 | 638 99 |
| 29 | 1044 95 | 641 13 |
| 30 | 1054 69 | 643 39 |
| 31 | 1064 41 | 645 75 |
| 32 | 1074 09 | 648 23 |
| 33 | 1083 75 | 650 82 |
| 34 | 1093 38 | 653 52 |
| 35 | 1102 98 | 656 33 |
| 36 | 1112 54 | 659 25 |
| 37 | 1122 07 | 662 28 |
| 38 | 1131 57 | 665 41 |
| 39 | 1141 03 | 668 66 |
| 40 | 1150 45 | 672 02 |
| 41 | 1159 83 | 675 48 |
| 42 | 1169 17 | 679 05 |
| 43 | 1178 47 | 682 73 |
| 44 | 1187 72 | 686 52 |
| 45 | 1196 94 | 690 41 |
| 46 | 1206 10 | 694 40 |
| 47 | 1215 22 | 698 50 |
| 48 | 1224 30 | 702 71 |
| 49 | 1233 32 | 707 02 |
| 50 | 1242 29 | 711 43 |
| 51 | 1251 21 | 715 95 |
| 52 | 1260 08 | 720 57 |
| 53 | 1268 90 | 725 29 |
| 54 | 1271 57 | 726 75 |

Circle Center At X = 853 5 , Y = 1490 5 and Radius, 870 7
 *** 0 947 ***

Failure Surface Specified By 46 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 83 | 630 69 |
| 3 | 817 77 | 629 55 |
| 4 | 827 72 | 628 57 |
| 5 | 837 69 | 627 74 |
| 6 | 847 66 | 627 08 |
| 7 | 857 65 | 626 57 |
| 8 | 867 65 | 626 22 |
| 9 | 877 64 | 626 03 |
| 10 | 887 64 | 626 00 |
| 11 | 897 64 | 626 12 |
| 12 | 907 64 | 626 41 |
| 13 | 917 63 | 626 85 |
| 14 | 927 61 | 627 44 |
| 15 | 937 58 | 628 20 |
| 16 | 947 54 | 629 11 |
| 17 | 957 48 | 630 19 |
| 18 | 967 41 | 631 41 |

43/46

| | | |
|----|---------|--------|
| 19 | 977 31 | 632 80 |
| 20 | 987 19 | 634 34 |
| 21 | 997 05 | 636 04 |
| 22 | 1006 87 | 637 89 |
| 23 | 1016 67 | 639 90 |
| 24 | 1026 43 | 542 06 |
| 25 | 1036 16 | 544 38 |
| 26 | 1045 85 | 646 84 |
| 27 | 1055 50 | 649 47 |
| 28 | 1065 11 | 652 24 |
| 29 | 1074 67 | 655 17 |
| 30 | 1084 19 | 658 25 |
| 31 | 1093 65 | 661 47 |
| 32 | 1103 06 | 664 85 |
| 33 | 1112 42 | 668 37 |
| 34 | 1121 72 | 672 05 |
| 35 | 1130 97 | 675 86 |
| 36 | 1140 15 | 679 83 |
| 37 | 1149 26 | 683 94 |
| 38 | 1158 31 | 688 19 |
| 39 | 1167 30 | 692 58 |
| 40 | 1176 21 | 697 12 |
| 41 | 1185 05 | 701 80 |
| 42 | 1193 81 | 706 61 |
| 43 | 1202 50 | 711 57 |
| 44 | 1211 11 | 716 66 |
| 45 | 1219 63 | 721 88 |
| 46 | 1223 06 | 724 06 |

Circle Center At X = 884 8 Y = 1258 5 and Radius 632 5
 *** 0 951 ***

Failure Surface Specified By 56 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 23 | 620 99 |
| 3 | 776 22 | 620 50 |
| 4 | 786 22 | 620 12 |
| 5 | 796 21 | 619 83 |
| 6 | 806 21 | 619 63 |
| 7 | 816 21 | 619 54 |
| 8 | 826 21 | 619 53 |
| 9 | 836 21 | 619 63 |
| 10 | 846 21 | 619 82 |
| 11 | 856 20 | 620 10 |
| 12 | 866 19 | 620 48 |
| 13 | 876 18 | 620 96 |
| 14 | 886 17 | 621 53 |
| 15 | 896 14 | 622 20 |
| 16 | 906 12 | 622 96 |
| 17 | 916 08 | 623 82 |
| 18 | 926 03 | 624 78 |
| 19 | 935 98 | 625 83 |
| 20 | 945 91 | 626 98 |
| 21 | 955 83 | 628 22 |
| 22 | 965 74 | 629 55 |
| 23 | 975 64 | 630 99 |
| 24 | 985 52 | 632 51 |
| 25 | 995 39 | 634 13 |
| 26 | 1005 24 | 635 85 |
| 27 | 1015 08 | 637 66 |
| 28 | 1024 90 | 639 56 |
| 29 | 1034 69 | 641 56 |
| 30 | 1044 47 | 643 65 |
| 31 | 1054 23 | 645 84 |
| 32 | 1063 97 | 648 12 |
| 33 | 1073 66 | 650 49 |
| 34 | 1083 37 | 652 95 |
| 35 | 1093 04 | 655 51 |

44/26

| | | |
|----|---------|--------|
| 36 | 1102 68 | 658 16 |
| 37 | 1112 30 | 660 91 |
| 38 | 1121 89 | 663 74 |
| 39 | 1131 45 | 666 67 |
| 40 | 1140 98 | 669 69 |
| 41 | 1150 49 | 672 80 |
| 42 | 1159 96 | 676 00 |
| 43 | 1169 41 | 679 29 |
| 44 | 1178 82 | 682 67 |
| 45 | 1188 19 | 686 15 |
| 46 | 1197 54 | 689 71 |
| 47 | 1206 85 | 693 36 |
| 48 | 1216 12 | 697 10 |
| 49 | 1225 36 | 700 93 |
| 50 | 1234 56 | 704 85 |
| 51 | 1243 72 | 708 85 |
| 52 | 1252 85 | 712 95 |
| 53 | 1261 93 | 717 13 |
| 54 | 1270 97 | 721 39 |
| 55 | 1279 98 | 725 75 |
| 56 | 1283 32 | 727 41 |

Circle Center At X = 821 5 Y = 1662 1 and Radius 1042 6
*** 0 953 ***

Failure Surface Specified By 57 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 756 25 | 621 56 |
| 2 | 766 23 | 620 93 |
| 3 | 776 22 | 620 39 |
| 4 | 786 21 | 619 95 |
| 5 | 796 20 | 619 60 |
| 6 | 806 20 | 619 34 |
| 7 | 816 20 | 619 18 |
| 8 | 826 20 | 619 11 |
| 9 | 836 20 | 619 14 |
| 10 | 846 19 | 619 26 |
| 11 | 856 19 | 619 47 |
| 12 | 866 19 | 619 77 |
| 13 | 876 18 | 620 17 |
| 14 | 886 17 | 620 67 |
| 15 | 896 15 | 621 25 |
| 16 | 906 13 | 621 93 |
| 17 | 916 10 | 622 71 |
| 18 | 926 06 | 623 57 |
| 19 | 936 01 | 624 53 |
| 20 | 945 96 | 625 59 |
| 21 | 955 89 | 626 73 |
| 22 | 965 81 | 627 97 |
| 23 | 975 73 | 629 31 |
| 24 | 985 62 | 630 73 |
| 25 | 995 51 | 632 25 |
| 26 | 1005 38 | 633 86 |
| 27 | 1015 23 | 635 56 |
| 28 | 1025 07 | 637 36 |
| 29 | 1034 89 | 639 25 |
| 30 | 1044 69 | 641 23 |
| 31 | 1054 47 | 643 30 |
| 32 | 1064 24 | 645 46 |
| 33 | 1073 98 | 647 71 |
| 34 | 1083 70 | 650 06 |
| 35 | 1093 40 | 652 50 |
| 36 | 1103 08 | 655 02 |
| 37 | 1112 73 | 657 64 |
| 38 | 1122 35 | 660 35 |
| 39 | 1131 95 | 663 15 |
| 40 | 1141 53 | 666 03 |
| 41 | 1151 07 | 669 01 |
| 42 | 1160 59 | 672 08 |

45/Me

| | | |
|----|---------|--------|
| 43 | 1170 08 | 675 23 |
| 44 | 1179 54 | 678 48 |
| 45 | 1188 97 | 681 81 |
| 46 | 1198 36 | 685 23 |
| 47 | 1207 73 | 688 74 |
| 48 | 1217 06 | 692 34 |
| 49 | 1226 36 | 696 02 |
| 50 | 1235 62 | 699 79 |
| 51 | 1244 84 | 703 65 |
| 52 | 1254 03 | 707 60 |
| 53 | 1263 19 | 711 63 |
| 54 | 1272 30 | 715 74 |
| 55 | 1281 37 | 719 94 |
| 56 | 1290 41 | 724 23 |
| 57 | 1298 71 | 728 26 |

Circle Center At X = 828 6 Y = 1686 3 and Radius 1067 2
*** 0 954 ***

Failure Surface Specified By 48 Coordinate Points

| Point No | X-Surf (ft) | Y-Surf (ft) |
|----------|-------------|-------------|
| 1 | 797 92 | 631 98 |
| 2 | 807 85 | 630 85 |
| 3 | 817 80 | 629 86 |
| 4 | 827 77 | 629 01 |
| 5 | 837 74 | 628 30 |
| 6 | 847 73 | 627 74 |
| 7 | 857 72 | 627 31 |
| 8 | 867 71 | 627 02 |
| 9 | 877 71 | 626 87 |
| 10 | 887 71 | 626 86 |
| 11 | 897 71 | 626 99 |
| 12 | 907 71 | 627 27 |
| 13 | 917 70 | 627 68 |
| 14 | 927 68 | 628 23 |
| 15 | 937 66 | 628 92 |
| 16 | 947 63 | 629 76 |
| 17 | 957 58 | 630 73 |
| 18 | 967 52 | 631 84 |
| 19 | 977 44 | 633 09 |
| 20 | 987 34 | 634 48 |
| 21 | 997 22 | 636 01 |
| 22 | 1007 08 | 637 68 |
| 23 | 1016 92 | 639 49 |
| 24 | 1026 73 | 641 43 |
| 25 | 1036 51 | 643 51 |
| 26 | 1046 26 | 645 73 |
| 27 | 1055 98 | 648 08 |
| 28 | 1065 66 | 650 58 |
| 29 | 1075 31 | 653 20 |
| 30 | 1084 92 | 655 96 |
| 31 | 1094 49 | 658 86 |
| 32 | 1104 02 | 661 89 |
| 33 | 1113 51 | 665 05 |
| 34 | 1122 95 | 668 35 |
| 35 | 1132 35 | 671 78 |
| 36 | 1141 69 | 675 34 |
| 37 | 1150 98 | 679 03 |
| 38 | 1160 22 | 682 85 |
| 39 | 1169 41 | 686 80 |
| 40 | 1178 54 | 690 88 |
| 41 | 1187 61 | 695 09 |
| 42 | 1196 63 | 699 42 |
| 43 | 1205 58 | 703 88 |
| 44 | 1214 46 | 708 47 |
| 45 | 1223 29 | 713 17 |
| 46 | 1232 04 | 718 01 |
| 47 | 1240 73 | 722 96 |
| 48 | 1244 62 | 725 26 |

46/46

Circle Center At X = 883 3 Y = 1339 4 and Radius 712 5
*** 0 956 ***

ATTACHMENT 3· SETTLEMENT CALCULATIONS

| | | | | | |
|---------|---------------------------------|----------|--------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Leachate Collection | Checked | PHD | Date | 4/24/10 |
| Task | LCRS Settlement | Page | 1 of 2 | | |
| Job # | Dept 00143 | No | 125184 | | |

3.1 Task

- A Determine the settlement along the leachate piping alignments
 - a Verify that positive drainage towards the sumps is maintained after placement of the waste
 - b Verify maximum strains along the leachate do not exceed the maximum allowed

3.2 References

- A Earthtec Testing & Engineering, P C (2006) Geotechnical Study Intermountain Regional Landfill
- B Das, B , (1990) Principles of Foundation Engineering, 2nd Ed
- C HDR (2010) Determination of the MHA and Design EQ Calculations, 1 0
- D HDR (2010) Slope Stability Calculations and determination of soil design values, 2 3 C
- E Koerner, R M (2005) Designing With Geosynthetics, 5th Ed

3.3 Analysis

- A Determine the consolidation values of the compressible zone soil based on Reference A
- B Determine the thickness of the compressible zone, Hc
- C Determine the initial pressure at the center of the compressible zone, P1
- D Determine the pressure at the center of the compressible zone after excavation, P2
- E Determine the final pressure at the center of the compressible zone, after waste placement, P3
- F Calculation of Settlement

$$S_c = \left(\left(\frac{C_s * H_c}{1 + e_0} \right) \text{Log} \frac{P_c}{P_0} \right) + \left(\left(\frac{C_c * H_c}{1 + e_0} \right) \text{Log} \left(\frac{P_0 + \Delta P}{P_c} \right) \right)$$

Where

Sc = Total consolidation settlement

Cs = Swell Index

Cc = Compression Index

P0 = Pressure after excavation (prior to filling with waste), P2

e0 = initial void ratio after excavation

Pc = Preconsolidation pressure, Ref A and attached = 2.4 KSF

He = Thickness of compressive soil = 100 FT

ΔP = Change in pressure, P3 – P2 KSF

Since, P0 > Pc (P2 > Pc), Disregard the settlement on the swell index part of the curve

| | | | | | |
|---------|---------------------------------|-------------|------------|------|------------|
| Project | Intermountain Regional Landfill | Computed | GMS | Date | March 2010 |
| Subject | Leachate Collection | Checked | <i>PHD</i> | Date | 4 26 10 |
| Task | LCRS Settlement | Page 2 of 2 | | | |
| Job # | Dept 00143 | No | 125184 | | |

i) Settlement

| Pt # | Depth to Center (FT) | Initial Pressure, P1 (KSF) | Thickness of Excavation (FT) | Pressure after Excavation P2 (KSF) | Thickness of Waste (FT) | Final Pressure, P3 (KSF) | Total | | |
|------|----------------------|----------------------------|------------------------------|------------------------------------|-------------------------|--------------------------|------------------------------|-----------------|-----------------|
| | | | | | | | Change in Pressure, ΔP (KSF) | Settlement (IN) | Settlement (FT) |
| 1 | 70.0 | 8.47 | 20.0 | 6.05 | 42.0 | 8.57 | 2.52 | 18.7 | 1.6 |
| 2 | 72.0 | 8.71 | 22.0 | 6.05 | 72.0 | 10.37 | 4.32 | 21.5 | 1.8 |
| 3 | 75.0 | 9.08 | 25.0 | 6.05 | 100.0 | 12.05 | 6.00 | 23.7 | 2.0 |
| 4 | 82.0 | 9.92 | 32.0 | 6.05 | 134.0 | 14.09 | 8.04 | 26.0 | 2.2 |
| 5 | 90.0 | 10.89 | 40.0 | 6.05 | 73.0 | 10.43 | 4.38 | 21.6 | 1.8 |
| 6 | 95.0 | 11.50 | 45.0 | 6.05 | 46.0 | 8.81 | 2.76 | 19.1 | 1.6 |

Soil M Density = 121.0 (PCF)
Waste Density = 60.0 (PCF)

Cr = Cc = 0.048 Ref A and see attached
Hc = 100.0 FT (assumed)
e0 = 0.704 Ref A and see attached
Pc = 2.4 KSF

ii) Slope and Strain Check along Leachate lines See also attached sketch

| Pt # | Distance (FT) | Initial Slope | Initial Elev (FT) | Initial Length (FT) | Settlement at Left Point (FT) | Settlement at Right Point (FT) | Final Elev (FT) | Final Slope | Verify | | |
|------|---------------|---------------|-------------------|---------------------|-------------------------------|--------------------------------|-----------------|-------------|-------------|-------------------|---------|
| | | | | | | | | | Final Slope | Final Length (FT) | Strain |
| 1-2 | 120.0 | 1.50% | 1.8 | 120.0 | 1.60 | 1.83 | 2.03 | 1.69% | OK | 120.0 | 0.003% |
| 2-3 | 440.0 | 1.50% | 6.6 | 440.0 | 1.83 | 2.00 | 6.77 | 1.54% | OK | 440.1 | 0.001% |
| 3-4 | 550.0 | 1.50% | 8.3 | 550.1 | 2.00 | 2.17 | 8.42 | 1.53% | OK | 550.1 | 0.000% |
| 4-5 | 550.0 | 1.50% | 8.3 | 550.1 | 2.17 | 1.83 | 7.91 | 1.44% | OK | 550.1 | -0.001% |
| 5-6 | 500.0 | 1.50% | 7.5 | 500.1 | 1.83 | 1.58 | 7.25 | 1.45% | OK | 500.1 | -0.001% |


3.4 Conclusions

- A All segments of the leachate collection alignment remain positive towards the sump
- B Strains are less than 1 percent which is much less than maximum of 17%
Reference D, pg 442

**ATTACHMENT 3A: SETTLEMENT AND
CONSOLIDATION CALCULATIONS**

| | | | | | |
|---------|-------------------|----------|-----|------|---------|
| Project | IRL | Computed | Gms | Date | 3/20/10 |
| Subject | Settlement | Checked | PHH | Date | 4 26 10 |
| Task | Verify LCES slope | Page | 1 | of | 8 |
| Job # | 125/84 Dept 143 | No | | | |

Calculations Approach



$$\text{Initial length} = \sqrt{D^2 + \left[(\text{Initial slope}) * D \right]^2}$$

Final length =

$$\Delta_1 = \text{Initial } \Delta f = D * (\text{Initial slope}) = \Delta_i$$

$$\Delta_f = \Delta_1 + (S_R - S_L)$$

| Point # | Depth to Center | Initial Pressure P_1 (ksf)* | Thickness of Excavation | Pressure after EXCAT (ksf) | Tot Waste | P_3 (ksf) Pressure Final** | ΔP |
|---------|-----------------|-------------------------------|-------------------------|----------------------------|-----------|------------------------------|------------|
| ① | 70' | 8.47 | 20' | 6.05 | 42' | 8.57 | 2.52 |
| ② | 72' | 8.71 | 22' | 6.05 | 72' | 10.37 | 4.32 |
| ③ | 75' | 9.08 | 25' | 6.06 | 100' | 12.06 | 6.00 |
| ④ | 82' | 9.92 | 32' | 6.05 | 134' | 14.09 | 8.04 |
| ⑤ | 90' | 10.89 | 40' | 6.05 | 73' | 10.43 | 4.38 |
| ⑥ | 95' | 11.50 | 45' | 6.06 | 46' | 8.82 | 2.76 |

| # | S' | S'' |
|---|-------|-----|
| ① | 1.56' | 19" |
| ② | 1.79' | 22" |
| ③ | 1.98' | 24" |
| ④ | 2.17' | 26" |
| ⑤ | 1.80' | 22" |
| ⑥ | 1.59' | 19" |

$P_1 = (\text{Depth to Center}) * (\text{Moist unit wt of soil})$

$P_2 = P_1 - [\text{Thickness of Ex} * (\text{Moist unit wt of soil})]$


$P_3 = P_2 + [(\text{Thickness of waste fill}) * (\text{Moist unit wt. of waste})]$

Consolidation settlement

$$s_c = \frac{C_c H_c}{1+e_0} \log \frac{P_c}{P_0} + \frac{C_c H_c}{1+e_0} \log \frac{P_0 + \Delta P}{P_c} \quad \text{Das}$$

$P_c = 24 \text{ ksf}$
 $P_0 = P_2$
 $\Delta P = P_3 - P_2$
 $C_c = C_r = 0.048$
 $H_c = 100'$
 $P_0 > P_c$
 $e_0 = 0.704$

* Moist Density = 121.0 PCF (soil)
 ** Moist Density = 60 PCF (waste - saturated)




CROSS SECTION EAST-WEST
ALL CELLS

| | | | | |
|---|---|---|--|--|
| $\Delta = 170(0.015) = 1.9$ $22 - 19 = 3' = 0.25'$ $1.9 + 0.25 = 2.05'$ $\Delta = \frac{2.05}{120} = 1.7\% \text{ OK}$ | $\Delta = (140)(0.015) = 6.6$ $24 - 22 = 2' = 0.17$ $6.6 + 0.17 = 6.8$ $\Delta = \frac{6.8}{240} = 1.5\% \text{ OK}$ | $\Delta = (550)(0.015) = 8.25'$ $26 - 24 = 2' = 0.17'$ $8.25 + 0.17 = 8.42$ $\Delta = \frac{8.42}{550} = 1.5\% \text{ OK}$ | $\Delta = 550(0.015) = 8.25'$ $22 - 26 = -4' = -0.33'$ $8.25 - 0.33 = 7.92$ $\Delta = \frac{7.92}{550} = 1.44\% \text{ OK}$ | $\Delta = 500(0.015) = 7.5$ $19 - 22 = -3 = -0.25$ $7.5 - 0.25 = 7.25$ $\Delta = \frac{7.25}{50} = 1.45\% \text{ OK}$ |
|---|---|---|--|--|

s 1 = 20"
 1" = 40'
 1" = 200'
 Sheet 7 of 12

4/8

CONSOLIDATION - SWELL TEST



$$e_1 = \frac{G_s \gamma_w}{\gamma_d} - 1 = \frac{2.7(62.4)}{97} - 1 = 0.737$$

$$C_s = \frac{0.710 - 0.697}{\log 8} = 0.014$$

| | |
|---------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TH-1 |
| Sample Depth | 15 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 97 |
| Natural Moisture, % | 21 |
| Liquid Limit | 77 |
| Plasticity Index | 51 |
| Water Added at | 1 ksf |
| Percent Swell | 07 |

$$P_0 = \frac{155(1.2)(97)}{1000 \text{ psf}} = 1.8 \text{ tsf}$$

$$C_c = \frac{0.722 - 0.697}{\log \frac{8}{2.4}} = 0.048$$


PROJECT NO 062496



FIGURE NO 30

5/8

CONSOLIDATION - SWELL TEST



$$e_c = \frac{27(62.4)}{93} - 1 = 0.812$$

$$C_r = \frac{(0.794 - 0.779)}{\log\left(\frac{8}{4}\right)} = 0.05$$

$$e_s = \frac{e_3 - e_4}{\log\left(\frac{P_2}{P_1}\right)} = \frac{8.5 \text{ KSF}}{\log\left(\frac{4.0}{0.73}\right)}$$

$$0.013 = \frac{0.791 - 0.779}{\log\left(\frac{8}{1}\right)}$$

Project
Location
Sample Depth
Description
Soil Type
Dry Density, pcf
Natural Moisture, %
Liquid Limit
Plasticity Index
Water Added at
Percent Swell

Intermountain Regional Landfill
TP-14
6
Block
FTA CLAY (CH)
93
20
71
47
1 ksf
0.9

$$P_0 = \frac{(6.5)(120)(930)}{1000 \text{ pcf}} = 0.73 \text{ tsf}$$

$$OCR = \frac{4.0 \text{ tsf}}{0.73 \text{ tsf}} = 55$$


$$LL = 71 \quad 0.0463 \left(\frac{71}{100}\right) 27 = 0.09$$

PROJECT NO 062496



FIGURE NO 28

CONSOLIDATION - SWELL TEST



$e_0 = 0.851$
 0.843
 0.834
 0.826

$$e_s = \frac{C_s \gamma_w}{\gamma_d} - 1 - \frac{27(62.4)}{91} - 1 = 0.85$$

$$C_s = \frac{0.837 - 0.826}{\log 8} = 0.012$$

(100 ft) (60 pcf)
 wast

$$\frac{(50')(110)}{100} = 55 \text{ ksf}$$

$$\frac{50(110)}{1000 \text{ LBS}} = 1 \text{ kip}$$


| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-10 |
| Sample Depth | 8 1/2 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 91 |
| Natural Moisture, % | 26 |
| Liquid Limit | 70 |
| Plasticity Index | 50 |
| Water Added at | 1 ksf |
| Percent Swell | 11 |

$$P_0 = \frac{(9 \text{ Ft})(91)(126)}{1000} \text{ kips} = 103 \text{ tsf}$$

$$OCR = \frac{1.7 \text{ tsf}}{10 \text{ tsf}} = 17$$

$$C_c = \frac{0.841 - 0.826}{\log \left(\frac{8}{17} \right)} = 0.022$$

CONSOLIDATION - SWELL TEST



$e_0 = \frac{27(62.4)}{90} = 1 = 0.872$

$C_c = \frac{0.872 - 0.848}{\log(8/30)} = 0.056$


Pressure (ksf) $P_c = 3.0 \text{ tsf}$
 $C_s = \frac{0.865 - 0.848}{\log 8} = 0.019$

| | |
|----------------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-7 |
| Sample Depth | 9 |
| Description | Block |
| Soil Type | FAT CLAY (CH) |
| Dry Density, pcf | 90 |
| Natural Moisture, % | 23 |
| Liquid Limit | 70 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 15 |

$P_0 = \frac{925(1.23)(900 \text{ pcf})}{1000} = 1.02 \text{ tsf}$

$OCR = \frac{P_c}{P_0} = \frac{3.0 \text{ tsf}}{1.0 \text{ tsf}} = 3.0$

CONSOLIDATION - SWELL TEST



| | |
|---------------------|---------------------------------|
| Project | Intermountain Regional Landfill |
| Location | TP-15 |
| Sample Depth | 7 1/2 |
| Description | Block |
| Soil Type | FTA CLAY (CH) |
| Dry Density, pcf | 93 |
| Natural Moisture, % | 19 |
| Liquid Limit | 61 |
| Plasticity Index | 37 |
| Water Added at | 1 ksf |
| Percent Swell | 0.9 |

$P_0 = \frac{(8 \times 93 \times 19)}{1000} = 1.42 \text{ ksf}$

$P_0 = 0.9 \text{ ksf}$

$C_r = \frac{0.800 - 0.782}{\log \frac{3}{0.9}} = 0.042$

$OCR = \frac{3.0 \text{ ksf}}{0.9 \text{ ksf}} = 3.3$

PROJECT NO 062496



FIGURE NO 29

APPENDIX G

GROUNDWATER MONITORING PLAN

APPENDIX G

**GROUNDWATER MONITORING PLAN
FOR
INTERMOUNTAIN REGIONAL LANDFILL**

Prepared by

**HDR Engineering, Inc
3949 South 700 East, Suite 500
Salt Lake City, Utah 84107
(801) 743-7800**

**Submitted
August 2010**

TABLE OF CONTENTS

| | | |
|-------|---|---|
| 1 0 | INTRODUCTION | 1 |
| 1 1 | Groundwater Monitoring System | 1 |
| 1 2 | Well Construction and Abandonment | 1 |
| 2 0 | GROUNDWATER ELEVATION MONITORING | 1 |
| 2 1 | Well Inspections | 1 |
| 2 2 | Monitoring Procedures | 2 |
| 2 3 | Protocol for Water-Level Measurements and Instrumentation | 2 |
| 3 0 | DECONTAMINATION PROCEDURES | 2 |
| 4 0 | GROUNDWATER SAMPLE COLLECTION | 3 |
| 4 1 | Well-Purging Procedures | 3 |
| 4 2 | Groundwater Collection and Handling Procedures | 3 |
| 4 2 1 | Sampling Frequency of Detection Monitoring | 4 |
| 4 3 | Quality Assurance and Quality Control Samples | 4 |
| 4 4 | Health and Safety Protocol | 4 |
| 4 5 | Purge Water Handling Procedures | 4 |
| 5 0 | ANALYTICAL TESTING | 5 |
| 5 1 | Laboratory Performing the Analyses | 5 |
| 5 2 | Laboratory Procedures | 5 |
| 5 3 | Laboratory Quality Assurance and Quality Control Samples | 5 |
| 5 4 | Constituents To Be Analyzed and Test Methods | 5 |
| 5 5 | Establishing Background Data | 7 |
| 6 0 | STATISTICAL METHOD TO EVALUATE ANALYTICAL DATA | 7 |
| 7 0 | REPORTING REQUIREMENTS | 7 |

LIST OF TABLES

| | | |
|---------|--|---|
| Table 1 | Background/Detection Monitoring Constituents | 6 |
|---------|--|---|

LIST OF ATTACHMENTS

| | |
|--------------|-------------------------------|
| Attachment 1 | Field Data Form |
| Attachment 2 | Typical Chain-of-Custody Form |
| Attachment 3 | Figures |

1 0 INTRODUCTION

This Groundwater Monitoring Plan (GMP) addresses the groundwater monitoring and sampling program at Intermountain Regional Landfill in Fairfield, Utah. The GMP is required by the Utah Department of Environmental Quality (UDEQ) Municipal Solid Waste Regulations (R315-308-2) and will meet the requirements of the federal U.S. Environmental Protection Agency (EPA) regulations under Subtitle D of the Resource Conservation and Recovery Act (RCRA).

1 1 Groundwater Monitoring System

The groundwater monitoring system for the site consists of seven permanent monitoring wells (DMW), DMW-1 through DMW-7 and one temporary monitoring well (TMW-1). Well DMW-1 serves as the upgradient or background well for the landfill. DMW-2 serves as the downgradient or compliance well for the leachate pond. DMW-3 and TMW-1 serve as the compliance wells for Cell 1. Construction of Cell 2 will begin on the east side of the cell. TMW-1 will be removed once landfill excavations are needed for future phases of Cell 2. DMW-4 will serve as the compliance well for the Cell 2. Future Cells will also be developed from east to west across the site. DMW-5 will serve as compliance point for Cell 3 and portions of Cell 4. DMW-6 will be used to monitor groundwater immediately downgradient of Cell 5. DMW-7 will serve as the compliance point for Cell 6.

Monitoring well locations are shown on Figure G-1 in Attachment 3. The monitoring wells will be installed during the initial phases of landfill construction. Groundwater samples will also be collected during the initial operations in order to establish background water quality.

1 2 Well Construction and Abandonment

Groundwater monitoring wells will be constructed of 2-inch or 2.5-inch-diameter polyvinyl chloride (PVC) pipe with a 20-foot screen interval and a 1-foot silt sump. Figure G-2 in Attachment 3 shows a typical design of a groundwater monitoring well. A licensed well driller will install the monitoring wells to ensure reporting compliance with Utah Administrative Rules (Rule 655-4) and that minimum well construction standards are followed.

As mentioned above, one temporary monitoring well is included in the monitoring system. Once the landfill excavation is required for the area around TMP-1, the monitoring well will be abandoned. To ensure proper techniques are used, the monitoring well will be abandoned according to the requirements found in R655-4-12 (Abandonment of Wells). In general, the abandonment requires a bentonite seal and ten feet of cement grout at the surface to ensure a water tight seal.

2 0 GROUNDWATER ELEVATION MONITORING

2 1 Well Inspections

During each monitoring event, the wells will be inspected for damage to the well casing, protective cover, lock, well cap, and concrete pad. In addition, the ground surface around the well pads will be inspected for erosion. If any problems are discovered, the problem elements will be repaired or replaced as soon as practicable.

2.2 Monitoring Procedures

Groundwater-level measurements will be collected using an electric well sounder with measurements recorded to the nearest 0.5-inch (0.04-foot) increment. For each monitoring event, the total well depth will be measured to evaluate whether the casing has silted up. Water levels in the monitor wells will be measured before purging or sampling to minimize the potential effects of these activities on the water levels. The groundwater-level measurement will be recorded to the nearest 0.04 foot from the top of the monitor well casing. Water-level measurements will always be referenced to the survey mark on the well casing. When a measurement is collected, the measuring device will be raised and lowered several times to ensure that the correct measurement is obtained. Water-level measurements collected for each monitoring event will be converted to elevations (nearest 0.04 foot) and submitted with the groundwater sampling report. The survey data for each monitoring well will be referenced to the benchmark established for the landfill.

2.3 Protocol for Water-Level Measurements and Instrumentation

During each monitoring event, the current water-level readings will be compared to the readings from the previous monitoring event in order to avoid discrepancies. If an obvious discrepancy is noticed, the water level will be measured again to ensure that the measurement was recorded correctly.

Before collecting water-level measurements, the measuring device will be checked for damage, including bends or kinks in the tape. To maintain consistency and precision, and to the degree possible, the same measuring device will be used during each monitoring event.

Before conducting the well-purging activities, the pH and conductivity meters will be calibrated. The instruments will be calibrated according to the manufacturer's procedures for each instrument. At a minimum, the pH meter will be calibrated using standard calibration solutions as recommended by the manufacturer. The conductivity meter will be calibrated using standard solutions as recommended or supplied by the manufacturer. The same instruments will be used for each monitoring event.

3.0 DECONTAMINATION PROCEDURES

Before beginning each sampling event and between wells, all non-dedicated equipment including the water-level measuring device will be decontaminated thoroughly to minimize the potential for cross-contamination. The decontamination procedures will consist of thoroughly flushing the equipment with potable water three times followed by a final rinse with deionized water. Purge and decontamination water will be discharged on the ground. If contamination is found in compliance monitoring events, subsequent purge and decontamination water will be stored in containers until analytical results are provided. Purge water will be discharged to the leachate detention basin if contaminated or to the ground if uncontaminated.

4 0 GROUNDWATER SAMPLE COLLECTION

4 1 Well-Purging Procedures

Before each sampling event, the groundwater level in each well and the total well depth will be measured as described in Section 2 2, Monitoring Procedures. During the purging activities, the sampling team will wear disposable latex gloves and will change them between wells. To purge a well, a disposable bailer will be lowered into the monitoring well. The bailer will be raised to the surface and water evacuated. Three well volumes will be removed from the well before a sample is collected. If a well dewateres before achieving the stable water quality parameters, it will be allowed to recharge before sampling. During the purging operations, the sampling team will record the climatic conditions, condition of the wells and surrounding ground surface, field collected water quality, color, odors, water level, depth of well, and purge rate. The information will be recorded in indelible ink, will be stored either on site at the landfill office, and will become part of the site operating record for the landfill.

4 2 Groundwater Collection and Handling Procedures

Before collecting a groundwater sample, the monitor wells will be purged of groundwater as described in Section 4 1, Well-Purging Procedures. Purge water will be handled as discussed in Section 4 5, Purge Water Handling Procedures. The monitor wells will be sampled in the same order as they are purged. Samples will be collected within 24 hours following purging. If sufficient recharge does not occur within 7 days following purging, then the well will be considered dry and a sample will not be collected. The Intermountain Regional Landfill's operators will follow the laboratory's quality assurance/quality control (QA/QC) protocols regarding sampling containers, preservation, and holding times.

The samples will be collected directly from the bailer. The sample containers will be held as close to the bailer as possible without touching it to minimize the loss of volatile organic compounds (VOCs). The containers for the VOCs will be tilted slightly to allow the water to gently run down the inside wall of the container.

After each sample container is filled, it will be labeled with the well number, date and time collected, preservatives used, analyses to be run, and the sampler's initials. The 40-mL (milliliter) vials will be placed in zip-locked plastic bags. The sample containers for each well will include, at a minimum, two 40-mL volatile organic analysis (VOA) glass vials with Teflon[®] septa screw caps for VOCs and other bottles provided by the laboratory. Sample containers for VOCs will be completely filled and sealed carefully to prevent air bubbles. If an air bubble is present, then the sample will be discarded and the sample will be collected again. All other sample containers will be filled as completely as possible.

Once the samples have been properly sealed and labeled as described above, they will be recorded on a Chain-of-Custody (COC) form that is signed and dated by the sampling technician(s). An example of a typical COC is presented in Attachment 2. The COC will accompany the samples to the laboratory.

The samples will be placed in a plastic ice chest (similar to an Igloo ice chest) with ice or a refreezable product to maintain a temperature as close to 4 degrees Celsius as possible until the

analyses are performed. Dry ice is **not permitted** because it could freeze the samples and break the containers. Precautions will be taken to secure the samples in the ice chest to prevent them from breaking during transport.

The samples will be delivered to the laboratory within **24 hours** after collection, so it will not be necessary to preserve the samples in the field, except samples collected for dissolved constituent analyses. Any samples, other than the samples collected for dissolved constituent analyses, that require preservatives will be collected in pre-preserved containers supplied by the laboratory.

4.2.1 Sampling Frequency of Detection Monitoring

The sampling schedule for detection monitoring consists of collecting samples from each monitor well for the detection monitoring constituents on a semi-annual basis after background data have been established. Any changes to the frequency and/or number and type of constituents for detection monitoring must be approved by the Executive Secretary of the Division of Solid and Hazardous Waste before implementing the change. The schedule for establishing background data is discussed in Section 5.5, Establishing Background Data.

4.3 Quality Assurance and Quality Control Samples

To screen field procedures, additional samples will be collected. Periodically, trip blank samples will be prepared by the laboratory and will accompany the empty sample containers and collected samples to and from the laboratory. The trip blank will consist of four 40-mL VOA vials, two with deionized water and two with laboratory-grade water. The purpose of the trip blank is to assess whether any of the sample containers or collected samples has been contaminated before or during sampling and during transport to the laboratory. At least one trip blank will be prepared for each day of sampling or for every container transported to the laboratory. The QA/QC samples will be collected and handled in a similar fashion as the other samples and will be analyzed for VOCs.

At the discretion of the owner or at the direction of UDEQ, blind field duplicate samples will be collected to assess the precision of the sampling and laboratory methods. The blind duplicate samples will be collected from well(s) with typically the highest concentrations of contaminants. When a blind sample is collected, it will be handled in a similar fashion as the other samples but will be labeled so that the laboratory does not know it is a duplicate sample for QA/QC purposes.

4.4 Health and Safety Protocol

Sampling of the monitor wells will not be permitted during inclement weather, including thunderstorms. To the extent possible, monitor wells will not be sampled when the temperature is below freezing. Caution should be taken when the temperature exceeds 100 degrees Fahrenheit. If contamination is detected, the Intermountain Regional Landfill owner will develop a health and safety plan for future groundwater monitoring.

4.5 Purge Water Handling Procedures

If contamination is found in prior samples, purge and decontamination water will be collected in closable drums and stored on-site for subsequent disposal. The analytical data will be reviewed to determine the proper disposal procedures. If needed, UDEQ will be consulted to help determine proper disposal procedures.

5 0 ANALYTICAL TESTING

5 1 Laboratory Performing the Analyses

The analytical laboratory selected to perform the required analyses will be licensed and certified by the State of Utah. At a minimum, the selected laboratory will apply quality-control procedures in accordance with EPA SW-846, Test Methods for Evaluating Solid Waste, Third Edition, as revised February 2007.

5 2 Laboratory Procedures

The laboratory will follow appropriate QA/QC protocols developed as part of its licensing and certification. At a minimum, on receipt of the samples by the laboratory, the sample lot will be verified with the information on the COC (see Attachment 2). If there is a discrepancy with the samples, the responsible party that collected the samples will be notified, and the problem will be resolved before the analyses are performed. The COC will be signed and dated by the designated receiving personnel at the laboratory. The COC will remain with the laboratory until the analyses are completed and then will be attached to the completed laboratory report.

For samples that require overnight transport to the laboratory, the COC will be signed, and the date and time when the samples were received by the transporter will be recorded. The COC will be attached to the sample container(s) and delivered to the laboratory, and a copy of the bill of lading will be supplied by the transporter. After the analysis is completed and the laboratory report is finalized, the complete COC with the bill of lading (or receipt if sent by certified mail) will be attached to the laboratory report.

The laboratory will keep a copy of the COC and laboratory results for at least 3 years.

5 3 Laboratory Quality Assurance and Quality Control Samples

The laboratory will follow its QA/QC plan developed as part of its licensing and certification. If practical, the laboratory will be required to achieve detection limits (DLs) that are at least one order of magnitude below the maximum contaminant levels (MCLs) for a constituent for which an MCL has been established.

5 4 Constituents To Be Analyzed and Test Methods

As specified in the UDEQ (R315-308-2) and Subtitle D (40 Code of Federal Regulations [CFR] 258.53) regulations, the groundwater monitoring program at all municipal solid waste landfill facilities shall consist of detection monitoring that includes specific constituents. The constituents to be tested for during the detection-monitoring program are listed in Table 1 below. Approved testing methods as described in Section 5.1, Laboratory Performing the Analyses, will be used for all constituents. The laboratory DLs will be below the MCLs for each of the constituents, if practical. If a change in the analytical method is needed, then the Executive Secretary will be notified in writing. The Executive Secretary shall approve of the change before the change is implemented. All samples will be analyzed within the required holding times for the particular analyses. The laboratory will report the Chemical Abstracts Service (CAS) number for each constituent analyzed.

Table 1 Background/Detection Monitoring Constituents

| Inorganic Constituents | Heavy Metals |
|--|---|
| Ammonia (7664-41-7) | Antimony (7440-36-0) |
| Carbonate/bicarbonate | Arsenic (7440-38-2) |
| Calcium | Barium (7440-39-3) |
| Chemical oxygen demand (COD) | Beryllium (7440-41-7) |
| Chlorides | Cadmium (7440-43-9) |
| Iron (7439 89-6) | Chromium |
| Magnesium | Cobalt (7440-48-4) |
| Manganese (7439-96-5) | Copper (7440-50-8) |
| Nitrate (as N) | Lead |
| pH | Mercury (7439-97-6) |
| Potassium | Nickel (7440-02-0) |
| Sodium | Selenium (7782-49-2) |
| Sulfate | Silver (7440-22-4) |
| Total dissolved solids (TDS) | Thallium |
| Total organic carbon (TOC) | Vanadium (7440 62-2) |
| | Zinc (7440-66-6) |
| VOCs | |
| Acetone (67-64-1) | is-1 3-Dichloropropene (100061-01-5) |
| Acrylonitrile (107-13-1) | trans-1 3-Dichloropropene (10061-02-6) |
| Benzene (71 43-2) | Ethylbenzene (100-41-4) |
| Bromochloromethane (74 97-5) | 2-Hexanone (591-78-6) |
| Bromodichloromethane (75-27-4) | Methyl bromide (74-83-9) |
| Bromoform (75-25-2) | Methyl chloride (74-87-3) |
| Carbon disulfide (75-15-0) | Methylene bromide (74-95-3) |
| Carbon tetrachloride (56-23-5) | Methylene chloride (75-09-2) |
| Chlorobenzene (108-90-7) | Methyl ethyl ketone MEK (78-93-3) |
| Chloroethane (75-00-3) | Methyl iodide (74-88-4) |
| Chloroform (67-66-3) | 4-Methyl-2-pentanone (108-10-1) |
| Dibromochloromethane (124-48-1) | Styrene (100-42-5) |
| 1 2-Dibromo-3-chloropropane (96-12-8) | 1 1,1 2-Tetrachloroethane (630-20-6) |
| 1 2-Dibromoethane (106-93-4) | 1 1 2 2-Tetrachloroethane (79-34-5) |
| 1 2-Dichlorobenzene ortho (95-50-1) | Tetrachloroethylene (127-18-4) |
| 1 4-Dichlorobenzene para (106-46-7) | Toluene (108-88-3) |
| trans-1 4-Dichloro-2-butene (110-57-6) | 1,1 1-Trichloroethane (71-55-6) |
| 1 1-Dichloroethane (75-34-3) | 1 1 2-Trichloroethane (79-00-5) |
| 1 2-Dichloroethane (107-06-2) | Trichloroethylene (79-01-6) |
| 1 1-Dichloroethylene (75-35-4) | Trichlorofluoromethane CFC-11 (75-69-4) |
| cis-1 2-Dichloroethylene (156-59-2) | 1 2 3-Trichloropropane (96-18-4) |
| trans-1,2-Dichloroethylene (156-60-5) | Vinyl acetate (108 05-4) |
| 1 2-Dichloropropane (78-87-5) | Vinyl chloride (75-01-4) |
| | Xylenes (1330-20-7) |

Note The CAS Number (if appropriate) is listed in parentheses These parameters were taken from UAC R315-308 4 and should be verified at least annually

5.5 Establishing Background Data

Monitoring wells will be installed during initial landfill construction. As specified in the UDEQ regulations (R315-308-2(4)(a)) and Subtitle D (40 CFR 258.53) regulations, background data for the detection monitoring constituents will be established on all monitoring wells as they are constructed. Background data will be generated by sampling the monitoring wells on a monthly basis after construction. To provide an acceptable level of confidence in the data, eight samples will be collected to establish background concentrations.

6.0 STATISTICAL METHOD TO EVALUATE ANALYTICAL DATA

After each sampling event, the groundwater monitoring data will be evaluated to determine if statistically significant changes from background values have occurred for each constituent listed in Table 1 above. The statistical analyses will be performed in accordance with R315-308-2(7). The anticipated statistical method selected for this landfill will be an intra-well comparison with a control chart such as a Shewhart-CUSUM control chart. This procedure is the preferred method because it is relatively easy to implement and because it is especially applicable to sites without groundwater contamination. The analytical data may also be analyzed using prediction limits (PL), with the PLs determined based on the background data collected. The background data, once obtained, will be reviewed to determine the most appropriate statistical method to evaluate statistically significant changes during the detection-monitoring period.

7.0 REPORTING REQUIREMENTS

After each detection monitoring sampling event, the analytical data will be summarized in a report. The report will be submitted with the landfill's annual report unless immediate notification is required. Any statistically significant change observed from the background data will be reported in writing to UDEQ within 60 days after a sampling event. Only statistically significant changes (SSC) detected in the compliance wells (downgradient wells) will be reported to UDEQ.

When an SSC has been determined, the owner/operator within 14 days of receiving the statistical analysis results will enter this information into the operating record and notify the Executive Secretary of the finding in writing. The notification must indicate the constituents that have shown SSC. In addition, the owner/operator will immediately resample all monitoring wells for the constituents listed in Table 1. If an SSC is still present after resampling, the owner/operator must notify the Executive Secretary in writing within 7 days of receiving the sample results. However, if the SSC from the background data is believed to be caused by a source other than the landfill, then the owner/operator can prepare a report that explains the cause of the SSC. This report must be prepared and certified by a qualified groundwater scientist and submitted to the Executive Secretary for approval within 90 days after the sampling event. If the Executive Secretary approves the report, then the landfill can return to detection monitoring. If the Executive Secretary believes that a satisfactory explanation is not given, the assessment monitoring program will be implemented at the direction of the Executive Secretary. The assessment monitoring program shall be implemented in accordance with R315-308-2(11).

ATTACHMENT 1
FIELD DATA FORM

ATTACHMENT 2

TYPICAL CHAIN-OF-CUSTODY FORM

Phone 801 964-2511
 Fax 801 964 2721
 www.enviroprolabs.com

ENVIROPRO LABORATORIES

2712 South 3600 West, Suite E
 West Valley City UT 84119


Chain of Custody Record

Date _____ Page _____ of _____


| Contact Information | | | | | Preservation Code | Number of Containers | Rash | Container Size | Analysis Request | | | | | | Preservation Code | | | |
|--|-----------------------|-----------------------|--------------|---------------|---------------------|----------------------|------|---------------------|------------------|------|-----------------------------|-----|--------------|---------------|-------------------|---|---|---|
| Contact Name | Phone Number | Fax Number | | Company Name | | | | | Street Address | City | State | Zip | Project Name | Site Location | 1 | 2 | 3 | 4 |
| | | | | | | | | | | | | | | | | | | 1 = 4 C 2 = HNO ₃ 3 = HCl 4 = H ₂ SO ₄ 5 = NaOH 6 = Other |
| Sample ID | Date Collected | Time Collected | Matrx | Lab ID | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| Special Instructions / Comments | | | | | (1) Relinquished By | | | (2) Relinquished By | | | Sampler Initials | | | | | | | |
| | | | | | (1) Date / Time | | | (2) Date / Time | | | Method of Shipment | | | | | | | |
| | | | | | (1) Company | | | (2) Company | | | HAND CARRY USPS FEDX UPS | | | | | | | |
| | | | | | (1) Received By | | | (2) Received By | | | CoC | | | | | | | |
| Route Results Through | | | | | (1) Date / Time | | | (2) Date / Time | | | Seal Intact? | | | | | | | |
| Email address | | | | | (1) Company | | | (2) Company | | | Yes No | | | | | | | |


APPENDIX 3

FIGURES



LEGEND


-  MONITORING WELL
- DMW-X DEEP MONITORING WELL
- TMW-X TEMPORARY MONITORING WELL



INTERMOUNTAIN REGIONAL LANDFILL
MONITORING WELL LOCATIONS

| | |
|--------|-------------|
| DATE | AUGUST 2010 |
| FIGURE | G-1 |

NOTE: LOCATIONS OF MONITORING WELLS ARE APPROXIMATE. THIS FIGURE IS INTENDED TO PRESENT THE GENERAL LOCATION RELATIVE TO THE LANDFILL CELLS.



HDR Engineering Inc

Typical Monitoring Well

Date
April 2010

Figure
G-2

Piezometer.cdr
R:\Hatch\co\Figures
10/22/2001

1

APPENDIX H

LEACHATE GENERATION CALCULATIONS

APPENDIX H

LEACHATE GENERATION CALCULATIONS

**Intermountain Regional Landfill
Class I Landfill Permit Application**

Submitted August 2010

**Prepared By
HDR ENGINEERING, INC**

HELP Model Introduction and Parameters

The Hydrologic Evaluation of Landfill Performance (HELP) model was used to determine the amount of leachate generated at Intermountain Regional Landfill for two scenarios

- Scenario 1 Cell Area of one acre with an initial height of 10 feet and 6" of daily cover for 1 year
 - Layer 1 6 inches of daily cover (layer type 1, texture 6)
 - Layer 2 10 feet of waste (layer type 1, texture 18)
 - Layer 3 2 feet of a drainage layer (layer type 2, texture 6)
 - Layer 4 60 mil HDPE Liner (layer type 4, texture 35)
 - Layer 5 0.25" Bentonite Mat (layer type 3, texture 17)

- Scenario 2 Cell area of 1 acre with 100 feet of waste and 12" of intermediate cover (prior to final cap)
 - Layer 1 12 inches of intermediate cover (layer type 1, texture 6)
 - Layer 2 100 feet of waste (layer type 1, texture 18)
 - Layer 3 2 feet of a drainage layer (layer type 2, texture 6)
 - Layer 4 60 mil HDPE Liner (layer type 4, texture 35)
 - Layer 5 0.25" Bentonite Mat (layer type 3, texture 17)

It is noted that an area of 1 acre was used for the calculations because the calculations can then be applied to any area to determine leachate generation

The texture types shown above are defined in the HELP program as shown in attachment 1. The layer types shown above are defined in the HELP program as follows

- Layer type 1 Vertical drainage layer
- Layer type 2 Lateral drainage layer
- Layer type 3 Flexible membrane liner
- Layer type 4 Earthen soil layer

To be conservative, the intermediate cover, daily cover, lateral drainage layer and the barrier soil layer were assumed to be saturated at the beginning of the simulation for both conditions. The initial moisture content of the waste was assumed to be 11%.

For the 60 mil HDPE flexible membrane liner, the following properties were used:

- Pinhole density: 2 holes per acre
- Installed defects: 4 holes per acre
- Placement quality: Good

The maximum drainage path used for the analysis is 2,500 feet with an average drainage slope of 1.6%.

The synthetic rainfall generator (SRG) from the HELP model was used for Salt Lake City, Utah for 20 years. The SRG was then adjusted using monthly temperature and precipitation data for Fairfield, Utah from the Western Regional Climate Center (see attachment 2).

Leachate Generation and Maximum Head

Leachate generation calculations for Scenarios 1 and 2 are attached, and show that no leachate is generated in either scenario (see attachment 3). Because no leachate is generated, the head on the liner is negligible and is therefore less than the 12" maximum head specified in R-315.

Leachate Collection and Management

As stated previously, the HELP Model results show that no leachate is generated. However, an 8" leachate collection pipe will be installed at a 1.4% slope to collect any leachate that may be generated. The capacity of the pipe is 1.88 cfs (see attachment 4).

Stormwater that comes into contact with solid waste or daily cover is typically allowed to infiltrate into the waste to be managed by the leachate system. Contaminated stormwater will be minimized by keeping the active face as small as possible and by placing soil cover on all waste-filled areas not currently being utilized for disposal.

The following is a list of attachments

Attachment 1 HELP Program Texture Types

Attachment 2 Western Regional Climate Center data

Attachment 3 HELP Program Output

Attachment 4 Leachate Collection Pipe Capacity Calculation

References

The Hydrologic Evaluation of Landfill Performance (HELP) Model Engineering Documentation for Version 3 <http://el.ercdc.usace.army.mil/elmodels/pdf/help3doc.pdf> Site visited May 3, 2010

Western Regional Climate Center website <http://www.wrcc.dri.edu/> Site visited May 20, 2010

APPENDIX H

ATTACHMENT 1
HELP Program Texture Types

TABLE 4 DEFAULT SOIL, WASTE, AND GEOSYNTHETIC CHARACTERISTICS

| Classification | | | Total Porosity | Field Capacity | Wilting Pomt | Saturated Hydraulic Conductivity |
|----------------|--|------|----------------|----------------|--------------|----------------------------------|
| HELP | USDA | USCS | vol/vol | vol/vol | vol/vol | cm/sec |
| 1 | CoS | SP | 0.417 | 0.045 | 0.018 | 1.0x10 ⁻² |
| 2 | S | SW | 0.437 | 0.062 | 0.024 | 5.8x10 ⁻³ |
| 3 | FS | SW | 0.457 | 0.083 | 0.033 | 3.1x10 ⁻³ |
| 4 | LS | SM | 0.437 | 0.105 | 0.047 | 1.7x10 ⁻³ |
| 5 | LFS | SM | 0.457 | 0.131 | 0.058 | 1.0x10 ⁻³ |
| 6 | SL | SM | 0.453 | 0.190 | 0.085 | 7.2x10 ⁻⁴ |
| 7 | FSL | SM | 0.473 | 0.222 | 0.104 | 5.2x10 ⁻⁴ |
| 8 | L | ML | 0.463 | 0.232 | 0.116 | 3.7x10 ⁻⁴ |
| 9 | SiL | ML | 0.501 | 0.284 | 0.135 | 1.9x10 ⁻⁴ |
| 10 | SCL | SC | 0.398 | 0.244 | 0.136 | 1.2x10 ⁻⁴ |
| 11 | CL | CL | 0.464 | 0.310 | 0.187 | 6.4x10 ⁻³ |
| 12 | SiCL | CL | 0.471 | 0.342 | 0.210 | 4.2x10 ⁻⁶ |
| 13 | SC | SC | 0.430 | 0.321 | 0.221 | 3.3x10 ⁻³ |
| 14 | SiC | CH | 0.479 | 0.371 | 0.251 | 2.5x10 ⁻⁶ |
| 15 | C | CH | 0.475 | 0.378 | 0.265 | 1.7x10 ⁻⁶ |
| 16 | Barrier Soil | | 0.427 | 0.418 | 0.367 | 1.0x10 ⁻⁷ |
| 17 | Bentonite Mat (0.6 cm) | | 0.750 | 0.747 | 0.400 | 3.0x10 ⁻⁹ |
| 18 | Municipal Waste (900 lb/yd ³ or 312 kg/m ³) | | 0.671 | 0.292 | 0.077 | 1.0x10 ⁻³ |
| 19 | Municipal Waste (channeling and dead zones) | | 0.168 | 0.073 | 0.019 | 1.0x10 ⁻³ |
| 20 | Drainage Net (0.5 cm) | | 0.850 | 0.010 | 0.005 | 1.0x10 ⁺¹ |
| 21 | Gravel | | 0.397 | 0.032 | 0.013 | 3.0x10 ⁻¹ |
| 22 | L | ML | 0.419 | 0.307 | 0.180 | 1.9x10 ⁻⁶ |
| 23 | SiL | ML | 0.461 | 0.360 | 0.203 | 9.0x10 ⁻⁶ |
| 24 | SCL | SC | 0.365 | 0.305 | 0.202 | 2.7x10 ⁻⁶ |
| 25 | CL | CL | 0.437 | 0.373 | 0.266 | 3.6x10 ⁻⁶ |
| 26 | SiCL | CL | 0.445 | 0.393 | 0.277 | 1.9x10 ⁻⁶ |
| 27 | SC | SC | 0.400 | 0.366 | 0.288 | 7.8x10 ⁻⁷ |
| 28 | SiC | CH | 0.452 | 0.411 | 0.311 | 1.2x10 ⁻⁶ |
| 29 | C | CH | 0.451 | 0.419 | 0.332 | 6.8x10 ⁻⁷ |
| 30 | Coal Burning Electric Plant Fly Ash | | 0.541 | 0.187 | 0.047 | 5.0x10 ⁻⁶ |
| 31 | Coal Burning Electric Plant Bottom Ash | | 0.578 | 0.076 | 0.025 | 4.1x10 ⁻³ |
| 32 | Municipal Incinerator Fly Ash | | 0.450 | 0.116 | 0.049 | 1.0x10 ⁻³ |
| 33 | Fine Copper Slag | | 0.375 | 0.055 | 0.020 | 4.1x10 ⁻³ |
| 34 | Drainage Net (0.6 cm) | | 0.850 | 0.010 | 0.005 | 3.3x10 ⁺¹ |

* Moderately Compacted (Continued)

TABLE 4 (continued) DEFAULT SOIL, WASTE, AND GEOSYNTHETIC CHARACTERISTICS

| Classification | | Total Porosity | Field Capacity | Wilting Point | Saturated Hydraulic Conductivity |
|----------------|---|----------------|----------------|---------------|----------------------------------|
| HELP | Geomembrane Material | vol/vol | vol/vol | vol/vol | cm/sec |
| 35 | High Density Polyethylene (HDPE) | | | | 2.0×10^{-12} |
| 36 | Low Density Polyethylene (LDPE) | | | | 4.0×10^{-12} |
| 37 | Polyvinyl Chloride (PVC) | | | | 2.0×10^{-12} |
| 38 | Butyl Rubber | | | | 1.0×10^{-12} |
| 39 | Chlorinated Polyethylene (CPE) | | | | 4.0×10^{-12} |
| 40 | Hypalon or Chlorosulfonated Polyethylene (CSPE) | | | | 3.0×10^{-12} |
| 41 | Ethylene Propylene Diene Monomer (EPDM) | | | | 2.0×10^{-12} |
| 42 | Neoprene | | | | 3.0×10^{-12} |

(concluded)

user-defined soil option accepts non-default soil characteristics for layers assigned soil type numbers greater than 42. This is especially convenient for specifying characteristics of waste layers. User-specified soil characteristics can be assigned any soil type number greater than 42.

When a default soil type is used to describe the top soil layer, the program adjusts the saturated hydraulic conductivities of the soils in the top half of the evaporative zone for the effects of root channels. The saturated hydraulic conductivity value is multiplied by an empirical factor that is computed as a function of the user-specified maximum leaf area index. Example values of this factor are 1.0 for a maximum LAI of 0 (bare ground), 1.8 for a maximum LAI of 1 (poor stand of grass), 3.0 for a maximum LAI of 2 (fair stand of grass), 4.2 for a maximum LAI of 3.3 (good stand of grass) and 5.0 for a maximum LAI of 5 (excellent stand of grass).

The manual option requires values for porosity, field capacity, wilting point, and saturated hydraulic conductivity. These and related soil properties are defined below.

Soil Water Storage (Volumetric Content) the ratio of the volume of water in a soil to the total volume occupied by the soil, water and voids

Total Porosity the soil water storage/volumetric content at saturation (fraction of total volume)

APPENDIX H

ATTACHMENT 2

WESTERN REGIONAL CLIMATE CENTER DATA

Source Western Regional Climate Center
<http://www.wrcc.dri.edu/cgi-bin/cliRECtM.pl?ut2696>

FAIRFIELD, UTAH (422696)

Period of Record Monthly Climate Summary

Period of Record 1/1/1911 to 12/31/2009

| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Annual |
|----------------------------------|------|------|------|------|------|------|------|------|------|------|------|------|--------|
| Average Max Temperature (F) | 38.3 | 43.6 | 53.1 | 62.3 | 71.9 | 81.7 | 89.4 | 87.7 | 79.2 | 66.5 | 50.9 | 39.4 | 63.7 |
| Average Mm Temperature (F) | 11.8 | 16.8 | 23.9 | 29.5 | 36.8 | 43.8 | 50.8 | 49.4 | 39.6 | 28.9 | 20.2 | 12.9 | 30.4 |
| Average Total Precipitation (in) | 1.09 | 1.00 | 1.09 | 1.02 | 1.17 | 0.74 | 0.92 | 0.94 | 0.92 | 1.10 | 0.89 | 0.98 | 11.87 |
| Average Total Snowfall (in) | 9.1 | 6.7 | 4.5 | 1.8 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.9 | 4.0 | 8.4 | 35.7 |
| Average Snow Depth (in) | 3 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 1 |

Percent of possible observations for period of record

Max Temp 91% Mm Temp 91.2% Precipitation 93.3% Snowfall 91.1% Snow Depth 88.8%

Check [Station Metadata](#) or [Metadata graphics](#) for more detail about data completeness

Western Regional Climate Center wrcc@dri.edu

Source Western Regional Climate Center
http://www.wrcc.dri.edu/htmlfiles/ut/ut_avg.html

UTAH

MONTHLY AVERAGE TEMPERATURES (F)

| | PERIOD OF RECORD | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC | YEAR |
|-------------------------|---------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|
| ALLEN S RANCH | 1962-2001 | 24 9 | 30 1 | 37 3 | 45 5 | 54 9 | 63 6 | 71 0 | 68 5 | 59 4 | 47 9 | 35 5 | 26 2 | 47 1 |
| ALPINE | 1948-2007 | 29 0 | 33 0 | 41 2 | 48 8 | 56 9 | 65 7 | 73 4 | 71 5 | 62 6 | 51 0 | 33 6 | 30 3 | 50 2 |
| ALTA | 1948-2007 | 21 6 | 22 8 | 25 9 | 32 6 | 42 5 | 52 3 | 60 4 | 59 2 | 50 5 | 39 8 | 28 1 | 22 8 | 38 2 |
| ALTAMONT | 1953-2007 | 19 4 | 24 3 | 34 0 | 43 1 | 52 3 | 60 8 | 68 0 | 66 0 | 57 3 | 46 0 | 32 3 | 21 7 | 43 8 |
| ALTON | 1928-2007 | 27 3 | 29 8 | 34 8 | 42 8 | 51 0 | 59 4 | 66 2 | 64 7 | 57 8 | 48 0 | 36 5 | 29 3 | 45 5 |
| ANETH PLANT | 1959-2007 | 29 8 | 38 6 | 47 0 | 54 5 | 64 3 | 73 5 | 79 9 | 78 6 | 68 9 | 55 9 | 42 7 | 32 1 | 55 5 |
| ANGLE | 1981-2007 | 23 9 | 29 5 | 36 7 | 43 0 | 51 8 | 59 6 | 66 1 | 64 6 | 55 1 | 45 5 | 33 9 | 25 2 | 44 7 |
| ANTELOPE ISLAND | 1952-1972 | 28 6 | 33 8 | 40 8 | 48 8 | 59 2 | 68 3 | 78 4 | 76 3 | 64 9 | 53 1 | 39 4 | 30 0 | 51 8 |
| ARCHES NATL PARK HQ | 1980-2007 | 31 9 | 38 8 | 48 7 | 56 5 | 66 5 | 76 7 | 83 2 | 80 9 | 71 0 | 57 5 | 43 5 | 33 2 | 57 4 |
| BEAR RIVER BAY | 1969-1996 | 26 1 | 31 3 | 41 7 | 50 0 | 59 6 | 70 2 | 77 3 | 75 4 | 64 4 | 52 4 | 38 7 | 29 1 | 51 3 |
| BEAR RIVER REFUGE | 1948-1984 | 24 4 | 29 5 | 39 7 | 49 3 | 59 2 | 67 7 | 75 5 | 73 3 | 63 9 | 52 0 | 38 8 | 28 7 | 50 2 |
| BEAVER | 1889-1990 | 27 5 | 31 6 | 37 7 | 45 4 | 53 5 | 62 0 | 69 1 | 67 4 | 59 2 | 48 5 | 37 0 | 29 3 | 47 4 |
| BEAVER CANYON P H | 1948-2007 | 29 1 | 30 3 | 36 4 | 42 3 | 53 2 | 61 4 | 68 2 | 65 7 | 58 5 | 47 6 | 37 4 | 28 2 | 46 5 |
| BIG WATER | 1986-2007 | 35 4 | 41 4 | 50 0 | 58 5 | 67 4 | 77 2 | 82 9 | 80 3 | 71 6 | 59 4 | 45 3 | 35 0 | 58 7 |
| BINGHAM CANYON | 1948-1974 | 27 6 | 30 6 | 35 8 | 44 0 | 54 5 | 63 2 | 72 0 | 70 0 | 61 7 | 50 3 | 37 4 | 29 3 | 48 0 |
| BINGHAM CANYON 2 NE | 1974-1985 | 27 0 | 31 9 | 37 5 | 45 9 | 54 9 | 66 0 | 74 9 | 72 6 | 64 4 | 50 8 | 38 0 | 30 6 | 49 6 |
| BIRDSEYE | 1948-1992 | 20 4 | 25 7 | 34 0 | 41 7 | 50 5 | 58 5 | 65 6 | 63 9 | 54 7 | 45 4 | 33 6 | 21 9 | 43 0 |
| BLACK ROCK | 1951-2007 | 27 9 | 33 6 | 41 1 | 48 5 | 57 0 | 65 6 | 73 2 | 71 2 | 61 8 | 50 2 | 37 6 | 28 7 | 49 7 |
| BLANDING | 1904-2007 | 28 2 | 33 6 | 40 3 | 48 3 | 57 3 | 67 1 | 73 3 | 71 2 | 63 2 | 52 0 | 39 1 | 30 2 | 50 3 |
| BLOWHARD MTN RADAR | 1964-2006 | 20 8 | 21 1 | 24 5 | 29 7 | 38 8 | 49 1 | 55 8 | 54 1 | 47 2 | 37 9 | 27 1 | 21 4 | 35 6 |
| BLUFF | 1928-2007 | 30 5 | 37 8 | 45 9 | 54 5 | 63 6 | 72 5 | 79 1 | 76 9 | 67 9 | 54 9 | 41 0 | 31 7 | 54 7 |
| BONANZA | 1948-1993 | 18 8 | 25 3 | 37 5 | 48 6 | 57 9 | 67 8 | 74 6 | 72 2 | 63 8 | 51 0 | 35 9 | 23 7 | 48 1 |
| BOUNTIFUL-VAL VERDA | 1981-2007 | 29 6 | 33 3 | 42 7 | 49 8 | 58 8 | 68 1 | 75 6 | 75 0 | 64 4 | 52 5 | 39 6 | 30 8 | 51 8 |
| BOULDER | 1954-2007 | 28 4 | 32 5 | 39 0 | 46 2 | 55 4 | 65 1 | 71 6 | 69 2 | 61 7 | 51 1 | 38 0 | 29 9 | 49 0 |
| BRIAN HEAD | 1991-2007 | 19 6 | 21 0 | 25 8 | 31 4 | 40 2 | 50 0 | 56 0 | 55 1 | 46 9 | 35 8 | 25 1 | 19 1 | 35 5 |
| BRIGHAM CITY | 1948-1974 | 27 4 | 32 8 | 40 0 | 49 2 | 59 6 | 67 9 | 77 4 | 74 9 | 64 5 | 52 8 | 39 3 | 29 9 | 51 3 |
| BRIGHAM CITY WASTE PLT | 1974-2007 | 26 6 | 31 6 | 41 6 | 49 0 | 57 5 | 66 3 | 73 8 | 71 9 | 62 8 | 50 8 | 37 7 | 28 5 | 49 8 |
| BRYCE CANYON FAA AIRPOR | 1948-1983 | 19 6 | 23 2 | 28 8 | 37 4 | 46 2 | 54 3 | 62 0 | 60 0 | 52 8 | 42 9 | 30 4 | 22 0 | 40 0 |
| BRYCE CANYON NAT L PRK | 1971-1978 | 19 0 | 22 8 | 29 6 | 35 6 | 45 2 | 55 2 | 61 0 | 58 3 | 50 9 | 40 5 | 29 2 | 20 8 | 39 0 |
| BRYCE CANYON NAT L PRK | 1948-1959 | 21 2 | 23 7 | 29 3 | 38 9 | 46 5 | 55 9 | 62 8 | 60 8 | 54 3 | 43 3 | 31 0 | 24 5 | 41 0 |
| BRYCE CANYON NATL PK HD | 1959-2007 | 22 6 | 25 2 | 31 0 | 38 3 | 47 4 | 56 5 | 63 1 | 60 9 | 53 0 | 43 0 | 31 1 | 23 6 | 41 3 |
| BULLFROG BASIN | 1967-2007 | 35 5 | 41 3 | 49 7 | 57 4 | 68 3 | 78 5 | 85 2 | 82 3 | 73 2 | 60 2 | 46 7 | 36 6 | 59 6 |
| CALLAO | 1948-2007 | 27 1 | 32 9 | 41 5 | 48 8 | 57 6 | 66 1 | 73 9 | 72 1 | 61 9 | 49 9 | 37 5 | 28 0 | 49 8 |
| CALLISTER RANCH | 1967-1984 | 27 6 | 33 7 | 40 7 | 47 1 | 57 0 | 67 2 | 75 3 | 74 2 | 63 7 | 50 4 | 38 4 | 29 4 | 50 4 |
| CANYONLANDS THE NECK | 1965-2007 | 28 9 | 34 8 | 42 9 | 50 7 | 61 2 | 72 0 | 78 2 | 75 7 | 66 6 | 53 8 | 39 9 | 29 8 | 52 9 |
| CANYONLANDS THE NEEDLE | 1965-2007 | 28 9 | 35 9 | 44 5 | 52 0 | 62 2 | 72 2 | 78 7 | 76 5 | 66 8 | 53 9 | 40 6 | 30 2 | 53 5 |
| CAPITOL REEF NATL PARK | 1967-2007 | 30 1 | 36 2 | 45 0 | 52 4 | 62 1 | 72 0 | 78 0 | 75 5 | 67 3 | 55 2 | 40 8 | 31 3 | 53 8 |
| CASTLE DALE | 1928-2007 | 21 8 | 28 9 | 38 5 | 46 7 | 55 9 | 64 9 | 71 2 | 68 9 | 60 2 | 48 9 | 35 1 | 25 1 | 47 2 |
| CASTLE VALLEY INST | 1978-2007 | 30 1 | 36 5 | 45 7 | 54 0 | 63 3 | 73 4 | 79 2 | 76 5 | 67 3 | 55 2 | 41 3 | 31 1 | 54 5 |
| CEDAR CITY 5 E | 1983-2006 | 30 8 | 33 4 | 39 8 | 47 0 | 55 5 | 64 1 | 70 3 | 69 0 | 61 6 | 51 3 | 39 2 | 30 4 | 49 4 |
| CEDAR CITY FAA AIRPORT | 1948-2007 | 29 7 | 34 1 | 40 2 | 47 6 | 56 6 | 66 5 | 73 9 | 72 0 | 63 4 | 51 5 | 38 9 | 30 6 | 50 4 |
| CEDAR CITY POWERHOUSE | 1928-1961 | 28 8 | 33 0 | 40 0 | 48 7 | 57 0 | 66 5 | 73 5 | 71 7 | 64 1 | 52 2 | 38 9 | 32 2 | 50 5 |
| CEDAR CITY STEAM PLANT | 1961-1983 | 31 1 | 35 6 | 39 2 | 46 6 | 56 5 | 66 7 | 74 3 | 72 0 | 64 3 | 53 3 | 41 1 | 32 6 | 51 1 |
| CEDAR POINT | 1957-2007 | 26 1 | 29 8 | 36 3 | 44 4 | 54 0 | 64 0 | 70 2 | 67 9 | 59 8 | 48 7 | 36 1 | 27 8 | 47 1 |
| CHURCH WELLS | 1975-1986 | 32 5 | 38 3 | 46 1 | 54 7 | 63 1 | 74 7 | 80 9 | 78 4 | 68 2 | 56 7 | 43 0 | 34 1 | 55 9 |
| CIRCLEVILLE | 1948-2006 | 28 0 | 32 1 | 38 1 | 44 9 | 54 3 | 63 4 | 70 4 | 68 1 | 59 6 | 48 6 | 36 9 | 28 8 | 47 8 |
| CISCO | 1952-1967 | 23 0 | 31 7 | 40 1 | 51 1 | 61 9 | 71 8 | 79 7 | 76 3 | 66 4 | 53 9 | 38 0 | 26 4 | 51 7 |
| CITY CREEK WATER PLANT | 1955-2007 | 28 4 | 31 0 | 40 0 | 47 7 | 56 4 | 64 8 | 74 2 | 70 9 | 61 3 | 50 1 | 37 3 | 29 7 | 49 3 |
| CLEAR CREEK | 1948-1967 | 18 9 | 21 1 | 25 5 | 34 8 | 43 0 | 52 1 | 59 3 | 57 4 | 50 3 | 41 7 | 29 3 | 21 6 | 37 9 |
| CLEAR LAKE REFUGE | 1963-1984 | 25 8 | 32 6 | 39 6 | 46 9 | 57 1 | 66 9 | 75 6 | 73 0 | 62 8 | 50 3 | 37 7 | 27 3 | 49 6 |
| COALVILLE | 1948-2007 | 24 6 | 28 2 | 36 7 | 44 1 | 52 4 | 59 8 | 66 4 | 64 8 | 56 6 | 45 9 | 34 8 | 26 2 | 45 1 |
| COALVILLE 13 E | 1974-2007 | 22 8 | 24 4 | 31 9 | 40 6 | 48 6 | 56 5 | 64 0 | 62 0 | 53 9 | 43 8 | 31 5 | 24 1 | 42 0 |
| CORINNE | 1871-2006 | 24 6 | 30 1 | 39 0 | 48 2 | 57 0 | 65 8 | 74 1 | 72 4 | 62 1 | 50 2 | 37 2 | 27 5 | 49 0 |
| COTTONWOOD WEIR | 1948-2007 | 30 7 | 35 8 | 43 1 | 50 9 | 60 4 | 70 0 | 79 0 | 77 3 | 67 6 | 55 1 | 41 1 | 32 0 | 53 6 |
| COVE FORT | 1948-1980 | 27 4 | 30 7 | 35 9 | 43 8 | 53 8 | 63 1 | 72 1 | 70 0 | 61 3 | 49 5 | 36 9 | 28 9 | 47 8 |
| CUTLER DAM UTAH P&L CO | 1980-2007 | 25 6 | 29 7 | 41 5 | 50 3 | 58 7 | 67 4 | 75 8 | 74 3 | 53 7 | 51 6 | 38 1 | 26 9 | 50 3 |
| DEER CREEK DAM | 1948-2007 | 20 9 | 24 3 | 33 6 | 42 8 | 51 3 | 59 2 | 66 8 | 65 2 | 56 6 | 46 2 | 34 3 | 25 0 | 43 8 |
| DELTA | 1938-2007 | 25 9 | 32 3 | 40 4 | 48 6 | 58 0 | 67 1 | 75 7 | 73 6 | 53 5 | 51 1 | 37 0 | 27 8 | 50 1 |
| DESERET | 1891-2007 | 25 8 | 32 1 | 40 5 | 48 3 | 57 1 | 66 0 | 74 0 | 72 0 | 62 0 | 50 0 | 37 1 | 27 3 | 49 4 |
| DESERT EXP RANGE | 1950-1984 | 26 6 | 32 9 | 38 6 | 46 4 | 55 8 | 65 7 | 73 7 | 71 3 | 62 2 | 50 2 | 37 0 | 28 1 | 49 0 |
| DEWEY | 1967-2004 | 26 9 | 35 2 | 45 8 | 53 8 | 63 4 | 73 0 | 79 7 | 77 6 | 67 3 | 54 0 | 40 0 | 29 9 | 53 9 |
| DINOSAUR NM QUARRY AREA | 1958-2007 | 17 9 | 25 5 | 39 0 | 49 1 | 59 0 | 68 2 | 75 2 | 72 7 | 62 8 | 49 8 | 35 4 | 22 6 | 48 1 |
| DRAPER POINT OF THE MTN | 1985-2007 | 32 0 | 36 2 | 45 5 | 52 2 | 61 4 | 71 2 | 78 2 | 76 8 | 67 0 | 54 7 | 41 4 | 31 8 | 54 0 |
| DUCHESNE | 1906-2007 | 17 9 | 24 6 | 36 4 | 46 2 | 55 0 | 63 1 | 69 8 | 67 8 | 58 9 | 47 3 | 33 1 | 21 4 | 45 1 |
| DUGWAY | 1950-2007 | 27 2 | 33 8 | 41 3 | 49 4 | 59 0 | 69 1 | 78 0 | 75 6 | 64 5 | 51 5 | 38 1 | 28 7 | 51 3 |
| ECHO DAM | 1948-2007 | 22 8 | 26 7 | 35 4 | 43 9 | 52 5 | 60 5 | 68 3 | 66 8 | 57 8 | 47 2 | 34 2 | 25 0 | 45 1 |
| ELBERTA | 1928-1992 | 26 4 | 32 2 | 40 2 | 49 1 | 57 5 | 66 9 | 75 1 | 73 2 | 63 8 | 51 6 | 38 0 | 29 1 | 50 3 |
| ELECTRIC LAKE U P & L | 1980-2007 | 13 9 | 16 2 | 23 1 | 31 0 | 41 7 | 50 7 | 57 2 | 55 5 | 47 2 | 36 5 | 24 4 | 14 9 | 34 4 |
| EMERY | 1901-1978 | 24 1 | 29 1 | 36 4 | 44 6 | 53 3 | 61 5 | 67 9 | 66 0 | 58 2 | 47 9 | 35 9 | 26 6 | 46 0 |
| EMERY 15 SW | 1979-1986 | 23 1 | 23 1 | 28 9 | 36 7 | 45 8 | 55 9 | 62 3 | 60 7 | 53 2 | 40 0 | 28 6 | 23 3 | 40 1 |
| ENTERPRISE BERYL JCT | 1948-2006 | 27 8 | 32 9 | 39 2 | 45 7 | 54 9 | 63 2 | 70 3 | 68 7 | 59 8 | 49 0 | 36 5 | 28 1 | 48 0 |
| EPHRAIM SORENSSENS FLD | 1949-2007 | 24 7 | 30 1 | 38 0 | 45 6 | 54 6 | 64 1 | 71 8 | 69 7 | 60 6 | 49 5 | 36 5 | 26 2 | 47 6 |
| ESCALANTE | 1901-2007 | 27 4 | 33 0 | 40 4 | 48 0 | 56 5 | 65 5 | 71 5 | 69 2 | 61 4 | 51 0 | 38 5 | 29 1 | 49 3 |
| ESKDALE | 1966-2007 | 28 3 | 34 0 | 42 3 | 49 1 | 58 4 | 67 7 | 75 2 | 73 1 | 62 9 | 51 0 | 38 2 | 28 7 | 50 8 |
| FAIRFIELD | 1950-2007 | 25 3 | 30 2 | 38 6 | 45 9 | 54 4 | 62 8 | 70 1 | 68 5 | 59 4 | 47 8 | 35 4 | 26 4 | 47 1 |
| FARMINGTON | 1948-2007 | 28 5 | 34 0 | 40 5 | 50 3 | 59 2 | 67 5 | 75 7 | 74 5 | 65 5 | 54 0 | 39 8 | 31 2 | 51 7 |
| FARMINGTON USU FLD STN | 1948-2007 | 29 6 | 34 2 | 42 6 | 50 1 | 59 0 | 68 1 | 76 5 | 74 5 | 64 7 | 52 4 | 39 9 | 30 4 | 51 8 |
| FERRON | 1948-2007 | 23 9 | 29 6 | 38 5 | 47 3 | 56 9 | 66 3 | 73 0 | 70 4 | 62 1 | 50 5 | 36 4 | 26 2 | 48 4 |

APPENDIX H

**ATTACHMENT 3
HELP PROGRAM OUTPUT**


```

*****
*****
**
**
**          HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE          **
**          HELP MODEL VERSION 3 07 (1 NOVEMBER 1997)              **
**          DEVELOPED BY ENVIRONMENTAL LABORATORY                  **
**          USAE WATERWAYS EXPERIMENT STATION                    **
**          FOR USEPA RISK REDUCTION ENGINEERING LABORATORY       **
**
**
*****
*****

```

```

PRECIPITATION DATA FILE      C \HELP\IRL\s2\DATA4 D4
TEMPERATURE DATA FILE       C \HELP\IRL\s2\DATA7 D7
SOLAR RADIATION DATA FILE   C \HELP\IRL\s2\DATA13 D13
EVAPOTRANSPIRATION DATA     C \HELP\IRL\s2\DATA11 D11
SOIL AND DESIGN DATA FILE   C \HELP\IRL\s2\DATA10 D10
OUTPUT DATA FILE            C \HELP\IRL\s2\out OUT

```

TIME 15 19 DATE 5/21/2010

```

*****
TITLE Intermountain Regional Landfill Scenario 2
*****

```

NOTE INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE SPECIFIED BY THE USER

LAYER 1

```

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 6
THICKNESS = 12 00 INCHES
POROSITY = 0 4530 VOL/VOL
FIELD CAPACITY = 0 1900 VOL/VOL
WILTING POINT = 0 0850 VOL/VOL
INITIAL SOIL WATER CONTENT = 0 1900 VOL/VOL
EFFECTIVE SAT HYD COND = 0 720000011000E-03 CM/SEC
NOTE SATURATED HYDRAULIC CONDUCTIVITY IS MULTIPLIED BY 2 49
FOR ROOT CHANNELS IN TOP HALF OF EVAPORATIVE ZONE

```

LAYER 2

```

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 18
THICKNESS = 1200 00 INCHES
POROSITY = 0 6710 VOL/VOL
FIELD CAPACITY = 0 2920 VOL/VOL
WILTING POINT = 0 0770 VOL/VOL
INITIAL SOIL WATER CONTENT = 0 1100 VOL/VOL
EFFECTIVE SAT HYD COND = 0 100000005000E-02 CM/SEC

```


LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 6

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 24 00 | INCHES |
| POROSITY | = | 0 4530 | VOL/VOL |
| FIELD CAPACITY | = | 0 1900 | VOL/VOL |
| WILTING POINT | = | 0 0850 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0 1900 | VOL/VOL |
| EFFECTIVE SAT HYD COND | = | 0 720000011000E-03 | CM/SEC |
| SLOPE | = | 1 60 | PERCENT |
| DRAINAGE LENGTH | = | 2500 0 | FEET |

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

| | | | |
|----------------------------|---|--------------------|------------|
| THICKNESS | = | 0 06 | INCHES |
| POROSITY | = | 0 0000 | VOL/VOL |
| FIELD CAPACITY | = | 0 0000 | VOL/VOL |
| WILTING POINT | = | 0 0000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0 0000 | VOL/VOL |
| EFFECTIVE SAT HYD COND | = | 0 199999996000E-12 | CM/SEC |
| FML PINHOLE DENSITY | = | 2 00 | HOLES/ACRE |
| FML INSTALLATION DEFECTS | = | 4 00 | HOLES/ACRE |
| FML PLACEMENT QUALITY | = | 3 - | GOOD |

LAYER 5

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 17

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 0 25 | INCHES |
| POROSITY | = | 0 7500 | VOL/VOL |
| FIELD CAPACITY | = | 0 7470 | VOL/VOL |
| WILTING POINT | = | 0 4000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0 7500 | VOL/VOL |
| EFFECTIVE SAT HYD COND | = | 0 300000003000E-08 | CM/SEC |

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED

| | | | |
|------------------------------------|---|---------|-------------|
| SCS RUNOFF CURVE NUMBER | = | 77 00 | |
| FRACTION OF AREA ALLOWING RUNOFF | = | 0 0 | PERCENT |
| AREA PROJECTED ON HORIZONTAL PLANE | = | 1 000 | ACRES |
| EVAPORATIVE ZONE DEPTH | = | 16 0 | INCHES |
| INITIAL WATER IN EVAPORATIVE ZONE | = | 2 720 | INCHES |
| UPPER LIMIT OF EVAPORATIVE STORAGE | = | 8 120 | INCHES |
| LOWER LIMIT OF EVAPORATIVE STORAGE | = | 1 328 | INCHES |
| INITIAL SNOW WATER | = | 0 000 | INCHES |
| INITIAL WATER IN LAYER MATERIALS | = | 139 027 | INCHES |
| TOTAL INITIAL WATER | = | 139 027 | INCHES |
| TOTAL SUBSURFACE INFLOW | = | 0 00 | INCHES/YEAR |

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40 76 DEGREES
 MAXIMUM LEAF AREA INDEX = 1 60
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16 0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8 80 MPH
 AVERAGE 1ST QDARTER RELATIVE HUMIDITY = 67 00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48 00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39 00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65 00 %

NOTE PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 1 09 | 1 00 | 1 09 | 1 02 | 1 17 | 0 74 |
| 0 92 | 0 94 | 0 92 | 1 10 | 0 89 | 0 98 |

NOTE TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 25 30 | 30 20 | 38 60 | 45 90 | 54 40 | 62 80 |
| 70 10 | 68 50 | 59 40 | 47 80 | 35 40 | 26 40 |

NOTE SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH
AND STATION LATITUDE = 40 76 DEGREES

ANNUAL TOTALS FOR YEAR 1

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| | ----- | ----- | ----- |
| PRECIPITATION | 9 97 | 36191 109 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 10 184 | 36968 621 | 102 15 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|---------|------------|-------|
| CHANGE IN WATER STORAGE | -0 214 | -777 513 | -2 15 |
| SOIL WATER AT START OF YEAR | 139 027 | 504669 687 | |
| SOIL WATER AT END OF YEAR | 138 698 | 503474 125 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 115 | 418 067 | 1 16 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 002 | 0 00 |

ANNUAL TOTALS FOR YEAR 2

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 12 61 | 45774 297 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 503 | 45387 187 | 99 15 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 107 | 387 129 | 0 85 |
| SOIL WATER AT START OF YEAR | 138 698 | 503474 125 | |
| SOIL WATER AT END OF YEAR | 138 920 | 504279 312 | |
| SNOW WATER AT START OF YEAR | 0 115 | 418 067 | 0 91 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 022 | 0 00 |

ANNUAL TOTALS FOR YEAR 3

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 7 95 | 28858 504 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 7 906 | 28697 498 | 99 44 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|---------|------------|------|
| CHANGE IN WATER STORAGE | 0 044 | 161 027 | 0 56 |
| SOIL WATER AT START OF YEAR | 138 920 | 504279 312 | |
| SOIL WATER AT END OF YEAR | 138 304 | 502043 969 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 660 | 2396 377 | 8 30 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 021 | 0 00 |

ANNUAL TOTALS FOR YEAR 4

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 13 95 | 50638 508 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 358 | 44860 863 | 88 59 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 592 | 5777 574 | 11 41 |
| SOIL WATER AT START OF YEAR | 138 304 | 502043 969 | |
| SOIL WATER AT END OF YEAR | 140 328 | 509390 156 | |
| SNOW WATER AT START OF YEAR | 0 660 | 2396 377 | 4 73 |
| SNOW WATER AT END OF YEAR | 0 228 | 827 766 | 1 63 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 067 | 0 00 |

ANNUAL TOTALS FOR YEAR 5

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 9 43 | 34230 898 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 326 | 33854 625 | 98 90 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 104 | 376 289 | 1 10 |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT START OF YEAR | 140 328 | 509390 156 | |
| SOIL WATER AT END OF YEAR | 140 552 | 510203 531 | |
| SNOW WATER AT START OF YEAR | 0 228 | 827 766 | 2 42 |
| SNOW WATER AT END OF YEAR | 0 108 | 390 661 | 1 14 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 014 | 0 00 |

ANNUAL TOTALS FOR YEAR 6

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 14 03 | 50928 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 918 | 46893 496 | 92 08 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 112 | 4035 456 | 7 92 |
| SOIL WATER AT START OF YEAR | 140 552 | 510203 531 | |
| SOIL WATER AT END OF YEAR | 141 185 | 512500 719 | |
| SNOW WATER AT START OF YEAR | 0 108 | 390 661 | 0 77 |
| SNOW WATER AT END OF YEAR | 0 586 | 2128 952 | 4 18 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 047 | 0 00 |

ANNUAL TOTALS FOR YEAR 7

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 69 | 42434 707 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 584 | 45681 336 | 107 65 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 894 | -3246 695 | -7 65 |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT START OF YEAR | 141 185 | 512500 719 | |
| SOIL WATER AT END OF YEAR | 140 496 | 510000 719 | |
| SNOW WATER AT START OF YEAR | 0 586 | 2128 952 | 5 02 |
| SNOW WATER AT END OF YEAR | 0 381 | 1382 258 | 3 26 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 066 | 0 00 |

ANNUAL TOTALS FOR YEAR 8

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 8 61 | 31254 299 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 8 556 | 31060 027 | 99 38 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 054 | 194 333 | 0 62 |
| SOIL WATER AT START OF YEAR | 140 496 | 510000 719 | |
| SOIL WATER AT END OF YEAR | 140 816 | 511163 281 | |
| SNOW WATER AT START OF YEAR | 0 381 | 1382 258 | 4 42 |
| SNOW WATER AT END OF YEAR | 0 114 | 414 023 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 062 | 0 00 |

ANNUAL TOTALS FOR YEAR 9

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 12 75 | 46282 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 099 | 43918 012 | 94 89 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 651 | 2364 476 | 5 11 |
| SOIL WATER AT START OF YEAR | 140 816 | 511163 281 | |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT END OF YEAR | 141 582 | 513941 781 | |
| SNOW WATER AT START OF YEAR | 0 114 | 414 023 | 0 89 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 011 | 0 00 |

ANNUAL TOTALS FOR YEAR 10

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 11 38 | 41309 402 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 192 | 40626 805 | 98 35 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 188 | 682 588 | 1 65 |
| SOIL WATER AT START OF YEAR | 141 582 | 513941 781 | |
| SOIL WATER AT END OF YEAR | 141 497 | 513632 750 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 273 | 991 606 | 2 40 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 010 | 0 00 |

ANNUAL TOTALS FOR YEAR 11

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 12 56 | 45592 812 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 902 | 43204 625 | 94 76 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 658 | 2388 200 | 5 24 |
| SOIL WATER AT START OF YEAR | 141 497 | 513632 750 | |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT END OF YEAR | 142 428 | 517012 562 | |
| SNOW WATER AT START OF YEAR | 0 273 | 991 606 | 2 17 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 013 | 0 00 |

ANNUAL TOTALS FOR YEAR 12

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 21 | 37062 305 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 10 317 | 37452 348 | 101 05 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 107 | -390 066 | -1 05 |
| SOIL WATER AT START OF YEAR | 142 428 | 517012 562 | |
| SOIL WATER AT END OF YEAR | 142 185 | 516131 531 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 135 | 490 958 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 020 | 0 00 |

ANNUAL TOTALS FOR YEAR 13

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 9 17 | 33287 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 8 294 | 30108 729 | 90 45 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 876 | 3178 381 | 9 55 |
| SOIL WATER AT START OF YEAR | 142 185 | 516131 531 | |
| SOIL WATER AT END OF YEAR | 143 103 | 519465 312 | |

| | | | |
|-----------------------------|--------|---------|------|
| SNOW WATER AT START OF YEAR | 0 135 | 490 958 | 1 47 |
| SNOW WATER AT END OF YEAR | 0 092 | 335 562 | 1 01 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 005 | 0 00 |

ANNUAL TOTALS FOR YEAR 14

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 57 | 38369 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 409 | 34154 027 | 89 01 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 161 | 4215 101 | 10 99 |
| SOIL WATER AT START OF YEAR | 143 103 | 519465 312 | |
| SOIL WATER AT END OF YEAR | 143 759 | 521844 562 | |
| SNOW WATER AT START OF YEAR | 0 092 | 335 562 | 0 87 |
| SNOW WATER AT END OF YEAR | 0 598 | 2171 410 | 5 66 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 015 | 0 00 |

ANNUAL TOTALS FOR YEAR 15

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 35 | 37570 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 314 | 33809 922 | 89 99 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 036 | 3760 573 | 10 01 |
| SOIL WATER AT START OF YEAR | 143 759 | 521844 562 | |
| SOIL WATER AT END OF YEAR | 145 393 | 527776 562 | |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT START OF YEAR | 0 598 | 2171 410 | 5 78 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 007 | 0 00 |

ANNUAL TOTALS FOR YEAR 16

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 11 13 | 40401 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 001 | 39934 230 | 98 84 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 129 | 467 708 | 1 16 |
| SOIL WATER AT START OF YEAR | 145 393 | 527776 562 | |
| SOIL WATER AT END OF YEAR | 145 522 | 528244 250 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 031 | 0 00 |

ANNUAL TOTALS FOR YEAR 17

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 60 | 38478 008 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 377 | 34037 777 | 88 46 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 223 | 4440 155 | 11 54 |
| SOIL WATER AT START OF YEAR | 145 522 | 528244 250 | |
| SOIL WATER AT END OF YEAR | 146 362 | 531294 375 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 383 | 1390 027 | 3 61 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 074 | 0 00 |

ANNUAL TOTALS FOR YEAR 18

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 11 99 | 43523 711 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 302 | 41027 914 | 94 27 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 688 | 2495 821 | 5 73 |
| SOIL WATER AT START OF YEAR | 146 362 | 531294 375 | |
| SOIL WATER AT END OF YEAR | 147 391 | 535030 375 | |
| SNOW WATER AT START OF YEAR | 0 383 | 1390 027 | 3 19 |
| SNOW WATER AT END OF YEAR | 0 041 | 149 833 | 0 34 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 027 | 0 00 |

ANNUAL TOTALS FOR YEAR 19

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 6 95 | 25228 502 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 6 331 | 22981 078 | 91 09 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 619 | 2247 439 | 8 91 |
| SOIL WATER AT START OF YEAR | 147 391 | 535030 375 | |
| SOIL WATER AT END OF YEAR | 147 602 | 535794 437 | |
| SNOW WATER AT START OF YEAR | 0 041 | 149 833 | 0 59 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 450 | 1633 231 | 6 47 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 016 | 0 00 |

ANNUAL TOTALS FOR YEAR 20

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 13 72 | 49803 602 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 057 | 43768 371 | 87 88 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 663 | 6035 281 | 12 12 |
| SOIL WATER AT START OF YEAR | 147 602 | 535794 437 | |
| SOIL WATER AT END OF YEAR | 149 239 | 541738 625 | |
| SNOW WATER AT START OF YEAR | 0 450 | 1633 231 | 3 28 |
| SNOW WATER AT END OF YEAR | 0 475 | 1724 343 | 3 46 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 052 | 0 00 |

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|--------------------|----------------|----------------|----------------|----------------|----------------|----------------|
| PRECIPITATION | | | | | | |
| TOTALS | 0 94 0 81 | 0 86 0 89 | 1 22 0 83 | 0 96 0 87 | 1 01 0 80 | 0 75 1 04 |
| STD DEVIATIONS | 0 50 0 57 | 0 46 0 89 | 0 50 0 70 | 0 44 0 61 | 0 56 0 38 | 0 52 0 46 |
| RUNOFF | | | | | | |
| TOTALS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| STD DEVIATIONS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| EVAPOTRANSPIRATION | | | | | | |

| | | | | | | |
|--------|-------|-------|-------|-------|-------|-------|
| TOTALS | 0 517 | 0 560 | 1 465 | 1 544 | 1 165 | 1 125 |
| | 0 825 | 0 857 | 0 714 | 0 505 | 0 597 | 0 573 |

| | | | | | | |
|----------------|-------|-------|-------|-------|-------|-------|
| STD DEVIATIONS | 0 205 | 0 175 | 0 380 | 0 619 | 0 568 | 0 575 |
| | 0 569 | 0 897 | 0 626 | 0 398 | 0 222 | 0 163 |

LATERAL DRAINAGE COLLECTED FROM LAYER 3

| | | | | | | |
|--------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

| | | | | | | |
|--------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

 AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|----------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

AVERAGE ANNUAL TOTALS & (STD DEVIATIONS) FOR YEARS 1 THROUGH 20

| | INCHES | CU FEET | PERCENT |
|---|--------------------|----------|---------|
| PRECIPITATION | 10 98 (1 982) | 39861 0 | 100 00 |
| RUNOFF | 0 000 (0 0000) | 0 00 | 0 000 |
| EVAPOTRANSPIRATION | 10 447 (1 8360) | 37921 37 | 95 134 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 (0 00000) | 0 000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 00000 (0 00000) | 0 000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 (0 000) | | |
| CHANGE IN WATER STORAGE | 0 534 (0 6552) | 1939 66 | 4 866 |

| PEAK DAILY VALUES FOR YEARS | 1 THROUGH 20 | |
|--|--------------|-----------|
| | (INCHES) | (CU FT) |
| PRECIPITATION | 1 27 | 4610 100 |
| RUNOFF | 0 000 | 0 0000 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 | |
| MAXIMUM HEAD ON TOP OF LAYER 4 | 0 000 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN) | 0 0 FEET | |
| SNOW WATER | 1 55 | 5618 2544 |
| MAXIMUM VEG SOIL WATER (VOL/VOL) | | 0 3003 |
| MINIMUM VEG SOIL WATER (VOL/VOL) | | 0 0830 |

*** Maximum heads are computed using McEnroe s equations ***

Reference Maximum Saturated Depth over Landfill Liner
 by Bruce M McEnroe University of Kansas
 ASCE Journal of Environmental Engineering
 Vol 119 No 2 March 1993 pp 262-270

| FINAL WATER STORAGE AT END OF YEAR 20 | | |
|---------------------------------------|----------|-----------|
| LAYER | (INCHES) | (VOL/VOL) |
| 1 | 3 0539 | 0 2545 |
| 2 | 141 4379 | 0 1179 |
| 3 | 4 5600 | 0 1900 |
| 4 | 0 0000 | 0 0000 |
| 5 | 0 1875 | 0 7500 |
| SNOW WATER | 0 475 | |

LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 6

THICKNESS = 24 00 INCHES
 POROSITY = 0 4530 VOL/VOL
 FIELD CAPACITY = 0 1900 VOL/VOL
 WILTING POINT = 0 0850 VOL/VOL
 INITIAL SOIL WATER CONTENT = 0 1900 VOL/VOL
 EFFECTIVE SAT HYD COND = 0 720000011000E-03 CM/SEC
 SLOPE = 1 60 PERCENT
 DRAINAGE LENGTH = 2500 0 FEET

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

THICKNESS = 0 06 INCHES
 POROSITY = 0 0000 VOL/VOL
 FIELD CAPACITY = 0 0000 VOL/VOL
 WILTING POINT = 0 0000 VOL/VOL
 INITIAL SOIL WATER CONTENT = 0 0000 VOL/VOL
 EFFECTIVE SAT HYD COND = 0 199999996000E-12 CM/SEC
 FML PINHOLE DENSITY = 2 00 HOLES/ACRE
 FML INSTALLATION DEFECTS = 4 00 HOLES/ACRE
 FML PLACEMENT QUALITY = 3 - GOOD

LAYER 5

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 17

THICKNESS = 0 25 INCHES
 POROSITY = 0 7500 VOL/VOL
 FIELD CAPACITY = 0 7470 VOL/VOL
 WILTING POINT = 0 4000 VOL/VOL
 INITIAL SOIL WATER CONTENT = 0 7500 VOL/VOL
 EFFECTIVE SAT HYD COND = 0 300000003000E-08 CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED

SCS RUNOFF CURVE NUMBER = 77 00
 FRACTION OF AREA ALLOWING RUNOFF = 0 0 PERCENT
 AREA PROJECTED ON HORIZONTAL PLANE = 1 000 ACRES
 EVAPORATIVE ZONE DEPTH = 16 0 INCHES
 INITIAL WATER IN EVAPORATIVE ZONE = 2 240 INCHES
 UPPER LIMIT OF EVAPORATIVE STORAGE = 9 428 INCHES
 LOWER LIMIT OF EVAPORATIVE STORAGE = 1 280 INCHES
 INITIAL SNOW WATER = 0 000 INCHES
 INITIAL WATER IN LAYER MATERIALS = 19 087 INCHES
 TOTAL INITIAL WATER = 19 087 INCHES
 TOTAL SUBSURFACE INFLOW = 0 00 INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40 76 DEGREES
 MAXIMUM LEAF AREA INDEX = 1 60
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16 0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8 80 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67 00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48 00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39 00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65 00 %

NOTE PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 1 09 | 1 00 | 1 09 | 1 02 | 1 17 | 0 74 |
| 0 92 | 0 94 | 0 92 | 1 10 | 0 89 | 0 98 |

NOTE TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 25 30 | 30 20 | 38 60 | 45 90 | 54 40 | 62 80 |
| 70 10 | 68 50 | 59 40 | 47 80 | 35 40 | 26 40 |

NOTE SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH
AND STATION LATITUDE = 40 76 DEGREES

ANNUAL TOTALS FOR YEAR 1

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| | ----- | ----- | ----- |
| PRECIPITATION | 9 97 | 36191 109 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 791 | 35540 309 | 98 20 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|--------|-----------|------|
| CHANGE IN WATER STORAGE | 0 179 | 650 786 | 1 80 |
| SOIL WATER AT START OF YEAR | 19 087 | 69287 547 | |
| SOIL WATER AT END OF YEAR | 19 152 | 69520 266 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 115 | 418 067 | 1 16 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 012 | 0 00 |

ANNUAL TOTALS FOR YEAR 2

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 12 61 | 45774 297 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 751 | 46284 473 | 101 11 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 141 | -510 152 | -1 11 |
| SOIL WATER AT START OF YEAR | 19 152 | 69520 266 | |
| SOIL WATER AT END OF YEAR | 19 126 | 69428 180 | |
| SNOW WATER AT START OF YEAR | 0 115 | 418 067 | 0 91 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 026 | 0 00 |

ANNUAL TOTALS FOR YEAR 3

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 7 95 | 28858 504 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 7 865 | 28548 961 | 98 93 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|--------|-----------|------|
| CHANGE IN WATER STORAGE | 0 085 | 309 526 | 1 07 |
| SOIL WATER AT START OF YEAR | 19 126 | 69428 180 | |
| SOIL WATER AT END OF YEAR | 18 551 | 67341 328 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 660 | 2396 377 | 8 30 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 018 | 0 00 |

ANNUAL TOTALS FOR YEAR 4

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 13 95 | 50638 508 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 516 | 45431 453 | 89 72 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 434 | 5207 050 | 10 28 |
| SOIL WATER AT START OF YEAR | 18 551 | 67341 328 | |
| SOIL WATER AT END OF YEAR | 20 418 | 74116 992 | |
| SNOW WATER AT START OF YEAR | 0 660 | 2396 377 | 4 73 |
| SNOW WATER AT END OF YEAR | 0 228 | 827 766 | 1 63 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 004 | 0 00 |

ANNUAL TOTALS FOR YEAR 5

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 9 43 | 34230 898 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 718 | 35274 770 | 103 05 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 288 | -1043 868 | -3 05 |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT START OF YEAR | 20 418 | 74116 992 | |
| SOIL WATER AT END OF YEAR | 20 251 | 73510 227 | |
| SNOW WATER AT START OF YEAR | 0 228 | 827 766 | 2 42 |
| SNOW WATER AT END OF YEAR | 0 108 | 390 661 | 1 14 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 004 | 0 00 |

ANNUAL TOTALS FOR YEAR 6

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 14 03 | 50928 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 938 | 46964 297 | 92 22 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 092 | 3964 634 | 7 78 |
| SOIL WATER AT START OF YEAR | 20 251 | 73510 227 | |
| SOIL WATER AT END OF YEAR | 20 864 | 75736 570 | |
| SNOW WATER AT START OF YEAR | 0 108 | 390 661 | 0 77 |
| SNOW WATER AT END OF YEAR | 0 586 | 2128 952 | 4 18 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 026 | 0 00 |

ANNUAL TOTALS FOR YEAR 7

| | INCHES | CD FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 69 | 42434 707 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 570 | 45629 660 | 107 53 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 880 | -3194 955 | -7 53 |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT START OF YEAR | 20 864 | 75736 570 | |
| SOIL WATER AT END OF YEAR | 20 190 | 73288 312 | |
| SNOW WATER AT START OF YEAR | 0 586 | 2128 952 | 5 02 |
| SNOW WATER AT END OF YEAR | 0 381 | 1382 258 | 3 26 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 000 | 0 00 |

ANNUAL TOTALS FOR YEAR 8

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 8 61 | 31254 299 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 8 182 | 29700 090 | 95 03 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 428 | 1554 205 | 4 97 |
| SOIL WATER AT START OF YEAR | 20 190 | 73288 312 | |
| SOIL WATER AT END OF YEAR | 20 885 | 75810 750 | |
| SNOW WATER AT START OF YEAR | 0 381 | 1382 258 | 4 42 |
| SNOW WATER AT END OF YEAR | 0 114 | 414 023 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 004 | 0 00 |

ANNUAL TOTALS FOR YEAR 9

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 12 75 | 46282 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 497 | 45364 285 | 98 02 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 253 | 918 217 | 1 98 |
| SOIL WATER AT START OF YEAR | 20 885 | 75810 750 | |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT END OF YEAR | 21 252 | 77142 992 | |
| SNOW WATER AT START OF YEAR | 0 114 | 414 023 | 0 89 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 003 | 0 00 |

ANNUAL TOTALS FOR YEAR 10

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 38 | 41309 402 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 454 | 41579 582 | 100 65 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 074 | -270 179 | -0 65 |
| SOIL WATER AT START OF YEAR | 21 252 | 77142 992 | |
| SOIL WATER AT END OF YEAR | 20 904 | 75881 203 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 273 | 991 606 | 2 40 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 000 | 0 00 |

ANNUAL TOTALS FOR YEAR 11

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 12 56 | 45592 812 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 805 | 42850 980 | 93 99 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 755 | 2741 820 | 6 01 |
| SOIL WATER AT START OF YEAR | 20 904 | 75881 203 | |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT END OF YEAR | 21 932 | 79614 633 | |
| SNOW WATER AT START OF YEAR | 0 273 | 991 606 | 2 17 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 011 | 0 00 |

ANNUAL TOTALS FOR YEAR 12

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 21 | 37062 305 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 10 571 | 38373 039 | 103 54 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 361 | -1310 734 | -3 54 |
| SOIL WATER AT START OF YEAR | 21 932 | 79614 633 | |
| SOIL WATER AT END OF YEAR | 21 436 | 77812 937 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 135 | 490 958 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 000 | 0 00 |

ANNUAL TOTALS FOR YEAR 13

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 9 17 | 33287 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 7 927 | 28774 422 | 86 44 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 243 | 4512 684 | 13 56 |
| SOIL WATER AT START OF YEAR | 21 436 | 77812 937 | |
| SOIL WATER AT END OF YEAR | 22 722 | 82481 023 | |

| | | | |
|-----------------------------|--------|---------|------|
| SNOW WATER AT START OF YEAR | 0 135 | 490 958 | 1 47 |
| SNOW WATER AT END OF YEAR | 0 092 | 335 562 | 1 01 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 009 | 0 00 |

ANNUAL TOTALS FOR YEAR 14

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 57 | 38369 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 781 | 35505 859 | 92 54 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 789 | 2863 267 | 7 46 |
| SOIL WATER AT START OF YEAR | 22 722 | 82481 023 | |
| SOIL WATER AT END OF YEAR | 23 005 | 83508 437 | |
| SNOW WATER AT START OF YEAR | 0 092 | 335 562 | 0 87 |
| SNOW WATER AT END OF YEAR | 0 598 | 2171 410 | 5 66 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 012 | 0 00 |

ANNUAL TOTALS FOR YEAR 15

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 35 | 37570 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 131 | 33147 066 | 88 23 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 219 | 4423 439 | 11 77 |
| SOIL WATER AT START OF YEAR | 23 005 | 83508 437 | |
| SOIL WATER AT END OF YEAR | 24 822 | 90103 289 | |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT START OF YEAR | 0 598 | 2171 410 | 5 78 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 003 | 0 00 |

ANNUAL TOTALS FOR YEAR 16

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 13 | 40401 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 440 | 41527 703 | 102 79 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 310 | -1125 803 | -2 79 |
| SOIL WATER AT START OF YEAR | 24 822 | 90103 289 | |
| SOIL WATER AT END OF YEAR | 24 512 | 88977 484 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 007 | 0 00 |

ANNUAL TOTALS FOR YEAR 17

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 60 | 38478 008 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 838 | 35713 051 | 92 81 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 762 | 2764 944 | 7 19 |
| SOIL WATER AT START OF YEAR | 24 512 | 88977 484 | |
| SOIL WATER AT END OF YEAR | 24 890 | 90352 398 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 383 | 1390 027 | 3 61 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 012 | 0 00 |

ANNUAL TOTALS FOR YEAR 18

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 99 | 43523 711 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 623 | 42190 238 | 96 94 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 367 | 1333 475 | 3 06 |
| SOIL WATER AT START OF YEAR | 24 890 | 90352 398 | |
| SOIL WATER AT END OF YEAR | 25 599 | 92926 070 | |
| SNOW WATER AT START OF YEAR | 0 383 | 1390 027 | 3 19 |
| SNOW WATER AT END OF YEAR | 0 041 | 149 833 | 0 34 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 002 | 0 00 |

ANNUAL TOTALS FOR YEAR 19

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 6 95 | 25228 502 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 6 739 | 24463 023 | 96 97 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 211 | 765 475 | 3 03 |
| SOIL WATER AT START OF YEAR | 25 599 | 92926 070 | |
| SOIL WATER AT END OF YEAR | 25 402 | 92208 148 | |
| SNOW WATER AT START OF YEAR | 0 041 | 149 833 | 0 59 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 450 | 1633 231 | 6 47 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 003 | 0 00 |

ANNUAL TOTALS FOR YEAR 20

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 13 72 | 49803 602 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 102 | 43931 852 | 88 21 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 618 | 5871 737 | 11 79 |
| SOIL WATER AT START OF YEAR | 25 402 | 92208 148 | |
| SOIL WATER AT END OF YEAR | 26 994 | 97988 773 | |
| SNOW WATER AT START OF YEAR | 0 450 | 1633 231 | 3 28 |
| SNOW WATER AT END OF YEAR | 0 475 | 1724 343 | 3 46 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 014 | 0 00 |

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|--------------------|----------------|----------------|----------------|----------------|----------------|----------------|
| PRECIPITATION | | | | | | |
| TOTALS | 0 94 0 81 | 0 86 0 89 | 1 22 0 83 | 0 96 0 87 | 1 01 0 80 | 0 75 1 04 |
| STD DEVIATIONS | 0 50 0 57 | 0 46 0 89 | 0 50 0 70 | 0 44 0 61 | 0 56 0 38 | 0 52 0 46 |
| RUNOFF | | | | | | |
| TOTALS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| STD DEVIATIONS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| EVAPOTRANSPIRATION | | | | | | |

| | | | | | | |
|----------------|-------|-------|-------|-------|-------|-------|
| TOTALS | 0 518 | 0 560 | 1 446 | 1 594 | 1 245 | 1 245 |
| | 0 818 | 0 820 | 0 744 | 0 474 | 0 525 | 0 572 |
| STD DEVIATIONS | 0 205 | 0 173 | 0 381 | 0 636 | 0 552 | 0 538 |
| | 0 558 | 0 885 | 0 625 | 0 342 | 0 164 | 0 163 |

LATERAL DRAINAGE COLLECTED FROM LAYER 3

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

AVERAGE ANNUAL TOTALS & (STD DEVIATIONS) FOR YEARS 1 THROUGH 20

| | INCHES | | CU FEET | PERCENT |
|---|---------|------------|----------|---------|
| PRECIPITATION | 10 98 | (1 982) | 39861 0 | 100 00 |
| RUNOFF | 0 000 | (0 0000) | 0 00 | 0 000 |
| EVAPOTRANSPIRATION | 10 562 | (1 8866) | 38339 75 | 96 184 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 | (0 00000) | 0 000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 00000 | (0 00000) | 0 000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 | (0 000) | | |
| CHANGE IN WATER STORAGE | 0 419 | (0 6780) | 1521 28 | 3 816 |

| PEAK DAILY VALUES FOR YEARS | 1 THROUGH 20 | |
|--|--------------|-----------|
| | (INCHES) | (CU FT) |
| PRECIPITATION | 1 27 | 4610 100 |
| RUNOFF | 0 000 | 0 0000 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 | |
| MAXIMUM HEAD ON TOP OF LAYER 4 | 0 000 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN) | 0 0 FEET | |
| SNOW WATER | 1 55 | 5618 2544 |
| MAXIMUM VEG SOIL WATER (VOL/VOL) | | 0 3100 |
| MINIMUM VEG SOIL WATER (VOL/VOL) | | 0 0800 |

*** Maximum heads are computed using McEnroe s equations ***

Reference Maximum Saturated Depth over Landfill Liner
 by Bruce M McEnroe University of Kansas
 ASCE Journal of Environmental Engineering
 Vol 119 No 2 March 1993 pp 262-270

| FINAL WATER STORAGE AT END OF YEAR 20 | | |
|---------------------------------------|----------|-----------|
| LAYER | (INCHES) | (VOL/VOL) |
| 1 | 1 8406 | 0 3068 |
| 2 | 20 4060 | 0 1701 |
| 3 | 4 5600 | 0 1900 |
| 4 | 0 0000 | 0 0000 |
| 5 | 0 1875 | 0 7500 |
| SNOW WATER | 0 475 | |


```

*****
*****
**
**
**
**          HYDROLOGIC EVALUATION OF LANDFILL PERFORMANCE          **
**          HELP MODEL VERSION 3 07 (1 NOVEMBER 1997)              **
**          DEVELOPED BY ENVIRONMENTAL LABORATORY                  **
**          USAE WATERWAYS EXPERIMENT STATION                    **
**          FOR USEPA RISK REDUCTION ENGINEERING LABORATORY      **
**
**
*****
*****

```

```

PRECIPITATION DATA FILE   C \HELP\IRL\s2\DATA4 D4
TEMPERATURE DATA FILE    C \HELP\IRL\s2\DATA7 D7
SOLAR RADIATION DATA FILE C \HELP\IRL\s2\DATA13 D13
EVAPOTRANSPIRATION DATA  C \HELP\IRL\s2\DATA11 D11
SOIL AND DESIGN DATA FILE C \HELP\IRL\s2\DATA10 D10
OUTPUT DATA FILE         C \HELP\IRL\s2\out OUT

```

TIME 15 19 DATE 5/21/2010

```

*****
TITLE Intermountain Regional Landfill Scenario 2
*****

```

NOTE INITIAL MOISTURE CONTENT OF THE LAYERS AND SNOW WATER WERE SPECIFIED BY THE USER

LAYER 1

```

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 6
THICKNESS           = 12 00 INCHES
POROSITY             = 0 4530 VOL/VOL
FIELD CAPACITY      = 0 1900 VOL/VOL
WILTING POINT       = 0 0850 VOL/VOL
INITIAL SOIL WATER CONTENT = 0 1900 VOL/VOL
EFFECTIVE SAT HYD COND = 0 720000011000E-03 CM/SEC
NOTE SATURATED HYDRAULIC CONDUCTIVITY IS MULTIPLIED BY 2 49
FOR ROOT CHANNELS IN TOP HALF OF EVAPORATIVE ZONE

```

LAYER 2

```

TYPE 1 - VERTICAL PERCOLATION LAYER
MATERIAL TEXTURE NUMBER 18
THICKNESS           = 1200 00 INCHES
POROSITY             = 0 6710 VOL/VOL
FIELD CAPACITY      = 0 2920 VOL/VOL
WILTING POINT       = 0 0770 VOL/VOL
INITIAL SOIL WATER CONTENT = 0 1100 VOL/VOL
EFFECTIVE SAT HYD COND = 0 100000005000E-02 CM/SEC

```

LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 6

THICKNESS = 24 00 INCHES
POROSITY = 0 4530 VOL/VOL
FIELD CAPACITY = 0 1900 VOL/VOL
WILTING POINT = 0 0850 VOL/VOL
INITIAL SOIL WATER CONTENT = 0 1900 VOL/VOL
EFFECTIVE SAT HYD COND = 0 720000011000E-03 CM/SEC
SLOPE = 1 60 PERCENT
DRAINAGE LENGTH = 2500 0 FEET

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

THICKNESS = 0 06 INCHES
POROSITY = 0 0000 VOL/VOL
FIELD CAPACITY = 0 0000 VOL/VOL
WILTING POINT = 0 0000 VOL/VOL
INITIAL SOIL WATER CONTENT = 0 0000 VOL/VOL
EFFECTIVE SAT HYD COND = 0 199999996000E-12 CM/SEC
FML PINHOLE DENSITY = 2 00 HOLES/ACRE
FML INSTALLATION DEFECTS = 4 00 HOLES/ACRE
FML PLACEMENT QUALITY = 3 - GOOD

LAYER 5

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 17

THICKNESS = 0 25 INCHES
POROSITY = 0 7500 VOL/VOL
FIELD CAPACITY = 0 7470 VOL/VOL
WILTING POINT = 0 4000 VOL/VOL
INITIAL SOIL WATER CONTENT = 0 7500 VOL/VOL
EFFECTIVE SAT HYD COND = 0 300000003000E-08 CM/SEC

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED

SCS RUNOFF CURVE NUMBER = 77 00
FRACTION OF AREA ALLOWING RUNOFF = 0 0 PERCENT
AREA PROJECTED ON HORIZONTAL PLANE = 1 000 ACRES
EVAPORATIVE ZONE DEPTH = 16 0 INCHES
INITIAL WATER IN EVAPORATIVE ZONE = 2 720 INCHES
UPPER LIMIT OF EVAPORATIVE STORAGE = 8 120 INCHES
LOWER LIMIT OF EVAPORATIVE STORAGE = 1 328 INCHES
INITIAL SNOW WATER = 0 000 INCHES
INITIAL WATER IN LAYER MATERIALS = 139 027 INCHES
TOTAL INITIAL WATER = 139 027 INCHES
TOTAL SUBSURFACE INFLOW = 0 00 INCHES/YEAR

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40 76 DEGREES
 MAXIMUM LEAF AREA INDEX = 1 60
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16 0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8 80 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67 00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48 00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39 00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65 00 %

NOTE PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 1 09 | 1 00 | 1 09 | 1 02 | 1 17 | 0 74 |
| 0 92 | 0 94 | 0 92 | 1 10 | 0 89 | 0 98 |

NOTE TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 25 30 | 30 20 | 38 60 | 45 90 | 54 40 | 62 80 |
| 70 10 | 68 50 | 59 40 | 47 80 | 35 40 | 26 40 |

NOTE SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH
AND STATION LATITUDE = 40 76 DEGREES

ANNUAL TOTALS FOR YEAR 1

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| | ----- | ----- | ----- |
| PRECIPITATION | 9 97 | 36191 109 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 10 184 | 36968 621 | 102 15 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|---------|------------|-------|
| CHANGE IN WATER STORAGE | -0 214 | -777 513 | -2 15 |
| SOIL WATER AT START OF YEAR | 139 027 | 504669 687 | |
| SOIL WATER AT END OF YEAR | 138 698 | 503474 125 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 115 | 418 067 | 1 16 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 002 | 0 00 |

ANNUAL TOTALS FOR YEAR 2

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 12 61 | 45774 297 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 503 | 45387 187 | 99 15 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 107 | 387 129 | 0 85 |
| SOIL WATER AT START OF YEAR | 138 698 | 503474 125 | |
| SOIL WATER AT END OF YEAR | 138 920 | 504279 312 | |
| SNOW WATER AT START OF YEAR | 0 115 | 413 067 | 0 91 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 022 | 0 00 |

ANNUAL TOTALS FOR YEAR 3

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 7 95 | 28858 504 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 7 906 | 28697 498 | 99 44 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|---------|------------|------|
| CHANGE IN WATER STORAGE | 0 044 | 161 027 | 0 56 |
| SOIL WATER AT START OF YEAR | 138 920 | 504279 312 | |
| SOIL WATER AT END OF YEAR | 138 304 | 502043 969 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 660 | 2396 377 | 8 30 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 021 | 0 00 |

ANNUAL TOTALS FOR YEAR 4

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 13 95 | 50638 508 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 358 | 44860 863 | 83 59 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 592 | 5777 574 | 11 41 |
| SOIL WATER AT START OF YEAR | 138 304 | 502043 969 | |
| SOIL WATER AT END OF YEAR | 140 328 | 509390 156 | |
| SNOW WATER AT START OF YEAR | 0 660 | 2396 377 | 4 73 |
| SNOW WATER AT END OF YEAR | 0 228 | 827 766 | 1 63 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 067 | 0 00 |

ANNUAL TOTALS FOR YEAR 5

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 9 43 | 34230 898 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 326 | 33854 625 | 98 90 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 104 | 376 289 | 1 10 |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT START OF YEAR | 140 328 | 509390 156 | |
| SOIL WATER AT END OF YEAR | 140 552 | 510203 531 | |
| SNOW WATER AT START OF YEAR | 0 223 | 827 766 | 2 42 |
| SNOW WATER AT END OF YEAR | 0 108 | 390 661 | 1 14 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 014 | 0 00 |

ANNUAL TOTALS FOR YEAR 6

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 14 03 | 50928 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 918 | 46893 496 | 92 08 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 112 | 4035 456 | 7 92 |
| SOIL WATER AT START OF YEAR | 140 552 | 510203 531 | |
| SOIL WATER AT END OF YEAR | 141 185 | 512500 719 | |
| SNOW WATER AT START OF YEAR | 0 108 | 390 661 | 0 77 |
| SNOW WATER AT END OF YEAR | 0 586 | 2128 952 | 4 18 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 047 | 0 00 |

ANNUAL TOTALS FOR YEAR 7

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 69 | 42434 707 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 584 | 45681 336 | 107 65 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 894 | -3246 695 | -7 65 |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT START OF YEAR | 141 185 | 512500 719 | |
| SOIL WATER AT END OF YEAR | 140 496 | 510000 719 | |
| SNOW WATER AT START OF YEAR | 0 586 | 2128 952 | 5 02 |
| SNOW WATER AT END OF YEAR | 0 381 | 1332 258 | 3 26 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 066 | 0 00 |

ANNUAL TOTALS FOR YEAR 8

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 3 61 | 31254 299 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 8 556 | 31060 027 | 99 38 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 054 | 194 333 | 0 62 |
| SOIL WATER AT START OF YEAR | 140 496 | 510000 719 | |
| SOIL WATER AT END OF YEAR | 140 816 | 511163 281 | |
| SNOW WATER AT START OF YEAR | 0 381 | 1382 258 | 4 42 |
| SNOW WATER AT END OF YEAR | 0 114 | 414 023 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 062 | 0 00 |

ANNUAL TOTALS FOR YEAR 9

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 12 75 | 46232 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 099 | 43918 012 | 94 89 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 651 | 2364 476 | 5 11 |
| SOIL WATER AT START OF YEAR | 140 816 | 511163 281 | |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT END OF YEAR | 141 582 | 513941 781 | |
| SNOW WATER AT START OF YEAR | 0 114 | 414 023 | 0 89 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 011 | 0 00 |

ANNUAL TOTALS FOR YEAR 10

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 11 38 | 41309 402 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 192 | 40626 805 | 98 35 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 188 | 682 588 | 1 65 |
| SOIL WATER AT START OF YEAR | 141 582 | 513941 781 | |
| SOIL WATER AT END OF YEAR | 141 497 | 513632 750 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 273 | 991 606 | 2 40 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 010 | 0 00 |

ANNUAL TOTALS FOR YEAR 11

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 12 56 | 45592 812 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 902 | 43204 625 | 94 76 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 658 | 2388 200 | 5 24 |
| SOIL WATER AT START OF YEAR | 141 497 | 513632 750 | |

| | | | |
|-----------------------------|---------|------------|------|
| SOIL WATER AT END OF YEAR | 142 428 | 517012 562 | |
| SNOW WATER AT START OF YEAR | 0 273 | 991 606 | 2 17 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 013 | 0 00 |

ANNUAL TOTALS FOR YEAR 12

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 21 | 37062 305 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 10 317 | 37452 348 | 101 05 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 107 | -390 066 | -1 05 |
| SOIL WATER AT START OF YEAR | 142 428 | 517012 562 | |
| SOIL WATER AT END OF YEAR | 142 185 | 516131 531 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 135 | 490 958 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 020 | 0 00 |

ANNUAL TOTALS FOR YEAR 13

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 9 17 | 33287 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 8 294 | 30108 729 | 90 45 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 376 | 3178 381 | 9 55 |
| SOIL WATER AT START OF YEAR | 142 185 | 516131 531 | |
| SOIL WATER AT END OF YEAR | 143 103 | 519465 312 | |

| | | | |
|-----------------------------|--------|---------|------|
| SNOW WATER AT START OF YEAR | 0 135 | 490 958 | 1 47 |
| SNOW WATER AT END OF YEAR | 0 092 | 335 562 | 1 01 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 005 | 0 00 |

ANNUAL TOTALS FOR YEAR 14

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 57 | 38369 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 409 | 34154 027 | 39 01 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 161 | 4215 101 | 10 99 |
| SOIL WATER AT START OF YEAR | 143 103 | 519465 312 | |
| SOIL WATER AT END OF YEAR | 143 759 | 521844 562 | |
| SNOW WATER AT START OF YEAR | 0 092 | 335 562 | 0 87 |
| SNOW WATER AT END OF YEAR | 0 598 | 2171 410 | 5 66 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 015 | 0 00 |

ANNUAL TOTALS FOR YEAR 15

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 35 | 37570 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 314 | 33809 922 | 89 99 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 036 | 3760 573 | 10 01 |
| SOIL WATER AT START OF YEAR | 143 759 | 521844 562 | |
| SOIL WATER AT END OF YEAR | 145 393 | 527776 562 | |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT START OF YEAR | 0 598 | 2171 410 | 5 78 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 007 | 0 00 |

ANNUAL TOTALS FOR YEAR 16

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 11 13 | 40401 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 001 | 39934 230 | 98 84 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 129 | 467 708 | 1 16 |
| SOIL WATER AT START OF YEAR | 145 393 | 527776 562 | |
| SOIL WATER AT END OF YEAR | 145 522 | 528244 250 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 031 | 0 00 |

ANNUAL TOTALS FOR YEAR 17

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 10 60 | 38478 008 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 377 | 34037 777 | 38 46 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 223 | 4440 155 | 11 54 |
| SOIL WATER AT START OF YEAR | 145 522 | 528244 250 | |
| SOIL WATER AT END OF YEAR | 146 362 | 531294 375 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 383 | 1390 027 | 3 61 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 074 | 0 00 |

ANNUAL TOTALS FOR YEAR 13

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 11 99 | 43523 711 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 302 | 41027 914 | 94 27 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 688 | 2495 821 | 5 73 |
| SOIL WATER AT START OF YEAR | 146 362 | 531294 375 | |
| SOIL WATER AT END OF YEAR | 147 391 | 535030 375 | |
| SNOW WATER AT START OF YEAR | 0 383 | 1390 027 | 3 19 |
| SNOW WATER AT END OF YEAR | 0 041 | 149 833 | 0 34 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 027 | 0 00 |

ANNUAL TOTALS FOR YEAR 19

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 6 95 | 25228 502 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 6 331 | 22981 078 | 91 09 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 619 | 2247 439 | 8 91 |
| SOIL WATER AT START OF YEAR | 147 391 | 535030 375 | |
| SOIL WATER AT END OF YEAR | 147 602 | 535794 437 | |
| SNOW WATER AT START OF YEAR | 0 041 | 149 833 | 0 59 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 450 | 1633 231 | 6 47 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 016 | 0 00 |

ANNUAL TOTALS FOR YEAR 20

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|------------|---------|
| PRECIPITATION | 13 72 | 49803 602 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 057 | 43768 371 | 87 88 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 663 | 6035 281 | 12 12 |
| SOIL WATER AT START OF YEAR | 147 602 | 535794 437 | |
| SOIL WATER AT END OF YEAR | 149 239 | 541738 625 | |
| SNOW WATER AT START OF YEAR | 0 450 | 1633 231 | 3 28 |
| SNOW WATER AT END OF YEAR | 0 475 | 1724 343 | 3 46 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 052 | 0 00 |

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|--------------------|----------------|----------------|----------------|----------------|----------------|----------------|
| PRECIPITATION | | | | | | |
| TOTALS | 0 94 0 81 | 0 86 0 39 | 1 22 0 83 | 0 96 0 87 | 1 01 0 80 | 0 75 1 04 |
| STD DEVIATIONS | 0 50 0 57 | 0 46 0 89 | 0 50 0 70 | 0 44 0 61 | 0 56 0 38 | 0 52 0 46 |
| RUNOFF | | | | | | |
| TOTALS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| STD DEVIATIONS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| EVAPOTRANSPIRATION | | | | | | |

| | | | | | | |
|----------------|-------|-------|-------|-------|-------|-------|
| TOTALS | 0 517 | 0 560 | 1 465 | 1 544 | 1 165 | 1 125 |
| | 0 825 | 0 857 | 0 714 | 0 505 | 0 597 | 0 573 |
| STD DEVIATIONS | 0 205 | 0 175 | 0 380 | 0 619 | 0 563 | 0 575 |
| | 0 569 | 0 897 | 0 626 | 0 398 | 0 222 | 0 163 |

LATERAL DRAINAGE COLLECTED FROM LAYER 3

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

AVERAGE ANNUAL TOTALS & (STD DEVIATIONS) FOR YEARS 1 THROUGH 20

| | INCHES | | CU FEET | PERCENT |
|---|---------|------------|----------|---------|
| PRECIPITATION | 10 98 | (1 932) | 39861 0 | 100 00 |
| RUNOFF | 0 000 | (0 0000) | 0 00 | 0 000 |
| EVAPOTRANSPIRATION | 10 447 | (1 8360) | 37921 37 | 95 134 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 | (0 00000) | 0 000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 00000 | (0 00000) | 0 000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 | (0 000) | | |
| CHANGE IN WATER STORAGE | 0 534 | (0 6552) | 1939 66 | 4 866 |

| PEAK DAILY VALUES FOR YEARS | 1 THROUGH 20 | |
|--|--------------|-----------|
| | (INCHES) | (CU FT) |
| PRECIPITATION | 1 27 | 4610 100 |
| RUNOFF | 0 000 | 0 0000 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 | |
| MAXIMUM HEAD ON TOP OF LAYER 4 | 0 000 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN) | 0 0 FEET | |
| SNOW WATER | 1 55 | 5618 2544 |
| MAXIMUM VEG SOIL WATER (VOL/VOL) | | 0 3003 |
| MINIMUM VEG SOIL WATER (VOL/VOL) | | 0 0830 |

*** Maximum heads are computed using McEnroe a equations ***

Reference Maximum Saturated Depth over Landfill Liner
 by Bruce M McEnroe University of Kansas
 ASCE Journal of Environmental Engineering
 Vol 119 No 2 March 1993 pp 262-270

| FINAL WATER STORAGE AT END OF YEAR 20 | | |
|---------------------------------------|----------|-----------|
| LAYER | (INCHES) | (VOL/VOL) |
| 1 | 3 0539 | 0 2545 |
| 2 | 141 4379 | 0 1179 |
| 3 | 4 5600 | 0 1900 |
| 4 | 0 0000 | 0 0000 |
| 5 | 0 1875 | 0 7500 |
| SNOW WATER | 0 475 | |

LAYER 3

TYPE 2 - LATERAL DRAINAGE LAYER

MATERIAL TEXTURE NUMBER 6

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 24 00 | INCHES |
| POROSITY | = | 0 4530 | VOL/VOL |
| FIELD CAPACITY | = | 0 1900 | VOL/VOL |
| WILTING POINT | = | 0 0850 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0 1900 | VOL/VOL |
| EFFECTIVE SAT HYD COND | = | 0 720000011000E-03 | CM/SEC |
| SLOPE | = | 1 60 | PERCENT |
| DRAINAGE LENGTH | = | 2500 0 | FEET |

LAYER 4

TYPE 4 - FLEXIBLE MEMBRANE LINER

MATERIAL TEXTURE NUMBER 35

| | | | |
|----------------------------|---|--------------------|------------|
| THICKNESS | = | 0 06 | INCHES |
| POROSITY | = | 0 0000 | VOL/VOL |
| FIELD CAPACITY | = | 0 0000 | VOL/VOL |
| WILTING POINT | = | 0 0000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0 0000 | VOL/VOL |
| EFFECTIVE SAT HYD COND | = | 0 199999996000E-12 | CM/SEC |
| FML PINHOLE DENSITY | = | 2 00 | HOLES/ACRE |
| FML INSTALLATION DEFECTS | = | 4 00 | HOLES/ACRE |
| FML PLACEMENT QUALITY | = | 3 - | GOOD |

LAYER 5

TYPE 3 - BARRIER SOIL LINER

MATERIAL TEXTURE NUMBER 17

| | | | |
|----------------------------|---|--------------------|---------|
| THICKNESS | = | 0 25 | INCHES |
| POROSITY | = | 0 7500 | VOL/VOL |
| FIELD CAPACITY | = | 0 7470 | VOL/VOL |
| WILTING POINT | = | 0 4000 | VOL/VOL |
| INITIAL SOIL WATER CONTENT | = | 0 7500 | VOL/VOL |
| EFFECTIVE SAT HYD COND | = | 0 300000003000E-08 | CM/SEC |

GENERAL DESIGN AND EVAPORATIVE ZONE DATA

NOTE SCS RUNOFF CURVE NUMBER WAS USER-SPECIFIED

| | | | |
|------------------------------------|---|--------|-------------|
| SCS RUNOFF CURVE NUMBER | = | 77 00 | |
| FRACTION OF AREA ALLOWING RUNOFF | = | 0 0 | PERCENT |
| AREA PROJECTED ON HORIZONTAL PLANE | = | 1 000 | ACRES |
| EVAPORATIVE ZONE DEPTH | = | 16 0 | INCHES |
| INITIAL WATER IN EVAPORATIVE ZONE | = | 2 240 | INCHES |
| UPPER LIMIT OF EVAPORATIVE STORAGE | = | 9 428 | INCHES |
| LOWER LIMIT OF EVAPORATIVE STORAGE | = | 1 280 | INCHES |
| INITIAL SNOW WATER | = | 0 000 | INCHES |
| INITIAL WATER IN LAYER MATERIALS | = | 19 087 | INCHES |
| TOTAL INITIAL WATER | = | 19 087 | INCHES |
| TOTAL SUBSURFACE INFLOW | = | 0 00 | INCHES/YEAR |

EVAPOTRANSPIRATION AND WEATHER DATA

NOTE EVAPOTRANSPIRATION DATA WAS OBTAINED FROM
SALT LAKE CITY UTAH

STATION LATITUDE = 40 76 DEGREES
 MAXIMUM LEAF AREA INDEX = 1 60
 START OF GROWING SEASON (JULIAN DATE) = 117
 END OF GROWING SEASON (JULIAN DATE) = 289
 EVAPORATIVE ZONE DEPTH = 16 0 INCHES
 AVERAGE ANNUAL WIND SPEED = 8 80 MPH
 AVERAGE 1ST QUARTER RELATIVE HUMIDITY = 67 00 %
 AVERAGE 2ND QUARTER RELATIVE HUMIDITY = 48 00 %
 AVERAGE 3RD QUARTER RELATIVE HUMIDITY = 39 00 %
 AVERAGE 4TH QUARTER RELATIVE HUMIDITY = 65 00 %

NOTE PRECIPITATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY PRECIPITATION (INCHES)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 1 09 | 1 00 | 1 09 | 1 02 | 1 17 | 0 74 |
| 0 92 | 0 94 | 0 92 | 1 10 | 0 89 | 0 98 |

NOTE TEMPERATURE DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH

NORMAL MEAN MONTHLY TEMPERATURE (DEGREES FAHRENHEIT)

| JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|---------|---------|---------|---------|---------|---------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| 25 30 | 30 20 | 38 60 | 45 90 | 54 40 | 62 80 |
| 70 10 | 68 50 | 59 40 | 47 80 | 35 40 | 26 40 |

NOTE SOLAR RADIATION DATA WAS SYNTHETICALLY GENERATED USING
COEFFICIENTS FOR SALT LAKE CITY UTAH
AND STATION LATITUDE = 40 76 DEGREES

ANNUAL TOTALS FOR YEAR 1

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| | ----- | ----- | ----- |
| PRECIPITATION | 9 97 | 36191 109 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 791 | 35540 309 | 98 20 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|--------|-----------|------|
| CHANGE IN WATER STORAGE | 0 179 | 650 786 | 1 80 |
| SOIL WATER AT START OF YEAR | 19 087 | 69287 547 | |
| SOIL WATER AT END OF YEAR | 19 152 | 69520 266 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 115 | 418 067 | 1 16 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 012 | 0 00 |

ANNUAL TOTALS FOR YEAR 2

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 12 61 | 45774 297 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 751 | 46284 473 | 101 11 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 141 | -510 152 | -1 11 |
| SOIL WATER AT START OF YEAR | 19 152 | 69520 266 | |
| SOIL WATER AT END OF YEAR | 19 126 | 69428 180 | |
| SNOW WATER AT START OF YEAR | 0 115 | 418 067 | 0 91 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 026 | 0 00 |

ANNUAL TOTALS FOR YEAR 3

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 7 95 | 28858 504 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 7 865 | 28548 961 | 98 93 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |

| | | | |
|-----------------------------|--------|-----------|------|
| CHANGE IN WATER STORAGE | 0 085 | 309 526 | 1 07 |
| SOIL WATER AT START OF YEAR | 19 126 | 69428 180 | |
| SOIL WATER AT END OF YEAR | 18 551 | 67341 328 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 660 | 2396 377 | 8 30 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 018 | 0 00 |

ANNUAL TOTALS FOR YEAR 4

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 13 95 | 50638 508 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 516 | 45431 453 | 89 72 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 434 | 5207 050 | 10 28 |
| SOIL WATER AT START OF YEAR | 18 551 | 67341 328 | |
| SOIL WATER AT END OF YEAR | 20 418 | 74116 992 | |
| SNOW WATER AT START OF YEAR | 0 660 | 2396 377 | 4 73 |
| SNOW WATER AT END OF YEAR | 0 228 | 827 766 | 1 63 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 004 | 0 00 |

ANNUAL TOTALS FOR YEAR 5

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 9 43 | 34230 898 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 718 | 35274 770 | 103 05 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 288 | -1043 868 | -3 05 |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT START OF YEAR | 20 418 | 74116 992 | |
| SOIL WATER AT END OF YEAR | 20 251 | 73510 227 | |
| SNOW WATER AT START OF YEAR | 0 228 | 827 766 | 2 42 |
| SNOW WATER AT END OF YEAR | 0 108 | 390 661 | 1 14 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 004 | 0 00 |

ANNUAL TOTALS FOR YEAR 6

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 14 03 | 50928 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 938 | 46964 297 | 92 22 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 092 | 3964 634 | 7 78 |
| SOIL WATER AT START OF YEAR | 20 251 | 73510 227 | |
| SOIL WATER AT END OF YEAR | 20 864 | 75736 570 | |
| SNOW WATER AT START OF YEAR | 0 108 | 390 661 | 0 77 |
| SNOW WATER AT END OF YEAR | 0 586 | 2128 952 | 4 18 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 026 | 0 00 |

ANNUAL TOTALS FOR YEAR 7

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 69 | 42434 707 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 570 | 45629 660 | 107 53 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 880 | -3194 955 | -7 53 |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT START OF YEAR | 20 864 | 75736 570 | |
| SOIL WATER AT END OF YEAR | 20 190 | 73288 312 | |
| SNOW WATER AT START OF YEAR | 0 586 | 2128 952 | 5 02 |
| SNOW WATER AT END OF YEAR | 0 381 | 1382 258 | 3 26 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 000 | 0 00 |

ANNUAL TOTALS FOR YEAR 8

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 8 61 | 31254 299 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 8 182 | 29700 090 | 95 03 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 428 | 1554 205 | 4 97 |
| SOIL WATER AT START OF YEAR | 20 190 | 73288 312 | |
| SOIL WATER AT END OF YEAR | 20 885 | 75810 750 | |
| SNOW WATER AT START OF YEAR | 0 381 | 1382 258 | 4 42 |
| SNOW WATER AT END OF YEAR | 0 114 | 414 023 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 004 | 0 00 |

ANNUAL TOTALS FOR YEAR 9

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 12 75 | 46282 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 497 | 45364 285 | 98 02 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 253 | 918 217 | 1 98 |
| SOIL WATER AT START OF YEAR | 20 885 | 75810 750 | |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT END OF YEAR | 21 252 | 77142 992 | |
| SNOW WATER AT START OF YEAR | 0 114 | 414 023 | 0 89 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 003 | 0 00 |

ANNUAL TOTALS FOR YEAR 10

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 38 | 41309 402 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 454 | 41579 582 | 100 65 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 074 | -270 179 | -0 65 |
| SOIL WATER AT START OF YEAR | 21 252 | 77142 992 | |
| SOIL WATER AT END OF YEAR | 20 904 | 75881 203 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 273 | 991 606 | 2 40 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 000 | 0 00 |

ANNUAL TOTALS FOR YEAR 11

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 12 56 | 45592 812 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 805 | 42850 980 | 93 99 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 755 | 2741 820 | 6 01 |
| SOIL WATER AT START OF YEAR | 20 904 | 75881 203 | |

| | | | |
|-----------------------------|--------|-----------|------|
| SOIL WATER AT END OF YEAR | 21 932 | 79614 633 | |
| SNOW WATER AT START OF YEAR | 0 273 | 991 606 | 2 17 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 011 | 0 00 |

ANNUAL TOTALS FOR YEAR 12

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 21 | 37062 305 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 10 571 | 38373 039 | 103 54 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 361 | -1310 734 | -3 54 |
| SOIL WATER AT START OF YEAR | 21 932 | 79614 633 | |
| SOIL WATER AT END OF YEAR | 21 436 | 77812 937 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 135 | 490 958 | 1 32 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 000 | 0 00 |

ANNUAL TOTALS FOR YEAR 13

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 9 17 | 33287 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 7 927 | 28774 422 | 36 44 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 243 | 4512 684 | 13 56 |
| SOIL WATER AT START OF YEAR | 21 436 | 77812 937 | |
| SOIL WATER AT END OF YEAR | 22 722 | 82481 023 | |

| | | | |
|-----------------------------|--------|---------|------|
| SNOW WATER AT START OF YEAR | 0 135 | 490 958 | 1 47 |
| SNOW WATER AT END OF YEAR | 0 092 | 335 552 | 1 01 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 009 | 0 00 |

ANNUAL TOTALS FOR YEAR 14

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 57 | 33369 113 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 731 | 35505 859 | 92 54 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 789 | 2863 267 | 7 46 |
| SOIL WATER AT START OF YEAR | 22 722 | 82481 023 | |
| SOIL WATER AT END OF YEAR | 23 005 | 83508 437 | |
| SNOW WATER AT START OF YEAR | 0 092 | 335 562 | 0 87 |
| SNOW WATER AT END OF YEAR | 0 598 | 2171 410 | 5 66 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 012 | 0 00 |

ANNUAL TOTALS FOR YEAR 15

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 35 | 37570 500 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 131 | 33147 066 | 88 23 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 219 | 4423 439 | 11 77 |
| SOIL WATER AT START OF YEAR | 23 005 | 83508 437 | |
| SOIL WATER AT END OF YEAR | 24 822 | 90103 289 | |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT START OF YEAR | 0 598 | 2171 410 | 5 78 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 003 | 0 00 |

ANNUAL TOTALS FOR YEAR 16

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 13 | 40401 906 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 440 | 41527 703 | 102 79 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | -0 310 | -1125 803 | -2 79 |
| SOIL WATER AT START OF YEAR | 24 822 | 90103 289 | |
| SOIL WATER AT END OF YEAR | 24 512 | 88977 484 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |
| SNOW WATER AT END OF YEAR | 0 000 | 0 000 | 0 00 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 007 | 0 00 |

ANNUAL TOTALS FOR YEAR 17

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 10 60 | 38478 008 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 9 838 | 35713 051 | 92 81 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 762 | 2764 944 | 7 19 |
| SOIL WATER AT START OF YEAR | 24 512 | 88977 484 | |
| SOIL WATER AT END OF YEAR | 24 890 | 90352 398 | |
| SNOW WATER AT START OF YEAR | 0 000 | 0 000 | 0 00 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 383 | 1390 027 | 3 61 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 012 | 0 00 |

ANNUAL TOTALS FOR YEAR 13

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 11 99 | 43523 711 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 11 623 | 42190 238 | 96 94 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 367 | 1333 475 | 3 06 |
| SOIL WATER AT START OF YEAR | 24 890 | 90352 398 | |
| SOIL WATER AT END OF YEAR | 25 599 | 92926 070 | |
| SNOW WATER AT START OF YEAR | 0 383 | 1390 027 | 3 19 |
| SNOW WATER AT END OF YEAR | 0 041 | 149 833 | 0 34 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | -0 002 | 0 00 |

ANNUAL TOTALS FOR YEAR 19

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 6 95 | 25228 502 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 6 739 | 24463 023 | 96 97 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 0 211 | 765 475 | 3 03 |
| SOIL WATER AT START OF YEAR | 25 599 | 92926 070 | |
| SOIL WATER AT END OF YEAR | 25 402 | 92208 148 | |
| SNOW WATER AT START OF YEAR | 0 041 | 149 833 | 0 59 |

| | | | |
|-----------------------------|--------|----------|------|
| SNOW WATER AT END OF YEAR | 0 450 | 1633 231 | 6 47 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 003 | 0 00 |

ANNUAL TOTALS FOR YEAR 20

| | INCHES | CU FEET | PERCENT |
|---------------------------------|----------|-----------|---------|
| PRECIPITATION | 13 72 | 49803 602 | 100 00 |
| RUNOFF | 0 000 | 0 000 | 0 00 |
| EVAPOTRANSPIRATION | 12 102 | 43931 852 | 88 21 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 0000 | 0 000 | 0 00 |
| PERC /LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 000 | 0 00 |
| AVG HEAD ON TOP OF LAYER 4 | 0 0000 | | |
| CHANGE IN WATER STORAGE | 1 618 | 5871 737 | 11 79 |
| SOIL WATER AT START OF YEAR | 25 402 | 92208 148 | |
| SOIL WATER AT END OF YEAR | 26 994 | 97988 773 | |
| SNOW WATER AT START OF YEAR | 0 450 | 1633 231 | 3 28 |
| SNOW WATER AT END OF YEAR | 0 475 | 1724 343 | 3 46 |
| ANNUAL WATER BUDGET BALANCE | 0 0000 | 0 014 | 0 00 |

AVERAGE MONTHLY VALUES IN INCHES FOR YEARS 1 THROUGH 20

| | JAN/JUL | FEB/AUG | MAR/SEP | APR/OCT | MAY/NOV | JUN/DEC |
|--------------------|----------------|----------------|----------------|----------------|----------------|----------------|
| PRECIPITATION | | | | | | |
| TOTALS | 0 94 0 81 | 0 86 0 89 | 1 22 0 83 | 0 96 0 87 | 1 01 0 80 | 0 75 1 04 |
| STD DEVIATIONS | 0 50 0 57 | 0 46 0 89 | 0 50 0 70 | 0 44 0 61 | 0 56 0 38 | 0 52 0 46 |
| RUNOFF | | | | | | |
| TOTALS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| STD DEVIATIONS | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 | 0 000 0 000 |
| EVAPOTRANSPIRATION | | | | | | |

| | | | | | | |
|----------------|-------|-------|-------|-------|-------|-------|
| TOTALS | 0 518 | 0 560 | 1 446 | 1 594 | 1 245 | 1 245 |
| | 0 818 | 0 820 | 0 744 | 0 474 | 0 525 | 0 572 |
| STD DEVIATIONS | 0 205 | 0 173 | 0 381 | 0 636 | 0 552 | 0 538 |
| | 0 558 | 0 835 | 0 625 | 0 342 | 0 164 | 0 163 |

LATERAL DRAINAGE COLLECTED FROM LAYER 3

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

PERCOLATION/LEAKAGE THROUGH LAYER 5

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| TOTALS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

AVERAGES OF MONTHLY AVERAGED DAILY HEADS (INCHES)

DAILY AVERAGE HEAD ON TOP OF LAYER 4

| | | | | | | |
|----------------|--------|--------|--------|--------|--------|--------|
| AVERAGES | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| STD DEVIATIONS | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |
| | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 | 0 0000 |

AVERAGE ANNUAL TOTALS & (STD DEVIATIONS) FOR YEARS 1 THROUGH 20

| | INCHES | CU FEET | PERCENT |
|---|--------------------|----------|---------|
| PRECIPITATION | 10 98 (1 982) | 39861 0 | 100 00 |
| RUNOFF | 0 000 (0 0000) | 0 00 | 0 000 |
| EVAPOTRANSPIRATION | 10 562 (1 8866) | 38339 75 | 96 184 |
| LATERAL DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 (0 00000) | 0 000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 00000 (0 00000) | 0 000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 (0 000) | | |
| CHANGE IN WATER STORAGE | 0 419 (0 6780) | 1521 28 | 3 816 |

| PEAK DAILY VALUES FOR YEARS | 1 THROUGH 20 | |
|--|--------------|-----------|
| | (INCHES) | (CU FT) |
| PRECIPITATION | 1 27 | 4610 100 |
| RUNOFF | 0 000 | 0 0000 |
| DRAINAGE COLLECTED FROM LAYER 3 | 0 00000 | 0 00000 |
| PERCOLATION/LEAKAGE THROUGH LAYER 5 | 0 000000 | 0 00000 |
| AVERAGE HEAD ON TOP OF LAYER 4 | 0 000 | |
| MAXIMUM HEAD ON TOP OF LAYER 4 | 0 000 | |
| LOCATION OF MAXIMUM HEAD IN LAYER 3 (DISTANCE FROM DRAIN) | 0 0 FEET | |
| SNOW WATER | 1 55 | 5618 2544 |
| MAXIMUM VEG SOIL WATER (VOL/VOL) | | 0 3100 |
| MINIMUM VEG SOIL WATER (VOL/VOL) | | 0 0800 |

*** Maximum heads are computed using McEnroe s equations ***

Reference Maximum Saturated Depth over Landfill Liner
 by Bruce M McEnroe University of Kansas
 ASCE Journal of Environmental Engineering
 Vol 119 No 2 March 1993 pp 262-270

| FINAL WATER STORAGE AT END OF YEAR 20 | | |
|---------------------------------------|----------|-----------|
| LAYER | (INCHES) | (VOL/VOL) |
| 1 | 1 8406 | 0 3068 |
| 2 | 20 4060 | 0 1701 |
| 3 | 4 5600 | 0 1900 |
| 4 | 0 0000 | 0 0000 |
| 5 | 0 1875 | 0 7500 |
| SNOW WATER | 0 475 | |

APPENDIX H

ATTACHMENT 4

LEACHATE COLLECTION PIPE CAPACITY CALCULATION

Worksheet for IRL 8" Leachate Collection Pipe

Project Description

Friction Method Manning Formula
Solve For Full Flow Capacity

Input Data

| | | |
|-----------------------|---------|--------------------|
| Roughness Coefficient | 0 013 | |
| Channel Slope | 0 01400 | ft/ft |
| Normal Depth | 0 67 | ft |
| Diameter | 0 67 | ft |
| Discharge | 1 45 | ft ³ /s |

Results

| | | |
|-------------------|-------------|--------------------|
| Discharge | 1 45 | ft ³ /s |
| Normal Depth | 0 67 | ft |
| Flow Area | 0 35 | ft ² |
| Wetted Perimeter | 2 10 | ft |
| Top Width | 0 00 | ft |
| Critical Depth | 0 56 | ft |
| Percent Full | 100 0 | % |
| Critical Slope | 0 01337 | ft/ft |
| Velocity | 4 11 | ft/s |
| Velocity Head | 0 26 | ft |
| Specific Energy | 0 93 | ft |
| Froude Number | 0 00 | |
| Maximum Discharge | 1 56 | ft ³ /s |
| Discharge Full | 1 45 | ft ³ /s |
| Slope Full | 0 01400 | ft/ft |
| Flow Type | SubCritical | |

GVF Input Data

| | | |
|------------------|------|----|
| Downstream Depth | 0 00 | ft |
| Length | 0 00 | ft |
| Number Of Steps | 0 | |

GVF Output Data

| | | |
|-----------------------------|--------|----|
| Upstream Depth | 0 00 | ft |
| Profile Description | | |
| Profile Headless | 0 00 | ft |
| Average End Depth Over Rise | 0 00 | % |
| Normal Depth Over Rise | 100 00 | % |

Worksheet for IRL 8" Leachate Collection Pipe

| | |
|-----------------|--|
| GVF Output Data | |
|-----------------|--|

| | | |
|---------------------|----------|-------|
| Downstream Velocity | Infinity | ft/s |
| Upstream Velocity | Infinity | ft/s |
| Normal Depth | 0.67 | ft |
| Critical Depth | 0.56 | ft |
| Channel Slope | 0.01400 | ft/ft |
| Critical Slope | 0.01337 | ft/ft |

APPENDIX I

LEACHATE POND CALCULATIONS



| | | | | | |
|---------|-----------------------------------|----------|-----|------|-----------|
| Project | Intermountain Regional Landfill | Computed | RLR | Date | 3/1/2010 |
| Subject | Hydrologic Analysis | Checked | TW | Date | 6/10/2010 |
| Task | Leachate Fbnd Volume Calculations | | | | |
| Job # | | | | | |

The required volume of the intermediate leachate pond was calculated using the area of Cell 1 Phase 1. The design storm for the leachate pond is the 25-year 24-hour storm. The pond was designed to hold the entire 25-year 24-hour storm.

25-yr 24-hr Precip = 1.74 inches
 From NOAA Atlas 14 Point Precipitation Frequency Estimates (See attached)

Volume Required

| Cell Name | Area (Ac) A | 25-yr 24-hr Precip (in) | Volume Required ⁽¹⁾ (ac-ft) | Volume Required (ft ³) |
|----------------|-------------|-------------------------|--|------------------------------------|
| Cell 1 Stage 1 | 8.0 | 1.74 | 1.16 | 50,530 |

Volume Provided

Bottom Elevation= 4824.00
 Top Elevation= 4826.00
 Volume Provided= 66,635 ft³ (Volume determined using AutoCAD Civil 3D 2008)

Summary

Volume Provided 66,635 ft³
 Volume Required 50,530 ft³
 Balance 16,105 ft³

Volume Provided > Volume Required

⁽¹⁾ Vrequired = (P_{25/24} A)/12



**POINT PRECIPITATION
FREQUENCY ESTIMATES
FROM NOAA ATLAS 14**



Utah 40 210671 N 112 077606 W 4845 feet
 from Precipitation Frequency Atlas of the United States NOAA Atlas 14 Volume I Version 4
 G M Bonnin D Martin B Lin T Parzybok M Yelda and D Riley
 NOAA National Weather Service Silver Spring Maryland 2006
 Extracted Mon Mar 1 2010

| | | | | | | | |
|-----------------------------------|-----------------------------|-------------------------------|----------------------------|--------------------------|----------------------|----------------------|-------------------------------------|
| Confidence Limits | Seasonality | Locat on Maps | Other Info | GIS data | Maps | Docs | Return to State Map |
|-----------------------------------|-----------------------------|-------------------------------|----------------------------|--------------------------|----------------------|----------------------|-------------------------------------|

| Precipitation Frequency Estimates (inches) | | | | | | | | | | | | | | | | | | |
|--|---------|----------|----------|----------|----------|-----------|---------|---------|----------|----------|----------|----------|----------|-----------|-----------|-----------|-----------|-----------|
| ARI* (years) | 5 mm | 10 mm | 15 mm | 30 mm | 60 mm | 120 mm | 3 hr | 6 hr | 12 hr | 24 hr | 48 hr | 4 day | 7 day | 10 day | 20 day | 30 day | 45 day | 60 day |
| 1 | 0.11 | 0.17 | 0.21 | 0.29 | 0.36 | 0.44 | 0.49 | 0.62 | 0.76 | 0.90 | 1.00 | 1.19 | 1.39 | 1.57 | 2.04 | 2.41 | 2.99 | 3.51 |
| 2 | 0.14 | 0.22 | 0.27 | 0.37 | 0.45 | 0.55 | 0.61 | 0.76 | 0.93 | 1.11 | 1.23 | 1.46 | 1.71 | 1.92 | 2.50 | 2.95 | 3.66 | 4.29 |
| 5 | 0.20 | 0.31 | 0.38 | 0.51 | 0.63 | 0.72 | 0.78 | 0.94 | 1.13 | 1.32 | 1.47 | 1.75 | 2.04 | 2.29 | 2.97 | 3.50 | 4.31 | 5.05 |
| 10 | 0.25 | 0.38 | 0.47 | 0.64 | 0.79 | 0.89 | 0.93 | 1.09 | 1.29 | 1.50 | 1.67 | 2.00 | 2.32 | 2.59 | 3.33 | 3.94 | 4.81 | 5.62 |
| 25 | 0.33 | 0.50 | 0.62 | 0.84 | 1.03 | 1.14 | 1.17 | 1.31 | 1.52 | 1.74 | 1.94 | 2.34 | 2.70 | 2.98 | 3.80 | 4.51 | 5.45 | 6.34 |
| 50 | 0.40 | 0.61 | 0.76 | 1.02 | 1.26 | 1.36 | 1.39 | 1.50 | 1.69 | 1.92 | 2.14 | 2.62 | 2.99 | 3.28 | 4.13 | 4.93 | 5.91 | 6.86 |
| 100 | 0.48 | 0.73 | 0.91 | 1.23 | 1.52 | 1.63 | 1.64 | 1.74 | 1.88 | 2.10 | 2.35 | 2.90 | 3.28 | 3.58 | 4.46 | 5.35 | 6.34 | 7.34 |
| 200 | 0.58 | 0.88 | 1.09 | 1.47 | 1.82 | 1.93 | 1.95 | 2.02 | 2.15 | 2.28 | 2.56 | 3.19 | 3.57 | 3.87 | 4.77 | 5.75 | 6.74 | 7.79 |
| 500 | 0.73 | 1.10 | 1.37 | 1.84 | 2.28 | 2.41 | 2.42 | 2.50 | 2.57 | 2.60 | 2.85 | 3.58 | 3.96 | 4.24 | 5.15 | 6.27 | 7.22 | 8.31 |
| 1000 | 0.86 | 1.31 | 1.62 | 2.18 | 2.70 | 2.84 | 2.84 | 2.91 | 2.92 | 2.95 | 3.06 | 3.89 | 4.25 | 4.51 | 5.42 | 6.64 | 7.55 | 8.66 |

These precipitation frequency estimates are based on a partial duration series. ARI is the Average Recurrence Interval. Please refer to NOAA Atlas 14 Document for more information. NOTE: Formatting forces estimates near zero to appear as zero.

| * Upper bound of the 90% confidence interval Precipitation Frequency Estimates (inches) | | | | | | | | | | | | | | | | | | |
|--|---------|----------|----------|----------|----------|-----------|---------|---------|----------|----------|----------|----------|----------|-----------|-----------|-----------|-----------|-----------|
| ARI** (years) | 5 mm | 10 mm | 15 mm | 30 mm | 60 mm | 120 mm | 3 hr | 6 hr | 12 hr | 24 hr | 48 hr | 4 day | 7 day | 10 day | 20 day | 30 day | 45 day | 60 day |
| 1 | 0.14 | 0.20 | 0.25 | 0.34 | 0.42 | 0.50 | 0.55 | 0.69 | 0.83 | 0.98 | 1.09 | 1.30 | 1.52 | 1.71 | 2.21 | 2.60 | 3.23 | 3.75 |
| 2 | 0.17 | 0.26 | 0.32 | 0.44 | 0.54 | 0.64 | 0.69 | 0.84 | 1.03 | 1.20 | 1.33 | 1.59 | 1.86 | 2.08 | 2.72 | 3.19 | 3.95 | 4.59 |
| 5 | 0.24 | 0.37 | 0.45 | 0.61 | 0.76 | 0.84 | 0.89 | 1.04 | 1.24 | 1.43 | 1.59 | 1.92 | 2.23 | 2.48 | 3.22 | 3.78 | 4.64 | 5.39 |
| 10 | 0.30 | 0.46 | 0.57 | 0.77 | 0.95 | 1.03 | 1.06 | 1.21 | 1.43 | 1.62 | 1.81 | 2.19 | 2.53 | 2.80 | 3.61 | 4.24 | 5.17 | 5.99 |
| 25 | 0.40 | 0.60 | 0.75 | 1.01 | 1.25 | 1.32 | 1.34 | 1.46 | 1.68 | 1.88 | 2.09 | 2.56 | 2.93 | 3.22 | 4.11 | 4.86 | 5.85 | 6.75 |
| 50 | 0.48 | 0.74 | 0.92 | 1.23 | 1.53 | 1.60 | 1.61 | 1.68 | 1.88 | 2.07 | 2.31 | 2.86 | 3.24 | 3.54 | 4.46 | 5.32 | 6.35 | 7.30 |
| 100 | 0.59 | 0.89 | 1.11 | 1.49 | 1.84 | 1.92 | 1.94 | 1.96 | 2.11 | 2.27 | 2.55 | 3.17 | 3.56 | 3.87 | 4.83 | 5.78 | 6.81 | 7.81 |
| 200 | 0.71 | 1.08 | 1.34 | 1.81 | 2.24 | 2.31 | 2.34 | 2.36 | 2.43 | 2.46 | 2.78 | 3.49 | 3.88 | 4.18 | 5.17 | 6.22 | 7.24 | 8.29 |
| 500 | 0.91 | 1.38 | 1.71 | 2.31 | 2.86 | 2.93 | 2.96 | 2.99 | 3.02 | 3.05 | 3.10 | 3.94 | 4.31 | 4.60 | 5.60 | 6.80 | 7.76 | 8.86 |
| 1000 | 1.09 | 1.65 | 2.05 | 2.76 | 3.41 | 3.52 | 3.55 | 3.59 | 3.62 | 3.66 | 3.69 | 4.30 | 4.64 | 4.92 | 5.91 | 7.21 | 8.12 | 9.24 |

The upper bound of the confidence interval at 90% confidence level is the value which 5% of the simulated quantile values for a given frequency are greater than. ** These precipitation frequency estimates are based on a partial duration series. ARI is the Average Recurrence Interval.

Please refer to NOAA Atlas 14 Document for more information. NOTE: Formatting prevents estimates near zero to appear as zero.


| * Lower bound of the 90% confidence interval Precipitation Frequency Estimates (inches) | | | | | | | | | | | | | | | | | | |
|--|---------|----------|----------|----------|----------|-----------|---------|---------|----------|----------|----------|----------|----------|-----------|-----------|-----------|-----------|-----------|
| ARI** (years) | 5 mm | 10 mm | 15 mm | 30 mm | 60 mm | 120 mm | 3 hr | 6 hr | 12 hr | 24 hr | 48 hr | 4 day | 7 day | 10 day | 20 day | 30 day | 45 day | 60 day |
| 1 | 0.10 | 0.15 | 0.18 | 0.24 | 0.30 | 0.39 | 0.44 | 0.57 | 0.70 | 0.83 | 0.93 | 1.09 | 1.28 | 1.45 | 1.88 | 2.22 | 2.78 | 3.27 |
| 2 | 0.12 | 0.19 | 0.23 | 0.32 | 0.39 | 0.48 | 0.54 | 0.70 | 0.85 | 1.02 | 1.14 | 1.34 | 1.57 | 1.77 | 2.31 | 2.73 | 3.40 | 4.00 |
| 5 | 0.17 | 0.26 | 0.32 | 0.44 | 0.54 | 0.63 | 0.69 | 0.85 | 1.03 | 1.22 | 1.36 | 1.61 | 1.88 | 2.11 | 2.75 | 3.24 | 4.01 | 4.70 |
| 10 | 0.21 | 0.32 | 0.40 | 0.54 | 0.67 | 0.77 | 0.82 | 0.99 | 1.18 | 1.38 | 1.54 | 1.83 | 2.13 | 2.39 | 3.08 | 3.64 | 4.47 | 5.24 |
| 25 | 0.27 | 0.41 | 0.51 | 0.69 | 0.85 | 0.96 | 1.02 | 1.17 | 1.38 | 1.59 | 1.78 | 2.14 | 2.47 | 2.74 | 3.51 | 4.17 | 5.07 | 5.90 |
| 50 | 0.32 | 0.49 | 0.61 | 0.82 | 1.02 | 1.13 | 1.18 | 1.32 | 1.52 | 1.75 | 1.97 | 2.38 | 2.73 | 3.01 | 3.82 | 4.54 | 5.49 | 6.38 |
| 100 | 0.38 | 0.58 | 0.72 | 0.96 | 1.19 | 1.32 | 1.37 | 1.50 | 1.67 | 1.91 | 2.16 | 2.63 | 2.98 | 3.27 | 4.11 | 4.92 | 5.88 | 6.81 |
| 200 | 0.44 | 0.67 | 0.83 | 1.12 | 1.39 | 1.51 | 1.58 | 1.72 | 1.87 | 2.06 | 2.33 | 2.87 | 3.24 | 3.52 | 4.38 | 5.26 | 6.25 | 7.21 |
| 500 | 0.53 | 0.81 | 1.00 | 1.35 | 1.67 | 1.81 | 1.88 | 2.06 | 2.19 | 2.26 | 2.57 | 3.20 | 3.56 | 3.84 | 4.72 | 5.71 | 6.68 | 7.68 |
| 1000 | 0.60 | 0.92 | 1.14 | 1.53 | 1.90 | 2.05 | 2.13 | 2.34 | 2.44 | 2.47 | 2.75 | 3.44 | 3.80 | 4.07 | 4.95 | 6.02 | 6.96 | 7.99 |

The lower bound of the confidence interval at 90% confidence level is the value which 5% of the simulated quantile values for a given frequency are less than.

These precipitation frequency estimates are based on a partial duration maxima series. ARI is the Average Recurrence Interval. Please refer to NOAA Atlas 14 Document for more information. NOTE: Formatting prevents estimates near zero to appear as zero.

Text version of tables


Partial duration based Point Precipitation Frequency Estimates - Version 4
48 810671 N 118 077000 W 4848 ft



Mon Mar 01 09:24:47 0810

| Duration | | | |
|----------|---------|--------|--------|
| 5-min | 120-min | 48-hr | 30-day |
| 10-min | 3-hr | 4-day | 45-day |
| 15-min | 6-hr | 7-day | 60-day |
| 30-min | 12-hr | 10-day | |
| 60-min | 24-hr | 20-day | |



Partial duration based Point Precipitation Frequency Estimates - Version 4
48 210071 N 112 077000 W 4045 ft



Mon Mar 01 09:14:47 2010

| Average Recurrence Interval (years) | |
|-------------------------------------|------|
| 1 | 50 |
| 2 | 100 |
| 5 | 200 |
| 10 | 500 |
| 25 | 1000 |

Maps -



These maps were produced using a direct map request from the U.S. Census Bureau Mapping and Cartographic Resources Tiger Map Server

Please read [this link](#) for more information

LEGEND

| | |
|-------------------|-----------------|
| — State | — Connector |
| — County | — Stream |
| — Indian Resv | — Military Area |
| — Lake/Pond/Ocean | — National Park |
| — Street | — Other Park |
| — Expressway | — City |
| — Highway | — County |

Scale 1:228583
 *average—true scale depends on monitor resolution

Other Maps/Photographs -

View USGS digital orthophoto quadrangle (DOQ) covering this location from TerraServer. USGS Aerial Photograph may also be available from this site. A DOQ is a computer generated image of an aerial photograph in which image displacement caused by terrain relief and camera tilts has been removed. It combines the image characteristics of a photograph with the geometric qualities of a map. Visit the [USGS](#) for more information.

Watershed/Stream Flow Information -

Find the [Watershed](#) for this location using the U.S. Environmental Protection Agency's site.

Climate Data Sources -

Precipitation frequency results are based on data from a variety of sources but largely NCDC. The following links provide general information about observing sites in the area regardless of whether data was used in this study. For detailed information about the stations used in this study please refer to [NOAA Atlas 14 Document](#).

Using the [National Climatic Data Center's \(NCDC\)](#) station search engine locate other climate stations within

OR of this location (40 210671/ 112 077606). Digital ASCII data can be obtained directly from [NCDC](#).

Find [Natural Resources Conservation Service \(NRCS\)](#) SNOTEL (SNOWpack TELEmetry) stations by visiting the [Western Regional Climate Center's](#) state specific SNOTEL station maps.

Hydrometeorological Design Studies Center
 DOC/NOAA/National Weather Service
 1325 East West Highway
 Silver Spring MD 20910
 (301) 713 1669
 Questions? HDSC.Questions@noaa.gov

[Disclaimer](#)

APPENDIX J

RUN-ON AND RUN-OFF CALCULATIONS

APPENDIX J

RUN-ON / RUN-OFF CALCULATIONS

**Intermountain Regional Landfill
Class I Landfill Permit Application**

Submitted August 2010

**Prepared By
HDR ENGINEERING, INC**

INTRODUCTION

The run-on/run-off calculations were performed to determine the size of drainage ditches required to control run-on and run-off flows. The run-on/run-off peak flows were calculated using the Rational Method

$$Q = CiA$$

where Q = Run-off flow (ft³/sec)
 C = Run-off Coefficient
 i = rainfall intensity (in/hr)
 A = Area contributing to run-off (acres)

The run-off coefficient, C , was multiplied by the run-off coefficient adjustment factor, C_f , of 1.1 to adjust the rational method for a recurrence interval of 25 years

Once the run-on/run-off flows were calculated, the capacity of the ditch designed to carry the run-on/run-off was calculated using Manning's Equation

$$Q = \frac{1.49}{n} AR^{2/3} S^{1/2}$$

where Q = Maximum capacity of ditch (ft³/sec, cfs)
 n = Manning's roughness coefficient
 A = Cross-sectional area of ditch (ft²)
 R = Hydraulic radius (A/wetted perimeter) (ft)
 S = slope of ditch (ft/ft)

If the capacity of the ditch exceeds the run-on/run-off flow, then the ditch is adequate

Runoff

Figure J-1 shows a portion of Cell 1 where runoff will be directed to the north and south sides of Cell 1 with final cover in place. The calculations shown in Attachment 1 are for the run-off from Cell 1. Ditches that will be constructed north and south of Cell 1 will direct the run-off to the east where the ditch will end and the flow will exit the site as sheet flow. The final cover on Cell 1 will be overlaid with short grass prairie, which has a Manning's roughness coefficient, n , of 0.15. This was considered to be cultivated land on a rural catchment, so a value of 0.30 was chosen as the basic factor for the run-off coefficient, C .

The calculations were done for the design of drainage ditches which will be constructed around the perimeter of Cell 1. The run-off was calculated as if Cell 1 were filled to capacity prior to installation of the final cap as a worst-case scenario so that the ditches can be constructed as Cell 1 is filled and will not need to be redesigned. A Manning's roughness coefficient of 0.027 (earth with weeds) was used for the channel design and a run-off coefficient (C-value) of 0.30 was used for run-off calculations (undeveloped land).

Runoff flow rates from the intermediate final cover and northern side slope of Cell 1 is approximately 16 cfs. Runoff from the Cell 1 intermediate southern side slopes is about 21 cfs. A triangular ditch that is nominally 1.5 feet deep will convey these flow rates.

Run-on

No defined drainage features were noted at the landfill property. Run-on is, therefore, limited to the stormwater runoff from the property that abuts the western property boundary. The calculations shown in Attachment 2 are for the run-on to the Landfill. The run-on contributing area is approximately 419 acres. The runoff from a 25-year storm event is approximately 142 cfs. A run-on conveyance ditch with a 10 foot bottom width, with 4 to 1 (horizontal to vertical) side slopes, and nominally 3 feet deep will be constructed along the west and north sides of the property. The ditch will terminate in a level spreader to return collected run-on to sheet flow on the east side of the property.

APPENDIX J

Attachment 1

REQUIRED CAPACITY OF DRAINAGE DITCH FOR RUN-OFF

| | | | | | |
|---------|--|----------|-----|------|-----------|
| Project | Intermountain Regional Landfill | Computed | RLR | Date | 8/13/2010 |
| Subject | Run-off calculations | Checked | trw | Date | 7/12/2010 |
| Task | Determine Flow Rates using Rational Method | | | | |
| Job # | | | | | |

DA 1 Cell 1 North - Diversion Ditch around Cell 1

Rational Equation Parameters

Drainage Area (A) = 19.37 ac

Time of Concentration $t_c = \sum_{i=1}^k T_{ti} = \sum_{i=1}^k \left(\frac{L_i}{60V_i} \right)$ Eq 7.11 from UDOT Manual Roadway Drainage Hydrology (See Attached)

$V = kS^{0.5}$ Eq 7.12 from UDOT Manual Roadway Drainage Hydrology (See Attached)

where t_c = Time of concentration (min) V = Velocity (ft/s)
 L = Length of segment (ft) S = Slope (%)
 k = Intercept coefficient from Table 7.10 from UDOT Manual Roadway Drainage Hydrology (See Attached)

Segment 1 $L = 310$ ft
 $S = 25.0\%$
 $k = 1.61$ (Assume shallow concentrated flow)
 $V = 8.1$ ft/s

Therefore $t_c = 0.64$ min

Segment 2 $L = 3300$ ft
 $S = 2.0\%$
 $k = 1.61$ (Assume shallow concentrated flow)
 $V = 2.3$ ft/s

Therefore $t_c = 24.16$ min

Total $t_c = 24.80$ min

Rainfall intensity (i) for 25 year storm

For $t_c = 24.80$ min
 $i_{25} = 2.48$ in/hr (From IDF curves from NOAA Atlas 14 (See attached))

Rainfall Runoff Coefficient

$C = 0.30$ (C value for unimproved area from Table 7.24 from UDOT Manual of Instruction (See attached))

Frequency Factor for Rational Formula

$C_f = 1.1$ (Frequency Factor for 25 year recurrence interval from Table 7.21 from UDOT Manual of Instruction)

Discharge Calculation

$Q = C * C_f * I * A$

| | | |
|------------|----|-----|
| $Q_{25} =$ | 16 | cfs |
|------------|----|-----|

| | | | | | |
|-----------|---|-----------|-----|------|-----------|
| Project | Intermittent Rain Region I Landfill | Completed | RLR | Date | 8/13/2010 |
| Submitted | Runoff calculations | Checked | trw | Date | 7/12/2010 |
| Task | Determine Run Rates Using Rational Method | | | | |
| Job # | | | | | |

DA 1 Cell 1 South Diversion Ditch around Cell 1

Rational Equation Parameters

Drainage Area (A) = 25.20 ac

Time of Concentration

$$t_c = \sum_{i=1}^k T_{bi} = \sum_{i=1}^k \left(\frac{L_i}{60V_i} \right)$$

Eq 7.11 from UDOT Manual Roadway Drainage Hydrology (See Attached)

$$V = kS^{0.5}$$

Eq 7.12 from UDOT Manual Roadway Drainage Hydrology (See Attached)

where
 tc = Time of concentration (min)
 L = Length of segment (ft)
 k = Intercept coefficient from Table 7.10 from UDOT Manual Roadway Drainage Hydrology (See Attached)
 V = Velocity (ft/s)
 S = Slope (%)

Segment 1
 L = 310 ft
 S = 25.0%
 k = 1.61 (Assume shallow concentrated flow)
 V = 8.1 ft/s
 Therefore tc = 0.64 min

Segment 2
 L = 2540 ft
 S = 2.0%
 k = 1.61 (Assume shallow concentrated flow)
 V = 2.3 ft/s
 Therefore tc = 18.59 min

Total tc = 19.23 min

Rainfall intensity (i) for 25 year storm

For tc = 19.23 min
 $i_{25} = 2.48$ in/hr (From IDF curves from NOAA Atlas 14 (See attached))

Rainfall Runoff Coefficient

C = 0.30 (C value for unimproved area from Table 7.24 from UDOT Manual of Instruction (See attached))

Frequency Factor for Rational Formula

$C_f = 1.1$ (Frequency Factor for 25 year recurrence interval from Table 7.21 from UDOT Manual of Instruction (See attached))

Discharge Calculation

$$Q = C * C_f * I * A$$

| | | |
|------------|----|-----|
| $Q_{25} =$ | 21 | cfs |
|------------|----|-----|

Worksheet for IRL Triangular Channel for Run-off (16 CFS)

Project Description

Friction Method Manning Formula
Solve For Normal Depth

Input Data

Roughness Coefficient 0 027
Channel Slope 0 01000 ft/ft
Left Side Slope 4 00 ft/ft (H V)
Right Side Slope 4 00 ft/ft (H V)
Discharge 16 00 ft³/s

Results

Normal Depth 1 06 ft
Flow Area 4 52 ft²
Wetted Perimeter 8 77 ft
Top Width 8 50 ft
Critical Depth 1 00 ft
Critical Slope 0 01394 ft/ft
Velocity 3 54 ft/s
Velocity Head 0 19 ft
Specific Energy 1 26 ft
Froude Number 0 86
Flow Type Subcritical

GVF Input Data

Downstream Depth 0 00 ft
Length 0 00 ft
Number Of Steps 0

GVF Output Data

Upstream Depth 0 00 ft
Profile Description
Profile Headloss 0 00 ft
Downstream Velocity Infinity ft/s
Upstream Velocity Infinity ft/s
Normal Depth 1 06 ft
Critical Depth 1 00 ft
Channel Slope 0 01000 ft/ft
Critical Slope 0 01394 ft/ft

Worksheet for IRL Triangular Channel for Run-off (21 CFS)

Project Description

Friction Method Manning Formula
Solve For Normal Depth

Input Data

| | | |
|-----------------------|---------|--------------------|
| Roughness Coefficient | 0.027 | |
| Channel Slope | 0.01000 | ft/ft |
| Left Side Slope | 4.00 | ft/ft (H V) |
| Right Side Slope | 4.00 | ft/ft (H V) |
| Discharge | 21.00 | ft ³ /s |

Results

| | | |
|------------------|-------------|-----------------|
| Normal Depth | 1.18 | ft |
| Flow Area | 5.54 | ft ² |
| Wetted Perimeter | 9.71 | ft |
| Top Width | 9.42 | ft |
| Critical Depth | 1.11 | ft |
| Critical Slope | 0.01344 | ft/ft |
| Velocity | 3.79 | ft/s |
| Velocity Head | 0.22 | ft |
| Specific Energy | 1.40 | ft |
| Froude Number | 0.87 | |
| Flow Type | Subcritical | |

GVF Input Data

| | | |
|------------------|------|----|
| Downstream Depth | 0.00 | ft |
| Length | 0.00 | ft |
| Number Of Steps | 0 | |

GVF Output Data

| | | |
|---------------------|----------|-------|
| Upstream Depth | 0.00 | ft |
| Profile Description | | |
| Profile Headloss | 0.00 | ft |
| Downstream Velocity | Infinity | ft/s |
| Upstream Velocity | Infinity | ft/s |
| Normal Depth | 1.18 | ft |
| Critical Depth | 1.11 | ft |
| Channel Slope | 0.01000 | ft/ft |
| Critical Slope | 0.01344 | ft/ft |

APPENDIX J

Attachment 2

REQUIRED CAPACITY OF SURFACE WATER DIVERSION DITCH FOR RUN-ON

| | | | | | |
|---------|--|----------|-----|------|-----------|
| Project | Intermountain Regional Landfill | Computed | KDW | Date | 2/13/2010 |
| Subject | Run on calculations | Checked | TRW | Date | 7/12/2010 |
| Task | Determine Runoff Rates using Rational Method | | | | |
| Job # | | | | | |

DA 1 Off Site Contributing Area

Rational Equation Parameters

Drainage Area (A) = 419.00 ac

Time of Concentration

$$t_c = \sum_{i=1}^k T_{ti} = \sum_{i=1}^k \left(\frac{L}{60V_i} \right)$$

Eq 7.11 from UDOT Manual Roadway Drainage Hydrology (See Attached)

$$V = kS^{0.5}$$

Eq 7.12 from UDOT Manual Roadway Drainage Hydrology (See Attached)

- where
- tc = Time of concentration (min)
 - L = Length of segment (ft)
 - k = Intercept coefficient from Table 7.10 from UDOT Manual Roadway Drainage Hydrology (See Attached)
 - V = Velocity (ft/s)
 - S = Slope (%)

Segment 1 L = 3952 ft
 Upper Elevation 4864 ft
 Lower Elevation 4851 ft
 S = 0.3%
 k = 1.61
 V = 1.0 ft/s

(Assume shallow concentrated flow)

Therefore tc = 69.23 min

Total tc = 69.23 min

Rainfall intensity (i) for 25 year storm

For tc = 69.23 min
 $i_{25} = 1.03$ in/hr (From IDF curves from NOAA Atlas 14 (See attached))

Rainfall Runoff Coefficient

C = 0.30 (C value for unimproved area from Table 7.24 from UDOT Manual of Instruction (See attached))

Frequency Factor for Rational Formula

$C_f = 1.1$ (Frequency Factor for 25 year recurrence interval from Table 7.21 from UDOT Manual of Instruction)

Discharge Calculation

$$Q = C * C_f * I * A$$

| | | |
|------------|-----|-----|
| $Q_{25} =$ | 142 | cfs |
|------------|-----|-----|

Worksheet for North Channel

Project Description

Friction Method Manning Formula
Solve For Normal Depth

Input Data

| | | |
|-----------------------|---------|--------------------|
| Roughness Coefficient | 0.020 | |
| Channel Slope | 0.00200 | ft/ft |
| Left Side Slope | 4.00 | ft/ft (H V) |
| Right Side Slope | 4.00 | ft/ft (H V) |
| Bottom Width | 10.00 | ft |
| Discharge | 142.00 | ft ³ /s |

Results

| | | |
|------------------|-------------|-----------------|
| Normal Depth | 1.97 | ft |
| Flow Area | 35.15 | ft ² |
| Wetted Perimeter | 26.22 | ft |
| Top Width | 25.74 | ft |
| Critical Depth | 1.50 | ft |
| Critical Slope | 0.00579 | ft/ft |
| Velocity | 4.04 | ft/s |
| Velocity Head | 0.25 | ft |
| Specific Energy | 2.22 | ft |
| Froude Number | 0.61 | |
| Flow Type | Subcritical | |

GVF Input Data

| | | |
|------------------|------|----|
| Downstream Depth | 0.00 | ft |
| Length | 0.00 | ft |
| Number Of Steps | 0 | |

GVF Output Data

| | | |
|---------------------|----------|-------|
| Upstream Depth | 0.00 | ft |
| Profile Description | | |
| Profile Headloss | 0.00 | ft |
| Downstream Velocity | Infinity | ft/s |
| Upstream Velocity | Infinity | ft/s |
| Normal Depth | 1.97 | ft |
| Critical Depth | 1.50 | ft |
| Channel Slope | 0.00200 | ft/ft |
| Critical Slope | 0.00579 | ft/ft |

APPENDIX K

WATER RIGHTS DATA


[Online Services](#)
[Agency List](#)
[Business](#)

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009

WATER RIGHT **54 493** APPLICATION/CLAIM NO **A52843** CERT NO

OWNERSHIP** *****

NAME Douglas Young
 ADDR 4770 South 900 East
 Murray UT 84107

DATES ETC * * * * *

LAND OWNED BY APPLICANT No COUNTY TAX ID#
 FILED 03/30/1979|PRIORITY 03/30/1979|PUB BEGAN
 ProtestEnd |PROTESTED [No]|HEARNG HLD
 EXTENSION |ELEC/PROOF []|ELEC/PROOF
 RUSH LETTR |RENOVATE |RECON REQ
 PD BOOK | 54- |MAP []|PUB DATE
 Type of Right Application to Appropriate Source of Info /

SPAPER
 ionDate 09/06/1979|PROOF DUE
 ETC 01/18/1982|LAPS LETTER

Status Lapsed

LOCATION OF WATER RIGHT*** (Points of Diversion Click on Locat

*****MAP VIEWER*****

FLOW 0 015 cfs SOURCE Und
 COUNTY Utah COMMON DESCRIPTION APPROX 3 5 MI S/E OF

POINT OF DIVERSION -- UNDERGROUND (Click Well ID# link for more well data ;
 1) S 20 ft E 50 ft from N4 0 1 1 7s R 2W SLB
 DIAMETER OF WELL 6 ins DEPTH 100 to 500 ft YEAR DRILLED WELL LOG NO WELL ID#
 Comment

USES OF WATER RIGHT* ** ** ELU -- Equivalent Livestock Unit (cow horse etc) ** **** EDU -- Equivalent Domestic Unit or 1 Fsmly

SUPPLEMENTAL GROUP NO 400461

| | | |
|--------------------------------|--------------------|------------------------------|
| IRRIGATION 0 25 acres | Div Limit 0 0 acft | PERIOD OF USE 04/01 TO 10/31 |
| STOCKWATER 10 0000 Stock Units | Div Limit | PERIOD OF USE 01/01 TO 12/31 |
| DOMESTIC 1 0000 EDUs | Div Limit | PERIOD OF USE 01/01 TO 12/31 |

| ##PLACE OF USE | -----NORTH WEST QUARTER----- | | | | -----NORTH EAST QUARTER----- | | | | -----SOUTH WEST QUARTER----- | | | | -----SOUTH EAST QUARTER----- | | | | Section Totals |
|----------------------|------------------------------|----|----|----|------------------------------|----|----|----|------------------------------|----|----|----|------------------------------|----|----|--------|----------------|
| | NW | NE | SW | SE | NW | NE | SW | SE | NW | NE | SW | SE | NW | NE | SW | SE | |
| Sec 16 T 7S R 2W SLB | | | | | 0 2500 | | | | | | | | | | | | 0 2500 |
| GROUP ACREAGE TOTAL | | | | | | | | | | | | | | | | 0 2500 | |

PLACE OF USE for STOCKWAIERING** * * * * *

| | | | | |
|-----------------------|-------------|-------------|-------------|-------------|
| | NORTH-WEST¼ | NORTH-EAST¼ | SOUTH-WEST¼ | SOUTH-EAST¼ |
| Sec 16 T 7S R 2W SLBM | NW NE SW SE | NW NE SW SE | NW NE SW SE | NW NE SW SE |
| | | X | | |

DIVERSION & DEPLETION ESTIMATES* ****

(All values in acre-feet Growing Season in days)

| | IRRIGATION | STOCK | DOMESTIC | MUNICIPAL | MINING | POWER | OTHER | MANUALLY EVALUATED | ACRE-FEET EXPORTED | DIVERSION DUTY | DEPLETION DUTY | GROWING WATER-USE SEASON REPORTING |
|-----|------------|-------|----------|-----------|--------|-------|-------|--------------------|--------------------|----------------|----------------|------------------------------------|
| DIV | | | | | | | | Yes | | | | |
| DEP | | | | | | | | | | | | |

OTHER COMMENTS * * * * *

APPLICANT BUYING LAND ON CONTRACT

 ** * * * * E N D O F D A T A * * * * *

Utah Division of Water Rights | 1594 West North Temple Suite 220 P O Box 146300 Salt Lake City Utah 84114-6300 | 801 538 7240
[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

Utah Online Services Agency List Business

Search

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009 Page 1

CHANGE a22976 WATER RIGHT 3 14 7 CERT NO COUNTY TAX 1D#
BASE WATER RIGHTS -1d
RIGHT EVIDENCED BY 53 1437
CHANGES Point of Diversion [X] Place of Use [X] Nature of Use [X] Reservoir Storage []

NAME Ev Joh on
ADDR 327 North 200 E t #2
Am a Fork UT B4003
REMARKS

FILED 02/12/1999 PRIORITY 02/12/1999 ADV BEGAN 03/03/1999 ADV ENDED 03/10/1999 NEWSPAPER Leh Free Pr
Point End 03/31/1999 PROTESTED [No He] HEARING HLD [SE ACTION [] Act on Dat [PROOF DUE
EXTENSION [ELEC/PROOF [] ELEC/PROOF [CERT/WUC [LAP ETC 03/17/2001 LAPS LETTER
RUSH LETTER [RENOVATE [RECON REQ [TYPE []

Status Withdrawn

HERETOFORE

HEREAFTER

FLOW 129.2 acre feet FLOW 126.746 acre-feet
SOURCE Warm Springs SOURCE Undergound Well
COUNTY Utah COUNTY Utah COM DESC Cedar Valley

POINT(S) OF DIVERSION > MAP VIEWER
Point S f c
Dvrt ng Wks Concrete L ned Ca al
Sou e Warm Springs
Po nt Und g ound
CHANGED AS FOLLOWS (Click Locat on link for WRPLAT)
(1) H 66) ft 66 ft o W4 cor, ec 20, T 7S, R 2W, SLBM
Diameter 2 ins Depth 100 to 1000 ft WELL ID#
COMMENT 2 to 16 Diameter
(2) S 37) f w 0 ft from UE o, Sec 0, P 7, R 2W, SLBM
Diameter 2 ns Depth 100 to 1000 ft WELL ID#
COMMENT 2 TO 16 D m ter
(3) S 50 f w 0 ft r om F4 cor, Sec 0, T 7S, P 2W, SLBM
D amete 2 na D pth 100 to 1000 ft WELL ID#
COMMENT 2 to 16 D mete

PLACe OF USE --> CHANGED as follows
NW4 -NE4-- SW4 SE4
|N N S S| |N N S S| |N N S S| |N N S S|
|W E W E| |W E W E| |W E W E| |W E W E|
IS c 32 T 93 R 1E SLBM X X X X
ISec 05 T 10S R 1E SLBM X X X X
ISec 06 T 10S R 1E SLBM X X

NATURE OF USE -> CHANGED as follows
SUPPLEMENTAL to Oth W t Rights No SUPPLEMENTAL to Othe Wate R ght No

| | | | | | | | |
|-----|---------------------|----------------|-------|-----|---------------------------------|---------------|-------|
| IRR | 32 3000 acs Sol/S p | acs USED 04/01 | 10/31 | IRR | 30 0000 a s Sol/Sup | ac USED 04/01 | 10/31 |
| | | | | STK | 7 0000 Cattle o Equ valent | USED 01/01 - | 12/31 |
| | | | | DOM | 19 0000 Eq v lent D me tic Un t | USED 01/01 | 12/31 |

PROTESTANTS

NAME P ovo River Water U er s Association
 ADDR 1788 North State St eet
 O m UT 84057

NAME Prove Riv r Wate U r s A o ation
 ADDR c/o Scott H Mart n (PO Box 45000)
 10 Exchange Place 11th Floo
 Salt Lake City UT 84145-5000

END OF DATA * * * ** * * * **

Utah Division of Water Rights | 1594 W tN rth T mpl S it 220 P O Bck 145300 SaltL k City Ut h 84114-5300 | 801-538-7240
[Name of Reason](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

utah.gov Online Services Agency List Business

Search

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009

WATER RIGHT 53 1510 APPLICATION/CLAIM NO A2136 CERT NO 1970 SHARES OF STOCK 30 0
CHANGES 0608 Withdrawn
0207 Withdrawn

OWNERSHIP * * * * *

NAME Utah Lake Distributing Company
ADDR 1156 South State Street #201
Orem UT 84097
INTEREST 100 REMARKS

NAME WW Ranches L C
ADDR c/o William N White
4195 Summermeadow Dr
Bountiful UT 84010

DATES ETC * * * * *

LAND OWNED BY APPLICANT COUNTY TAX ID#
FILED 10/27/1908|PRIORITY 10/27/1903|PUB BEGAN |PUB ENDED |NEWSPAPER
ProtestEnd |PROTESTED [No]|HEARNG HLD |SE ACTION [Approved]|ActionDate 03/19/1910|PROOF DUE
EXTENSION |ELEC/PROOF []|ELEC/PROOF |CERT/WUC 01/27/1931|LAP ETC |LAPS LETTER
RUSH LETTR |RENOVATE |RECON REQ |TYPE []
PD BOOK [53-]|MAP []|PUB DATE
Type of Right Application to Appropriate Source of Info Ownership Segregation Status Certificate

LOCATION OF WATER RIGHT **(Points of Diversion Click on Location to access PLAT Program)**** ***** MAP VIEWER*****

FLOW 153 3 acre-feet SOURCE Utah Lake and Jordan River
COUNTY Utah COMMON DESCRIPTION Jordan Narrows

POINT OF DIVERSION -- SURFACE
(1) 512 ft 17 ft from NW cor. of Sec 26, T 40, R 14, S1PM
Diverting Works Utah Lake Dam Source Utah Lake

Stream Alt Required? No

POINT OF REDIVERSION
(1) 395 ft 2338 ft from NW cor. of Sec 26, T 40, R 14, S1PM
Diverting Works USBR/MWDSLIC Pump Station Source Jordan River

USES OF WATER RIGHT***** * ELU -- Equivalent Livestock Unit (cov horse etc) * * * ** EDU -- Equivalent Domestic Unit or 1 Family

SUPPLEMENTAL GROUP NO 233948

IRRIGATION Sole Supply UNEVALUATED acres Group Total 30 66 Div Limit 0 0 acft PERIOD OF USE 04/01 TO 10/31

Table with 4 columns: PLACE OF USE, NORTH WEST QUARTER, NORTH EAST QUARTER, SOUTH WEST QUARTER, SOUTH EAST QUARTER, Section Totals. Includes grid of NW, NE, SW, SE and X marks.

Utah Online Services Agency List Business Search

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009 Pag 1

CHANGE a26638 WATER RIGHT 0 CERT NO COUNTY TAX ID# AMENDATORY No
BASE WATER RIGHTS 3-1510
RIGHT EVIDENCED BY 53 1510 a po t on of 59 13 (A2136) (Cert No 1970) Based on 30 ha es of
Utah Lake Distributi g Comp y took
CHANGES Point of Diversion [X] Place of Use [X] N tu of Use [X] Rese vol Sto age []

NAME Utah Lake D atr b t g Comp ny
ADDR 1156 South St te St eet #201
O em UT 84097
INTEREST 100% REMARKS

NAME WW Ranches L C
ADDR /o W 111 m N Whit
4195 Summ rmeadow Dr
Bountiful UT 84010
REMARKS

FILED 05/02/2002|PRIORITY 05/02/2002|ADV BEGAN 05/29/2002|ADV ENDED 06/05/2002|NEWSPAPER The Pay on Chro cle
P otestEnd 06/25/2002|PROTESTED [No Hearl]|HEARNG HLD |SE ACTION [Approved]|Act ond t 07/30/2003|PROOF DUE 07/31/2006
EXTENSION |ELEC/PROOF []|ELEC/PROOF |CERT/WUC |LAP ETC 03/20/2006|LAPS LETTER
RENOVATE |RECON REQ |TYPE []

St t W thdrawn

HERETOFORE

HEREAFTER

FLOW 153 3 a f t FLOW 153 3 a -feet
SOURCE Ut h Lake a d Jo da R ve SOURCE Und g ound W te Well (33)
COUNTY Salt Lak COUNTY Utah COM DESC We t Mounta n
All u e nd any omb n t on the eof
comb ed tog th h ll not exceed 153 3
c e feet Th s change pplicat on s
being f led pur unt to the tt ched
ag eement between Utah L ke Distributi g C
ompa y and J L C If e th r party
to the ag eement dete mine the chang
application is n ona stent w th th
att ched ag eement or that there l a
breach of the ag eement ith party
to the agreem nt may unilaterally
withdraw thi change pplicat o

POINT(s) OF DIVERSION - > MAP VIEWER CHANGED AS FOLLOWS (O1 ck Location l nk for WRPLAT)
Pol t Su face Po nt Surf ce
(1) 1.8 ft W 17 t f N4 , <c 2>, l S, P l , BM (1) N 1517 f W 364 ft on Co Sec 09, T 8S, R 1, LBM
Dvrtng Wks Utah Lake Dam Dvrtng Wks Pump
Sou Ut h Lake Source Utah L k
St eam Alt No
Po t U de grou d UNDERGROUND (CI ck L nk fo PLAT data Well ID# l nk for data)
(1) 40 t W 32 ft from H co , S 14, T 7S, R 2W, SLBM
D amete 16 ns Depth 100 to 1000 ft W LL ID#


```

|| COMMENT
|| (1) 0 ft W 0 ft from S4 cor, Sec 20, T 7s, R 2W, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (3) S 1480 ft W 149 ft from H4 cor, Sec 20, T 7s, R 2W, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (4) 1370 ft W 50 ft on NE cor, Sec 20, T 7s, R 2W, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (5) 1000 ft E 100 ft from 4 cor, Sec 0, T 8S, R 1E, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (6) S 600 ft E 600 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (7) S 600 ft E 600 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (8) 40 ft E 1000 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (9) 200 ft E 1000 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (10) S 0 ft E 0 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (11) 0 ft E 100 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ns Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (12) 200 ft W 600 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (13) N 200 ft E 400 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ns Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (14) N 200 ft E 1200 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (15) N 400 ft E 0 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (16) N 600 ft W 200 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (17) N 600 ft E 1200 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ns Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (18) N 800 ft W 200 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ns Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (19) N 800 ft E 100 ft from 4 cor, Sec 0, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (20) N 000 ft E 100 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (21) N 1000 ft E 1000 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ns Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (22) N 1000 ft E 1200 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (23) N 100 ft E 800 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (24) N 200 ft E 1200 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 ins Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (25) N 1400 ft E 800 ft from 4 cor, Sec 09, T 8S, R 1E, SLBM
|| Diameter 16 in Depth 100 to 1000 ft WELL ID#
|| COMMENT
|| (26) N 1400 ft W 1000 ft from S4 cor, Sec 09, T 8S, R 1E, SLBM

```

```

D meter 16 in Depth 100 to 1000 ft WELL ID#
COMMENT
( ) 400 ft E 1200 ft from 4 cor, Se. 09, T 8, R 1E, SLBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID#
COMMENT
(29) 800 ft N 500 ft W 54 cor, S c 09, T 8, R 1E, SLBM
Diameter 16 in Depth 100 to 1000 ft WELL ID#
COMMENT
(29) N 000 ft W 600 ft from S4 cor, S c 09, T 6, R 1E, SLBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID#
COMMENT
(30) 1100 ft E 1200 ft from 4 cor, S c 09, T 8, R 1E, SLBM
Diameter 16 in Depth 100 to 1000 ft WELL ID#
COMMENT
( ) 600 ft E 1200 ft from S4 cor, Se. 09, T 8S, R 1E, SLBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID#
COMMENT
(32) 1600 ft E 600 ft from 4 cor, S c 09, T 8, R 1E, SLBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID#
COMMENT
( ) 200 ft L 1000 ft from N4 cor, sec 16, T 8S, R 1E, SLBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID#
COMMENT
Point Red vein
( ) 33 ft L 138 ft from 4 cor, S c 09, T 4, R 1W, BM
Dwelling Wks USBR/MWDSL Pump Station
Source Jordan River

```

PLACE OF USE >

| CHANGED as follows | | | |
|--|--|--|--|
| --- | --- | --- | --- |
| ---NW4--- | ---NE4--- | ---SW4--- | ---SE4--- |
| IN N S S I I N N S S I I N N S S I I N N S S I | IN N S S I I N N S S I I N N S S I I N N S S I | IN N S S I I N N S S I I N N S S I I N N S S I | IN N S S I I N N S S I I N N S S I I N N S S I |
| W E W E I I W E W E I I W E W E I I W E W E I | W E W E I I W E W E I I W E W E I I W E W E I | W E W E I I W E W E I I W E W E I I W E W E I | W E W E I I W E W E I I W E W E I I W E W E I |
| S c 16 T 2S R 1W SLBM | X | Sec 19 T 7S R 2W SLBM | X |
| | | Sec 20 T 7S R 2W SLBM | X X |
| | | S c 09 T 8S R 1E SLBM | X X X X X X |
| | | Sec 16 T 8S R 1E SLBM | X X X X |

NATURE OF USE >

| CHANGED as follows | | | |
|---|-----|---|------------------|
| --- | --- | --- | --- |
| SUPPLEMENTAL to Other Water Rights No | | SUPPLEMENTAL to Other Water Rights No | |
| IRR 30 6600 acs Sol/Sup ac USED 04/01 10/31 | | IRR 30 0000 acs Sol/Sup ac USED 04/01 10/31 | |
| | | STK 30 0000 Cattle or Equivalent | USED 01/01 12/31 |
| | | DOM 90 0000 Equivalent Domestic Units | USED 01/01 12/31 |
| | | OTH FIRE PROTECTION | USED 01/01 12/31 |
| | | OTH COMMERCIAL | USED 01/01 12/31 |
| | | OTH INDUSTRIAL | USED 01/01 12/31 |

PROTESTANTS

| | |
|-------------------------|---|
| NAME Bu u of R lam t on | NAME Jorda Vail y Wat Con ervancy D tr ct |
| ADDR Jon th B Jones | ADDR c/o Richard P Bay |
| 302 E t 1860 So th | P O Box 70 |
| P ovo UT 84606 7317 | West Jordan UT 84088 0070 |
| | |
| NAME Western Water LLC | NAME |
| ADDR H vey L Hutch on | ADDR |

194 E Paradise Ln
Alpine UT 84004

E N D O F D A T A

Utah Water Rights | 1984 West North Temple Suite 220 P.O. Box 140300 Salt Lake City Utah 84114-0300 | 801-638 7240
[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

Utah Online Services Agency List Business

Search

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009 Page 1

CHANGE a28617 WATER RIGHT 3 10 CERT NO COUNTY TAX ID# AMENDATORY No

BASE WATER RIGHTS 53 1510

5 1543

RIGHT EVIDENCED BY a26638(53 1510) 53 1543(A2136) both gated po t on of 59 13 ba ed o 36 har s Ut h Lake D t

CHANGES Point of Dive s n [] PI of Us [] Natur of U e [X] Res rvoir Sto age []

NAME St te f Ut h Bo d of W t Re ou
ADDR H Id fo Ut h L k Dist but ng Company
1594 W t No th T mpl St 310
Salt L k C ty UT B4114 6201
INTEREST 100% REMARKS

NAME Ut h Lake Distr b t g Company
ADDR 1156 South St t St t #201
Orem UT 84097
REMARKS Held by St t of Ut h Boa d of Wate Resou c

NAME WW R nch L C
ADDR c/o W 11 am N Wh t
4195 S mme m dow D
Bo tiful UT 84010
REMARKS

FILED 01/29/2004|PRIORITY 01/29/2004|ADV BEGAN 02/11/2004|ADV ENDED 02/18/2004|NEWSPAPER The Payson Ch onicle
P ot tEnd 03/09/2004|PROTESTED [No He]|HEARNG HLD |SE ACTION []|A t o Date |PROOF DUE
EXTENSION |ELEC/PROOF []|ELEC/PROOF |CERT/WUC |LAP ETC 09/14/2006|LAPS LETTER
RUSH LETTR |RENOVATE |RECON REQ |TYPE []

Status With) wn

HERETOFORE

* HEREAFTER **

FLOW 183 96 a fe t FLOW 183 96 acre-feet
SOURCE Underg ound W te W 11 (31) (x t ng) SOURCE 31 Ex ting app oved under a26638
COUNTY Ut h COUNTY Utah COM DESC West Mou tain
All u e nd ny combination thereof
comb ed tog the sh ll not xc ed 183 96
acre feet This hange pplic tion 1
b ng filed pursuant to th attached
g eem nt between Utah Lake D stributing C
ompany d J L C If the pa ty
to th ag eeme t d termin the ch ge
application is co s ste t w th the
attached ag ment r th t th a
breach of th g eem nt th p ty
to th g e ment m y un l t lly
withd w th h ng ppl c t on

POINT(S) OF DIVERSION - > MAP VIEWER SAME AS HERETOFORE
Point Su face
11 W 11 ft W 264 L f 9 d o 09 J PS R JL SIB
Dv t g Wks Pump
Sou c Ut h Lake

```

- - - - -
Po t Und g round
(1) 19.5 ft L 3.5 t from S4 co, ec 09, T 1, R W, SLEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) N 10 ft L 0 t from S4 co, ec 09, T 1, R 2W, IEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 1.0 ft W 50 t L o NE co, ec 20, T 7, L 2, S B
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) S I ft L 0 t from S4 co, ec 09, T 1, R W, SLEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 1000 ft L 0 t from S4 co, ec 09, T 8, R 1, SLEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) It E 100 ft from 1 o, ec 09, T 0, R IE, IPM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 20 ft L 0 t from S4 co, ec 09, T 6S, R IE, LBN
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) S 0 ft E 200 t from S4 co, ec 09, T 8S, R IE, B4
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 00 ft E 0 t from S4 co, ec 09, T 8, R IL, SLEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(10) S 40 ft E 100 t from S4 co, ec 09, T 3, R IF, IEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(11) It L 0 ft from S4 co, ec 09, T 8S, P IL, S B
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 20 ft L 0 t from S4 co, ec 09, T 1 8S, R IL, B4
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) W 20 ft L 400 ft from S4 co, ec 09, T 8, R 1, IL
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) N 0 ft L 00 t from S4 co, ec 09, T 8S, P 1b, SLEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) N 40 ft E 100 t from S4 co, ec 09, T 1 6S, P IE, LBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 4 60 ft L 200 t from S4 co, ec 09, T 1 B, R IL, LBN
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(17) 4 00 ft E 200 t from S4 co, ec 09, T 1 8, R 1, S B
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) N 80 ft L 0 t from S4 co, ec 09, T 1 8S, P IE, LBN
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) N 20 ft E 100 ft from S4 co, ec 09, T 1 8, P IE, LBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 1000 ft L 20 t from S4 co, ec 09, T 1 8, R 1b, LBN
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
( ) 10 ft E 100 ft from S4 co, ec 09, T 1 8, R 1, IE, LBN
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(22) 100 ft L 0 t from S4 co, ec 09, T 1 3S, R IE, LBN
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(23) N 100 ft L 800 t from S4 co, ec 09, T 1 8S, P 1b, SLEM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(24) N 1200 ft E 200 t from S4 co, ec 09, T 1 8, R 1, LBN
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT

```

```

(2) 11100 ft b 609 ft from 4 co, 3p UJ, 1 E, R IE, SLBM
Diameter 16 ns Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(6) 11400 ft 610 ft from 4 co, Se 09, 1 d3, R IL, LDM
Diameter 16 n Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(27) 1400 ft 100 ft from 4 co, S c 0, r B, R IE, SLBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(2B) N 800 ft 100 ft from S4 of, Sec 09, T B3, P IE, LBM
Diameter 16 n Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(29) 1100 ft 620 ft from 34 co, Sec 09, T B, R IE, SLBM
Diameter 16 n Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(30) H 100 ft 100 ft from 4 S 0, T 6, R IL, LDM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
(31) 1200 ft 1100 ft from N4, Sec 16, T B3, R IE, SLBM
Diameter 16 ins Depth 100 to 1000 ft WELL ID# 000000
COMMENT
Point Rediver on
11335 ft F 433 ft from 14 co, Sec 6, T 43, R IW, LBM
Dwrtng Wks USBR/MWDSLIC Pump Station
Source Jord n River
    
```

| PLACE OF USE | SAME AS HERETOFORE |
|--|--------------------|
| NWM - NEM 3WM - SEM INNSSIHNSSIINNSSIINHS IWEWEIWEWEIWEWEIWEWE | |
| Sec 19 T 7S R 2W SLBM | X |
| 13 c 20 T 7S R 2W SLBM | X X |
| 1Sec 09 T 63 R IE SLBM | X X X X X |
| 1Sec 16 T 8S R IE SLBM | X X X |

| NATURE OF USE | CHANGED as follows |
|--|--|
| SUPPLEMENTAL to Other Water Rights No | SUPPLEMENTAL to Other Water Rights No |
| IRR 36 7920 acs Sol/Sup c USED 04/01 10/31 | |
| STK 30 0000 Cattle or Equivalent USED 01/01 12/31 | |
| DOM 90 0000 Equ valem t Domestic Un t USED 01/01 12/31 | DOM 40B 0000 Equivalent Domestic Unit USED 01/01 12/31 |
| OTH COMMERCIAL USED 01/01 12/31 | |
| OTH INDUSTRIAL USED 01/01 - 12/31 | |
| OTH FIRE PROTECTION USED 01/01 12/31 | |

PROTESTANTS

```

NAME USA Sure u of Reclamat o
ADDR /o Jonath n B Jo
302 East 1B60 South
P ovo UT B4606 7317
NAME P ovo Rive Wate U r A oc at on
ADDR c/o Wa n H Pet rson
362 West Main Street
Delt UT B4624
    
```

END OF DATA

Utah Division of Water Rights | 1594 West North Temple, Suite 220, P.O. Box 146300, Salt Lake City, Utah 84114-6300 | 801 536-7240
[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

Utah Online Services Agency List Business

Search

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009

WATER RIGHT 54 1045 APPLICATION/CLAIM NO CERT NO
CHANGES a-306 Withdrawn
a2091 Rejected
a2071 Approved

OWNERSHIP *****

NAME East Jordan Irrigation Company
ADDR 13849 Lookout Peak Drive
Riverton UT 84096-6441

NAME Scott McLachlan
ADDR P O Box 37
Lehi UT 84043

REMARKS 65 34 acft 13 068 acres

DATES ETC *****

LAND OWNED BY APPLICANT COUNTY TAX ID#
FILED |PRIORITY / /I877|PUB BEGAN |PUB ENDED |NEWSPAPER
ProtestEnd |PROTESTED [No |HEARNG HLD |SE ACTION | |ActionDate |PROOF DUE
EXTENSION |ELEC/PROOF []|ELEC/PROOF |CERT/WUC 06/16/1969|LAP ETC |LAPS LETTER
RUSH LETTR |RENOVATE |RECON REQ |TYPE [|
PD BOOK [54-]|MAP [|PUB DATE
Type of Right Decree Source of Info Ownership Segregation Status

LOCATION OF WATER RIGHT **(Points of Diversion Click on Location to access PIAT Program)**** ** MAP VIEWER*****

FLOW 64 34 acre-feet SOURCE Utah Lake and Jordan River
COUNTY Utah COMMON DESCRIPTION Jordan Narrows

POINTS OF DIVERSION -- SURFACE
(1, N 180 ft F 880 ft from W4 cor, S 20, T S, E 1N, SLB)
Diverting Works Turner Dam Source Jordan River
000 ft v 40 ft from N4 or, S, I 50, R 11, SLBM
Diverting Works Utah Lake Pumping Plant Source Utah Lake

Stream Alt Required No

USES OF WATER RIGHT * * ELU -- Equivalent Livestock Unit (cow horse etc) ***** EDU -- Equivalent Domestic Unit or I Family

SUPPLEMENTAL GROUP NO 400052 Water Rights Appurtenant to the following use(s)
5 -104 (DEC) 20 (DEC)

IRRIGATION Sole Supply 12 818 acres of the Group Total of 13 068 Div Limit 0 0 acft PERIOD OF USE 04/01 TO 10/31

Table with 4 columns: PLACE OF USE, NORTH WEST QUARTER, NORTH EAST QUARTER, SOUTH WEST QUARTER, SOUTH EAST QUARTER, Section Totals. Values include NW, NE, SW, SE, and 0 0000.

| | | | | | | | | | | | | | | | | | | | | |
|-------------------------|---|----|----|----|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|--------|
| Sec 18 T 2S R 1E S LBM | X | IX | IX | IX | | | | | | | | | | | | | | | | 0 0000 |
| Sec 19 T 3S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 20 T 4S R 1E S LBM | X | IX | IX | IX | | | | | | | | | | | | | | | | 0 0000 |
| Sec 21 T 5S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 22 T 6S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 23 T 7S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 24 T 8S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 25 T 9S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 26 T 10S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 27 T 11S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 28 T 12S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 29 T 13S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 30 T 14S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 31 T 15S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 32 T 16S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 33 T 17S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 34 T 18S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 35 T 19S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 36 T 20S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 37 T 21S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 38 T 22S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 39 T 23S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 40 T 24S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 41 T 25S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 42 T 26S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 43 T 27S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 44 T 28S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 45 T 29S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 46 T 30S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 47 T 31S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 48 T 32S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 49 T 33S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 50 T 34S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 51 T 35S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 52 T 36S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 53 T 37S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 54 T 38S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 55 T 39S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 56 T 40S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 57 T 41S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 58 T 42S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 59 T 43S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 60 T 44S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 61 T 45S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 62 T 46S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 63 T 47S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 64 T 48S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 65 T 49S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 66 T 50S R 1E S LBM | X | IX | IX | IX | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| GROUP ACREAGE TOTAL | | | | | | | | | | | | | | | | | | | | 0 0000 |

SEGREGATION HISTORY** *****

This Right was Segregated from 7-7-31 with Appl# Approval Date / / under which Proof is to be submitted
 This Right as originally filed
 FLOW IN QUANTITY IN -----W A T E R U S E S-----
 CFS ACRE-FEET IRRIGATED STOCK DOMESTIC MUNICIPAL MINING POWER OTHER
 ACREAGE (ELUs) (FAMILIES) (-----ACRE-FEET-----)
 130 68 26 1360
 based on 27 shares of stock see Change Application

- The following Water Rights have been Segregated from 54-1045
- (1) WRNUM 4-1102 65 34 13 0680
 APPL#
 NAME East Jordan Irrigation Company et al
 FILED 05/08/2003 STATUS
 APPR
 - (2) WRNUM 4-122 1 0 0 2500
 APPL#
 NAME East Jordan Irrigation Company et al
 FILED 10/01/2007 STATUS
 APPR

```

=====
CFS          ACRE-FEET  IRRIGATED  STOCK   DOMESTIC  MUNICIPAL  MINING   POWER   OTHER
              ACREAGE   ACREAGE    (ELUs)  (FAMILIES) (-----ACRE-FEET-----)
54-1045 currently has          64 34      12 8180
*****
*****
***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** *
***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** *
***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** *
***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** * ***** *
*****

```

Utah Division of Water Rights | 1594 West North Temple Suite 220 P.O. Box 148300 Salt Lake City Utah 84114-8300 | 801 538 7240
[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

utah | Online Services | Agency List | Business

Search

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009 Page 1

CHANGE a24306 WATER RIGHT 51104 CERT NO COUNTY TAX ID# AMENDATORY No

BASE WATER RIGHTS 541045

RIGHT EVIDENCED BY 541045 wh ch is a po t on of 57 7637 (Ba d on 27 h e of E t Jo d n Irr g tion Company stock)

CHANGES Po nt of D vers on (X) Plac of Use (X) Natu e of U e (X) Re e voi Storage ()

NAME East Jo da I rigatio Comp y
ADDR 13B49 Lookout Peak Drive
Riverton UT 84096 6441
REMARKS

NAME Scott McLa h l n
ADDR 9300 No th 10400 We t
L h UT 94043

REMARKS 64 13 acft 71 fam l e 8 0425 ac es

FILED 03/27/2000|PRIORITY 03/27/2000|ADV BEGAN 04/12/2000|ADV ENDED 04/19/2000|NEWSPAPER Leh Free Press
ProtestEnd 05/09/2000|PROTESTED [No Heari]|HEARNG HLD |SE ACTION [Approved]|ActionDate 07/07/2000|PROOF DUE
EXTENSION |ELEC/PROOF []|ELEC/PROOF |CERT/WUC |LAP ETC |LAPS LETTER
RUSH LETTER |RENOVATE |RECON REQ |TYPE []

Status Withdrawn

HERETOFORE

* * * * *
HEREAFTER

FLOW 65 34 c e f e t
SOURCE Ut h Lake a d Jo d n R v
COUNTY Salt L ke
FLOW 65 34 acre feet
SOURCE U de g ound Water Well (4)
COUNTY Utah COM DESC 4 5 miles South of Fa field

POINT(S) OP DIVERSION - > MAP VIEWER
Point Surface
(1) N 80 ft F 900 ft fr o N4 o , S e 20, T 1S, R 1W, SLBM
Dvrtng Wks Turner Dam
So Jorda Riv
(2) S 1000 ft ? 40 ft f om N4 co , S e 25, T 1 S, R 1W, SLBM
Dvrtng Wks Utah Lake Pumping PI nt
Sou ce Utah Lake

CHANGED AS FOLLOWS (Click Locat on l nk for WRPLAT)
UNDERGROUND (Click Link for PLAT d ta Well ID# link for data)
(1) S 1350 t W 3 5 ft f om NE cor, Sec 19, T 7S, R 2W, SLBM
Diameter 16 i s Depth 100 to 1000 ft WELL ID#
COMMENT
(2) S 1980 fr W 1 00 ft f o N4 cor, ec 20, T 1 , R 2W, SLBM
D amete 16 in Depth 100 to 1000 ft WELL ID#
COMMENT
(3) 70 ft W 0 ft from NE co , Se 20, T 7 , R 2W, SLBM
D amete 16 n D pth 100 to 1000 ft WELL ID#
COMMENT
(4) H 50 fr W 0 ft on E tor, Sec 20, T 7S, R H, SLBM
Diameter 16 ns Depth 100 to 1000 ft WELL ID#
COMMENT

PLACE OF USE -- -->
CHANGED as follows

| | NW4 | NE4 | SW4 | SE4 | | NW4 | NE4 | SW4 | SE4 |
|-----------------------|-------------|----------|----------|----------|-----------------------|----------|----------|----------|----------|
| | IN N 3 S | IN N 3 S | IN N 3 S | IN N 3 S | | IN N 3 S | IN N 3 S | IN N 3 S | IN N 3 S |
| | W E W E | W E W E | W E W E | W E W E | | W E W E | W E W E | W E W E | W E W E |
| Sec 07 T 2S R 1E SLBM | | | | | Sec 19 T 7S R 2W SLBW | | | | |
| Sec 18 T 2S R 1E SLBM | X X X X | X X | X X X X | X X X X | Sec 20 T 7S R 2W SLBW | X X | | | |
| Se 19 T 2S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 20 T 2S R 1E SLBM | X | | X X X X | X | | | | | |
| Sec 29 T 2S R 1E SLBM | X X X | X X | X X | X | | | | | |
| Sec 30 T 2S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| S c 31 T 2S R 1E SLBM | X X X X | X X X | X X X X | X | | | | | |
| Sec 11 T 2S R 1W SLBW | | X X | X X | X X X X | | | | | |
| Sec 12 T 2S R 1W SLBW | X X X X | X | X X X X | X X X X | | | | | |
| Sec 13 T 2S R 1W SLBW | X X X X | X X | X X X X | X X X X | | | | | |
| Sec 14 T 2S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 23 T 2S R 1W SLBW | X X X X X X | X | X X | X X | | | | | |
| Sec 24 T 2S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 25 T 2S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 36 T 2S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 06 T 3S R 1E SLBM | X X X | | X X | | | | | | |
| Sec 07 T 3S R 1E SLBM | X | | X X X | | | | | | |
| S c 18 T 3S R 1E SLBM | X X X | | X X X X | | | | | | |
| Sec 19 T 3S R 1E SLBM | X X | | X X X | | | | | | |
| Se 29 T 3S R 1E SLBM | | | X | | | | | | |
| Sec 30 T 3S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| S c 31 T 3S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| S c 32 T 3S R 1E SLBM | | | X X | | | | | | |
| S c 01 T 3S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| S c 02 T 3S R 1W SLBW | | | | X | | | | | |
| S c 11 T 3S R 1W SLBW | | X X X X | | X | | | | | |
| Sec 12 T 3S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 13 T 3S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 24 T 3S R 1W SLBW | X X X X X X | X X X X | X X X X | X X X X | | | | | |
| S c 25 T 3S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 26 T 3S R 1W SLBW | X | X X | X | X X | | | | | |
| Sec 35 T 3S R 1W SLBW | | X | | X X | | | | | |
| Sec 36 T 3S R 1W SLBW | X X X X | X X X X | X X | X X X X | | | | | |
| Se 05 T 4S R 1E SLBM | X | | | | | | | | |
| Sec 06 T 4S R 1E SLBM | X X X X | X X X X | X X X X | X | | | | | |
| S c 01 T 4S R 1W SLBW | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 02 T 4S R 1W SLBW | | X X | | X X X X | | | | | |
| Sec 11 T 4S R 1W SLBW | X X | X X X X | X X X | X X | | | | | |
| Sec 12 T 4S R 1W SLBW | X X | X X X | | | | | | | |
| Sec 14 T 4S R 1W SLBW | X X X X | | X X | | | | | | |

| NATURE OF USE | > | CHANGED as follows |
|------------------------------------|----------------------|--|
| SUPPLEMENTAL to Other Water Rights | No | SUPPLEMENTAL to Other Water Rights No |
| 1RR 13 0680 acs Sol/Sup | acs USED 04/01 10/31 | 1RR 8 1225 cs Sol/Sup acs USED 04/01 - 10/31 |
| | | DGM 73 0000 Equivalent Domestic Units USED 01/01 12/31 |

| SEGREGATION HISTORY | | * * * * * |
|---|---------------|---------------------------|
| Th s Chang a or g n lly f led | | |
| FLOW IN | QUANTITY IN | W A T E R U S E S |
| CFS | ACRE-FEET | IRRIGATED STOCK DOMESTIC |
| | 130 68 | 16 2450 0000 146 0000 |
| Th follow ng Ch ges have bee Segregated from a24306 | | |
| (1) CHANGE a24306 | WRNUM 54 1102 | 65 34 8 1225 0000 73 0000 |
| NAME Eat Jo d n l g tion Compa y etal | | |
| FILED 05/08/2003 STATUS AMEN APPR/REJ | | |
| CFS | ACRE FEET | IRRIGATED STOCK DOMESTIC |
| a24306 currently has | 65 34 | 8 1225 0000 73 0000 |

PROTESTANTS

NAME P clflCorp
ADDR c/o Jody L Williams
299 South Main St St 1800
Salt Lake City UT 84111

NAME P flC rp
ADDR c/o Claudia Cond r
1407 West North Temple #320
Salt Lake City UT 84116

NAME USA B u of Reclamat o
ADDR ATTN Jonathan Jones
302 East 1860 South
P ovo UT 84606 7317

NAME
ADDR

EXTENSIONS OF TIME WITHIN WHICH TO FILE PROOF

FILED 07/25/2003 1PUB BEGAN |PUB ENDED |NEWSPAPER No Adv Requid
Pote tE d 1PROTESTED [No Hear] [HEARNG HLD |SE ACTION [App oved] [Act onDate 04/15/2004 |PROOF DUE 07/31/2008

* * * * *
* * * * *
* * * * *
* * * * *

Ut h Di |W t R ghts | 1594 W t N rth T mpl S t 220 P O Box 146300 S tLak C ty Utah 84114-6300 | 801 538 7240
[Natural Resources](#) | [Contact](#) | [Data/Map](#) | [Privacy Policy](#) | [Accessibility Policy](#)

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009

WATER RIGHT **54 1102** APPLICATION/CLAIM NO CERT NO
 CHANGES 3-30c Amended by Subsequent Change
320375 Approved
422033 Amended by Subsequent Change

OWNERSHIP * * * * *

NAME East Jordan Irrigation Company
 ADDR 13849 Lookout Peak Drive
 Riverton UT 84096-6441

NAME Keith Jonsson
 ADDR 9250 West 8170 North
 Lehi UT 84043

REMARKS 65 34 acft 13 068 acres

DATES ETC * * * * *

LAND OWNED BY APPLICANT? COUNTY TAX ID#
 FILED | PRIORITY 00/00/1877 | PUB BEGAN | PUB ENDED | NEWSPAPER
 ProtestEnd | PROTESTED [No] | HEARING HLD | SE ACTION [] | ActionDate | PROOF DUE
 EXTENSION | ELEC/PROOF [] | ELEC/PROOF | CERT/WUC 06/16/1969 | LAP ETC | LAPS LETTER
 RUSH LETTR | RENOVATE | RECON REQ | TYPE []
 PD BOOK [54-] | MAP [] | PUB DATE
 Type of Right Decree Source of Info Ownership Segregation Status

LOCATION OF WATEE RIGHT *(Points of Diversion Click on Location to access PLAT Program) * ***** **MAP VIEWER*******

FLOW 65 34 acre-feet SOURCE Utah Lake and Jordan River
 COUNTY BAD-COUNTY COMMON DESCRIPTION Jordan Narrows

POINTS OF DIVERSION -- SURFACE
 (1, N 133 ft E 180 ft from W4 cor, Sec 28, T 4S, R 1E, S1B4
 Diverting Works Turner Dam Source Jordan River
 () 000 ft W 40 ft from N4 cor, sec 5, T 4S, R 1E, S1B4
 Diverting Works Utah Lake Pumping Plant Source Utah Lake

Stream Alt Required? No

USES OF WATER RIGHT * * ELU -- Equivalent Livestock Unit (cow horse etc) ***** EDU -- Equivalent Domestic Unit or 1 Family

SUPPLEMENTAL GROUP NO 400111

IRRIGATION Sole Supply UNEVALUATED acres Group Total 13 068 Div Limit 0 0 acft PERIOD OF USE 04/01 TO 10/31

| ###PLACE OF USE | -----NORTH WEST QUARTER----- | | | | -----NORTH EAST QUARTER----- | | | | -----SOUTH WEST QUARTER----- | | | | -----SOUTH EAST QUARTER----- | | | | Section Totals |
|---------------------|------------------------------|----|----|----|------------------------------|----|----|----|------------------------------|----|----|----|------------------------------|----|----|----|----------------|
| | NW | NE | SW | SE | NW | NE | SW | SE | NW | NE | SW | SE | NW | NE | SW | SB | |
| Sec 17 1 R 1E LEM | | | | | | | | | | | X | | | | | | 0 0000 |
| Sec 15 1 S 3 1E LEM | X | X | X | X | | | X | X | X | X | X | X | X | X | X | X | 0 0000 |
| Sec 1 T 2 R 1 E 1B1 | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | X | 0 0000 |

Utah Online Services Agency List Business

Search

Utah Division of Water Rights

Select Related Information

(WARNING Water Rights makes NO claims as to the accuracy of this data) RUN DATE 12/15/2009 Page 1

CHANGE a24306a WATER RIGHT 4 1102 CERT NO COUNTY TAX ID# AMENDATORY No

BASE WATER RIGHTS -1102
RIGHT EVIDENCED BY 54-1102 a seg po tio 54 1045 which is portion of 57 7637 (Based on 27 shar of East Jordan
I rigat on Comp ny to k)

CHANGES Po nt of D ve on [X] PI e of U e [X] Natu of U e [X] Rase vo Stor ge []

NAME Ea t Jo dn l g t n Comp ny
ADDR 13849 Lookout Peak Drive
R ve ton UT 84096 6441
REMARKS

NAME Ke th Jonsson
ADDR 9250 We t 8170 North
Lehl UT 84003
REMARKS

PILED 05/08/2003|PRIORITY 05/08/2003|ADV BEGAN 04/12/2000|ADV ENDED 04/19/2000|NEWSPAPER Leh Fr Pre
P ote tEnd 05/09/2000|PROTESTED [No H r]|HEARNG HLD |SE ACTION {App ov d}|Act o D te 07/07/2000|PROOF DUE 07/31/2008
EXTENSION |ELEC/PROOF []|ELEC/PROOF |CERT/WUC |LAP ETC [LAPS LETTER
RD SH LETTR |RPHRVATE |RECON REQ |TYPE []

Statu Amenaed by Subsequent Change

HERE TO F O R E

H E R E A F T E R

FLOW 65 34 c f t SOURCE Utah L k and Jo dan R v COUNTY Salt L ke
FLOW 65 34 ac -feet SOURCE U derground W te Well (4) COUNTY Ut h COM DESC 4 5 mil South of F lrf Id

POINT(S) OF DIVERSION > MAP VIEWER
Po t Surfa e
(1) H 180 ft E I 0 ft from W4 o , e 26, T 4S, R IW, S LB
Dvrtng Wks Tu ne Dam
Sou e Jo dn R ve
(2) 1000 ft W 0 ft from N4 o , S-c 25, T S, R IW, S LB
Dvrtng Wks Utah Lake Pumping Plant
Source Utah Lake
CHANGED AS FOLLOWS (CI ck Location l nk for WRPLAT)
UNDERGROUND (Click Link for PLAT data W 11 ID# link for data)
(1) S 1350 ft W 3 5 ft f om NE cor, Sec 19, T 7, R 2W, S LB
D amete 16 i s Depth 100 to 1000 ft WELL ID#
COMMENT
(2) S 1450 ft W 1980 ft rom H4 cor, Sec 20, T 7, R 2W, S LB
D ameter 16 in Depth 100 to 1000 ft WELL ID#
COMMENT
(3) 137 ft W 0 ft from NE co , e 20, T 7, R 2W, S LB
D meter 16 ins Depth 100 to 1000 ft WELL ID#
COMMENT
(4) H 6 ft W 0 ft f c SE cor, Sec 20, T 7, R 2W, S LB
D met 16 n Depth 100 to 1000 ft WELL ID#
COMMENT

PLACE OF USE -> CHANGED as follows

| | MW4 | NE4 | SW4 | SE4 | | MW4 | NE4 | SW4 | SE4 |
|-----------------------|---------|---------|---------|---------|-----------------------|-----|-----|-----|-----|
| S 07 T 2S R 1E SLBM | | | X | | Sec 19 T 7S R 2W SLBM | | | | |
| Sec 18 T 2S R 1E SLBM | X X X X | X X | X X X X | X X X X | Se 20 T 7S R 2W SLBM | X X | | | |
| Sec 19 T 2S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 20 T 2S R 1E SLBM | X | | X X X X | X | | | | | |
| Sec 29 T 2S R 1E SLBM | X X X | X X | X X | | | | | | |
| S 30 T 2S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 31 T 2S R 1E SLBM | X X X X | X X X | X X X X | | | | | | |
| Sec 11 T 2S R 1W SLBM | | X X | X X | X X X X | | | | | |
| Sec 12 T 2S R 1W SLBM | X X X X | X | X X X X | X X X | | | | | |
| Sec 13 T 2S R 1W SLBM | X X X X | X X X | X X X X | X X X X | | | | | |
| S c 14 T 2S R 1W SLBM | X X X X | X X X X | X X | X X X X | | | | | |
| Sec 23 T 2S R 1W SLBM | X X | X X X X | X | X X | | | | | |
| Sec 24 T 2S R 1W SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 25 T 2S R 1W SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 36 T 2S R 1W SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| S 06 T 3S R 1E SLBM | X X X | | X X | | | | | | |
| Sec 07 T 3S R 1E SLBM | X | | X X X | | | | | | |
| Sec 18 T 3S R 1E SLBM | X X X X | | X X X X | | | | | | |
| Sec 19 T 3S R 1E SLBN | X X | | X X X | | | | | | |
| Sec 29 T 3S R 1E SLBM | | | X | | | | | | |
| S o 30 T 3S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 31 T 3S R 1E SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 32 T 3S R 1E SLBM | | | X X | | | | | | |
| S c 01 T 3S R 1W SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 02 T 3S R 1W SLBM | | | | X | | | | | |
| S c 11 T 3S R 1W SLBM | | X X X X | | X | | | | | |
| Sec 12 T 3S R 1W SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 13 T 3S R 1W SLBM | X X X X | X X X X | X X | X X X X | | | | | |
| Sec 24 T 3S R 1W SLBM | X X | X X X X | X X X X | X X X X | | | | | |
| Sec 25 T 3S R 1W SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 26 T 3S R 1W SLBM | X | X X | X | X X | | | | | |
| Se 35 T 3S R 1W SLBM | | X | | X X | | | | | |
| Se 36 T 3S R 1W SLBM | X X X X | X X X X | X X | X X X X | | | | | |
| Se 05 T 4S R 1E SLBM | X | | | | | | | | |
| S 06 T 4S R 1E SLBM | X X X X | X X X X | X X X X | X | | | | | |
| Sec 01 T 4S R 1W SLBM | X X X X | X X X X | X X X X | X X X X | | | | | |
| Sec 02 T 4S R 1W SLBM | | X X | | X X X X | | | | | |
| Se 11 T 4S R 1W SLBM | X X | X X X X | X X X | X X | | | | | |
| Sec 12 T 4S R 1W SLBM | X X X | X X X | | | | | | | |
| Sec 14 T 4S R 1W SLBM | X X X X | | X X | | | | | | |

| NATURE OF USE | CHANGED a follows |
|--|---|
| SUPPLEMENTAL to Oth r M t R ght No | SUPPLEMENTAL to Oth r Wate R ghts No |
| 1RR 13 0680 acs Sol/Sup acs USED 04/01 - 10/31 | 1RR B 1225 acs Sol/Sup acs USED 04/01 10/31 |
| | DOM 73 0000 Equ valent Dom stic Un t USED 01/01 12/31 |

SEGREGATION HISTORY

* * *

This Change originally filed

| FLOW IN | QUANTITY IN | WATER USES | | |
|--|---------------|-------------------|-------------------|----------------------------------|
| CFS | ACRE FEET | IRRIGATED ACREAGE | STOCK (ELDs) | DOMESTIC (FAMILIES) |
| | 130 68 | 16 2450 | 0000 | 146 0000 |
| Th following Change h v b S greg t d from 24306a | | | | |
| (1) CHANGE a2431f | WRNUM 54 1102 | 65 34 | 8 1225 | 0000 73 0000 |
| NAME East Jo d n l r g t i o n C o m p a y e t a l | | | | |
| FILED 05/08/2003 STATUS AMEN APPR/REJ | | | | |
| | CFS | ACRE-FEET | IRRIGATED ACREAGE | STOCK (ELU) DOMESTIC (FAMILIES) |
| a24306 cur ntly h | | 65 34 | 8 1225 | 0000 73 0000 |

PROTESTANTS

NAME Pac f Co p
ADDR c/o Jody L W ll m
299 South Mai St Ste 1600
Salt Lake City UT 84111

NAME Pa fiCorp/Claudia
ADDR c/o Cl udia Conder
1407 West North Temple #320
Salt Lake City UT 84116

NAME USA Bu eau of R clamat on
ADDR ATTN Jonathan Jone
302 E t 1860 South
P ovo UT 84606-7317

NAME
ADDR

EXTENSIONS OF TIME WITHIN WHICH TO FILE PROOF

FILED 07/23/2003 1PUB BEGAN |PUB ENDED |NEWSPAPER No Adv Requ red
ProtestE d |PROTESTED [No Hear]|HEARNG HLD |SE ACTION [Approved]|Act onDate 01/08/2004|PROOF DUE 07/31/2008

* * * * *
* * * * *
* * * * *

Ut h D i f Wat R ghts | 1504 W t N rth T mpl S t 220 P O Bx 146300 Salt L k City Utah 84114-6300 | 801 538-7240
[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)